

Facility Condition Assessment Summary Report

This report provides a summary of the Facility Condition Index (FCI) value of a school facility and select major building systems. The FCI calculation represents the cost of needed repairs divided by the replacement value. The FCI is a numerical value of condition and helps to identify the need for renewal or replacement of specific parts of the facility. The FCI is particularly useful when comparing similar facilities within the same portfolio.

Wister School

Governance	CHARTER	Report Type	Elementary
Address	67 E. Brighthurst St. Philadelphia, Pa 19144	Enrollment	522
Phone/Fax	N/A / N/A	Grade Range	'00-05'
Website	Http://Www.Masterycharter.Org/Schools/Elementary-Schools/John-Wister-Elementary/	Admissions Category	Neighborhood
		Turnaround Model	Renaissance Charter

Building/System FCI Tiers

Facility Condition Index (FCI) = $\frac{\text{Cost of Assessed Deficiencies}}{\text{Replacement Value}}$				
< 15%	15 to 25%	25 to 45%	45 to 60%	> 60%
Buildings				
Minimal Current Capital Funding Required	Refurbish Systems in building	Replace Systems in building.	Building should be considered for major renovation.	Building should be considered for closing/replacement.
Systems				
Perform routine maintenance on system	System requires minor repairs	System should be studied to determine repair vs. replacement.	System is nearing end of its life expectancy and should be considered for replacement	System should be replaced as part of the Capital Program

Building and Grounds

	FCI	Repair Costs	Replacement Cost
Overall	45.11%	\$22,482,848	\$49,841,072
Building	46.24 %	\$22,014,447	\$47,612,533
Grounds	21.02 %	\$468,401	\$2,228,539

Major Building Systems

Building System	System FCI	Repair Costs	Replacement Cost
Roof (Shows physical condition of roof)	89.33 %	\$1,118,716	\$1,252,383
Exterior Walls (Shows condition of the structural condition of the exterior facade)	09.60 %	\$332,176	\$3,459,021
Windows (Shows functionality of exterior windows)	118.50 %	\$1,999,981	\$1,687,807
Exterior Doors (Shows condition of exterior doors)	215.30 %	\$292,567	\$135,887
Interior Doors (Classroom doors)	105.53 %	\$347,127	\$328,940
Interior Walls (Paint and Finishes)	00.00 %	\$0	\$1,844,312
Plumbing Fixtures	37.21 %	\$471,516	\$1,267,027
Boilers	14.03 %	\$245,555	\$1,749,659
Chillers/Cooling Towers	48.30 %	\$1,108,098	\$2,294,143
Radiators/Unit Ventilators/HVAC	107.68 %	\$4,338,156	\$4,028,808
Heating/Cooling Controls	157.69 %	\$1,995,045	\$1,265,153
Electrical Service and Distribution	87.35 %	\$794,010	\$909,036
Lighting	28.86 %	\$937,894	\$3,250,036
Communications and Security (Cameras, Pa System and Fire Alarm)	61.73 %	\$751,502	\$1,217,358

Please note that some FCIs may be over 100% because there are times when replacing a building system requires that other building systems be upgraded to complete the installation. A FCI of 0.0% represents that there are no current deficiencies with the associated system.

School District of Philadelphia

S643001;Wister

Final

Site Assessment Report

February 1, 2017



Table of Contents

Site Executive Summary	4
Site Condition Summary	10
<u>B643001:Wister</u>	12
Executive Summary	12
Condition Summary	13
Condition Detail	14
System Listing	15
System Notes	17
Renewal Schedule	18
Forecasted Sustainment Requirement	21
Condition Index Forecast by Investment Scenario	22
Deficiency Summary By System	23
Deficiency Summary By Priority	24
Deficiency By Priority Investment	25
Deficiency Summary By Category	26
Deficiency Details By Priority	27
Equipment Inventory Detail	54
<u>G643001:Grounds</u>	55
Executive Summary	55
Condition Summary	56
Condition Detail	57
System Listing	58
System Notes	59
Renewal Schedule	60
Forecasted Sustainment Requirement	61
Condition Index Forecast by Investment Scenario	62
Deficiency Summary By System	63
Deficiency Summary By Priority	64
Deficiency By Priority Investment	65

Site Assessment Report

Deficiency Summary By Category	66
Deficiency Details By Priority	67
Equipment Inventory Detail	71
Glossary	72

Site Executive Summary

The organization of this report, as displayed in the Table of Contents, follows the structure of the associated eCOMET database. The overall node for each school campus begins with the letter "S", which indicates the "Site" label. Each Site is comprised of separate "Building" and "Grounds" nodes; their asset names begin with the letters "B" and "G" respectively. Information rolls up to the Site node from the Building and Grounds nodes. This Site report combines facility information with subsections for the Buildings And Grounds nodes.

The basis for the evaluation of condition is the functional systems and elements of a building and grounds organized according to the UNIFORMAT II Elemental Classification. The grouping of these systems and elements and applying a current replacement value to them develops a representative building cost model. Cost Models are typically developed for similar building types and functions. Evaluation of systems and their elements takes into account their current replacement values, life cycles, installation dates and next renewal dates. Systems and their elements that are within their useful lives are further evaluated to identify current deficient conditions that may have a significant impact on a system's or element's remaining service life, and to determine if they are beyond their predicted expected life. The system's or element's current replacement value is based on RS Means Commercial Cost Data.

Following are the cost model's system details for this facility. The Replacement Value is the amount needed to replace the property of the same present value. The Current Repair Amount, also known as Condition Needs, represents the budgeted contractor installed costs plus owner's soft costs for the repair, replacement or renewal for a component or system level deficiency. It excludes contributing costs for other components or systems that might also be associated with the corrective actions due to packaging the work. Facility Condition Index (FCI) is an industry-standard measurement calculated as the ratio of the repair costs to correct a facility's deficiencies to the facility's Current Replacement Value. Condition Index (CI) for a system is calculated as the sum of the deficiencies divided by the sum of a system's Replacement Value (both values include soft-cost) expressed as a percentage ranging from 0% 100%.

Gross Area (SF):	93,715
Year Built:	1955
Last Renovation:	
Replacement Value:	\$49,841,072
Repair Cost:	\$22,482,847.87
Total FCI:	45.11 %
Total RSLI:	72.02 %



Description:

Facility Assessment

December 2015

School District of Philadelphia

John Wister Elementary School

67 East Brighthurst Street

Philadelphia, PA 19144

93,715 SF / 517 Students / LN 06

The John Wister Elementary School building is located at 67 East Brighthurst Street in Philadelphia, PA. The 3 story, 93,715 square foot building was originally constructed in 1955. A 2 story classroom addition of approximately 18,200 SF was built in 1967, extending the classroom wing to the southeast. It appears that the kitchen is also an addition of unknown construction date, adjacent to the

Site Assessment Report - S643001;Wister

gym/cafeteria at the northeast end of the building. The building has a partial basement. The science and technology classrooms and the library have been renovated circa 2000.

The school capacity is listed at 517 students with 2015/16 enrollment of 373 serving grades K-5.

The school plan is L shaped with the long leg housing classrooms, offices, and the library running SE to NW. The perpendicular 1 story leg houses a spacious lobby, auditorium, gym, kitchen and boiler/mechanical rooms in the basement.

Mr. Lorenza Davis, a Building Engineer from a nearby school, accompanied the team on its tour of the school.

ARCHITECTURAL/STRUCTURAL SYSTEMS

The building bears on concrete foundations that are not showing visible signs of significant settlement or damage. Most of the first floor is constructed over crawl space with utility distribution tunnels. The 1970 addition is a half a level lower than the original building. The main structure is cast in place concrete framing. The auditorium and gym roofs are supported on steel joists with concrete plank. Exterior walls are brick on CMU. Several elevations have large murals decorating the exterior walls. In general, masonry is in fair condition. There are numerous holes in the brick from removed security grilles. There is also some loss of mortar at various locations, and some cracking, possibly due to minor settlement. The expansion joint between original construction and the addition is caulked and in poor condition. Columns at the addition are stone clad. Windows are single pane glass and acrylic glazing in aluminum frames. Operable units are hopper style or single hung. Glazing at toilet rooms is frosted. Windows are not energy efficient and are in poor condition with failed gaskets, difficult operation and discolored glazing. Windows have security grilles. Exterior doors are hollow metal in hollow metal frames with glazing, in functional condition. Door appearance is poor. Roofing is low slope built-up with a granular cap sheet. Roofs are in poor condition with some patching evident, wrinkling and splitting, and considerable loss of granules on the wear surface. Perimeter flashing is foil faced modified bitumen torch applied membranes. Roof to wall flashing is copper. Exterior walls are protected by metal cap flashing. Drainage is via interior roof drains with no overflow drains or scuppers. Roof access is via stairwell to a door at the main roof. There is a fixed ladder to the addition roof. The auditorium/gym roof is accessed via interior fixed ladder to an upper platform with an exterior door. There are no ladders to lower entry lobby and kitchen roofs. Generally, the building is not accessible per ADA requirements.

Partition walls are typically CMU in good condition. Glass block borrowed lites are installed at corridor walls of the office. A vestibule at the front entry is an aluminum and glass storefront type system with hollow metal doors. Interior classroom and office doors are generally original solid core wood veneer in hollow metal frames with lights. Classroom doors at original construction have glass block sidelites and transom lites. Select doors have security grilles installed over the door openings. Doors do not have ADA hardware and are in overall fair condition. Doors at the auditorium are broken. Wardrobe doors are typically removed. Doors leading to exit stairways are hollow metal with slot lights in hollow metal frames in functional condition with panic hardware. Doors swing in the direction of exit and are recessed, therefore they do not reduce exit width when opened.

Fittings include: toilet accessories are typically missing; toilet partitions are a mixture of baked enamel, stone and plastic in fair to poor condition; obsolete chalk boards; marker boards; bulletin boards; interior identifying signage is typically missing or is painted on walls or doors; and metal storage lockers are installed in some classrooms.

Stair construction is concrete filled metal pans. Tread and landing finishes vary and include textured resilient, paint, and terrazzo. Handrails are aluminum. Handrails do not meet modern codes for configuration with no extensions at landings. Handrail clearance at intermediate landings is a problem at the southeast stair.

Interior wall finishes are typically paint in good condition. Painted and mosaic murals decorate the lobby. Toilet rooms and some stairwells have ceramic tile walls. There are limited areas of interior brick in good condition. Flooring in classrooms and corridors is a mixture of VCT, 9" VAT and terrazzo in varied condition. In general, the VCT is in good condition, while the 9" VAT has some damage and/or missing tile. The auditorium has 9" VAT flooring. Carpet is installed in the library and is in fair condition with some damage and staining noted. Toilet rooms have terrazzo, ceramic tile, or painted concrete floors. Tiled floors are in fair condition. Terrazzo and painted toilet room floors are in poor condition. The kitchen has quarry tile flooring in good condition. The cafeteria/gym and stage have wood flooring that appears to be original and is in need of refinishing. Ceilings are typically painted structure in fair to good condition with some staining evident, likely from roof leaks. The 1967 addition and kitchen have 2x4 suspended acoustical tile ceilings. Grid is generally yellowed and in some cases rusted. Many water damaged tiles were observed. Glued on acoustical tile is installed in the lobby, auditorium, and offices. Tile is in fair to poor condition with many loose and stained tile noted. There are some areas of wood soffits in the auditorium ceiling.

The building has no elevator.

Site Assessment Report - S643001;Wister

Institutional Equipment includes: a motorized projection screen at the multipurpose room that is adequate; manual projection screens in classrooms; Smartboards in about half of the classrooms; and library shelving that is adequate. Other equipment includes kitchen equipment in fair to good condition and basketball backstops in the gym in good condition.

Furnishings include: plastic laminate and wood veneer fixed casework in classrooms, generally in fair to poor condition; display cabinets in corridors; auditorium seating in fair condition with some damage observed; and window roller shades that are typically in use as a display surface.

MECHANICAL SYSTEMS

Fixtures are a mixture of various styles and vintages. Many fixtures are out of service, stained, or cracked. Flush valves are installed in pipe chases. Lavatories are mostly enameled cast iron and many are rusty. Faucets are separate hot and cold with momentary action valves. Half the toilet fixtures should be replaced. The cafeteria kitchen has a single basin cook sink, a triple basin wash sink with sanitization chemical injection and grease trap, and one lavatory. Sinks are commercial stainless steel and in good condition and should last 15 more years. Classrooms in the original construction have (or had) cast iron sinks with fountains, and the addition classrooms have stainless steel sinks. Cast iron service sinks with stainless rims are located in cleaning closets. They are heavily stained, and the third floor sink leaks from the vacuum breaker and drains slowly. Classroom and service sinks should be replaced. There were showers in the gym toilet rooms, but the boys' have been removed and replaced with urinals and the girls' still has one. Water fountains include porcelain and painted steel units in corridors. They have exceeded their service life and should be replaced with accessible fixtures.

Water enters the building in the boiler room through a 4 inch line. There is a compound water meter and Y-strainer but the back flow preventer has been removed and replaced with a spool piece. The water meter bypass line has a 2 inch back flow preventer. A new backflow preventer should be installed. Domestic hot water is heated by 2 Paloma model 24M-DN tankless natural gas water heaters manufactured in 1986. Each heater has a circulation pump. Heaters have exceeded their expected life span by 20 years and should be replaced due to age. Domestic water distribution pipe is soldered copper. Somehow there are rust streaks in porcelain fixtures, so perhaps some of the domestic piping is steel. Stained fixtures indicate corroding pipes, so domestic water distribution pipes should be replaced. The building does not have a domestic water pressure booster.

Sanitary drain pipes are threaded galvanized steel. There are problems with drains clogging in the building at classroom sinks, service sinks, and drinking fountains. Drain pipes are likely original and should be replaced due to age. There is no sewage ejector.

Rain water drain pipes are threaded galvanized steel and run inside the building. They appear original and are in fair condition. Some areas have been repaired with banded couplings. Roof top drains have cast iron strainers. Drain pipes should be serviceable for 10 - 15 more years. There is a floor sump in the basement with two replacement end suction pumps.

The building is heated by steam and hot water via unit vents, fan coil unit heaters, and finned tube convection units with air handlers for gym and auditorium.

Steam is generated by 3 Smith model 450 16 section boilers with Power Flame oil burners. They have capacity 2223 MBH (66 HP). Burners were manufactured in 1990. Boilers may be older but certificated could not be found. One boiler has a chronic leak from a water drum with lots of rust and scale built up around it. It should be replaced. Boilers 2 and 3 were running at 5 psi during the inspection. Hot water is generated by a steam to water heat exchanger in the room behind the boiler room. The heat exchanger has its own condensate sump with two pumps and there is another condensate collection tank in the boiler room that serves as the feedwater tank. Both feed pumps connect to a single line serving all 3 boilers. Both condensate tanks were venting steam excessively and the entire basement was damp from humidity. The steam traps need to be surveyed and repaired. The building has an underground storage tank for oil with 12,000 gallon capacity. Two oil circulation pumps are in the east corner of the boiler room and sounded good while running but they leak a little bit and have not been cleaned in a very long while. Gas service enters the building in a 2 inch line from northwest side of the building. Mr. Davis detected a natural gas leak in the kitchen by odor. The gas supply was shut off, the gas company was notified, and a workman arrived before we left the location.

Cooling is only provided by 13 window unit air conditioners and 1 ductless split system, approximately 28 ton total capacity. A chiller system should be installed for the entire building with 230 ton capacity.

Classrooms are heated and vented by unit ventilators. The styles are different between the original construction and the classroom addition, but they are all beyond their life expectancy and lack cooling capability. They should be replaced due to age. Classroom excess air exhausts through transfer ducts in closets to the corridors and then to vertical duct chases to gravity vents on the roof. The gym and auditorium are supplied by equipment located in a mechanical room upstairs between them. There are separate supply and exhaust fans for both, and fans are 1.5 HP each. The kitchen has a large horizontal unit vent along its ceiling. These units have all

Site Assessment Report - S643001;Wister

exceeded their service life and lack cooling capacity so should be replaced. There is a gas burning range (8 burners, 2 ovens) and a convection oven. They are installed under an exhaust hood, but it does not have a fire suppression system. A fire suppression system should be installed for the range and oven. Toilet rooms have dedicated exhaust fans, but some locations are missing the fans or they are inoperable. Some toilet rooms still had unpleasant odors present on Saturday. Toilet exhaust fans should be replaced. The original building has steam heat and the classroom addition has hot water. The steam and condensate pipes are heavily rusted throughout the building and should be replaced. Steam hammer was occurring and easily audible in the health suite. Hydronic circulation is provided by two 7.5 HP circulation pumps. One was running well at the time of inspection. They are both in good condition and appear to have been replaced recently, so they should last 15-20 year more.

Classroom unit vents are flanked by finned tube convection units installed in bookcases. Toilet rooms, entryways, small offices, and store rooms have convectors as their only source of heat. Unit vents are mostly original, many have badly bent fins, and some are very rust. They should all be replaced.

Controls for heating are pneumatic. There is an air compressor with one pump and tank, but the filter dryer is inoperative because the power cable is removed. The pneumatic control panel is located in the basement and all of the gauges read zero. Classrooms have pneumatic thermostats which are falling apart and unit vents have pneumatic actuators. The whole system is obsolete and should be replaced with a digital control system when the HVAC equipment is overhauled.

The building does not have sprinklers or stand pipes. A fire protection sprinkler system should be installed.

ELECTRICAL SYSTEMS

Most probably an underground lateral service from a pole mounted transformer on Wakefield Street serves this school. The electrical equipment is located in the basement. The basement houses the utility main disconnect switch, utility metering PECO 01019314820 and 600A 120/240V distribution section. At the basement there are several disconnect switches indicating that electrical loads have been removed/relocated from the 600A, 120/240V original distribution section. The existing service has no extra capacity for expansion or new Heating, Ventilation, Air Conditioning (HVAC) system. The electrical service needs to be upgraded. The new service will be 277/480V, 3 phase power, and approximate 1600A and will be located in the vicinity of the existing electrical service. The new electrical service would feed a 480V Motor Control Center (MCC) and HVAC (Heating, Ventilation and Air Conditioning) equipment, and a 480V 3 phase to 120/208V 3 phase, 500KVA step-down transformer to feed receptacles, lighting and other smaller loads.

There are 120/240V panel-boards in each floor for lighting and receptacles, panelboard ages varies from 10 to 50 years old. Since the electrical service is going to be upgraded and the voltage system will change. Replace existing panelboards. There is (1) 75KVA (estimated) phase converter from 240V to 120/208V which normally feeds newest mechanical equipment.

The number of receptacles in 80% of the classrooms are inadequate. Teachers use extension cords. The teacher's whiteboard wall and the opposite of it need to be provided with double compartment surface raceways, the other two walls with minimum two duplex outlets each, when feasible.

Most of the classrooms are illuminated with pendant mounted, wraparound fluorescent fixtures, the first, second and third floor corridors are illuminated with 1'x4' recessed fluorescent fixtures, the basement corridor and the stairways are illuminated with surface mounted fluorescent fixtures, the entrance and the auditorium are illuminated with pendant, up/down light, white acrylic lens, deep bowl architectural lighting fixture, mechanical rooms are illuminated with industrial/strip fluorescent fixtures. Fluorescent fixtures in the corridors and stairways have been retrofitted with T-8 fluorescent lamps all other areas the fluorescent fixtures are with T-12 lamps. T-12 lamps are becoming more expensive, difficult to find and consume more energy. Therefore replace fluorescent fixtures with T-12 lamps with fluorescent fixtures with T-8 lamps.

The Fire Alarm system is manufactured by Edwards GS and interface with the fire alarm control panel manufactured by S.H. Couch Co Inc. The system is approximately 30 years old. The present Fire Alarm system does not meet current code and needs to be replaced. Fire alarm system is tested every day in the morning.

The present telephone system is adequate. During the assessment, randomly, we verified that each wall mounted handset is provided with dial tone. An independent and separate PA system does not exist, or is not working. School uses the telephone systems for public announcement. System is working adequately for most part. The present clocks and control panel are manufactured by Standard. Clock system is old and difficult to find parts and repair, most of the classrooms are provided with stand-alone clocks. Replace clock system with wireless, synchronized, battery operated system. There is not television system. The security system consists of surveillance (5) CCTV cameras at the first floor. To have the complete coverage of the interior of the school building additional surveillance CCTV cameras are required. During the assessment, we did not have access to the IT room. School district standard is to provide adequate UPS in the IT room.

Site Assessment Report - S643001;Wister

The emergency power system consists of a gas powered generator, manufactured by Generac, rated 15KW, 120/240V. The present emergency power system serves the corridor, exit signs, stair ways, gymnasium, auditorium and boiler room. The gas powered generator was installed in 1994 and is expected to provide 10 more years of useful service life. Present emergency system does not have the capacity to carry future emergency loads. Provide new outdoor, diesel powered generator. The emergency lighting is obtained with dedicated fixtures connected to the emergency generator. Exit signs are located at each exit door and corridors and are connected to the school emergency system.

The lightning protection is obtained with air terminals at the school chimney. A study should be conducted to determine if the existing lightning system provide the proper protection to the school building. The stage theatrical lighting is composed of two rows of upstage and one row of front floodlight fixtures. Theatrical lighting fixtures are controlled by a local panelboard. Modern school auditorium requires front, upstage, high side, back, theatrical lighting and to create different scenes theatrical lighting fixtures are controlled by a dimming system. Provide theatrical lighting and dimming control system. The sound system is by GS General Sound System. During the assessment the GS General Sound System cabinet was not accessible indicating that is not frequently use. Most probably the stage sound system is provided by a portable system. Provide a permanent installed modern sound system.

The school perimeter is illuminated with wall mounted fixtures providing total perimeter coverage. There are six outdoor surveillance CCTV cameras. Add more outdoor surveillance CCTV cameras to provide a complete coverage of the building perimeter. The exterior of the school is provided with two loud speakers, one is facing the play area and the other is facing the parking lot. No additional outdoor loud speakers are required.

GROUPS SYSTEMS

The asphalt parking lot is located in the northeast corner of the site. Striping is faded. There are no parking bumpers. There is no designated accessible parking with an accessible route to the building. Asphalt is in fair to poor condition with some settled areas, ponding, alligatoring, deeper cracking and vegetation in the asphalt. The parking area is segregated from playgrounds with low picket fencing. The western side has a retaining wall at the grade separation to adjacent playgrounds. Asphalt playgrounds are in fair condition with some settled areas, ponding, alligatoring, deeper cracking and vegetation in the asphalt. Other pedestrian paving is concrete along city streets and a large swath from Wakefield St. to the main entry. Exterior steps

Fencing types include metal picket and chain link and brick. Fencing adjacent to commercial property at the south end is topped with razor wire. Playground equipment is installed over a padded play surface at the front of the building and at the back. There is a rectangle of artificial turf at the back of the building. There is a rusted flagpole in the front yard and pole mounted basketball hoops with backboards in the back. A retaining wall topped by chain link fence runs south of the building along the west property line and shows no signs of distress.

Landscaping consists of mature and newly planted street trees at the site perimeter and some on-site mature trees and shrubs. There is a lawn area with several large stumps around the kitchen and another couple of small lawn areas near the entry. There is no irrigation system.

RECOMMENDATIONS

- Replace roofing
- Install ladders from gym/auditorium roof to lower roofs at kitchen and entry areas
- Repair exterior walls: point brick, particularly around windows; install expansion joint between the original construction and the addition
- Replace exterior windows
- Replace exterior doors
- Reconfigure toilet rooms on each floor and at the cafeteria/auditorium for accessibility; provide new toilet partitions and toilet accessories including grab bars. Provide unisex accessible toilets on each floor for faculty/staff and in the nurse office.
- Replace handrails in stairwells
- Replace 9" VAT with 12" VCT
- Refinish wood floors
- Replace library carpeting
- Replace interior signage
- Replace glued acoustical tile ceilings where they occur
- Replace damaged/stained 2x4 acoustical tiles in existing grid. Replace damaged grid
- Replace chalkboards with marker boards
- Install an interior ramp from entrance to 1st floor school level
- Install an elevator between the original building and the classroom addition with landings/stops at each level.

Site Assessment Report - S643001;Wister

- Refurbish auditorium seating
- Replace classroom cabinetry

MECHANICAL

- Replace half of water closets due to age, stains, cracks, 28
- Replace half of urinals due to appearance and age, 12
- Replace half of toilet lavatories and classroom sinks due to age and appearance, 20 lav and 11 sinks
- Replace service sinks due to age and appearance, 5
- Replace fountains due to accessibility, 5
- Install backflow preventer at water entry, 4 inch
- Replace domestic tankless water heaters due to age, 2
- Replace sanitary drain pipes due to age, 97,000 s.f.
- Repair or replace boiler due to water leak, 66 HP
- Survey and repair steam traps, 69,000 s.f.
- Install 230 ton chiller system, 69,000 s.f.
- Replace unit ventilators, 51
- Replace auditorium AHU, 298 seats
- Replace gym AHU, 4,400 s.f.
- Replace missing, inoperable, and inadequate toilet exhaust fans, 11
- Replace steam pipe due to age and rust, 69,000 s.f.
- Replace finned tube convection units, 300 l.f.
- Convert pneumatic controls to DDC, 93,000 s.f.
- Install fire protection sprinkler system, 93,000 s.f.
- Install fire suppression system for kitchen range and oven in exhaust hood

ELECTRICAL

- Provide a new electrical service 277/480V, 3 phase power, 1600 Amperes and 500KVA step-down transformer.
- Replace the entire distribution system with new panels and new wiring/conduits. Approximate (12) 208/120V panel boards.
- Provide (2)25FT of surface raceways with receptacles spaced 24" on center/classroom and 4 wall mount receptacles/classroom. Approximate 512 receptacles.
- Replace fluorescent fixtures with T-12 lamps with fluorescent fixtures with T-8 lamps. Approximate 870 fixtures.
- Replace old fire alarm system with addressable type with audio/visual devices at corridors and classrooms. Approximate 125 devices
- Replace clock system with wireless, synchronized, battery operated, clock system. Approximate 70 clocks.
- Provide indoor surveillance CCTV cameras for complete coverage of the school building interior. Approximate 30
- Provide 100KW, outdoor, diesel powered generator.
- Prepare a study to determine if the air terminals mounted on the chimney provide the proper protection to the school building.
- Provide theatrical lighting and dimming control system.
- Provide a permanent installed modern sound system.
- Provide outdoor surveillance CCTV cameras to the building exterior for full coverage of the perimeter. Approximate 4 CCTV cameras.

GROUNDS

- Resurface asphalt parking lot & playground
- Repair site steps. Install additional landings/steps at exterior doors where step exceeds 8"
- Install ramp to front entry doors

Attributes:

General Attributes:

Active:	Open	Bldg Lot Tm:	Lot 5 / Tm 3
Status:	Accepted by SDP	Team:	Tm 3
Site ID:	S643001		

Site Condition Summary

The Table below shows the CI and FCI for each major system shown at the UNIFORMAT classification Level II. Note that Systems with lower FCIs require less investment than systems with higher FCIs.


Current Investment Requirement and Condition by Uniformat Classification

UNIFORMAT Classification	RSLI%	FCI %	Current Repair
A10 - Foundations	40.00 %	0.00 %	\$0.00
A20 - Basement Construction	40.00 %	0.00 %	\$0.00
B10 - Superstructure	40.00 %	0.67 %	\$56,207.07
B20 - Exterior Enclosure	62.52 %	49.69 %	\$2,624,723.33
B30 - Roofing	109.51 %	89.33 %	\$1,118,716.26
C10 - Interior Construction	57.56 %	103.35 %	\$2,376,829.90
C20 - Stairs	40.00 %	102.05 %	\$134,850.11
C30 - Interior Finishes	75.36 %	10.98 %	\$587,384.58
D10 - Conveying	105.71 %	304.96 %	\$1,251,764.48
D20 - Plumbing	88.54 %	75.16 %	\$1,438,212.47
D30 - HVAC	94.83 %	73.74 %	\$7,686,853.34
D40 - Fire Protection	105.71 %	185.92 %	\$1,404,369.51
D50 - Electrical	110.11 %	49.17 %	\$2,708,678.16
E10 - Equipment	51.93 %	19.68 %	\$293,594.70
E20 - Furnishings	105.00 %	166.45 %	\$332,263.31
G20 - Site Improvements	39.47 %	22.83 %	\$394,649.67
G40 - Site Electrical Utilities	46.31 %	14.74 %	\$73,750.98
Totals:	72.02 %	45.11 %	\$22,482,847.87

Condition Deficiency Priority

Facility Name	Gross Area (S.F.)	FCI %	1 - Response Time (< 2 yr)	2 - Response Time (2-3 yrs)	3 - Response Time (3-4 yrs)	4 - Response Time (4-5 yrs)	5 - Response Time (> 5 yrs)
B643001;Wister	93,715	46.24	\$1,479,963.03	\$8,958,242.77	\$3,387,013.32	\$1,857,231.38	\$6,331,996.72
G643001;Grounds	115,000	21.02	\$9,093.63	\$29,005.10	\$430,301.92	\$0.00	\$0.00
Total:		45.11	\$1,489,056.66	\$8,987,247.87	\$3,817,315.24	\$1,857,231.38	\$6,331,996.72

Deficiencies By Priority




Executive Summary

Building condition is evaluated based on the functional systems and elements of a building and organized according to the UNIFORMAT II Elemental Classification. The grouping of these systems and elements and applying a current replacement value to them develops a representative building cost model. Cost Models are developed for similar building types and functions. Systems and their elements are evaluated based on their current replacement values, life cycles, installation dates and next renewal dates. Systems and their elements that are within their useful lives are further evaluated to identify current deficient conditions that may have a significant impact on a system's or element's remaining service life, and to determine if they are beyond their predicted expected life. The system's or element's current replacement value is based on RS Means Commercial Cost Data.

Following are the cost model's system details for this facility. The Replacement Value is the amount needed to replace the property of the same present value. The Current Repair Amount, also known as Condition Needs, represents the budgeted contractor installed costs plus owner's soft costs for the repair, replacement or renewal for a component or system level deficiency. It excludes contributing costs for other components or systems that might also be associated with the corrective actions due to packaging the work. Facility Condition Index (FCI) FCI is an industry-standard measurement of facility condition calculated as the ratio of the costs to correct a facility's deficiencies to the facility's Current Replacement Value. It ranges from 0% (new) to 100% (very poor). Condition Index (CI) is calculated as the sum of a renewable system's Remaining Service Life (RSL) divided by the sum of a system's Replacement Value (both values exclude soft-cost to simplify calculation updates) expressed as a percentage ranging from 100% (new) to 0% (expired).

Function:	Elementary School
Gross Area (SF):	93,715
Year Built:	1955
Last Renovation:	
Replacement Value:	\$47,612,533
Repair Cost:	\$22,014,447.22
Total FCI:	46.24 %
Total RSLI:	73.47 %



Description:

Attributes:

General Attributes:

Active:	Open	Bldg ID:	B643001
Sewage Ejector:	No	Status:	Accepted by SDP
Site ID:	S643001		

Condition Summary

The Table below shows the CI and FCI for each major building system shown at the UNIFORMAT classification Level II. Note that Systems with lower FCIs require less investment than systems with higher FCIs.

UNIFORMAT Classification	RSLI %	FCI %	Current Repair Cost
A10 - Foundations	40.00 %	0.00 %	\$0.00
A20 - Basement Construction	40.00 %	0.00 %	\$0.00
B10 - Superstructure	40.00 %	0.67 %	\$56,207.07
B20 - Exterior Enclosure	62.52 %	49.69 %	\$2,624,723.33
B30 - Roofing	109.51 %	89.33 %	\$1,118,716.26
C10 - Interior Construction	57.56 %	103.35 %	\$2,376,829.90
C20 - Stairs	40.00 %	102.05 %	\$134,850.11
C30 - Interior Finishes	75.36 %	10.98 %	\$587,384.58
D10 - Conveying	105.71 %	304.96 %	\$1,251,764.48
D20 - Plumbing	88.54 %	75.16 %	\$1,438,212.47
D30 - HVAC	94.83 %	73.74 %	\$7,686,853.34
D40 - Fire Protection	105.71 %	185.92 %	\$1,404,369.51
D50 - Electrical	110.11 %	49.17 %	\$2,708,678.16
E10 - Equipment	51.93 %	19.68 %	\$293,594.70
E20 - Furnishings	105.00 %	166.45 %	\$332,263.31
Totals:	73.47 %	46.24 %	\$22,014,447.22

Condition Detail

This section of the report contains results of the Facility Condition Assessment. The building is separated into system components based on UNIFORMAT II classification. The columns in the System Listing table below represent the following:

1. System Code: A code that identifies the system.
2. System Description: A brief description of a system present in the building.
3. Unit Price \$: The unit price of the system.
4. UoM: The unit of measure for of the system.
5. Qty: The quantity for the system
6. Life: anticipated service life for the system based on Building Owners and Managers Association (BOMA) recommendations.
7. Year Installed: The date of system installation.
8. Calc Next Renewal Year: The date of system expiration based on the life, NR stands for non renewable.
9. Next Renewal Year: The suggested system expiration date by the assessor based on visual inspection.
10. CI: The Condition Index of the system.
11. FCI: The Facility Condition Index of the system.
12. RSL: Remaining Service Life.
13. eCR: eCOMET Condition Rating (not used).
14. Deficiency \$: The financial investment to repair/replace system.

System Listing

The System Listing table below lists each of the systems organized by their UNIFORMAT II classification. The assessment team was tasked with recording the most recent replacement year of each system, determining the remaining service life based on the theoretical life, and evaluating the condition to confirm the forecast next replacement year. The system listing is the basis for all data contained in the Building Assessment Report.

Additionally, a condition rating (eCR) based on the following guidelines is provided as observed at the time of the assessment.

- Excellent (E) - No noticeable distress or damage. The entire system is free from observable defect.
- Very Good (VG) - Overall no serviceability reduction for the entire system. No degradation of critical components and minor distress and defect noticeable for some but not non critical components within the system.
- Good (G) - Slight or no serviceability reduction for the entire system. There may be noticeable defects for some non critical components and slight noticeable degradation of the critical components.
- Fair (F) - Overall serviceability is degraded but adequate. There may be moderate deterioration for very few of the critical components and few of the non critical components may have severe degradation.
- Marginal (MA) - Overall serviceability and reliability loss. Most if not all of the non critical components suffer from severe degradation and a few of the critical component may have severe degradation.
- Moderate (MO) - Overall a significant serviceability loss. Most if not all the components have severe degradation with the reminder of the component showing visible distress.
- Very Poor (VP) - Overall the system is barely functional. All of the components are severely degraded.
- Non-Functional (NF) - Overall the system does not function with all the components having no serviceability and suffer from severe degradation.

System Code	System Description	Unit Price \$	UoM	Qty	Life	Year Installed	Calc Next Renewal Year	Next Renewal Year	RSLI%	FCI%	RSL	eCR	Deficiency \$	Replacement Value \$
A1010	Standard Foundations	\$18.40	S.F.	93,715	100	1955	2055		40.00 %	0.00 %	40			\$1,724,356
A1030	Slab on Grade	\$7.73	S.F.	93,715	100	1955	2055		40.00 %	0.00 %	40			\$724,417
A2010	Basement Excavation	\$6.55	S.F.	93,715	100	1955	2055		40.00 %	0.00 %	40			\$613,833
A2020	Basement Walls	\$12.70	S.F.	93,715	100	1955	2055		40.00 %	0.00 %	40			\$1,190,181
B1010	Floor Construction	\$75.10	S.F.	93,715	100	1955	2055		40.00 %	0.80 %	40		\$56,207.07	\$7,037,997
B1020	Roof Construction	\$13.88	S.F.	93,715	100	1955	2055		40.00 %	0.00 %	40			\$1,300,764
B2010	Exterior Walls	\$36.91	S.F.	93,715	100	1955	2055		40.00 %	9.60 %	40		\$332,176.08	\$3,459,021
B2020	Exterior Windows	\$18.01	S.F.	93,715	40	1955	1995	2057	105.00 %	118.50 %	42		\$1,999,980.50	\$1,687,807
B2030	Exterior Doors	\$1.45	S.F.	93,715	25	1990	2015	2042	108.00 %	215.30 %	27		\$292,566.75	\$135,887
B3010105	Built-Up	\$37.76	S.F.	33,018	20	1995	2015	2037	110.00 %	89.73 %	22		\$1,118,716.26	\$1,246,760
B3010120	Single Ply Membrane	\$38.73	S.F.		20				0.00 %	0.00 %				\$0
B3010130	Preformed Metal Roofing	\$54.22	S.F.		30				0.00 %	0.00 %				\$0
B3010140	Shingle & Tile	\$38.73	S.F.		25				0.00 %	0.00 %				\$0
B3020	Roof Openings	\$0.06	S.F.	93,715	20				0.00 %	0.00 %				\$5,623
C1010	Partitions	\$17.91	S.F.	93,715	100	1955	2055		40.00 %	117.21 %	40		\$1,967,335.90	\$1,678,436
C1020	Interior Doors	\$3.51	S.F.	93,715	40	1955	1995	2057	105.00 %	105.53 %	42		\$347,127.31	\$328,940
C1030	Fittings	\$3.12	S.F.	93,715	40	1955	1995	2057	105.00 %	21.33 %	42		\$62,366.69	\$292,391
C2010	Stair Construction	\$1.41	S.F.	93,715	100	1955	2055		40.00 %	102.05 %	40		\$134,850.11	\$132,138

Site Assessment Report - B643001;Wister

System Code	System Description	Unit Price \$	UoM	Qty	Life	Year Installed	Calc Next Renewal Year	Next Renewal Year	RSI%	FCI%	RSL	eCR	Deficiency \$	Replacement Value \$
C3010230	Paint & Covering	\$17.70	S.F.	93,715	10	2012	2022	2022	70.00 %	0.00 %	7			\$1,658,756
C3010231	Vinyl Wall Covering	\$0.00	S.F.		15				0.00 %	0.00 %				\$0
C3010232	Wall Tile	\$1.98	S.F.	93,715	30	1955	1985	2047	106.67 %	0.00 %	32			\$185,556
C3020411	Carpet	\$7.30	S.F.	1,800	10	2000	2010	2027	120.00 %	153.30 %	12		\$20,143.38	\$13,140
C3020412	Terrazzo & Tile	\$75.52	S.F.	9,400	50	1955	2005	2067	104.00 %	0.00 %	52			\$709,888
C3020413	Vinyl Flooring	\$9.68	S.F.	73,115	20	1955	1975	2037	110.00 %	62.79 %	22		\$444,383.37	\$707,753
C3020414	Wood Flooring	\$22.27	S.F.	4,700	25	1955	1980	2042	108.00 %	48.35 %	27		\$50,604.62	\$104,669
C3020415	Concrete Floor Finishes	\$0.97	S.F.	4,700	50	1955	2005	2067	104.00 %	0.00 %	52			\$4,559
C3030	Ceiling Finishes	\$20.97	S.F.	93,715	25	1955	1980	2028	52.00 %	3.68 %	13		\$72,253.21	\$1,965,204
D1010	Elevators and Lifts	\$4.38	S.F.	93,715	35			2052	105.71 %	304.96 %	37		\$1,251,764.48	\$410,472
D2010	Plumbing Fixtures	\$13.52	S.F.	93,715	35	1955	1990	2047	91.43 %	37.21 %	32		\$471,516.46	\$1,267,027
D2020	Domestic Water Distribution	\$1.68	S.F.	93,715	25	1955	1980	2042	108.00 %	352.37 %	27		\$554,774.98	\$157,441
D2030	Sanitary Waste	\$2.90	S.F.	93,715	25	1955	1980	2042	108.00 %	151.57 %	27		\$411,921.03	\$271,774
D2040	Rain Water Drainage	\$2.32	S.F.	93,715	30	1955	1985	2025	33.33 %	0.00 %	10			\$217,419
D3020	Heat Generating Systems	\$18.67	S.F.	93,715	35	1990	2025		28.57 %	14.03 %	10		\$245,555.06	\$1,749,659
D3030	Cooling Generating Systems	\$24.48	S.F.	93,715	30			2047	106.67 %	48.30 %	32		\$1,108,098.20	\$2,294,143
D3040	Distribution Systems	\$42.99	S.F.	93,715	25	1955	1980	2042	108.00 %	107.68 %	27		\$4,338,155.58	\$4,028,808
D3050	Terminal & Package Units	\$11.60	S.F.	93,715	20	1955	1975	2037	110.00 %	0.00 %	22			\$1,087,094
D3060	Controls & Instrumentation	\$13.50	S.F.	93,715	20	1955	1975	2037	110.00 %	157.69 %	22		\$1,995,044.50	\$1,265,153
D4010	Sprinklers	\$7.05	S.F.	93,715	35			2052	105.71 %	212.56 %	37		\$1,404,369.51	\$660,691
D4020	Standpipes	\$1.01	S.F.	93,715	35			2052	105.71 %	0.00 %	37			\$94,652
D5010	Electrical Service/Distribution	\$9.70	S.F.	93,715	30	1955	1985	2047	106.67 %	87.35 %	32		\$794,009.71	\$909,036
D5020	Lighting and Branch Wiring	\$34.68	S.F.	93,715	20	1955	1975	2037	110.00 %	28.86 %	22		\$937,894.16	\$3,250,036
D5030	Communications and Security	\$12.99	S.F.	93,715	15	1955	1970	2032	113.33 %	61.73 %	17		\$751,502.10	\$1,217,358
D5090	Other Electrical Systems	\$1.41	S.F.	93,715	30	1955	1985	2047	106.67 %	170.48 %	32		\$225,272.19	\$132,138
E1020	Institutional Equipment	\$4.82	S.F.	93,715	35	1955	1990	2052	105.71 %	65.00 %	37		\$293,594.70	\$451,706
E1090	Other Equipment	\$11.10	S.F.	93,715	35	1990	2025		28.57 %	0.00 %	10			\$1,040,237
E2010	Fixed Furnishings	\$2.13	S.F.	93,715	40	1955	1995	2057	105.00 %	166.45 %	42		\$332,263.31	\$199,613
Total									73.47 %	46.24 %			\$22,014,447.22	\$47,612,533

System Notes

The facility description in the site executive summary contains an overview of each system. The notes listed below provide additional information on select systems found within the facility.

System:	C3010 - Wall Finishes	This system contains no images
Note:	Paint 90% Tile 10%	
System:	C3020 - Floor Finishes	This system contains no images
Note:	Carpet 2% Terrazzo/Tile 10% Vinyl 78% Wood 5% Concrete 5%	
System:	C3030 - Ceiling Finishes	This system contains no images
Note:	Painted structure 65% 2x4 suspended acoustical tile 25% 12" or 1x2 glue-on acoustical tile 10%	

System: D5010 - Electrical Service/Distribution



Note: There is a phase converter rated 75KVA (estimated)

Renewal Schedule

eCOMET forecasts future Capital Renewal funding needed to address expiring systems based on the Next Renewal year found in the Cost Models. A 3% annual inflation factor is applied to the costs for systems expiring in future years. The table below reflects recommended Capital Renewal funding needs over the next 10 years. Note: Cells with a zero value indicate systems for which renewal is not scheduled in that year.

Inflation Rate: 3%

System	Current Deficiencies	2016	2017	2018	2019	2020	2021	2022	2023	2024	2025	Total
Total:	\$22,014,447	\$0	\$0	\$0	\$0	\$0	\$0	\$2,244,066	\$0	\$0	\$4,445,737	\$28,704,250
* A - Substructure	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0
A10 - Foundations	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0
A1010 - Standard Foundations	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0
A1030 - Slab on Grade	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0
A20 - Basement Construction	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0
A2010 - Basement Excavation	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0
A2020 - Basement Walls	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0
B - Shell	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0
B10 - Superstructure	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0
B1010 - Floor Construction	\$56,207	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$56,207
B1020 - Roof Construction	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0
B20 - Exterior Enclosure	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0
B2010 - Exterior Walls	\$332,176	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$332,176
B2020 - Exterior Windows	\$1,999,981	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$1,999,981
B2030 - Exterior Doors	\$292,567	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$292,567
B30 - Roofing	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0
B3010 - Roof Coverings	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0
B3010105 - Built-Up	\$1,118,716	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$1,118,716
B3010120 - Single Ply Membrane	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0
B3010130 - Preformed Metal Roofing	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0
B3010140 - Shingle & Tile	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0
B3020 - Roof Openings	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0
C - Interiors	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0
C10 - Interior Construction	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0
C1010 - Partitions	\$1,967,336	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$1,967,336

Site Assessment Report - B643001;Wister

C1020 - Interior Doors	\$347,127	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$347,127
C1030 - Fittings	\$62,367	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$62,367
C20 - Stairs	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0
C2010 - Stair Construction	\$134,850	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$134,850
C30 - Interior Finishes	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0
C3010 - Wall Finishes	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0
C3010230 - Paint & Covering	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$2,244,066	\$0	\$0	\$0	\$2,244,066
C3010231 - Vinyl Wall Covering	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0
C3010232 - Wall Tile	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0
C3020 - Floor Finishes	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0
C3020411 - Carpet	\$20,143	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$20,143
C3020412 - Terrazzo & Tile	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0
C3020413 - Vinyl Flooring	\$444,383	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$444,383
C3020414 - Wood Flooring	\$50,605	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$50,605
C3020415 - Concrete Floor Finishes	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0
C3030 - Ceiling Finishes	\$72,253	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$72,253
D - Services	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0
D10 - Conveying	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0
D1010 - Elevators and Lifts	\$1,251,764	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$1,251,764
D20 - Plumbing	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0
D2010 - Plumbing Fixtures	\$471,516	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$471,516
D2020 - Domestic Water Distribution	\$554,775	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$554,775
D2030 - Sanitary Waste	\$411,921	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$411,921
D2040 - Rain Water Drainage	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$321,412	\$321,412
D30 - HVAC	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0
D3020 - Heat Generating Systems	\$245,555	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$2,586,535	\$2,832,090
D3030 - Cooling Generating Systems	\$1,108,098	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$1,108,098
D3040 - Distribution Systems	\$4,338,156	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$4,338,156
D3050 - Terminal & Package Units	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0
D3060 - Controls & Instrumentation	\$1,995,045	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$1,995,045
D40 - Fire Protection	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0
D4010 - Sprinklers	\$1,404,370	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$1,404,370
D4020 - Standpipes	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0


Site Assessment Report - B643001;Wister

D50 - Electrical	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0
D5010 - Electrical Service/Distribution	\$794,010	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$794,010
D5020 - Lighting and Branch Wiring	\$937,894	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$937,894
D5030 - Communications and Security	\$751,502	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$751,502
D5090 - Other Electrical Systems	\$225,272	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$225,272
E - Equipment & Furnishings	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0
E10 - Equipment	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0
E1020 - Institutional Equipment	\$293,595	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$293,595
E1090 - Other Equipment	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$1,537,790	\$1,537,790
E20 - Furnishings	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0
E2010 - Fixed Furnishings	\$332,263	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$332,263

* Indicates non-renewable system

Forecasted Sustainment Requirement

The following chart shows the current building deficiencies and forecasting sustainment requirements over the next ten years.




10 Year FCI Forecast by Investment Scenario

The chart below illustrates the effect of various investment levels on the building FCI for the next 10 years. The levels of investment shown below include:

- Current FCI: a variable investment amount based on renewing expired systems to maintain the current FCI for the building
- 2% Investment: an annual investment of 2% of the replacement value of the building, escalated for inflation
- 4% Investment: an annual investment of 4% of the replacement value of the building, escalated for inflation


Facility Investment vs. FCI Forecast



Year	Investment Amount Current FCI - 46.24%	2% Investment		4% Investment	
		Amount	FCI	Amount	FCI
2016	\$0	\$980,818.00	44.24 %	\$1,961,636.00	42.24 %
2017	\$25,495,773	\$1,010,243.00	92.71 %	\$2,020,485.00	88.71 %
2018	\$0	\$1,040,550.00	90.71 %	\$2,081,100.00	84.71 %
2019	\$0	\$1,071,767.00	88.71 %	\$2,143,533.00	80.71 %
2020	\$0	\$1,103,920.00	86.71 %	\$2,207,839.00	76.71 %
2021	\$0	\$1,137,037.00	84.71 %	\$2,274,074.00	72.71 %
2022	\$2,244,066	\$1,171,148.00	86.54 %	\$2,342,296.00	72.54 %
2023	\$0	\$1,206,283.00	84.54 %	\$2,412,565.00	68.54 %
2024	\$0	\$1,242,471.00	82.54 %	\$2,484,942.00	64.54 %
2025	\$4,445,737	\$1,279,745.00	87.49 %	\$2,559,491.00	67.49 %
Total:	\$32,185,576	\$11,243,982.00		\$22,487,961.00	

Deficiency Summary by System


Current deficiencies included assemblies that have reached or exceeded their design life or components of the assemblies that are in need of repair. Assemblies that have reached their design life are identified as current deficiencies and assigned the distress 'Beyond Useful Life'. The following chart lists all current deficiencies associated with this facility.



Budget Estimate Total: \$22,014,447.22

Deficiency Summary by Priority

The following chart shows the total repair costs broken down by priority. Assessors assigned deficiencies within eCOMET to one of the following priority categories:



Budget Estimate Total: \$22,014,447.22


Deficiency By Priority Investment Table

The table below shows the current investment cost grouped by deficiency priority and building system.

System Code	System Description	1 - Response Time (< 2 yr)	2 - Response Time (2-3 yrs)	3 - Response Time (3-4 yrs)	4 - Response Time (4-5 yrs)	5 - Response Time (> 5 yrs)	Total
B1010	Floor Construction	\$0.00	\$0.00	\$56,207.07	\$0.00	\$0.00	\$56,207.07
B2010	Exterior Walls	\$0.00	\$332,176.08	\$0.00	\$0.00	\$0.00	\$332,176.08
B2020	Exterior Windows	\$0.00	\$1,999,980.50	\$0.00	\$0.00	\$0.00	\$1,999,980.50
B2030	Exterior Doors	\$0.00	\$0.00	\$0.00	\$292,566.75	\$0.00	\$292,566.75
B3010105	Built-Up	\$1,118,716.26	\$0.00	\$0.00	\$0.00	\$0.00	\$1,118,716.26
C1010	Partitions	\$0.00	\$1,967,335.90	\$0.00	\$0.00	\$0.00	\$1,967,335.90
C1020	Interior Doors	\$0.00	\$347,127.31	\$0.00	\$0.00	\$0.00	\$347,127.31
C1030	Fittings	\$0.00	\$62,366.69	\$0.00	\$0.00	\$0.00	\$62,366.69
C2010	Stair Construction	\$134,850.11	\$0.00	\$0.00	\$0.00	\$0.00	\$134,850.11
C3020411	Carpet	\$0.00	\$0.00	\$0.00	\$20,143.38	\$0.00	\$20,143.38
C3020413	Vinyl Flooring	\$0.00	\$444,383.37	\$0.00	\$0.00	\$0.00	\$444,383.37
C3020414	Wood Flooring	\$0.00	\$0.00	\$50,604.62	\$0.00	\$0.00	\$50,604.62
C3030	Ceiling Finishes	\$0.00	\$72,253.21	\$0.00	\$0.00	\$0.00	\$72,253.21
D1010	Elevators and Lifts	\$0.00	\$1,251,764.48	\$0.00	\$0.00	\$0.00	\$1,251,764.48
D2010	Plumbing Fixtures	\$0.00	\$471,516.46	\$0.00	\$0.00	\$0.00	\$471,516.46
D2020	Domestic Water Distribution	\$0.00	\$14,294.27	\$0.00	\$48,947.09	\$491,533.62	\$554,774.98
D2030	Sanitary Waste	\$0.00	\$0.00	\$411,921.03	\$0.00	\$0.00	\$411,921.03
D3020	Heat Generating Systems	\$0.00	\$0.00	\$245,555.06	\$0.00	\$0.00	\$245,555.06
D3030	Cooling Generating Systems	\$0.00	\$0.00	\$0.00	\$0.00	\$1,108,098.20	\$1,108,098.20
D3040	Distribution Systems	\$226,396.66	\$0.00	\$783,763.53	\$0.00	\$3,327,995.39	\$4,338,155.58
D3060	Controls & Instrumentation	\$0.00	\$1,995,044.50	\$0.00	\$0.00	\$0.00	\$1,995,044.50
D4010	Sprinklers	\$0.00	\$0.00	\$0.00	\$0.00	\$1,404,369.51	\$1,404,369.51
D5010	Electrical Service/Distribution	\$0.00	\$0.00	\$794,009.71	\$0.00	\$0.00	\$794,009.71
D5020	Lighting and Branch Wiring	\$0.00	\$0.00	\$188,093.95	\$749,800.21	\$0.00	\$937,894.16
D5030	Communications and Security	\$0.00	\$0.00	\$299,322.85	\$452,179.25	\$0.00	\$751,502.10
D5090	Other Electrical Systems	\$0.00	\$0.00	\$225,272.19	\$0.00	\$0.00	\$225,272.19
E1020	Institutional Equipment	\$0.00	\$0.00	\$0.00	\$293,594.70	\$0.00	\$293,594.70
E2010	Fixed Furnishings	\$0.00	\$0.00	\$332,263.31	\$0.00	\$0.00	\$332,263.31
Total:		\$1,479,963.03	\$8,958,242.77	\$3,387,013.32	\$1,857,231.38	\$6,331,996.72	\$22,014,447.22

Deficiency Summary by Category

The following chart shows the total repair costs broken down by deficiency categories. Assessors assigned deficiencies to one of the following categories:



Deficiency Details by Priority

The deficiency detail notes listed below provide additional information on identified deficiencies found within the facility.

Priority 1 - Response Time (< 2 yr):

System: B3010105 - Built-Up



Location: Roofs

Distress: Building Envelope Integrity

Category: 3 - Operations / Maint.

Priority: 1 - Response Time (< 2 yr)

Correction: Remove and Replace Built Up Roof

Qty: 33,018.00

Unit of Measure: S.F.


Estimate: \$1,118,716.26

Assessor Name: System

Date Created: 02/18/2016

Notes: Replace roofs at the end of expected service life. Roofs are in poor condition with some patching evident, wrinkling and splitting, and considerable loss of granules on the wear surface.

System: C2010 - Stair Construction



Location: Interior stairs

Distress: Building / MEP Codes

Category: 2 - Code Compliance

Priority: 1 - Response Time (< 2 yr)

Correction: Replace inadequate or install proper stair railing - select appropriate material

Qty: 400.00

Unit of Measure: L.F.

Estimate: \$134,850.11

Assessor Name: System

Date Created: 02/17/2016

Notes: Handrails in stairwells do not conform to modern codes. There are pinch points at intermediate landings in some stairwells. Barrier rails at landings are too low. Handrails do not extend at landings or return to walls.

System: D3040 - Distribution Systems



Location: Original building

Distress: Failing

Category: 3 - Operations / Maint.

Priority: 1 - Response Time (< 2 yr)

Correction: Conduct a steam trap survey and replace failed units.

Qty: 69,000.00

Unit of Measure: S.F.

Estimate: \$226,396.66

Assessor Name: System

Date Created: 02/23/2016

Notes: Survey and repair steam traps

Priority 2 - Response Time (2-3 yrs):

System: B2010 - Exterior Walls



Location: Around the building

Distress: Damaged

Category: 3 - Operations / Maint.

Priority: 2 - Response Time (2-3 yrs)

Correction: Repair cracks in masonry - replace missing mortar and repoint - SF of wall area

Qty: 10,000.00

Unit of Measure: S.F.

Estimate: \$322,894.72

Assessor Name: System

Date Created: 02/17/2016

Notes: Repair exterior walls, particularly around windows where security grilles have been removed. Repoint mortar joints and fill anchor holes.

System: B2010 - Exterior Walls



Location: Northwest wing

Distress: OSHA

Category: 2 - Code Compliance

Priority: 2 - Response Time (2-3 yrs)

Correction: Add fixed ladders to wall

Qty: 18.00

Unit of Measure: V.L.F.

Estimate: \$4,992.92

Assessor Name: System

Date Created: 02/17/2016

Notes: Install fixed ladders to low roofs at kitchen and lobby to provide safe access for inspection and maintenance of roofs and roof mounted equipment.

System: B2010 - Exterior Walls



Location: At addition

Distress: Building Envelope Integrity

Category: 3 - Operations / Maint.

Priority: 2 - Response Time (2-3 yrs)

Correction: Remove and replace expansion joints at exterior walls

Qty: 48.00

Unit of Measure: L.F.


Estimate: \$4,288.44

Assessor Name: System

Date Created: 02/17/2016

Notes: Provide expansion joint between original building and addition. Caulk joint is failing.

System: B2020 - Exterior Windows



Location: Exterior windows

Distress: Building Envelope Integrity

Category: 3 - Operations / Maint.

Priority: 2 - Response Time (2-3 yrs)

Correction: Remove and replace aluminum windows - pick the appropriate size and style and insert the number of units

Qty: 315.00

Unit of Measure: Ea.

Estimate: \$1,999,980.50

Assessor Name: System

Date Created: 02/18/2016

Notes: Windows are not energy efficient and are in poor condition with failed gaskets, difficult operation and discolored glazing.

System: C1010 - Partitions



Location: Student restrooms

Distress: Accessibility

Category: 2 - Code Compliance

Priority: 2 - Response Time (2-3 yrs)

Correction: Build new gang restroom to meet code or occupant needs - select type and number of fixtures and toilet partitions for mens or womens

Qty: 8.00

Unit of Measure: Ea.

Estimate: \$1,686,032.01

Assessor Name: System

Date Created: 02/18/2016

Notes: Student restrooms do not comply with ADA codes for accessibility. Renovate restrooms for each sex on each floor of the building, as well as locker/toilet rooms at the cafeteria/gym/auditorium wing for accessibility. This deficiency/correction will also address condition issues in toilet rooms where flooring and toilet partitions are in poor condition.

System: C1010 - Partitions



Location: TBD

Distress: Accessibility

Category: 2 - Code Compliance

Priority: 2 - Response Time (2-3 yrs)

Correction: Build new single restroom to meet code requirements

Qty: 4.00

Unit of Measure: Ea.

Estimate: \$281,303.89

Assessor Name: System

Date Created: 02/18/2016

Notes: Provide unisex accessible toilet rooms for faculty and staff at each level of the building. Provide accessible toilet room at nurse office.

System: C1020 - Interior Doors



Location: Interior doors

Distress: Beyond Service Life

Category: 3 - Operations / Maint.

Priority: 2 - Response Time (2-3 yrs)

Correction: Remove and replace interior doors - wood doors with hollow metal frames - per leaf

Qty: 100.00

Unit of Measure: Ea.

Estimate: \$347,127.31

Assessor Name: System

Date Created: 02/17/2016

Notes: Doors are in fair to poor condition, and do not have ADA compliant hardware. Master key system in building is not functional and needs an overhaul. Replace interior doors in existing frames.

System: C1030 - Fittings



Location: Classrooms

Distress: Obsolete

Category: 3 - Operations / Maint.

Priority: 2 - Response Time (2-3 yrs)

Correction: Replace blackboards with marker boards - pick the appropriate size and insert the quantities

Qty: 24.00

Unit of Measure: Ea.

Estimate: \$35,275.44

Assessor Name: System

Date Created: 02/17/2016

Notes: Replace chalkboards with marker boards

System: C1030 - Fittings



Location: Interiors throughout

Distress: Building / MEP Codes

Category: 2 - Code Compliance

Priority: 2 - Response Time (2-3 yrs)

Correction: Replace missing or damaged signage - insert the number of rooms

Qty: 100.00

Unit of Measure: Ea.

Estimate: \$27,091.25

Assessor Name: System

Date Created: 02/17/2016

Notes: Install code compliant interior signage throughout the building.

System: C3020413 - Vinyl Flooring



Location: Auditorium, classrooms, corridors

Distress: Health Hazard / Risk

Category: 1 - Health & Safety

Priority: 2 - Response Time (2-3 yrs)

Correction: Remove VAT and replace with VCT - SF of area

Qty: 29,300.00

Unit of Measure: S.F.


Estimate: \$444,383.37

Assessor Name: System

Date Created: 02/17/2016

Notes: Replace 9" VAT with 12" VCT wherever it occurs.

System: C3030 - Ceiling Finishes



Location: Auditorium, lobby, misc. spaces

Distress: Damaged

Category: 3 - Operations / Maint.

Priority: 2 - Response Time (2-3 yrs)

Correction: Remove and replace glued on or mechanically attached acoustical ceiling tiles

Qty: 5,500.00

Unit of Measure: S.F.

Estimate: \$68,633.43

Assessor Name: System

Date Created: 02/17/2016

Notes: Replace glued acoustical tile ceilings where they occur. Ceilings are presumed original and have exceeded their expected life. Staining and loss of adhesion is widespread.

System: C3030 - Ceiling Finishes



Location: Classroom addition

Distress: Damaged

Category: 3 - Operations / Maint.

Priority: 2 - Response Time (2-3 yrs)

Correction: Remove and replace suspended acoustic ceilings - lighting not included

Qty: 240.00

Unit of Measure: S.F.

Estimate: \$3,619.78

Assessor Name: System

Date Created: 02/17/2016

Notes: Replace damaged 2 x 4 ceiling tiles. Replace a small area of damaged grid.

System: D1010 - Elevators and Lifts



Location: Between addition and main building

Distress: Accessibility

Category: 4 - Capital Improvement

Priority: 2 - Response Time (2-3 yrs)

Correction: Add external 5 stop elevator - adjust the electrical run lengths to hook up the elevator

Qty: 1.00

Unit of Measure: Ea.

Estimate: \$1,251,764.48

Assessor Name: System

Date Created: 02/17/2016

Notes: Install elevator to service classroom wing.

System: D2010 - Plumbing Fixtures



Location: Toilet rooms

Distress: Beyond Service Life

Category: 3 - Operations / Maint.

Priority: 2 - Response Time (2-3 yrs)

Correction: Remove and replace or replace water closet - quantify additional units

Qty: 28.00

Unit of Measure: Ea.

Estimate: \$208,940.14

Assessor Name: System

Date Created: 02/23/2016

Notes: Replace half of water closets due to age, stains, cracks,...

System: D2010 - Plumbing Fixtures



Location: Toilet rooms

Distress: Beyond Service Life

Category: 3 - Operations / Maint.

Priority: 2 - Response Time (2-3 yrs)

Correction: Remove and replace or replace lavatory - quantify accessible if required

Qty: 31.00

Unit of Measure: Ea.


Estimate: \$105,558.73

Assessor Name: System

Date Created: 02/23/2016

Notes: Replace half of toilet lavatories and classroom sinks due to age and appearance

System: D2010 - Plumbing Fixtures



Location: Corridors

Distress: Beyond Service Life

Category: 3 - Operations / Maint.

Priority: 2 - Response Time (2-3 yrs)

Correction: Remove and replace water fountains to meet ADA - includes high and low fountains and new recessed alcove

Qty: 5.00

Unit of Measure: Ea.

Estimate: \$78,464.48

Assessor Name: System

Date Created: 02/23/2016

Notes: Replace fountains due to accessibility

System: D2010 - Plumbing Fixtures



Location: Toilet rooms

Distress: Beyond Service Life

Category: 3 - Operations / Maint.

Priority: 2 - Response Time (2-3 yrs)

Correction: Remove and replace or replace wall hung urinals

Qty: 12.00

Unit of Measure: Ea.

Estimate: \$44,472.65

Assessor Name: System

Date Created: 02/23/2016

Notes: Replace half of urinals due to appearance and age

System: D2010 - Plumbing Fixtures



Location: Service closets

Distress: Beyond Service Life

Category: 3 - Operations / Maint.

Priority: 2 - Response Time (2-3 yrs)

Correction: Remove and replace floor janitor or mop sink - insert the quantity

Qty: 5.00

Unit of Measure: Ea.

Estimate: \$34,080.46

Assessor Name: System

Date Created: 02/23/2016

Notes: Replace service sinks due to age and appearance

System: D2020 - Domestic Water Distribution



Location: Boiler room

Distress: Building / MEP Codes

Category: 2 - Code Compliance

Priority: 2 - Response Time (2-3 yrs)

Correction: Provide 4" reduced pressure back flow preventer

Qty: 1.00

Unit of Measure: Ea.


Estimate: \$14,294.27

Assessor Name: System

Date Created: 02/23/2016

Notes: Install backflow preventer at water entry

System: D3060 - Controls & Instrumentation



Location: Entire building

Distress: Obsolete

Category: 3 - Operations / Maint.

Priority: 2 - Response Time (2-3 yrs)

Correction: Replace pneumatic controls with DDC (75KSF)

Qty: 93,000.00

Unit of Measure: S.F.

Estimate: \$1,995,044.50

Assessor Name: System

Date Created: 02/23/2016

Notes: Convert pneumatic controls to DDC

Priority 3 - Response Time (3-4 yrs):

System: B1010 - Floor Construction



Location: Lobby

Distress: Accessibility

Category: 2 - Code Compliance

Priority: 3 - Response Time (3-4 yrs)

Correction: Install interior handicap ramp - per LF 5' wide - insert the LF in the quantity

Qty: 28.00

Unit of Measure: L.F.

Estimate: \$56,207.07

Assessor Name: System

Date Created: 02/17/2016

Notes: Install interior ramp from entry lobby to classroom wing 1st floor,

System: C3020414 - Wood Flooring



Location: Gym and stage

Distress: Maintenance Required

Category: 3 - Operations / Maint.

Priority: 3 - Response Time (3-4 yrs)

Correction: Refinish wood floors

Qty: 4,700.00

Unit of Measure: S.F.


Estimate: \$50,604.62

Assessor Name: System

Date Created: 02/17/2016

Notes: Refinish worn wood floors

System: D2030 - Sanitary Waste



Location: Entire building

Distress: Beyond Service Life

Category: 3 - Operations / Maint.

Priority: 3 - Response Time (3-4 yrs)

Correction: Inspect sanitary waste piping and replace damaged sections. (+100KSF)

Qty: 97,000.00

Unit of Measure: S.F.

Estimate: \$411,921.03

Assessor Name: System

Date Created: 02/23/2016

Notes: Replace sanitary drain pipes due to age

System: D3020 - Heat Generating Systems



Location: Boiler room

Distress: Failing

Category: 3 - Operations / Maint.

Priority: 3 - Response Time (3-4 yrs)

Correction: Replace boiler, cast iron sectional (50 HP)

Qty: 1.00

Unit of Measure: Ea.

Estimate: \$245,555.06

Assessor Name: System

Date Created: 02/23/2016

Notes: Repair or replace boiler due to water leak, 66 HP

System: D3040 - Distribution Systems



Location: Original building

Distress: Beyond Service Life

Category: 3 - Operations / Maint.

Priority: 3 - Response Time (3-4 yrs)

Correction: Perform testing to identify and replace damaged steam and condensate piping.

Qty: 69,000.00

Unit of Measure: S.F.

Estimate: \$652,765.70

Assessor Name: System

Date Created: 02/23/2016

Notes: Replace steam pipe due to age and rust

System: D3040 - Distribution Systems



Location: Toilet room

Distress: Failing

Category: 3 - Operations / Maint.

Priority: 3 - Response Time (3-4 yrs)

Correction: Provide inline centrifugal fan and wall outlet louver for restroom exhaust (8 plbg fixtures)

Qty: 11.00

Unit of Measure: Ea.

Estimate: \$130,997.83

Assessor Name: System

Date Created: 02/23/2016

Notes: Replace missing, inoperable, and inadequate toilet exhaust fans

System: D5010 - Electrical Service/Distribution



Location: Basement

Distress: Inadequate

Category: 4 - Capital Improvement

Priority: 3 - Response Time (3-4 yrs)

Correction: Replace Switchboard

Qty: 1.00

Unit of Measure: Ea.

Estimate: \$468,870.59

Assessor Name: System

Date Created: 02/08/2016

Notes: Provide a new electrical service 277/480V, 3 phase power, 1600 Amperes and 500KVA step-down transformer.

System: D5010 - Electrical Service/Distribution



Location: Entire Building

Distress: Inadequate

Category: 4 - Capital Improvement

Priority: 3 - Response Time (3-4 yrs)

Correction: Replace Electrical Distribution System (U)

Qty: 1.00

Unit of Measure: Ea.

Estimate: \$325,139.12

Assessor Name: System

Date Created: 02/08/2016

Notes: Replace the entire distribution system with new panels and new wiring/conduits. Approximate (12) 208/120V panel boards.

System: D5020 - Lighting and Branch Wiring



Location: Entire Building

Distress: Inadequate

Category: 4 - Capital Improvement

Priority: 3 - Response Time (3-4 yrs)

Correction: Add wiring device

Qty: 1.00

Unit of Measure: Ea.

Estimate: \$188,093.95

Assessor Name: System

Date Created: 02/08/2016

Notes: Provide (2)25FT of surface raceways with receptacles spaced 24" on center/classroom and 4 wall mount receptacles/classroom. Approximate 512 receptacles.

System: D5030 - Communications and Security



Location: Entire Building

Distress: Life Safety / NFPA / PFD

Category: 1 - Health & Safety

Priority: 3 - Response Time (3-4 yrs)

Correction: Replace fire alarm system

Qty: 1.00

Unit of Measure: S.F.

Estimate: \$299,322.85

Assessor Name: System

Date Created: 02/08/2016

Notes: Replace old fire alarm system with addressable type with audio/visual devices at corridors and classrooms. Approximate 125 devices

System: D5090 - Other Electrical Systems



Location: Outdoor

Distress: Inadequate

Category: 4 - Capital Improvement

Priority: 3 - Response Time (3-4 yrs)

Correction: Add Standby Generator System

Qty: 1.00

Unit of Measure: Ea.

Estimate: \$201,022.37

Assessor Name: System

Date Created: 02/08/2016

Notes: Provide 100KW, outdoor, diesel powered generator.

System: D5090 - Other Electrical Systems



Location: Roof

Distress: Building / MEP Codes

Category: 2 - Code Compliance

Priority: 3 - Response Time (3-4 yrs)

Correction: Repair Lightning Protection System

Qty: 1.00

Unit of Measure: Job

Estimate: \$24,249.82

Assessor Name: System

Date Created: 02/08/2016

Notes: Prepare a study to determine if the air terminals mounted on the chimney provide the proper protection to the school building.

System: E2010 - Fixed Furnishings



Notes: Refurbish auditorium seating.

Location: Auditorium

Distress: Maintenance Required

Category: 3 - Operations / Maint.

Priority: 3 - Response Time (3-4 yrs)

Correction: Refinish auditorium seating

Qty: 300.00

Unit of Measure: Ea.

Estimate: \$193,206.54

Assessor Name: System

Date Created: 02/17/2016

System: E2010 - Fixed Furnishings



Notes: Replace classroom cabinetry that is delaminated, missing hardware, and generally in disrepair.

Location: Classrooms

Distress: Beyond Service Life

Category: 3 - Operations / Maint.

Priority: 3 - Response Time (3-4 yrs)

Correction: Remove and replace casework - per LF - insert quantities for cabinets in the estimate

Qty: 120.00

Unit of Measure: L.F.

Estimate: \$139,056.77

Assessor Name: System

Date Created: 02/17/2016

Priority 4 - Response Time (4-5 yrs):

System: B2030 - Exterior Doors



Location: Exterior doors throughout the building

Distress: Beyond Service Life

Category: 3 - Operations / Maint.

Priority: 4 - Response Time (4-5 yrs)

Correction: Remove and replace exterior doors - per leaf

Qty: 33.00

Unit of Measure: Ea.


Estimate: \$292,566.75

Assessor Name: System

Date Created: 02/18/2016

Notes: Replace exterior doors to maintain security and functionality.

System: C3020411 - Carpet



Location: Library

Distress: Damaged

Category: 3 - Operations / Maint.

Priority: 4 - Response Time (4-5 yrs)

Correction: Remove and replace carpet

Qty: 1,800.00

Unit of Measure: S.F.

Estimate: \$20,143.38

Assessor Name: System

Date Created: 02/18/2016

Notes: Replace library carpeting that is stained and damaged.

System: D2020 - Domestic Water Distribution



Location: Boiler room

Distress: Beyond Service Life

Category: 3 - Operations / Maint.

Priority: 4 - Response Time (4-5 yrs)

Correction: Replace instantaneous water heater

Qty: 2.00

Unit of Measure: Ea.


Estimate: \$48,947.09

Assessor Name: System

Date Created: 02/23/2016

Notes: Replace domestic tankless water heaters due to age

System: D5020 - Lighting and Branch Wiring



Location: Entire Building

Distress: Obsolete

Category: 3 - Operations / Maint.

Priority: 4 - Response Time (4-5 yrs)

Correction: Add Lighting Fixtures

Qty: 870.00

Unit of Measure: Ea.

Estimate: \$749,800.21

Assessor Name: System

Date Created: 02/08/2016

Notes: Replace fluorescent fixtures with T-12 lamps with fluorescent fixtures with T-8 lamps. Approximate 870 fixtures.

System: D5030 - Communications and Security



Location: Entire Building

Distress: Security Issue

Category: 1 - Health & Safety

Priority: 4 - Response Time (4-5 yrs)

Correction: Add/Replace Video Surveillance System

Qty: 1.00

Unit of Measure: Ea.

Estimate: \$377,075.76

Assessor Name: System

Date Created: 02/08/2016

Notes: Provide indoor surveillance CCTV cameras for complete coverage of the school building interior. Approximate 30

System: D5030 - Communications and Security



Location: Entire Building

Distress: Obsolete

Category: 3 - Operations / Maint.

Priority: 4 - Response Time (4-5 yrs)

Correction: Provide wireless GPS clock system

Qty: 1.00

Unit of Measure: LS

Estimate: \$48,958.59

Assessor Name: System

Date Created: 02/08/2016

Notes: Replace clock system with wireless, synchronized, battery operated, clock system. Approximate 70 clocks.

System: D5030 - Communications and Security



Location: Auditorium

Distress: Inadequate

Category: 4 - Capital Improvement

Priority: 4 - Response Time (4-5 yrs)

Correction: Add/Replace Sound System

Qty: 1.00

Unit of Measure: LS

Estimate: \$26,144.90

Assessor Name: System

Date Created: 02/08/2016

Notes: Provide a permanent installed modern sound system.

System: E1020 - Institutional Equipment



Location: Auditorium

Distress: Inadequate

Category: 4 - Capital Improvement

Priority: 4 - Response Time (4-5 yrs)

Correction: Add/Replace Stage Theatrical Lighting System

Qty: 1.00

Unit of Measure: Ea.

Estimate: \$293,594.70

Assessor Name: System

Date Created: 02/08/2016

Notes: Provide theatrical lighting and dimming control system.

Priority 5 - Response Time (> 5 yrs):

System: D2020 - Domestic Water Distribution



Location: Entire building

Distress: Beyond Service Life

Category: 3 - Operations / Maint.

Priority: 5 - Response Time (> 5 yrs)

Correction: Replace domestic water piping (75 KSF)

Qty: 97,000.00

Unit of Measure: S.F.

Estimate: \$491,533.62

Assessor Name: System

Date Created: 02/23/2016

Notes: Replace domestic water pipes due to age and signs of internal corrosion

System: D3030 - Cooling Generating Systems



Location: Entire building

Distress: Inadequate

Category: 4 - Capital Improvement

Priority: 5 - Response Time (> 5 yrs)

Correction: Install chilled water system with distribution piping and pumps. (+75KSF)

Qty: 69,000.00

Unit of Measure: S.F.


Estimate: \$1,108,098.20

Assessor Name: System

Date Created: 02/23/2016

Notes: install 230 ton chiller system

System: D3040 - Distribution Systems



Location: Classrooms

Distress: Beyond Service Life

Category: 3 - Operations / Maint.

Priority: 5 - Response Time (> 5 yrs)

Correction: Replace classroom unit ventilator (htg/clg coils, 5 tons, 2,000 CFM)

Qty: 51.00

Unit of Measure: Ea.

Estimate: \$2,543,812.31

Assessor Name: System

Date Created: 02/23/2016

Notes: Replace unit ventilators

System: D3040 - Distribution Systems



Location: Auditorium

Distress: Beyond Service Life

Category: 3 - Operations / Maint.

Priority: 5 - Response Time (> 5 yrs)

Correction: Replace HVAC unit for Auditorium (200 seat).

Qty: 298.00

Unit of Measure: Seat

Estimate: \$496,309.09

Assessor Name: System

Date Created: 02/23/2016

Notes: Replace auditorium AHU

System: D3040 - Distribution Systems



Location: Gym

Distress: Beyond Service Life

Category: 3 - Operations / Maint.

Priority: 5 - Response Time (> 5 yrs)

Correction: Replace HVAC unit for Gymnasium (single station)

Qty: 4,400.00

Unit of Measure: S.F.


Estimate: \$166,811.56

Assessor Name: System

Date Created: 02/23/2016

Notes: Replace gym AHU

System: D3040 - Distribution Systems



Location: Entire building

Distress: Beyond Service Life

Category: 3 - Operations / Maint.

Priority: 5 - Response Time (> 5 yrs)

Correction: Replace finned tube radiation terminals (per 100 LF)

Qty: 300.00

Unit of Measure: L.F.


Estimate: \$121,062.43

Assessor Name: System

Date Created: 02/23/2016

Notes: Replace finned tube convection units

System: D4010 - Sprinklers



Location: Entire building

Distress: Life Safety / NFPA / PFD

Category: 1 - Health & Safety

Priority: 5 - Response Time (> 5 yrs)

Correction: Install a fire protection sprinkler system

Qty: 97,000.00

Unit of Measure: S.F.

Estimate: \$1,387,629.73

Assessor Name: System

Date Created: 02/23/2016

Notes: Install fire protection sprinkler system

System: D4010 - Sprinklers



Location: Kitchen

Distress: Life Safety / NFPA / PFD

Category: 1 - Health & Safety

Priority: 5 - Response Time (> 5 yrs)

Correction: Provide kitchen hood fire suppression system (8 FT)

Qty: 1.00

Unit of Measure: Ea.

Estimate: \$16,739.78

Assessor Name: System

Date Created: 02/23/2016

Notes: Install fire suppression system for kitchen range fume hood

Equipment Inventory

The following table represents the inventory details of the inventory found in the building, which fall under the following subsystems:

Subsystem	Inventory	Qty	UoM	Location	Manufacturer	Model Number	Serial Number	Barcode	Life	Install Date	Next Renewal	Raw Cost	Inventory Cost
D3020 Heat Generating Systems	Boiler, oil fired, flame retention burner, cast iron, steam, gross output, 2480 MBH, includes standard controls and insulated flush jacket, packaged	3.00	Ea.	Boiler room					35	1990	2025	\$40,212.00	\$132,699.60
D5010 Electrical Service/Distribution	Panelboards, 3 pole 4 wire, main lugs, 240 V, 600 amp, no main breaker	1.00	Ea.	Basement					30	1955	2047	\$2,639.25	\$2,903.18
												Total:	\$135,602.78

Executive Summary

Building condition is evaluated based on the functional systems and elements of a building and organized according to the UNIFORMAT II Elemental Classification. The grouping of these systems and elements and applying a current replacement value to them develops a representative building cost model. Cost Models are developed for similar building types and functions. Systems and their elements are evaluated based on their current replacement values, life cycles, installation dates and next renewal dates. Systems and their elements that are within their useful lives are further evaluated to identify current deficient conditions that may have a significant impact on a system's or element's remaining service life, and to determine if they are beyond their predicted expected life. The system's or element's current replacement value is based on RS Means Commercial Cost Data.

Following are the cost model's system details for this facility. The Replacement Value is the amount needed to replace the property of the same present value. The Current Repair Amount, also known as Condition Needs, represents the budgeted contractor installed costs plus owner's soft costs for the repair, replacement or renewal for a component or system level deficiency. It excludes contributing costs for other components or systems that might also be associated with the corrective actions due to packaging the work. Facility Condition Index (FCI) FCI is an industry-standard measurement of facility condition calculated as the ratio of the costs to correct a facility's deficiencies to the facility's Current Replacement Value. It ranges from 0% (new) to 100% (very poor). Condition Index (CI) is calculated as the sum of a renewable system's Remaining Service Life (RSL) divided by the sum of a system's Replacement Value (both values exclude soft-cost to simplify calculation updates) expressed as a percentage ranging from 100% (new) to 0% (expired).

Function:

Gross Area (SF): 115,000

Year Built: 1955

Last Renovation:

Replacement Value: \$2,228,539

Repair Cost: \$468,400.65

Total FCI: 21.02 %

Total RSLI: 41.01 %



Description:

Attributes:

General Attributes:

Bldg ID:	S643001	Site ID:	S643001
----------	---------	----------	---------

Condition Summary

The Table below shows the CI and FCI for each major building system shown at the UNIFORMAT classification Level II. Note that Systems with lower FCIs require less investment than systems with higher FCIs.

UNIFORMAT Classification	RSLI %	FCI %	Current Repair Cost
G20 - Site Improvements	39.47 %	22.83 %	\$394,649.67
G40 - Site Electrical Utilities	46.31 %	14.74 %	\$73,750.98
Totals:	41.01 %	21.02 %	\$468,400.65

Condition Detail

This section of the report contains results of the Facility Condition Assessment. The building is separated into system components based on UNIFORMAT II classification. The columns in the System Listing table below represent the following:

1. System Code: A code that identifies the system.
2. System Description: A brief description of a system present in the building.
3. Unit Price \$: The unit price of the system.
4. UoM: The unit of measure for of the system.
5. Qty: The quantity for the system
6. Life: anticipated service life for thesystem based on Building Owners and Managers Association (BOMA) recommendations.
7. Year Installed: The date of system installation.
8. Calc Next Renewal Year: The date of system expiration based on the life, NR stands for non renewable.
9. Next Renewal Year: The suggested system expiration date by the assessor based on visual inspection.
10. CI: The Condition Index of the system.
11. FCI: The Facility Condition Index of the system.
12. RSL: Remaining Service Life.
13. eCR: eCOMET Condition Rating (not used).
14. Deficiency \$: The financial investment to repair/replace system.

System Listing

The System Listing table below lists each of the systems organized by their UNIFORMAT II classification. The assessment team was tasked with recording the most recent replacement year of each system, determining the remaining service life based on the theoretical life, and evaluating the condition to confirm the forecast next replacement year. The system listing is the basis for all data contained in the Building Assessment Report.

Additionally, a condition rating (eCR) based on the following guidelines is provided as observed at the time of the assessment.

- Excellent (E) - No noticeable distress or damage. The entire system is free from observable defect.
- Very Good (VG) - Overall no serviceability reduction for the entire system. No degradation of critical components and minor distress and defect noticeable for some but not non critical components within the system.
- Good (G) - Slight or no serviceability reduction for the entire system. There may be noticeable defects for some non critical components and slight noticeable degradation of the critical components.
- Fair (F) - Overall serviceability is degraded but adequate. There may be moderate deterioration for very few of the critical components and few of the non critical components may have severe degradation.
- Marginal (MA) - Overall serviceability and reliability loss. Most if not all of the non critical components suffer from severe degradation and a few of the critical component may have severe degradation.
- Moderate (MO) - Overall a significant serviceability loss. Most if not all the components have severe degradation with the reminder of the component showing visible distress.
- Very Poor (VP) - Overall the system is barely functional. All of the components are severely degraded.
- Non-Functional (NF) - Overall the system does not function with all the components having no serviceability and suffer from severe degradation.

System Code	System Description	Unit Price \$	UoM	Qty	Life	Year Installed	Calc Next Renewal Year	Next Renewal Year	RSLI%	FCI%	RSL	eCR	Deficiency \$	Replacement Value \$
G2010	Roadways	\$11.52	S.F.		30				0.00 %	0.00 %				\$0
G2020	Parking Lots	\$7.65	S.F.	16,300	30	1955	1985	2028	43.33 %	51.46 %	13		\$64,173.91	\$124,695
G2030	Pedestrian Paving	\$11.52	S.F.	94,200	40	1955	1995	2028	32.50 %	30.45 %	13		\$330,475.76	\$1,085,184
G2040	Site Development	\$4.36	S.F.	115,000	25	1955	1980	2028	52.00 %	0.00 %	13			\$501,400
G2050	Landscaping & Irrigation	\$3.78	S.F.	4,500	15	1955	1970	2028	86.67 %	0.00 %	13			\$17,010
G4020	Site Lighting	\$3.58	S.F.	115,000	30	1955	1985	2025	33.33 %	0.00 %	10			\$411,700
G4030	Site Communications & Security	\$0.77	S.F.	115,000	30	1955	1985	2047	106.67 %	83.29 %	32		\$73,750.98	\$88,550
Total									41.01 %	21.02 %			\$468,400.65	\$2,228,539

System Notes

The facility description in the site executive summary contains an overview of each system. The notes listed below provide additional information on select systems found within the facility.

No data found for this asset

Renewal Schedule

eCOMET forecasts future Capital Renewal funding needed to address expiring systems based on the Next Renewal year found in the Cost Models. A 3% annual inflation factor is applied to the costs for systems expiring in future years. The table below reflects recommended Capital Renewal funding needs over the next 10 years. Note: Cells with a zero value indicate systems for which renewal is not scheduled in that year.


Inflation Rate: 3%

System	Current Deficiencies	2016	2017	2018	2019	2020	2021	2022	2023	2024	2025	Total
Total:	\$468,401	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$608,619	\$1,077,020
G - Building Sitework	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0
G20 - Site Improvements	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0
G2010 - Roadways	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0
G2020 - Parking Lots	\$64,174	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$64,174
G2030 - Pedestrian Paving	\$330,476	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$330,476
G2040 - Site Development	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0
G2050 - Landscaping & Irrigation	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0
G40 - Site Electrical Utilities	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0
G4020 - Site Lighting	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$608,619	\$608,619
G4030 - Site Communications & Security	\$73,751	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$73,751

** Indicates non-renewable system*

Forecasted Sustainment Requirement

The following chart shows the current building deficiencies and forecasting sustainment requirements over the next ten years.




10 Year FCI Forecast by Investment Scenario

The chart below illustrates the effect of various investment levels on the building FCI for the next 10 years. The levels of investment shown below include:

- Current FCI: a variable investment amount based on renewing expired systems to maintain the current FCI for the building
- 2% Investment: an annual investment of 2% of the replacement value of the building, escalated for inflation
- 4% Investment: an annual investment of 4% of the replacement value of the building, escalated for inflation


Facility Investment vs. FCI Forecast



Year	Investment Amount Current FCI - 21.02%	2% Investment		4% Investment	
		Amount	FCI	Amount	FCI
2016	\$0	\$45,908.00	19.02 %	\$91,816.00	17.02 %
2017	\$103,337	\$47,285.00	21.39 %	\$94,570.00	17.39 %
2018	\$0	\$48,704.00	19.39 %	\$97,407.00	13.39 %
2019	\$0	\$50,165.00	17.39 %	\$100,330.00	9.39 %
2020	\$0	\$51,670.00	15.39 %	\$103,339.00	5.39 %
2021	\$0	\$53,220.00	13.39 %	\$106,440.00	1.39 %
2022	\$0	\$54,816.00	11.39 %	\$109,633.00	-2.61 %
2023	\$0	\$56,461.00	9.39 %	\$112,922.00	-6.61 %
2024	\$0	\$58,155.00	7.39 %	\$116,310.00	-10.61 %
2025	\$608,619	\$59,899.00	25.71 %	\$119,799.00	5.71 %
Total:	\$711,956	\$526,283.00		\$1,052,566.00	

Deficiency Summary by System


Current deficiencies included assemblies that have reached or exceeded their design life or components of the assemblies that are in need of repair. Assemblies that have reached their design life are identified as current deficiencies and assigned the distress 'Beyond Useful Life'. The following chart lists all current deficiencies associated with this facility.



Budget Estimate Total: \$468,400.65

Deficiency Summary by Priority

The following chart shows the total repair costs broken down by priority. Assessors assigned deficiencies within eCOMET to one of the following priority categories:



Budget Estimate Total: \$468,400.65


Deficiency By Priority Investment Table

The table below shows the current investment cost grouped by deficiency priority and building system.

System Code	System Description	1 - Response Time (< 2 yr)	2 - Response Time (2-3 yrs)	3 - Response Time (3-4 yrs)	4 - Response Time (4-5 yrs)	5 - Response Time (> 5 yrs)	Total
G2020	Parking Lots	\$0.00	\$0.00	\$64,173.91	\$0.00	\$0.00	\$64,173.91
G2030	Pedestrian Paving	\$9,093.63	\$29,005.10	\$292,377.03	\$0.00	\$0.00	\$330,475.76
G4030	Site Communications & Security	\$0.00	\$0.00	\$73,750.98	\$0.00	\$0.00	\$73,750.98
	Total:	\$9,093.63	\$29,005.10	\$430,301.92	\$0.00	\$0.00	\$468,400.65

Deficiency Summary by Category

The following chart shows the total repair costs broken down by deficiency categories. Assessors assigned deficiencies to one of the following categories:



Deficiency Details by Priority

The deficiency detail notes listed below provide additional information on identified deficiencies found within the facility.

Priority 1 - Response Time (< 2 yr):

System: G2030 - Pedestrian Paving



Location: Front entry

Distress: Accessibility

Category: 2 - Code Compliance

Priority: 1 - Response Time (< 2 yr)

Correction: Install an exterior ADA ramp - based on 5' wide by the linear foot - up to a 48" rise - per LF of ramp - figure 1 LF per inch of rise

Qty: 7.00

Unit of Measure: L.F.

Estimate: \$9,093.63

Assessor Name: Craig Anding

Date Created: 02/18/2016

Notes: Provide exterior ramp to front entry.

Priority 2 - Response Time (2-3 yrs):

System: G2030 - Pedestrian Paving



Location: Entry area to Wakefield St. and city sidewalks

Distress: Health Hazard / Risk

Category: 1 - Health & Safety

Priority: 2 - Response Time (2-3 yrs)

Correction: Remove and replace concrete sidewalk or concrete paving - 4" concrete thickness

Qty: 1,500.00

Unit of Measure: S.F.

Estimate: \$21,574.28

Assessor Name: Craig Anding

Date Created: 02/18/2016

Notes: Repair damaged concrete pavement that creates tripping hazards and impedes access.

System: G2030 - Pedestrian Paving



Location: Gym exit and steps near main entrance

Distress: Health Hazard / Risk

Category: 1 - Health & Safety

Priority: 2 - Response Time (2-3 yrs)

Correction: Repair on grade concrete stairs - nosings and exposed rebar

Qty: 3.00

Unit of Measure: Riser

Estimate: \$7,430.82

Assessor Name: Craig Anding

Date Created: 02/18/2016

Notes: Steps are deteriorating at gym exit. Repair and add handrail. Replace handrail at steps near main entry.

Priority 3 - Response Time (3-4 yrs):

System: G2020 - Parking Lots



Location: Site

Distress: Damaged

Category: 3 - Operations / Maint.

Priority: 3 - Response Time (3-4 yrs)

Correction: Resurface parking lot - grind and resurface including striping

Qty: 16,300.00

Unit of Measure: S.F.

Estimate: \$64,173.91

Assessor Name: Craig Anding

Date Created: 02/18/2016

Notes: Asphalt is in fair to poor condition with some settled areas, ponding, alligatoring, deeper cracking and vegetation in the asphalt. Resurface the parking lot, restripe, and provide signage for designated accessible spaces.

System: G2030 - Pedestrian Paving



Location: Site

Distress: Health Hazard / Risk

Category: 1 - Health & Safety

Priority: 3 - Response Time (3-4 yrs)

Correction: Resurface AC pedestrian paving - grind and resurface

Qty: 80,000.00

Unit of Measure: S.F.


Estimate: \$285,564.35

Assessor Name: Craig Anding

Date Created: 02/18/2016

Notes: Asphalt playgrounds are in deteriorating condition, creating trip hazards for children. Resurfacing is recommended.

System: G2030 - Pedestrian Paving



Location: At exterior doors

Distress: Health Hazard / Risk

Category: 1 - Health & Safety

Priority: 3 - Response Time (3-4 yrs)

Correction: Install missing concrete landings at exterior doors reducing the step down from the door

Qty: 4.00

Unit of Measure: Ea.

Estimate: \$6,812.68

Assessor Name: Craig Anding

Date Created: 02/18/2016

Notes: Landings at exterior doors are missing in some cases. In others, the step to adjacent grade exceeds 8" and is unacceptable.

System: G4030 - Site Communications & Security



Location: Building Perimeter

Distress: Security Issue

Category: 1 - Health & Safety

Priority: 3 - Response Time (3-4 yrs)

Correction: Add Video Surveillance System

Qty: 4.00

Unit of Measure: Ea.

Estimate: \$73,750.98

Assessor Name: Craig Anding

Date Created: 02/08/2016

Notes: Provide outdoor surveillance CCTV cameras to the building exterior for full coverage of the perimeter. Approximate 4 CCTV cameras.

Equipment Inventory

The following table represents the inventory details of the inventory found in the building, which fall under the following subsystems:

No data found for this asset

Glossary

ABMA	American Boiler Manufacturers Association http://www.abma.com/
ACEEE	American Council for an Energy-Efficient Economy
ACGIH	American Council of Governmental and Industrial Hygienists
AEE	Association of Energy Engineers
AFD	Adjustable Frequency Drive
AFTC	After Tax Cash Flow
AGA	American Gas Association
AHU	Air Handling Unit
Amp	Ampere
ANSI	American National Standards Institute
ARI	Air Conditioning and Refrigeration Institute
ASD	Adjustable Speed Drive
ASHRAE	American Society of Heating Refrigerating and Air-Conditioning Engineers Inc.
ASME	American Society of Mechanical Engineers
Assessment	Visual survey of a facility to determine its condition. It involves looking at the age of systems reviewing information from local sources and visual evidence of potential problems to assign a condition rating. It does not include destructive testing of materials or testing of systems or equipment for functionality.
ATS	After Tax Savings
AW	Annual worth
BACNET	Building Automation Control Network
BAS	Building Automation System
BCR	Benefit Cost Ratio
BEP	Business Energy Professional (AEE)
BF	Ballast Factor
BHP	Boiler Horsepower (boilers)
BHP	Brake Horsepower (motors)
BLCC	Building Life Cycle Cost analysis program (FEMP)
BOCA	Building Officials and Code Administrators
BTCF	Before Tax Cash Flow

Site Assessment Report - S643001;Wister

BTS	Before Tax Savings
Btu	British thermal unit
Building Addition	An area space or component of a building added to a building after the original building's year built date.
CAA	Clean Air Act
CAAA-90	Clean Air Act Amendments of 1990
CABO	Council of American Building Officials
CAC	Conventional Air Conditioning
CADDET	Center for the Analysis and Dissemination of Demonstrated Energy Technologies
Calculated Next Renewal	The year a system or element would be expected to expire based solely on the date it was installed and the expected useful lifetime for that kind of system.
Capital Renewal	Capital renewal is condition work (excluding suitability and energy audit work) that includes the replacement of building systems or elements (as they become obsolete or beyond their useful life) not normally included in an annual operating budget. Calculated next renewal The year a system or element would be expected to expire based solely on the date it was installed and the expected useful lifetime for that kind of system. Next renewal The assessor adjusted expected useful life of a system or element based on on-site inspection.
CDD	Cooling Degree Days
CDGP	Certified Distributed Generation Professional
CEC	California Energy Commission
CEM	Certified Energy Manager
CEP	Certified Energy Procurement Professional
CFC	Chlorofluorocarbon
CFD	Cash Flow Diagram
CFL	Compact Fluorescent Light
CFM cfm	Cubic Feet per Minute
CHP	Combined Heat and Power (a.k.a. cogeneration)
CHW	Chilled Water
Condition	Condition refers to the state of physical fitness or readiness of a facility system or system element for its intended use.
COP	Coefficient of Performance
Cp	Heat Capacity of Material
CPUC	California Public Utility Commission
CRI	Color Rendering Index
CRT	Cathode Ray Tube VDT HMI

Site Assessment Report - S643001;Wister

CTC	Competitive Transition Charge
Cu	Coefficient of Utilization
Current Replacement Value (CRV)	CRV represents the hypothetical total cost of rebuilding or replacing an existing facility in current dollars to its optimal condition (excluding auxiliary facilities) under current codes and construction standards.
Cv	Value Coefficient
CWS	Chilled Water System
D d	Distance (usually feet)
DB	Dry Bulb
DCV	Demand Control Ventilation
DD	Degree Day
DDB	Double Declining Balance
DDC	Direct Digital Controls
Deferred maintenance	Deferred maintenance is condition work (excluding suitability and energy audit needs) deferred on a planned or unplanned basis to a future budget cycle or postponed until funds are available.
Deficiency	A deficiency is a repair item that is damaged missing inadequate or insufficient for an intended purpose.
Delta	Difference
Delta P	Pressure Difference
Delta T	Temperature Difference
DG	Distributed Generation
DOE	Department of Energy
DP	Dew Point
DR	Demand Response
DX	Direct Expansion Air Conditioner
EA	Energy Audit
EBITDA	Earnings before Interest Taxes Depreciation and Amortization
ECI	Energy Cost Index
ECM	Energy Conservation Measure
ECO	Energy Conservation Opportunity
ECPA	Energy Conservation and Production Act
ECR	Energy Conservation Recommendation
ECS	Energy Control System

Site Assessment Report - S643001;Wister

EER	Energy Efficiency Ratio
EERE	Energy Efficiency and Renewable Energy division of US DOE
EIA	Energy Information Agency
EIS	Energy Information System
EMCS	Energy Management Computer System
EMO	Energy Management Opportunity
EMP	Energy Management Project
EMR	Energy Management Recommendation
EMS	Energy Management System
Energy Utilization Index (EUI)	EUI is the measure of total energy consumed in the cooling or heating of a building in a period expressed as British thermal unit (BTU) per (cooled or heated) gross square foot.
EO	Executive Order
EPA	Environmental Protection Agency
EPACT	Energy Policy Act of 1992
EPCA	Energy Production and Conservation Act of 1975
EPRI	Electric Power Research Institute
EREN	Efficiency and Renewable Energy (Division of USDOE)
ERV	Energy Recovery Ventilator
ESCO	Energy Service Company
ESPC	Energy Savings Performance Contract
EUI	Energy Use Index
EWG	Exempt Wholesale Generators
Extended Facility Condition Index (EFCI)	EFCI is calculated as the condition needs for the current year plus facility system renewal needs going out to a set time in the future divided by Current Replacement Value.
f	Frequency
F	Fahrenheit
Facility	A facility refers to site(s) building(s) or building addition(s) or combinations thereof that provide a particular service.
Facility Condition Assessment (FCA)	FCA is a process for evaluating the condition of buildings and facilities for programming and budgetary purposes through an on site inspection and evaluation process.
Facility Condition Index (FCI)	FCI is an industry-standard measurement of a facility's condition that is the ratio of the cost to correct a facility's deficiencies to the Current Replacement Value of the facilities. The higher the FCI the poorer the condition of a facility. After an FCI is established for all buildings within a portfolio a building's condition can be ranked relative to other buildings. The FCI may also represent the condition of a portfolio based on the cumulative FCIs of the portfolio's facilities.

Site Assessment Report - S643001;Wister

FC	Footcandle
FCA	Fuel Cost Adjustment
FEMIA	Federal Energy Management Improvement Act of 1988
FEMP	Federal Energy Management Program
FERC	Federal Energy Regulatory Commission
FESR	Fuel Energy Savings Ratio
FLA	Full Load Amps
FLF	Facility Load Factor (usually monthly)
FLRPM	Full Load Revolutions per Minute
FMS	Facility Management System
FPM fpm	Feet per Minute (velocity)
FSEC	Florida Solar Energy Center
Ft	Foot
GPM gpm	Gallons per Minute
GRI	Gas Research Institute
Gross Square Feet (GSF)	The size of the enclosed floor space of a building in square feet measured to the outside face of the enclosing wall.
GUI	Graphical User Interface
H h	Enthalpy Btu/lb
HCFC	Hydrochlorofluorocarbons
HDD	Heating Degree days
HFC	Hydrofluorocarbons
HHV	Higher Heating Value
HID	High Intensity Discharge (lamp)
HMI	Human Machine Interface
HMMI	Human Man Machine Interface
HO	High Output (lamp)
HP Hp hp	Horsepower
HPS	High Pressure Sodium (lamp)
HR	Humidity Ratio
Hr hr	Hour

Site Assessment Report - S643001;Wister

HRU	Heat Recovery Unit
HVAC	Heating Ventilation and Air-Conditioning
Hz	Hertz
I	Intensity (lumen output of lamp)
I i	Interest rate or Discount rate
IAQ	Indoor Air Quality
ICA	International Cogeneration Alliance
ICBO	International Conference of Buildings Officials
ICC	International Code Council
ICP	Institutional Conservation Program
IECC	International Energy Conservation Code
IEEE	Institute of Electrical and Electronic Engineers
IESNA	Illuminating Engineering Society of North America
Install year	The year a building or system was built or the most recent major renovation date (where a minimum of 70 of the system's Current Replacement Value (CRV) was replaced).
IRP	Integrated Resource Planning
IRR	Internal Rate of Return
ISO	Independent System Operator
ITA	Independent Tariff Administrator
k	Kilo multiple of thousands in SI system
K	Kelvins (color temperature of lamp)
K k	Thermal Conductivity of Material
KVA	Kilovolt Ampere
KVAR	Kilovolt Ampere Reactive
kW	kiloWatt
kWh	kiloWatt hour
L	Length (usually feet)
LCC	Life Cycle Costing
LDC	Local Distribution Company
LEED	Leadership in Energy and Environmental Design
LEED EB	LEED for Existing Buildings

Site Assessment Report - S643001;Wister

LEED NC	LEED for new construction
LF	Load Factor
LHV	Lower Heating Value
Life cycle	The period of time that a building or site system or element can be expected to adequately serve its intended function.
LPS	Low Pressure Sodium (lamp)
Lu	Lumen Output of a Lamp or Fixture
M	Mega multiple of millions in SI system
M&V	Measurement and Verification
MACRS	Modified Accelerated Cost Recovery System
MARR	Minimum Attractive Rate of Return
Mbtu	Thousand Btu
MCF	Thousand Cubic Feet (usually of gas)
MEC	Model Energy Code
Mm	Multiple of Thousands in I/P System
MMBtu	Million Btu
MMCS	Maintenance Management Computer System
MMI	Man Machine Interface
MMS	Maintenance Management System
MSE 2000	Management System for Energy 2000 (ANSI Georgia Tech Univ)
MW	MegaWatt
MWH MWh	MegaWatt hour
NAAQS	National Ambient Air Quality Standards
NAESCO	National Association of Energy Service Companies
NAIMA	North American Insulation Manufacturers Association
NEA	National Energy Act of 1978
NECPA	National Energy Conservation Policy Act
NEMA	National Electrical Manufacturer's Association
NERC	North American Electric Reliability Council
Next Renewal	The Next Renewal date is an override of the 'Calculated Next Renewal' date and is based upon the assessor's visual inspection.

Site Assessment Report - S643001;Wister

NFPA	National Fire Protection Association
NGPA	National Gas Policy Act of 1978
NLRPM	No Load Revolutions per Minute (speed)
Nn	Equipment or Project lifetime in economic analysis
NOPR	Notice of Proposed Rule Making from FERC
NOx	Nitrogen Oxide Compounds
NPV	Net present value in economic analysis
NREL	National Renewable Energy Laboratory
NUG	Non-Utility Generator
O&M	Operation and Maintenance
OA	Outside Air
ODP	Ozone Depletion Potential
OPAC	Off-Peak Air Conditioning
P	Present value in economic analysis
PBR	Performance Based Rates
PEA	Preliminary Energy Audit
PF	Power Factor
PID	Proportional plus integral plus derivative (control system)
PM	Portfolio Manager in Energy Star rating system
PM	Preventive Maintenance
PoolCo	Power Pool Company or Organization
POU	Point of Use
PQ	Power Quality
PSC	Public Service Commission
PSIA psia	Pounds per square inch absolute (pressure)
PSIG psig	Pounds per square inch gauge (pressure)
PUC	Public Utility Commission
PUHCA	Public Utilities Holding Company Act of 1935
PURPA	Public Utilities Regulatory Policies of 1978
PV	Photovoltaic system

Site Assessment Report - S643001;Wister

PV	Present Value
PW	Present Worth
PX	Power Exchange
q	Rate of heat flow in Btu per hour
Q	Heat load due to conduction using degree days
QF	Qualifying Facility
R	Electrical resistance
R	Thermal Resistance
RC	Remote controller
RCR	Room Cavity Ratio
RCRA	Resource Conservation and Recovery Act
Remaining Service Life (RSL)	RSL is the number of years service remaining for a system or equipment item. It is automatically calculated based on the difference between the current year and the 'Calculated Next Renewal' date or the 'Next Renewal' date whichever one is the later date.
Remaining Service Life Index (RSLI)	RSLI is defined as a percentage ratio of the remaining service life of a system. It usually ranges from 0 to 100
REMR	Repair Evaluation Maintenance Rehabilitation (REMR) is a scale used to objectively rank systems based on their condition
Renewal Schedule	A timeline that provides the items that need repair the year in which the repair is needed and the estimated price of the renewal.
RH	Relative Humidity
RLA	Running Load Amps
RMS	Root Mean Square
RO	Reverse Osmosis
ROI	Return on Investment
RPM	Revolutions Per Minute
RTG	Regional Transmission Group
RTO	Regional Transmission Organization
RTP	Real Time Pricing
SBCCI	Southern Building Code Congress International
SC	Scheduling Coordinator
SC	Shading Coefficient
SCADA	Supervisory Control and Data Acquisition Systems

Site Assessment Report - S643001;Wister

SEER	Seasonal Energy Efficiency Ratio
SHR	Sensible Heat Ratio
Site	The grounds and utilities roadways landscaping fencing and other typical land improvements needed to support the facility.
Soft Cost	An expense item that is not considered direct construction cost. Soft cost includes architectural engineering financing legal fees and other pre-and-post construction expenses.
SOx	Sulfur Oxide Compounds
SP	Static Pressure
SP SPB	Simple Payback
SPP	Simple Payback Period
SPP	Small Power Producers
STR	Stack Temperature Rise
SV	Specific Volume
System	System refers to building and related site work elements as described by ASTM Uniformat II Classification for Building Elements (E1557-97) a format for classifying major facility elements common to most buildings. Elements usually perform a given function regardless of the design specification construction method or materials used. See also Uniformat II.
T	Temperature
T	Tubular (lamps)
TAA	Technical Assistance Audit
TCP/IP	Transmission Control Protocol/Internet Protocol
TES	Thermal Energy Storage
THD	Total Harmonic Distortion
TOD	Time of Day
TOU	Time of Use
TQM	Total Quality Management
TransCo	Transmission Company
U	Thermal Conductance
UDC	Utility Distribution Company
UL	Underwriters Laboratories
UNIFORMAT II	The ASTM UNIFORMAT II Classification for Building Elements (E1557-97) a format for classifying major facility components common to most buildings.
USGBC	US Green Building Council
v	Specific Volume

Site Assessment Report - S643001;Wister

V	Volts Voltage
V	Volume
VAV	Variable Air Volume
VDT	Video Display Terminal
VFD	Variable Frequency Drive
VHO	Very High Output
VSD	Variable Speed Drive
W	Watts
W	Width
WB	Wet bulb
WH Wh	Watt Hours
Year built	The year that a building or addition was originally built based on substantial completion or occupancy.
Z	Electrical Impedance