

SCHOOL DISTRICT OF PHILADELPHIA



Asbestos Hazard Emergency Response Act “AHERA”

THREE-YEAR RE-INSPECTION 2015-2016 and ASBESTOS MANAGEMENT PLAN for the

Central High School

**ULCS# 6010
Building # B601001-1
1700 West Olney Avenue
Philadelphia, Pennsylvania
19141**

Year Built: 1939

January 2016

Conducted by:

Accredited Environmental Technologies, Incorporated
Batta Environmental Associates, Incorporated
Criterion Laboratories, Incorporated
Environmental Testing Consultants, LLC
G & C Environmental Services, Incorporated
KEM Partners, Incorporated
Synertech, Inc.
TTI Environmental, Inc.
USA Environmental Management, Inc.
The Vertex Companies, Inc.

Management Plan Prepared by:
Criterion Labs, Inc and Synertech Inc.

This report must remain in the Main Office as mandated by the US EPA AHERA Regulations.

AHERA THREE-YEAR REINSPECTION VOLUME IX

Table of Contents

Transmittal Letter

Executive Summary

- I. Summary list of Confirmed Asbestos Containing Building Materials
- II. Summary list of Assumed Asbestos Contain Building Materials
- III. Summary list of Non-Asbestos Containing Building Materials
- IV. Summary list of Non Suspect Asbestos Containing Building Materials
- V. Summary List of Auditorium DATA for this location
- VI. Summary list of Attic and/or Crawlspace DATA for this location
- VII. Summary list of Pipe Chase/Pipe Shaft DATA for this location

Section I Report of Re-Inspection

- A. Introduction
- B. Three-Year Re-inspection IX Overview
- C. Post- Management Plan Activities and Changes
 - C.1 - Sampling and Analysis
 - C.2 - New Floor Tile Sampling
 - C.3 - Abatement Activity
 - C.4 - Periodic (Six-Month) Surveillance (Damaged Materials)

Section II Re-Inspection Data

- A. Introduction
- B. Re-Inspection Key Definitions
- C. Room by Room Location Log Report

Section III Certificates

- A. Management Planner/Building Inspector Certificates

| | | |
|-------------------|------------------------------|-----------|
| Section IV | Cross Reference Table | Page 1-8 |
| | Asbestos Management Program | Page 9-19 |

SCHOOL DISTRICT OF PHILADELPHIA
EDUCATIONAL CENTER
440 NORTH BROAD STREET
PHILADELPHIA, PENNSYLVANIA 19130

OFFICE OF ENVIRONMENTAL MANAGEMENT AND SERVICES

PHONE (215)-400-4750

January 2016


TO: All Principals
All Building Administrators


FROM: Fran Burns
Chief Operating Officer

Francine Locke, M.S., Director
Office of Environmental Management and Services

SUBJECT: AHERA Three (3) Year Re-inspection IX report

In order to comply with the provisions of the Asbestos Hazard Emergency Response Act (AHERA) the attached report is submitted to you. The law requires that this report be kept in the Main/Principal's office. It cannot be removed from these locations. *If the school (program) is relocated to a different building, these environmental documents are to be safely retained for the next school/building occupants.* All asbestos reports must be available to the public and Federal EPA upon request.



Fran Burns
Chief Operation Officer

Francine Locke, M.S., Director
Office of Environmental Management
and Services

Executive Summary

This Asbestos Hazard Emergency Response Act (AHERA) Three-Year Re-inspection “Volume # IX” Management Plan at this location, has been completed and the report of re-inspection submitted to the School District of Philadelphia. The re-inspections in all School District of Philadelphia buildings of 2015-2016 were conducted and completed between October 5th, 2015 through March 30th, 2016 as a joint project by Accredited Environmental Technologies, Inc., Batta Environmental Associates, Inc., Criterion Laboratories, Inc., Environmental Testing Consultants, LLC, G & C Environmental Services, Inc., KEM Partners, Inc., Synertech, Inc., TTI Environmental, Inc., USA Environmental Management, Inc. and The Vertex Companies, Inc.

In general, the School District of Philadelphia Office of Environmental Management and Services conducts Environmental Impact Evaluations and provides Asbestos Inspection Reports prior to any renovation, demolition and/or maintenance activities. The AHERA report must be reviewed prior to any renovation, demolition and/or maintenance activities in order to avoid the unknowing disturbance to Asbestos Containing Building Materials identified within this location. In addition, prior to work activities above all drop ceilings this report should be reviewed to avoid potential disturbances to Asbestos Containing Materials. Refer to Section IV of the Cross Reference Table, for additional Asbestos Management Program information. Contact the Office of Environmental Management and Services to have an Environmental Impact Evaluation conducted prior to any renovation, demolition and/or maintenance activities within this facility.

The information contained in this report was obtained from the original Asbestos Management Plan for the school, from update reports on changes and activities since the completion of the 1st Management Plan for each location and from all prior inspections performed and documented in Volume # I through Volume VIII (dated respectively 1992, 1995, 1998, 2001, 2004, 2007, 2010 or 2013) (if applicable) - and by this Three-Year Re-inspection of this school. The re-inspection report/Management Plan of 2015-2016 were reviewed and prepared collectively by Management Planner Megan Vala, Mary Anne Lerro of Criterion Laboratories, Inc. and/or Monique Causley, of Synertech Inc.

The 2015-2016 inspection process included the addition of a comprehensive Room by Room Inventory of all Thermal (T), Surfacing (S) and Miscellaneous (M) Materials specific to each room of this facility. Inspections of each room's thermal, ceilings, walls, floors and miscellaneous items regardless of Asbestos Content are categorized on the Room by Room Location Log Report for this location. Rooms or areas of the facility that were not accessible at the time of the inspection are marked with an "X". The Room by Room Location Log Report is found in Section II C of this Management Plan.

All Presumed or Suspect Asbestos Containing Building Materials (ACBMs), listed in the following summary charts are categorized as Confirmed, Assumed, Non-Asbestos, and/or Non-Suspect (ACBMs) were identified in the original Management Plan, or in the Volume I through Volume VIII AHERA Three-Year Re-inspection reports, and were re-inspected as part of this project.

As mandated by the U S EPA AHERA regulations, periodic Six-Month inspections and Three-Year Re-inspections of this location will be performed and the Inspection Data in this report will be updated accordingly.

Please feel free to contact the School District of Philadelphia's Office of Environmental Management and Services (OEMS) regarding any comments, questions, or concerns regarding this report or any Environmental related topic. OEMS staff can be reached at (215) 400 4750, via fax at (215) 400 4751 or via e-mail at flocke@philasd.org and/or gfunod@philasd.org.

Additional information can be found on our website. Here is the link to the OEMS website.
<http://webgui.phila.k12.pa.us/offices/e/environmental>

I. Summary list of Confirmed Asbestos Containing Building Materials within this facility

These charts are to be used for a quick reference* in order to avoid the unknowing disturbance of Asbestos Containing Materials during any and all Operations, Maintenance, Renovation, and/or Demolition activities at this location. *These materials have been sampled and Laboratory Analysis has CONFIRMED the presence of Asbestos. Contact OEMS prior to the disturbance of any of the following materials.*

Confirmed Asbestos Containing Building Materials for this location

| |
|------------------------|
| Floor Tile VAT 9" x 9" |
|------------------------|

* *Always refer to the Room by Room Logs for each specific material classification as the material classification findings may be different in various rooms throughout this facility.*

** *Some Materials may have multiple classifications (Confirmed, Assumed, NAD and Non Suspect) within this facility.*

II. Summary list of Assumed Asbestos Containing Building Materials within this facility

These charts are to be used for a quick reference* in order to avoid the unknowing disturbance of Asbestos Containing Materials during any and all Operations, Maintenance, Renovation, and/or Demolition activities at this location. These materials have not been sampled and should not be disturbed until verification of Asbestos Content. Contact OEMS for assessment and sampling prior to the disturbance of these materials.

Assumed Asbestos Containing Building Materials for this location

| | | |
|----------------------------|--------------------------|------------------------|
| Acoustical Plaster Ceiling | Floor Tile VAT 12" x 12" | Sheetrock Wall |
| Acoustical Plaster Walls | Kiln Bricks | Sink Undercoat Mastic |
| Blackboard Glue Dots | Linoleum | Transite |
| Ceiling Tile 2' x 2' | Radiator Insulation | Transite Stalls |
| Fireproofing | Sheetrock Ceiling | Vibration Damper Cloth |

** Always refer to the Room by Room Logs for each specific material classification as the material classification findings may be different in various rooms throughout this facility.*

*** Some Materials may have multiple classifications (Confirmed, Assumed, NAD and Non Suspect) within this facility.*

III. Summary list of Non-Asbestos Containing Building Materials within this facility

These charts are to be used for a quick reference* in order to avoid the unknowing disturbance of Asbestos Containing Materials during any and all Operations, Maintenance, Renovation, and/or Demolition activities at this location. *These materials have been sampled and Laboratory Analysis has indicated NO Asbestos present or NO ASBESTOS DETECTED (NAD).*

Non-Asbestos Containing Building Materials for this location

| | | |
|---|--------------------------|-----------------|
| Acoustical Plaster Ceiling | Ceiling Tile 1' x 1' | Plaster Ceiling |
| Acoustical Plaster Walls | Ceiling Tile 2' x 4' | Plaster Walls |
| Black/Yellow Mastic a/w Floor Tile VAT 12" x 12" | Floor Tile VAT 12" x 12" | |

* *Always refer to the Room by Room Logs for each specific material classification as the material classification findings may be different in various rooms throughout this facility.*

** *Some Materials may have multiple classifications (Confirmed, Assumed, NAD and Non Suspect) within this facility.*

IV. Summary list of Non-Suspect Asbestos Containing Building Materials within this facility

These charts are to be used for a quick reference* in order to avoid the unknowing disturbance of Asbestos Containing Materials during any and all Operations, Maintenance, Renovation, and/or Demolition activities at this location. These materials are not typically known to contain Asbestos.

Non-Suspect Asbestos Containing Building Materials for this location

| | | |
|---------------------|---------------------------------|--------------------|
| Brick Wall | Concrete Ceiling | Metal Deck Ceiling |
| Carpet | Fiberglass Ceiling Tile 2' x 4' | Terrazzo Floor |
| Cement Floor | Fiberglass Duct Insulation | Wood Floor |
| Ceramic Tile Floors | Fiberglass Pipe Insulation | Wood Panel Wall |
| Ceramic Tile Walls | Fiberglass Tank Insulation | |
| Concrete Block Wall | Marble Wall | |

* *Always refer to the Room by Room Logs for each specific material classification as the material classification findings may be different in various rooms throughout this facility.*

** *Some Materials may have multiple classifications (Confirmed, Assumed, NAD and Non Suspect) within this facility.*

V. Summary list of Auditorium DATA for this location

These charts are to be used for a quick reference of the Auditorium DATA within this facility. Sampling of the Auditorium Ceilings throughout the District is more difficult because of the various ceiling heights. As sampling occurs this information is updated on a case by case basis for each specific location and facility.

This is a list of known materials for this location's Auditorium

| | | |
|--------------------|----------------------------|-----------------|
| Auditorium | Radiator Insulation | Assumed |
| Auditorium | Acoustical Plaster Ceiling | NAD |
| Auditorium | Acoustical Plaster Walls | NAD |
| Auditorium | Wood Floor | Non Suspect ACM |
| Stage | Concrete Ceiling | Non Suspect ACM |
| Stage | Plaster Walls | NAD |
| Stage | Wood Floor | Non Suspect ACM |
| Auditorium Balcony | Acoustical Plaster Ceiling | NAD |
| Auditorium Balcony | Acoustical Plaster Walls | NAD |
| Auditorium Balcony | Wood Floor | Non Suspect ACM |

** Always refer to the Room by Room Logs for each specific material classification as the material classification findings may be different in various rooms throughout this facility.*

*** Some Materials may have multiple classifications (Confirmed, Assumed, NAD and Non Suspect) within this facility.*

VI. Summary list of Attic and/or Crawlspace DATA for this location

These charts are to be used for a quick reference regarding the Attics and/or Crawlspaces inspection DATA within this facility. Contact OEMS prior to entering any attic or crawlspace within this facility and refer to the below chart and legend for Category Rank determination. The Data relative to these spaces is updated as conditions change regarding Abatement or Renovation activity on a case by case basis for each specific location and facility. In general, Crawlspaces are below the basement or 1st floor and Attics are above the floor space.

Category Rank Legend

| |
|---|
| "A" - No Asbestos Containing Materials - Sample Results indicate NO ACM on pipes, fittings, elbows, or equipment located within this functional space, and NO VISIBLE DEBRIS or DAMAGE observed at time of this inspection. |
| "B" - Asbestos Containing Materials Exist - Sample Results indicate ACM on pipes, fittings, elbows, or equipment located within this functional space, HOWEVER, NO VISIBLE DEBRIS or DAMAGE observed at time of this inspection. |
| "C" - Asbestos Containing Materials Exist - Sample Results indicate ACM on pipes, fittings, elbows, or equipment located within this functional space, and LOCALIZED VISIBLE DEBRIS or DAMAGE observed at time of this inspection. |
| "D" - Asbestos Containing Materials Exist - Sample Results indicate ACM on pipes, fittings, elbows, or equipment located within this functional space and DISTRIBUTED VISIBLE DEBRIS or SIGNIFICANT DAMAGE observed at time of this inspection. |
| "E" - No Bulk Sample Results Available SUSPECT ACM OBSERVED. Contact OEMS immediately for additional instructions. |

| Attic/ Crawl Space | Access Area | Floor Surface | Category Rank | Comments |
|-----------------------|---|------------------|---------------|--|
| Attic | Attic above 3rd Floor accessible by Penthouse Central Stair | | "A" | 500 LF Fiberglass |
| Attic | Attic above Auditorium accessible by 3rd Floor Corridor | | "A" | Fiberglass Duct Insulation |
| Crawl Space | Crawl Space in Boiler Room/Pump Room | | "A" | |
| Crawl Space | Crawl Space/Basement | | | Access Ladder 20ft from Ground/Door Rusted/Could not inspect |

VII. Summary list of Pipe Chase/Pipe Shaft DATA for this location

These charts are to be used for a quick reference regarding the information known about the Pipe Chases and/or Pipe Shafts inspection DATA within this facility. Contact OEMS prior to performing renovation activities any Pipe Chase and/or Pipe Shaft within this facility and refer to the below chart and legend for Asbestos Content of various materials identified within each space. The Data relative to these spaces is updated as conditions change regarding Inspection, Abatement and/or Renovation activity on a case by case basis for each specific location and facility. In general, Pipe Chases are horizontal spaces and Pipe Shafts are vertical spaces.

| <i>Element</i> | <i>Floor</i> | <i>On Site Room Name</i> | <i>Material</i> | <i>Confirmed /Assumed NAD/Non Suspect</i> | <i>Amount of Material</i> | <i>Amount of Damage</i> |
|----------------|--------------|------------------------------|----------------------------|---|-----------------------------------|---------------------------------|
| 1 | SB | Pipe Chase at Men's Restroom | Fiberglass Pipe Insulation | Non Suspect ACM | 50 LF | 0 LF |
| 1 | SB | Pipe Chase at Men's Restroom | Concrete Ceiling | Non Suspect ACM | 90 SF | 0 SF |
| 1 | SB | Pipe Chase at Men's Restroom | Concrete Block Wall | Non Suspect ACM | 400 SF | 0 SF |
| 1 | SB | Pipe Chase at Men's Restroom | Cement Floor | Non Suspect ACM | 90 SF | 0 SF |

Section I

Report of Re-Inspection

A. Introduction

B. Three-Year Re-Inspection IX Overview

C. Post-Management Plan Activities and Changes

C.1 Sampling and Analysis

C.2 New Floor Tile Sampling

C.3 Abatement Activity

C.4 Periodic Six-Month Surveillance (Damaged Materials)

Section I - A

Report of Re-inspection

Introduction

The Three-Year Re-inspection IX was performed to fulfill the requirements of 40 CFR Part 763 - the Asbestos Hazard Emergency Response Act (AHERA). As required by AHERA, each Local Education Agency (LEA) must re-inspect all known confirmed or assumed Asbestos Containing Building Material (ACBM) located in the LEA's facilities. This re-inspection is intended to update the original Asbestos Management Plan for the LEA's facilities.

Multiple Building Inspectors of several firms performed the 2015/2016 re-inspection. The re-inspection report/Management Plan of 2015-2016 were reviewed and prepared collectively by Management Planner Megan Vala, Mary Anne Lerro of Criterion Laboratories, Inc. and Monique Causley, of Synertech Inc.

All of the certificates can be found in Section III.

During the re-inspection of each School District of Philadelphia facility, all of the Management Plans for that facility were reviewed. Information from the conclusions section of that report is included in this report. Additionally, information on activities such as abatements, cleanings, sampling and inspections, which have taken place since the completion of the original Management Plan, were reviewed during the re-inspection. Information on those activities is included in this report.

As mandated by the U S EPA AHERA regulations, all future periodic Six-Month inspections and Three-Year Re-inspections of this location will be performed and the Inspection Data in this report will be updated accordingly.

Section I - B

Three-Year Re-inspection IX Overview

Each homogeneous area of Asbestos Containing Building Material (ACBM) listed in the original Management Plan or in the 1992, 1995, 1998, 2001, etc., Three-Year Re-inspection reports were inspected for the AHERA Three-Year Re-inspection Volume IX, and the information for that material verified. Any changes to a homogeneous area listed in the updates to the Management Plans were verified. Any area of suspected ACBM found in the course of the re-inspection, and not listed in the Management Plan or updates, were either assumed to contain asbestos or sampled and analyzed to determine their asbestos content. Any such new areas either assumed to contain asbestos or determined through analysis to contain asbestos were included in the report of the Three-Year Re-inspection. The results of the AHERA Three-Year Re-inspection IX are tabulated in the Room by Room log reports located in *Section II-C* of this report.

As previously noted, all future periodic Six-Month inspections and Three-Year Re-inspections of this location will be performed and the Inspection Data in this report will be updated accordingly.

Section I – C.1

Post Management Plan Activities/Changes

Information on activities affecting Asbestos Containing Building Materials (ACBMs) at this location is contained in updates to the Management Plan. These updates are kept on file by the School District of Philadelphia and were reviewed for this project. Updates to the Management Plan include the following: *Sampling and Analysis, New Tile Installation, Abatement Activity and Periodic Six-Month Surveillance Data.*

Sampling and Analysis

In the event Sampling occurs, data will be listed here.

Section I – C.2

Information on the installation of new floor tiles/renovation activities affecting Asbestos Containing Building Materials (ACBMs) at this location is contained in updates to the Management Plan. These updates are kept on file by the School District of Philadelphia and were reviewed for this project. Updates to the Management Plan include the following:

New Floor Tile Sampling

In the event that new tile is installed, the material must be tested prior to installation.

Section I – C.3

Information on the Asbestos Abatement and renovation activities affecting Asbestos Containing Building Materials (ACBMs) at this location is contained in updates to the Management Plan. These updates are kept on file by the School District of Philadelphia and were reviewed for this project. Updates to the Management Plan include the following:

Abatement Activity

In the event Abatement occurs, data will be listed here.

Section I – C.4

Information on the AHERA inspection that noted damage to various Building Materials at this location is contained in updates to the Management Plan. These updates are kept on file by the School District of Philadelphia and were reviewed for this project. Work orders are created for Corrective Action responses and tracked for completion. Updates to the Management Plan include the following:

Periodic (Six-Month) Surveillance (Damaged Materials)

| <i>Date</i> | <i>Element</i> | <i>Floor</i> | <i>On Site Room Name</i> | <i>Material</i> | <i>Amount of Material</i> | <i>Amount of Damage</i> |
|-------------|----------------|--------------|--------------------------|--------------------------|---------------------------|-------------------------|
| 7/5/2016 | 1 | 3 | Computer Class Room 311 | Floor Tile VAT 12" x 12" | 864 SF | 5 SF |

Section II

Re-Inspection Data

A. Introduction

B. Re-Inspection Key Definitions

C. Room by Room Location Log Report

Section II - A

Re-inspection Data

Introduction

The following information documents the Three-Year Re-inspection IX of the subject school/facility. The Homogeneous Area Reports were produced using the building inspector's field data on the facility. The key to the Homogeneous Area Report is outlined in the following pages of this report.

Section II - B
(page 1 of 4)

SCHOOL DISTRICT OF PHILADELPHIA
AHERA THREE YEAR RE-INSPECTION IX

| ITEM | DEFINITION |
|---------------------------------|---|
| ULCS# | Individual identification number assigned to each school within the School District of Philadelphia. |
| HOMOGENEOUS AREA ID# | Identification number assigned to each homogeneous area in a school/facility. Each section of the homogeneous area ID is significant. 1010/01/01/01 A B C D A. Is the ULCS# for the school. B. Designates the specific building/building area within the school. C. Designates the floor or level within the building/building area. D. Designates the homogeneous material within that floor or level. Note: Item D may be a number or a letter. |
| SYSTEM AFFECTED | Corresponds to the AHERA system for classifying materials. T : Thermal System S : Surfacing System M : Miscellaneous |
| ITEM AFFECTED | Is a description of the homogeneous material. |
| ORIGINAL INSPECTION DATA | This section contains the information found in the original Management Plan (1988-1989). |
| AMOUNT OF MATERIAL/ UNIT | Quantity of material, and measuring unit. Units include: Square Feet (SF) Each (EA) Linear Feet (LF) Cubic Feet (CF). |

**SCHOOL DISTRICT OF PHILADELPHIA
AHERA THREE YEAR RE-INSPECTION IX**

RE-INSPECTION FORM KEY

| ITEM | DEFINITION |
|--------------------------------------|---|
| CND Condition | Corresponds to AHERA condition rating for materials. 0 : No Damage 1 : Damage 2 : Significant Damage |
| DP Damage Potential | Corresponds to the AHERA material assessment system. 1 : Potential for Damage 2 : Potential for Significant Damage |
| ASMD Assumed Asbestos | This means that a material was not sampled for asbestos content during the original Management Plan inspection. |
| RA Response Action | This corresponds to the AHERA system of response action rating for materials. 1 : Establish O&M Program 2 : Repair and Establish O&M Program 3 : Enclose 4 : Encapsulate 5 : Remove 6 : Partial Removal and Establish O&M Program |
| CHANGES | This section describes changes to the homogeneous material in the twenty-four years since the original AHERA inspection. The abbreviations are defined below. RMVD : Removed ENCL : Enclosed ENCP : Encapsulated DMGD : Damaged SMPLD : Sampled MTRL : Material RPRD : Repaired N/L : None Located RPLCD : Replaced |

**SCHOOL DISTRICT OF PHILADELPHIA
AHERA THREE-YEAR RE-INSPECTION IX**

RE-INSPECTION FORM KEY

| ITEM | DEFINITION | | | | | | | | | | | | |
|-------------------------------------|---|----|-----------------------|----|----------------------------------|----|---------|----|-------------|----|--------|----|---|
| THREE YEAR RE-INSPECTION | <p>This section contains the information obtained from the Three-Year Re-inspection IX. With three exceptions, the information categories are identical in format and meaning to those found in the original inspection data section. The three exceptions are defined below.</p> | | | | | | | | | | | | |
| DMGD AMT Amount Damaged | <p>This section gives the quantity of damaged material in a homogeneous area. The quantity is shown in the same format as the amount of material/unit section.</p> | | | | | | | | | | | | |
| NF Newly Friable | <p>This section identifies materials in the original Management Plan which have since become friable.</p> | | | | | | | | | | | | |
| RA Response Action | <p>This rating is based on the AHERA regulations, and is comparable to the RA rating found in the "Original Inspection Data" section. The following table details the response actions.</p> <table><tr><td>1.</td><td>Establish O&M Program</td></tr><tr><td>2.</td><td>Repair and Establish O&M Program</td></tr><tr><td>3.</td><td>Enclose</td></tr><tr><td>4.</td><td>Encapsulate</td></tr><tr><td>5.</td><td>Remove</td></tr><tr><td>6.</td><td>Partial Removal and Establish O&M Program</td></tr></table> <p>a. High Priority Response The homogeneous material has been scheduled for abatement or other response action.</p> <p>b. Medium Priority Response The homogeneous material will be scheduled for abatement or other response action as soon as the high priority responses have been addressed.</p> <p>c. Low Priority Response The homogeneous material will be scheduled for abatement or other response action as soon as the medium priority responses have been addressed.</p> <p>d. On-Going Response/Operations and Maintenance The homogeneous material does not require abatement or other response action at present, and should be included in the facility's on-going operations and maintenance program.</p> | 1. | Establish O&M Program | 2. | Repair and Establish O&M Program | 3. | Enclose | 4. | Encapsulate | 5. | Remove | 6. | Partial Removal and Establish O&M Program |
| 1. | Establish O&M Program | | | | | | | | | | | | |
| 2. | Repair and Establish O&M Program | | | | | | | | | | | | |
| 3. | Enclose | | | | | | | | | | | | |
| 4. | Encapsulate | | | | | | | | | | | | |
| 5. | Remove | | | | | | | | | | | | |
| 6. | Partial Removal and Establish O&M Program | | | | | | | | | | | | |

**SCHOOL DISTRICT OF PHILADELPHIA
AHERA THREE-YEAR RE-INSPECTION IX**

RE-INSPECTION FORM KEY

The information presented in the changes section has been compiled from a variety of sources, including the Re-inspection and the following:

- * Quality Control/Quality Assurance Reports of asbestos abatement projects, prepared by consultants to the School District.
- * Permit and Notification Forms for asbestos abatement projects.
- * Periodic Surveillance Forms
- * Operations and Maintenance activities performed by School District personnel.
- * Verbal information from School District personnel.
- * Reports of sampling and analysis of suspected materials by both School District personnel and outside consultants.

**ROOM BY
ROOM
LOCATION LOG
REPORT**

This section gives information, including damage amount and location, for a specific homogeneous material on a room-by-room basis and follows the Re-inspection form.

NOTE: The disparate nature of the above sources of information prohibits the verification of much information within the scope of the AHERA Three-Year Re-inspection. Discrepancies and omissions may exist in this information, and therefore is included on an "as is" basis. The inspectors for the Three-Year Re-inspection IX evaluated homogeneous areas based on the materials current condition and location, as evidenced during the inspector's site visit.

Section II - C

Room by Room Location Log Report

These charts are to be used for a quick reference* in order to avoid the unknowing disturbance of Asbestos Containing Materials during any and all Operations, Maintenance, Renovation, and/or Demolition activities at this location.

NOTE:

*Contact OEMS prior to the disturbance of any of the materials that are listed as **Confirmed and/or Assumed**.*

The quantities listed for (NAD) non-asbestos containing materials and/or Non-Suspect Materials are only estimated and were not measured for the purpose of this report. Field verification of quantities for renovation purposes would be necessary.

6010 Central HS - 2015 2016 AHERA Three-Year Report.xls

| School District of Philadelphia Central High School 1700 W. Olney Avenue, Philadelphia, PA 19141 ULCS# 6010 Year Built: 1939 | | | AHERA Three-Year Reinspection 2015-2016 Room by Room Location Log Report | | | | | | | | Reinspection Date: 7/5/2016 Building Inspector: Ananth K. Vinjamuri Number: 374 Management Planner: Mary Anne Lerro Number: 742327 | | | | | |
|--|-------|--|---|---------------------------------|-----------------------|--|--------------------|------------|------------------|----------|--|--|---------------------------|-----------------------|--------------------|----------------------|
| Element | Floor | On Site Room Name | System Affected | Material Description | HID# | Confirmed, Assumed, NAD, Non Suspect ACM | Amount of Material | (SF/LF/EA) | Amount of Damage | SF LF EA | Color required for VAT | Comments/Description/Notes | Attic/Crawl space Ranking | Damage Potential (DP) | Newly Friable (NF) | Response Action (RA) |
| | | | | | | | | | | | | | | | | |
| 1 | 1 | Classroom 101/103 | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 60 | LF | 0 | LF | | | | N/A | N/A | N/A |
| 1 | 1 | Classroom 101/103 | N/A | Fiberglass Ceiling Tile 2' x 4' | | Non Suspect ACM | 1248 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 1 | Classroom 101/103 | N/A | Plaster Walls | | NAD | 1400 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 1 | Classroom 101/103 | N/A | Wood Floor | | Non Suspect ACM | 1248 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 1 | Classroom 101/103 | M | Blackboard Glue Dots | 6010/01/01/GC/AV/2600 | Assumed | 200 | SF | 0 | SF | | | | 1 | No | 1/D |
| 1 | 1 | Classroom 102 | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 30 | LF | 0 | LF | | | | N/A | N/A | N/A |
| 1 | 1 | Classroom 102 | N/A | Fiberglass Ceiling Tile 2' x 4' | | Non Suspect ACM | 864 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 1 | Classroom 102 | N/A | Plaster Walls | | NAD | 1200 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 1 | Classroom 102 | N/A | Wood Floor | | Non Suspect ACM | 864 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 1 | Classroom 102 | M | Blackboard Glue Dots | 6010/01/01/GC/AV/2600 | Assumed | 200 | SF | 0 | SF | | | | 1 | No | 1/D |
| 1 | 1 | Classroom 104 | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 30 | LF | 0 | LF | | | | N/A | N/A | N/A |
| 1 | 1 | Classroom 104 | N/A | Fiberglass Ceiling Tile 2' x 4' | | Non Suspect ACM | 720 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 1 | Classroom 104 | N/A | Plaster Walls | | NAD | 1000 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 1 | Classroom 104 | N/A | Wood Floor | | Non Suspect ACM | 720 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 1 | Classroom 104 | M | Blackboard Glue Dots | 6010/01/01/GC/AV/2600 | Assumed | 200 | SF | 0 | SF | | | | 1 | No | 1/D |
| 1 | 1 | Classroom 105 | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 30 | LF | 0 | LF | | | | N/A | N/A | N/A |
| 1 | 1 | Classroom 105 | N/A | Fiberglass Ceiling Tile 2' x 4' | | Non Suspect ACM | 720 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 1 | Classroom 105 | N/A | Plaster Walls | | NAD | 1000 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 1 | Classroom 105 | N/A | Wood Floor | | Non Suspect ACM | 720 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 1 | Classroom 105 | M | Blackboard Glue Dots | 6010/01/01/GC/AV/2600 | Assumed | 200 | SF | 0 | SF | | | | 1 | No | 1/D |
| 1 | 1 | Classroom 106 | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 30 | LF | 0 | LF | | | | N/A | N/A | N/A |
| 1 | 1 | Classroom 106 | N/A | Fiberglass Ceiling Tile 2' x 4' | | Non Suspect ACM | 720 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 1 | Classroom 106 | N/A | Plaster Walls | | NAD | 1000 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 1 | Classroom 106 | N/A | Wood Floor | | Non Suspect ACM | 720 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 1 | Classroom 106 | M | Blackboard Glue Dots | 6010/01/01/GC/AV/2600 | Assumed | 200 | SF | 0 | SF | | | | 1 | No | 1/D |
| 1 | 1 | Classroom 107 | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 30 | LF | 0 | LF | | | | N/A | N/A | N/A |
| 1 | 1 | Classroom 107 | N/A | Fiberglass Ceiling Tile 2' x 4' | | Non Suspect ACM | 720 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 1 | Classroom 107 | N/A | Plaster Walls | | NAD | 1000 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 1 | Classroom 107 | N/A | Wood Floor | | Non Suspect ACM | 720 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 1 | Classroom 107 | M | Blackboard Glue Dots | 6010/01/01/GC/AV/2600 | Assumed | 200 | SF | 0 | SF | | | | 1 | No | 1/D |
| 1 | 1 | Classroom 108 | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 30 | LF | 0 | LF | | | | N/A | N/A | N/A |
| 1 | 1 | Classroom 108 | N/A | Fiberglass Ceiling Tile 2' x 4' | | Non Suspect ACM | 720 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 1 | Classroom 108 | N/A | Plaster Walls | | NAD | 1000 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 1 | Classroom 108 | N/A | Wood Floor | | Non Suspect ACM | 720 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 1 | Classroom 108 | M | Blackboard Glue Dots | 6010/01/01/GC/AV/2600 | Assumed | 200 | SF | 0 | SF | | | | 1 | No | 1/D |
| 1 | 1 | Classroom 109 | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 30 | LF | 0 | LF | | | | N/A | N/A | N/A |
| 1 | 1 | Classroom 109 | N/A | Fiberglass Ceiling Tile 2' x 4' | | Non Suspect ACM | 720 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 1 | Classroom 109 | N/A | Plaster Walls | | NAD | 1000 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 1 | Classroom 109 | N/A | Wood Floor | | Non Suspect ACM | 720 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 1 | Classroom 109 | M | Blackboard Glue Dots | 6010/01/01/GC/AV/2600 | Assumed | 200 | SF | 0 | SF | | | | 1 | No | 1/D |
| 1 | 1 | Office Room 110 | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 30 | LF | 0 | LF | | | | N/A | N/A | N/A |
| 1 | 1 | Office Room 110 | N/A | Fiberglass Ceiling Tile 2' x 4' | | Non Suspect ACM | 360 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 1 | Office Room 110 | N/A | Plaster Walls | | NAD | 700 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 1 | Office Room 110 | N/A | Wood Floor | | Non Suspect ACM | 360 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 1 | Classroom 111 | N/A | Fiberglass Ceiling Tile 2' x 4' | | Non Suspect ACM | 672 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 1 | Classroom 111 | N/A | Plaster Walls | | NAD | 900 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 1 | Classroom 111 | N/A | Wood Floor | | Non Suspect ACM | 672 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 1 | Classroom 111 | M | Blackboard Glue Dots | 6010/01/01/GC/AV/2600 | Assumed | 200 | SF | 0 | SF | | | | 1 | No | 1/D |
| 1 | 1 | Classroom 111 Storage/Office | N/A | Plaster Ceiling | | NAD | 126 | SF | 50 | SF | | Plaster Damage, Effervescence, debris | | N/A | N/A | N/A |
| 1 | 1 | Classroom 111 Storage/Office | N/A | Plaster Walls | | NAD | 400 | SF | 50 | SF | | Plaster Damage, Effervescence, debris | | N/A | N/A | N/A |
| 1 | 1 | Room 113 - Classroom 111 Storage/Office | N/A | Wood Floor | | Non Suspect ACM | 126 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 1 | X | X | X | | X | X | X | X | X | X | Department Head's Office - No access at this time. Please verify On Site Room Name | | X | X | X |
| 1 | 1 | X | X | X | | X | X | X | X | X | X | Department Head's Office - No access at this time. Please verify On Site Room Name | | X | X | X |
| 1 | 1 | IMC/Library | S | Acoustical Plaster Ceiling | 6010/01/01/GC/AV/1902 | Assumed | 1056 | SF | 0 | SF | | | | 1 | No | 1/D |
| 1 | 1 | IMC/Library | N/A | Plaster Ceiling | | NAD | 1500 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 1 | IMC/Library | N/A | Plaster Walls | | NAD | 4000 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 1 | IMC/Library | N/A | Carpet | | Non Suspect ACM | 2500 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 1 | Library classroom | M | Ceiling Tile 2' x 2' | 6010/01/01/GC/AV/1730 | Assumed | 300 | SF | 0 | SF | | | | 1 | No | 1/D |
| 1 | 1 | Library classroom | N/A | Plaster Walls | | NAD | 650 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 1 | Library classroom | N/A | Carpet | | Non Suspect ACM | 300 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 1 | Library classroom | M | Ceiling Tile 2' x 2' | 6010/01/01/GC/AV/1730 | Assumed | 300 | SF | 0 | SF | | | | 1 | No | 1/D |
| 1 | 1 | Library classroom | N/A | Plaster Walls | | NAD | 650 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 1 | Library classroom | N/A | Carpet | | Non Suspect ACM | 300 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 1 | Library classroom | M | Ceiling Tile 2' x 2' | 6010/01/01/GC/AV/1730 | Assumed | 300 | SF | 0 | SF | | | | 1 | No | 1/D |
| 1 | 1 | Library classroom | N/A | Plaster Walls | | NAD | 650 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 1 | Library classroom | N/A | Carpet | | Non Suspect ACM | 300 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 1 | Girl's Restroom across from the Auditorium | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 13 | LF | 0 | LF | | | | N/A | N/A | N/A |
| 1 | 1 | Girl's Restroom across from the Auditorium | N/A | Plaster Ceiling | | NAD | 540 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 1 | Girl's Restroom across from the Auditorium | N/A | Ceramic Tile Walls | | Non Suspect ACM | 800 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 1 | Girl's Restroom across from the Auditorium | N/A | Ceramic Tile Floors | | Non Suspect ACM | 540 | SF | 0 | SF | | | | N/A | N/A | N/A |

6010 Central HS - 2015 2016 AHERA Three-Year Report.xls

| School District of Philadelphia Central High School 1700 W. Olney Avenue, Philadelphia, PA 19141 ULCS# 6010 Year Built: 1939 | | AHERA Three-Year Reinspection 2015-2016 Room by Room Location Log Report | | | | | | | | | | Reinspection Date: 7/5/2016 Building Inspector: Ananth K. Vinjamuri Number: 374 Management Planner: Mary Anne Lerro Number: 742327 | | | | | |
|--|---|---|-----------------------|--|-----------------------|----------------------|-------|--|-------------------------------|------------------|----------|--|----------------------------|------------------------------|-----------------------|--------------------|----------------------|
| | | E l e m e n t | F l o o r | On Site Room Name | System Affected | Material Description | HID# | Confirmed, Assumed, NAD, Non Suspect ACM | Amount of Material (SF/LF/EA) | Amount of Damage | SF LF EA | Color required for VAT | Comments/Description/Notes | Attic/Crawlsp ace Ranking | Damage Potential (DP) | Newly Friable (NF) | Response Action (RA) |
| | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | |
| 1 | 1 | Custodial Storage next to Girl's Restroom | N/A | Plaster Ceiling | | NAD | 18 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 1 | Custodial Storage next to Girl's Restroom | N/A | Ceramic Tile Walls | | Non Suspect ACM | 150 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 1 | Custodial Storage next to Girl's Restroom | N/A | Ceramic Tile Floors | | Non Suspect ACM | 18 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 1 | Auditorium | T | Radiator Insulation | 6010/01/01/GC/AV/1600 | Assumed | 350 | SF | 0 | SF | | | | 1 | No | 1/D | |
| 1 | 1 | Auditorium | N/A | Acoustical Plaster Ceiling | | NAD | 8900 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 1 | Auditorium | N/A | Acoustical Plaster Walls | | NAD | 10000 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 1 | Auditorium | N/A | Wood Floor | | Non Suspect ACM | 8900 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 1 | Stage | N/A | Concrete Ceiling | | Non Suspect ACM | 1800 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 1 | Stage | N/A | Plaster Walls | | NAD | 3000 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 1 | Stage | N/A | Wood Floor | | Non Suspect ACM | 1800 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 1 | Women's Restroom across from the Auditorium | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 15 | LF | 0 | LF | | | | N/A | N/A | N/A | |
| 1 | 1 | Women's Restroom across from the Auditorium | N/A | Plaster Ceiling | | NAD | 350 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 1 | Women's Restroom across from the Auditorium | N/A | Plaster Walls | | NAD | 500 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 1 | Women's Restroom across from the Auditorium | N/A | Ceramic Tile Walls | | Non Suspect ACM | 500 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 1 | Women's Restroom across from the Auditorium | M | Floor Tile VAT 12" x 12" | 6010/01/01/NN | Assumed | 150 | SF | 0 | SF | White | | | 1 | No | 1/D | |
| 1 | 1 | Women's Restroom across from the Auditorium | N/A | Ceramic Tile Floors | | Non Suspect ACM | 200 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 1 | Room 112B | X | X | | X | X | X | X | X | X | Book Closet - No access | | X | X | X | |
| 1 | 1 | Room 112C | X | X | | X | X | X | X | X | X | Book Closet - No access | | X | X | X | |
| 1 | 1 | Classroom 119 | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 30 | LF | 0 | LF | | | | N/A | N/A | N/A | |
| 1 | 1 | Classroom 119 | N/A | Plaster Ceiling | | NAD | 480 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 1 | Classroom 119 | N/A | Plaster Walls | | NAD | 700 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 1 | Classroom 119 | N/A | Floor Tile VAT 12" x 12" | | NAD | 480 | SF | 0 | SF | Green | | | N/A | N/A | N/A | |
| 1 | 1 | Classroom 119 | N/A | Black/Yellow Mastic a/w Floor Tile VAT 12" x 12" | | NAD | 480 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 1 | Classroom 119 | M | Blackboard Glue Dots | 6010/01/01/GC/AV/2600 | Assumed | 100 | SF | 0 | SF | | | | 1 | No | 1/D | |
| 1 | 1 | Classroom 120 | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 30 | LF | 0 | LF | | | | N/A | N/A | N/A | |
| 1 | 1 | Classroom 120 | N/A | Plaster Ceiling | | NAD | 864 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 1 | Classroom 120 | N/A | Plaster Walls | | NAD | 1100 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 1 | Classroom 120 | M | Wood Floor | | Non Suspect ACM | 864 | SF | 0 | SF | | | | 1 | No | 1/D | |
| 1 | 1 | Classroom 120 | M | Blackboard Glue Dots | 6010/01/01/GC/AV/2600 | Assumed | 100 | SF | 0 | SF | | | | 1 | No | 1/D | |
| 1 | 1 | Classroom 121 | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 45 | LF | 0 | LF | | | | N/A | N/A | N/A | |
| 1 | 1 | Classroom 121 | N/A | Fiberglass Ceiling Tile 2' x 4' | | Non Suspect ACM | 720 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 1 | Classroom 121 | N/A | Plaster Walls | | NAD | 1000 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 1 | Classroom 121 | N/A | Wood Floor | | Non Suspect ACM | 720 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 1 | Classroom 121 | M | Blackboard Glue Dots | 6010/01/01/GC/AV/2600 | Assumed | 200 | SF | 0 | SF | | | | 1 | No | 1/D | |
| 1 | 1 | Classroom 122 | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 45 | LF | 0 | LF | | | | N/A | N/A | N/A | |
| 1 | 1 | Classroom 122 | N/A | Fiberglass Ceiling Tile 2' x 4' | | Non Suspect ACM | 720 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 1 | Classroom 122 | N/A | Plaster Walls | | NAD | 1000 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 1 | Classroom 122 | N/A | Wood Floor | | Non Suspect ACM | 720 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 1 | Classroom 122 | M | Blackboard Glue Dots | 6010/01/01/GC/AV/2600 | Assumed | 200 | SF | 0 | SF | | | | 1 | No | 1/D | |
| 1 | 1 | Classroom 123 | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 30 | LF | 0 | LF | | | | N/A | N/A | N/A | |
| 1 | 1 | Classroom 123 | N/A | Fiberglass Ceiling Tile 2' x 4' | | Non Suspect ACM | 720 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 1 | Classroom 123 | N/A | Plaster Walls | | NAD | 1000 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 1 | Classroom 123 | N/A | Wood Floor | | Non Suspect ACM | 720 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 1 | Classroom 123 | M | Blackboard Glue Dots | 6010/01/01/GC/AV/2600 | Assumed | 200 | SF | 0 | SF | | | | 1 | No | 1/D | |
| 1 | 1 | Classroom 124 | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 30 | LF | 0 | LF | | | | N/A | N/A | N/A | |
| 1 | 1 | Classroom 124 | N/A | Fiberglass Ceiling Tile 2' x 4' | | Non Suspect ACM | 720 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 1 | Classroom 124 | N/A | Plaster Walls | | NAD | 1000 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 1 | Classroom 124 | N/A | Wood Floor | | Non Suspect ACM | 720 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 1 | Classroom 124 | M | Blackboard Glue Dots | 6010/01/01/GC/AV/2600 | Assumed | 200 | SF | 0 | SF | | | | 1 | No | 1/D | |
| 1 | 1 | Classroom 125 | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 30 | LF | 0 | LF | | | | N/A | N/A | N/A | |
| 1 | 1 | Classroom 125 | N/A | Fiberglass Ceiling Tile 2' x 4' | | Non Suspect ACM | 720 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 1 | Classroom 125 | N/A | Plaster Walls | | NAD | 1000 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 1 | Classroom 125 | N/A | Wood Floor | | Non Suspect ACM | 720 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 1 | Classroom 125 | M | Blackboard Glue Dots | 6010/01/01/GC/AV/2600 | Assumed | 200 | SF | 0 | SF | | | | 1 | No | 1/D | |
| 1 | 1 | Classroom 126 | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 30 | LF | 0 | LF | | | | N/A | N/A | N/A | |
| 1 | 1 | Classroom 126 | N/A | Fiberglass Ceiling Tile 2' x 4' | | Non Suspect ACM | 720 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 1 | Classroom 126 | N/A | Plaster Walls | | NAD | 1000 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 1 | Classroom 126 | N/A | Wood Floor | | Non Suspect ACM | 720 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 1 | Classroom 126 | M | Blackboard Glue Dots | 6010/01/01/GC/AV/2600 | Assumed | 200 | SF | 0 | SF | | | | 1 | No | 1/D | |
| 1 | 1 | Classroom 127 | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 30 | LF | 0 | LF | | | | N/A | N/A | N/A | |
| 1 | 1 | Classroom 127 | N/A | Fiberglass Ceiling Tile 2' x 4' | | Non Suspect ACM | 720 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 1 | Classroom 127 | N/A | Plaster Walls | | NAD | 1000 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 1 | Classroom 127 | N/A | Wood Floor | | Non Suspect ACM | 720 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 1 | Classroom 127 | M | Blackboard Glue Dots | 6010/01/01/GC/AV/2600 | Assumed | 200 | SF | 0 | SF | | | | 1 | No | 1/D | |
| 1 | 1 | Room 128 -Office | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 26 | LF | 0 | LF | | | | N/A | N/A | N/A | |
| 1 | 1 | Room 128 -Office | N/A | Fiberglass Ceiling Tile 2' x 4' | | Non Suspect ACM | 360 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 1 | Room 128 -Office | N/A | Plaster Walls | | NAD | 700 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 1 | Room 128 -Office | N/A | Wood Floor | | Non Suspect ACM | 360 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 1 | Room 128 -Office Closet | N/A | Plaster Ceiling | | NAD | 40 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 1 | Room 128 -Office Closet | N/A | Plaster Walls | | NAD | 250 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 1 | Room 128 -Office Closet | N/A | Wood Floor | | Non Suspect ACM | 48 | SF | 0 | SF | | | | N/A | N/A | N/A | |

6010 Central HS - 2015 2016 AHERA Three-Year Report.xls

| School District of Philadelphia Central High School 1700 W. Olney Avenue, Philadelphia, PA 19141 ULCS# 6010 Year Built: 1939 | | AHERA Three-Year Reinspection 2015-2016 Room by Room Location Log Report | | | | | | | | | | Reinspection Date: 7/5/2016 Building Inspector: Ananth K. Vinjamuri Number: 374 Management Planner: Mary Anne Lerro Number: 742327 | | | | |
|--|-----------------------|---|-----------------|---------------------------------|---------------|--|--------------------|------------|------------------|----------|------------------------|--|---------------------------|-----------------------|--------------------|----------------------|
| E l e m e n t | F l o o r | On Site Room Name | System Affected | Material Description | HID# | Confirmed, Assumed, NAD, Non Suspect ACM | Amount of Material | (SF/LF/EA) | Amount of Damage | SF LF EA | Color required for VAT | Comments/Description/Notes | Attic/Crawl space Ranking | Damage Potential (DP) | Newly Friable (NF) | Response Action (RA) |
| 1 | 1 | Storage Room across from the Auditorium | N/A | Plaster Ceiling | | NAD | 196 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 1 | Storage Room across from the Auditorium | N/A | Plaster Walls | | NAD | 500 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 1 | Storage Room across from the Auditorium | N/A | Wood Floor | | Non Suspect ACM | 196 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 1 | Men's Restroom across from the Auditorium | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 15 | LF | 0 | LF | | | | N/A | N/A | N/A |
| 1 | 1 | Men's Restroom across from the Auditorium | N/A | Plaster Ceiling | | NAD | 350 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 1 | Men's Restroom across from the Auditorium | N/A | Plaster Walls | | NAD | 500 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 1 | Men's Restroom across from the Auditorium | N/A | Ceramic Tile Walls | | Non Suspect ACM | 500 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 1 | Men's Restroom across from the Auditorium | M | Floor Tile VAT 12" x 12" | 6010/01/01/NN | Assumed | 150 | SF | 0 | SF | White | | 1 | No | 1/D | |
| 1 | 1 | Men's Restroom across from the Auditorium | N/A | Ceramic Tile Floors | | Non Suspect ACM | 200 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 1 | Boy's Restroom across from the Auditorium | N/A | Plaster Ceiling | | NAD | 540 | SF | 40 | SF | | | | N/A | N/A | N/A |
| 1 | 1 | Boy's Restroom across from the Auditorium | N/A | Ceramic Tile Walls | | Non Suspect ACM | 800 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 1 | Boy's Restroom across from the Auditorium | N/A | Ceramic Tile Floors | | Non Suspect ACM | 540 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 1 | Custodial Storage next to Boy's Restroom | N/A | Plaster Ceiling | | NAD | 18 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 1 | Custodial Storage next to Boy's Restroom | N/A | Ceramic Tile Walls | | Non Suspect ACM | 150 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 1 | Custodial Storage next to Boy's Restroom | N/A | Ceramic Tile Floors | | Non Suspect ACM | 18 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 1 | Counselor Office #1-left side of walkway | N/A | Fiberglass Ceiling Tile 2' x 4' | | Non Suspect ACM | 80 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 1 | Counselor Office #1-left side of walkway | N/A | Plaster Walls | | NAD | 280 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 1 | Counselor Office #1-left side of walkway | M | Floor Tile VAT 12" x 12" | 6010/01/01/NN | Assumed | 80 | SF | 0 | SF | Green | | 1 | No | 1/D | |
| 1 | 1 | Counselor Office #2-left end of the walkway | N/A | Fiberglass Ceiling Tile 2' x 4' | | Non Suspect ACM | 64 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 1 | Counselor Office #2-left end of the walkway | N/A | Plaster Walls | | NAD | 250 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 1 | Counselor Office #2-left end of the walkway | M | Floor Tile VAT 12" x 12" | 6010/01/01/NN | Assumed | 64 | SF | 0 | SF | Green | | 1 | No | 1/D | |
| 1 | 1 | Counselor Office #3-right end of the walkway | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 20 | LF | 0 | LF | | | | N/A | N/A | N/A |
| 1 | 1 | Counselor Office #3-right end of the walkway | N/A | Fiberglass Ceiling Tile 2' x 4' | | Non Suspect ACM | 80 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 1 | Counselor Office #3-right end of the walkway | N/A | Plaster Walls | | NAD | 280 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 1 | Counselor Office #3-right end of the walkway | M | Floor Tile VAT 12" x 12" | 6010/01/01/NN | Assumed | 80 | SF | 0 | LF | Green | | 1 | No | 1/D | |
| 1 | 1 | Counselor Office #4-right side of the walkway | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 20 | LF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 1 | Counselor Office #4-right side of the walkway | N/A | Fiberglass Ceiling Tile 2' x 4' | | Non Suspect ACM | 100 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 1 | Counselor Office #4-right side of the walkway | N/A | Plaster Walls | | NAD | 320 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 1 | Counselor Office #4-right side of the walkway | M | Floor Tile VAT 12" x 12" | 6010/01/01/NN | Assumed | 100 | SF | 0 | SF | Green | | 1 | No | 1/D | |
| 1 | 1 | Counselor Office #5 (left) - in front of waiting area | N/A | Fiberglass Ceiling Tile 2' x 4' | | Non Suspect ACM | 100 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 1 | Counselor Office #5 (left) - in front of waiting area | N/A | Plaster Walls | | NAD | 280 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 1 | Counselor Office #5 (left) - in front of waiting area | M | Floor Tile VAT 12" x 12" | 6010/01/01/NN | Assumed | 100 | SF | 0 | SF | Green | | 1 | No | 1/D | |
| 1 | 1 | Counselor Office #6 (right) - in front of waiting area | N/A | Fiberglass Ceiling Tile 2' x 4' | | Non Suspect ACM | 90 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 1 | Counselor Office #6 (right) - in front of waiting area | N/A | Plaster Walls | | NAD | 264 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 1 | Counselor Office #6 (right) - in front of waiting area | M | Floor Tile VAT 12" x 12" | 6010/01/01/NN | Assumed | 90 | SF | 0 | SF | Green | | 1 | No | 1/D | |
| 1 | 1 | Counselor Office waiting area | N/A | Fiberglass Ceiling Tile 2' x 4' | | Non Suspect ACM | 294 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 1 | Counselor Office waiting area | N/A | Plaster Walls | | NAD | 600 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 1 | Counselor Office waiting area | M | Floor Tile VAT 12" x 12" | 6010/01/01/NN | Assumed | 294 | SF | 0 | SF | Green | | 1 | No | 1/D | |
| 1 | 1 | Conference Room next to Principal's Office | N/A | Fiberglass Ceiling Tile 2' x 4' | | Non Suspect ACM | 288 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 1 | Conference Room next to Principal's Office | N/A | Plaster Walls | | NAD | 600 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 1 | Conference Room next to Principal's Office | M | Floor Tile VAT 12" x 12" | 6010/01/01/NN | Assumed | 288 | SF | 0 | SF | Green | | 1 | No | 1/D | |
| 1 | 1 | Nurse's Suite | N/A | Fiberglass Ceiling Tile 2' x 4' | | Non Suspect ACM | 528 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 1 | Nurse's Suite | N/A | Plaster Walls | | NAD | 900 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 1 | Nurse's Suite | N/A | Wood Floor | | Non Suspect ACM | 528 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 1 | Nurse's Suite Office-Front | N/A | Fiberglass Ceiling Tile 2' x 4' | | Non Suspect ACM | 54 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 1 | Nurse's Suite Office-Front | N/A | Plaster Walls | | NAD | 240 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 1 | Nurse's Suite Office-Front | N/A | Wood Floor | | Non Suspect ACM | 54 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 1 | Nurse's Suite Office-Rear | N/A | Fiberglass Ceiling Tile 2' x 4' | | Non Suspect ACM | 24 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 1 | Nurse's Suite Office-Rear | N/A | Plaster Walls | | NAD | 160 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 1 | Nurse's Suite Office-Rear | N/A | Wood Floor | | Non Suspect ACM | 24 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 1 | Nurse's Suite Office-Right side | N/A | Fiberglass Ceiling Tile 2' x 4' | | Non Suspect ACM | 195 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 1 | Nurse's Suite Office-Right side | N/A | Plaster Walls | | NAD | 500 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 1 | Nurse's Suite Office-Right side | N/A | Wood Floor | | Non Suspect ACM | 195 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 1 | Nurse's Suite Restroom | N/A | Fiberglass Ceiling Tile 2' x 4' | | Non Suspect ACM | 60 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 1 | Nurse's Suite Restroom | N/A | Ceramic Tile Walls | | Non Suspect ACM | 300 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 1 | Nurse's Suite Restroom | N/A | Ceramic Tile Floors | | Non Suspect ACM | 60 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 1 | Principal's Office | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 30 | LF | 0 | LF | | | | N/A | N/A | N/A |
| 1 | 1 | Principal's Office | N/A | Fiberglass Ceiling Tile 2' x 4' | | Non Suspect ACM | 288 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 1 | Principal's Office | N/A | Plaster Walls | | NAD | 400 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 1 | Principal's Office | N/A | Carpet | | Non Suspect ACM | 288 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 1 | Principal's Office Restroom | N/A | Fiberglass Ceiling Tile 2' x 4' | | Non Suspect ACM | 48 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 1 | Principal's Office Restroom | N/A | Ceramic Tile Walls | | Non Suspect ACM | 250 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 1 | Principal's Office Restroom | N/A | Ceramic Tile Floors | | Non Suspect ACM | 48 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 1 | Office next to Nurse's Suite | N/A | Fiberglass Ceiling Tile 2' x 4' | | Non Suspect ACM | 196 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 1 | Office next to Nurse's Suite | N/A | Plaster Walls | | NAD | 500 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 1 | Office next to Nurse's Suite | N/A | Wood Floor | | Non Suspect ACM | 196 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 1 | Storage in Office next to Nurse's Suite | N/A | Fiberglass Ceiling Tile 2' x 4' | | Non Suspect ACM | 126 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 1 | Storage in Office next to Nurse's Suite | N/A | Plaster Walls | | NAD | 400 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 1 | Storage in Office next to Nurse's Suite | N/A | Wood Floor | | Non Suspect ACM | 126 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 1 | Storage in Office next to Nurse's Suite | N/A | Fiberglass Ceiling Tile 2' x 4' | | Non Suspect ACM | 84 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 1 | Storage in Office next to Nurse's Suite | N/A | Plaster Walls | | NAD | 400 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 1 | Storage in Office next to Nurse's Suite | N/A | Wood Floor | | Non Suspect ACM | 84 | SF | 0 | SF | | | | N/A | N/A | N/A |

6010 Central HS - 2015 2016 AHERA Three-Year Report.xls

| School District of Philadelphia Central High School 1700 W. Olney Avenue, Philadelphia, PA 19141 ULCS# 6010 Year Built: 1939 | | AHERA Three-Year Reinspection 2015-2016 Room by Room Location Log Report | | | | | | | | | | Reinspection Date: 7/5/2016 Building Inspector: Ananth K. Vinjamuri Number: 374 Management Planner: Mary Anne Lerro Number: 742327 | | | | |
|--|-----------------------|---|-----------------|---------------------------------|-----------------------|--|--------------------|------------|------------------|----------|------------------------|--|------------------------------|-----------------------|--------------------|----------------------|
| E l e m e n t | F l o o r | On Site Room Name | System Affected | Material Description | HID# | Confirmed, Assumed, NAD, Non Suspect ACM | Amount of Material | (SF/LF/EA) | Amount of Damage | SF LF EA | Color required for VAT | Comments/Description/Notes | Attic/Crawlsp ace Ranking | Damage Potential (DP) | Newly Friable (NF) | Response Action (RA) |
| 1 | 1 | Office next to Main Office | N/A | Fiberglass Ceiling Tile 2' x 4' | | Non Suspect ACM | 308 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 1 | Office next to Main Office | N/A | Plaster Walls | | NAD | 700 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 1 | Office next to Main Office | M | Floor Tile VAT 12" x 12" | 6010/01/01/NN | Assumed | 308 | SF | 0 | SF | Blue | | | 1 | No | 1/D |
| 1 | 1 | Main Office Kitchen | N/A | Fiberglass Ceiling Tile 2' x 4' | | Non Suspect ACM | 108 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 1 | Main Office Kitchen | N/A | Plaster Walls | | NAD | 400 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 1 | Main Office Kitchen | M | Floor Tile VAT 12" x 12" | 6010/01/01/NN | Assumed | 108 | SF | 0 | SF | White | | | 1 | No | 1/D |
| 1 | 1 | Office Walkway | N/A | Fiberglass Ceiling Tile 2' x 4' | | Non Suspect ACM | 60 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 1 | Office Walkway | N/A | Plaster Walls | | NAD | 300 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 1 | Office Walkway | M | Floor Tile VAT 12" x 12" | 6010/01/01/NN | Assumed | 60 | SF | 0 | SF | White | | | 1 | No | 1/D |
| 1 | 1 | Classroom 141 | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 30 | LF | 0 | LF | | | | N/A | N/A | N/A |
| 1 | 1 | Classroom 141 | N/A | Fiberglass Ceiling Tile 2' x 4' | | Non Suspect ACM | 720 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 1 | Classroom 141 | N/A | Plaster Walls | | NAD | 1100 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 1 | Classroom 141 | N/A | Wood Floor | | Non Suspect ACM | 720 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 1 | Main Office | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 60 | LF | 0 | LF | | | | N/A | N/A | N/A |
| 1 | 1 | Main Office | N/A | Fiberglass Ceiling Tile 2' x 4' | | Non Suspect ACM | 1032 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 1 | Main Office | N/A | Plaster Walls | | NAD | 1500 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 1 | Main Office | M | Floor Tile VAT 12" x 12" | 6010/01/01/NN | Assumed | 696 | SF | 0 | SF | Blue | | | 1 | No | 1/D |
| 1 | 1 | Main Office | M | Floor Tile VAT 12" x 12" | 6010/01/01/NN | Assumed | 336 | SF | 0 | SF | White | | | 1 | No | 1/D |
| 1 | 1 | Classroom 143 | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 30 | LF | 0 | LF | | | | N/A | N/A | N/A |
| 1 | 1 | Classroom 143 | N/A | Fiberglass Ceiling Tile 2' x 4' | | Non Suspect ACM | 720 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 1 | Classroom 143 | N/A | Plaster Walls | | NAD | 1100 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 1 | Classroom 143 | N/A | Wood Floor | | Non Suspect ACM | 720 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 1 | Room 144 - Roster Office | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 30 | LF | 0 | LF | | | | N/A | N/A | N/A |
| 1 | 1 | Room 144 - Roster Office | N/A | Fiberglass Ceiling Tile 2' x 4' | | Non Suspect ACM | 624 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 1 | Room 144 - Roster Office | N/A | Plaster Walls | | NAD | 900 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 1 | Room 144 - Roster Office | M | Floor Tile VAT 12" x 12" | 6010/01/01/NN | Assumed | 624 | SF | 0 | SF | White | | | 1 | No | 1/D |
| 1 | 1 | Roster Office Restroom | N/A | Plaster Ceiling | | NAD | 50 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 1 | Roster Office Restroom | N/A | Ceramic Tile Walls | | Non Suspect ACM | 300 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 1 | Roster Office Restroom | N/A | Ceramic Tile Floors | | Non Suspect ACM | 50 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 1 | Copier Room in Roster Office | N/A | Fiberglass Ceiling Tile 2' x 4' | | Non Suspect ACM | 80 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 1 | Copier Room in Roster Office | N/A | Plaster Walls | | NAD | 350 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 1 | Copier Room in Roster Office | M | Floor Tile VAT 12" x 12" | 6010/01/01/NN | Assumed | 80 | SF | 0 | SF | White | | | 1 | No | 1/D |
| 1 | 1 | Classroom 145 | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 30 | LF | 0 | LF | | | | N/A | N/A | N/A |
| 1 | 1 | Classroom 145 | N/A | Fiberglass Ceiling Tile 2' x 4' | | Non Suspect ACM | 720 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 1 | Classroom 145 | N/A | Plaster Walls | | NAD | 1100 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 1 | Classroom 145 | N/A | Wood Floor | | Non Suspect ACM | 720 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 1 | Storage next to Roster Office | N/A | Fiberglass Ceiling Tile 2' x 4' | | Non Suspect ACM | 312 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 1 | Storage next to Roster Office | N/A | Plaster Walls | | NAD | 700 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 1 | Storage next to Roster Office | N/A | Cement Floor | | Non Suspect ACM | 312 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 1 | Gym | N/A | Fiberglass Ceiling Tile 2' x 4' | | Non Suspect ACM | 7550 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 1 | Gym | N/A | Brick Wall | | Non Suspect ACM | 7000 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 1 | Gym | N/A | Wood Floor | | Non Suspect ACM | 7550 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 1 | Gym Closet | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 2 | LF | 0 | LF | | | | N/A | N/A | N/A |
| 1 | 1 | Gym Closet | N/A | Plaster Ceiling | | NAD | 100 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 1 | Gym Closet | N/A | Plaster Walls | | NAD | 400 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 1 | Gym | N/A | Wood Floor | | Non Suspect ACM | 100 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 1 | Gym Storage | N/A | Plaster Ceiling | | NAD | 236 | SF | 30 | SF | | | | N/A | N/A | N/A |
| 1 | 1 | Gym Storage | N/A | Brick Wall | | Non Suspect ACM | 350 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 1 | Gym Storage | N/A | Sheetrock Wall | 6010/01/01/GC/AV/2100 | Assumed | 100 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 1 | Gym Storage | N/A | Wood Floor | | Non Suspect ACM | 336 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 1 | Gym Storage | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 65 | LF | 0 | LF | | | | N/A | N/A | N/A |
| 1 | 1 | Gym Storage | N/A | Plaster Ceiling | | NAD | 130 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 1 | Gym Storage | N/A | Brick Wall | | Non Suspect ACM | 200 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 1 | Gym Storage | N/A | Wood Floor | | Non Suspect ACM | 130 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 1 | Work Room | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 36 | LF | 0 | LF | | | | N/A | N/A | N/A |
| 1 | 1 | Work Room | N/A | Fiberglass Ceiling Tile 2' x 4' | | Non Suspect ACM | 200 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 1 | Work Room | N/A | Plaster Walls | | NAD | 600 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 1 | Work Room | N/A | Wood Floor | | Non Suspect ACM | 200 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 1 | Work Room | M | Blackboard Glue Dots | 6010/01/01/GC/AV/2600 | Assumed | 50 | SF | 0 | SF | | | | 1 | No | 1/D |
| 1 | 1 | Hallway at Rooms 134 to 146 | N/A | Fiberglass Ceiling Tile 2' x 4' | | Non Suspect ACM | 1740 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 1 | Hallway at Rooms 134 to 146 | N/A | Plaster Walls | | NAD | 1500 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 1 | Hallway at Rooms 134 to 146 | N/A | Concrete Block Wall | | Non Suspect ACM | 1500 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 1 | Hallway at Rooms 134 to 146 | N/A | Cement Floor | | Non Suspect ACM | 1740 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 1 | Hallway at Rooms 101 to 111 | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 40 | LF | 0 | LF | | | | N/A | N/A | N/A |
| 1 | 1 | Hallway at Rooms 101 to 111 | N/A | Fiberglass Ceiling Tile 2' x 4' | | Non Suspect ACM | 1740 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 1 | Hallway at Rooms 101 to 111 | N/A | Plaster Walls | | NAD | 1500 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 1 | Hallway at Rooms 101 to 111 | N/A | Concrete Block Wall | | Non Suspect ACM | 1500 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 1 | Hallway at Rooms 101 to 111 | N/A | Cement Floor | | Non Suspect ACM | 1740 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 1 | Main Hallway | N/A | Ceiling Tile 1' x 1' | | NAD | 4872 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 1 | Main Hallway | N/A | Plaster Ceiling | | NAD | 4872 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 1 | Main Hallway | N/A | Plaster Walls | | NAD | 3250 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 1 | Main Hallway | N/A | Concrete Block Wall | | Non Suspect ACM | 3250 | SF | 0 | SF | | | | N/A | N/A | N/A |

6010 Central HS - 2015 2016 AHERA Three-Year Report.xls

| School District of Philadelphia Central High School 1700 W. Olney Avenue, Philadelphia, PA 19141 ULCS# 6010 Year Built: 1939 | | AHERA Three-Year Reinspection 2015-2016 Room by Room Location Log Report | | | | | | | | | | Reinspection Date: 7/5/2016 | | | | | |
|--|-----------------------|---|-----------------|---------------------------------|-----------------------|--|--------------------|------------|------------------|----------|------------------------|---|--------------------------|-----------------------|--------------------|----------------------|--|
| | | | | | | | | | | | | Building Inspector: Ananth K. Vinjamuri | | | | | |
| | | | | | | | | | | | | Number: 374 | | | | | |
| | | | | | | | | | | | | Management Planner: Mary Anne Lerro | | | | | |
| | | | | | | | | | | | | Number: 742327 | | | | | |
| E l e m e n t | F l o o r | | | | | | | | | | | | | | | | |
| | | On Site Room Name | System Affected | Material Description | HID# | Confirmed, Assumed, NAD, Non Suspect ACM | Amount of Material | (SF/LF/EA) | Amount of Damage | SF LF EA | Color required for VAT | Comments/Description/Notes | Attic/Crawlspace Ranking | Damage Potential (DP) | Newly Friable (NF) | Response Action (RA) | |
| 1 | 1 | Main Hallway | N/A | Terrazzo Floor | | Non Suspect ACM | 4872 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 1 | Exit Foyer at Library | N/A | Plaster Ceiling | | NAD | 140 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 1 | Exit Foyer at Library | N/A | Marble Wall | | Non Suspect ACM | 400 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 1 | Exit Foyer at Library | N/A | Terrazzo Floor | | Non Suspect ACM | 140 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 1 | Hallway between Library and Auditorium | N/A | Fiberglass Ceiling Tile 2' x 4' | | Non Suspect ACM | 1152 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 1 | Hallway between Library and Auditorium | N/A | Plaster Walls | | NAD | 800 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 1 | Hallway between Library and Auditorium | N/A | Concrete Block Wall | | Non Suspect ACM | 800 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 1 | Hallway between Library and Auditorium | N/A | Cement Floor | | Non Suspect ACM | 1152 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 1 | Hallway at Rooms 119 to 128 | N/A | Fiberglass Ceiling Tile 2' x 4' | | Non Suspect ACM | 1992 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 1 | Hallway at Rooms 119 to 128 | N/A | Plaster Walls | | NAD | 1700 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 1 | Hallway at Rooms 119 to 128 | N/A | Concrete Block Wall | | Non Suspect ACM | 1700 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 1 | Hallway at Rooms 119 to 128 | N/A | Cement Floor | | Non Suspect ACM | 1992 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 1 | Hallway by Stage | N/A | Ceiling Tile 1' x 1' | | NAD | 1152 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 1 | Hallway by Stage | N/A | Plaster Ceiling | | NAD | 1152 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 1 | Hallway by Stage | N/A | Plaster Walls | | NAD | 750 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 1 | Hallway by Stage | N/A | Concrete Block Wall | | Non Suspect ACM | 750 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 1 | Hallway by Stage | N/A | Terrazzo Floor | | Non Suspect ACM | 1152 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 1 | Stairwell next to Room 110 | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 30 | LF | 0 | LF | | | | N/A | N/A | N/A | |
| 1 | 1 | Stairwell next to Room 110 | N/A | Plaster Ceiling | | NAD | 300 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 1 | Stairwell next to Room 110 | N/A | Plaster Walls | | NAD | 1000 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 1 | Stairwell next to Room 110 | N/A | Cement Floor | | Non Suspect ACM | 300 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 1 | Stairwell at Room 101 | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 32 | LF | 0 | LF | | | | N/A | N/A | N/A | |
| 1 | 1 | Stairwell at Room 101 | N/A | Plaster Ceiling | | NAD | 300 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 1 | Stairwell at Room 101 | N/A | Plaster Walls | | NAD | 1000 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 1 | Stairwell at Room 101 | N/A | Cement Floor | | Non Suspect ACM | 300 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 1 | Stairwell next to Room 128 | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 40 | LF | 0 | LF | | | | N/A | N/A | N/A | |
| 1 | 1 | Stairwell next to Room 128 | N/A | Plaster Ceiling | | NAD | 300 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 1 | Stairwell next to Room 128 | N/A | Plaster Walls | | NAD | 1000 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 1 | Stairwell next to Room 128 | N/A | Cement Floor | | Non Suspect ACM | 300 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 1 | Stairwell next to Room 119 | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 30 | LF | 0 | LF | | | | N/A | N/A | N/A | |
| 1 | 1 | Stairwell next to Room 119 | N/A | Plaster Ceiling | | NAD | 300 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 1 | Stairwell next to Room 119 | N/A | Plaster Walls | | NAD | 1000 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 1 | Stairwell next to Room 119 | N/A | Cement Floor | | Non Suspect ACM | 300 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 1 | Stairwell next to Room 145 | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 30 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 1 | Stairwell next to Room 145 | N/A | Plaster Ceiling | | NAD | 300 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 1 | Stairwell next to Room 145 | N/A | Plaster Walls | | NAD | 1000 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 1 | Stairwell next to Room 145 | N/A | Cement Floor | | Non Suspect ACM | 300 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 1 | Stairwell by Nurse's Suite (Room 137) | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 30 | LF | 0 | LF | | | | N/A | N/A | N/A | |
| 1 | 1 | Stairwell by Nurse's Suite (Room 137) | N/A | Plaster Ceiling | | NAD | 300 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 1 | Stairwell by Nurse's Suite (Room 137) | N/A | Plaster Walls | | NAD | 1000 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 1 | Stairwell by Nurse's Suite (Room 137) | N/A | Cement Floor | | Non Suspect ACM | 300 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 2 | Classroom 202 | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 24 | LF | 0 | LF | | | | N/A | N/A | N/A | |
| 1 | 2 | Classroom 202 | N/A | Fiberglass Ceiling Tile 2' x 4' | | Non Suspect ACM | 864 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 2 | Classroom 202 | N/A | Plaster Walls | | NAD | 1200 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 2 | Classroom 202 | N/A | Wood Floor | | Non Suspect ACM | 864 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 2 | Classroom 202 | M | Blackboard Glue Dots | 6010/01/02/GC/AV/2600 | Assumed | 100 | SF | 0 | SF | | | | 1 | No | 1/D | |
| 1 | 2 | Classroom 203 | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 24 | LF | 0 | LF | | | | N/A | N/A | N/A | |
| 1 | 2 | Classroom 203 | N/A | Fiberglass Ceiling Tile 2' x 4' | | Non Suspect ACM | 1200 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 2 | Classroom 203 | N/A | Plaster Walls | | NAD | 1400 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 2 | Classroom 203 | N/A | Wood Floor | | Non Suspect ACM | 1200 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 2 | Classroom 203 | M | Blackboard Glue Dots | 6010/01/02/GC/AV/2600 | Assumed | 100 | SF | 0 | SF | | | | 1 | No | 1/D | |
| 1 | 2 | Classroom 204 | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 24 | LF | 0 | LF | | | | N/A | N/A | N/A | |
| 1 | 2 | Classroom 204 | N/A | Fiberglass Ceiling Tile 2' x 4' | | Non Suspect ACM | 720 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 2 | Classroom 204 | N/A | Plaster Walls | | NAD | 1100 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 2 | Classroom 204 | N/A | Wood Floor | | Non Suspect ACM | 720 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 2 | Classroom 204 | M | Blackboard Glue Dots | 6010/01/02/GC/AV/2600 | Assumed | 100 | SF | 0 | SF | | | | 1 | No | 1/D | |
| 1 | 2 | Classroom 205 | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 24 | LF | 0 | LF | | | | N/A | N/A | N/A | |
| 1 | 2 | Classroom 205 | N/A | Fiberglass Ceiling Tile 2' x 4' | | Non Suspect ACM | 720 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 2 | Classroom 205 | N/A | Plaster Walls | | NAD | 1100 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 2 | Classroom 205 | N/A | Wood Floor | | Non Suspect ACM | 720 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 2 | Classroom 205 | M | Blackboard Glue Dots | 6010/01/02/GC/AV/2600 | Assumed | 100 | SF | 0 | SF | | | | 1 | No | 1/D | |
| 1 | 2 | Classroom 206 | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 24 | LF | 0 | LF | | | | N/A | N/A | N/A | |
| 1 | 2 | Classroom 206 | N/A | Fiberglass Ceiling Tile 2' x 4' | | Non Suspect ACM | 720 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 2 | Classroom 206 | N/A | Plaster Walls | | NAD | 1100 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 2 | Classroom 206 | N/A | Wood Floor | | Non Suspect ACM | 720 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 2 | Classroom 206 | M | Blackboard Glue Dots | 6010/01/02/GC/AV/2600 | Assumed | 100 | SF | 0 | SF | | | | 1 | No | 1/D | |
| 1 | 2 | Classroom 207 | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 24 | LF | 0 | LF | | | | N/A | N/A | N/A | |
| 1 | 2 | Classroom 207 | N/A | Fiberglass Ceiling Tile 2' x 4' | | Non Suspect ACM | 720 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 2 | Classroom 207 | N/A | Plaster Walls | | NAD | 1100 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 2 | Classroom 207 | N/A | Wood Floor | | Non Suspect ACM | 720 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 2 | Classroom 207 | M | Blackboard Glue Dots | 6010/01/02/GC/AV/2600 | Assumed | 100 | SF | 0 | SF | | | | 1 | No | 1/D | |
| 1 | 2 | Classroom 208 | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 24 | LF | 0 | LF | | | | N/A | N/A | N/A | |

6010 Central HS - 2015 2016 AHERA Three-Year Report.xls

| | | School District of Philadelphia Central High School 1700 W. Olney Avenue, Philadelphia, PA 19141 ULCS# 6010 Year Built: 1939 | AHERA Three-Year Reinspection 2015-2016 Room by Room Location Log Report | | | | | | | | | Reinspection Date: 7/5/2016 Building Inspector: Ananth K. Vinjamuri Number: 374 Management Planner: Mary Anne Lerro Number: 742327 | | | | | |
|---------------------------------|-----------------------|--|---|---------------------------------|-----------------------|--|--------------------|------------|------------------|----------|------------------------|--|------------------------------|-----------------------|--------------------|----------------------|--|
| E l e m e n t | F l o o r | On Site Room Name | System Affected | Material Description | HID# | Confirmed, Assumed, NAD, Non Suspect ACM | Amount of Material | (SF/LF/EA) | Amount of Damage | SF LF EA | Color required for VAT | Comments/Description/Notes | Attic/Crawlsp ace Ranking | Damage Potential (DP) | Newly Friable (NF) | Response Action (RA) | |
| 1 | 2 | Classroom 208 | N/A | Fiberglass Ceiling Tile 2' x 4' | | Non Suspect ACM | 720 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 2 | Classroom 208 | N/A | Plaster Walls | | NAD | 1100 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 2 | Classroom 208 | N/A | Wood Floor | | Non Suspect ACM | 720 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 2 | Classroom 208 | M | Blackboard Glue Dots | 6010/01/02/GC/AV/2600 | Assumed | 100 | SF | 0 | SF | | | | 1 | No | 1/D | |
| 1 | 2 | Classroom 209 | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 24 | LF | 0 | LF | | | | N/A | N/A | N/A | |
| 1 | 2 | Classroom 209 | N/A | Fiberglass Ceiling Tile 2' x 4' | | Non Suspect ACM | 720 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 2 | Classroom 209 | N/A | Plaster Walls | | NAD | 1100 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 2 | Classroom 209 | N/A | Wood Floor | | Non Suspect ACM | 720 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 2 | Classroom 209 | M | Blackboard Glue Dots | 6010/01/02/GC/AV/2600 | Assumed | 100 | SF | 0 | SF | | | | 1 | No | 1/D | |
| 1 | 2 | Office 210 next to Room 208 | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 24 | LF | 0 | LF | | | | N/A | N/A | N/A | |
| 1 | 2 | Office 210 next to Room 208 | N/A | Fiberglass Ceiling Tile 2' x 4' | | Non Suspect ACM | 360 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 2 | Office 210 next to Room 208 | N/A | Plaster Walls | | NAD | 750 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 2 | Office 210 next to Room 208 | N/A | Wood Floor | | Non Suspect ACM | 360 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 2 | Classroom 211 | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 24 | LF | 0 | LF | | | | N/A | N/A | N/A | |
| 1 | 2 | Classroom 211 | N/A | Fiberglass Ceiling Tile 2' x 4' | | Non Suspect ACM | 720 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 2 | Classroom 211 | N/A | Plaster Walls | | NAD | 1100 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 2 | Classroom 211 | N/A | Wood Floor | | Non Suspect ACM | 720 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 2 | Classroom 211 | M | Blackboard Glue Dots | 6010/01/02/GC/AV/2600 | Assumed | 100 | SF | 0 | SF | | | | 1 | No | 1/D | |
| 1 | 2 | Classroom 211 Storage/Office | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 12 | LF | 0 | LF | | | | N/A | N/A | N/A | |
| 1 | 2 | Classroom 211 Storage/Office | N/A | Fiberglass Ceiling Tile 2' x 4' | | Non Suspect ACM | 126 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 2 | Classroom 211 Storage/Office | N/A | Plaster Walls | | NAD | 400 | SF | 70 | SF | | | | N/A | N/A | N/A | |
| 1 | 2 | Classroom 211 Storage/Office | M | Floor Tile VAT 12" x 12" | 6010/01/02/PP | Assumed | 126 | SF | 0 | SF | Tan | | | 1 | No | 1/D | |
| 1 | 2 | Library Balcony | M | Ceiling Tile 2' x 2' | 6010/01/02/GC/AV/1730 | Assumed | 1680 | SF | 0 | SF | | | | 1 | No | 1/D | |
| 1 | 2 | Library Balcony | N/A | Plaster Walls | | NAD | 1400 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 2 | Library Balcony | N/A | Carpet | | Non Suspect ACM | 1680 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 2 | Space (Library) | M | Ceiling Tile 2' x 2' | 6010/01/02/GC/AV/1730 | Assumed | 288 | SF | 0 | SF | | | | 1 | No | 1/D | |
| 1 | 2 | Space (Library) | N/A | Plaster Walls | | NAD | 500 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 2 | Space (Library) | N/A | Carpet | | Non Suspect ACM | 288 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 2 | Library Storage | M | Ceiling Tile 2' x 2' | 6010/01/02/GC/AV/1730 | Assumed | 300 | SF | 0 | SF | | | | 1 | No | 1/D | |
| 1 | 2 | Library Storage | N/A | Plaster Walls | | NAD | 500 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 2 | Library Storage | N/A | Carpet | | Non Suspect ACM | 300 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 2 | Storage across from Library | X | X | | X | X | X | X | X | X | Department Storage - No access | | X | X | X | |
| 1 | 2 | Storage across from Library | X | X | | X | X | X | X | X | X | Department Storage - No access | | X | X | X | |
| 1 | 2 | Auditorium Balcony | N/A | Acoustical Plaster Ceiling | | NAD | 2736 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 2 | Auditorium Balcony | N/A | Acoustical Plaster Walls | | NAD | 2500 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 2 | Auditorium Balcony | N/A | Wood Floor | | Non Suspect ACM | 2736 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 2 | Teacher Lounge at Auditorium Balcony | N/A | Fiberglass Ceiling Tile 2' x 4' | | Non Suspect ACM | 544 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 2 | Teacher Lounge at Auditorium Balcony | N/A | Plaster Walls | | NAD | 1000 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 2 | Teacher Lounge at Auditorium Balcony | N/A | Terrazzo Floor | | Non Suspect ACM | 544 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 2 | Custodial Storage next to Girl's Restroom | N/A | Plaster Ceiling | | NAD | 18 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 2 | Custodial Storage next to Girl's Restroom | N/A | Ceramic Tile Walls | | Non Suspect ACM | 150 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 2 | Custodial Storage next to Girl's Restroom | N/A | Ceramic Tile Floors | | Non Suspect ACM | 18 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 2 | Girl's Restroom across from the Auditorium | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 12 | LF | 0 | LF | | | | N/A | N/A | N/A | |
| 1 | 2 | Girl's Restroom across from the Auditorium | N/A | Plaster Ceiling | | NAD | 748 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 2 | Girl's Restroom across from the Auditorium | N/A | Ceramic Tile Walls | | Non Suspect ACM | 1000 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 2 | Girl's Restroom across from the Auditorium | N/A | Ceramic Tile Floors | | Non Suspect ACM | 748 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 2 | Men's Restroom across from the Auditorium | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 20 | LF | 0 | LF | | | | N/A | N/A | N/A | |
| 1 | 2 | Men's Restroom across from the Auditorium | N/A | Plaster Ceiling | | NAD | 126 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 2 | Men's Restroom across from the Auditorium | N/A | Ceramic Tile Walls | | Non Suspect ACM | 300 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 2 | Men's Restroom across from the Auditorium | N/A | Ceramic Tile Floors | | Non Suspect ACM | 126 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 2 | Men's Teacher Lounge | N/A | Plaster Ceiling | | NAD | 180 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 2 | Men's Teacher Lounge | N/A | Plaster Walls | | NAD | 500 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 2 | Men's Teacher Lounge | M | Floor Tile VAT 12" x 12" | 6010/01/02/PP | Assumed | 180 | SF | 0 | SF | White | | | 1 | No | 1/D | |
| 1 | 2 | Classroom 224 | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 24 | LF | 0 | LF | | | | N/A | N/A | N/A | |
| 1 | 2 | Classroom 224 | N/A | Fiberglass Ceiling Tile 2' x 4' | | Non Suspect ACM | 864 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 2 | Classroom 224 | N/A | Plaster Walls | | NAD | 1300 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 2 | Classroom 224 | M | Floor Tile VAT 12" x 12" | 6010/01/02/PP | Assumed | 864 | SF | 0 | SF | | | | 1 | No | 1/D | |
| 1 | 2 | Classroom 224 | M | Blackboard Glue Dots | 6010/01/02/GC/AV/2600 | Assumed | 100 | SF | 0 | SF | | Inspector please verify color | | 1 | No | 1/D | |
| 1 | 2 | Classroom 225 | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 24 | LF | 0 | LF | | | | N/A | N/A | N/A | |
| 1 | 2 | Classroom 225 | N/A | Fiberglass Ceiling Tile 2' x 4' | | Non Suspect ACM | 840 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 2 | Classroom 225 | N/A | Plaster Walls | | NAD | 1300 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 2 | Classroom 225 | N/A | Wood Floor | | Non Suspect ACM | 840 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 2 | Classroom 225 | M | Blackboard Glue Dots | 6010/01/02/GC/AV/2600 | Assumed | 100 | SF | 0 | SF | | | | 1 | No | 1/D | |
| 1 | 2 | Classroom 226 | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 24 | LF | 0 | LF | | | | N/A | N/A | N/A | |
| 1 | 2 | Classroom 226 | N/A | Fiberglass Ceiling Tile 2' x 4' | | Non Suspect ACM | 696 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 2 | Classroom 226 | N/A | Plaster Walls | | NAD | 1100 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 2 | Classroom 226 | N/A | Wood Floor | | Non Suspect ACM | 696 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 2 | Classroom 226 | M | Blackboard Glue Dots | 6010/01/02/GC/AV/2600 | Assumed | 100 | SF | 0 | SF | | | | 1 | No | 1/D | |
| 1 | 2 | Classroom 227 | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 24 | LF | 0 | LF | | | | N/A | N/A | N/A | |
| 1 | 2 | Classroom 227 | N/A | Fiberglass Ceiling Tile 2' x 4' | | Non Suspect ACM | 720 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 2 | Classroom 227 | N/A | Plaster Walls | | NAD | 1100 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 2 | Classroom 227 | N/A | Wood Floor | | Non Suspect ACM | 720 | SF | 0 | SF | | | | N/A | N/A | N/A | |

6010 Central HS - 2015 2016 AHERA Three-Year Report.xls

| School District of Philadelphia Central High School 1700 W. Olney Avenue, Philadelphia, PA 19141 ULCS# 6010 Year Built: 1939 | | | AHERA Three-Year Reinspection 2015-2016 Room by Room Location Log Report | | | | | | | | | | Reinspection Date: 7/5/2016 Building Inspector: Ananth K. Vinjamuri Number: 374 Management Planner: Mary Anne Lerro Number: 742327 | | | | |
|--|-----------------------|--|---|---------------------------------|-----------------------|--|--------------------|------------|------------------|----------|------------------------|----------------------------|--|-----------------------|--------------------|----------------------|--|
| E l e m e n t | F l o o r | On Site Room Name | System Affected | Material Description | HID# | Confirmed, Assumed, NAD, Non Suspect ACM | Amount of Material | (SF/LF/EA) | Amount of Damage | SF LF EA | Color required for VAT | Comments/Description/Notes | Attic/Crawlsp ace Ranking | Damage Potential (DP) | Newly Friable (NF) | Response Action (RA) | |
| 1 | 2 | Classroom 227 | M | Blackboard Glue Dots | 6010/01/02/GC/AV/2600 | Assumed | 100 | SF | 0 | SF | | | | 1 | No | 1/D | |
| 1 | 2 | Room 228 - Office next to Room 227 | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 24 | LF | 0 | LF | | | | N/A | N/A | N/A | |
| 1 | 2 | Room 228 - Office next to Room 227 | N/A | Fiberglass Ceiling Tile 2' x 4' | | Non Suspect ACM | 336 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 2 | Room 228 - Office next to Room 227 | N/A | Plaster Walls | | NAD | 700 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 2 | Room 228 - Office next to Room 227 | N/A | Wood Floor | | Non Suspect ACM | 336 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 2 | Room 228 - Office next to Room 227 | M | Blackboard Glue Dots | 6010/01/02/GC/AV/2600 | Assumed | 50 | SF | 0 | SF | | | | 1 | No | 1/D | |
| 1 | 2 | Classroom 229 | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 24 | LF | 0 | LF | | | | N/A | N/A | N/A | |
| 1 | 2 | Classroom 229 | N/A | Fiberglass Ceiling Tile 2' x 4' | | Non Suspect ACM | 696 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 2 | Classroom 229 | N/A | Plaster Walls | | NAD | 1100 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 2 | Classroom 229 | N/A | Wood Floor | | Non Suspect ACM | 696 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 2 | Classroom 229 | M | Blackboard Glue Dots | 6010/01/02/GC/AV/2600 | Assumed | 100 | SF | 0 | SF | | | | 1 | No | 1/D | |
| 1 | 2 | Classroom 230 | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 24 | LF | 0 | LF | | | | N/A | N/A | N/A | |
| 1 | 2 | Classroom 230 | N/A | Fiberglass Ceiling Tile 2' x 4' | | Non Suspect ACM | 720 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 2 | Classroom 230 | N/A | Plaster Walls | | NAD | 1100 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 2 | Classroom 230 | N/A | Wood Floor | | Non Suspect ACM | 720 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 2 | Classroom 230 | M | Blackboard Glue Dots | 6010/01/02/GC/AV/2600 | Assumed | 100 | SF | 0 | SF | | | | 1 | No | 1/D | |
| 1 | 2 | Classroom 231 | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 24 | LF | 0 | LF | | | | N/A | N/A | N/A | |
| 1 | 2 | Classroom 231 | N/A | Fiberglass Ceiling Tile 2' x 4' | | Non Suspect ACM | 696 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 2 | Classroom 231 | N/A | Plaster Walls | | NAD | 1100 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 2 | Classroom 231 | N/A | Wood Floor | | Non Suspect ACM | 696 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 2 | Classroom 231 | M | Blackboard Glue Dots | 6010/01/02/GC/AV/2600 | Assumed | 100 | SF | 0 | SF | | | | 1 | No | 1/D | |
| 1 | 2 | Classroom 232 | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 24 | LF | 0 | LF | | | | N/A | N/A | N/A | |
| 1 | 2 | Classroom 232 | N/A | Fiberglass Ceiling Tile 2' x 4' | | Non Suspect ACM | 720 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 2 | Classroom 232 | N/A | Plaster Walls | | NAD | 1100 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 2 | Classroom 232 | N/A | Wood Floor | | Non Suspect ACM | 720 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 2 | Classroom 232 | M | Blackboard Glue Dots | 6010/01/02/GC/AV/2600 | Assumed | 100 | SF | 0 | SF | | | | 1 | No | 1/D | |
| 1 | 2 | Classroom 233 | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 24 | LF | 0 | LF | | | | N/A | N/A | N/A | |
| 1 | 2 | Classroom 233 | N/A | Fiberglass Ceiling Tile 2' x 4' | | Non Suspect ACM | 672 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 2 | Classroom 233 | N/A | Plaster Walls | | NAD | 1000 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 2 | Classroom 233 | M | Floor Tile VAT 12" x 12" | 6010/01/02/PP | Assumed | 672 | SF | 0 | SF | Tan | | | 1 | No | 1/D | |
| 1 | 2 | Classroom 233 | M | Blackboard Glue Dots | 6010/01/02/GC/AV/2600 | Assumed | 100 | SF | 0 | SF | | | | 1 | No | 1/D | |
| 1 | 2 | Storage across from the Auditorium | N/A | Plaster Ceiling | | NAD | 168 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 2 | Storage across from the Auditorium | N/A | Plaster Walls | | NAD | 550 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 2 | Storage across from the Auditorium | N/A | Cement Floor | | Non Suspect ACM | 168 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 2 | Office across from the Auditorium | N/A | Fiberglass Ceiling Tile 2' x 4' | | Non Suspect ACM | 330 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 2 | Office across from the Auditorium | N/A | Plaster Walls | | NAD | 700 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 2 | Office across from the Auditorium | M | Floor Tile VAT 12" x 12" | 6010/01/02/PP | Assumed | 330 | SF | 0 | SF | Grey | | | 1 | No | 1/D | |
| 1 | 2 | Custodial Storage across from the Auditorium | N/A | Plaster Ceiling | | NAD | 24 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 2 | Custodial Storage across from the Auditorium | N/A | Ceramic Tile Walls | | Non Suspect ACM | 200 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 2 | Custodial Storage across from the Auditorium | N/A | Ceramic Tile Floors | | Non Suspect ACM | 24 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 2 | Boy's Restroom across from the Auditorium | N/A | Plaster Ceiling | | NAD | 850 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 2 | Boy's Restroom across from the Auditorium | N/A | Ceramic Tile Walls | | Non Suspect ACM | 1350 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 2 | Boy's Restroom across from the Auditorium | N/A | Ceramic Tile Floors | | Non Suspect ACM | 850 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 2 | Weight Room | N/A | Plaster Ceiling | | NAD | 1548 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 2 | Weight Room | N/A | Concrete Block Wall | | Non Suspect ACM | 2000 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 2 | Weight Room | N/A | Wood Floor | | Non Suspect ACM | 1548 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 2 | Storage next to Weight Room | N/A | Plaster Ceiling | | NAD | 126 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 2 | Storage next to Weight Room | N/A | Concrete Block Wall | | Non Suspect ACM | 400 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 2 | Storage next to Weight Room | N/A | Wood Floor | | Non Suspect ACM | 126 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 2 | Storage next to Weight Room | N/A | Plaster Ceiling | | NAD | 126 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 2 | Storage next to Weight Room | N/A | Concrete Block Wall | | Non Suspect ACM | 400 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 2 | Storage next to Weight Room | N/A | Wood Floor | | Non Suspect ACM | 126 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 2 | Storage next to Boy's Restroom | N/A | Plaster Ceiling | | NAD | 24 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 2 | Storage next to Boy's Restroom | N/A | Concrete Block Wall | | Non Suspect ACM | 200 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 2 | Storage next to Boy's Restroom | N/A | Wood Floor | | Non Suspect ACM | 24 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 2 | Storage next to stairwell | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 16 | LF | 0 | LF | | | | N/A | N/A | N/A | |
| 1 | 2 | Storage next to stairwell | N/A | Plaster Ceiling | | NAD | 228 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 2 | Storage next to stairwell | N/A | Plaster Walls | | NAD | 600 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 2 | Storage next to stairwell | M | Linoleum | 6010/01/02/KK | Assumed | 228 | SF | 0 | SF | | | | 1 | No | 1/D | |
| 1 | 2 | Storage next to Teacher Lounge | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 8 | LF | 0 | LF | | | | N/A | N/A | N/A | |
| 1 | 2 | Storage next to Teacher Lounge | N/A | Plaster Ceiling | | NAD | 144 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 2 | Storage next to Teacher Lounge | N/A | Plaster Walls | | NAD | 400 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 2 | Storage next to Teacher Lounge | N/A | Terrazzo Floor | | Non Suspect ACM | 144 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 2 | Storage 2-F | N/A | Plaster Ceiling | | NAD | 168 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 2 | Storage 2-F | N/A | Plaster Walls | | NAD | 500 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 2 | Storage 2-F | N/A | Cement Floor | | Non Suspect ACM | 168 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 2 | Room 241-Teacher Lounge | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 20 | LF | 0 | LF | | | | N/A | N/A | N/A | |
| 1 | 2 | Room 241-Teacher Lounge | N/A | Plaster Ceiling | | NAD | 228 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 2 | Room 241-Teacher Lounge | N/A | Plaster Walls | | NAD | 600 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 2 | Room 241-Teacher Lounge | M | Linoleum | 6010/01/02/KK | Assumed | 228 | SF | 0 | SF | | | | 1 | No | 1/D | |
| 1 | 2 | TeacherLounge Storage | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 5 | LF | 0 | LF | | | | N/A | N/A | N/A | |
| 1 | 2 | TeacherLounge Storage | N/A | Plaster Ceiling | | NAD | 72 | SF | 0 | SF | | | | N/A | N/A | N/A | |

6010 Central HS - 2015 2016 AHERA Three-Year Report.xls

| School District of Philadelphia Central High School 1700 W. Olney Avenue, Philadelphia, PA 19141 ULCS# 6010 Year Built: 1939 | | AHERA Three-Year Reinspection 2015-2016 Room by Room Location Log Report | | | | | | | | | | Reinspection Date: 7/5/2016 Building Inspector: Ananth K. Vinjamuri Number: 374 Management Planner: Mary Anne Lerro Number: 742327 | | | | |
|--|-----------------------|---|-----------------|---------------------------------|-----------------------|--|--------------------|------------|------------------|----------|------------------------|--|------------------------------|-----------------------|--------------------|----------------------|
| E l e m e n t | F l o o r | On Site Room Name | System Affected | Material Description | HID# | Confirmed, Assumed, NAD, Non Suspect ACM | Amount of Material | (SF/LF/EA) | Amount of Damage | SF LF EA | Color required for VAT | Comments/Description/Notes | Attic/Crawlsp ace Ranking | Damage Potential (DP) | Newly Friable (NF) | Response Action (RA) |
| 1 | 2 | TeacherLounge Storage | N/A | Plaster Walls | | NAD | 300 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 2 | TeacherLounge Storage | M | Linoleum | 6010/01/02/KK | Assumed | 72 | SF | 0 | SF | | | | 1 | No | 1/D |
| 1 | 2 | Room 242-Storage outside Room 243 | N/A | Plaster Ceiling | | NAD | 120 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 2 | Room 242-Storage outside Room 243 | N/A | Plaster Walls | | NAD | 400 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 2 | Room 242-Storage outside Room 243 | N/A | Cement Floor | | Non Suspect ACM | 120 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 2 | Room 243-Office near Teacher Lounge | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 5 | LF | 0 | LF | | | | N/A | N/A | N/A |
| 1 | 2 | Room 243-Office near Teacher Lounge | N/A | Ceiling Tile 2' x 4' | | NAD | 350 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 2 | Room 243-Office near Teacher Lounge | N/A | Plaster Walls | | NAD | 750 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 2 | Room 243-Office near Teacher Lounge | M | Linoleum | 6010/01/02/KK | Assumed | 350 | SF | 0 | SF | | | | 1 | No | 1/D |
| 1 | 2 | Room 243 Storage | N/A | Plaster Ceiling | | NAD | 72 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 2 | Room 243 Storage | N/A | Plaster Walls | | NAD | 300 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 2 | Room 243 Storage | M | Linoleum | 6010/01/02/KK | Assumed | 72 | SF | 0 | SF | | | | 1 | No | 1/D |
| 1 | 2 | Classroom 244 | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 24 | LF | 0 | LF | | | | N/A | N/A | N/A |
| 1 | 2 | Classroom 244 | N/A | Fiberglass Ceiling Tile 2' x 4' | | Non Suspect ACM | 864 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 2 | Classroom 244 | N/A | Plaster Walls | | NAD | 1300 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 2 | Classroom 244 | N/A | Wood Floor | | Non Suspect ACM | 864 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 2 | Classroom 244 | M | Blackboard Glue Dots | 6010/01/02/GC/AV/2600 | Assumed | 200 | SF | 0 | SF | | | | 1 | No | 1/D |
| 1 | 2 | Classroom 245 | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 24 | LF | 0 | LF | | | | N/A | N/A | N/A |
| 1 | 2 | Classroom 245 | N/A | Fiberglass Ceiling Tile 2' x 4' | | Non Suspect ACM | 864 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 2 | Classroom 245 | N/A | Plaster Walls | | NAD | 1300 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 2 | Classroom 245 | N/A | Wood Floor | | Non Suspect ACM | 864 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 2 | Classroom 245 | M | Blackboard Glue Dots | 6010/01/02/GC/AV/2600 | Assumed | 200 | SF | 0 | SF | | | | 1 | No | 1/D |
| 1 | 2 | Classroom 246 | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 24 | LF | 0 | LF | | | | N/A | N/A | N/A |
| 1 | 2 | Classroom 246 | N/A | Fiberglass Ceiling Tile 2' x 4' | | Non Suspect ACM | 720 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 2 | Classroom 246 | N/A | Plaster Walls | | NAD | 1100 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 2 | Classroom 246 | N/A | Wood Floor | | Non Suspect ACM | 720 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 2 | Classroom 246 | M | Blackboard Glue Dots | 6010/01/02/GC/AV/2600 | Assumed | 200 | SF | 0 | SF | | | | 1 | No | 1/D |
| 1 | 2 | Classroom 247 | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 24 | LF | 0 | LF | | | | N/A | N/A | N/A |
| 1 | 2 | Classroom 247 | N/A | Fiberglass Ceiling Tile 2' x 4' | | Non Suspect ACM | 720 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 2 | Classroom 247 | N/A | Plaster Walls | | NAD | 1100 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 2 | Classroom 247 | N/A | Wood Floor | | Non Suspect ACM | 720 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 2 | Classroom 247 | M | Blackboard Glue Dots | 6010/01/02/GC/AV/2600 | Assumed | 200 | SF | 0 | SF | | | | 1 | No | 1/D |
| 1 | 2 | Classroom 248 | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 24 | LF | 0 | LF | | | | N/A | N/A | N/A |
| 1 | 2 | Classroom 248 | N/A | Fiberglass Ceiling Tile 2' x 4' | | Non Suspect ACM | 720 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 2 | Classroom 248 | N/A | Plaster Walls | | NAD | 1100 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 2 | Classroom 248 | N/A | Wood Floor | | Non Suspect ACM | 720 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 2 | Classroom 248 | M | Blackboard Glue Dots | 6010/01/02/GC/AV/2600 | Assumed | 200 | SF | 0 | SF | | | | 1 | No | 1/D |
| 1 | 2 | Classroom 249 | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 24 | LF | 0 | LF | | | | N/A | N/A | N/A |
| 1 | 2 | Classroom 249 | N/A | Fiberglass Ceiling Tile 2' x 4' | | Non Suspect ACM | 720 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 2 | Classroom 249 | N/A | Plaster Walls | | NAD | 1100 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 2 | Classroom 249 | N/A | Wood Floor | | Non Suspect ACM | 720 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 2 | Classroom 249 | M | Blackboard Glue Dots | 6010/01/02/GC/AV/2600 | Assumed | 200 | SF | 0 | SF | | | | 1 | No | 1/D |
| 1 | 2 | Classroom 250 | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 24 | LF | 0 | LF | | | | N/A | N/A | N/A |
| 1 | 2 | Classroom 250 | N/A | Fiberglass Ceiling Tile 2' x 4' | | Non Suspect ACM | 720 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 2 | Classroom 250 | N/A | Plaster Walls | | NAD | 1100 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 2 | Classroom 250 | N/A | Wood Floor | | Non Suspect ACM | 720 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 2 | Classroom 250 | M | Blackboard Glue Dots | 6010/01/02/GC/AV/2600 | Assumed | 200 | SF | 0 | SF | | | | 1 | No | 1/D |
| 1 | 2 | Classroom 251 | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 24 | LF | 0 | LF | | | | N/A | N/A | N/A |
| 1 | 2 | Classroom 251 | N/A | Fiberglass Ceiling Tile 2' x 4' | | Non Suspect ACM | 720 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 2 | Classroom 251 | N/A | Plaster Walls | | NAD | 1100 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 2 | Classroom 251 | N/A | Wood Floor | | Non Suspect ACM | 720 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 2 | Classroom 251 | M | Blackboard Glue Dots | 6010/01/02/GC/AV/2600 | Assumed | 200 | SF | 0 | SF | | | | 1 | No | 1/D |
| 1 | 2 | Classroom 252 | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 24 | LF | 0 | LF | | | | N/A | N/A | N/A |
| 1 | 2 | Classroom 252 | N/A | Fiberglass Ceiling Tile 2' x 4' | | Non Suspect ACM | 720 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 2 | Classroom 252 | N/A | Plaster Walls | | NAD | 1100 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 2 | Classroom 252 | N/A | Wood Floor | | Non Suspect ACM | 720 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 2 | Classroom 252 | M | Blackboard Glue Dots | 6010/01/02/GC/AV/2600 | Assumed | 200 | SF | 0 | SF | | | | 1 | No | 1/D |
| 1 | 2 | Classroom 253 | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 24 | LF | 0 | LF | | | | N/A | N/A | N/A |
| 1 | 2 | Classroom 253 | N/A | Fiberglass Ceiling Tile 2' x 4' | | Non Suspect ACM | 336 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 2 | Classroom 253 | N/A | Plaster Walls | | NAD | 700 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 2 | Classroom 253 | N/A | Wood Floor | | Non Suspect ACM | 336 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 2 | Classroom 253 | M | Blackboard Glue Dots | 6010/01/02/GC/AV/2600 | Assumed | 100 | SF | 0 | SF | | | | 1 | No | 1/D |
| 1 | 2 | Room 254 - Office | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 24 | LF | 0 | LF | | | | N/A | N/A | N/A |
| 1 | 2 | Room 254 - Office | N/A | Fiberglass Ceiling Tile 2' x 4' | | Non Suspect ACM | 507 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 2 | Room 254 - Office | N/A | Plaster Walls | | NAD | 1000 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 2 | Room 254 - Office | N/A | Floor Tile VAT 12" x 12" | 6010/01/02/PP | Assumed | 507 | SF | 0 | SF | Blue | | | N/A | N/A | N/A |
| 1 | 2 | Hallway at Rooms 244 to 254 | N/A | Fiberglass Ceiling Tile 2' x 4' | | Non Suspect ACM | 1617 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 2 | Hallway at Rooms 244 to 254 | N/A | Plaster Walls | | NAD | 1500 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 2 | Hallway at Rooms 244 to 254 | N/A | Concrete Block Wall | | Non Suspect ACM | 1500 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 2 | Hallway at Rooms 244 to 254 | N/A | Cement Floor | | Non Suspect ACM | 1617 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 2 | Hallway at Rooms 202 to 211 | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 20 | LF | 0 | LF | | | | N/A | N/A | N/A |
| 1 | 2 | Hallway at Rooms 202 to 211 | N/A | Fiberglass Ceiling Tile 2' x 4' | | Non Suspect ACM | 1764 | SF | 0 | SF | | | | N/A | N/A | N/A |

6010 Central HS - 2015 2016 AHERA Three-Year Report.xls

| E l e m e n t | | F l o o r | | School District of Philadelphia Central High School 1700 W. Olney Avenue, Philadelphia, PA 19141 ULCS# 6010 Year Built: 1939 | | AHERA Three-Year Reinspection 2015-2016 Room by Room Location Log Report | | | | | | | | | | Reinspection Date: 7/5/2016 Building Inspector: Ananth K. Vinjamuri Number: 374 Management Planner: Mary Anne Lerro Number: 742327 | | | | |
|---------------------------------|---|--|----------------------|--|--|---|------------|------------------|----------|------------------------|----------------------------|---------------------------|-----------------------|--------------------|----------------------|--|--|--|--|--|
| | | | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | | | |
| On Site Room Name | | System Affected | Material Description | HID# | Confirmed, Assumed, NAD, Non Suspect ACM | Amount of Material | (SF/LF/EA) | Amount of Damage | SF LF EA | Color required for VAT | Comments/Description/Notes | Attic/Crawl space Ranking | Damage Potential (DP) | Newly Friable (NF) | Response Action (RA) | | | | | |
| 1 | 2 | Hallway at Rooms 202 to 211 | N/A | Plaster Walls | | NAD | 1500 | SF | 0 | SF | | | N/A | N/A | N/A | | | | | |
| 1 | 2 | Hallway at Rooms 202 to 211 | N/A | Concrete Block Wall | | Non Suspect ACM | 1500 | SF | 0 | SF | | | N/A | N/A | N/A | | | | | |
| 1 | 2 | Hallway at Rooms 202 to 211 | N/A | Cement Floor | | Non Suspect ACM | 1764 | SF | 0 | SF | | | N/A | N/A | N/A | | | | | |
| 1 | 2 | Main Hallway | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 40 | LF | 0 | LF | | | N/A | N/A | N/A | | | | | |
| 1 | 2 | Main Hallway | N/A | Plaster Ceiling | | NAD | 4088 | SF | 0 | SF | | | N/A | N/A | N/A | | | | | |
| 1 | 2 | Main Hallway | N/A | Plaster Walls | | NAD | 3000 | SF | 0 | SF | | | N/A | N/A | N/A | | | | | |
| 1 | 2 | Main Hallway | N/A | Concrete Block Wall | | Non Suspect ACM | 3000 | SF | 0 | SF | | | N/A | N/A | N/A | | | | | |
| 1 | 2 | Main Hallway | N/A | Terrazzo Floor | | Non Suspect ACM | 4088 | SF | 0 | SF | | | N/A | N/A | N/A | | | | | |
| 1 | 2 | Hallway between Library and Auditorium | N/A | Fiberglass Ceiling Tile 2' x 4' | | Non Suspect ACM | 864 | SF | 0 | SF | | | N/A | N/A | N/A | | | | | |
| 1 | 2 | Hallway between Library and Auditorium | N/A | Plaster Walls | | NAD | 600 | SF | 0 | SF | | | N/A | N/A | N/A | | | | | |
| 1 | 2 | Hallway between Library and Auditorium | N/A | Concrete Block Wall | | Non Suspect ACM | 600 | SF | 0 | SF | | | N/A | N/A | N/A | | | | | |
| 1 | 2 | Hallway between Library and Auditorium | N/A | Cement Floor | | Non Suspect ACM | 864 | SF | 0 | SF | | | N/A | N/A | N/A | | | | | |
| 1 | 2 | Hallway at Rooms 224 to 233 | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 30 | SF | 0 | SF | | | N/A | N/A | N/A | | | | | |
| 1 | 2 | Hallway at Rooms 224 to 233 | N/A | Fiberglass Ceiling Tile 2' x 4' | | Non Suspect ACM | 2016 | SF | 0 | SF | | | N/A | N/A | N/A | | | | | |
| 1 | 2 | Hallway at Rooms 224 to 233 | N/A | Plaster Walls | | NAD | 1200 | SF | 0 | SF | | | N/A | N/A | N/A | | | | | |
| 1 | 2 | Hallway at Rooms 224 to 233 | N/A | Concrete Block Wall | | Non Suspect ACM | 1200 | SF | 0 | SF | | | N/A | N/A | N/A | | | | | |
| 1 | 2 | Hallway at Rooms 224 to 233 | N/A | Cement Floor | | Non Suspect ACM | 2016 | SF | 0 | SF | | | N/A | N/A | N/A | | | | | |
| 1 | 2 | Stairwell next to Room 210 | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 30 | LF | 0 | LF | | | N/A | N/A | N/A | | | | | |
| 1 | 2 | Stairwell next to Room 210 | N/A | Plaster Ceiling | | NAD | 300 | SF | 0 | SF | | | N/A | N/A | N/A | | | | | |
| 1 | 2 | Stairwell next to Room 210 | N/A | Plaster Walls | | NAD | 1000 | SF | 0 | SF | | | N/A | N/A | N/A | | | | | |
| 1 | 2 | Stairwell next to Room 210 | N/A | Cement Floor | | Non Suspect ACM | 300 | SF | 0 | SF | | | N/A | N/A | N/A | | | | | |
| 1 | 2 | Stairwell at Room 203 | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 32 | LF | 0 | LF | | | N/A | N/A | N/A | | | | | |
| 1 | 2 | Stairwell at Room 203 | N/A | Plaster Ceiling | | NAD | 300 | SF | 0 | SF | | | N/A | N/A | N/A | | | | | |
| 1 | 2 | Stairwell at Room 203 | N/A | Plaster Walls | | NAD | 1000 | SF | 0 | SF | | | N/A | N/A | N/A | | | | | |
| 1 | 2 | Stairwell at Room 203 | N/A | Cement Floor | | Non Suspect ACM | 300 | SF | 0 | SF | | | N/A | N/A | N/A | | | | | |
| 1 | 2 | Stairwell next to Room 232 | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 40 | LF | 0 | LF | | | N/A | N/A | N/A | | | | | |
| 1 | 2 | Stairwell next to Room 232 | N/A | Plaster Ceiling | | NAD | 300 | SF | 0 | SF | | | N/A | N/A | N/A | | | | | |
| 1 | 2 | Stairwell next to Room 232 | N/A | Plaster Walls | | NAD | 1000 | SF | 0 | SF | | | N/A | N/A | N/A | | | | | |
| 1 | 2 | Stairwell next to Room 232 | N/A | Cement Floor | | Non Suspect ACM | 300 | SF | 0 | SF | | | N/A | N/A | N/A | | | | | |
| 1 | 2 | Stairwell next to Room 225 | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 30 | LF | 0 | LF | | | N/A | N/A | N/A | | | | | |
| 1 | 2 | Stairwell next to Room 225 | N/A | Plaster Ceiling | | NAD | 300 | SF | 0 | SF | | | N/A | N/A | N/A | | | | | |
| 1 | 2 | Stairwell next to Room 225 | N/A | Plaster Walls | | NAD | 1000 | SF | 0 | SF | | | N/A | N/A | N/A | | | | | |
| 1 | 2 | Stairwell next to Room 225 | N/A | Cement Floor | | Non Suspect ACM | 300 | SF | 0 | SF | | | N/A | N/A | N/A | | | | | |
| 1 | 2 | Stairwell by Room 245 | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 40 | LF | 0 | LF | | | N/A | N/A | N/A | | | | | |
| 1 | 2 | Stairwell by Room 245 | N/A | Plaster Ceiling | | NAD | 300 | SF | 0 | SF | | | N/A | N/A | N/A | | | | | |
| 1 | 2 | Stairwell by Room 245 | N/A | Plaster Walls | | NAD | 1000 | SF | 0 | SF | | | N/A | N/A | N/A | | | | | |
| 1 | 2 | Stairwell by Room 245 | N/A | Cement Floor | | Non Suspect ACM | 300 | SF | 0 | SF | | | N/A | N/A | N/A | | | | | |
| 1 | 3 | Classroom 301 | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 24 | LF | 0 | LF | | | N/A | N/A | N/A | | | | | |
| 1 | 3 | Classroom 301 | N/A | Fiberglass Ceiling Tile 2' x 4' | | Non Suspect ACM | 1200 | SF | 0 | SF | | | N/A | N/A | N/A | | | | | |
| 1 | 3 | Classroom 301 | N/A | Plaster Walls | | NAD | 1400 | SF | 0 | SF | | | N/A | N/A | N/A | | | | | |
| 1 | 3 | Classroom 301 | M | Floor Tile VAT 12" x 12" | 6010/01/03/RR | Assumed | 1200 | SF | 0 | SF | Tan | | 1 | No | 1/D | | | | | |
| 1 | 3 | Classroom 301 | M | Blackboard Glue Dots | 6010/01/03/GC/AV/2600 | Assumed | 200 | SF | 0 | SF | | | 1 | No | 1/D | | | | | |
| 1 | 3 | Classroom 301 | M | Transite | 6010/01/03/VV | Assumed | 40 | SF | 0 | SF | | Lab Hoods | 1 | No | 1/D | | | | | |
| 1 | 3 | Classroom 302 | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 24 | LF | 0 | LF | | | N/A | N/A | N/A | | | | | |
| 1 | 3 | Classroom 302 | N/A | Fiberglass Ceiling Tile 2' x 4' | | Non Suspect ACM | 1248 | SF | 0 | SF | | | N/A | N/A | N/A | | | | | |
| 1 | 3 | Classroom 302 | N/A | Plaster Walls | | NAD | 1400 | SF | 0 | SF | | | N/A | N/A | N/A | | | | | |
| 1 | 3 | Classroom 302 | M | Floor Tile VAT 12" x 12" | 6010/01/03/RR | Assumed | 1248 | SF | 0 | SF | Tan | | 1 | No | 1/D | | | | | |
| 1 | 3 | Classroom 302 | M | Blackboard Glue Dots | 6010/01/03/GC/AV/2600 | Assumed | 200 | SF | 0 | SF | | | 1 | No | 1/D | | | | | |
| 1 | 3 | Classroom 302 | M | Transite | 6010/01/03/VV | Assumed | 40 | SF | 0 | SF | | Lab Hoods | 1 | No | 1/D | | | | | |
| 1 | 3 | Room 303 Lab Prep Room | N/A | Fiberglass Ceiling Tile 2' x 4' | | Non Suspect ACM | 408 | SF | 0 | SF | | | N/A | N/A | N/A | | | | | |
| 1 | 3 | Room 303 Lab Prep Room | N/A | Plaster Walls | | NAD | 750 | SF | 0 | SF | | | N/A | N/A | N/A | | | | | |
| 1 | 3 | Room 303 Lab Prep Room | M | Floor Tile VAT 12" x 12" | 6010/01/03/RR | Assumed | 408 | SF | 0 | SF | Tan | | 1 | No | 1/D | | | | | |
| 1 | 3 | Classroom 304 | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 24 | LF | 0 | LF | | | N/A | N/A | N/A | | | | | |
| 1 | 3 | Classroom 304 | N/A | Fiberglass Ceiling Tile 2' x 4' | | Non Suspect ACM | 720 | SF | 0 | SF | | | N/A | N/A | N/A | | | | | |
| 1 | 3 | Classroom 304 | N/A | Plaster Walls | | NAD | 1100 | SF | 24 | SF | | | N/A | N/A | N/A | | | | | |
| 1 | 3 | Classroom 304 | N/A | Wood Floor | | Non Suspect ACM | 720 | SF | 0 | SF | | | N/A | N/A | N/A | | | | | |
| 1 | 3 | Classroom 304 | M | Blackboard Glue Dots | 6010/01/03/GC/AV/2600 | Assumed | 200 | SF | 0 | SF | | | 1 | No | 1/D | | | | | |
| 1 | 3 | Classroom 305 | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 24 | LF | 0 | LF | | | N/A | N/A | N/A | | | | | |
| 1 | 3 | Classroom 305 | N/A | Fiberglass Ceiling Tile 2' x 4' | | Non Suspect ACM | 720 | SF | 0 | SF | | | N/A | N/A | N/A | | | | | |
| 1 | 3 | Classroom 305 | N/A | Plaster Walls | | NAD | 1100 | SF | 24 | SF | | | N/A | N/A | N/A | | | | | |
| 1 | 3 | Classroom 305 | N/A | Wood Floor | | Non Suspect ACM | 720 | SF | 0 | SF | | | N/A | N/A | N/A | | | | | |
| 1 | 3 | Classroom 305 | M | Blackboard Glue Dots | 6010/01/03/GC/AV/2600 | Assumed | 200 | SF | 0 | SF | | | 1 | No | 1/D | | | | | |
| 1 | 3 | Classroom 306 | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 24 | LF | 0 | LF | | | N/A | N/A | N/A | | | | | |
| 1 | 3 | Classroom 306 | N/A | Fiberglass Ceiling Tile 2' x 4' | | Non Suspect ACM | 720 | SF | 0 | SF | | | N/A | N/A | N/A | | | | | |
| 1 | 3 | Classroom 306 | N/A | Plaster Walls | | NAD | 1100 | SF | 24 | SF | | | N/A | N/A | N/A | | | | | |
| 1 | 3 | Classroom 306 | N/A | Wood Floor | | Non Suspect ACM | 720 | SF | 0 | SF | | | N/A | N/A | N/A | | | | | |
| 1 | 3 | Classroom 306 | M | Blackboard Glue Dots | 6010/01/03/GC/AV/2600 | Assumed | 200 | SF | 0 | SF | | | 1 | No | 1/D | | | | | |
| 1 | 3 | Classroom 307 | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 24 | LF | 0 | LF | | | N/A | N/A | N/A | | | | | |

6010 Central HS - 2015 2016 AHERA Three-Year Report.xls

| School District of Philadelphia Central High School 1700 W. Olney Avenue, Philadelphia, PA 19141 ULCS# 6010 Year Built: 1939 | | AHERA Three-Year Reinspection 2015-2016 Room by Room Location Log Report | | | | | | | | | | Reinspection Date: 7/5/2016 Building Inspector: Ananth K. Vinjamuri Number: 374 Management Planner: Mary Anne Lerro Number: 742327 | | | | |
|--|-----------------------|---|-----------------|---------------------------------|-----------------------|--|--------------------|------------|------------------|----------|------------------------|--|------------------------------|-----------------------|--------------------|----------------------|
| E l e m e n t | F l o o r | On Site Room Name | System Affected | Material Description | HID# | Confirmed, Assumed, NAD, Non Suspect ACM | Amount of Material | (SF/LF/EA) | Amount of Damage | SF LF EA | Color required for VAT | Comments/Description/Notes | Attic/Crawlsp ace Ranking | Damage Potential (DP) | Newly Friable (NF) | Response Action (RA) |
| 1 | 3 | Classroom 307 | N/A | Fiberglass Ceiling Tile 2' x 4' | | Non Suspect ACM | 720 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 3 | Classroom 307 | N/A | Plaster Walls | | NAD | 1100 | SF | 24 | SF | | | | N/A | N/A | N/A |
| 1 | 3 | Classroom 307 | N/A | Wood Floor | | Non Suspect ACM | 720 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 3 | Classroom 307 | M | Blackboard Glue Dots | 6010/01/03/GC/AV/2600 | Assumed | 200 | SF | 0 | SF | | | | 1 | No | 1/D |
| 1 | 3 | Classroom 308 | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 24 | LF | 0 | LF | | | | N/A | N/A | N/A |
| 1 | 3 | Classroom 308 | N/A | Fiberglass Ceiling Tile 2' x 4' | | Non Suspect ACM | 720 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 3 | Classroom 308 | N/A | Plaster Walls | | NAD | 1100 | SF | 24 | SF | | | | N/A | N/A | N/A |
| 1 | 3 | Classroom 308 | N/A | Wood Floor | | Non Suspect ACM | 720 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 3 | Classroom 308 | M | Blackboard Glue Dots | 6010/01/03/GC/AV/2600 | Assumed | 200 | SF | 0 | SF | | | | 1 | No | 1/D |
| 1 | 3 | Classroom 309 | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 24 | LF | 0 | LF | | | | N/A | N/A | N/A |
| 1 | 3 | Classroom 309 | N/A | Fiberglass Ceiling Tile 2' x 4' | | Non Suspect ACM | 720 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 3 | Classroom 309 | N/A | Plaster Walls | | NAD | 1100 | SF | 24 | SF | | | | N/A | N/A | N/A |
| 1 | 3 | Classroom 309 | N/A | Wood Floor | | Non Suspect ACM | 720 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 3 | Classroom 309 | M | Blackboard Glue Dots | 6010/01/03/GC/AV/2600 | Assumed | 200 | SF | 0 | SF | | | | 1 | No | 1/D |
| 1 | 3 | Storage 3-B next to Women's Restroom | X | X | | X | X | X | X | X | X | Department Storage Room - No access | | X | X | X |
| 1 | 3 | Women's Restroom | N/A | Plaster Ceiling | | NAD | 180 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 3 | Women's Restroom | N/A | Ceramic Tile Walls | | Non Suspect ACM | 500 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 3 | Women's Restroom | N/A | Ceramic Tile Floors | | Non Suspect ACM | 180 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 3 | Computer Class Room 311 | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 12 | LF | 0 | LF | | | | N/A | N/A | N/A |
| 1 | 3 | Computer Class Room 311 | N/A | Fiberglass Ceiling Tile 2' x 4' | | Non Suspect ACM | 864 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 3 | Computer Class Room 311 | N/A | Plaster Walls | | NAD | 1300 | SF | 24 | SF | | | | N/A | N/A | N/A |
| 1 | 3 | Computer Class Room 311 | M | Floor Tile VAT 12" x 12" | 6010/01/03/RR | Assumed | 864 | SF | 5 | SF | Tan | Inspector, please fill out damage conditions | | 1 | 1 | 1/C |
| 1 | 3 | Computer Class Room 311 | M | Blackboard Glue Dots | 6010/01/03/GC/AV/2600 | Assumed | 200 | SF | 0 | SF | | | | 1 | No | 1/D |
| 1 | 3 | Room 313 Office next to Room 311 | N/A | Fiberglass Ceiling Tile 2' x 4' | | Non Suspect ACM | 160 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 3 | Room 313 Office next to Room 311 | N/A | Plaster Walls | | NAD | 500 | SF | 24 | SF | | | | N/A | N/A | N/A |
| 1 | 3 | Room 313 Office next to Room 311 | N/A | Wood Floor | | Non Suspect ACM | 160 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 3 | Room 315 Office next to Office Room 313 | N/A | Fiberglass Ceiling Tile 2' x 4' | | Non Suspect ACM | 160 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 3 | Room 315 Office next to Office Room 313 | N/A | Plaster Walls | | NAD | 500 | SF | 24 | SF | | | | N/A | N/A | N/A |
| 1 | 3 | Room 315 Office next to Office Room 313 | N/A | Wood Floor | | Non Suspect ACM | 160 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 3 | Storage next to Room 315 | N/A | Plaster Ceiling | | NAD | 300 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 3 | Storage next to Room 315 | N/A | Plaster Walls | | NAD | 500 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 3 | Storage next to Room 315 | N/A | Cement Floor | | Non Suspect ACM | 300 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 3 | Mechanical Room next to Room 317A | N/A | Concrete Ceiling | | Non Suspect ACM | 440 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 3 | Mechanical Room next to Room 317A | N/A | Concrete Block Wall | | Non Suspect ACM | 800 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 3 | Mechanical Room next to Room 317A | N/A | Cement Floor | | Non Suspect ACM | 440 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 3 | Mechanical Room next to Room 317A | T | Vibration Damper Cloth | 6010/01/03/60 | Assumed | 16 | SF | 0 | SF | | | | 1 | No | 1/D |
| 1 | 3 | Book Storage across from Boy's Restroom | N/A | Plaster Ceiling | | NAD | 230 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 3 | Book Storage across from Boy's Restroom | N/A | Concrete Block Wall | | Non Suspect ACM | 400 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 3 | Book Storage across from Boy's Restroom | N/A | Cement Floor | | Non Suspect ACM | 230 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 3 | Mechanical Room at the end of the Hallway across from Boy's Restroom | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 40 | LF | 0 | LF | | | | N/A | N/A | N/A |
| 1 | 3 | Mechanical Room at the end of the Hallway across from Boy's Restroom | N/A | Fiberglass Duct Insulation | | Non Suspect ACM | 300 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 3 | Mechanical Room at the end of the Hallway across from Boy's Restroom | N/A | Concrete Ceiling | | Non Suspect ACM | 1512 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 3 | Mechanical Room at the end of the Hallway across from Boy's Restroom | N/A | Concrete Block Wall | | Non Suspect ACM | 1600 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 3 | Mechanical Room at the end of the Hallway across from Boy's Restroom | N/A | Cement Floor | | Non Suspect ACM | 1512 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 3 | Girls Restroom across from Auditorium Balcony | N/A | Plaster Ceiling | | NAD | 285 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 3 | Girls Restroom across from Auditorium Balcony | N/A | Ceramic Tile Walls | | Non Suspect ACM | 600 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 3 | Girls Restroom across from Auditorium Balcony | N/A | Ceramic Tile Floors | | Non Suspect ACM | 285 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 3 | Custodial Storage between Restrooms | N/A | Plaster Ceiling | | NAD | 24 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 3 | Custodial Storage between Restrooms | N/A | Ceramic Tile Walls | | Non Suspect ACM | 200 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 3 | Custodial Storage between Restrooms | N/A | Ceramic Tile Floors | | Non Suspect ACM | 24 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 3 | Boy's Restroom across from Auditorium Balcony | N/A | Plaster Ceiling | | NAD | 400 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 3 | Boy's Restroom across from Auditorium Balcony | N/A | Ceramic Tile Walls | | Non Suspect ACM | 800 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 3 | Boy's Restroom across from Auditorium Balcony | N/A | Ceramic Tile Floors | | Non Suspect ACM | 400 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 3 | Men's Teacher Lounge across from Auditorium Balcony | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 15 | LF | 0 | LF | | | | N/A | N/A | N/A |
| 1 | 3 | Men's Teacher Lounge across from Auditorium Balcony | N/A | Fiberglass Ceiling Tile 2' x 4' | | Non Suspect ACM | 168 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 3 | Men's Teacher Lounge across from Auditorium Balcony | N/A | Plaster Walls | | NAD | 500 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 3 | Men's Teacher Lounge across from Auditorium Balcony | M | Floor Tile VAT 12" x 12" | 6010/01/03/RR | Assumed | 168 | SF | 0 | SF | White | | | 1 | No | 1/D |
| 1 | 3 | Men's Restroom across from Auditorium Balcony | N/A | Plaster Ceiling | | NAD | 88 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 3 | Men's Restroom across from Auditorium Balcony | N/A | Ceramic Tile Walls | | Non Suspect ACM | 350 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 3 | Men's Restroom across from Auditorium Balcony | N/A | Ceramic Tile Floors | | Non Suspect ACM | 88 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 3 | Storage next to Men's Restroom | N/A | Plaster Ceiling | | NAD | 180 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 3 | Storage next to Men's Restroom | N/A | Plaster Walls | | NAD | 500 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 3 | Storage next to Men's Restroom | N/A | Cement Floor | | Non Suspect ACM | 180 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 3 | Office across from Auditorium Balcony | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 30 | LF | 0 | LF | | | | N/A | N/A | N/A |

6010 Central HS - 2015 2016 AHERA Three-Year Report.xls

| School District of Philadelphia Central High School 1700 W. Olney Avenue, Philadelphia, PA 19141 ULCS# 6010 Year Built: 1939 | | AHERA Three-Year Reinspection 2015-2016 Room by Room Location Log Report | | | | | | | | | | Reinspection Date: 7/5/2016 Building Inspector: Ananth K. Vinjamuri Number: 374 Management Planner: Mary Anne Lerro Number: 742327 | | | | |
|--|-----------------------|---|-----------------|---------------------------------|-----------------------|--|--------------------|------------|------------------|----------|------------------------|--|------------------------------|-----------------------|--------------------|----------------------|
| E l e m e n t | F l o o r | On Site Room Name | System Affected | Material Description | HID# | Confirmed, Assumed, NAD, Non Suspect ACM | Amount of Material | (SF/LF/EA) | Amount of Damage | SF LF EA | Color required for VAT | Comments/Description/Notes | Attic/Crawlsp ace Ranking | Damage Potential (DP) | Newly Friable (NF) | Response Action (RA) |
| 1 | 3 | Office across from Auditorium Balcony | N/A | Plaster Ceiling | | NAD | 100 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 3 | Office across from Auditorium Balcony | N/A | Plaster Walls | | NAD | 400 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 3 | Office across from Auditorium Balcony | N/A | Cement Floor | | Non Suspect ACM | 100 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 3 | Music Office walkway | N/A | Fiberglass Ceiling Tile 2' x 4' | | Non Suspect ACM | 126 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 3 | Music Office walkway | N/A | Plaster Walls | | NAD | 300 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 3 | Music Office walkway | M | Floor Tile VAT 12" x 12" | 6010/01/03/RR | Assumed | 126 | SF | 0 | SF | White | | | 1 | No | 1/D |
| 1 | 3 | Music Room Office #1 | N/A | Fiberglass Ceiling Tile 2' x 4' | | Non Suspect ACM | 49 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 3 | Music Room Office #1 | N/A | Plaster Walls | | NAD | 250 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 3 | Music Room Office #1 | M | Floor Tile VAT 12" x 12" | 6010/01/03/RR | Assumed | 49 | SF | 0 | SF | White | | | 1 | No | 1/D |
| 1 | 3 | Music Room Office #2 | N/A | Fiberglass Ceiling Tile 2' x 4' | | Non Suspect ACM | 49 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 3 | Music Room Office #2 | N/A | Plaster Walls | | NAD | 250 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 3 | Music Room Office #2 | M | Floor Tile VAT 12" x 12" | 6010/01/03/RR | Assumed | 49 | SF | 0 | SF | White | | | 1 | No | 1/D |
| 1 | 3 | Music Room Office #3 | N/A | Fiberglass Ceiling Tile 2' x 4' | | Non Suspect ACM | 160 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 3 | Music Room Office #3 | N/A | Plaster Walls | | NAD | 450 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 3 | Music Room Office #3 | M | Floor Tile VAT 12" x 12" | 6010/01/03/RR | Assumed | 160 | SF | 0 | SF | White | | | 1 | No | 1/D |
| 1 | 3 | Music Room Office #4 | N/A | Fiberglass Ceiling Tile 2' x 4' | | Non Suspect ACM | 160 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 3 | Music Room Office #4 | N/A | Plaster Walls | | NAD | 450 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 3 | Music Room Office #4 | M | Floor Tile VAT 12" x 12" | 6010/01/03/RR | Assumed | 160 | SF | 0 | SF | White | | | 1 | No | 1/D |
| 1 | 3 | Room 322 - Office waiting area | N/A | Fiberglass Ceiling Tile 2' x 4' | | Non Suspect ACM | 280 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 3 | Room 322 - Office waiting area | N/A | Plaster Walls | | NAD | 550 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 3 | Room 322 - Office waiting area | M | Floor Tile VAT 12" x 12" | 6010/01/03/RR | Assumed | 280 | SF | 0 | SF | Tan | | | 1 | No | 1/D |
| 1 | 3 | Room 322A - Office #1 | N/A | Fiberglass Ceiling Tile 2' x 4' | | Non Suspect ACM | 204 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 3 | Room 322A - Office #1 | N/A | Plaster Walls | | NAD | 500 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 3 | Room 322A - Office #1 | N/A | Carpet | | Non Suspect ACM | 204 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 3 | Room 322B - Office #2 | N/A | Fiberglass Ceiling Tile 2' x 4' | | Non Suspect ACM | 192 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 3 | Room 322B - Office #2 | N/A | Plaster Walls | | NAD | 500 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 3 | Room 322B - Office #2 | M | Floor Tile VAT 12" x 12" | 6010/01/03/RR | Assumed | 192 | SF | 0 | SF | Tan | | | 1 | No | 1/D |
| 1 | 3 | Room 322C - Office #3 | N/A | Fiberglass Ceiling Tile 2' x 4' | | Non Suspect ACM | 208 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 3 | Room 322C - Office #3 | N/A | Plaster Walls | | NAD | 500 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 3 | Room 322C - Office #3 | M | Floor Tile VAT 12" x 12" | 6010/01/03/RR | Assumed | 208 | SF | 0 | SF | Tan | | | 1 | No | 1/D |
| 1 | 3 | Room 322D - Storage | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 7 | LF | 0 | LF | | | | N/A | N/A | N/A |
| 1 | 3 | Room 322D - Storage | N/A | Fiberglass Ceiling Tile 2' x 4' | | Non Suspect ACM | 36 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 3 | Room 322D - Storage | N/A | Plaster Walls | | NAD | 200 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 3 | Room 322D - Storage | M | Floor Tile VAT 12" x 12" | 6010/01/03/RR | Assumed | 36 | SF | 0 | SF | Tan | | | 1 | No | 1/D |
| 1 | 3 | Room 323 - Music Room | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 24 | LF | 0 | LF | | | | N/A | N/A | N/A |
| 1 | 3 | Room 323 - Music Room | N/A | Fiberglass Ceiling Tile 2' x 4' | | Non Suspect ACM | 1188 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 3 | Room 323 - Music Room | S | Acoustical Plaster Walls | 6010/01/03/WW | Assumed | 300 | SF | 0 | SF | | | | 1 | No | 1/D |
| 1 | 3 | Room 323 - Music Room | N/A | Plaster Walls | | NAD | 1100 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 3 | Room 323 - Music Room | M | Floor Tile VAT 12" x 12" | 6010/01/03/RR | Assumed | 1188 | SF | 0 | SF | Tan | | | 1 | No | 1/D |
| 1 | 3 | Room 323 - Music Room | M | Blackboard Glue Dots | 6010/01/03/GC/AV/2600 | Assumed | 100 | SF | 0 | SF | | | | 1 | No | 1/D |
| 1 | 3 | Room 324 - Music Room | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 24 | LF | 0 | LF | | | | N/A | N/A | N/A |
| 1 | 3 | Room 324 - Music Room | N/A | Fiberglass Ceiling Tile 2' x 4' | | Non Suspect ACM | 1188 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 3 | Room 324 - Music Room | S | Acoustical Plaster Walls | 6010/01/03/WW | Assumed | 300 | SF | 0 | SF | | | | 1 | No | 1/D |
| 1 | 3 | Room 324 - Music Room | N/A | Plaster Walls | | NAD | 1100 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 3 | Room 324 - Music Room | M | Floor Tile VAT 12" x 12" | 6010/01/03/RR | Assumed | 1188 | SF | 0 | SF | Tan | | | 1 | No | 1/D |
| 1 | 3 | Room 324 - Music Room | M | Blackboard Glue Dots | 6010/01/03/GC/AV/2600 | Assumed | 100 | SF | 0 | SF | | | | 1 | No | 1/D |
| 1 | 3 | Classroom 325 | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 24 | LF | 0 | LF | | | | N/A | N/A | N/A |
| 1 | 3 | Classroom 325 | N/A | Fiberglass Ceiling Tile 2' x 4' | | Non Suspect ACM | 810 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 3 | Classroom 325 | N/A | Plaster Walls | | NAD | 1100 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 3 | Classroom 325 | N/A | Wood Floor | | Non Suspect ACM | 810 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 3 | Classroom 325 | M | Blackboard Glue Dots | 6010/01/03/GC/AV/2600 | Assumed | 100 | SF | 0 | SF | | | | 1 | No | 1/D |
| 1 | 3 | Classroom 326 | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 24 | LF | 0 | LF | | | | N/A | N/A | N/A |
| 1 | 3 | Classroom 326 | N/A | Fiberglass Ceiling Tile 2' x 4' | | Non Suspect ACM | 810 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 3 | Classroom 326 | N/A | Plaster Walls | | NAD | 1100 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 3 | Classroom 326 | N/A | Wood Floor | | Non Suspect ACM | 810 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 3 | Classroom 326 | M | Blackboard Glue Dots | 6010/01/03/GC/AV/2600 | Assumed | 100 | SF | 0 | SF | | | | 1 | No | 1/D |
| 1 | 3 | Classroom 327 | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 24 | LF | 0 | LF | | | | N/A | N/A | N/A |
| 1 | 3 | Classroom 327 | N/A | Fiberglass Ceiling Tile 2' x 4' | | Non Suspect ACM | 810 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 3 | Classroom 327 | N/A | Plaster Walls | | NAD | 1100 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 3 | Classroom 327 | N/A | Wood Floor | | Non Suspect ACM | 810 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 3 | Classroom 327 | M | Blackboard Glue Dots | 6010/01/03/GC/AV/2600 | Assumed | 200 | SF | 0 | SF | | | | 1 | No | 1/D |
| 1 | 3 | Classroom 328 | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 24 | LF | 0 | LF | | | | N/A | N/A | N/A |
| 1 | 3 | Classroom 328 | N/A | Fiberglass Ceiling Tile 2' x 4' | | Non Suspect ACM | 810 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 3 | Classroom 328 | N/A | Plaster Walls | | NAD | 1100 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 3 | Classroom 328 | N/A | Wood Floor | | Non Suspect ACM | 810 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 3 | Classroom 328 | M | Blackboard Glue Dots | 6010/01/03/GC/AV/2600 | Assumed | 200 | SF | 0 | SF | | | | 1 | No | 1/D |
| 1 | 3 | Classroom 329 | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 30 | LF | 0 | LF | | | | N/A | N/A | N/A |
| 1 | 3 | Room 329 - Office next to Room 327 | N/A | Fiberglass Ceiling Tile 2' x 4' | | Non Suspect ACM | 338 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 3 | Room 329 - Office next to Room 327 | N/A | Plaster Walls | | NAD | 700 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 3 | Room 329 - Office next to Room 327 | M | Linoleum | 6010/01/03/MM | Assumed | 338 | SF | 0 | SF | Brown | | | 1 | No | 1/D |
| 1 | 3 | Room 329 - Office next to Room 327 | M | Blackboard Glue Dots | 6010/01/03/GC/AV/2600 | Assumed | 50 | SF | 0 | SF | | | | 1 | No | 1/D |
| 1 | 3 | Storage Room 3-F | N/A | Plaster Ceiling | | NAD | 180 | SF | 10 | SF | | | | N/A | N/A | N/A |

6010 Central HS - 2015 2016 AHERA Three-Year Report.xls

| School District of Philadelphia Central High School 1700 W. Olney Avenue, Philadelphia, PA 19141 ULCS# 6010 Year Built: 1939 | | AHERA Three-Year Reinspection 2015-2016 Room by Room Location Log Report | | | | | | | | | | Reinspection Date: 7/5/2016 Building Inspector: Ananth K. Vinjamuri Number: 374 Management Planner: Mary Anne Lerro Number: 742327 | | | | |
|--|-----------------------|---|-----------------|---------------------------------|---------------|--|--------------------|------------|------------------|----------|------------------------|--|------------------------------|-----------------------|--------------------|----------------------|
| E l e m e n t | F l o o r | On Site Room Name | System Affected | Material Description | HID# | Confirmed, Assumed, NAD, Non Suspect ACM | Amount of Material | (SF/LF/EA) | Amount of Damage | SF LF EA | Color required for VAT | Comments/Description/Notes | Attic/Crawlsp ace Ranking | Damage Potential (DP) | Newly Friable (NF) | Response Action (RA) |
| 1 | 3 | Storage Room 3-F | N/A | Plaster Walls | | NAD | 600 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 3 | Storage Room 3-F | N/A | Cement Floor | | Non Suspect ACM | 180 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 3 | Teacher Lounge/Dining | N/A | Plaster Ceiling | | NAD | 1420 | SF | 10 | SF | | | | N/A | N/A | N/A |
| 1 | 3 | Teacher Lounge/Dining | N/A | Plaster Walls | | NAD | 1800 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 3 | Teacher Lounge/Dining | N/A | Carpet | | Non Suspect ACM | 1420 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 3 | Room 331 - Kitchen Supply Room | N/A | Plaster Ceiling | | NAD | 220 | SF | 10 | SF | | | | N/A | N/A | N/A |
| 1 | 3 | Room 331 - Kitchen Supply Room | N/A | Plaster Walls | | NAD | 550 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 3 | Room 331 - Kitchen Supply Room | N/A | Cement Floor | | Non Suspect ACM | 220 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 3 | Staff Restroom across from Teacher Lounge | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 6 | LF | 0 | LF | | | | N/A | N/A | N/A |
| 1 | 3 | Staff Restroom across from Teacher Lounge | N/A | Plaster Ceiling | | NAD | 80 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 3 | Staff Restroom across from Teacher Lounge | N/A | Ceramic Tile Walls | | Non Suspect ACM | 300 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 3 | Staff Restroom across from Teacher Lounge | N/A | Ceramic Tile Floors | | Non Suspect ACM | 80 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 3 | Room 333A - Kitchen and Dry Storage Area | N/A | Plaster Ceiling | | NAD | 440 | SF | 10 | SF | | | | N/A | N/A | N/A |
| 1 | 3 | Room 333A - Kitchen and Dry Storage Area | N/A | Plaster Walls | | NAD | 750 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 3 | Room 333A - Kitchen and Dry Storage Area | N/A | Cement Floor | | Non Suspect ACM | 440 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 3 | Alumni Office | N/A | Fiberglass Ceiling Tile 2' x 4' | | Non Suspect ACM | 400 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 3 | Alumni Office | N/A | Plaster Walls | | NAD | 700 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 3 | Alumni Office | N/A | Carpet | | Non Suspect ACM | 400 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 3 | Mechanical Room next to Alumni Office | N/A | Concrete Ceiling | | Non Suspect ACM | 925 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 3 | Mechanical Room next to Alumni Office | N/A | Concrete Block Wall | | Non Suspect ACM | 1400 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 3 | Mechanical Room next to Alumni Office | N/A | Cement Floor | | Non Suspect ACM | 925 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 3 | Mechanical Room next to Alumni Office | T | Vibration Damper Cloth | 6010/01/03/60 | Assumed | 40 | SF | 0 | SF | | | | 1 | No | 1/D |
| 1 | 3 | Storage Room next to Mechanical Room | N/A | Concrete Ceiling | | Non Suspect ACM | 165 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 3 | Storage Room next to Mechanical Room | N/A | Concrete Block Wall | | Non Suspect ACM | 450 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 3 | Storage Room next to Mechanical Room | N/A | Cement Floor | | Non Suspect ACM | 165 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 3 | Cafeteria | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 120 | LF | 0 | LF | | | | N/A | N/A | N/A |
| 1 | 3 | Cafeteria | N/A | Ceiling Tile 2' x 4' | | NAD | 7600 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 3 | Cafeteria | N/A | Plaster Walls | | NAD | 4500 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 3 | Cafeteria | M | Floor Tile VAT 12" x 12" | 6010/01/03/RR | Assumed | 7600 | SF | 0 | SF | Brown | | | 1 | No | 1/D |
| 1 | 3 | Cafeteria | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 30 | LF | 0 | LF | | | | N/A | N/A | N/A |
| 1 | 3 | Cafeteria | N/A | Ceiling Tile 2' x 4' | | NAD | 2200 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 3 | Cafeteria | N/A | Plaster Walls | | NAD | 2000 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 3 | Cafeteria | M | Floor Tile VAT 12" x 12" | 6010/01/03/RR | Assumed | 2200 | SF | 0 | SF | | Inspector please verify color | | 1 | No | 1/D |
| 1 | 3 | Kitchen Storage | N/A | Ceiling Tile 2' x 4' | | NAD | 112 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 3 | Kitchen Storage | N/A | Concrete Block Wall | | Non Suspect ACM | 400 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 3 | Kitchen Storage | M | Floor Tile VAT 12" x 12" | 6010/01/03/RR | Assumed | 112 | SF | 0 | SF | Brown | | | 1 | No | 1/D |
| 1 | 3 | Kitchen Storage | N/A | Ceiling Tile 2' x 4' | | NAD | 64 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 3 | Kitchen Storage | N/A | Concrete Block Wall | | Non Suspect ACM | 200 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 3 | Kitchen Storage | M | Floor Tile VAT 12" x 12" | 6010/01/03/RR | Assumed | 64 | SF | 0 | SF | Brown | | | 1 | No | 1/D |
| 1 | 3 | Kitchen Staff Locker Room | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 30 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 3 | Kitchen Staff Locker Room | N/A | Plaster Ceiling | | NAD | 184 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 3 | Kitchen Staff Locker Room | N/A | Ceramic Tile Walls | | Non Suspect ACM | 600 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 3 | Kitchen Staff Locker Room | N/A | Ceramic Tile Floors | | Non Suspect ACM | 184 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 3 | Kitchen Restroom | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 40 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 3 | Kitchen Restroom | N/A | Plaster Ceiling | | NAD | 10 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 3 | Kitchen Restroom | N/A | Ceramic Tile Walls | | Non Suspect ACM | 140 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 3 | Kitchen Restroom | N/A | Ceramic Tile Floors | | Non Suspect ACM | 10 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 3 | Kitchen | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 50 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 3 | Kitchen | N/A | Plaster Ceiling | | NAD | 1104 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 3 | Kitchen | N/A | Concrete Block Wall | | Non Suspect ACM | 1400 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 3 | Kitchen | N/A | Ceramic Tile Floors | | Non Suspect ACM | 1104 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 3 | Kitchen Office | N/A | Plaster Ceiling | | NAD | 196 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 3 | Kitchen Office | N/A | Concrete Block Wall | | Non Suspect ACM | 500 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 3 | Kitchen Office | M | Floor Tile VAT 12" x 12" | 6010/01/03/RR | Assumed | 196 | SF | 0 | SF | Brown | | | 1 | No | 1/D |
| 1 | 3 | Kitchen and Dry Storage Area | N/A | Plaster Ceiling | | NAD | 168 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 3 | Kitchen and Dry Storage Area | N/A | Concrete Block Wall | | Non Suspect ACM | 450 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 3 | Kitchen and Dry Storage Area | M | Floor Tile VAT 12" x 12" | 6010/01/03/RR | Assumed | 168 | SF | 0 | SF | Brown | | | 1 | No | 1/D |
| 1 | 3 | Hallway at Rooms 301 to 309 | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 20 | LF | 0 | LF | | | | N/A | N/A | N/A |
| 1 | 3 | Hallway at Rooms 301 to 309 | N/A | Fiberglass Ceiling Tile 2' x 4' | | Non Suspect ACM | 1776 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 3 | Hallway at Rooms 301 to 309 | N/A | Plaster Walls | | NAD | 1350 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 3 | Hallway at Rooms 301 to 309 | N/A | Concrete Block Wall | | Non Suspect ACM | 1350 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 3 | Hallway at Rooms 301 to 309 | N/A | Cement Floor | | Non Suspect ACM | 1776 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 3 | Main Hallway | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 30 | LF | 0 | LF | | | | N/A | N/A | N/A |
| 1 | 3 | Main Hallway | N/A | Fiberglass Ceiling Tile 2' x 4' | | Non Suspect ACM | 3192 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 3 | Main Hallway | N/A | Plaster Walls | | NAD | 2250 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 3 | Main Hallway | N/A | Concrete Block Wall | | Non Suspect ACM | 2250 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 3 | Main Hallway | N/A | Terrazzo Floor | | Non Suspect ACM | 3192 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 3 | Shorter Hallway across from Restrooms | N/A | Fiberglass Ceiling Tile 2' x 4' | | Non Suspect ACM | 93 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 3 | Shorter Hallway across from Restrooms | N/A | Plaster Walls | | NAD | 300 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 3 | Shorter Hallway across from Restrooms | N/A | Concrete Block Wall | | Non Suspect ACM | 300 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 3 | Shorter Hallway across from Restrooms | N/A | Cement Floor | | Non Suspect ACM | 93 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 3 | Hallway at Rooms 321 to 329 | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 10 | LF | 0 | LF | | | | N/A | N/A | N/A |

6010 Central HS - 2015 2016 AHERA Three-Year Report.xls

| School District of Philadelphia Central High School 1700 W. Olney Avenue, Philadelphia, PA 19141 ULCS# 6010 Year Built: 1939 | | AHERA Three-Year Reinspection 2015-2016 Room by Room Location Log Report | | | | | | | Reinspection Date: 7/5/2016 Building Inspector: Ananth K. Vinjamuri Number: 374 Management Planner: Mary Anne Lerro Number: 742327 | | | | | | |
|--|-----------------------|---|-----------------|---------------------------------|-----------------------|--|-------------------------------|------------------|--|------------------------|--|---------------------------|-----------------------|--------------------|----------------------|
| E l e m e n t | F l o o r | On Site Room Name | System Affected | Material Description | HID# | Confirmed, Assumed, NAD, Non Suspect ACM | Amount of Material (SF/LF/EA) | Amount of Damage | SF LF EA | Color required for VAT | Comments/Description/Notes | Attic/Crawlsp ace Ranking | Damage Potential (DP) | Newly Friable (NF) | Response Action (RA) |
| 1 | 3 | Hallway at Rooms 321 to 329 | N/A | Fiberglass Ceiling Tile 2' x 4' | | Non Suspect ACM | 1860 SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 3 | Hallway at Rooms 321 to 329 | N/A | Plaster Walls | | NAD | 1350 SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 3 | Hallway at Rooms 321 to 329 | N/A | Concrete Block Wall | | Non Suspect ACM | 1350 SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 3 | Hallway at Rooms 321 to 329 | N/A | Floor Tile VAT 12" x 12" | 6010/01/03/RR | Assumed | 504 SF | 0 | SF | White | | | 1 | No | 1/D |
| 1 | 3 | Hallway at Rooms 321 to 329 | N/A | Cement Floor | | Non Suspect ACM | 1360 SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 3 | Shorter Hallway across from Teacher Dining Area | N/A | Fiberglass Ceiling Tile 2' x 4' | | Non Suspect ACM | 294 SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 3 | Shorter Hallway across from Teacher Dining Area | N/A | Plaster Walls | | NAD | 400 SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 3 | Shorter Hallway across from Teacher Dining Area | N/A | Concrete Block Wall | | Non Suspect ACM | 400 SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 3 | Shorter Hallway across from Teacher Dining Area | N/A | Cement Floor | | Non Suspect ACM | 294 SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 3 | Stairwell next to Room 308 | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 30 LF | 0 | LF | | | | N/A | N/A | N/A |
| 1 | 3 | Stairwell next to Room 308 | N/A | Plaster Ceiling | | NAD | 300 SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 3 | Stairwell next to Room 308 | N/A | Plaster Walls | | NAD | 1000 SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 3 | Stairwell next to Room 308 | N/A | Cement Floor | | Non Suspect ACM | 300 SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 3 | Stairwell at Room 301 | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 25 LF | 0 | LF | | | | N/A | N/A | N/A |
| 1 | 3 | Stairwell at Room 301 | N/A | Plaster Ceiling | | NAD | 300 SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 3 | Stairwell at Room 301 | N/A | Plaster Walls | | NAD | 1000 SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 3 | Stairwell at Room 301 | N/A | Cement Floor | | Non Suspect ACM | 300 SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 3 | Stairwell next to Room 328 | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 40 LF | 0 | LF | | | | N/A | N/A | N/A |
| 1 | 3 | Stairwell next to Room 328 | N/A | Plaster Ceiling | | NAD | 300 SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 3 | Stairwell next to Room 328 | N/A | Plaster Walls | | NAD | 1000 SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 3 | Stairwell next to Room 328 | N/A | Cement Floor | | Non Suspect ACM | 300 SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 3 | Stairwell next to Room 321 | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 30 LF | 0 | LF | | | | N/A | N/A | N/A |
| 1 | 3 | Stairwell next to Room 321 | N/A | Plaster Ceiling | | NAD | 300 SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 3 | Stairwell next to Room 321 | N/A | Plaster Walls | | NAD | 1000 SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 3 | Stairwell next to Room 321 | N/A | Cement Floor | | Non Suspect ACM | 300 SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 3 | Stairwell at Cafeteria on the Kitchen Office Side | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 40 LF | 0 | LF | | | | N/A | N/A | N/A |
| 1 | 3 | Stairwell at Cafeteria on the Kitchen Office Side | N/A | Plaster Ceiling | | NAD | 300 SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 3 | Stairwell at Cafeteria on the Kitchen Office Side | N/A | Plaster Walls | | NAD | 1000 SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 3 | Stairwell at Cafeteria on the Kitchen Office Side | N/A | Cement Floor | | Non Suspect ACM | 300 SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 3 | Stairwell at Cafeteria | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 30 LF | 0 | LF | | | | N/A | N/A | N/A |
| 1 | 3 | Stairwell at Cafeteria | N/A | Plaster Ceiling | | NAD | 300 SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 3 | Stairwell at Cafeteria | N/A | Plaster Walls | | NAD | 1000 SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 3 | Stairwell at Cafeteria | N/A | Cement Floor | | Non Suspect ACM | 300 SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 4 | Classroom 402 | N/A | Ceiling Tile 2' x 4' | | NAD | 968 SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 4 | Classroom 402 | N/A | Plaster Walls | | NAD | 1200 SF | 0 | SF | Grey | | | 1 | No | 1/D |
| 1 | 4 | Classroom 402 | M | Floor Tile VAT 12" x 12" | 6010/01/04/SS | Assumed | 968 SF | 0 | SF | | | | 1 | No | 1/D |
| 1 | 4 | Classroom 402 | M | Blackboard Glue Dots | 6010/01/04/GC/AV/2600 | Assumed | 100 SF | 0 | SF | | | | 1 | No | 1/D |
| 1 | 4 | Classroom 402 | M | Transite | 6010/01/04/36 | Assumed | 100 SF | 0 | SF | | Counter Tops, Test tube holder on the wall | | 1 | No | 1/D |
| 1 | 4 | Classroom 402 Storage | N/A | Ceiling Tile 2' x 4' | | NAD | 24 SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 4 | Classroom 402 Storage | N/A | Plaster Walls | | NAD | 200 SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 4 | Classroom 402 Storage | M | Floor Tile VAT 12" x 12" | 6010/01/04/SS | Assumed | 24 SF | 0 | SF | Grey | | | 1 | No | 1/D |
| 1 | 4 | Classroom 403 | N/A | Ceiling Tile 2' x 4' | | NAD | 792 SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 4 | Classroom 403 | N/A | Plaster Walls | | NAD | 1000 SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 4 | Classroom 403 | M | Floor Tile VAT 12" x 12" | 6010/01/04/SS | Assumed | 792 SF | 0 | SF | Grey | | | 1 | No | 1/D |
| 1 | 4 | Classroom 403 | M | Blackboard Glue Dots | 6010/01/04/GC/AV/2600 | Assumed | 100 SF | 0 | SF | | | | 1 | No | 1/D |
| 1 | 4 | Classroom 403 | M | Transite | 6010/01/04/36 | Assumed | 100 SF | 0 | SF | | Counter Tops, Test tube holder on the wall | | 1 | No | 1/D |
| 1 | 4 | Classroom 403 Storage | N/A | Ceiling Tile 2' x 4' | | NAD | 144 SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 4 | Classroom 403 Storage | N/A | Plaster Walls | | NAD | 450 SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 4 | Classroom 403 Storage | M | Floor Tile VAT 12" x 12" | 6010/01/04/SS | Assumed | 144 SF | 0 | SF | Grey | | | 1 | No | 1/D |
| 1 | 4 | Classroom 403 Storage | N/A | Ceiling Tile 2' x 4' | | NAD | 15 SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 4 | Classroom 403 Storage | N/A | Plaster Walls | | NAD | 120 SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 4 | Classroom 403 Storage | M | Floor Tile VAT 12" x 12" | 6010/01/04/SS | Assumed | 15 SF | 0 | SF | Grey | | | 1 | No | 1/D |
| 1 | 4 | Classroom 404 | N/A | Ceiling Tile 2' x 4' | | NAD | 256 SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 4 | Classroom 404 | N/A | Plaster Walls | | NAD | 550 SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 4 | Classroom 404 | M | Floor Tile VAT 12" x 12" | 6010/01/04/SS | Assumed | 256 SF | 0 | SF | Grey | | | 1 | No | 1/D |
| 1 | 4 | Classroom 404 | M | Transite | 6010/01/04/36 | Assumed | 50 SF | 0 | SF | | Counter Tops, Test Tube holder on the wall | | 1 | No | 1/D |
| 1 | 4 | Classroom 404 Storage | N/A | Ceiling Tile 2' x 4' | | NAD | 160 SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 4 | Classroom 404 Storage | N/A | Plaster Walls | | NAD | 400 SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 4 | Classroom 404 Storage | M | Floor Tile VAT 12" x 12" | 6010/01/04/SS | Assumed | 160 SF | 0 | SF | Grey | | | 1 | No | 1/D |
| 1 | 4 | Classroom 406 | N/A | Ceiling Tile 2' x 4' | | NAD | 1122 SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 4 | Classroom 406 | N/A | Plaster Walls | | NAD | 1300 SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 4 | Classroom 406 | M | Floor Tile VAT 12" x 12" | 6010/01/04/SS | Assumed | 1122 SF | 0 | SF | Grey | | | 1 | No | 1/D |
| 1 | 4 | Classroom 406 | M | Blackboard Glue Dots | 6010/01/04/GC/AV/2600 | Assumed | 100 SF | 0 | SF | | | | 1 | No | 1/D |
| 1 | 4 | Classroom 406 | M | Transite | 6010/01/04/36 | Assumed | 100 SF | 0 | SF | | Counter Tops, Test Tube holder on the wall | | 1 | No | 1/D |
| 1 | 4 | Classroom 406 Storage | N/A | Ceiling Tile 2' x 4' | | NAD | 108 SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 4 | Classroom 406 Storage | N/A | Plaster Walls | | NAD | 300 SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 4 | Classroom 406 Storage | M | Floor Tile VAT 12" x 12" | 6010/01/04/SS | Assumed | 108 SF | 0 | SF | Grey | | | 1 | No | 1/D |
| 1 | 4 | Classroom 407 | N/A | Ceiling Tile 2' x 4' | | NAD | 1122 SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 4 | Classroom 407 | N/A | Plaster Walls | | NAD | 1300 SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 4 | Classroom 407 | M | Floor Tile VAT 12" x 12" | 6010/01/04/SS | Assumed | 1122 SF | 0 | SF | Grey | | | 1 | No | 1/D |
| 1 | 4 | Classroom 407 | M | Blackboard Glue Dots | 6010/01/04/GC/AV/2600 | Assumed | 100 SF | 0 | SF | | | | 1 | No | 1/D |
| 1 | 4 | Classroom 407 | M | Transite | 6010/01/04/36 | Assumed | 100 SF | 0 | SF | | Counter Tops, Test Tube holder on the wall | | 1 | No | 1/D |

6010 Central HS - 2015 2016 AHERA Three-Year Report.xls

| | | | | | | | | | | | | | | | | | |
|--|---|---|-----------------------|----------------------------|-----------------|----------------------|------|--|-------------------------------|--|----------|--|----------------------------|------------------------------|-----------------------|--------------------|----------------------|
| School District of Philadelphia Central High School 1700 W. Olney Avenue, Philadelphia, PA 19141 ULCS# 6010 Year Built: 1939 | | AHERA Three-Year Reinspection 2015-2016 Room by Room Location Log Report | | | | | | | | Reinspection Date: 7/5/2016 Building Inspector: Ananth K. Vinjamuri Number: 374 Management Planner: Mary Anne Lerro Number: 742327 | | | | | | | |
| | | E l e m e n t | F l o o r | On Site Room Name | System Affected | Material Description | HID# | Confirmed, Assumed, NAD, Non Suspect ACM | Amount of Material (SF/LF/EA) | Amount of Damage | SF LF EA | Color required for VAT | Comments/Description/Notes | Attic/Crawlsp ace Ranking | Damage Potential (DP) | Newly Friable (NF) | Response Action (RA) |
| | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | |
| 1 | 4 | Classroom 407 Storage | N/A | Ceiling Tile 2' x 4' | | NAD | 256 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 4 | Classroom 407 Storage | N/A | Plaster Walls | | NAD | 550 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 4 | Classroom 407 Storage | M | Floor Tile VAT 12" x 12" | 6010/01/04/SS | Assumed | 256 | SF | 0 | SF | Grey | | | 1 | No | 1/D | |
| 1 | 4 | Classroom 407 Storage | M | Transite | 6010/01/04/36 | Assumed | 50 | SF | 0 | SF | | Counter Tops, Test Tube holder on the wall | | 1 | No | 1/D | |
| 1 | 4 | Classroom 407 Storage | N/A | Ceiling Tile 2' x 4' | | NAD | 160 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 4 | Classroom 407 Storage | N/A | Plaster Walls | | NAD | 400 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 4 | Classroom 407 Storage | M | Floor Tile VAT 12" x 12" | 6010/01/04/SS | Assumed | 160 | SF | 0 | SF | Grey | | | 1 | No | 1/D | |
| 1 | 4 | Classroom 407 Storage | N/A | Ceiling Tile 2' x 4' | | NAD | 90 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 4 | Classroom 407 Storage | N/A | Plaster Walls | | NAD | 300 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 4 | Classroom 407 Storage | M | Floor Tile VAT 12" x 12" | 6010/01/04/SS | Assumed | 90 | SF | 0 | SF | Grey | | | 1 | No | 1/D | |
| 1 | 4 | Hallway Restroom | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 2 | LF | 0 | LF | | | | N/A | N/A | N/A | |
| 1 | 4 | Hallway Restroom | N/A | Plaster Ceiling | | NAD | 140 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 4 | Hallway Restroom | N/A | Ceramic Tile Walls | | Non Suspect ACM | 350 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 4 | Hallway Restroom | N/A | Ceramic Tile Floors | | Non Suspect ACM | 140 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 4 | Fan Room next to Classroom 402 | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 65 | LF | 0 | LF | | | | N/A | N/A | N/A | |
| 1 | 4 | Fan Room next to Classroom 402 | N/A | Concrete Ceiling | | Non Suspect ACM | 1224 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 4 | Fan Room next to Classroom 402 | N/A | Concrete Block Wall | | Non Suspect ACM | 1300 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 4 | Fan Room next to Classroom 402 | N/A | Cement Floor | | Non Suspect ACM | 1224 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 4 | Fan Room next to Classroom 402 | T | Vibration Damper Cloth | 6010/01/04/FF | Assumed | 15 | SF | 0 | SF | | | | 1 | No | 1/D | |
| 1 | 4 | Hallway at Rooms 402 to 407 | N/A | Ceiling Tile 2' x 4' | | NAD | 740 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 4 | Hallway at Rooms 402 to 407 | N/A | Plaster Walls | | NAD | 600 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 4 | Hallway at Rooms 402 to 407 | N/A | Concrete Block Wall | | Non Suspect ACM | 600 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 4 | Hallway at Rooms 402 to 407 | M | Floor Tile VAT 12" x 12" | 6010/01/04/SS | Assumed | 740 | SF | 0 | SF | White | | | 1 | No | 1/D | |
| 1 | 4 | Hallway at Mechanical Room | N/A | Ceiling Tile 2' x 4' | | NAD | 574 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 4 | Hallway at Mechanical Room | N/A | Plaster Walls | | NAD | 400 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 4 | Hallway at Mechanical Room | N/A | Concrete Block Wall | | Non Suspect ACM | 400 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 4 | Hallway at Mechanical Room | M | Floor Tile VAT 12" x 12" | 6010/01/04/SS | Assumed | 574 | SF | 0 | SF | White | | | 1 | No | 1/D | |
| 1 | 4 | Elevator Foyer | N/A | Ceiling Tile 2' x 4' | | NAD | 168 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 4 | Elevator Foyer | N/A | Plaster Walls | | NAD | 200 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 4 | Elevator Foyer | N/A | Concrete Block Wall | | Non Suspect ACM | 200 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 4 | Elevator Foyer | M | Floor Tile VAT 12" x 12" | 6010/01/04/SS | Assumed | 168 | SF | 0 | SF | White | | | 1 | No | 1/D | |
| 1 | 4 | Stairwell by Mechanical Room | N/A | Plaster Ceiling | | NAD | 300 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 4 | Stairwell by Mechanical Room | N/A | Plaster Walls | | NAD | 1000 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 4 | Stairwell by Mechanical Room | N/A | Cement Floor | | Non Suspect ACM | 300 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 4 | Stairwell by Room 406 | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 50 | LF | 0 | LF | | | | N/A | N/A | N/A | |
| 1 | 4 | Stairwell by Room 406 | N/A | Plaster Ceiling | | NAD | 300 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 4 | Stairwell by Room 406 | N/A | Plaster Walls | | NAD | 1000 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 4 | Stairwell by Room 406 | N/A | Cement Floor | | Non Suspect ACM | 300 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | B | Room 008 in the Main Hallway | N/A | Concrete Ceiling | | Non Suspect ACM | 150 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | B | Room 008 in the Main Hallway | N/A | Concrete Block Wall | | Non Suspect ACM | 300 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | B | Room 008 in the Main Hallway | N/A | Cement Floor | | Non Suspect ACM | 150 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | B | Room 010 - Office in the Main Hallway | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 25 | LF | 0 | LF | | | | N/A | N/A | N/A | |
| 1 | B | Room 010 - Office in the Main Hallway | N/A | Plaster Ceiling | | NAD | 280 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | B | Room 010 - Office in the Main Hallway | N/A | Plaster Walls | | NAD | 500 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | B | Room 010 - Office in the Main Hallway | M | Floor Tile VAT 12" x 12" | 6010/01/0B/TT | Assumed | 280 | SF | 0 | SF | Brown | | | 1 | No | 1/D | |
| 1 | B | Room 010 - Office Restroom | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 30 | LF | 0 | LF | | | | N/A | N/A | N/A | |
| 1 | B | Room 010 - Office Storage | N/A | Plaster Ceiling | | NAD | 40 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | B | Room 010 - Office Storage | N/A | Ceramic Tile Walls | | Non Suspect ACM | 300 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | B | Room 010 - Office Storage | N/A | Ceramic Tile Floors | | Non Suspect ACM | 40 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | B | Room 018 - Mechanical Room in the Main Hallway | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 100 | LF | 0 | LF | | | | N/A | N/A | N/A | |
| 1 | B | Room 018 - Mechanical Room in the Main Hallway | N/A | Concrete Ceiling | | Non Suspect ACM | 800 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | B | Room 018 - Mechanical Room in the Main Hallway | N/A | Plaster Walls | | NAD | 1600 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | B | Room 018 - Mechanical Room in the Main Hallway | N/A | Cement Floor | | Non Suspect ACM | 800 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | B | Room 19 - Walkway to Mechanical Room 19B | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 12 | LF | 0 | LF | | | | N/A | N/A | N/A | |
| 1 | B | Room 19 - Walkway to Mechanical Room 19B | N/A | Plaster Ceiling | | NAD | 369 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | B | Room 19 - Walkway to Mechanical Room 19B | N/A | Plaster Walls | | NAD | 1000 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | B | Room 19 - Walkway to Mechanical Room 19B | N/A | Cement Floor | | Non Suspect ACM | 369 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | B | Room 19B - Mechanical Room | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 400 | LF | 0 | LF | | | | N/A | N/A | N/A | |
| 1 | B | Room 19B - Mechanical Room | N/A | Fiberglass Duct Insulation | | Non Suspect ACM | 160 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | B | Room 19B - Mechanical Room | N/A | Concrete Ceiling | | Non Suspect ACM | 2014 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | B | Room 19B - Mechanical Room | N/A | Plaster Walls | | NAD | 2500 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | B | Room 19B - Mechanical Room | N/A | Cement Floor | | Non Suspect ACM | 2014 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | B | Mechanical Room Storage | N/A | Concrete Ceiling | | Non Suspect ACM | 160 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | B | Mechanical Room Storage | N/A | Plaster Walls | | NAD | 500 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | B | Mechanical Room Storage | N/A | Cement Floor | | Non Suspect ACM | 160 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | B | Storage inside Room 037 | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 30 | LF | 0 | LF | | | | N/A | N/A | N/A | |
| 1 | B | Storage inside Room 037 | N/A | Plaster Ceiling | | NAD | 680 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | B | Storage inside Room 037 | N/A | Plaster Walls | | NAD | 1000 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | B | Storage inside Room 037 | N/A | Cement Floor | | Non Suspect ACM | 680 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | B | Transformer Room at the end of Mechanical Rooms Hallway | N/A | Concrete Ceiling | | Non Suspect ACM | 960 | SF | 0 | SF | | | | N/A | N/A | N/A | |

6010 Central HS - 2015 2016 AHERA Three-Year Report.xls

| School District of Philadelphia Central High School 1700 W. Olney Avenue, Philadelphia, PA 19141 ULCS# 6010 Year Built: 1939 | | AHERA Three-Year Reinspection 2015-2016 Room by Room Location Log Report | | | | | | | | | | Reinspection Date: 7/5/2016 Building Inspector: Ananth K. Vinjamuri Number: 374 Management Planner: Mary Anne Lerro Number: 742327 | | | |
|--|-----------------------|---|-----------------|---------------------------------|---------------|--|-------------------------------|------------------|----------|------------------------|----------------------------|--|-----------------------|--------------------|----------------------|
| E l e m e n t | F l o o r | On Site Room Name | System Affected | Material Description | HID# | Confirmed, Assumed, NAD, Non Suspect ACM | Amount of Material (SF/LF/EA) | Amount of Damage | SF LF EA | Color required for VAT | Comments/Description/Notes | Attic/Crawlsp ace Ranking | Damage Potential (DP) | Newly Friable (NF) | Response Action (RA) |
| 1 | B | Transformer Room at the end of Mechanical Rooms Hallway | N/A | Brick Wall | | Non Suspect ACM | 1200 | SF | 0 | SF | | | N/A | N/A | N/A |
| 1 | B | Transformer Room at the end of Mechanical Rooms Hallway | N/A | Cement Floor | | Non Suspect ACM | 960 | SF | 0 | SF | | | N/A | N/A | N/A |
| 1 | B | Pump Room at the end of Mechanical Rooms Hallway | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 200 | LF | 0 | LF | | | N/A | N/A | N/A |
| 1 | B | Pump Room at the end of Mechanical Rooms Hallway | N/A | Fiberglass Tank Insulation | | Non Suspect ACM | 250 | SF | 0 | SF | | | N/A | N/A | N/A |
| 1 | B | Pump Room at the end of Mechanical Rooms Hallway | N/A | Concrete Ceiling | | Non Suspect ACM | 576 | SF | 0 | SF | | | N/A | N/A | N/A |
| 1 | B | Pump Room at the end of Mechanical Rooms Hallway | N/A | Concrete Block Wall | | Non Suspect ACM | 1000 | SF | 0 | SF | | | N/A | N/A | N/A |
| 1 | B | Pump Room at the end of Mechanical Rooms Hallway | N/A | Cement Floor | | Non Suspect ACM | 576 | SF | 0 | SF | | | N/A | N/A | N/A |
| 1 | B | Boiler Room | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 300 | LF | 0 | LF | | | N/A | N/A | N/A |
| 1 | B | Boiler Room | N/A | Concrete Ceiling | | Non Suspect ACM | 5000 | SF | 0 | SF | | | N/A | N/A | N/A |
| 1 | B | Boiler Room | N/A | Concrete Block Wall | | Non Suspect ACM | 7000 | SF | 0 | SF | | | N/A | N/A | N/A |
| 1 | B | Boiler Room | N/A | Cement Floor | | Non Suspect ACM | 5000 | SF | 0 | SF | | | N/A | N/A | N/A |
| 1 | B | Electrical Room across from Building Engineer's Office | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 12 | LF | 0 | LF | | | N/A | N/A | N/A |
| 1 | B | Electrical Room across from Building Engineer's Office | N/A | Concrete Ceiling | | Non Suspect ACM | 720 | SF | 0 | SF | | | N/A | N/A | N/A |
| 1 | B | Electrical Room across from Building Engineer's Office | N/A | Plaster Walls | | NAD | 1200 | SF | 0 | SF | | | N/A | N/A | N/A |
| 1 | B | Electrical Room across from Building Engineer's Office | N/A | Cement Floor | | Non Suspect ACM | 720 | SF | 0 | SF | | | N/A | N/A | N/A |
| 1 | B | Custodial Lounge next to Building Engineer's Office | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 40 | LF | 0 | LF | | | N/A | N/A | N/A |
| 1 | B | Custodial Lounge next to Building Engineer's Office | N/A | Concrete Ceiling | | Non Suspect ACM | 264 | SF | 0 | SF | | | N/A | N/A | N/A |
| 1 | B | Custodial Lounge next to Building Engineer's Office | N/A | Plaster Walls | | NAD | 800 | SF | 0 | SF | | | N/A | N/A | N/A |
| 1 | B | Custodial Lounge next to Building Engineer's Office | N/A | Cement Floor | | Non Suspect ACM | 264 | SF | 0 | SF | | | N/A | N/A | N/A |
| 1 | B | Custodial Lounge Restroom | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 30 | LF | 0 | LF | | | N/A | N/A | N/A |
| 1 | B | Custodial Lounge Restroom | N/A | Concrete Ceiling | | Non Suspect ACM | 96 | SF | 0 | SF | | | N/A | N/A | N/A |
| 1 | B | Custodial Lounge Restroom | N/A | Ceramic Tile Walls | | Non Suspect ACM | 500 | SF | 0 | SF | | | N/A | N/A | N/A |
| 1 | B | Custodial Lounge Restroom | N/A | Ceramic Tile Floors | | Non Suspect ACM | 96 | SF | 0 | SF | | | N/A | N/A | N/A |
| 1 | B | School Store | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 60 | LF | 0 | LF | | | N/A | N/A | N/A |
| 1 | B | School Store | N/A | Fiberglass Ceiling Tile 2' x 4' | | Non Suspect ACM | 720 | SF | 0 | SF | | | N/A | N/A | N/A |
| 1 | B | School Store | N/A | Plaster Walls | | NAD | 1200 | SF | 0 | SF | | | N/A | N/A | N/A |
| 1 | B | School Store | N/A | Cement Floor | | Non Suspect ACM | 720 | SF | 0 | SF | | | N/A | N/A | N/A |
| 1 | B | Storage next to Building Engineer's Office | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 50 | LF | 0 | LF | | | N/A | N/A | N/A |
| 1 | B | Storage next to Building Engineer's Office | N/A | Concrete Ceiling | | Non Suspect ACM | 192 | SF | 0 | SF | | | N/A | N/A | N/A |
| 1 | B | Storage next to Building Engineer's Office | N/A | Plaster Walls | | NAD | 700 | SF | 0 | SF | | | N/A | N/A | N/A |
| 1 | B | Storage next to Building Engineer's Office | N/A | Cement Floor | | Non Suspect ACM | 192 | SF | 0 | SF | | | N/A | N/A | N/A |
| 1 | B | Robotics Office | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 250 | LF | 0 | LF | | | N/A | N/A | N/A |
| 1 | B | Robotics Office | N/A | Concrete Ceiling | | Non Suspect ACM | 750 | SF | 0 | SF | | | N/A | N/A | N/A |
| 1 | B | Robotics Office | N/A | Plaster Walls | | NAD | 1200 | SF | 0 | SF | | | N/A | N/A | N/A |
| 1 | B | Robotics Office | M | Floor Tile VAT 12' x 12" | 6010/01/0B/TT | Assumed | 750 | SF | 0 | SF | Grey | | 1 | No | 1/D |
| 1 | B | Building Engineer's Office | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 12 | LF | 0 | LF | | | N/A | N/A | N/A |
| 1 | B | Building Engineer's Office | N/A | Fiberglass Ceiling Tile 2' x 4' | | Non Suspect ACM | 336 | SF | 0 | SF | | | N/A | N/A | N/A |
| 1 | B | Building Engineer's Office | N/A | Plaster Walls | | NAD | 700 | SF | 0 | SF | | | N/A | N/A | N/A |
| 1 | B | Building Engineer's Office | M | Floor Tile VAT 9' x 9" | 6010/01/0B/40 | Confirmed | 336 | SF | 0 | SF | Grey | | 1 | No | 1/D |
| 1 | B | Men's Locker Room next to Building Engineer's Office | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 80 | LF | 0 | LF | | | N/A | N/A | N/A |
| 1 | B | Men's Locker Room next to Building Engineer's Office | N/A | Concrete Ceiling | | Non Suspect ACM | 336 | SF | 0 | SF | | | N/A | N/A | N/A |
| 1 | B | Men's Locker Room next to Building Engineer's Office | N/A | Plaster Walls | | NAD | 700 | SF | 0 | SF | | | N/A | N/A | N/A |
| 1 | B | Men's Locker Room next to Building Engineer's Office | N/A | Cement Floor | | Non Suspect ACM | 336 | SF | 0 | SF | | | N/A | N/A | N/A |
| 1 | B | Restroom in Men's Locker Room | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 30 | LF | 0 | LF | | | N/A | N/A | N/A |
| 1 | B | Restroom in Men's Locker Room | N/A | Plaster Ceiling | | NAD | 70 | SF | 0 | SF | | | N/A | N/A | N/A |
| 1 | B | Restroom in Men's Locker Room | N/A | Ceramic Tile Walls | | Non Suspect ACM | 300 | SF | 0 | SF | | | N/A | N/A | N/A |
| 1 | B | Restroom in Men's Locker Room | N/A | Ceramic Tile Floors | | Non Suspect ACM | 70 | SF | 0 | SF | | | N/A | N/A | N/A |
| 1 | B | Fan Room next to Men's Locker Room | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 200 | LF | 0 | LF | | | N/A | N/A | N/A |
| 1 | B | Fan Room next to Men's Locker Room | N/A | Concrete Ceiling | | Non Suspect ACM | 400 | SF | 0 | SF | | | N/A | N/A | N/A |
| 1 | B | Fan Room next to Men's Locker Room | N/A | Plaster Walls | | NAD | 800 | SF | 0 | SF | | | N/A | N/A | N/A |
| 1 | B | Fan Room next to Men's Locker Room | N/A | Cement Floor | | Non Suspect ACM | 400 | SF | 0 | SF | | | N/A | N/A | N/A |
| 1 | B | Fan Room next to Men's Locker Room | T | Vibration Damper Cloth | 6010/01/0B/EE | Assumed | 30 | SF | 0 | SF | | | 1 | No | 1/D |
| 1 | B | Girl's Restroom in the Main Hallway | N/A | Plaster Ceiling | | NAD | 300 | SF | 0 | SF | | | N/A | N/A | N/A |
| 1 | B | Girl's Restroom in the Main Hallway | N/A | Ceramic Tile Walls | | Non Suspect ACM | 700 | SF | 0 | SF | | | N/A | N/A | N/A |
| 1 | B | Girl's Restroom in the Main Hallway | N/A | Ceramic Tile Floors | | Non Suspect ACM | 300 | SF | 0 | SF | | | N/A | N/A | N/A |
| 1 | B | Boy's Restroom in the Main Hallway | N/A | Plaster Ceiling | | NAD | 300 | SF | 0 | SF | | | N/A | N/A | N/A |
| 1 | B | Boy's Restroom in the Main Hallway | N/A | Ceramic Tile Walls | | Non Suspect ACM | 700 | SF | 0 | SF | | | N/A | N/A | N/A |
| 1 | B | Boy's Restroom in the Main Hallway | N/A | Ceramic Tile Floors | | Non Suspect ACM | 300 | SF | 0 | SF | | | N/A | N/A | N/A |
| 1 | B | Custodial Storage between Restrooms | N/A | Plaster Ceiling | | NAD | 24 | SF | 0 | SF | | | N/A | N/A | N/A |
| 1 | B | Custodial Storage between Restrooms | N/A | Ceramic Tile Walls | | Non Suspect ACM | 200 | SF | 0 | SF | | | N/A | N/A | N/A |
| 1 | B | Custodial Storage between Restrooms | N/A | Ceramic Tile Floors | | Non Suspect ACM | 24 | SF | 0 | SF | | | N/A | N/A | N/A |
| 1 | B | Room 37-Costume Room across from Boy's Restroom | N/A | Plaster Ceiling | | NAD | 841 | SF | 0 | SF | | | N/A | N/A | N/A |
| 1 | B | Room 37-Costume Room across from Boy's Restroom | N/A | Plaster Walls | | NAD | 1200 | SF | 0 | SF | | | N/A | N/A | N/A |
| 1 | B | Room 37-Costume Room across from Boy's Restroom | N/A | Cement Floor | | Non Suspect ACM | 841 | SF | 0 | SF | | | N/A | N/A | N/A |

6010 Central HS - 2015 2016 AHERA Three-Year Report.xls

| School District of Philadelphia Central High School 1700 W. Olney Avenue, Philadelphia, PA 19141 ULCS# 6010 Year Built: 1939 | | AHERA Three-Year Reinspection 2015-2016 Room by Room Location Log Report | | | | | | | | | | Reinspection Date: 7/5/2016 Building Inspector: Ananth K. Vinjamuri Number: 374 Management Planner: Mary Anne Lerro Number: 742327 | | | | |
|--|-----------------------|---|-----------------|---------------------------------|-----------------------|--|--------------------|------------|------------------|----------|------------------------|--|------------------------------|-----------------------|--------------------|----------------------|
| E l e m e n t | F l o o r | On Site Room Name | System Affected | Material Description | HID# | Confirmed, Assumed, NAD, Non Suspect ACM | Amount of Material | (SF/LF/EA) | Amount of Damage | SF LF EA | Color required for VAT | Comments/Description/Notes | Attic/Crawlsp ace Ranking | Damage Potential (DP) | Newly Friable (NF) | Response Action (RA) |
| 1 | B | Room 1 - Art Room | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 75 | LF | 0 | LF | | | | N/A | N/A | N/A |
| 1 | B | Room 1 - Art Room | N/A | Fiberglass Duct Insulation | | Non Suspect ACM | 800 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | B | Room 1 - Art Room | N/A | Concrete Ceiling | | Non Suspect ACM | 756 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | B | Room 1 - Art Room | N/A | Concrete Block Wall | | Non Suspect ACM | 1000 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | B | Room 1 - Art Room | M | Floor Tile VAT 12" x 12" | 6010/01/0B/TT | Assumed | 700 | SF | 0 | SF | White | | | 1 | No | 1/D |
| 1 | B | Room 1 - Art Room | M | Floor Tile VAT 12" x 12" | 6010/01/0B/TT | Assumed | 56 | SF | 0 | SF | Blue | | | 1 | No | 1/D |
| 1 | B | Room 1 - Art Room | T | Vibration Damper Cloth | 6010/01/0B/EE | Assumed | 6 | SF | 0 | SF | | | | 1 | No | 1/D |
| 1 | B | Paint Room | M | Kiln Bricks | 6010/01/0B/GC/AV/1650 | Assumed | 90 | SF | 0 | SF | | | | 1 | No | 1/D |
| 1 | B | Paint Room | S | Plaster Ceiling | | NAD | 120 | SF | 0 | SF | | | | 1 | No | 1/D |
| 1 | B | Paint Room | N/A | Concrete Block Wall | | Non Suspect ACM | 400 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | B | Paint Room | N/A | Cement Floor | | Non Suspect ACM | 120 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | B | Room 3 - Art Room | N/A | Fiberglass Duct Insulation | | Non Suspect ACM | 2016 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | B | Room 3 - Art Room | N/A | Concrete Ceiling | | Non Suspect ACM | 1728 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | B | Room 3 - Art Room | N/A | Concrete Block Wall | | Non Suspect ACM | 1600 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | B | Room 3 - Art Room | M | Floor Tile VAT 12" x 12" | 6010/01/0B/TT | Assumed | 1628 | SF | 0 | SF | White | | | 1 | No | 1/D |
| 1 | B | Room 3 - Art Room | M | Floor Tile VAT 12" x 12" | 6010/01/0B/TT | Assumed | 100 | SF | 0 | SF | Blue | | | 1 | No | 1/D |
| 1 | B | Dark Room | N/A | Ceiling Tile 2' x 4' | | NAD | 308 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | B | Dark Room | N/A | Concrete Block Wall | | Non Suspect ACM | 600 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | B | Dark Room | M | Floor Tile VAT 12" x 12" | 6010/01/0B/TT | Assumed | 272 | SF | 0 | SF | White | | | 1 | No | 1/D |
| 1 | B | Dark Room | M | Floor Tile VAT 12" x 12" | 6010/01/0B/TT | Assumed | 36 | SF | 0 | SF | Blue | | | 1 | No | 1/D |
| 1 | B | Art Department Office | N/A | Ceiling Tile 2' x 4' | | NAD | 420 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | B | Art Department Office | N/A | Concrete Block Wall | | Non Suspect ACM | 800 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | B | Art Department Office | M | Floor Tile VAT 12" x 12" | 6010/01/0B/TT | Assumed | 384 | SF | 0 | SF | White | | | 1 | No | 1/D |
| 1 | B | Art Department Office | M | Floor Tile VAT 12" x 12" | 6010/01/0B/TT | Assumed | 36 | SF | 0 | SF | Blue | | | 1 | No | 1/D |
| 1 | B | Art Storage | N/A | Ceiling Tile 2' x 4' | | NAD | 168 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | B | Art Storage | N/A | Concrete Block Wall | | Non Suspect ACM | 500 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | B | Art Storage | M | Floor Tile VAT 12" x 12" | 6010/01/0B/TT | Assumed | 150 | SF | 0 | SF | White | | | 1 | No | 1/D |
| 1 | B | Art Storage | M | Floor Tile VAT 12" x 12" | 6010/01/0B/TT | Assumed | 18 | SF | 0 | SF | Blue | | | 1 | No | 1/D |
| 1 | B | Art Department Computer Room | N/A | Ceiling Tile 2' x 4' | | NAD | 140 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | B | Art Department Computer Room | N/A | Concrete Block Wall | | Non Suspect ACM | 400 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | B | Art Department Computer Room | M | Floor Tile VAT 12" x 12" | 6010/01/0B/TT | Assumed | 122 | SF | 0 | SF | White | | | 1 | No | 1/D |
| 1 | B | Art Department Computer Room | M | Floor Tile VAT 12" x 12" | 6010/01/0B/TT | Assumed | 18 | SF | 0 | SF | Blue | | | 1 | No | 1/D |
| 1 | B | Art Department Computer Room | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 400 | LF | 0 | LF | | | | N/A | N/A | N/A |
| 1 | B | Art Studio | N/A | Fiberglass Duct Insulation | | Non Suspect ACM | 300 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | B | Art Studio | M | Sink Undercoat Mastic | 6010/0B/GC/AV/1602 | Assumed | 4 | SF | 0 | SF | | | | 1 | No | 1/D |
| 1 | B | Art Studio | N/A | Concrete Ceiling | | Non Suspect ACM | 3680 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | B | Art Studio | N/A | Concrete Block Wall | | Non Suspect ACM | 2500 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | B | Art Studio | M | Floor Tile VAT 12" x 12" | 6010/01/0B/TT | Assumed | 3280 | SF | 0 | SF | White | | | 1 | No | 1/D |
| 1 | B | Art Studio | M | Floor Tile VAT 12" x 12" | 6010/01/0B/TT | Assumed | 400 | SF | 0 | SF | Blue | | | 1 | No | 1/D |
| 1 | B | Art Studio | T | Vibration Damper Cloth | 6010/01/0B/EE | Assumed | 6 | SF | 0 | SF | | | | 1 | No | 1/D |
| 1 | B | Room 9 in Art Studio | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 120 | LF | 0 | LF | | | | N/A | N/A | N/A |
| 1 | B | Room 9 in Art Studio | M | Sink Undercoat Mastic | 6010/0B/GC/AV/1602 | Assumed | 4 | SF | 0 | SF | | | | 1 | No | 1/D |
| 1 | B | Room 9 in Art Studio | N/A | Ceiling Tile 2' x 4' | | NAD | 400 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | B | Room 9 in Art Studio | N/A | Concrete Block Wall | | Non Suspect ACM | 800 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | B | Room 9 in Art Studio | M | Floor Tile VAT 12" x 12" | 6010/01/0B/TT | Assumed | 382 | SF | 0 | SF | White | | | 1 | No | 1/D |
| 1 | B | Room 9 in Art Studio | M | Floor Tile VAT 12" x 12" | 6010/01/0B/TT | Assumed | 18 | SF | 0 | SF | Blue | | | 1 | No | 1/D |
| 1 | B | Room 9 in Art Studio | T | Vibration Damper Cloth | 6010/01/0B/EE | Assumed | 6 | SF | 0 | SF | | | | 1 | No | 1/D |
| 1 | B | Room 9 in Art Studio | M | Transite | 6010/01/0B/GC/AV/2305 | Assumed | 12 | SF | 0 | SF | | Counter Tops | | 1 | No | 1/D |
| 1 | B | Art Studio Storage | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 10 | LF | 0 | LF | | | | N/A | N/A | N/A |
| 1 | B | Art Studio Storage | N/A | Fireproofing | 6010/01/0B/GC/AV/0100 | Assumed | 24 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | B | Art Studio Storage | N/A | Plaster Ceiling | | NAD | 24 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | B | Art Studio Storage | N/A | Plaster Walls | | NAD | 300 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | B | Art Studio Storage | M | Floor Tile VAT 12" x 12" | 6010/01/0B/TT | Assumed | 24 | SF | 0 | SF | Brown | | | 1 | No | 1/D |
| 1 | B | Room 11 - Art Storage | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 45 | LF | 0 | LF | | | | N/A | N/A | N/A |
| 1 | B | Room 11 - Art Storage | N/A | Concrete Ceiling | | Non Suspect ACM | 180 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | B | Room 11 - Art Storage | N/A | Concrete Block Wall | | Non Suspect ACM | 500 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | B | Room 11 - Art Storage | N/A | Cement Floor | | Non Suspect ACM | 180 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | B | Room 12 - Art Classroom | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 40 | LF | 0 | LF | | | | N/A | N/A | N/A |
| 1 | B | Room 12 - Art Classroom | M | Sink Undercoat Mastic | 6010/0B/GC/AV/1602 | Assumed | 4 | SF | 0 | SF | | | | 1 | No | 1/D |
| 1 | B | Room 12 - Art Classroom | N/A | Ceiling Tile 2' x 4' | | NAD | 936 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | B | Room 12 - Art Classroom | N/A | Plaster Walls | | NAD | 1200 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | B | Room 12 - Art Classroom | M | Floor Tile VAT 12" x 12" | 6010/01/0B/TT | Assumed | 800 | SF | 0 | SF | White | | | 1 | No | 1/D |
| 1 | B | Room 12 - Art Classroom | M | Floor Tile VAT 12" x 12" | 6010/01/0B/TT | Assumed | 136 | SF | 0 | SF | Blue | | | 1 | No | 1/D |
| 1 | B | Room 12 - Art Classroom | M | Blackboard Glue Dots | 6010/01/0B/GC/AV/2600 | Assumed | 200 | SF | 0 | SF | | | | 1 | No | 1/D |
| 1 | B | Room 13 - Classroom | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 24 | LF | 0 | LF | | | | N/A | N/A | N/A |
| 1 | B | Room 13 - Classroom | N/A | Fiberglass Ceiling Tile 2' x 4' | | Non Suspect ACM | 696 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | B | Room 13 - Classroom | N/A | Plaster Walls | | NAD | 1000 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | B | Room 13 - Classroom | N/A | Cement Floor | | Non Suspect ACM | 696 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | B | Gym Storage | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 50 | LF | 0 | LF | | | | N/A | N/A | N/A |
| 1 | B | Gym Storage | N/A | Concrete Ceiling | | Non Suspect ACM | 336 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | B | Gym Storage | N/A | Plaster Walls | | NAD | 1000 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | B | Gym Storage | N/A | Cement Floor | | Non Suspect ACM | 336 | SF | 0 | SF | | | | N/A | N/A | N/A |

6010 Central HS - 2015 2016 AHERA Three-Year Report.xls

| School District of Philadelphia Central High School 1700 W. Olney Avenue, Philadelphia, PA 19141 ULCS# 6010 Year Built: 1939 | | AHERA Three-Year Reinspection 2015-2016 Room by Room Location Log Report | | | | | | | | | | Reinspection Date: 7/5/2016 Building Inspector: Ananth K. Vinjamuri Number: 374 Management Planner: Mary Anne Lerro Number: 742327 | | | | |
|--|-----------------------|---|-----------------|----------------------------|-----------------------|--|--------------------|------------|------------------|----------|------------------------|--|------------------------------|-----------------------|--------------------|----------------------|
| E l e m e n t | F l o o r | On Site Room Name | System Affected | Material Description | HID# | Confirmed, Assumed, NAD, Non Suspect ACM | Amount of Material | (SF/LF/EA) | Amount of Damage | SF LF EA | Color required for VAT | Comments/Description/Notes | Attic/Crawlsp ace Ranking | Damage Potential (DP) | Newly Friable (NF) | Response Action (RA) |
| 1 | B | Planetorium Room | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 50 | LF | 0 | LF | | | | N/A | N/A | N/A |
| 1 | B | Planetorium Room | N/A | Concrete Ceiling | | Non Suspect ACM | 540 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | B | Planetorium Room | N/A | Plaster Walls | | NAD | 900 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | B | Planetorium Room | M | Floor Tile VAT 9" x 9" | 6010/01/0B/40 | Confirmed | 540 | SF | 0 | SF | Black | | | 1 | No | 1/D |
| 1 | B | Gym Extra Room | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 130 | LF | 0 | LF | | | | N/A | N/A | N/A |
| 1 | B | Gym Extra Room | N/A | Concrete Ceiling | | Non Suspect ACM | 3080 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | B | Gym Extra Room | N/A | Sheetrock Ceiling | 1610/01/0B/GC/AV/2101 | Assumed | 750 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | B | Gym Extra Room | N/A | Plaster Walls | | NAD | 3000 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | B | Gym Extra Room | N/A | Sheetrock Wall | 6010/01/0B/GC/AV/2100 | Assumed | 1000 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | B | Gym Extra Room | N/A | Cement Floor | | Non Suspect ACM | 3080 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | B | Weight Room in Gym Extra Room | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 110 | LF | 0 | LF | | | | N/A | N/A | N/A |
| 1 | B | Weight Room in Gym Extra Room | N/A | Concrete Ceiling | | Non Suspect ACM | 1500 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | B | Weight Room in Gym Extra Room | N/A | Plaster Walls | | NAD | 1200 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | B | Weight Room in Gym Extra Room | N/A | Sheetrock Wall | 6010/01/0B/GC/AV/2100 | Assumed | 1200 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | B | Weight Room in Gym Extra Room | N/A | Cement Floor | | Non Suspect ACM | 1500 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | B | Room 82 - Chemistry Lab | N/A | Ceiling Tile 2' x 4' | | NAD | 1320 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | B | Room 82 - Chemistry Lab | N/A | Plaster Ceiling | | NAD | 1320 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | B | Room 82 - Chemistry Lab | N/A | Plaster Walls | | NAD | 800 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | B | Room 82 - Chemistry Lab | N/A | Concrete Block Wall | | Non Suspect ACM | 800 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | B | Room 82 - Chemistry Lab | M | Floor Tile VAT 12" x 12" | 6010/01/0B/TT | Assumed | 1020 | SF | 0 | SF | White | | | 1 | No | 1/D |
| 1 | B | Room 82 - Chemistry Lab | M | Floor Tile VAT 12" x 12" | 6010/01/0B/TT | Assumed | 300 | SF | 0 | SF | Blue | | | 1 | No | 1/D |
| 1 | B | Room 82 - Chemistry Lab | M | Transite | 6010/01/0B/GC/AV/2305 | Assumed | 50 | SF | 0 | SF | | Lab Hoods | | 1 | No | 1/D |
| 1 | B | Room 82 - Chemistry Lab | M | Blackboard Glue Dots | 6010/01/0B/GC/AV/2600 | Assumed | 200 | SF | 0 | SF | | | | 1 | No | 1/D |
| 1 | B | Room 80 - Book Closet next to Room 82 | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 120 | LF | 0 | LF | | | | N/A | N/A | N/A |
| 1 | B | Room 80 - Book Closet next to Room 82 | N/A | Plaster Ceiling | | NAD | 675 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | B | Room 80 - Book Closet next to Room 82 | N/A | Concrete Block Wall | | Non Suspect ACM | 1200 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | B | Room 80 - Book Closet next to Room 82 | M | Floor Tile VAT 12" x 12" | 6010/01/0B/TT | Assumed | 675 | SF | 0 | SF | White | | | 1 | No | 1/D |
| 1 | B | Room 81 - Materials Closet next to Room 82 | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 15 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | B | Room 81 - Materials Closet next to Room 82 | N/A | Plaster Ceiling | | NAD | 300 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | B | Room 81 - Materials Closet next to Room 82 | N/A | Concrete Block Wall | | Non Suspect ACM | 700 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | B | Room 81 - Materials Closet next to Room 82 | M | Floor Tile VAT 12" x 12" | 6010/01/0B/TT | Assumed | 300 | SF | 0 | SF | White | | | 1 | No | 1/D |
| 1 | B | Room 83 - Lab Prep Room | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 12 | LF | 0 | LF | | | | N/A | N/A | N/A |
| 1 | B | Room 83 - Lab Prep Room | N/A | Ceiling Tile 2' x 4' | | NAD | 288 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | B | Room 83 - Lab Prep Room | N/A | Plaster Ceiling | | NAD | 288 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | B | Room 83 - Lab Prep Room | N/A | Plaster Walls | | NAD | 250 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | B | Room 83 - Lab Prep Room | N/A | Concrete Block Wall | | Non Suspect ACM | 250 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | B | Room 83 - Lab Prep Room | M | Floor Tile VAT 12" x 12" | 6010/01/0B/TT | Assumed | 288 | SF | 0 | SF | White | | | 1 | No | 1/D |
| 1 | B | Room 84 - Chemistry Lab | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 12 | LF | 0 | LF | | | | N/A | N/A | N/A |
| 1 | B | Room 84 - Chemistry Lab | N/A | Ceiling Tile 2' x 4' | | NAD | 1248 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | B | Room 84 - Chemistry Lab | N/A | Plaster Ceiling | | NAD | 1248 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | B | Room 84 - Chemistry Lab | N/A | Plaster Walls | | NAD | 700 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | B | Room 84 - Chemistry Lab | N/A | Concrete Block Wall | | Non Suspect ACM | 700 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | B | Room 84 - Chemistry Lab | M | Floor Tile VAT 12" x 12" | 6010/01/0B/TT | Assumed | 1248 | SF | 0 | SF | White | | | 1 | No | 1/D |
| 1 | B | Room 84 - Chemistry Lab | M | Transite | 6010/01/0B/GC/AV/2305 | Assumed | 50 | SF | 0 | SF | | Lab Hoods and Test Tube holder | | 1 | No | 1/D |
| 1 | B | Room 84 - Chemistry Lab | M | Blackboard Glue Dots | 6010/01/0B/GC/AV/2600 | Assumed | 200 | SF | 0 | SF | | | | 1 | No | 1/D |
| 1 | B | Room 85 - Chemistry Lab | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 20 | LF | 0 | LF | | | | N/A | N/A | N/A |
| 1 | B | Room 85 - Chemistry Lab | N/A | Ceiling Tile 2' x 4' | | NAD | 1560 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | B | Room 85 - Chemistry Lab | N/A | Plaster Ceiling | | NAD | 1560 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | B | Room 85 - Chemistry Lab | N/A | Plaster Walls | | NAD | 900 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | B | Room 85 - Chemistry Lab | N/A | Concrete Block Wall | | Non Suspect ACM | 900 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | B | Room 85 - Chemistry Lab | M | Floor Tile VAT 12" x 12" | 6010/01/0B/TT | Assumed | 1060 | SF | 0 | SF | White | | | 1 | No | 1/D |
| 1 | B | Room 85 - Chemistry Lab | M | Floor Tile VAT 12" x 12" | 6010/01/0B/TT | Assumed | 500 | SF | 0 | SF | Blue | | | 1 | No | 1/D |
| 1 | B | Room 85 - Chemistry Lab | M | Transite | 6010/01/0B/GC/AV/2305 | Assumed | 50 | SF | 0 | SF | | | | 1 | No | 1/D |
| 1 | B | Room 85 - Chemistry Lab | M | Blackboard Glue Dots | 6010/01/0B/GC/AV/2600 | Assumed | 200 | SF | 0 | SF | | | | 1 | No | 1/D |
| 1 | B | Room 85 Storage | N/A | Ceiling Tile 2' x 4' | | NAD | 228 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | B | Room 85 Storage | N/A | Plaster Ceiling | | NAD | 228 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | B | Room 85 Storage | N/A | Plaster Walls | | NAD | 300 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | B | Room 85 Storage | N/A | Concrete Block Wall | | Non Suspect ACM | 300 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | B | Room 85 Storage | M | Floor Tile VAT 12" x 12" | 6010/01/0B/TT | Assumed | 170 | SF | 0 | SF | White | | | 1 | No | 1/D |
| 1 | B | Room 85 Storage | M | Floor Tile VAT 12" x 12" | 6010/01/0B/TT | Assumed | 58 | SF | 0 | SF | Blue | | | 1 | No | 1/D |
| 1 | B | Room 85 Storage | N/A | Ceiling Tile 2' x 4' | | NAD | 96 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | B | Room 85 Storage | N/A | Plaster Ceiling | | NAD | 96 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | B | Room 85 Storage | N/A | Plaster Walls | | NAD | 100 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | B | Room 85 Storage | N/A | Concrete Block Wall | | Non Suspect ACM | 100 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | B | Room 85 Storage | M | Floor Tile VAT 12" x 12" | 6010/01/0B/TT | Assumed | 60 | SF | 0 | SF | White | | | 1 | No | 1/D |
| 1 | B | Room 85 Storage | M | Floor Tile VAT 12" x 12" | 6010/01/0B/TT | Assumed | 36 | SF | 0 | SF | Blue | | | 1 | No | 1/D |
| 1 | B | Custodial Storage in Hallway at Room 82 | N/A | Concrete Ceiling | | Non Suspect ACM | 24 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | B | Custodial Storage in Hallway at Room 82 | N/A | Concrete Block Wall | | Non Suspect ACM | 200 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | B | Custodial Storage in Hallway at Room 82 | N/A | Cement Floor | | Non Suspect ACM | 24 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | B | Custodial Storage in Hallway at Room 86 | N/A | Concrete Ceiling | | Non Suspect ACM | 24 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | B | Custodial Storage in Hallway at Room 86 | N/A | Concrete Block Wall | | Non Suspect ACM | 200 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | B | Custodial Storage in Hallway at Room 86 | N/A | Cement Floor | | Non Suspect ACM | 24 | SF | 0 | SF | | | | N/A | N/A | N/A |

6010 Central HS - 2015 2016 AHERA Three-Year Report.xls

| School District of Philadelphia Central High School 1700 W. Olney Avenue, Philadelphia, PA 19141 ULCS# 6010 Year Built: 1939 | | AHERA Three-Year Reinspection 2015-2016 Room by Room Location Log Report | | | | | | | | | | Reinspection Date: 7/5/2016 Building Inspector: Ananth K. Vinjamuri Number: 374 Management Planner: Mary Anne Lerro Number: 742327 | | | | |
|--|-----------------------|---|-----------------|---------------------------------|-----------------------|--|--------------------|------------|------------------|----------|------------------------|--|------------------------------|-----------------------|--------------------|----------------------|
| E l e m e n t | F l o o r | On Site Room Name | System Affected | Material Description | HID# | Confirmed, Assumed, NAD, Non Suspect ACM | Amount of Material | (SF/LF/EA) | Amount of Damage | SF LF EA | Color required for VAT | Comments/Description/Notes | Attic/Crawlsp ace Ranking | Damage Potential (DP) | Newly Friable (NF) | Response Action (RA) |
| 1 | B | Room 89 - Chemistry Lab | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 20 | LF | 0 | LF | | | | N/A | N/A | N/A |
| 1 | B | Room 89 - Chemistry Lab | N/A | Ceiling Tile 2' x 4' | | NAD | 1320 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | B | Room 89 - Chemistry Lab | N/A | Plaster Ceiling | | NAD | 1320 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | B | Room 89 - Chemistry Lab | N/A | Plaster Walls | | NAD | 800 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | B | Room 89 - Chemistry Lab | N/A | Concrete Block Wall | | Non Suspect ACM | 800 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | B | Room 89 - Chemistry Lab | M | Floor Tile VAT 12" x 12" | 6010/01/0B/TT | Assumed | 1200 | SF | 0 | SF | White | | | 1 | No | 1/D |
| 1 | B | Room 89 - Chemistry Lab | M | Floor Tile VAT 12" x 12" | 6010/01/0B/TT | Assumed | 120 | SF | 0 | SF | Blue | | | 1 | No | 1/D |
| 1 | B | Room 89 - Chemistry Lab | M | Transite | 6010/01/0B/GC/AV/2305 | Assumed | 50 | SF | 0 | SF | | Lab Hood | | 1 | No | 1/D |
| 1 | B | Room 89 - Chemistry Lab | M | Blackboard Glue Dots | 6010/01/0B/GC/AV/2600 | Assumed | 200 | SF | 0 | SF | | | | 1 | No | 1/D |
| 1 | B | Room 89 Storage | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 16 | EA | 0 | EA | | | | N/A | N/A | N/A |
| 1 | B | Room 89 Storage | N/A | Ceiling Tile 2' x 4' | | NAD | 288 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | B | Room 89 Storage | N/A | Plaster Ceiling | | NAD | 288 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | B | Room 89 Storage | N/A | Plaster Walls | | NAD | 350 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | B | Room 89 Storage | N/A | Concrete Block Wall | | Non Suspect ACM | 350 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | B | Room 89 Storage | M | Floor Tile VAT 12" x 12" | 6010/01/0B/TT | Assumed | 228 | SF | 0 | SF | White | | | 1 | No | 1/D |
| 1 | B | Room 89 Storage | M | Floor Tile VAT 12" x 12" | 6010/01/0B/TT | Assumed | 60 | SF | 0 | SF | Blue | | | 1 | No | 1/D |
| 1 | B | Room 89 Storage | M | Transite | 6010/01/0B/GC/AV/2305 | Assumed | 50 | SF | 0 | SF | | | | 1 | No | 1/D |
| 1 | B | Room 91 - Work Room | N/A | Ceiling Tile 2' x 4' | | NAD | 176 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | B | Room 91 - Work Room | N/A | Plaster Ceiling | | NAD | 176 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | B | Room 91 - Work Room | N/A | Plaster Walls | | NAD | 250 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | B | Room 91 - Work Room | N/A | Concrete Block Wall | | Non Suspect ACM | 250 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | B | Room 91 - Work Room | M | Floor Tile VAT 12" x 12" | 6010/01/0B/TT | Assumed | 140 | SF | 0 | SF | White | | | 1 | No | 1/D |
| 1 | B | Room 91 - Work Room | M | Floor Tile VAT 12" x 12" | 6010/01/0B/TT | Assumed | 36 | SF | 0 | SF | Blue | | | 1 | No | 1/D |
| 1 | B | Room 91 Restroom | N/A | Fiberglass Ceiling Tile 2' x 4' | | Non Suspect ACM | 25 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | B | Room 91 Restroom | N/A | Plaster Ceiling | | NAD | 25 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | B | Room 91 Restroom | N/A | Plaster Walls | | NAD | 100 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | B | Room 91 Restroom | N/A | Concrete Block Wall | | Non Suspect ACM | 100 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | B | Room 91 Restroom | M | Floor Tile VAT 12" x 12" | 6010/01/0B/TT | Assumed | 15 | SF | 0 | SF | White | | | 1 | No | 1/D |
| 1 | B | Room 91 Restroom | M | Floor Tile VAT 12" x 12" | 6010/01/0B/TT | Assumed | 10 | SF | 0 | SF | Blue | | | 1 | No | 1/D |
| 1 | B | Room 94 Restroom | N/A | Fiberglass Ceiling Tile 2' x 4' | | Non Suspect ACM | 32 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | B | Room 94 Restroom | N/A | Plaster Ceiling | | NAD | 32 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | B | Room 94 Restroom | N/A | Plaster Walls | | NAD | 100 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | B | Room 94 Restroom | N/A | Concrete Block Wall | | Non Suspect ACM | 100 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | B | Room 94 Restroom | N/A | Floor Tile VAT 12" x 12" | 6010/01/0B/TT | Assumed | 20 | SF | 0 | SF | White | | | N/A | N/A | N/A |
| 1 | B | Room 94 Restroom | N/A | Floor Tile VAT 12" x 12" | 6010/01/0B/TT | Assumed | 12 | SF | 0 | SF | Blue | | | N/A | N/A | N/A |
| 1 | B | Room 94 - Department Office | N/A | Ceiling Tile 2' x 4' | | NAD | 150 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | B | Room 94 - Department Office | N/A | Plaster Ceiling | | NAD | 150 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | B | Room 94 - Department Office | N/A | Plaster Walls | | NAD | 200 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | B | Room 94 - Department Office | N/A | Concrete Block Wall | | Non Suspect ACM | 200 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | B | Room 94 - Department Office | M | Floor Tile VAT 12" x 12" | 6010/01/0B/TT | Assumed | 100 | SF | 0 | SF | White | | | 1 | No | 1/D |
| 1 | B | Room 94 - Department Office | M | Floor Tile VAT 12" x 12" | 6010/01/0B/TT | Assumed | 50 | SF | 0 | SF | Blue | | | 1 | No | 1/D |
| 1 | B | Room 94 Storage | N/A | Ceiling Tile 2' x 4' | | NAD | 15 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | B | Room 94 Storage | N/A | Plaster Ceiling | | NAD | 15 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | B | Room 94 Storage | N/A | Plaster Walls | | NAD | 60 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | B | Room 94 Storage | N/A | Concrete Block Wall | | Non Suspect ACM | 60 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | B | Room 94 Storage | M | Floor Tile VAT 12" x 12" | 6010/01/0B/TT | Assumed | 10 | SF | 0 | SF | White | | | 1 | No | 1/D |
| 1 | B | Room 94 Storage | M | Floor Tile VAT 12" x 12" | 6010/01/0B/TT | Assumed | 5 | SF | 0 | SF | Blue | | | 1 | No | 1/D |
| 1 | B | Room 95 - Physics Lab | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 36 | LF | 0 | LF | | | | N/A | N/A | N/A |
| 1 | B | Room 95 - Physics Lab | N/A | Ceiling Tile 2' x 4' | | NAD | 1232 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | B | Room 95 - Physics Lab | N/A | Plaster Ceiling | | NAD | 1232 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | B | Room 95 - Physics Lab | N/A | Plaster Walls | | NAD | 750 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | B | Room 95 - Physics Lab | N/A | Concrete Block Wall | | Non Suspect ACM | 750 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | B | Room 95 - Physics Lab | M | Floor Tile VAT 12" x 12" | 6010/01/0B/TT | Assumed | 1000 | SF | 0 | SF | White | | | 1 | No | 1/D |
| 1 | B | Room 95 - Physics Lab | M | Floor Tile VAT 12" x 12" | 6010/01/0B/TT | Assumed | 232 | SF | 0 | SF | Blue | | | 1 | No | 1/D |
| 1 | B | Room 96 - Lab Prep Room | N/A | Ceiling Tile 2' x 4' | | NAD | 264 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | B | Room 96 - Lab Prep Room | N/A | Plaster Ceiling | | NAD | 264 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | B | Room 96 - Lab Prep Room | N/A | Plaster Walls | | NAD | 300 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | B | Room 96 - Lab Prep Room | N/A | Concrete Block Wall | | Non Suspect ACM | 300 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | B | Room 96 - Lab Prep Room | M | Floor Tile VAT 12" x 12" | 6010/01/0B/TT | Assumed | 220 | SF | 0 | SF | White | | | 1 | No | 1/D |
| 1 | B | Room 96 - Lab Prep Room | M | Floor Tile VAT 12" x 12" | 6010/01/0B/TT | Assumed | 44 | SF | 0 | SF | Blue | | | 1 | No | 1/D |
| 1 | B | Room 97 - Physics Lab | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 65 | LF | 0 | LF | | | | N/A | N/A | N/A |
| 1 | B | Room 97 - Physics Lab | N/A | Ceiling Tile 2' x 4' | | NAD | 1364 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | B | Room 97 - Physics Lab | N/A | Plaster Walls | | NAD | 800 | SF | 40 | SF | | Effervescence and debris | | N/A | N/A | N/A |
| 1 | B | Room 97 - Physics Lab | N/A | Concrete Block Wall | | Non Suspect ACM | 800 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | B | Room 97 - Physics Lab | M | Floor Tile VAT 12" x 12" | 6010/01/0B/TT | Assumed | 1256 | SF | 0 | SF | White | | | 1 | No | 1/D |
| 1 | B | Room 97 - Physics Lab | M | Floor Tile VAT 12" x 12" | 6010/01/0B/TT | Assumed | 108 | SF | 0 | SF | Blue | | | 1 | No | 1/D |
| 1 | B | Room 98 - Physics Lab | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 40 | LF | 0 | LF | | | | N/A | N/A | N/A |
| 1 | B | Room 98 - Physics Lab | N/A | Ceiling Tile 2' x 4' | | NAD | 1320 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | B | Room 98 - Physics Lab | N/A | Plaster Ceiling | | NAD | 1320 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | B | Room 98 - Physics Lab | N/A | Plaster Walls | | NAD | 800 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | B | Room 98 - Physics Lab | N/A | Concrete Block Wall | | Non Suspect ACM | 800 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | B | Room 98 - Physics Lab | M | Floor Tile VAT 12" x 12" | 6010/01/0B/TT | Assumed | 1000 | SF | 0 | SF | White | | | 1 | No | 1/D |

6010 Central HS - 2015 2016 AHERA Three-Year Report.xls

| School District of Philadelphia Central High School 1700 W. Olney Avenue, Philadelphia, PA 19141 ULCS# 6010 Year Built: 1939 | | AHERA Three-Year Reinspection 2015-2016 Room by Room Location Log Report | | | | | | | | | | Reinspection Date: 7/5/2016 Building Inspector: Ananth K. Vinjamuri Number: 374 Management Planner: Mary Anne Lerro Number: 742327 | | | | | |
|--|---|---|-----------------------|---------------------------------|-----------------------|----------------------|------|--|-------------------------------|------------------|----------|--|----------------------------|---------------------------|-----------------------|--------------------|----------------------|
| | | E l e m e n t | F l o o r | On Site Room Name | System Affected | Material Description | HID# | Confirmed, Assumed, NAD, Non Suspect ACM | Amount of Material (SF/LF/EA) | Amount of Damage | SF LF EA | Color required for VAT | Comments/Description/Notes | Attic/Crawlsp ace Ranking | Damage Potential (DP) | Newly Friable (NF) | Response Action (RA) |
| | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | |
| 1 | B | Room 98 - Physics Lab | M | Floor Tile VAT 12" x 12" | 6010/01/0B/TT | Assumed | 320 | SF | 0 | SF | Blue | | | 1 | No | 1/D | |
| 1 | B | Room 99 - Physics Lab | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 70 | LF | 0 | LF | | | | N/A | N/A | N/A | |
| 1 | B | Room 99 - Physics Lab | N/A | Ceiling Tile 2' x 4' | | NAD | 1364 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | B | Room 99 - Physics Lab | N/A | Plaster Ceiling | | NAD | 1364 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | B | Room 99 - Physics Lab | N/A | Plaster Walls | | NAD | 800 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | B | Room 99 - Physics Lab | N/A | Concrete Block Wall | | Non Suspect ACM | 800 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | B | Room 99 - Physics Lab | M | Floor Tile VAT 12" x 12" | 6010/01/0B/TT | Assumed | 1000 | SF | 0 | SF | White | | | 1 | No | 1/D | |
| 1 | B | Room 99 - Physics Lab | M | Floor Tile VAT 12" x 12" | 6010/01/0B/TT | Assumed | 364 | SF | 0 | SF | Blue | | | 1 | No | 1/D | |
| 1 | B | Room 100 - Lab Prep Room | N/A | Ceiling Tile 2' x 4' | | NAD | 264 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | B | Room 100 - Lab Prep Room | N/A | Plaster Ceiling | | NAD | 264 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | B | Room 100 - Lab Prep Room | N/A | Plaster Walls | | NAD | 300 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | B | Room 100 - Lab Prep Room | N/A | Concrete Block Wall | | Non Suspect ACM | 300 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | B | Room 100 - Lab Prep Room | M | Floor Tile VAT 12" x 12" | 6010/01/0B/TT | Assumed | 200 | SF | 0 | SF | White | | | 1 | No | 1/D | |
| 1 | B | Room 100 - Lab Prep Room | M | Floor Tile VAT 12" x 12" | 6010/01/0B/TT | Assumed | 64 | SF | 0 | SF | Blue | | | 1 | No | 1/D | |
| 1 | B | Storage D next to Prep Room 100 | N/A | Plaster Ceiling | | NAD | 40 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | B | Storage D next to Prep Room 100 | N/A | Plaster Walls | | NAD | 200 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | B | Storage D next to Prep Room 100 | N/A | Cement Floor | | Non Suspect ACM | 40 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | B | Weight Room next to Locker Room | N/A | Fiberglass Ceiling Tile 2' x 4' | | Non Suspect ACM | 1500 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | B | Weight Room next to Locker Room | N/A | Concrete Block Wall | | Non Suspect ACM | 1800 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | B | Weight Room next to Locker Room | N/A | Carpet | | Non Suspect ACM | 1500 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | B | Boy's Locker Room Area | N/A | Plaster Ceiling | | NAD | 1008 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | B | Boy's Locker Room Area | N/A | Concrete Block Wall | | Non Suspect ACM | 1300 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | B | Boy's Locker Room Area | N/A | Cement Floor | | Non Suspect ACM | 1008 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | B | Shower Area in Boy's Locker Room | N/A | Plaster Ceiling | | NAD | 377 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | B | Shower Area in Boy's Locker Room | N/A | Concrete Block Wall | | Non Suspect ACM | 500 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | B | Shower Area in Boy's Locker Room | N/A | Cement Floor | | Non Suspect ACM | 377 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | B | Restroom in Boy's Locker Room | N/A | Plaster Ceiling | | NAD | 195 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | B | Restroom in Boy's Locker Room | N/A | Ceramic Tile Walls | | Non Suspect ACM | 400 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | B | Restroom in Boy's Locker Room | N/A | Ceramic Tile Floors | | Non Suspect ACM | 195 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | B | Boy's Locker Room Hallway | N/A | Plaster Ceiling | | NAD | 756 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | B | Boy's Locker Room Hallway | N/A | Concrete Block Wall | | Non Suspect ACM | 2000 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | B | Boy's Locker Room Hallway | N/A | Cement Floor | | Non Suspect ACM | 756 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | B | Girl's Locker Room Area | N/A | Plaster Ceiling | | NAD | 1008 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | B | Girl's Locker Room Area | N/A | Concrete Block Wall | | Non Suspect ACM | 1300 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | B | Girl's Locker Room Area | N/A | Cement Floor | | Non Suspect ACM | 1008 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | B | Shower Area in Girl's Locker Room | N/A | Plaster Ceiling | | NAD | 377 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | B | Shower Area in Girl's Locker Room | N/A | Concrete Block Wall | | Non Suspect ACM | 500 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | B | Shower Area in Girl's Locker Room | N/A | Cement Floor | | Non Suspect ACM | 377 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | B | Restroom in Girl's Locker Room | N/A | Plaster Ceiling | | NAD | 195 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | B | Restroom in Girl's Locker Room | N/A | Ceramic Tile Walls | | Non Suspect ACM | 400 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | B | Restroom in Girl's Locker Room | N/A | Ceramic Tile Floors | | Non Suspect ACM | 195 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | B | Girl's Locker Room Hallway | N/A | Plaster Ceiling | | NAD | 756 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | B | Girl's Locker Room Hallway | N/A | Concrete Block Wall | | Non Suspect ACM | 2000 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | B | Girl's Locker Room Hallway | N/A | Cement Floor | | Non Suspect ACM | 756 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | B | Hallway between Lockers | N/A | Fiberglass Ceiling Tile 2' x 4' | | Non Suspect ACM | 870 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | B | Hallway between Lockers | N/A | Concrete Block Wall | | Non Suspect ACM | 1400 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | B | Hallway between Lockers | N/A | Cement Floor | | Non Suspect ACM | 870 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | B | Health Classroom 50 | N/A | Fiberglass Ceiling Tile 2' x 4' | | Non Suspect ACM | 728 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | B | Health Classroom 50 | N/A | Concrete Block Wall | | Non Suspect ACM | 900 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | B | Health Classroom 50 | M | Floor Tile VAT 12" x 12" | 6010/01/0B/TT | Assumed | 364 | SF | 0 | SF | White | | | 1 | No | 1/D | |
| 1 | B | Health Classroom 50 | M | Floor Tile VAT 12" x 12" | 6010/01/0B/TT | Assumed | 364 | SF | 0 | SF | Blue | | | 1 | No | 1/D | |
| 1 | B | Health Classroom 50 | M | Blackboard Glue Dots | 6010/01/0B/GC/AV/2600 | Assumed | 150 | SF | 0 | SF | | | | 1 | No | 1/D | |
| 1 | B | Health Classroom 51 | N/A | Fiberglass Ceiling Tile 2' x 4' | | Non Suspect ACM | 728 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | B | Health Classroom 51 | N/A | Concrete Block Wall | | Non Suspect ACM | 900 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | B | Health Classroom 51 | M | Floor Tile VAT 12" x 12" | 6010/01/0B/TT | Assumed | 364 | SF | 0 | SF | White | | | 1 | No | 1/D | |
| 1 | B | Health Classroom 51 | M | Floor Tile VAT 12" x 12" | 6010/01/0B/TT | Assumed | 364 | SF | 0 | SF | Blue | | | 1 | No | 1/D | |
| 1 | B | Health Classroom 51 | M | Blackboard Glue Dots | 6010/01/0B/GC/AV/2600 | Assumed | 150 | SF | 0 | SF | | | | 1 | No | 1/D | |
| 1 | B | Staff Restroom Upper Gym Entrance from Street | N/A | Plaster Ceiling | | NAD | 30 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | B | Staff Restroom Upper Gym Entrance from Street | N/A | Concrete Block Wall | | Non Suspect ACM | 150 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | B | Staff Restroom at Upper Gym Entrance from Street | N/A | Cement Floor | | Non Suspect ACM | 30 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | B | Ticket Office at Upper Gym Entrance from Street | N/A | Plaster Ceiling | | NAD | 40 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | B | Ticket Office at Upper Gym Entrance from Street | N/A | Concrete Block Wall | | Non Suspect ACM | 200 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | B | Ticket Office at Upper Gym Entrance from Street | N/A | Cement Floor | | Non Suspect ACM | 40 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | B | Upper Gym Lobby at Street Level | N/A | Plaster Ceiling | | NAD | 1560 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | B | Upper Gym Lobby at Street Level | N/A | Concrete Block Wall | | Non Suspect ACM | 2000 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | B | Upper Gym Lobby at Street Level | N/A | Terrazzo Floor | | Non Suspect ACM | 1560 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | B | Upper Gym Entrance at Street Level | N/A | Plaster Ceiling | | NAD | 272 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | B | Upper Gym Entrance at Street Level | N/A | Concrete Block Wall | | Non Suspect ACM | 700 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | B | Upper Gym Entrance at Street Level | N/A | Cement Floor | | Non Suspect ACM | 272 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | B | Hallway between Health Classrooms | N/A | Plaster Ceiling | | NAD | 342 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | B | Hallway between Health Classrooms | N/A | Concrete Block Wall | | Non Suspect ACM | 750 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | B | Hallway between Health Classrooms | N/A | Cement Floor | | Non Suspect ACM | 342 | SF | 0 | SF | | | | N/A | N/A | N/A | |

6010 Central HS - 2015 2016 AHERA Three-Year Report.xls

| School District of Philadelphia Central High School 1700 W. Olney Avenue, Philadelphia, PA 19141 ULCS# 6010 Year Built: 1939 | | AHERA Three-Year Reinspection 2015-2016 Room by Room Location Log Report | | | | | | | | | | Reinspection Date: 7/5/2016 Building Inspector: Ananth K. Vinjamuri Number: 374 Management Planner: Mary Anne Lerro Number: 742327 | | | | |
|--|------|---|-----------------|---------------------------------|-----------------------|--|--------------------|------------|------------------|----------|------------------------|--|---------------------------|-----------------------|--------------------|----------------------|
| Element | Room | On Site Room Name | System Affected | Material Description | HID# | Confirmed, Assumed, NAD, Non Suspect ACM | Amount of Material | (SF/LF/EA) | Amount of Damage | SF LF EA | Color required for VAT | Comments/Description/Notes | Attic/Crawl space Ranking | Damage Potential (DP) | Newly Friable (NF) | Response Action (RA) |
| 1 | B | Hallway next to Classroom 51 | N/A | Plaster Ceiling | | NAD | 312 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | B | Hallway next to Classroom 51 | N/A | Concrete Block Wall | | Non Suspect ACM | 750 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | B | Hallway next to Classroom 51 | N/A | Cement Floor | | Non Suspect ACM | 312 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | B | Hallway next to Classroom 50 | N/A | Plaster Ceiling | | NAD | 312 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | B | Hallway next to Classroom 50 | N/A | Concrete Block Wall | | Non Suspect ACM | 750 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | B | Hallway next to Classroom 50 | N/A | Cement Floor | | Non Suspect ACM | 312 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | B | Hallway at Art Studio and Planetorium | N/A | Fiberglass Ceiling Tile 2' x 4' | | Non Suspect ACM | 1400 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | B | Hallway at Art Studio and Planetorium | N/A | Plaster Ceiling | | NAD | 1400 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | B | Hallway at Art Studio and Planetorium | N/A | Plaster Walls | | NAD | 1200 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | B | Hallway at Art Studio and Planetorium | N/A | Concrete Block Wall | | Non Suspect ACM | 1200 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | B | Hallway at Art Studio and Planetorium | N/A | Cement Floor | | Non Suspect ACM | 1400 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | B | Main Hallway | N/A | Fiberglass Ceiling Tile 2' x 4' | | Non Suspect ACM | 4004 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | B | Main Hallway | N/A | Plaster Ceiling | | NAD | 4004 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | B | Main Hallway | N/A | Plaster Walls | | NAD | 2500 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | B | Main Hallway | N/A | Concrete Block Wall | | Non Suspect ACM | 2500 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | B | Main Hallway | N/A | Cement Floor | | Non Suspect ACM | 4004 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | B | Hallway at Mechanical Rooms | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 16 | LF | 0 | LF | | | | N/A | N/A | N/A |
| 1 | B | Hallway at Mechanical Rooms | N/A | Fiberglass Ceiling Tile 2' x 4' | | Non Suspect ACM | 1272 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | B | Hallway at Mechanical Rooms | N/A | Plaster Ceiling | | NAD | 1272 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | B | Hallway at Mechanical Rooms | N/A | Plaster Walls | | NAD | 800 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | B | Hallway at Mechanical Rooms | N/A | Concrete Block Wall | | Non Suspect ACM | 800 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | B | Hallway at Mechanical Rooms | N/A | Cement Floor | | Non Suspect ACM | 1272 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | B | Hallway at Science Labs | N/A | Fiberglass Ceiling Tile 2' x 4' | | Non Suspect ACM | 2016 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | B | Hallway at Science Labs | N/A | Plaster Ceiling | | NAD | 2016 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | B | Hallway at Science Labs | N/A | Plaster Walls | | NAD | 1300 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | B | Hallway at Science Labs | N/A | Concrete Block Wall | | Non Suspect ACM | 1300 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | B | Hallway at Science Labs | N/A | Cement Floor | | Non Suspect ACM | 2016 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | B | Stairwell across from Classroom 12 | N/A | Plaster Ceiling | | NAD | 300 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | B | Stairwell across from Classroom 12 | N/A | Plaster Walls | | NAD | 300 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | B | Stairwell across from Classroom 12 | N/A | Concrete Block Wall | | Non Suspect ACM | 500 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | B | Stairwell across from Classroom 12 | N/A | Cement Floor | | Non Suspect ACM | 300 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | B | Stairwell at Gym Extra Room - GX | N/A | Plaster Ceiling | | NAD | 300 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | B | Stairwell at Gym Extra Room - GX | N/A | Plaster Walls | | NAD | 500 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | B | Stairwell at Gym Extra Room - GX | N/A | Concrete Block Wall | | Non Suspect ACM | 500 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | B | Stairwell at Gym Extra Room - GX | N/A | Cement Floor | | Non Suspect ACM | 300 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | B | Stairwell across from Fan Room | N/A | Plaster Ceiling | | NAD | 300 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | B | Stairwell across from Fan Room | N/A | Plaster Walls | | NAD | 500 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | B | Stairwell across from Fan Room | N/A | Concrete Block Wall | | Non Suspect ACM | 500 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | B | Stairwell across from Fan Room | N/A | Cement Floor | | Non Suspect ACM | 300 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | SB | Main Gym | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 1000 | LF | 0 | LF | | | | N/A | N/A | N/A |
| 1 | SB | Main Gym | N/A | Metal Deck Ceiling | | Non Suspect ACM | 8736 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | SB | Main Gym | N/A | Concrete Block Wall | | Non Suspect ACM | 5000 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | SB | Main Gym | N/A | Wood Panel Wall | | Non Suspect ACM | 5000 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | SB | Main Gym | N/A | Wood Floor | | Non Suspect ACM | 8736 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | SB | Right side Gym | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 100 | LF | 0 | LF | | | | N/A | N/A | N/A |
| 1 | SB | Right side Gym | N/A | Metal Deck Ceiling | | Non Suspect ACM | 3948 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | SB | Right side Gym | N/A | Concrete Block Wall | | Non Suspect ACM | 5000 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | SB | Right side Gym | N/A | Wood Panel Wall | | Non Suspect ACM | 2000 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | SB | Right side Gym | N/A | Wood Floor | | Non Suspect ACM | 3948 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | SB | Left side Gym | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 100 | LF | 0 | LF | | | | N/A | N/A | N/A |
| 1 | SB | Left side Gym | N/A | Metal Deck Ceiling | | Non Suspect ACM | 3948 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | SB | Left side Gym | N/A | Concrete Block Wall | | Non Suspect ACM | 5000 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | SB | Left side Gym | N/A | Wood Panel Wall | | Non Suspect ACM | 2000 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | SB | Left side Gym | N/A | Wood Floor | | Non Suspect ACM | 3948 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | SB | Room 60 - Gym Office | N/A | Ceiling Tile 2' x 4' | | NAD | 288 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | SB | Room 60 - Gym Office | N/A | Concrete Block Wall | | Non Suspect ACM | 600 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | SB | Room 60 - Gym Office | M | Floor Tile VAT 12' x 12" | 6010/01/SB/GC/AV/2005 | Assumed | 144 | SF | 0 | SF | White | | | 1 | No | 1/D |
| 1 | SB | Room 60 - Gym Office | M | Floor Tile VAT 12' x 12" | 6010/01/SB/GC/AV/2001 | Assumed | 144 | SF | 0 | SF | Blue | | | 1 | No | 1/D |
| 1 | SB | Room 61 - Women's Locker Room | N/A | Ceiling Tile 2' x 4' | | NAD | 72 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | SB | Room 61 - Women's Locker Room | N/A | Concrete Block Wall | | Non Suspect ACM | 300 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | SB | Room 61 - Women's Locker Room | M | Floor Tile VAT 12' x 12" | 6010/01/SB/GC/AV/2005 | Assumed | 36 | SF | 0 | SF | White | | | 1 | No | 1/D |
| 1 | SB | Room 61 - Women's Locker Room | M | Floor Tile VAT 12' x 12" | 6010/01/SB/GC/AV/2001 | Assumed | 36 | SF | 0 | SF | Blue | | | 1 | No | 1/D |
| 1 | SB | Room 61A - Shower Area in Girl's Locker Room | N/A | Plaster Ceiling | | NAD | 27 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | SB | Room 61A - Shower Area in Girl's Locker Room | N/A | Concrete Block Wall | | Non Suspect ACM | 160 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | SB | Room 61A - Shower Area in Girl's Locker Room | N/A | Ceramic Tile Floors | | Non Suspect ACM | 27 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | SB | Room 61B - Restroom in Girl's Locker Room | N/A | Plaster Ceiling | | NAD | 50 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | SB | Room 61B - Restroom in Girl's Locker Room | N/A | Concrete Block Wall | | Non Suspect ACM | 200 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | SB | Room 61B - Restroom in Girl's Locker Room | M | Floor Tile VAT 12' x 12" | 6010/01/SB/GC/AV/2005 | Assumed | 25 | SF | 0 | SF | White | | | 1 | No | 1/D |
| 1 | SB | Room 61B - Restroom in Girl's Locker Room | M | Floor Tile VAT 12' x 12" | 6010/01/SB/GC/AV/2001 | Assumed | 25 | SF | 0 | SF | Blue | | | 1 | No | 1/D |
| 1 | SB | Room 62 - Department Office | N/A | Ceiling Tile 2' x 4' | | NAD | 144 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | SB | Room 62 - Department Office | N/A | Concrete Block Wall | | Non Suspect ACM | 500 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | SB | Room 62 - Department Office | M | Floor Tile VAT 12' x 12" | 6010/01/SB/GC/AV/2005 | Assumed | 72 | SF | 0 | SF | White | | | 1 | No | 1/D |

| Element Room | | School District of Philadelphia Central High School 1700 W. Olney Avenue, Philadelphia, PA 19141 ULCS# 6010 Year Built: 1939 | | AHERA Three-Year Reinspection 2015-2016 Room by Room Location Log Report | | | | | | | | | | Reinspection Date: 7/5/2016 Building Inspector: Ananth K. Vinjamuri Number: 374 Management Planner: Mary Anne Lerro Number: 742327 | | | | |
|---|-----|--|-----------------------|---|-------------------------|------|---|-----------------------|------------|--|-------------|------------------------------|----------------------------|--|-----------------------------|--------------------------|-------------------------|--|
| | | | | System Affected | Material Description | HID# | Confirmed, Assumed, NAD, Non Suspect ACM | Amount of Material | (SF/LF/EA) | Amount of Damage | SF LF EA | Color required for VAT | Comments/Description/Notes | Attic/Crawl/space Ranking | Damage Potential (DP) | Newly Friable (NF) | Response Action (RA) | |
| | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | |
| On Site Room Name | | | | | | | | | | | | | | | | | | |
| 1 SB Room 62 - Department Office | M | Floor Tile VAT 12" x 12" | 6010/01/SB/GC/AV/2001 | Assumed | 72 | SF | 0 | SF | Blue | | | | 1 | No | 1/D | | | |
| 1 SB Staff Restroom in Department Office | N/A | Plaster Ceiling | | NAD | 75 | SF | 0 | SF | | | | | N/A | N/A | N/A | | | |
| 1 SB Staff Restroom in Department Office | N/A | Concrete Block Wall | | Non Suspect ACM | 300 | SF | 0 | SF | | | | | N/A | N/A | N/A | | | |
| 1 SB Staff Restroom in Department Office | M | Floor Tile VAT 12" x 12" | 6010/01/SB/GC/AV/2005 | Assumed | 38 | SF | 0 | SF | White | | | | 1 | No | 1/D | | | |
| 1 SB Staff Restroom in Department Office | M | Floor Tile VAT 12" x 12" | 6010/01/SB/GC/AV/2001 | Assumed | 37 | SF | 0 | SF | Blue | | | | 1 | No | 1/D | | | |
| 1 SB Electrical Room outside Department Office | N/A | Sheetrock Ceiling | 1610/01/SB/GC/AV/2101 | Assumed | 25 | SF | 0 | SF | | | | | N/A | N/A | N/A | | | |
| 1 SB Electrical Room outside Department Office | N/A | Concrete Block Wall | | Non Suspect ACM | 200 | SF | 0 | SF | | | | | N/A | N/A | N/A | | | |
| 1 SB Electrical Room outside Department Office | N/A | Cement Floor | | Non Suspect ACM | 25 | SF | 0 | SF | | | | | N/A | N/A | N/A | | | |
| 1 SB Gym Coach's Office | N/A | Ceiling Tile 2' x 4' | | NAD | 432 | SF | 0 | SF | | | | | N/A | N/A | N/A | | | |
| 1 SB Gym Coach's Office | N/A | Concrete Block Wall | | Non Suspect ACM | 800 | SF | 0 | SF | | | | | N/A | N/A | N/A | | | |
| 1 SB Gym Coach's Office | M | Floor Tile VAT 12" x 12" | 6010/01/SB/GC/AV/2005 | Assumed | 216 | SF | 0 | SF | White | | | | 1 | No | 1/D | | | |
| 1 SB Gym Coach's Office | M | Floor Tile VAT 12" x 12" | 6010/01/SB/GC/AV/2001 | Assumed | 216 | SF | 0 | SF | Blue | | | | 1 | No | 1/D | | | |
| 1 SB Gym Coach's Office Rear Closet | N/A | Ceiling Tile 2' x 4' | | NAD | 24 | SF | 0 | SF | | | | | N/A | N/A | N/A | | | |
| 1 SB Gym Coach's Office Rear Closet | N/A | Concrete Block Wall | | Non Suspect ACM | 200 | SF | 0 | SF | | | | | N/A | N/A | N/A | | | |
| 1 SB Gym Coach's Office Rear Closet | N/A | Cement Floor | | Non Suspect ACM | 24 | SF | 0 | SF | | | | | N/A | N/A | N/A | | | |
| 1 SB Gym Coach's Office Front Closet | N/A | Ceiling Tile 2' x 4' | | NAD | 24 | SF | 0 | SF | | | | | N/A | N/A | N/A | | | |
| 1 SB Gym Coach's Office Front Closet | N/A | Concrete Block Wall | | Non Suspect ACM | 200 | SF | 0 | SF | | | | | N/A | N/A | N/A | | | |
| 1 SB Gym Coach's Office Front Closet | N/A | Cement Floor | | Non Suspect ACM | 24 | SF | 0 | SF | | | | | N/A | N/A | N/A | | | |
| 1 SB Men's Locker Area | N/A | Ceiling Tile 2' x 4' | | NAD | 84 | SF | 0 | SF | | | | | N/A | N/A | N/A | | | |
| 1 SB Men's Locker Area | N/A | Concrete Block Wall | | Non Suspect ACM | 400 | SF | 0 | SF | | | | | N/A | N/A | N/A | | | |
| 1 SB Men's Locker Area | M | Floor Tile VAT 12" x 12" | 6010/01/SB/GC/AV/2005 | Assumed | 42 | SF | 0 | SF | White | | | | 1 | No | 1/D | | | |
| 1 SB Men's Locker Area | M | Floor Tile VAT 12" x 12" | 6010/01/SB/GC/AV/2001 | Assumed | 42 | SF | 0 | SF | Blue | | | | 1 | No | 1/D | | | |
| 1 SB Men's Restroom in Locker Area | N/A | Ceiling Tile 2' x 4' | | NAD | 60 | SF | 0 | SF | | | | | N/A | N/A | N/A | | | |
| 1 SB Men's Restroom in Locker Area | N/A | Concrete Block Wall | | Non Suspect ACM | 300 | SF | 0 | SF | | | | | N/A | N/A | N/A | | | |
| 1 SB Men's Restroom in Locker Area | M | Floor Tile VAT 12" x 12" | 6010/01/SB/GC/AV/2005 | Assumed | 30 | SF | 0 | SF | White | | | | 1 | No | 1/D | | | |
| 1 SB Men's Restroom in Locker Area | M | Floor Tile VAT 12" x 12" | 6010/01/SB/GC/AV/2001 | Assumed | 30 | SF | 0 | SF | Blue | | | | 1 | No | 1/D | | | |
| 1 SB Shower Area in Men's Locker Area | N/A | Ceiling Tile 2' x 4' | | NAD | 36 | SF | 0 | SF | | | | | N/A | N/A | N/A | | | |
| 1 SB Men's Restroom in Locker Area | N/A | Concrete Block Wall | | Non Suspect ACM | 200 | SF | 0 | SF | | | | | N/A | N/A | N/A | | | |
| 1 SB Men's Restroom in Locker Area | N/A | Ceramic Tile Floors | | Non Suspect ACM | 18 | SF | 0 | SF | | | | | N/A | N/A | N/A | | | |
| 1 SB Men's Restroom in Locker Area | M | Floor Tile VAT 12" x 12" | 6010/01/SB/GC/AV/2001 | Assumed | 18 | SF | 0 | SF | Blue | | | | 1 | No | 1/D | | | |
| 1 SB Women's Restroom across from Gym Office | N/A | Plaster Ceiling | | NAD | 240 | SF | 0 | SF | | | | | N/A | N/A | N/A | | | |
| 1 SB Women's Restroom across from Gym Office | N/A | Concrete Block Wall | | Non Suspect ACM | 300 | SF | 0 | SF | | | | | N/A | N/A | N/A | | | |
| 1 SB Women's Restroom across from Gym Office | N/A | Cement Floor | | Non Suspect ACM | 240 | SF | 0 | SF | | | | | N/A | N/A | N/A | | | |
| 1 SB Women's Restroom across from Gym Office | M | Transite Stalls | 6010/01/SB/GC/AV/2310 | Assumed | 120 | SF | 0 | SF | | | | | 1 | No | 1/D | | | |
| 1 SB Hallway at Women's Restroom | N/A | Plaster Ceiling | | NAD | 70 | SF | 0 | SF | | | | | N/A | N/A | N/A | | | |
| 1 SB Hallway at Women's Restroom | N/A | Concrete Block Wall | | Non Suspect ACM | 240 | SF | 0 | SF | | | | | N/A | N/A | N/A | | | |
| 1 SB Hallway at Women's Restroom | N/A | Cement Floor | | Non Suspect ACM | 70 | SF | 0 | SF | | | | | N/A | N/A | N/A | | | |
| 1 SB Custodial Storage next to Women's Restroom | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 100 | LF | 0 | LF | | | | | N/A | N/A | N/A | | | |
| 1 SB Custodial Storage next to Women's Restroom | N/A | Concrete Ceiling | | Non Suspect ACM | 200 | SF | 0 | SF | | | | | N/A | N/A | N/A | | | |
| 1 SB Custodial Storage next to Women's Restroom | N/A | Concrete Block Wall | | Non Suspect ACM | 600 | SF | 0 | SF | | | | | N/A | N/A | N/A | | | |
| 1 SB Custodial Storage next to Women's Restroom | N/A | Cement Floor | | Non Suspect ACM | 200 | SF | 0 | SF | | | | | N/A | N/A | N/A | | | |
| 1 SB Storage at Men's Restroom | S | Fireproofing | 6010/01/SB/GC/AV/0100 | Assumed | 624 | SF | 0 | SF | | | | | 1 | No | 1/D | | | |
| 1 SB Storage at Men's Restroom | N/A | Ceiling Tile 2' x 4' | | NAD | 624 | SF | 0 | SF | | | | | N/A | N/A | N/A | | | |
| 1 SB Storage at Men's Restroom | N/A | Concrete Block Wall | | Non Suspect ACM | 900 | SF | 0 | SF | | | | | N/A | N/A | N/A | | | |
| 1 SB Storage at Men's Restroom | N/A | Cement Floor | | Non Suspect ACM | 624 | SF | 0 | SF | | | | | N/A | N/A | N/A | | | |
| 1 SB Hallway at Men's Restroom | N/A | Plaster Ceiling | | NAD | 196 | SF | 0 | SF | | | | | N/A | N/A | N/A | | | |
| 1 SB Hallway at Men's Restroom | N/A | Concrete Block Wall | | Non Suspect ACM | 400 | SF | 0 | SF | | | | | N/A | N/A | N/A | | | |
| 1 SB Hallway at Men's Restroom | N/A | Cement Floor | | Non Suspect ACM | 196 | SF | 0 | SF | | | | | N/A | N/A | N/A | | | |
| 1 SB Men's Restroom across from Gym Office | N/A | Plaster Ceiling | | NAD | 256 | SF | 0 | SF | | | | | N/A | N/A | N/A | | | |
| 1 SB Men's Restroom across from Gym Office | N/A | Concrete Block Wall | | Non Suspect ACM | 600 | SF | 0 | SF | | | | | N/A | N/A | N/A | | | |
| 1 SB Men's Restroom across from Gym Office | N/A | Cement Floor | | Non Suspect ACM | 256 | SF | 0 | SF | | | | | N/A | N/A | N/A | | | |
| 1 SB Men's Restroom across from Gym Office | M | Transite Stalls | 6010/01/SB/GC/AV/2310 | Assumed | 20 | SF | 0 | SF | | | | | 1 | No | 1/D | | | |
| 1 SB Pipe Chase at Men's Restroom | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 50 | LF | 0 | LF | | | | | N/A | N/A | N/A | | | |
| 1 SB Pipe Chase at Men's Restroom | N/A | Concrete Ceiling | | Non Suspect ACM | 90 | SF | 0 | SF | | | | | N/A | N/A | N/A | | | |
| 1 SB Pipe Chase at Men's Restroom | N/A | Concrete Block Wall | | Non Suspect ACM | 400 | SF | 0 | SF | | | | | N/A | N/A | N/A | | | |
| 1 SB Pipe Chase at Men's Restroom | N/A | Cement Floor | | Non Suspect ACM | 90 | SF | 0 | SF | | | | | N/A | N/A | N/A | | | |
| 1 SB Hallway at Gym Offices | N/A | Ceiling Tile 2' x 4' | | NAD | 140 | SF | 0 | SF | | | | | N/A | N/A | N/A | | | |
| 1 SB Hallway at Gym Offices | N/A | Concrete Block Wall | | Non Suspect ACM | 500 | SF | 0 | SF | | | | | N/A | N/A | N/A | | | |
| 1 SB Hallway at Gym Offices | M | Floor Tile VAT 12" x 12" | 6010/01/SB/GC/AV/2005 | Assumed | 70 | SF | 0 | SF | White | | | | 1 | No | 1/D | | | |
| 1 SB Hallway at Gym Offices | M | Floor Tile VAT 12" x 12" | 6010/01/SB/GC/AV/2001 | Assumed | 70 | SF | 0 | SF | Blue | | | | 1 | No | 1/D | | | |
| 1 A Attic above 3rd Floor accessible by Penthouse Central Stair | X | X | X | X | X | X | X | X | X | 500 LF Fiberglass | "A" | X | X | X | X | | | |
| 1 A Attic above Auditorium accessible by 3rd Floor Corridor | X | X | X | X | X | X | X | X | X | Fiberglass Duct Insulation | "A" | X | X | X | X | | | |
| 1 C Crawl Space in Boiler Room/Pump Room | X | X | X | X | X | X | X | X | X | | "A" | X | X | X | X | | | |
| 1 C Crawl Space/Basement | X | X | X | X | X | X | X | X | X | Access Ladder 20ft from Ground/Door Rusted/Could not inspect | | X | X | X | X | | | |
| | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | |

6010 Central HS - 2015 2016 AHERA Three-Year Report.xls

[illegible]

6010 Central HS - 2015 2016 AHERA Three-Year Report.xls

[illegible]

6010 Central HS - 2015 2016 AHERA Three-Year Report.xls

[illegible]

6010 Central HS - 2015 2016 AHERA Three-Year Report.xls

[illegible]

6010 Central HS - 2015 2016 AHERA Three-Year Report.xls

[illegible]

6010 Central HS - 2015 2016 AHERA Three-Year Report.xls

[illegible]

6010 Central HS - 2015 2016 AHERA Three-Year Report.xls

[illegible]

6010 Central HS - 2015 2016 AHERA Three-Year Report.xls

[illegible]

6010 Central HS - 2015 2016 AHERA Three-Year Report.xls

[illegible]

Section III Certificates

A. Management Planner/Building Inspector Certificates

Section III – A

Management Planner/Building Inspector Certificates

These charts indicate the Name, Course Date, Expiration Date and Corresponding Certificate Number of the Management Planner and Building Inspector of individuals that participated in the AHERA 3 Year Inspection and Management Plan process of 2015/2016.

| Management Planner | Date Granted | Expiration Date | Certificate Number |
|--------------------|--------------|-----------------|--------------------|
| Monique Causley | 2/15/2015 | 2/16/2016 | ACC-0215-8-010 |
| Monique Causley | 2/16/2016 | 2/17/2017 | ACC-0216-8-001 |
| Megan Vala | 5/22/2015 | 6/22/2016 | 740728 |
| Mary Anne Lerro | 4/5/2016 | 4/5/2017 | 742327 |

| Building Inspector | Date Granted | Expiration Date | Certificate Number |
|--------------------|--------------|-----------------|--------------------|
| Scott Magee | 8/15/2015 | 8/15/2016 | 70016699C |
| William Garrity | 8/15/2015 | 8/15/2016 | 70016699A |
| Bernard Brunner | 10/2/2015 | 8/2/2016 | 45397 |
| Mary Anne Lerro | 3/3/2015 | 3/3/2016 | 740092 |
| Mary Anne Lerro | 4/5/2016 | 4/5/2017 | 742322 |
| James Madden | 12/11/2014 | 12/11/2015 | ACC-1214-6-010 |
| James Madden | 12/3/2015 | 12/3/2016 | ACC-1215-6-018 |
| Troy Ray | 3/15/2015 | 3/19/2016 | ACC-0355-6-011 |
| Ananth Vinjamuri | 9/29/2015 | 9/29/2016 | 374 |
| Shelton Williams | 9/29/2015 | 9/29/2016 | 375 |
| Paul Davis | 2/12/2015 | 2/12/2016 | ACC-0215-6-015 |
| Paul Davis | 2/2/2016 | 2/2/2017 | 741836 |
| Bernard Bryson | 2/16/2015 | 2/16/2016 | ACC-0125-6-031 |
| Bernard Bryson | 2/15/2016 | 2/15/2017 | ACC-0216-6-005 |
| Alexander Roman | 9/18/2015 | 9/18/2016 | EHSBIR-150619-008 |
| Norm Harrison | 9/2/2015 | 9/2/2016 | ACC-0915-6-011 |
| Kelly Mayberry | 2/20/2015 | 2/20/2016 | EHSBIR-150220-005 |
| Kelly Mayberry | 2/18/2016 | 2/18/2017 | EHSBIR-160218-006 |
| Andrew Hine | 5/6/2015 | 5/6/2016 | AI05042015-3 |
| Maryellen Leotta | 2/12/2015 | 2/12/2016 | ACC-0215-6-024 |

Certificate of Completion

awarded to

Monique Causley

for successfully completing the prescribed course of study in

Pennsylvania Asbestos Management Planner Refresher Course

under TSCA Title II

presented by

ACCESS TRAINING SERVICES, INC.
7921 River Road, Pennsauken, NJ 08110
(856) 665-3449

2/16/15

Course Date

N/A

Exam Date

2/16/16

Expiration Date

Not Provided

Social Security Number

ACC-0215-8-010

Certificate Number

Mark K. Schlüger
Training Director

Certificate of Completion

awarded to

Monique Causley

for successfully completing the prescribed course of study in

Pennsylvania Asbestos Management Planner Refresher Course

under TSCA Title II

presented by

**ACCESS TRAINING SERVICES, INC.
7921 River Road, Pennsauken, NJ 08110
(856) 665-3449**

2/15/16

Course Date

N/A

Exam Date

2/15/17

Expiration Date

Not Provided

Social Security Number

ACC-0216-8-001

Certificate Number

Mark K. Schlüger
Training Director

Certificate of Training

CRITERION LABORATORIES, INC.

HEREBY CERTIFIES THAT

Megan Vala

HAS SUCCESSFULLY COMPLETED A 16 HOUR COURSE ENTITLED

Asbestos Management Planner Initial

INCLUDING CLASSROOM INSTRUCTION

05/21/2015 to 05/22/2015

Exam passed on this 22nd day of May 2015 - Score - 94

Approved for AHERA Accreditation Under TSCA Title II

3370 Progress Drive, Suite J
Bensalem, PA 19020
(215) 244-1300 - Phone
(215) 244-4349 - Fax
www.criterionlabs.com

Course is conducted in English

DIRECTOR:



James A. Welts, CIH, President

Certificate of Training

CRITERION LABORATORIES, INC.

HEREBY CERTIFIES THAT

Mary Anne Lerro

HAS SUCCESSFULLY COMPLETED A 4 HOUR COURSE ENTITLED

Asbestos Management Planner Refresher

INCLUDING CLASSROOM INSTRUCTION


on this 5th day of April 2016

Approved for AHERA Accreditation Under TSCA Title II

3370 Progress Drive, Suite J
Bensalem, PA 19020
(215) 244-1300 - Phone
(215) 244-4349 - Fax
www.criterionlabs.com

Course is conducted in English

DIRECTOR:



James A. Welts, CIH, President

EMSL ANALYTICAL, INC.

Certifies that

Scott Magee

has successfully completed the course of study for the

Asbestos Building Inspector Refresher Course

for Accreditation under TSCA Title II


EMSL Certificate No. 70016699C

Approved by:
PA Dept. of Labor and Industry
Accreditation # 137

Course Date: 8/15/2015
Granted: 8/15/2015
Expiration Date: 8/15/2016

Sponsored by:

EMSL Analytical, Inc.
200 Route 130 North
Cinnaminson, NJ 08077
Phone: (800) 220-3675
Fax: (856) 786-5973
www.emsl.com



Michael P. Menz

Michael P. Menz, CIH
Training Director

Environmental, Mold, Bacteria, IAQ, Asbestos, Lead, Forensic and Materials Testing Since 1981

EMSL ANALYTICAL, INC.

Certifies that

William Garrity

has successfully completed the course of study for the

Asbestos Building Inspector Refresher Course

for Accreditation under TSCA Title II

EMSL Certificate No. 70016699A


Approved by:

PA Dept. of Labor and Industry
Accreditation # 137

Course Date: 8/15/2015
Granted: 8/15/2015
Expiration Date: 8/15/2016

Sponsored by:

EMSL Analytical, Inc.
200 Route 130 North
Cinnaminson, NJ 08077
Phone: (800) 220-3675
Fax: (856) 786-5973
www.emsl.com



Michael P. Menz

Michael P. Menz, CIH
Training Director

Environmental, Mold, Bacteria, IAQ, Asbestos, Lead, Forensic and Materials Testing Since 1981

45397

National Asbestos & Environmental Training Institute

CERTIFICATE OF COMPLETION

AHERA/EPA Accredited Per 40 CFR Part 763
Asbestos Accreditation under TSCA Title II

This is to certify that


Bernard Brunner, Jr.

Successfully completed the course entitled

**1/2-Day New York State/EPA/AHERA Asbestos Building Inspector Annual Refresher on
October 2, 2015**

Examination Passed October 2, 2015

Expiration Date on October 2, 2016


Doris L. Adler
President, NAEETI

Per 10 NYCRR Part 73.2 (L) (1), DOH 2832 Certificate of Completion of Asbestos
Safety Training is the only official record of training for N.Y.S. students.

Language: English

ABIH 1/2 CM POINT

3321 Doris Avenue, Building B, Ocean, NJ 07712

Phone (732) 531-5571

Fax (732) 531-5956

www.naeti.com

Number 740092

Expiration Date:
03/03/2016

Certificate of Training

CRITERION LABORATORIES, INC.

HEREBY CERTIFIES THAT

Mary Anne Lerro

HAS SUCCESSFULLY COMPLETED A 4 HOUR COURSE ENTITLED

Asbestos Building Inspector Refresher

on this 3rd day of March 2015

Exam passed on this 3rd day of March 2015 - Score - 84

Approved for AHERA Accreditation Under TSCA Title II

3370 Progress Drive, Suite J
Bensalem, PA 19020
(215) 244-1300 - Phone
(215) 244-4349 - Fax
www.criterionlabs.com

Course is conducted in English

DIRECTOR:

James A. Weltz
James A. Weltz, CIH, President

Certificate of Training

CRITERION LABORATORIES, INC.

HEREBY CERTIFIES THAT

Mary Anne Lerro

HAS SUCCESSFULLY COMPLETED A 4 HOUR COURSE ENTITLED

Asbestos Building Inspector Refresher

INCLUDING CLASSROOM INSTRUCTION

on this 5th day of April 2016

Exam passed on this 5th day of April 2016 - Score - 88

Approved for AHERA Accreditation Under TSCA Title II

3370 Progress Drive, Suite J
Bensalem, PA 19020
(215) 244-1300 - Phone
(215) 244-4349 - Fax
www.criterionlabs.com

Course is conducted in English

DIRECTOR:



James A. Welts, CIH, President

Certificate of Completion

James Madden

for successfully completing the prescribed course of study in

Pennsylvania Asbestos Building Inspector Refresher Course

under TSCA Title II

presented by

ACCESS TRAINING SERVICES, INC.
7921 River Road, Pennsauken, NJ 08110
(856) 665-3449

12/11/14

Course Date

N/A

Exam Date

12/11/15

Expiration Date

Not Provided

Social Security Number

ACC-1214-6-010

Certificate Number

Mark K. Schlüger
Training Director

Certificate of Completion

James Madden

for successfully completing the prescribed course of study in

Pennsylvania Asbestos Building Inspector Refresher Course

under TSCA Title II

presented by

ACCESS TRAINING SERVICES, INC.
7921 River Road, Pennsauken, NJ 08110
(856) 665-3449

12/3/15

Course Date

N/A

Exam Date

12/3/16

Expiration Date

Not Provided

Social Security Number

ACC-1215-6-018

Certificate Number

Mark K. Schlüger
Training Director

Certificate of Completion

Troy A. Ray

for successfully completing the prescribed course of study in

Pennsylvania Asbestos Building Inspector Refresher Course

under TSCA Title II

presented by

ACCESS TRAINING SERVICES, INC.
7921 River Road, Pennsauken, NJ 08110
(856) 665-3449

3/19/15
Course Date

N/A
Exam Date

3/19/16
Expiration Date

Not Provided
Social Security Number

ACC-0355-6-011
Certificate Number

Mark K. Schlager
Training Director

CERTIFICATE NO 374

G&C Environmental Services, Inc. (#294)
2 Street Road, Newtown Square, Pennsylvania 19073
Telephone: (610) 993-9202 Facsimile: (610) 993-9232
Email: Training@gcenviro.com
www.GCenviro.com

This document certifies that Ananth K. Vinjamuri has successfully completed this
State of New York Department of Health Approved AHERA BUILDING INSPECTOR

REFRESHER COURSE, completed as required for asbestos accreditation under the Toxic

Substances Control Act, Title II. This course was held from 09/29/2015 to 09/29/2015.
MM DD YR MM DD YR

The examination date was 09/29/2015. This certificate expires one year from the date of
MM DD YR MM DD YR
successful completion of the examination 09/29/2016.
MM DD YR

*The official record of successful training completion is the New York State Department of
Health certificate of asbestos safety training completion (DPH 2832).*

Gail M. Conner
Training Director

Gail M. Conner

CERTIFICATE NO 375

G&C Environmental Services, Inc. (#294)
2 Street Road, Newtown Square, Pennsylvania 19073
Telephone: (610) 993-9202 Facsimile: (610) 993-9232
Email: Training@gcenviro.com
www.GCenviro.com

This document certifies that Shelton Williams has successfully completed this
State of New York Department of Health Approved AHERA BUILDING INSPECTOR

REFRESHER COURSE, completed as required for asbestos accreditation under the Toxic

Substances Control Act, Title II. This course was held from 09/29/2015 to 09/29/2015.

The examination date was 09/29/2015. This certificate expires one year from the date of

successful completion of the examination 09/29/2016.

*The official record of successful training completion is the New York State Department of
Health certificate of asbestos safety training completion (DPH 2832).*

Gail M. Conner
Training Director

Gail M. Conner

Certificate of Completion

Paul M. Davis

for successfully completing the prescribed course of study in

Pennsylvania Asbestos Building Inspector Refresher Course

under TSCA Title II

presented by

ACCESS TRAINING SERVICES, INC.
7921 River Road, Pennsauken, NJ 08110
(856) 665-3449

2/12/15

Course Date

N/A

Exam Date

2/12/16

Expiration Date

Not Provided

Social Security Number

ACC-0215-6-015

Certificate Number

Mark K. Schlüger
Training Director

Certificate of Training

CRITERION LABORATORIES, INC.

HEREBY CERTIFIES THAT

Paul M. Davis

HAS SUCCESSFULLY COMPLETED A 4 HOUR COURSE ENTITLED

Asbestos Building Inspector Refresher

INCLUDING CLASSROOM INSTRUCTION

on this 2nd day of February 2016

Exam passed on this 2nd day of February 2016 - Score - 92

Approved for AHERA Accreditation Under TSCA Title II

3370 Progress Drive, Suite J
Bensalem, PA 19020
(215) 244-1300 - Phone
(215) 244-4349 - Fax
www.criterionlabs.com

Course is conducted in English

DIRECTOR:

James A. Welch

James A. Welch, CIH, President

Certificate of Completion

Bernard J. Bryson


for successfully completing the prescribed course of study in

Pennsylvania Asbestos Building Inspector Refresher Course

under TSCA Title II

presented by

ACCESS TRAINING SERVICES, INC.
7921 River Road, Pennsauken, NJ 08110
(856) 665-3449

| | | |
|-------------------------------|---------------------------|---|
| 2/16/15 | N/A | 2/16/16 |
| <i>Course Date</i> | <i>Exam Date</i> | <i>Expiration Date</i> |
| Not Provided | ACC-0125-6-031 |  |
| <i>Social Security Number</i> | <i>Certificate Number</i> | Mark K. Schlager <i>Training Director</i> |

Certificate of Completion

Bernard J. Bryson

for successfully completing the prescribed course of study in

Pennsylvania Asbestos Building Inspector Refresher Course

under TSCA Title II

presented by

ACCESS TRAINING SERVICES, INC.
7921 River Road, Pennsauken, NJ 08110
(856) 665-3449

2/15/16

Course Date

N/A

Exam Date

2/15/17

Expiration Date

Not Provided

Social Security Number

ACC-0216-6-005

Certificate Number

Mark K. Schlager
Mark K. Schlager
Training Director

EHS TRAINING INSTITUTE, INC.
A Division of BATTI, Inc.

Certificate of Completion

AHERA Building Inspector

(Refresher)

Awarded To:

Alexander Roman

SS#:XXX-XX-1743
Who has completed this 4-hour course and examination,
EPA Approved under TSCA Title II
AHERA / ASHARA Rule
40 CFR Part 763.

EHS TRAINING INSTITUTE, INC.

A Division of BATTI, Inc.

Delaware Industrial Park • 6 Garfield Way

Newark, DE 19713-5817

(302) 737-3376 • Fax (302) 737-5764

Course Date: September 18, 2015

Date of Expiration: September 18, 201

Certification Number : EHSBIR 150619-008


Todd K. Zeisloff, Instructor


Neeraj K. Batta, President

Certificate of Completion

Norman Harrison

for successfully completing the prescribed course of study in

Pennsylvania Asbestos Building Inspector Refresher Course

under TSCA Title II

presented by

**ACCESS TRAINING SERVICES, INC.
7921 River Road, Pennsauken, NJ 08109
(856) 665-3449**

9/2/15

Course Date

N/A

Exam Date

9/2/16


Expiration Date

Not Provided

Social Security Number

ACC-0915-6-011

Certificate Number


Mark K. Schlager
Training Director

EHS TRAINING INSTITUTE, INC.
A Division of BATTI, Inc.

Certificate of Completion

AHERA Building Inspector

(Refresher)

Awarded To:

Kelly Mayberry

SS#:XXX-XX-1551

Who has completed this 4-hour course and examination,

EPA Approved under TSCA Title II

AHERA / ASHARA Rule

40 CFR Part 763.

EHS TRAINING INSTITUTE, INC.

A Division of BATTI, Inc.

Delaware Industrial Park • 6 Garfield Way

Newark, DE 19713-5817

(302) 737-3376 • Fax (302) 737-5764

Course Date: February 20, 2015

Date of Expiration: February 20, 2016

Certification Number : EHSBIR 150220-005


Todd K. Zeisloff, Instructor


Neeraj K. Batta, President

EHS TRAINING INSTITUTE, INC.

A Division of BATA, Inc.

Certificate of Completion

AHERA Building Inspector

(Refresher)

Awarded To:

Kelly Mayberry

SS#:XXX-XX-1551

Who has completed this 4-hour course and examination,

EPA Approved under TSCA Title II

AHERA / ASHARA Rule

40 CFR Part 763.

EHS TRAINING INSTITUTE, INC.

A Division of BATA, Inc.

Delaware Industrial Park • 6 Garfield Way

Newark, DE 19713-5817

(302) 737-3376 • Fax (302) 737-5764

Course Date: February 18, 2016

Date of Expiration: February 18, 2017

Certification Number : EHSBIR 160218-006

Todd K. Zeisloff, Instructor

Neeraj K. Batta, President

AEROSOL MONITORING & ANALYSIS, INC.

This is to certify that
ANDREW HINE

has met the attendance requirements and successfully completed

the course entitled

3-DAY EPA AHERA INSPECTOR

For Accreditation Under TSCA Title II

05/04/2015 to 05/06/2015

Course Date

05/06/2015

Exam Date

5/6/2016

Expiration Date

STEVE SIERACKI

Principal Instructor

Steve Sieracki

A105042015-3

Certification No.

E. Rush Barnett

Course Director

E. Rush Barnett

1331 Ashton Road

P.O.Box 646

Hanover, MD 21076

P: 410-684-3327

F: 410-684-3724

www.amatraining.com

Certificate of Completion

Maryellen Leotta

for successfully completing the prescribed course of study in

Pennsylvania Asbestos Building Inspector Refresher Course

under TSCA Title II

presented by

ACCESS TRAINING SERVICES, INC.
7921 River Road, Pennsauken, NJ 08110
(856) 665-3449

2/12/15

Course Date

N/A

Exam Date

2/12/16

Expiration Date

Not Provided

Social Security Number

ACC-0215-6-024

Certificate Number

Mark K. Schlager
Training Director

Section IV Cross Reference Table

Asbestos Hazard Emergency Response Act (AHERA) Environmental Compliance Audit Cross Reference Table

In response to the AHERA Environmental Compliance Audit a Cross Reference Table has been prepared for inclusion into the Environmental Management Plan. The purpose of this Cross Reference Table is to link the following documents to the AHERA Management Plan.

| Cross Reference Table | |
|--|--|
| 3 Year Reinspection Report follows this Cross Reference Table documentation. | |
| Subject Matter | Location of Required Documents |
| Designated Person | Pages 1 - 3 |
| Annual Notification | Pages 4 - 5 |
| 6 Month Periodic Surveillance Outline of Events | Page 6 |
| 3 Year Re-inspections Outline of Events | Page 7 |
| Asbestos Management Program (operations and maintenance) | Pages 8 - 19 |
| Asbestos Investigation Report (AIR) | Attachment 1 Letter Dated August 4, 2006 |
| Training (included in the Asbestos Management Program) | <p>The original records are centralized at the School District's Environmental Library. Copies are maintained on staff and are required to be maintained in the latest Reinspection Report.</p> <p>2 hour awareness training records for all Building Engineers, Custodian Assistants and maintenance personnel</p> <p>40 hour worker/supervisor training records for the OEMS A-Team and various AST tradesmen.</p> |
| Response Actions (monthly mailings if applicable) | The original documents are on file at the School District's Environmental Library. |
| | Copies of the original are mailed to the Schools Main Office for retention with the Management Plan documentation. These documents are typically kept separate from the management plan in an update binder due to the potential volume of response action reports. |

SCHOOL DISTRICT OF PHILADELPHIA

ASBESTOS DESIGNATED PERSON

Gerald F Junod
Office of Capital Programs
Environmental Management & Services
440 N Broad Street, 3rd Floor
Philadelphia, PA 19130
Telephone: 215 400 6738
Fax: 215 400 4751

| | |
|--|-------------------------------------|
| Drexel University- Asbestos Building Inspector Course | January 9-11, 1989 24 Hours |
| Drexel University- Asbestos Management Planner Course | January 12-13, 1989 16 Hours |
| Criterion Laboratories, Inc. - Asbestos Management Planner Course | October 11-12, 2012 16 Hours |

| | |
|---|------------------------|
| <u>Annual Building Inspector Refreshers</u> 4 Hours Drexel University Criterion Laboratories, Inc Access Training Services, Inc. | 1990 to Present |
|---|------------------------|

| | |
|---|---|
| <u>Annual Building Management Planner Refreshers</u> 4 Hours Drexel University Criterion Laboratories, Inc 4 Hours | 1990 to 1994 2013 to Present |
|---|---|

Environmental Manager, School District of Philadelphia

Manages the design and implementation of asbestos and lead projects for the Capital Improvement Program and other District Departments including Facilities & Operations and Information Technology. Ensures that asbestos abatement and lead remediation projects are expertly designed and executed in accordance with industry best management practice standards and regulations.

Manager, City of Philadelphia Asbestos Control Program

Served as the Asbestos Control Program Manager for the City of Philadelphia, Department of Public Health, Air Management Services, Asbestos Control Unit from August 1, 2003 through October 23, 2006.

Mid Atlantic Regional Environmental Consortium (MAREC)

Former member with attendance and participation commitments of all quarterly EPA Region III and yearly National Asbestos Regulatory Conferences sponsored by the EPA and the National Conference of State Legislators respectively as a representative for the City of Philadelphia Department of Public Health Air Management Services from 1994 through 2006.

Philadelphia Environmental Task Force


Former member of the Philadelphia Environmental Task force as a representative and point of contact for the City of Philadelphia Department of Public Health Air Management Services Asbestos Control Unit from 2002 through 2006.

Asbestos Instructor

Worked as the primary instructor for the initial and annual Asbestos Project Inspector training and licensing program as mandated by City of Philadelphia Department of Public Health Asbestos Control Regulations from August 1994 through October 2006.

Worked as a lead instructor with an Environmental Consulting Firm and approved by the US EPA for the initial and annual refresher training courses for various asbestos occupational disciplines such as the Building Inspector, Management Planner and Worker/Supervisor from 1991 through 1994.

I certify that the general, local agency responsibilities as stipulated in Section 763.84 will be met.



**Gerald F. Junod
Asbestos Designated Person
Environmental Manager
Office of Environmental Management and Services**

SCHOOL DISTRICT OF PHILADELPHIA

Accreditation Information Statement

All persons who inspect for Asbestos Containing Building Materials (ACBM) and who will design or carry out response actions with respect to assumed and confirmed ACBM, will be accredited by an EPA approved course and/or a State Contractors Accreditation Program under Sections 206 (c) and 206 (b) of Title II of the ACT.



**Gerald F. Junod
Asbestos Designated Person
Environmental Manager
Office of Environmental Management and Services**

SCHOOL DISTRICT OF PHILADELPHIA
OFFICE OF CAPITAL PROGRAMS
440 NORTH BROAD STREET, SUITE 373
PHILADELPHIA, PENNSYLVANIA 19130

OFFICE OF ENVIRONMENTAL MANAGEMENT AND SERVICES

PHONE (215)-400-4750

September 2015

TO: Principals
Building Administrators/Occupants
Parents/Guardians

FROM: Fran Burns
Chief Operating Officer

Francine Locke, M.S., Director
Office of Environmental Management and Services

SUBJECT: Annual EPA Notification Letter


Pursuant to the Federal Environmental Protection Agency (EPA) mandate, as required by 40 C.F.R. 763.84 (c)(d) of public access to environmental records, this letter is to acknowledge the availability of your facility's Asbestos Hazard Emergency Response Act (AHERA) Management Plan.

Each member of the school staff, parents/guardians, temporary workers and/or contractors, are required to receive a copy of the Notification Letter. At the direction of the Principal, a copy is to be posted on the bulletin boards and an appropriate amount of copies are to be generated for distribution.


Note: The AHERA Three-Year Reinspection reports, in colored binders; White with Pink, Tan, Black, Red, Dark Blue, Green, Yellow and White, are Federal EPA mandated inspection documents. The School District of Philadelphia is subject to severe monetary penalties if the reports and associated paperwork are not available to the EPA and the public upon request.

It is incumbent on designated school personnel to gather and retain this data as it is delivered, in one location for future review. Acceptable locations include the Principal's Office or Main Office for the primary data. The Building Engineer should maintain any secondary or duplicate copies.

If you have any questions, please call 215-400-4750. Thank you for your cooperation.



Fran Burns
Chief Operating Officer



Francine Locke, M.S., Director
Office of Environmental Management
and Services

c: Danielle Floyd

AHERA-4
8/21/15



School District of Philadelphia
OFFICIAL NOTICE

PLEASE POST

September 2015

TO: Principals
Building Administrators
Building Engineers
Building Occupants
Parents/Guardians

FROM: Fran Burns
Chief Operating Officer

Francine Locke, M.S., Director
Office of Environmental Management and Services

SUBJECT: Annual Notification Letter: Asbestos Hazard Emergency Response Act

The Federal Register published on October 30, 1987, Subpart E, in Schools: Final Rule and Notice, 763.84 (c)(d) states that each local education agency shall ensure that workers and building occupants or guardians are to be informed at least once each school year about inspections, response actions and post-response action activities including re-inspections and periodic surveillance activities. The School District as the Local Education Agency (LEA), retains such reports that are available for public inspection in the Office of the Principal or Building Administrator.

The Principal or Building Administrator is required to do the following with this notification:

- 1) Post in a Public Place or Main Office
- 2) Inform Building Occupants
- 3) Send a copy of this notification to Parents or Guardians
- 4) Insert a copy into the latest AHERA Three-Year Reinspection report (white/pink binder) in your office or facility.

A handwritten signature of Fran Burns in black ink, written over a horizontal line.

Fran Burns
Chief Operating Officer

A handwritten signature of Francine Locke in black ink, written over a horizontal line.

Francine Locke, M.S., Director
Office of Environmental Management
and Services

c: Danielle Floyd

AHERA-4a
8/21/15

SCHOOL DISTRICT OF PHILADELPHIA
Education Center
440 North Broad Street
Philadelphia, Pennsylvania 19130

Office of Environmental Management and Services

215-400-4750

AHERA
Six Month Surveillance
Outline of Events

- Pursuant to the Federal Environmental Protection Agency (EPA) mandate, as required by 40 CFR 763.92(b), the following procedure is to be implemented. At least once every six (6) months after a Management Plan is in effect, each Local Education Agency (LEA) shall conduct a periodic surveillance in each building that it owns or leases that contains Asbestos Containing Building Materials (ACBM) or is assumed to contain ACBM.
- The first Bi-Annual Inspection starts in the Spring (March, April, May) and again in the Fall (October, November, December) of each year. The Building Engineer/Assistant should assist the Building Inspector with appropriate access to all areas including (Crawlspace/Attics) and rooms in the facility. There is no action required of the Principal.
- The Building Inspector shall visually inspect all areas that are identified in the Management Plan as ACBM or assumed ACBM. The date of the surveillance is recorded, the inspectors name and any changes in the conditions of the materials.
- The Building Inspector shall make a copy of the inspection document and insert into the front of the latest Management Plan (AHERA Three Year Reinspection report). The original document is returned to the LEA's Environmental Library and filed.

SCHOOL DISTRICT OF PHILADELPHIA
Education Center
440 North Broad Street
Philadelphia, Pennsylvania 19130

Office of Environmental Management and Services

215-400-4750

AHERA
Three Year Reinspection
Outline of Events

- Pursuant to the Federal Environmental Protection Agency (EPA) mandate, as required by 40 CFR 763.85(b) the following procedure is to be implemented. At least once every three (3) years after a Management Plan is in effect, each Local Education Agency (LEA) shall conduct a reinspection of each building that it owns or leases that contains Asbestos Containing Building Material's (ACBM's) or is assumed to contain ACBM.
- Subsequent Three Year Re-inspections (2009, 2012, 2015, etc) shall start in the Fall (October, November, December, January). The Building Engineer/Assistant should assist the Building Inspector with appropriate access to all areas including (Crawlspaces/Attics) and rooms in the facility. There is no action required of the Principal.
- An accredited Building Inspector shall visually inspect and touch to determine friability, all areas that are identified in the Management Plan as ACBM or assumed ACBM. The date of the surveillance is recorded, the inspectors name and any changes in the conditions of the materials. The Building Inspectors state of accreditation and license number is required.
- After the inspection, the Building Inspector shall make a copy of the inspection documents and insert into the front of the latest Management Plan (AHERA Three Year Reinspection report). The original document is returned to the LEA's Environmental Library and filed.
- The Building Inspector shall return the reinspection data to the Management Planner to be assessed and determine appropriate response actions and a report issued (AHERA Three Year Reinspection report). One copy of the report is delivered to the schools Principal to be permanently retained with all previous environmental data. Another copy is retained in the LEA's Environmental Library.



School District of Philadelphia
Office of Environmental Management & Services
440 North Broad Street
Philadelphia, PA 19130
(215) 400-4750

**School District of Philadelphia
Asbestos Management Program**

TABLE OF CONTENTS

| | |
|--|----------------|
| Definitions..... | Page 9 |
| 1. Introduction..... | Page 10 |
| 2. Summary of Asbestos Management Plan | |
| 3. Asbestos Management Plan Execution..... | Page 11 |
| a. General Execution | |
| 4. Summary of Program Execution | |
| a. Asbestos Management Plan Execution | |
| 5. Responsibilities | |
| a. OEMS | |
| b. Asbestos Worker/Supervisor “A-TEAM”..... | Page 12 |
| c. Asbestos Designated Person | |
| d. Supervisor or Project Manager (Capital, Maintenance & Facilities) | |
| e. Employee Capital..... | Page 13 |
| f. Employee Maintenance | |
| g. Employee Facilities and Custodial | |
| 6. Requirements..... | Page 14 |
| a. Employee Exposure Monitoring | |
| b. Employee Notification | |
| c. Observation of Monitoring | |
| d. Training Program | |
| e. Access of Information | |
| f. Record Keeping | |
| 7. AHERA O&M Plan..... | Page 15 |
| a. Controls | |
| 8. O&M Response Actions..... | Page 16 |
| a. Facility Maintenance Isolation of Area | |
| b. Unlikely Contact with ACM/PACM | |
| c. Accidental Disturbance of ACM/PACM | |
| d. Planned Disturbance of ACM/PACM | |
| e. Miscellaneous ACM/PACM..... | Page 17 |
| f. Vinyl Asbestos Floor Tile | |
| g. Mastic/Adhesives | |
| h. Woven Vibration Dampers | |
| i. Other Work Practices | |
| j. Fiber Release Episodes | |
| 9. References and Resources..... | Page 18 |

DEFINITIONS / ACRONYMS

| | |
|-----------------------------------|--|
| ACM/PACM: | Asbestos Containing Material/Potential Asbestos Containing Material |
| AHERA: | Asbestos Hazard Emergency Response Act |
| AIR FORM: | Asbestos Inspection Report Form |
| Amended Water: | Water to which a surfactant (soap) has been added |
| AMP: | Asbestos Management Program/Asbestos Management Plan |
| Asbestos Designate Person: | Individual assigned by the district to oversee asbestos related issues. |
| Asbestos Regulated Area: | Location that is posted as an asbestos work area in which only approved and accredited personnel are permitted to enter |
| AST: | Asbestos Support Team involving approved and accredited school district tradespersons personnel that are school district person |
| A-TEAM: | School District of Philadelphia asbestos workers |
| CIP: | Capital Improvement Program |
| Consultant: | Asbestos consulting firm hired by the District |
| Demolition Directive: | Memorandum – August 4, 2006 from Patrick Henwood |
| EPA: | Environmental Protection Agency |
| In House Personnel: | School District of Philadelphia asbestos workers |
| LEA: | Local Education Agency |
| O&M: | Operations and Maintenance |
| OEMS: | Office of Environmental Management and Services |
| OSHA: | Occupational Safety and Health Administration |
| PEL: | Permissible Exposure Limit |
| PSD or SDP: | Philadelphia School District/School District of Philadelphia |
| PSIT: | Philadelphia School Improvement Team |
| STEL: | Short Term Exposure Limit |

1. Introduction

The School District of Philadelphia, Asbestos Policy Statement:

“The School District of Philadelphia is dedicated to providing a safe and healthful work environment for its employees, students, faculty, contractors and visitors. In recognition of the potential health problems associated with asbestos, the School District of Philadelphia is committed to a comprehensive asbestos control program. This program is implemented and maintained through the School District of Philadelphia's Office of Environmental Management and Services (OEMS).”

OEMS has the responsibility of establishing procedures for asbestos abatement, asbestos inspection, air monitoring, renovation and demolition activities within all School District of Philadelphia owned or leased facilities.

These procedures are developed to ensure that:

- (1) People are not exposed to significant levels of asbestos fibers
- (2) Asbestos waste is handled and disposed of properly
- (3) Members of the School District of Philadelphia community have access to the Office of Environmental Management and Services for information, assistance, guidance, and interpretation regarding asbestos related matters.
- (4) Members of the School District of Philadelphia community have access to the Asbestos Management Plans as required and outlined in the US EPA AHERA regulations including annual written notification to all parents.
- (5) Compliance with all applicable Federal, State and Local Asbestos Regulations

Requirements outlined in this manual are mandatory in nature where the word “SHALL” is used and are advisory in nature where the word “SHOULD” is used.

2. Summary of Asbestos Management Program

The School District of Philadelphia's Asbestos Management Program was established to meet the requirements of Federal, State, and Local Regulations.

These regulations include, but are not limited to:

- US Environmental Protection Agency Asbestos Hazard Emergency Response Act (US EPA AHERA) and National Emissions Standard for Hazardous Air Pollutants subpart M, Part 61 (NESHAP);
- US Department of Labor, Occupational Safety and Health Administration (OSHA) General Industry Standard (29 CFR 1910.1001) and the OSHA Asbestos Standard for the Construction Industry (29 CFR 1926.1101);
- The Commonwealth of Pennsylvania, Department of Labor and Industry, Asbestos Occupations, Accreditation and Certification Act;
- The City of Philadelphia, Department of Public Health, Asbestos Control Regulations.

3. Asbestos Management Program Execution

a) General Execution

The Office of Environmental Management and Services (OEMS) develops, implements and manages safety and health programs for the School District of Philadelphia faculty, staff and students and assists with ensuring that all contractors comply with Federal, State and Local Environmental Regulations. The OEMS provides the oversight of School District of Philadelphia employees (Asbestos A-Team), environmental consultants, and asbestos abatement contractors for all projects within the School District of Philadelphia concerning Asbestos Containing Materials.

The control of safety and health hazards at the School District of Philadelphia is primarily through the implementation of engineering, work practice and administrative controls. Personal Protective Equipment (PPE) is used to supplement these controls or whenever the controls are not feasible or are in the process of being implemented. PPE is also recommended whenever exposures to chemical, physical or biological agents can be prevented or reduced by its use.

This written program establishes the procedures necessary to:

- 1) meet established standards and federal regulations for occupational exposure to asbestos fibers;
- 2) meet the requirements of the City of Philadelphia Asbestos Control Regulations which encompasses the disturbance and/or abatement of asbestos containing building materials;
- 3) provide the necessary health and safety protection to the School District of Philadelphia staff, faculty, students, contractors and visitors.

This program is strengthened by input and cooperation with the Philadelphia Federation of Teachers (PFT), Health and Welfare Fund.

4. Summary of Program Execution

a) Asbestos Management Program Execution

The Asbestos Management Program is administered by the Office of Environmental Management and Services (OEMS). OEMS provides the following services primarily through professional consultants:

- (1) exposure monitoring services;
- (2) building inspection/surveys (bulk sampling) for the identification of asbestos containing materials;
- (3) asbestos project design services;
- (4) asbestos abatement project and air monitoring services;
- (5) emergency response to fiber release episodes;
- (6) education/information;
- (7) medical monitoring;
- (8) training for School District of Philadelphia personnel

5. Responsibilities

a) Office of Environmental Management and Services

OEMS is responsible for performing the following functions:

- (1) Developing and administering of the Asbestos Management Program.
- (2) Providing asbestos-related services to all School District of Philadelphia departments.
- (3) Conducting required training of the Asbestos Management Program and working jointly with departments to schedule training.
- (4) Identifying and posting areas where labeling/signage are required.
- (5) Medical Monitoring of OEMS "A-TEAM" and other departments "AST" Asbestos Program staff.

- (6) Certification and training as required for OEMS "A-TEAM" and other departments "AST" Asbestos program staff.
- (7) Record keeping as outlined in Section 3.5 and all records as by required by US EPA AHERA regulations.

b) Asbestos Worker/Supervisor - "A-TEAM"

- (1) OEMS shall ensure that all "A-TEAM" workers/supervisors adhere to the following requirements:
 - a) Attend an initial Worker/Supervisor Asbestos Course;
 - b) Maintain the annual re-certification per EPA AHERA requirements and Commonwealth of Pennsylvania Asbestos Occupations, Accreditation and Certifications Act;
 - c) Undergo an annual Asbestos Medical Evaluation;
 - d) Undergo an annual Respirator Medical Clearance;
 - e) Undergo an annual Respirator Fit Testing.

c) Asbestos Designated Person

The Asbestos Designated Person is responsible for:

- (1) Assuring the health and safety of employees, students and visitors in the School District of Philadelphia facilities under his/her control.
- (2) Being kept informed of all areas under his or her jurisdiction where potential asbestos exposures exist and initiating protection programs that adhere to the Asbestos Management Program requirements of this manual.
- (3) Assuring that Asbestos Management Program requirements are adhered to by principal investigators, project managers, supervisors, or division heads, and School District of Philadelphia personnel under their supervision.
- (4) Ensuring that all employees within the Asbestos Management Program comply with (OSHA 1910.1001 (j) (7) (iv)) and the US EPA AHERA regulations by attending the required training.
- (5) Ensure the posting of:
 - a) Warning labels/signage
 - b) Commonwealth of Pennsylvania Asbestos Abatement and Demolition/Renovation Notification form
 - c) Asbestos Inspection Reports (AIR) form (where required)
 - d) Ensuring that Construction Projects follow the Demolition Directive procedures as outlined in the August 4, 2006 letter.

d) Supervisor or Project Manager (Capital, Maintenance and Facilities)

Each person in charge of a project, maintenance/repair, renovation/demolition, or other activity from the Departments of Capital, Maintenance, and/or Facilities, where asbestos containing material may be present is responsible for:

Identifying, with the assistance of OEMS, asbestos containing building materials prior to any disturbance of these materials. Various Federal (EPA and OSHA) and Local (City of Philadelphia Asbestos Control Regulations) require Asbestos Inspections prior to renovation/demolition activities. This shall be accomplished by always following the Asbestos Management Program Procedures as follows:

- (1) Ensure that the requirements of the Asbestos Management Program Procedures are followed by all personnel, trades, and contractors who are involved with the project;

- (2) Review of the required Asbestos Inspection Report (AIR) form (Attachment 1) and AHERA Management Plan documents prior to activities that may disturb any Asbestos Containing Materials;
- (3) Perform all project related duties as outlined in the Project Management Responsibilities;
- (4) Keep the department chairperson or director informed on any actions proposed or taken regarding the Asbestos Management Plan;
- (5) Ensuring that Construction Projects follow the Demolition Directive procedure outlined in the August 4, 2006 letter.

e) Employee – Capital

School District of Philadelphia Capital employees and/or consultants shall:

- (1) Ensure that no suspect or asbestos containing building materials are disturbed in the course of the projects they are performing or managing. This shall be accomplished by notifying their supervisor and OEMS by issuance of a work order permit (a.k.a PSIT Service Request Form) and verifying that the materials which may be disturbed are non-asbestos containing. If this information is not available or verification has not been made, these materials should not be disturbed.
- (2) Immediately notify OEMS and their supervisor in the event of a potential fiber release episode upon discovery of visible damage to asbestos containing materials.
- (3) Ensuring that Construction Projects follow the Demolition Directive procedures as outlined in the August 4, 2006 letter.

The types of projects represented as part of the Capital Improvement Program are as follows:

- (1) Complete Renovation of an existing building that addresses all facility component concerns and educational program needs;
- (2) Major Renovation of an existing building addressing significant facility component and educational improvements;
- (3) Addition to an existing building (either as an attachment or stand-alone structure) to accommodate needed program space;
- (4) Conversion of an existing facility to accommodate a change in educational program;
- (5) Facility Component Improvement of specific facility needs (i.e. electrical or HVAC system upgrades, ADA improvements, life safety improvements, exterior renovations, etc.)

f) Employee – Maintenance

School District of Philadelphia Maintenance employees shall:

- (1) Ensure that no suspect or asbestos containing building materials are disturbed in the course of their duties or work they are performing. This shall be accomplished by notifying their supervisor and OEMS by issuance of a work order permit and verifying that the materials which may be disturbed are non-asbestos containing. If this information is not available or verification has not been made, these materials should not be disturbed.
- (2) Immediately notify OEMS and their supervisor in the event of a potential fiber release episode or upon discovery of visible damage to asbestos containing materials.
- (3) All employees involved in maintenance activities shall attend required Asbestos Awareness training program within 60 days of employment.

g) Employee – Facilities & Custodial

School District of Philadelphia Facilities and Custodial employees shall:

- (1) Ensure that no suspect or asbestos containing building materials are disturbed in the course of their duties or work they are performing. This shall be accomplished by notifying their supervisor and OEMS by issuance of a work permit and verifying that the materials which may be disturbed are non-asbestos containing. If this information is not available or verification has not been made, these materials should not be disturbed;
- (2) Immediately notify OEMS and their supervisor in the event of a potential fiber release episode or upon discovery of visible damage to asbestos containing materials.
- (3) All employees involved in Facilities and Custodial activities shall attend required Asbestos Awareness training program within 60 days of employment.

6. Requirements

a) Employee Exposure Monitoring

When information indicates that an employee's exposure to asbestos fibers may equal or exceed an 8-hour time-weighted average of 0.1 f/cc * (per OSHA 1910.1001 & 1926.1101), OEMS shall develop and implement an asbestos exposure monitoring program. The sampling strategy shall be designed to identify employees by work task (job classification) that is exposed to asbestos fibers that exceed an 8-hour time-weighted average of 0.1 f/cc.

b) Employee Notification

OEMS shall notify in writing, each employee exposed to asbestos fibers at or above an 8-hour time weighted average of 0.1 f/cc.

c) Observation and Monitoring

OEMS shall provide employees or their representatives with an opportunity to observe any exposure measurements conducted.

d) Training Program

OEMS shall institute a training program which meets the requirements of AHERA for all employees who perform maintenance operations in a facility/school which contains asbestos containing materials or presumed asbestos containing materials and 1910.1001 (j), and the Commonwealth of Pennsylvania Department of Labor and Industry and the City of Philadelphia Asbestos Control Regulations. The affected departments shall ensure employee participation in this program. The OEMS "A-TEAM" and other departments "AST" Asbestos Program staff training shall be conducted annually for each employee as required by all Federal, State and Local for each asbestos discipline.

All Asbestos Awareness training as required by AHERA shall be performed within 60 days of employment and shall include:

- Health effects of asbestos
- Locations of ACM and PACM in the building/facility
- Recognition of CM and PACM damage and deterioration
- Requirements of the OSHA 1910.1001 standard relating to maintenance
- Proper response to fiber release episodes
- Procedure to be followed to isolate areas affected by fiber release

e) Access to Information

OEMS shall make available to affected employees or their representative's copies of the Occupational Safety and Health Administration (OSHA) General Industry Standard Part 1910.1001 and the department shall post a copy in the workplace.

f) Record Keeping

OEMS shall maintain an accurate record of all employee exposure measurements. OEMS and/or the School District of Philadelphia Human Resources Department shall maintain records of employee medical monitoring program. OEMS shall maintain all employee training records. All records shall be provided upon request to employees, former employees, representatives designated by the individual employee.

7. AHERA OPERATIONS AND MAINTENANCE PLAN

a) CONTROLS

i. Work Order System

Minimizing disruption of ACM/PACM during maintenance and renovation activities is the primary goal and task encountered by OEMS. Operations and maintenance employees and contractors should be warned to avoid conducting any maintenance work which may disturb ACM/PACM. Initiating a work order system, where all work orders or requests are channeled through the Office of Environmental Management and Services (OEMS), will be the method used to control and minimize disruption of ACM/PACM.

Any work performed by in-house personnel or contractors that could or will impact ACM/PACM shall be coordinated by OEMS. A completed Asbestos Inspection Report Form (Attachment 1) shall be issued to in-house personnel and/or all contractors whose work could impact ACM/PACM. This form should accompany each contract issued to an outside contractor and posted on the jobsite.

All work order requests for maintenance and renovation activities in areas where ACM/PACM is suspected or known to be present are to be submitted to OEMS prior to proceeding with work. OEMS is responsible for reviewing asbestos survey records for information about the presence of ACM/PACM in the area where the work is to be performed. OEMS should physically inspect the area to ensure existing records reflect actual conditions. If no asbestos is present, a work order is not necessary and the planned actions can proceed. If ACM/PACM is found to be present in the area, OEMS will sign the work order application and obtain an approved and accredited asbestos contractor or assign OEMS "A-TEAM" to abate the ACM/PACM.

ii. Regulated Areas

The owner will identify and regulate all areas where airborne concentrations of ACM/PACM exceed the Permissible Exposure Limit (PEL)* (Per OSHA determined to be 0.1 f/cc) and/or short term exposure limit (STEL) (Per OSHA determined to be 0.1 f/cc), or there is reasonable possibility that the (PEL) and/or (STEL) may be exceeded. All ACM/PACM removal activities involving thermal system insulation ACM/PACM (Class I), surfacing ACM/PACM (Class I), and miscellaneous ACM/PACM such as floor tile, roofing, and siding mastic, etc. (Class II), and repair and maintenance operations where thermal system insulation and surfacing ACM/PACM is likely to be disturbed (Class III) will be performed in accordance with federal, state, and local regulations. All asbestos abatement work and activities will be designed and managed as asbestos regulated areas. These areas will be demarcated and labeled.

iii. Warning Signs

Warning signs shall be displayed at all approaches to each asbestos regulated area. The asbestos abatement contractor will provide OSHA warning signs in all regulated areas during removal, repair, and other maintenance activities. OEMS will provide AIRs to all contractors who must inform all employees and supervisors working in locations contiguous to asbestos regulated areas of the potential hazards and work practices required.

iv. Warning Labels

Warning labels and/or signage shall be affixed to all raw materials, mixtures, scrap, waste, debris, and other products containing asbestos fibers, or to their containers. Generally, the asbestos abatement contractor or OEMS A-Team personnel will provide all warning labels for ACM/PACM containment.

8. O & M RESPONSE ACTIONS

The Asbestos Management Program general O&M procedures are outlined in this section. Additional requirements specific to asbestos abatement activities are included in the Project Design documents for all Asbestos Abatement Work. Regular cleaning, inspection, and reporting of ACM/PACM deterioration or other problems must be diligently practiced by all employees including custodial and maintenance personnel.

a) Facility Maintenance Isolation of Area Responsibilities

Maintenance personnel are often required to work in areas where ACM/PACM may potentially be disturbed. Most maintenance activities are conducted by in-house staff, outside contractors, or a combination.

Emergency fiber release episodes, such as pipe fitting or valve breaks, emergency boiler work, or mechanical equipment repair will be responded to by OEMS A-Team personnel or asbestos abatement contractor personnel. The owner's maintenance staff will: (1) isolate the emergency fiber release area; (2) post warning signs to prevent unauthorized access, and (3) notify their supervisor and OEMS. OEMS will ensure that the fiber release area remains isolated and is properly cleaned by and approved and accredited abatement contractor or by OEMS A-TEAM personnel.

b) Unlikely Contact with ACM/PACM

Maintenance activities or repairs which can be performed without contacting or disturbing the ACM/PACM require little more than normal care and good workmanship. For example, valves which are either uncovered or covered with non-asbestos insulation can be packed or repaired without disturbing asbestos insulation on nearby pipes. The major precaution is to ensure that maintenance and custodial personnel are familiar with procedures such as isolating the area, posting warning signs, and notifying OEMS in the event of any accidental ACM/PACM disturbance.

c) Accidental Disturbance of ACM/PACM

Maintenance and facilities personnel shall notify OEMS any time a fiber release is suspected. If friable ACM/PACM becomes airborne in the building,

d) Planned Disturbance of ACM/PACM

Maintenance activities that may impact ACM/PACM include access to a valve, flange, duct, or related system component.

Where asbestos-containing insulation must be removed to maintain or repair the thermal system, the ACM/PACM will imminently be disturbed. ACM/PACM removal work shall be conducted by OEMS A-Team personnel or an approved and accredited asbestos abatement contractor.

If friable ACM/PACM becomes airborne in the building, maintenance and facilities personnel shall secure the area and contact OEMS. OEMS shall respond accordingly.

e) Miscellaneous ACM/PACM

Miscellaneous types of ACM/PACM may include vinyl asbestos floor tiles, mastics/adhesives and woven vibration dampers. Disturbance of these materials should be avoided. Routine maintenance activities involving these materials should not pose a problem if handled properly. Questions on the proper removal and disposal of miscellaneous ACM/PACM should be directed to OEMS. OEMS will contact an approved and accredited asbestos abatement contractor or utilize OEMS A-TEAM personnel to assist with miscellaneous ACM/PACM clean-up activities.

f) Vinyl Asbestos Floor Tile

Asbestos-containing floor tiles in good condition are considered non-friable unless they are crushed, drilled, sawed, sanded or disturbed by any activity that breaks up the material. Routine maintenance of these materials should employ the use of non-abrasive buffers and wet cleaning technique. Broken or loose floor tiles should be removed and disposed of as asbestos waste by OEMS. Remaining debris should be vacuumed with a HEPA vacuum and the area wet mopped using amended water.

g) Mastics/Adhesives

Mastics and adhesives containing asbestos in good condition are considered non-friable and do not pose a potential health concern unless crushed, drilled, sawed, sanded, or otherwise abraded. Questions on the proper removal should be directed to OEMS.

h) Woven Vibration Dampers

Woven vibration dampers in good condition are considered non-friable and do not pose a potential health concern unless cut, crushed, drilled, sawed, sanded, or otherwise abraded. Questions on the proper removal should be directed to OEMS.

i) Other Work Practices

Any special work not included in this section should be addressed to OEMS for review prior to the initiation of work that may involve the disturbance of ACM/PACM.

j) Fiber Release Episodes

Facilities and maintenance staff should report to OEMS the presence of asbestos debris, water or physical damage to ACM/PACM, or any other evidence of possible fiber release. OEMS should have the OEMS A-Team personnel or an approved and accredited abatement contractor respond to the site to clean up debris and make repairs as soon as possible. OEMS will also contact a consultant to conduct air monitoring and prepare a report and submit at project completion to OEMS for each episode. OEMS will forward the reports for each site location AHERA Management Plan accordingly.

9. REFERENCES and RESOURCES

Applicable regulations for asbestos projects impacted by renovation, demolition, and maintenance activities.

- **Philadelphia Air Management Services – Asbestos Control Unit**
<http://www.phila.gov/health/units/ams/Asbestos/asbestos.html>
- **Pennsylvania Asbestos Occupations, Accreditation and Certification Act**
<http://www.dli.state.pa.us/landi/cwp/view.asp?a=185&q=56262&landiNav=>
- **United States Environmental Protection Agency Asbestos Home Page**
<http://www.epa.gov/asbestos/>
- **Occupational Safety and Health Administration (OSHA) Asbestos Home**
<http://www.osha.gov/SLTC/asbestos>