

SCHOOL DISTRICT OF PHILADELPHIA



Asbestos Hazard Emergency Response Act “AHERA”

THREE-YEAR RE-INSPECTION 2015-2016 and ASBESTOS MANAGEMENT PLAN for the

ASPIRA Olney Charter High School

**ULCS# 7020
Building # B705001-1
100 E. Duncannon Street
Philadelphia, Pennsylvania
19120**

Year Built: 1931

December 2015

Conducted by:

Accredited Environmental Technologies, Incorporated
Batta Environmental Associates, Incorporated
Criterion Laboratories, Incorporated
Environmental Testing Consultants, LLC
G & C Environmental Services, Incorporated
KEM Partners, Incorporated
Synertech, Inc.
TTI Environmental, Inc.
USA Environmental Management, Inc.
The Vertex Companies, Inc.

Management Plan Prepared by:
Criterion Labs, Inc and Synertech Inc.

This report must remain in the Main Office as mandated by the US EPA AHERA Regulations.

AHERA THREE-YEAR REINSPECTION VOLUME IX

Table of Contents

Transmittal Letter

Executive Summary

- I. Summary list of Confirmed Asbestos Containing Building Materials
- II. Summary list of Assumed Asbestos Contain Building Materials
- III. Summary list of Non-Asbestos Containing Building Materials
- IV. Summary list of Non Suspect Asbestos Containing Building Materials
- V. Summary List of Auditorium DATA for this location
- VI. Summary list of Attic and/or Crawlspace DATA for this location
- VII. Summary list of Pipe Chase/Pipe Shaft DATA for this location

Section I Report of Re-Inspection

- A. Introduction
- B. Three-Year Re-inspection IX Overview
- C. Post- Management Plan Activities and Changes
 - C.1 - Sampling and Analysis
 - C.2 - New Floor Tile Sampling
 - C.3 - Abatement Activity
 - C.4 - Periodic (Six-Month) Surveillance (Damaged Materials)

Section II Re-Inspection Data

- A. Introduction
- B. Re-Inspection Key Definitions
- C. Room by Room Location Log Report

Section III Certificates

- A. Management Planner/Building Inspector Certificates

| | | |
|-------------------|------------------------------|-----------|
| Section IV | Cross Reference Table | Page 1-8 |
| | Asbestos Management Program | Page 9-19 |

SCHOOL DISTRICT OF PHILADELPHIA
EDUCATIONAL CENTER
440 NORTH BROAD STREET
PHILADELPHIA, PENNSYLVANIA 19130

OFFICE OF ENVIRONMENTAL MANAGEMENT AND SERVICES

PHONE (215)-400-4750

January 2016

TO: All Principals
All Building Administrators

FROM: Fran Burns
Chief Operating Officer

Francine Locke, M.S., Director
Office of Environmental Management and Services

SUBJECT: AHERA Three (3) Year Re-inspection IX report

In order to comply with the provisions of the Asbestos Hazard Emergency Response Act (AHERA) the attached report is submitted to you. The law requires that this report be kept in the Main/Principal's office. It cannot be removed from these locations. *If the school (program) is relocated to a different building, these environmental documents are to be safely retained for the next school/building occupants.* All asbestos reports must be available to the public and Federal EPA upon request.



Fran Burns
Chief Operation Officer

Francine Locke, M.S., Director
Office of Environmental Management
and Services

Executive Summary

This Asbestos Hazard Emergency Response Act (AHERA) Three-Year Re-inspection “Volume # IX” Management Plan at this location, has been completed and the report of re-inspection submitted to the School District of Philadelphia. The re-inspections in all School District of Philadelphia buildings of 2015-2016 were conducted and completed between October 5th, 2015 through March 30th, 2016 as a joint project by Accredited Environmental Technologies, Inc., Batta Environmental Associates, Inc., Criterion Laboratories, Inc., Environmental Testing Consultants, LLC, G & C Environmental Services, Inc., KEM Partners, Inc., Synertech, Inc., TTI Environmental, Inc., USA Environmental Management, Inc. and The Vertex Companies, Inc.

In general, the School District of Philadelphia Office of Environmental Management and Services conducts Environmental Impact Evaluations and provides Asbestos Inspection Reports prior to any renovation, demolition and/or maintenance activities. The AHERA report must be reviewed prior to any renovation, demolition and/or maintenance activities in order to avoid the unknowing disturbance to Asbestos Containing Building Materials identified within this location. In addition, prior to work activities above all drop ceilings this report should be reviewed to avoid potential disturbances to Asbestos Containing Materials. Refer to Section IV of the Cross Reference Table, for additional Asbestos Management Program information. Contact the Office of Environmental Management and Services to have an Environmental Impact Evaluation conducted prior to any renovation, demolition and/or maintenance activities within this facility.

The information contained in this report was obtained from the original Asbestos Management Plan for the school, from update reports on changes and activities since the completion of the 1st Management Plan for each location and from all prior inspections performed and documented in Volume # I through Volume VIII (dated respectively 1992, 1995, 1998, 2001, 2004, 2007, 2010 or 2013) (if applicable) - and by this Three-Year Re-inspection of this school. The re-inspection report/Management Plan of 2015-2016 were reviewed and prepared collectively by Management Planner Megan Vala, Mary Anne Lerro of Criterion Laboratories, Inc. and/or Monique Causley, of Synertech Inc.

The 2015-2016 inspection process included the addition of a comprehensive Room by Room Inventory of all Thermal (T), Surfacing (S) and Miscellaneous (M) Materials specific to each room of this facility. Inspections of each room's thermal, ceilings, walls, floors and miscellaneous items regardless of Asbestos Content are categorized on the Room by Room Location Log Report for this location. Rooms or areas of the facility that were not accessible at the time of the inspection are marked with an "X". The Room by Room Location Log Report is found in Section II C of this Management Plan.

All Presumed or Suspect Asbestos Containing Building Materials (ACBMs), listed in the following summary charts are categorized as Confirmed, Assumed, Non-Asbestos, and/or Non-Suspect (ACBMs) were identified in the original Management Plan, or in the Volume I through Volume VIII AHERA Three-Year Re-inspection reports, and were re-inspected as part of this project.

As mandated by the U S EPA AHERA regulations, periodic Six-Month inspections and Three-Year Re-inspections of this location will be performed and the Inspection Data in this report will be updated accordingly.

Please feel free to contact the School District of Philadelphia's Office of Environmental Management and Services (OEMS) regarding any comments, questions, or concerns regarding this report or any Environmental related topic. OEMS staff can be reached at (215) 400 4750, via fax at (215) 400 4751 or via e-mail at flocke@philasd.org and/or gfunod@philasd.org.

Additional information can be found on our website. Here is the link to the OEMS website.
<http://webgui.phila.k12.pa.us/offices/e/environmental>

I. Summary list of Confirmed Asbestos Containing Building Materials within this facility

These charts are to be used for a quick reference* in order to avoid the unknowing disturbance of Asbestos Containing Materials during any and all Operations, Maintenance, Renovation, and/or Demolition activities at this location. *These materials have been sampled and Laboratory Analysis has CONFIRMED the presence of Asbestos. Contact OEMS prior to the disturbance of any of the following materials.*

Confirmed Asbestos Containing Building Materials for this location

| | | |
|--------------------------|-------------------------|--------------------------|
| Floor Tile VAT 9" x 9" | Pipe Fitting Insulation | Pipe Insulation > 6 inch |
| Pipe Insulation 2-6 inch | Radiator Insulation | |

** Always refer to the Room by Room Logs for each specific material classification as the material classification findings may be different in various rooms throughout this facility.*

*** Some Materials may have multiple classifications (Confirmed, Assumed, NAD and Non Suspect) within this facility.*

II. Summary list of Assumed Asbestos Containing Building Materials within this facility

These charts are to be used for a quick reference* in order to avoid the unknowing disturbance of Asbestos Containing Materials during any and all Operations, Maintenance, Renovation, and/or Demolition activities at this location. These materials have not been sampled and should not be disturbed until verification of Asbestos Content. Contact OEMS for assessment and sampling prior to the disturbance of these materials.

Assumed Asbestos Containing Building Materials for this location

| | | |
|--------------------------|----------------------------|--------------------------|
| Blackboard Glue Dots | Floor Tile VAT 12" x 12" | Linoleum |
| Partition Room Dividers | Pipe Fitting Insulation | Pipe Insulation > 6 inch |
| Pipe Insulation 2-6 inch | Plaster Ceiling | Stage Lights Wiring |
| Transite Counter Tops | Transite Electrical Panel | Transite Lab Tables |
| Transite Sink | Unit Ventilator Insulation | Vibration Damper Cloth |

** Always refer to the Room by Room Logs for each specific material classification as the material classification findings may be different in various rooms throughout this facility.*

*** Some Materials may have multiple classifications (Confirmed, Assumed, NAD and Non Suspect) within this facility.*

III. Summary list of Non-Asbestos Containing Building Materials within this facility

These charts are to be used for a quick reference* in order to avoid the unknowing disturbance of Asbestos Containing Materials during any and all Operations, Maintenance, Renovation, and/or Demolition activities at this location. *These materials have been sampled and Laboratory Analysis has indicated NO Asbestos present or NO ASBESTOS DETECTED (NAD).*

Non- Asbestos Containing Building Materials for this location

| | | |
|----------------------|----------------------|----------------------|
| Ceiling Tile 1' x 1' | Ceiling Tile 2' x 2' | Ceiling Tile 2' x 4' |
| Plaster Ceiling | Plaster Walls | |

* *Always refer to the Room by Room Logs for each specific material classification as the material classification findings may be different in various rooms throughout this facility.*

** *Some Materials may have multiple classifications (Confirmed, Assumed, NAD and Non Suspect) within this facility.*

IV. Summary list of Non-Suspect Asbestos Containing Building Materials within this facility

These charts are to be used for a quick reference* in order to avoid the unknowing disturbance of Asbestos Containing Materials during any and all Operations, Maintenance, Renovation, and/or Demolition activities at this location. These materials are not typically known to contain Asbestos.

Non-Suspect Asbestos Containing Building Materials for this location

| | | |
|---------------------------------|------------------------------------|----------------------------|
| Brick Wall | Carpet | Ceiling Tile 2' x 4' |
| Cement Floor | Ceramic Tile Floors | Ceramic Tile Walls |
| CMU | Concrete Block Wall | Concrete Ceiling |
| Fiberglass Ceiling Tile 2' x 4' | Fiberglass Pipe Fitting Insulation | Fiberglass Pipe Insulation |
| Glass Ceiling | Marble Walls | Sheetrock Wall |
| Wood Floor | | |

** Always refer to the Room by Room Logs for each specific material classification as the material classification findings may be different in various rooms throughout this facility.*

*** Some Materials may have multiple classifications (Confirmed, Assumed, NAD and Non Suspect) within this facility.*

V. Summary list of Auditorium DATA for this location

These charts are to be used for a quick reference of the Auditorium DATA within this facility. Sampling of the Auditorium Ceilings throughout the District is more difficult because of the various ceiling heights. As sampling occurs this information is updated on a case by case basis for each specific location and facility.

This is a list of known materials for this location's Auditorium

| Auditorium | | |
|-------------------|---------------------|-----------------|
| Auditorium | Wood Floor | Non Suspect ACM |
| Auditorium | Plaster Ceiling | Assumed |
| Auditorium | Plaster Walls | NAD |
| Auditorium | Radiator Insulation | Confirmed |
| Auditorium | Stage Lights Wiring | Assumed |

** Always refer to the Room by Room Logs for each specific material classification as the material classification findings may be different in various rooms throughout this facility.*

*** Some Materials may have multiple classifications (Confirmed, Assumed, NAD and Non Suspect) within this facility.*

VI. Summary list of Attic and/or Crawlspace DATA for this location

These charts are to be used for a quick reference regarding the Attics and/or Crawlspaces inspection DATA within this facility. Contact OEMS prior to entering any attic or crawlspace within this facility and refer to the below chart and legend for Category Rank determination. The Data relative to these spaces is updated as conditions change regarding Abatement or Renovation activity on a case by case basis for each specific location and facility. In general, Crawlspaces are below the basement or 1st floor and Attics are above the floor space.

Category Rank Legend

| |
|---|
| "A" - No Asbestos Containing Materials - Sample Results indicate NO ACM on pipes, fittings, elbows, or equipment located within this functional space, and NO VISIBLE DEBRIS or DAMAGE observed at time of this inspection. |
| "B" - Asbestos Containing Materials Exist - Sample Results indicate ACM on pipes, fittings, elbows, or equipment located within this functional space, HOWEVER, NO VISIBLE DEBRIS or DAMAGE observed at time of this inspection. |
| "C" - Asbestos Containing Materials Exist - Sample Results indicate ACM on pipes, fittings, elbows, or equipment located within this functional space, and LOCALIZED VISIBLE DEBRIS or DAMAGE observed at time of this inspection. |
| "D" - Asbestos Containing Materials Exist - Sample Results indicate ACM on pipes, fittings, elbows, or equipment located within this functional space and DISTRIBUTED VISIBLE DEBRIS or SIGNIFICANT DAMAGE observed at time of this inspection. |
| "E" - No Bulk Sample Results Available SUSPECT ACM OBSERVED. Contact OEMS immediately for additional instructions. |

| Attic/Crawlspace | Access Area | Floor Surface | Category Rank | Comments |
|------------------|--------------------------------------|---------------|---------------|--|
| Attic | 5th Floor Stairwell #5 | Wire Lathe | D | Sealed Shut w/asbestos sign |
| Attic | 5th Floor Hallway | Wire Lathe | D | 300 Air Cell/50 Hard Fittings/600 Mag Blck |
| Crawl Space | Basement Fan Room | Concrete | B | 300 LF 2"-6" Mag Block undamaged |
| Crawl Space | Storage Room near Time clock | Concrete | A | Likely duplicated entry/See additional entries below |
| Crawl Space | Hall across from Fan Room | Unknown | ? | Door Screwed shut |
| Crawl Space | Storage Room near Time Clock (lower) | Concrete | ? | Access blocked by equipment/Upper/Lower CS likely mixed up from prior inspection 11/16/10. Inspector could not inspect |
| Crawl Space | Storage Rm near Time Clock (upper) | Concrete | C to A | No spray on insulation in Upper CS/Upper/Lower likely mixed up from prior inspection 11/16/10 |

VII. Summary list of Pipe Chase/Pipe Shaft DATA for this location

These charts are to be used for a quick reference regarding the information known about the Pipe Chases and/or Pipe Shafts inspection DATA within this facility. Contact OEMS prior to performing renovation activities any Pipe Chase and/or Pipe Shaft within this facility and refer to the below chart and legend for Asbestos Content of various materials identified within each space. The Data relative to these spaces is updated as conditions change regarding Inspection, Abatement and/or Renovation activity on a case by case basis for each specific location and facility. In general, Pipe Chases are horizontal spaces and Pipe Shafts are vertical spaces.

Pipe Chases and Pipe Shafts need to be assessed.

Section I

Report of Re-Inspection

A. Introduction

B. Three-Year Re-Inspection IX Overview

C. Post-Management Plan Activities and Changes

C.1 Sampling and Analysis

C.2 New Floor Tile Sampling

C.3 Abatement Activity

C.4 Periodic Six-Month Surveillance (Damaged Materials)

Section I - A

Report of Re-inspection

Introduction

The Three-Year Re-inspection IX was performed to fulfill the requirements of 40 CFR Part 763 - the Asbestos Hazard Emergency Response Act (AHERA). As required by AHERA, each Local Education Agency (LEA) must re-inspect all known confirmed or assumed Asbestos Containing Building Material (ACBM) located in the LEA's facilities. This re-inspection is intended to update the original Asbestos Management Plan for the LEA's facilities.

Multiple Building Inspectors of several firms performed the 2015/2016 re-inspection. The re-inspection report/Management Plan of 2015-2016 were reviewed and prepared collectively by Management Planner Megan Vala, Mary Anne Lerro of Criterion Laboratories, Inc. and Monique Causley, of Synertech Inc.

All of the certificates can be found in Section III.

During the re-inspection of each School District of Philadelphia facility, all of the Management Plans for that facility were reviewed. Information from the conclusions section of that report is included in this report. Additionally, information on activities such as abatements, cleanings, sampling and inspections, which have taken place since the completion of the original Management Plan, were reviewed during the re-inspection. Information on those activities is included in this report.

As mandated by the U S EPA AHERA regulations, all future periodic Six-Month inspections and Three-Year Re-inspections of this location will be performed and the Inspection Data in this report will be updated accordingly.

Section I - B

Three-Year Re-inspection IX Overview

Each homogeneous area of Asbestos Containing Building Material (ACBM) listed in the original Management Plan or in the 1992, 1995, 1998, 2001, etc., Three-Year Re-inspection reports were inspected for the AHERA Three-Year Re-inspection Volume IX, and the information for that material verified. Any changes to a homogeneous area listed in the updates to the Management Plans were verified. Any area of suspected ACBM found in the course of the re-inspection, and not listed in the Management Plan or updates, were either assumed to contain asbestos or sampled and analyzed to determine their asbestos content. Any such new areas either assumed to contain asbestos or determined through analysis to contain asbestos were included in the report of the Three-Year Re-inspection. The results of the AHERA Three-Year Re-inspection IX are tabulated in the Room by Room log reports located in *Section II-C* of this report.

As previously noted, all future periodic Six-Month inspections and Three-Year Re-inspections of this location will be performed and the Inspection Data in this report will be updated accordingly.

Section I – C.1

Post Management Plan Activities/Changes

Information on activities affecting Asbestos Containing Building Materials (ACBMs) at this location is contained in updates to the Management Plan. These updates are kept on file by the School District of Philadelphia and were reviewed for this project. Updates to the Management Plan include the following: *Sampling and Analysis, New Tile Installation, Abatement Activity and Periodic Six-Month Surveillance Data.*

Sampling and Analysis

In the event Sampling occurs, data will be listed here.

Section I – C.2

Information on the installation of new floor tiles/renovation activities affecting Asbestos Containing Building Materials (ACBMs) at this location is contained in updates to the Management Plan. These updates are kept on file by the School District of Philadelphia and were reviewed for this project. Updates to the Management Plan include the following:

New Floor Tile Sampling

In the event that new tile is installed, the material must be tested prior to installation.

Section I – C.3

Information on the Asbestos Abatement and renovation activities affecting Asbestos Containing Building Materials (ACBMs) at this location is contained in updates to the Management Plan. These updates are kept on file by the School District of Philadelphia and were reviewed for this project. Updates to the Management Plan include the following:

Abatement Activity

In the event Abatement occurs, data will be listed here.

Section I – C.4

Information on the AHERA inspection that noted damage to various Building Materials at this location is contained in updates to the Management Plan. These updates are kept on file by the School District of Philadelphia and were reviewed for this project. Work orders are created for Corrective Action responses and tracked for completion. Updates to the Management Plan include the following:

Periodic (Six-Month) Surveillance (Damaged Materials)

| <i>Date</i> | <i>Element</i> | <i>Floor</i> | <i>On Site Room Name</i> | <i>Material</i> | <i>Amount of Material</i> | <i>Amount of Damage</i> |
|-------------|----------------|--------------|--|--------------------------|---------------------------|-------------------------|
| 11/10/2016 | 1 | 1 | Classroom 111 | Pipe Insulation 2-6 inch | 70 LF | 1 LF |
| 11/10/2016 | 1 | 1 | Classroom 111 | Pipe Fitting Insulation | 22 EA | 2 EA |
| 11/10/2016 | 1 | 1 | Boy's Restroom next to Classroom 111 | Pipe Insulation 2-6 inch | 36 LF | 2 LF |
| 11/10/2016 | 1 | 1 | Classroom 120 | Floor Tile VAT 9" x 9" | 754 SF | 3 SF |
| 11/10/2016 | 1 | 1 | Office 125 | Pipe Insulation 2-6 inch | 80 LF | 2 LF |
| 11/10/2016 | 1 | 1 | Cafeteria closest to Office 125 | Pipe Insulation > 6 inch | 10 LF | 1 LF |
| 11/10/2016 | 1 | 2 | Classroom 218 | Floor Tile VAT 9" x 9" | 748 SF | 4 SF |
| 11/10/2016 | 1 | 2 | Classroom 221 | Pipe Fitting Insulation | 10 EA | 1 EA |
| 11/10/2016 | 1 | 2 | Classroom 225 | Pipe Insulation 2-6 inch | 32 LF | 2 LF |
| 11/10/2016 | 1 | 2 | Office 227 | Pipe Insulation > 6 inch | 23 LF | 2 LF |
| 11/10/2016 | 1 | 2 | Classroom 239 | Pipe Fitting Insulation | 10 EA | 1 EA |
| 11/10/2016 | 1 | 2 | Classroom 241 | Pipe Insulation 2-6 inch | 66 LF | 2 LF |
| 11/10/2016 | 1 | 2 | Classroom 251 | Pipe Fitting Insulation | 39 EA | 5 EA |
| 11/10/2016 | 1 | 2 | Office 263 | Pipe Insulation 2-6 inch | 14 LF | 2 LF |
| 11/10/2016 | 1 | 2 | Women's Restroom at Main Entrance Stairwell | Pipe Fitting Insulation | 16 EA | 2 EA |
| 11/10/2016 | 1 | 2 | Main Office | Pipe Insulation 2-6 inch | 12 LF | 1 LF |
| 11/10/2016 | 1 | 2 | Main Office Storage Room attached to Larger Storage Room | Pipe Insulation 2-6 inch | 48 LF | 2 LF |
| 11/10/2016 | 1 | 3 | Classroom 341 | Pipe Insulation 2-6 inch | 56 LF | 2 LF |
| 11/10/2016 | 1 | 3 | Classroom 337 | Pipe Insulation 2-6 inch | 51 LF | 2 LF |
| 11/10/2016 | 1 | 3 | Classroom 325 | Pipe Insulation 2-6 inch | 40 LF | 2 LF |
| 11/10/2016 | 1 | 3 | Girl's Restroom | Pipe Fitting Insulation | 9 EA | 2 EA |
| 11/10/2016 | 1 | 3 | Classroom 311 | Pipe Fitting Insulation | 10 EA | 1 EA |
| 11/10/2016 | 1 | 3 | Main Storage Room attached to Classroom 371 Closet Window Side | Pipe Fitting Insulation | 3 EA | 1 EA |
| 11/10/2016 | 1 | 3 | Classroom 357 | Floor Tile VAT 9" x 9" | 558 SF | 3 SF |
| 11/10/2016 | 1 | 3 | Classroom 355 | Pipe Insulation 2-6 inch | 14 LF | 2 LF |
| 11/10/2016 | 1 | 4 | Computer Room 453 | Pipe Insulation 2-6 inch | 28 LF | 2 LF |

Periodic (Six-Month) Surveillance (Damaged Materials) continued

| <i>Date</i> | <i>Element</i> | <i>Floor</i> | <i>On Site Room Name</i> | <i>Material</i> | <i>Amount of Material</i> | <i>Amount of Damage</i> |
|-------------|----------------|--------------|--|--------------------------|---------------------------|-------------------------|
| 11/10/2016 | 1 | 4 | Classroom 421 | Pipe Insulation 2-6 inch | 28 LF | 2 LF |
| 11/10/2016 | 1 | 4 | Copy Room across from Computer Room 453 | Floor Tile VAT 9" x 9" | 234 SF | 1 SF |
| 11/10/2016 | 1 | 5 | Stairwell Leading to abandoned 5th Floor | Pipe Fitting Insulation | 4 EA | 4 EA |
| 11/10/2016 | 1 | 5 | Stairwell Leading to abandoned 5th Floor | Pipe Insulation > 6 inch | 20 LF | 1 LF |
| 11/10/2016 | 1 | B | Vacant Classroom Directly across from door labeled T10 | Floor Tile VAT 12" x 12" | 624 SF | 3 SF |
| 11/10/2016 | 1 | B | Hallway just inside door labeled T10 | Floor Tile VAT 12" x 12" | 216 SF | 4 SF |
| 11/10/2016 | 2 | 1 | Storage Room next to Former Classroom T5 | Floor Tile VAT 12" x 12" | 576 SF | 4 SF |

Section II

Re-Inspection Data

A. Introduction

B. Re-Inspection Key Definitions

C. Room by Room Location Log Report

Section II - A

Re-inspection Data

Introduction

The following information documents the Three-Year Re-inspection IX of the subject school/facility. The Homogeneous Area Reports were produced using the building inspector's field data on the facility. The key to the Homogeneous Area Report is outlined in the following pages of this report.

Section II - B
(page 1 of 4)

SCHOOL DISTRICT OF PHILADELPHIA
AHERA THREE YEAR RE-INSPECTION IX

| ITEM | DEFINITION |
|---------------------------------|---|
| ULCS# | Individual identification number assigned to each school within the School District of Philadelphia. |
| HOMOGENEOUS AREA ID# | Identification number assigned to each homogeneous area in a school/facility. Each section of the homogeneous area ID is significant. 1010/01/01/01 A B C D A. Is the ULCS# for the school. B. Designates the specific building/building area within the school. C. Designates the floor or level within the building/building area. D. Designates the homogeneous material within that floor or level. Note: Item D may be a number or a letter. |
| SYSTEM AFFECTED | Corresponds to the AHERA system for classifying materials. T : Thermal System S : Surfacing System M : Miscellaneous |
| ITEM AFFECTED | Is a description of the homogeneous material. |
| ORIGINAL INSPECTION DATA | This section contains the information found in the original Management Plan (1988-1989). |
| AMOUNT OF MATERIAL/ UNIT | Quantity of material, and measuring unit. Units include: Square Feet (SF) Each (EA) Linear Feet (LF) Cubic Feet (CF). |

**SCHOOL DISTRICT OF PHILADELPHIA
AHERA THREE YEAR RE-INSPECTION IX**

RE-INSPECTION FORM KEY

| ITEM | DEFINITION |
|--------------------------------------|---|
| CND Condition | Corresponds to AHERA condition rating for materials. 0 : No Damage 1 : Damage 2 : Significant Damage |
| DP Damage Potential | Corresponds to the AHERA material assessment system. 1 : Potential for Damage 2 : Potential for Significant Damage |
| ASMD Assumed Asbestos | This means that a material was not sampled for asbestos content during the original Management Plan inspection. |
| RA Response Action | This corresponds to the AHERA system of response action rating for materials. 1 : Establish O&M Program 2 : Repair and Establish O&M Program 3 : Enclose 4 : Encapsulate 5 : Remove 6 : Partial Removal and Establish O&M Program |
| CHANGES | This section describes changes to the homogeneous material in the twenty-four years since the original AHERA inspection. The abbreviations are defined below. RMVD : Removed ENCL : Enclosed ENCP : Encapsulated DMGD : Damaged SMPLD : Sampled MTRL : Material RPRD : Repaired N/L : None Located RPLCD : Replaced |

**SCHOOL DISTRICT OF PHILADELPHIA
AHERA THREE-YEAR RE-INSPECTION IX**

RE-INSPECTION FORM KEY

| ITEM | DEFINITION | | | | | | | | | | | | |
|-------------------------------------|---|----|-----------------------|----|----------------------------------|----|---------|----|-------------|----|--------|----|---|
| THREE YEAR RE-INSPECTION | <p>This section contains the information obtained from the Three-Year Re-inspection IX. With three exceptions, the information categories are identical in format and meaning to those found in the original inspection data section. The three exceptions are defined below.</p> | | | | | | | | | | | | |
| DMGD AMT Amount Damaged | <p>This section gives the quantity of damaged material in a homogeneous area. The quantity is shown in the same format as the amount of material/unit section.</p> | | | | | | | | | | | | |
| NF Newly Friable | <p>This section identifies materials in the original Management Plan which have since become friable.</p> | | | | | | | | | | | | |
| RA Response Action | <p>This rating is based on the AHERA regulations, and is comparable to the RA rating found in the "Original Inspection Data" section. The following table details the response actions.</p> <table><tr><td>1.</td><td>Establish O&M Program</td></tr><tr><td>2.</td><td>Repair and Establish O&M Program</td></tr><tr><td>3.</td><td>Enclose</td></tr><tr><td>4.</td><td>Encapsulate</td></tr><tr><td>5.</td><td>Remove</td></tr><tr><td>6.</td><td>Partial Removal and Establish O&M Program</td></tr></table> <p>a. High Priority Response The homogeneous material has been scheduled for abatement or other response action.</p> <p>b. Medium Priority Response The homogeneous material will be scheduled for abatement or other response action as soon as the high priority responses have been addressed.</p> <p>c. Low Priority Response The homogeneous material will be scheduled for abatement or other response action as soon as the medium priority responses have been addressed.</p> <p>d. On-Going Response/Operations and Maintenance The homogeneous material does not require abatement or other response action at present, and should be included in the facility's on-going operations and maintenance program.</p> | 1. | Establish O&M Program | 2. | Repair and Establish O&M Program | 3. | Enclose | 4. | Encapsulate | 5. | Remove | 6. | Partial Removal and Establish O&M Program |
| 1. | Establish O&M Program | | | | | | | | | | | | |
| 2. | Repair and Establish O&M Program | | | | | | | | | | | | |
| 3. | Enclose | | | | | | | | | | | | |
| 4. | Encapsulate | | | | | | | | | | | | |
| 5. | Remove | | | | | | | | | | | | |
| 6. | Partial Removal and Establish O&M Program | | | | | | | | | | | | |

**SCHOOL DISTRICT OF PHILADELPHIA
AHERA THREE-YEAR RE-INSPECTION IX**

RE-INSPECTION FORM KEY

The information presented in the changes section has been compiled from a variety of sources, including the Re-inspection and the following:

- * Quality Control/Quality Assurance Reports of asbestos abatement projects, prepared by consultants to the School District.
- * Permit and Notification Forms for asbestos abatement projects.
- * Periodic Surveillance Forms
- * Operations and Maintenance activities performed by School District personnel.
- * Verbal information from School District personnel.
- * Reports of sampling and analysis of suspected materials by both School District personnel and outside consultants.

**ROOM BY
ROOM
LOCATION LOG
REPORT**

This section gives information, including damage amount and location, for a specific homogeneous material on a room-by-room basis and follows the Re-inspection form.

NOTE: The disparate nature of the above sources of information prohibits the verification of much information within the scope of the AHERA Three-Year Re-inspection. Discrepancies and omissions may exist in this information, and therefore is included on an "as is" basis. The inspectors for the Three-Year Re-inspection IX evaluated homogeneous areas based on the materials current condition and location, as evidenced during the inspector's site visit.

Section II - C

Room by Room Location Log Report

These charts are to be used for a quick reference* in order to avoid the unknowing disturbance of Asbestos Containing Materials during any and all Operations, Maintenance, Renovation, and/or Demolition activities at this location.

NOTE:

Contact OEMS prior to the disturbance of any of the materials that are listed as Confirmed and/or Assumed.

The quantities listed for (NAD) non-asbestos containing materials and/or Non-Suspect Materials are only estimated and were not measured for the purpose of this report. Field verification of quantities for renovation purposes would be necessary.

7020 Olney HS (ASPIRA) 2015 2016 AHERA Three-Year Report.xls

| School District of Philadelphia | | | AHERA Three-Year Reinspection 2015-2016 | | | | | | | | | | Reinspection Date: December 13, 2015 | | | |
|---|-----------------------|--|---|---------------------------------|--------------------------|---|-----------------------|-------------|---------------------|-------------|------------------------------|---|--------------------------------------|-----------------------------|--------------------------|-------------------------|
| Aspira Olney Charter High School | | | Room by Room Location Log Report | | | | | | | | | | Building Inspector: James Madden | | | |
| 100 E. Duncannon Street, Philadelphia, PA 19120 | | | | | | | | | | | | | Number: 030867 | | | |
| ULCS# 7029 | | | | | | | | | | | | | Management Planner: Megan Vala | | | |
| Year Built: 1931 | | | | | | | | | | | | | Number: 740728 | | | |
| E l e m e n t | F l o o r | On Site Room Name | System Affected | Material Description | HID# | Confirmed/Assumed/NAD/ Non Suspect ACM | Amount of Material | SF LF EA | Amount of Damage | SF LF EA | Color required for VAT | Comments/Description/Notes | Attic/ Crawl Space Ranking | Damage Potential (DP) | Newly Friable (NF) | Response Action (RA) |
| 1 | 1 | Men's Restroom next to Main Lobby | N/A | Concrete Ceiling | | Non Suspect ACM | 153 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 1 | Men's Restroom next to Main Lobby | N/A | Cement Floor | | Non Suspect ACM | 153 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 1 | Men's Restroom next to Main Lobby | N/A | Plaster Walls | | NAD | 728 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 1 | Men's Restroom next to Main Lobby | T | Pipe Insulation 2-6 inch | 7020/01/01/25 | Confirmed | 42 | LF | 0 | LF | | | | 1 | No | 1/D |
| 1 | 1 | Men's Restroom next to Main Lobby | T | Pipe Fitting Insulation | 7020/01/01/65 | Assumed | 3 | EA | 0 | EA | | | | 1 | No | 1/D |
| 1 | 1 | School Police Office near Main Lobby | N/A | Plaster Ceiling | | NAD | 442 | SF | 40 | SF | | | | N/A | N/A | N/A |
| 1 | 1 | School Police Office near Main Lobby | N/A | Cement Floor | | Non Suspect ACM | 442 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 1 | School Police Office near Main Lobby | N/A | Plaster Walls | | NAD | 1204 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 1 | School Police Office near Main Lobby | T | Pipe Insulation 2-6 inch | 7020/01/01/25 | Confirmed | 72 | LF | 0 | LF | | | | 1 | No | 1/D |
| 1 | 1 | School Police Office near Main Lobby | T | Pipe Fitting Insulation | 7020/01/01/65 | Assumed | 6 | EA | 0 | EA | | | | 1 | No | 1/D |
| 1 | 1 | School Police Office near Main Lobby | M | Blackboard Glue Dots | 7020/01/01/BATTA/AH/2600 | Assumed | 80 | SF | 0 | SF | | | | 1 | No | 1/D |
| 1 | 1 | Classroom 103 | N/A | Ceiling Tile 2' x 4' | | NAD | 780 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 1 | Classroom 103 | N/A | Wood Floor | | Non Suspect ACM | 780 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 1 | Classroom 103 | N/A | Plaster Walls | | NAD | 1200 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 1 | Classroom 103 | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 50 | LF | X | LF | | | | N/A | N/A | N/A |
| 1 | 1 | Classroom 105 | N/A | Ceiling Tile 2' x 4' | | NAD | 780 | SF | 8 | SF | | | | N/A | N/A | N/A |
| 1 | 1 | Classroom 105 | N/A | Wood Floor | | Non Suspect ACM | 780 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 1 | Classroom 105 | N/A | Plaster Walls | | NAD | 1344 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 1 | Classroom 105 | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 48 | LF | 1 | LF | | | | N/A | N/A | N/A |
| 1 | 1 | Classroom 107 | N/A | Wood Floor | | Non Suspect ACM | 750 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 1 | Classroom 107 | N/A | Plaster Walls | | NAD | 1540 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 1 | Classroom 107 | N/A | Ceiling Tile 2' x 4' | | NAD | 750 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 1 | Classroom 107 | T | Pipe Insulation 2-6 inch | 7020/01/01/25 | Confirmed | 12 | LF | 0 | LF | | | | 1 | No | 1/D |
| 1 | 1 | Closet next to Classroom 107 | X | X | | X | X | X | X | X | | No Access | | X | X | X |
| 1 | 1 | Classroom 111 | N/A | Plaster Walls | | NAD | 1596 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 1 | Classroom 111 | N/A | Plaster Ceiling | | NAD | 800 | SF | 12 | SF | | | | N/A | N/A | N/A |
| 1 | 1 | Classroom 111 | T | Pipe Insulation 2-6 inch | 7020/01/01/25 | Confirmed | 70 | LF | 1 | LF | | Slight Cracks | | 1 | Yes | 5/A |
| 1 | 1 | Classroom 111 | T | Pipe Fitting Insulation | 7020/01/01/65 | Assumed | 22 | EA | 2 | EA | | Slight Cracks | | 1 | Yes | 5/A |
| 1 | 1 | Classroom 111 | N/A | Wood Floor | | Non Suspect ACM | 800 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 1 | Classroom 111 | M | Blackboard Glue Dots | 7020/01/01/BATTA/AH/2600 | Assumed | 128 | SF | 0 | SF | | | | 1 | No | 1/D |
| 1 | 1 | Hallway from Classrooms 121 to 111 | N/A | Cement Floor | | Non Suspect ACM | 3240 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 1 | Hallway from Classrooms 121 to 111 | N/A | Plaster Walls | | NAD | 7896 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 1 | Hallway from Classrooms 121 to 111 | N/A | Fiberglass Ceiling Tile 2' x 4' | | Non Suspect ACM | 3240 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 1 | Hallway from Classrooms 121 to 111 | T | Pipe Insulation 2-6 inch | 7020/01/01/25 | Confirmed | 40 | LF | 0 | LF | | | | 1 | No | 1/D |
| 1 | 1 | Hallway from Classrooms 121 to 111 | T | Pipe Fitting Insulation | 7020/01/01/65 | Assumed | 5 | EA | 0 | EA | | | | 1 | No | 1/D |
| 1 | 1 | Hallway from Classrooms 121 to 111 | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 50 | LF | 0 | LF | | | | N/A | N/A | N/A |
| 1 | 1 | Boy's Restroom next to Classroom 111 | N/A | Cement Floor | | Non Suspect ACM | 200 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 1 | Boy's Restroom next to Classroom 111 | N/A | Plaster Walls | | NAD | 840 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 1 | Boy's Restroom next to Classroom 111 | N/A | Plaster Ceiling | | NAD | 200 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 1 | Boy's Restroom next to Classroom 111 | T | Pipe Insulation 2-6 inch | 7020/01/01/25 | Confirmed | 36 | LF | 2 | LF | | Slight Cracks | | 1 | Yes | 5/A |
| 1 | 1 | Boy's Restroom next to Classroom 111 | T | Pipe Fitting Insulation | 7020/01/01/65 | Assumed | 10 | EA | 0 | EA | | | | 1 | No | 1/D |
| 1 | 1 | School Exit Lobby next to Boy's Restroom | N/A | Plaster Ceiling | | NAD | 546 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 1 | School Exit Lobby next to Boy's Restroom | N/A | Cement Floor | | Non Suspect ACM | 546 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 1 | School Exit Lobby next to Boy's Restroom | N/A | Plaster Walls | | NAD | 1540 | SF | 4 | SF | | 20 SF Peeling Paint | | N/A | N/A | N/A |
| 1 | 1 | School Exit Lobby next to Boy's Restroom | T | Pipe Insulation 2-6 inch | 7020/01/01/25 | Confirmed | 3 | LF | 0 | LF | | | | 1 | No | 1/D |
| 1 | 1 | Security Office Near Classroom 103 attached to school exit lobby | N/A | Plaster Ceiling | | NAD | 300 | SF | 10 | SF | | Large Pieces Actively Breaking Off, and mild water damage | | N/A | N/A | N/A |
| 1 | 1 | Security Office Near Classroom 103 attached to school exit lobby | M | Floor Tile VAT 12" x 12" | 7020/01/01/A1 | Assumed | 300 | SF | 0 | SF | Blue | | | 1 | No | 1/D |
| 1 | 1 | Security Office Near Classroom 103 attached to school exit lobby | N/A | Plaster Walls | | NAD | 1120 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 1 | Security Office Near Classroom 103 attached to school exit lobby | T | Pipe Insulation 2-6 inch | 7020/01/01/25 | Confirmed | 25 | LF | 0 | LF | | | | 1 | No | 1/D |
| 1 | 1 | Security Office Near Classroom 103 attached to school exit lobby | T | Pipe Fitting Insulation | 7020/01/01/65 | Assumed | 5 | EA | 0 | EA | | | | 1 | No | 1/D |
| 1 | 1 | Office 116 | N/A | Cement Floor | | Non Suspect ACM | 234 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 1 | Office 116 | N/A | Plaster Walls | | NAD | 600 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 1 | Office 116 | N/A | Ceiling Tile 2' x 4' | | NAD | 234 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 1 | Office 116 | T | Pipe Insulation 2-6 inch | 7020/01/01/25 | Confirmed | 12 | LF | 0 | LF | | | | 1 | No | 1/D |
| 1 | 1 | Office 116 | N/A | Brick Wall | | Non Suspect ACM | 450 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 1 | Office 114 | X | X | | X | X | X | X | X | | No Access | | X | X | X |
| 1 | 1 | Classroom 115 | N/A | Wood Floor | | Non Suspect ACM | 780 | SF | X | SF | | | | N/A | N/A | N/A |
| 1 | 1 | Classroom 115 | N/A | Plaster Ceiling | | NAD | 780 | SF | 10 | SF | | | | N/A | N/A | N/A |
| 1 | 1 | Classroom 115 | N/A | Plaster Walls | | NAD | 1100 | SF | X | SF | | | | N/A | N/A | N/A |
| 1 | 1 | Classroom 115 | T | Pipe Insulation 2-6 inch | 7020/01/01/25 | Confirmed | 60 | LF | X | LF | | | | X | X | X |
| 1 | 1 | Classroom 115 | T | Pipe Fitting Insulation | 7020/01/01/65 | Assumed | 18 | EA | X | EA | | | | X | X | X |
| 1 | 1 | Classroom 117 | N/A | Plaster Ceiling | | NAD | 780 | SF | 10 | SF | | | | N/A | N/A | N/A |
| 1 | 1 | Classroom 117 | N/A | Wood Floor | | Non Suspect ACM | 780 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 1 | Classroom 117 | N/A | Plaster Walls | | NAD | 1568 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 1 | Classroom 117 | T | Pipe Insulation 2-6 inch | 7020/01/01/25 | Confirmed | 70 | LF | 0 | LF | | 1 unincapsulated end | | 1 | No | 1/D |
| 1 | 1 | Classroom 117 | T | Pipe Fitting Insulation | 7020/01/01/65 | Assumed | 20 | EA | 0 | EA | | | | 1 | No | 1/D |
| 1 | 1 | Classroom 117 | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 26 | LF | 0 | LF | | | | N/A | N/A | N/A |
| 1 | 1 | Classroom 117 | M | Blackboard Glue Dots | 7020/01/01/BATTA/AH/2600 | Assumed | 164 | SF | 0 | SF | | | | 1 | No | 1/D |
| 1 | 1 | Office 118 | M | Floor Tile VAT 12" x 12" | 7020/01/01/A1 | Assumed | 780 | SF | 0 | SF | Tan | | | 1 | No | 1/D |

7020 Olney HS (ASPIRA) 2015 2016 AHERA Three-Year Report.xls

| School District of Philadelphia | | | AHERA Three-Year Reinspection 2015-2016 | | | | | | | | | | Reinspection Date: December 13, 2015 | | | | |
|---|-----------------------|---|---|---------------------------------|--------------------------|---|-----------------------|-------------|---------------------|-------------|------------------------------|---|--------------------------------------|-----------------------------|--------------------------|-------------------------|--|
| Aspira Olney Charter High School | | | Room by Room Location Log Report | | | | | | | | | | Building Inspector: James Madden | | | | |
| 100 E. Duncannon Street, Philadelphia, PA 19120 | | | | | | | | | | | | | Number: 030867 | | | | |
| ULCS# 7029 | | | | | | | | | | | | | Management Planner: Megan Vala | | | | |
| Year Built: 1931 | | | | | | | | | | | | | Number: 740728 | | | | |
| E l e m e n t | F l o o r | On Site Room Name | System Affected | Material Description | HID# | Confirmed/Assumed/NAD/ Non Suspect ACM | Amount of Material | SF LF EA | Amount of Damage | SF LF EA | Color required for VAT | Comments/Description/Notes | Attic/ Crawl Space Ranking | Damage Potential (DP) | Newly Friable (NF) | Response Action (RA) | |
| 1 | 1 | Office 118 | N/A | Plaster Walls | | NAD | 1568 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 1 | Office 118 | N/A | Ceiling Tile 2' x 4' | | NAD | 780 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 1 | Office 118 | T | Pipe Insulation 2-6 inch | 7020/01/01/25 | Confirmed | 96 | LF | 0 | LF | | | | 1 | No | 1/D | |
| 1 | 1 | Office 118 | T | Pipe Fitting Insulation | 7020/01/01/65 | Assumed | 36 | EA | 0 | EA | | | | 1 | No | 1/D | |
| 1 | 1 | Office 118 | N/A | Brick Wall | | Non Suspect ACM | 1568 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 1 | Office 118 | M | Blackboard Glue Dots | 7020/01/01/BATTA/AH/2600 | Assumed | 80 | SF | 0 | SF | | | | 1 | No | 1/D | |
| 1 | 1 | Classroom 119 | N/A | Wood Floor | | Non Suspect ACM | 840 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 1 | Classroom 119 | N/A | Plaster Walls | | NAD | 1624 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 1 | Classroom 119 | N/A | Plaster Ceiling | | NAD | 840 | SF | 5 | SF | | | | N/A | N/A | N/A | |
| 1 | 1 | Classroom 119 | T | Pipe Insulation 2-6 inch | 7020/01/01/25 | Confirmed | 60 | LF | 0 | LF | | | | 1 | No | 1/D | |
| 1 | 1 | Classroom 119 | T | Pipe Fitting Insulation | 7020/01/01/65 | Assumed | 20 | EA | 0 | EA | | | | 1 | No | 1/D | |
| 1 | 1 | Classroom 119 | M | Blackboard Glue Dots | 7020/01/01/BATTA/AH/2600 | Assumed | 160 | SF | 0 | SF | | | | 1 | No | 1/D | |
| 1 | 1 | Classroom 119 | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 20 | LF | 2 | LF | | | | N/A | N/A | N/A | |
| 1 | 1 | Classroom 120 | M | Floor Tile VAT 9" x 9" | 7020/01/01/24 | Confirmed | 754 | SF | 3 | SF | Grey | Missing Tiles | | 1 | Yes | 5/B | |
| 1 | 1 | Classroom 120 | N/A | Plaster Walls | | NAD | 1040 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 1 | Classroom 120 | N/A | Plaster Ceiling | | NAD | 754 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 1 | Classroom 120 | T | Pipe Insulation 2-6 inch | 7020/01/01/25 | Confirmed | 45 | LF | 0 | LF | | | | 1 | No | 1/D | |
| 1 | 1 | Classroom 120 | T | Pipe Fitting Insulation | 7020/01/01/65 | Assumed | 20 | EA | 0 | EA | | | | 1 | No | 1/D | |
| 1 | 1 | Classroom 120 | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 12 | LF | 0 | LF | | | | N/A | N/A | N/A | |
| 1 | 1 | Classroom 120 | N/A | Brick Wall | | Non Suspect ACM | 500 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 1 | Girl's Restroom next to Classroom 120 | N/A | Cement Floor | | Non Suspect ACM | X | SF | 0 | SF | | No material? - Inspector please verify - No access (Fall 2016) | | N/A | N/A | N/A | |
| 1 | 1 | Girl's Restroom next to Classroom 120 | N/A | Plaster Walls | | NAD | X | SF | 0 | SF | | No material? - Inspector please verify | | N/A | N/A | N/A | |
| 1 | 1 | Girl's Restroom next to Classroom 120 | N/A | Plaster Ceiling | | NAD | X | SF | 0 | SF | | No material? - Inspector please verify | | N/A | N/A | N/A | |
| 1 | 1 | Girl's Restroom next to Classroom 120 | T | Pipe Insulation 2-6 inch | 7020/01/01/25 | Confirmed | 27 | LF | 0 | LF | | | | 1 | No | 1/D | |
| 1 | 1 | Girl's Restroom next to Classroom 120 | T | Pipe Fitting Insulation | 7020/01/01/65 | Assumed | 5 | EA | 0 | EA | | | | 1 | No | 1/D | |
| 1 | 1 | STM Camera Room | N/A | Cement Floor | | Non Suspect ACM | 300 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 1 | STM Camera Room | N/A | Plaster Walls | | NAD | 960 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 1 | STM Camera Room | N/A | Ceiling Tile 2' x 4' | | NAD | 300 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 1 | STM Camera Room | T | Pipe Insulation 2-6 inch | 7020/01/01/25 | Confirmed | 10 | LF | 0 | LF | | | | 1 | No | 1/D | |
| 1 | 1 | STM Camera Room | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 10 | LF | 0 | LF | | | | N/A | N/A | N/A | |
| 1 | 1 | Teacher's Lounge 123 | N/A | Plaster Ceiling | | NAD | 250 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 1 | Teacher's Lounge 123 | N/A | Wood Floor | | Non Suspect ACM | 250 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 1 | Teacher's Lounge 123 | N/A | Plaster Walls | | NAD | 980 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 1 | Teacher's Lounge 123 | T | Pipe Insulation 2-6 inch | 7020/01/01/25 | Confirmed | 28 | LF | 0 | LF | | | | 1 | No | 1/D | |
| 1 | 1 | Teacher's Lounge 123 | T | Pipe Fitting Insulation | 7020/01/01/65 | Assumed | 4 | EA | 0 | EA | | | | 1 | No | 1/D | |
| 1 | 1 | Hallway from Classroom 111 to Office 125 | N/A | Cement Floor | | Non Suspect ACM | 2040 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 1 | Hallway from Classroom 111 to Office 125 | N/A | Plaster Walls | | NAD | 3822 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 1 | Hallway from Classroom 111 to Office 125 | N/A | Marble Walls | | Non Suspect ACM | 1274 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 1 | Hallway from Classroom 111 to Office 125 | N/A | Fiberglass Ceiling Tile 2' x 4' | | Non Suspect ACM | 2040 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 1 | Office 125 | N/A | Plaster Ceiling | | NAD | 832 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 1 | Office 125 | N/A | Wood Floor | | Non Suspect ACM | 832 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 1 | Office 125 | N/A | Plaster Walls | | NAD | 1624 | SF | 30 | SF | | 18SF Peeling Paint | | N/A | N/A | N/A | |
| 1 | 1 | Office 125 | T | Pipe Insulation 2-6 inch | 7020/01/01/25 | Confirmed | 80 | LF | 2 | LF | | Unincapsulated Ends | | 1 | Yes | 5/A | |
| 1 | 1 | Office 125 | T | Pipe Fitting Insulation | 7020/01/01/65 | Assumed | 16 | EA | 0 | EA | | | | 1 | No | 1/D | |
| 1 | 1 | Office 125 | M | Blackboard Glue Dots | 7020/01/01/BATTA/AH/2600 | Assumed | 180 | SF | 0 | SF | | | | 1 | No | 1/D | |
| 1 | 1 | Custodial Closet next to Office 125 | N/A | Cement Floor | | Non Suspect ACM | 52 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 1 | Custodial Closet next to Office 125 | N/A | Plaster Ceiling | | NAD | 52 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 1 | Custodial Closet next to Office 125 | N/A | Brick Wall | | Non Suspect ACM | 476 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 1 | STM Storage next to STM Locker Room near Cafeteria | N/A | Cement Floor | | Non Suspect ACM | 336 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 1 | STM Storage next to STM Locker Room near Cafeteria | N/A | Brick Wall | | Non Suspect ACM | 1120 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 1 | STM Storage next to STM Locker Room near Cafeteria | N/A | Plaster Ceiling | | NAD | 336 | SF | 4 | SF | | | | N/A | N/A | N/A | |
| 1 | 1 | STM Locker Room near Office 125 | N/A | Cement Floor | | Non Suspect ACM | 364 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 1 | STM Locker Room near Office 125 | N/A | Plaster Ceiling | | NAD | 364 | SF | 0 | SF | | Stoage Closet and Locker Room both listed as Space 101D - Inspector please verify | | N/A | N/A | N/A | |
| 1 | 1 | STM Locker Room near Office 125 | N/A | Brick Wall | | Non Suspect ACM | 1148 | SF | 0 | SF | | Stoage Closet and Locker Room both listed as Space 101D - Inspector please verify | | N/A | N/A | N/A | |
| 1 | 1 | STM Locker Room near Office 125 | T | Pipe Insulation 2-6 inch | 7020/01/01/25 | Confirmed | 22 | LF | 0 | LF | | | | 1 | No | 1/D | |
| 1 | 1 | STM Locker Room near Office 125 | T | Pipe Fitting Insulation | 7020/01/01/65 | Assumed | 6 | EA | 0 | EA | | | | 1 | No | 1/D | |
| 1 | 1 | Cafeteria closest to Office 125 | M | Floor Tile VAT 12" x 12" | 7020/01/01/A1 | Assumed | 4002 | SF | 0 | SF | Multi | | | 1 | No | 1/D | |
| 1 | 1 | Cafeteria closest to Office 125 | N/A | Ceiling Tile 1' x 1' | | NAD | 4002 | SF | 200 | SF | | Minor to severe damage (Cracking, Missing, crumbling) throughout room | | N/A | N/A | N/A | |
| 1 | 1 | Cafeteria closest to Office 125 | N/A | Brick Wall | | Non Suspect ACM | 3566 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 1 | Cafeteria closest to Office 125 | T | Pipe Insulation 2-6 inch | 7020/01/01/25 | Confirmed | 92 | LF | 0 | LF | | | | 1 | No | 1/D | |
| 1 | 1 | Cafeteria closest to Office 125 | T | Pipe Fitting Insulation | 7020/01/01/65 | Assumed | 7 | EA | 0 | EA | | | | 1 | No | 1/D | |
| 1 | 1 | Cafeteria closest to Office 125 | T | Pipe Insulation > 6 inch | 7020/01/01/BATTA/AH/1110 | Assumed | 10 | LF | 1 | LF | | Cracked Pipe Insulation | | 1 | Yes | 5/A | |
| 1 | 1 | Food Service Area attached to Cafeteria near Office 125 | M | Floor Tile VAT 12" x 12" | 7020/01/01/A1 | Assumed | 1517 | SF | 0 | SF | Multi | Minor to severe damage (Cracking, Missing, crumbling) throughout room | | 1 | No | 1/D | |
| 1 | 1 | Food Service Area attached to Cafeteria near Office 125 | N/A | Ceiling Tile 1' x 1' | | NAD | 1517 | SF | 225 | SF | | | | N/A | N/A | N/A | |
| 1 | 1 | Food Service Area attached to Cafeteria near Office 125 | N/A | Concrete Block Wall | | Non Suspect ACM | 2184 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 1 | Main Kitchen for both Cafeterias located on the 1st floor | N/A | Cement Floor | | Non Suspect ACM | 3420 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 1 | Main Kitchen for both Cafeterias located on the 1st floor | N/A | Plaster Ceiling | | NAD | 3420 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 1 | Main Kitchen for both Cafeterias located on the 1st floor | N/A | Brick Wall | | Non Suspect ACM | 3584 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 1 | Main Kitchen for both Cafeterias located on the 1st floor | T | Pipe Insulation 2-6 inch | 7020/01/01/25 | Confirmed | 390 | LF | 0 | LF | | | | 1 | No | 1/D | |

7020 Olney HS (ASPIRA) 2015 2016 AHERA Three-Year Report.xls

| School District of Philadelphia Aspira Olney Charter High School 100 E. Duncannon Street, Philadelphia, PA 19120 ULCS# 7029 Year Built: 1931 | | | ASHERA Three-Year Reinspection 2015-2016 Room by Room Location Log Report | | | | | | | | | | Reinspection Date: December 13, 2015 | | | | | |
|--|-----------------------|---|--|------------------------------------|--------------------------|---|-----------------------|-------------|---------------------|-------------|------------------------------|----------------------------|--------------------------------------|-----------------------------|--------------------------|-------------------------|--|--|
| | | | | | | | | | | | | | Building Inspector: James Madden | | | | | |
| | | | | | | | | | | | | | Number: 030867 | | | | | |
| | | | | | | | | | | | | | Management Planner: Megan Vala | | | | | |
| | | | | | | | | | | | | | Number: 740728 | | | | | |
| E l e m e n t | F l o o r | On Site Room Name | System Affected | Material Description | HID# | Confirmed/Assumed/NAD/ Non Suspect ACM | Amount of Material | SF LF EA | Amount of Damage | SF LF EA | Color required for VAT | Comments/Description/Notes | Attic/ Crawl Space Ranking | Damage Potential (DP) | Newly Friable (NF) | Response Action (RA) | | |
| | | | | | | | | | | | | | | | | | | |
| 1 | 1 | Main Kitchen for both Cafeterias located on the 1st floor | T | Pipe Fitting Insulation | 7020/01/01/65 | Assumed | 42 | EA | 0 | EA | | | | 1 | No | 1/D | | |
| 1 | 1 | Main Kitchen for both Cafeterias located on the 1st floor | T | Pipe Insulation > 6 inch | 7020/01/01/BATTA/AH/1110 | Assumed | 65 | LF | 0 | LF | | | | 1 | No | 1/D | | |
| 1 | 1 | Main Kitchen for both Cafeterias located on the 1st floor | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 165 | LF | 5 | LF | | | | N/A | N/A | N/A | | |
| 1 | 1 | Main Kitchen Dry Storage Room | N/A | Cement Floor | | Non Suspect ACM | 322 | SF | 0 | SF | | | | N/A | N/A | N/A | | |
| 1 | 1 | Main Kitchen Dry Storage Room | N/A | Plaster Ceiling | | NAD | 322 | SF | 3 | SF | | | | N/A | N/A | N/A | | |
| 1 | 1 | Main Kitchen Dry Storage Room | N/A | Brick Wall | | Non Suspect ACM | 1036 | SF | 0 | SF | | | | N/A | N/A | N/A | | |
| 1 | 1 | Main Kitchen Custodial Closet | N/A | Cement Floor | | Non Suspect ACM | 40 | SF | 0 | SF | | | | N/A | N/A | N/A | | |
| 1 | 1 | Main Kitchen Custodial Closet | N/A | Plaster Ceiling | | NAD | 40 | SF | 0 | SF | | | | N/A | N/A | N/A | | |
| 1 | 1 | Main Kitchen Custodial Closet | N/A | Brick Wall | | Non Suspect ACM | 392 | SF | 0 | SF | | | | N/A | N/A | N/A | | |
| 1 | 1 | Main Kitchen Custodial Closet | T | Pipe Insulation 2-6 inch | 7020/01/01/25 | Confirmed | 24 | LF | 0 | LF | | | | 1 | No | 1/D | | |
| 1 | 1 | Main Kitchen Custodial Closet | T | Pipe Fitting Insulation | 7020/01/01/65 | Assumed | 5 | EA | 0 | EA | | | | 1 | No | 1/D | | |
| 1 | 1 | Food Service Area attached to Cafeteria near Office 136 | M | Floor Tile VAT 12" x 12" | 7020/01/01/A1 | Assumed | 2226 | SF | 0 | SF | Multi | | | 1 | No | 1/D | | |
| 1 | 1 | Food Service Area attached to Cafeteria near Office 136 | N/A | Ceiling Tile 1' x 1' | | NAD | 2226 | SF | 40 | SF | | minor damage throughout | | N/A | N/A | N/A | | |
| 1 | 1 | Food Service Area attached to Cafeteria near Office 136 | N/A | Brick Wall | | Non Suspect ACM | 2660 | SF | 0 | SF | | | | N/A | N/A | N/A | | |
| 1 | 1 | Cafeteria near Office 136 | M | Floor Tile VAT 12" x 12" | 7020/01/01/A1 | Assumed | 3850 | SF | 0 | SF | Multi | | | 1 | No | 1/D | | |
| 1 | 1 | Cafeteria near Office 136 | N/A | Ceiling Tile 1' x 1' | | NAD | 3850 | SF | 30 | SF | | minor damage throughout | | N/A | N/A | N/A | | |
| 1 | 1 | Cafeteria near Office 136 | N/A | Brick Wall | | Non Suspect ACM | 3500 | SF | 0 | SF | | | | N/A | N/A | N/A | | |
| 1 | 1 | Cafeteria near Office 136 | T | Pipe Insulation 2-6 inch | 7020/01/01/25 | Confirmed | 110 | LF | 0 | LF | | | | 1 | No | 1/D | | |
| 1 | 1 | Cafeteria near Office 136 | T | Pipe Fitting Insulation | 7020/01/01/65 | Assumed | 7 | EA | 0 | EA | | | | 1 | No | 1/D | | |
| 1 | 1 | Cafeteria near Office 136 | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 40 | LF | 0 | LF | | | | N/A | N/A | N/A | | |
| 1 | 1 | Cafeteria near Office 136 | T | Pipe Insulation > 6 inch | 7020/01/01/BATTA/AH/1110 | Assumed | 10 | LF | 0 | LF | | | | 1 | No | 1/D | | |
| 1 | 1 | Hallway outside Cafeterias | N/A | Cement Floor | | Non Suspect ACM | 3240 | SF | 0 | SF | | | | N/A | N/A | N/A | | |
| 1 | 1 | Hallway outside Cafeterias | N/A | Plaster Walls | | NAD | 7896 | SF | 0 | SF | | | | N/A | N/A | N/A | | |
| 1 | 1 | Hallway outside Cafeterias | N/A | Ceiling Tile 2' x 4' | | NAD | 3240 | SF | 0 | SF | | | | N/A | N/A | N/A | | |
| 1 | 1 | Hallway outside Cafeterias | T | Pipe Insulation 2-6 inch | 7020/01/01/25 | Confirmed | 40 | LF | X | LF | | | | X | X | X | | |
| 1 | 1 | Hallway outside Cafeterias | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 130 | LF | 20 | LF | | | | N/A | N/A | N/A | | |
| 1 | 1 | Classroom 143 | M | Floor Tile VAT 12" x 12" | 7020/01/01/A1 | Assumed | 1125 | SF | 0 | SF | Green | | | 1 | No | 1/D | | |
| 1 | 1 | Classroom 143 | N/A | Ceiling Tile 2' x 4' | | Non Suspect ACM | 1125 | SF | 0 | SF | | | | N/A | N/A | N/A | | |
| 1 | 1 | Classroom 143 | N/A | Plaster Walls | | NAD | 1300 | SF | 0 | SF | | | | N/A | N/A | N/A | | |
| 1 | 1 | Classroom 143 | T | Pipe Insulation 2-6 inch | 7020/01/01/25 | Confirmed | 15 | LF | 0 | LF | | | | 1 | No | 1/D | | |
| 1 | 1 | Classroom 143 | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 15 | LF | 0 | LF | | | | N/A | N/A | N/A | | |
| 1 | 1 | Classroom 143 Closet | N/A | Wood Floor | | Non Suspect ACM | 150 | SF | 0 | SF | | | | N/A | N/A | N/A | | |
| 1 | 1 | Classroom 143 Closet | N/A | Plaster Ceiling | | NAD | 150 | SF | 0 | SF | | | | N/A | N/A | N/A | | |
| 1 | 1 | Classroom 143 Closet | N/A | Plaster Walls | | NAD | 400 | SF | 0 | SF | | | | N/A | N/A | N/A | | |
| 1 | 1 | Classroom 143 Kitchen | M | Floor Tile VAT 12" x 12" | 7020/01/01/A1 | Assumed | 100 | SF | 0 | SF | Grey | | | 1 | No | 1/D | | |
| 1 | 1 | Classroom 143 Kitchen | N/A | Ceiling Tile 2' x 4' | | Non Suspect ACM | 100 | SF | 0 | SF | | | | N/A | N/A | N/A | | |
| 1 | 1 | Classroom 143 Kitchen | N/A | Plaster Walls | | NAD | 300 | SF | 0 | SF | | | | N/A | N/A | N/A | | |
| 1 | 1 | Classroom 135 | N/A | Plaster Ceiling | | NAD | 858 | SF | 0 | SF | | 25SF PeelingbPaint | | N/A | N/A | N/A | | |
| 1 | 1 | Classroom 135 | N/A | Wood Floor | | Non Suspect ACM | 858 | SF | 0 | SF | | | | N/A | N/A | N/A | | |
| 1 | 1 | Classroom 135 | N/A | Plaster Walls | | NAD | 1652 | SF | 0 | SF | | | | N/A | N/A | N/A | | |
| 1 | 1 | Classroom 135 | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 40 | LF | 0 | LF | | | | N/A | N/A | N/A | | |
| 1 | 1 | Classroom 135 | M | Blackboard Glue Dots | 7020/01/01/BATTA/AH/2600 | Assumed | 128 | SF | 0 | SF | | | | 1 | No | 1/D | | |
| 1 | 1 | Office 136 | M | Floor Tile VAT 12" x 12" | 7020/01/01/A1 | Assumed | 250 | SF | 0 | SF | White | | | 1 | No | 1/D | | |
| 1 | 1 | Office 136 | N/A | Plaster Ceiling | | NAD | 250 | SF | 0 | SF | | | | N/A | N/A | N/A | | |
| 1 | 1 | Office 136 | N/A | Plaster Walls | | NAD | 500 | SF | 0 | SF | | | | N/A | N/A | N/A | | |
| 1 | 1 | Office 136 | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 3 | LF | 0 | LF | | | | N/A | N/A | N/A | | |
| 1 | 1 | School Exit Lobby near Office 136 | N/A | Plaster Ceiling | | NAD | 455 | SF | 0 | SF | | | | N/A | N/A | N/A | | |
| 1 | 1 | School Exit Lobby near Office 136 | N/A | Cement Floor | | Non Suspect ACM | 455 | SF | 0 | SF | | | | N/A | N/A | N/A | | |
| 1 | 1 | School Exit Lobby near Office 136 | N/A | Plaster Walls | | NAD | 1344 | SF | 0 | SF | | | | N/A | N/A | N/A | | |
| 1 | 1 | Classroom 139 | M | Floor Tile VAT 12" x 12" | 7020/01/01/A1 | Assumed | 900 | SF | 0 | SF | White | | | 1 | No | 1/D | | |
| 1 | 1 | Classroom 139 | N/A | Ceiling Tile 1' x 1' | | NAD | 900 | SF | 0 | SF | | | | N/A | N/A | N/A | | |
| 1 | 1 | Classroom 139 | N/A | Plaster Walls | | NAD | 1200 | SF | 0 | SF | | | | N/A | N/A | N/A | | |
| 1 | 1 | Classroom 139 | T | Pipe Insulation > 6 inch | 7020/01/01/BATTA/AH/1110 | Confirmed | 40 | LF | 0 | LF | | | | 1 | No | 1/D | | |
| 1 | 1 | Classroom 139 | T | Pipe Fitting Insulation | 7020/01/01/65 | Confirmed | 2 | EA | 0 | EA | | | | 1 | No | 1/D | | |
| 1 | 1 | Classroom 139 | N/A | Fiberglass Pipe Fitting Insulation | | Non Suspect ACM | 3 | LF | 0 | LF | | | | N/A | N/A | N/A | | |
| 1 | 1 | Classroom 141 | M | Floor Tile VAT 12" x 12" | 7020/01/01/A1 | Assumed | 750 | SF | 0 | SF | White | | | 1 | No | 1/D | | |
| 1 | 1 | Classroom 141 | N/A | Ceiling Tile 1' x 1' | | NAD | 750 | SF | 0 | SF | | | | N/A | N/A | N/A | | |
| 1 | 1 | Classroom 141 | N/A | Plaster Walls | | NAD | 1000 | SF | 0 | SF | | | | N/A | N/A | N/A | | |
| 1 | 1 | Classroom 141 | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 10 | LF | 0 | LF | | | | N/A | N/A | N/A | | |
| 1 | 1 | Office 146 | N/A | Wood Floor | | Non Suspect ACM | 200 | SF | 0 | SF | | | | N/A | N/A | N/A | | |
| 1 | 1 | Office 146 | N/A | Plaster Ceiling | | NAD | 200 | SF | 0 | SF | | | | N/A | N/A | N/A | | |
| 1 | 1 | Office 146 | N/A | Plaster Walls | | NAD | 400 | SF | 0 | SF | | | | N/A | N/A | N/A | | |
| 1 | 1 | Office 146 | T | Pipe Insulation 2-6 inch | 7020/01/01/25 | Confirmed | 15 | LF | 0 | LF | | | | 1 | No | 1/D | | |
| 1 | 1 | Office 146 | T | Pipe Fitting Insulation | 7020/01/01/65 | Confirmed | 4 | EA | 0 | EA | | | | 1 | No | 1/D | | |
| 1 | 1 | School Exit Lobby near Classroom 143 | N/A | Plaster Ceiling | | NAD | 494 | SF | 0 | SF | | | | N/A | N/A | N/A | | |
| 1 | 1 | School Exit Lobby near Classroom 143 | N/A | Cement Floor | | Non Suspect ACM | 494 | SF | 0 | SF | | | | N/A | N/A | N/A | | |
| 1 | 1 | School Exit Lobby near Classroom 143 | N/A | Plaster Walls | | NAD | 1071 | SF | 0 | SF | | | | N/A | N/A | N/A | | |
| 1 | 1 | School Exit Lobby near Classroom 143 | N/A | Marble Walls | | Non Suspect ACM | 357 | SF | 0 | SF | | | | N/A | N/A | N/A | | |
| 1 | 1 | School Exit Lobby near Classroom 143 | T | Pipe Insulation 2-6 inch | 7020/01/01/25 | Confirmed | 3 | LF | 0 | LF | | | | 1 | No | 1/D | | |
| 1 | 1 | Office 145 | N/A | Plaster Ceiling | | NAD | 230 | SF | 0 | SF | | | | N/A | N/A | N/A | | |
| 1 | 1 | Office 145 | N/A | Wood Floor | | Non Suspect ACM | 230 | SF | 0 | SF | | | | N/A | N/A | N/A | | |
| 1 | 1 | Office 145 | N/A | Plaster Walls | | NAD | 924 | SF | 0 | SF | | | | N/A | N/A | N/A | | |
| 1 | 1 | Office 145 | T | Pipe Insulation 2-6 inch | 7020/01/01/25 | Confirmed | 15 | LF | 0 | LF | | | | 1 | No | 1/D | | |

7020 Olney HS (ASPIRA) 2015 2016 AHERA Three-Year Report.xls

| School District of Philadelphia | | | ASHERA Three-Year Reinspection 2015-2016 | | | | | | | | | | | Reinspection Date: December 13, 2015 | | | | | |
|---|---|--|--|----------------------------|--------------------------|------------------------|-----------|----|----|-----------|----|----|--------------|--|--------------|-----------|---------|-------------|--|
| Aspira Olney Charter High School | | | Room by Room Location Log Report | | | | | | | | | | | Building Inspector: James Madden | | | | | |
| 100 E. Duncannon Street, Philadelphia, PA 19120 | | | | | | | | | | | | | | Number: 030867 | | | | | |
| ULCS# 7029 | | | | | | | | | | | | | | Management Planner: Megan Vala | | | | | |
| Year Built: 1931 | | | | | | | | | | | | | | Number: 740728 | | | | | |
| E | F | | | | | | | | | | | | | | | | | | |
| l | o | | System | Material | HID# | Confirmed/Assumed/NAD/ | Amount of | SF | LF | Amount of | SF | LF | Color | | | | | | |
| n | n | On Site Room Name | Affected | Description | | Non Suspect ACM | Material | EA | EA | Damage | EA | EA | required for | Comments/Description/Notes | Attic/ Crawl | Damage | Newly | Response | |
| t | r | | | | | | | | | | | | VAT | | Space | Potential | Friable | Action (RA) | |
| 1 | 1 | Office 145 | T | Pipe Fitting Insulation | 7020/01/01/65 | Assumed | 3 | EA | 0 | EA | | | | Unincapsulated Ends wrapped in duct tape | | 1 | No | 1/D | |
| 1 | 1 | Office across from Room 121 | N/A | Ceiling Tile 2' x 4' | | NAD | 338 | SF | 0 | SF | | | | | | N/A | N/A | N/A | |
| 1 | 1 | Office across from Room 121 | N/A | Wood Floor | | Non Suspect ACM | 338 | SF | 0 | SF | | | | | | N/A | N/A | N/A | |
| 1 | 1 | Office across from Room 121 | N/A | Plaster Walls | | NAD | 1092 | SF | 0 | SF | | | | | | N/A | N/A | N/A | |
| 1 | 1 | Office across from Room 121 | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 16 | LF | 0 | LF | | | | | | N/A | N/A | N/A | |
| 1 | 1 | Special Education Kitchen Room 123/135 | N/A | Ceiling Tile 2' x 4' | | NAD | 416 | SF | 0 | SF | | | | | | N/A | N/A | N/A | |
| 1 | 1 | Special Education Kitchen Room 123/135 | M | Floor Tile VAT 12" x 12" | 7020/01/01/A1 | Assumed | 208 | SF | 0 | SF | | | White | | | 1 | No | 1/D | |
| 1 | 1 | Special Education Kitchen Room 123/135 | N/A | Plaster Walls | | NAD | 1176 | SF | 0 | SF | | | | | | N/A | N/A | N/A | |
| 1 | 1 | Special Education Kitchen Room 123/135 | T | Pipe Insulation 2-6 inch | 7020/01/01/25 | Confirmed | 20 | LF | 0 | LF | | | | | | 1 | No | 1/D | |
| 1 | 1 | Special Education Kitchen Room 123/135 | N/A | Ceramic Tile Walls | | Non Suspect ACM | 200 | SF | 0 | SF | | | | | | N/A | N/A | N/A | |
| 1 | 1 | Special Education Kitchen Room 123/135 | N/A | Plaster Ceiling | | NAD | 416 | SF | 15 | SF | | | | | | N/A | N/A | N/A | |
| 1 | 1 | Special Education Kitchen Room 123/135 | M | Floor Tile VAT 12" x 12" | 7020/01/01/A1 | Assumed | 208 | SF | 0 | SF | | | Blue | | | 1 | No | 1/D | |
| 1 | 1 | Special Education Kitchen Room 123/135 Closet | N/A | Wood Floor | | Non Suspect ACM | 24 | SF | 0 | SF | | | | | | N/A | N/A | N/A | |
| 1 | 1 | Special Education Kitchen Room 123/135 Closet | N/A | Plaster Walls | | NAD | 308 | SF | 0 | SF | | | | | | N/A | N/A | N/A | |
| 1 | 1 | Special Education Kitchen Room 123/135 Closet | N/A | Ceiling Tile 2' x 4' | | Non Suspect ACM | 24 | SF | 0 | SF | | | | | | N/A | N/A | N/A | |
| 1 | 1 | Hallway from Office 136 to Classroom 121 | N/A | Cement Floor | | Non Suspect ACM | 2040 | SF | 0 | SF | | | | | | N/A | N/A | N/A | |
| 1 | 1 | Hallway from Office 136 to Classroom 121 | N/A | Plaster Walls | | NAD | 5096 | SF | 0 | SF | | | | | | N/A | N/A | N/A | |
| 1 | 1 | Hallway from Office 136 to Classroom 121 | N/A | Ceiling Tile 2' x 4' | | NAD | 2040 | SF | 0 | SF | | | | | | N/A | N/A | N/A | |
| 1 | 1 | Special Education Room 121 | N/A | Ceiling Tile 2' x 4' | | NAD | 984 | SF | 0 | SF | | | | | | N/A | N/A | N/A | |
| 1 | 1 | Special Education Room 121 | M | Floor Tile VAT 12" x 12" | 7020/01/01/A1 | Assumed | 442 | SF | 0 | SF | | | White | | | 1 | No | 1/D | |
| 1 | 1 | Special Education Room 121 | N/A | Plaster Walls | | NAD | 1820 | SF | 12 | SF | | | | | | N/A | N/A | N/A | |
| 1 | 1 | Special Education Room 121 | T | Pipe Insulation 2-6 inch | 7020/01/01/25 | Confirmed | 10 | LF | 0 | LF | | | | | | 1 | No | 1/D | |
| 1 | 1 | Special Education Room 121 | N/A | Ceramic Tile Walls | | Non Suspect ACM | 150 | SF | 0 | SF | | | | | | N/A | N/A | N/A | |
| 1 | 1 | Special Education Room 121 | N/A | Plaster Ceiling | | NAD | 984 | SF | 0 | SF | | | | | | N/A | N/A | N/A | |
| 1 | 1 | Special Education Room 121 | M | Floor Tile VAT 12" x 12" | 7020/01/01/A1 | Assumed | 442 | SF | 0 | SF | | | Blue | | | 1 | No | 1/D | |
| 1 | 1 | Special Education Room 121 | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 10 | LF | 0 | LF | | | | | | N/A | N/A | N/A | |
| 1 | 1 | Special Education Room 121 Control Room | M | Floor Tile VAT 12" x 12" | 7020/01/01/A1 | Assumed | 75 | SF | 0 | SF | | | Blue | | | 1 | No | 1/D | |
| 1 | 1 | Special Education Room 121 Control Room | N/A | Plaster Ceiling | | NAD | 75 | SF | 0 | SF | | | | | | N/A | N/A | N/A | |
| 1 | 1 | Special Education Room 121 Control Room | N/A | Plaster Walls | | NAD | 560 | SF | 10 | SF | | | | | | N/A | N/A | N/A | |
| 1 | 1 | Classroom 151 | M | Floor Tile VAT 12" x 12" | 7020/01/01/A1 | Assumed | 432 | SF | 0 | SF | | | Blue | | | 1 | No | 1/D | |
| 1 | 1 | Classroom 151 | M | Floor Tile VAT 12" x 12" | 7020/01/01/A1 | Assumed | 432 | SF | 0 | SF | | | White | | | 1 | No | 1/D | |
| 1 | 1 | Classroom 151 | N/A | Plaster Ceiling | | NAD | 864 | SF | 0 | SF | | | | | | N/A | N/A | N/A | |
| 1 | 1 | Classroom 151 | N/A | Plaster Walls | | NAD | 1680 | SF | 0 | SF | | | | | | N/A | N/A | N/A | |
| 1 | 1 | Classroom 151 | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 10 | LF | 0 | LF | | | | | | N/A | N/A | N/A | |
| 1 | 1 | Office 153 | N/A | Wood Floor | | Non Suspect ACM | 425 | SF | 0 | SF | | | | | | N/A | N/A | N/A | |
| 1 | 1 | Office 153 | N/A | Plaster Ceiling | | NAD | 425 | SF | 0 | SF | | | | | | N/A | N/A | N/A | |
| 1 | 1 | Office 153 | N/A | Plaster Walls | | NAD | 1176 | SF | 0 | SF | | | | | | N/A | N/A | N/A | |
| 1 | 1 | Office 153 | T | Pipe Insulation 2-6 inch | 7020/01/01/25 | Confirmed | 20 | LF | 0 | LF | | | | | | 1 | No | 1/D | |
| 1 | 1 | Office 153 | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 18 | LF | 0 | LF | | | | | | N/A | N/A | N/A | |
| 1 | 1 | Canned Good Storage attached Office 153 | N/A | Wood Floor | | Non Suspect ACM | 112 | SF | 0 | SF | | | | | | N/A | N/A | N/A | |
| 1 | 1 | Canned Good Storage attached Office 153 | N/A | Plaster Ceiling | | NAD | 112 | SF | 0 | SF | | | | | | N/A | N/A | N/A | |
| 1 | 1 | Canned Good Storage attached Office 153 | N/A | Plaster Walls | | NAD | 616 | SF | 3 | SF | | | | | | N/A | N/A | N/A | |
| 1 | 1 | Uniform Storage Room attached to Office 153 | N/A | Wood Floor | | Non Suspect ACM | 112 | SF | 0 | SF | | | | | | N/A | N/A | N/A | |
| 1 | 1 | Uniform Storage Room attached to Office 153 | N/A | Plaster Ceiling | | NAD | 112 | SF | 0 | SF | | | | | | N/A | N/A | N/A | |
| 1 | 1 | Uniform Storage Room attached to Office 153 | N/A | Plaster Walls | | NAD | 616 | SF | 6 | SF | | | | | | N/A | N/A | N/A | |
| 1 | 1 | Uniform Storage Room attached to Office 153 | T | Pipe Insulation > 6 inch | 7020/01/01/BATTA/AH/1110 | Assumed | 5 | LF | 0 | LF | | | | | | 1 | No | 1/D | |
| 1 | 1 | Uniform Storage Room attached to Office 153 | T | Pipe Fitting Insulation | 7020/01/01/65 | Assumed | 3 | EA | 0 | EA | | | | | | 1 | No | 1/D | |
| 1 | 1 | Auditorium | N/A | Wood Floor | | Non Suspect ACM | 11070 | SF | 0 | SF | | | | | | N/A | N/A | N/A | |
| 1 | 1 | Auditorium | S | Plaster Ceiling | 7020/01/01/A8 | Assumed | 11070 | SF | 0 | SF | | | | | | 1 | No | 1/D | |
| 1 | 1 | Auditorium | N/A | Plaster Walls | | NAD | 19530 | SF | 35 | SF | | | | 131 SF Peeling Paint | | N/A | N/A | N/A | |
| 1 | 1 | Auditorium | T | Radiator Insulation | 7020/01/01/TT | Confirmed | 140 | SF | 0 | SF | | | | | | 1 | No | 1/D | |
| 1 | 1 | Auditorium | M | Stage Lights Wiring | 7020/01/01/UU | Assumed | 200 | LF | 0 | LF | | | | | | 1 | No | 1/D | |
| 1 | 1 | Women's Restroom next to Main Lobby | N/A | Cement Floor | | Non Suspect ACM | 153 | SF | 0 | SF | | | | | | N/A | N/A | N/A | |
| 1 | 1 | Women's Restroom next to Main Lobby | N/A | Concrete Ceiling | | Non Suspect ACM | 153 | SF | 0 | SF | | | | | | N/A | N/A | N/A | |
| 1 | 1 | Women's Restroom next to Main Lobby | N/A | Plaster Walls | | NAD | 728 | SF | 0 | SF | | | | | | N/A | N/A | N/A | |
| 3 | 1 | Gymnasium | T | Pipe Fitting Insulation | 7020/03/01/78 | Assumed | 10 | EA | 0 | EA | | | | | | 1 | No | 1/D | |
| 3 | 1 | Gymnasium | N/A | Wood Floor | | Non Suspect ACM | 11200 | SF | 0 | SF | | | | | | N/A | N/A | N/A | |
| 3 | 1 | Gymnasium | N/A | Concrete Block Wall | | Non Suspect ACM | 12320 | SF | 0 | SF | | | | | | N/A | N/A | N/A | |
| 3 | 1 | Gymnasium | N/A | Concrete Ceiling | | Non Suspect ACM | 11200 | SF | 0 | SF | | | | | | N/A | N/A | N/A | |
| 3 | 1 | Gymnasium | M | Partition Room Dividers | 7020/03/01/BATTA/AH/2607 | Assumed | 1400 | SF | 0 | SF | | | | | | 1 | No | 1/D | |
| 3 | 1 | Gymnasium | T | Pipe Insulation > 6 inch | 7020/03/01/BATTA/AH/1110 | Assumed | 70 | LF | 0 | LF | | | | Possibly fiberglass | | 1 | No | 1/D | |
| 3 | 1 | Classroom A103 | X | X | | X | X | X | X | X | | | | No Access | | X | X | X | |
| 3 | 1 | Classroom A105 | N/A | Wood Floor | | Non Suspect ACM | 2236 | SF | 0 | SF | | | | | | N/A | N/A | N/A | |
| 3 | 1 | Classroom A105 | N/A | Concrete Block Wall | | Non Suspect ACM | 2850 | SF | 0 | SF | | | | | | N/A | N/A | N/A | |
| 3 | 1 | Classroom A105 | N/A | Ceiling Tile 2' x 4' | | NAD | 2236 | SF | 0 | SF | | | | | | N/A | N/A | N/A | |
| 3 | 1 | Classroom A105 | M | Floor Tile VAT 9" x 9" | 7020/03/01/77 | Confirmed | 500 | SF | 0 | SF | | | Brown | | | 1 | No | 1/D | |
| 3 | 1 | Classroom A105 | N/A | Sheetrock Wall | | Non Suspect ACM | 400 | SF | 0 | SF | | | | | | N/A | N/A | N/A | |
| 3 | 1 | Classroom A105 Office | N/A | Concrete Block Wall | | Non Suspect ACM | 768 | SF | 0 | SF | | | | | | N/A | N/A | N/A | |
| 3 | 1 | Classroom A105 Office | N/A | Ceiling Tile 2' x 4' | | NAD | 240 | SF | 0 | SF | | | | | | N/A | N/A | N/A | |
| 3 | 1 | Classroom A105 Office | M | Floor Tile VAT 9" x 9" | 7020/03/01/77 | Confirmed | 240 | SF | 0 | SF | | | Brown | | | 1 | No | 1/D | |
| 3 | 1 | Music Practice Room D attached to Classroom A105 | N/A | Concrete Block Wall | | Non Suspect ACM | 768 | SF | 0 | SF | | | | | | N/A | N/A | N/A | |
| 3 | 1 | Music Practice Room D attached to Classroom A105 | N/A | Ceiling Tile 2' x 4' | | NAD | 231 | SF | 0 | SF | | | | | | N/A | N/A | N/A | |
| 3 | 1 | Music Practice Room D attached to Classroom A105 | M | Floor Tile VAT 9" x 9" | 7020/03/01/77 | Confirmed | 231 | SF | 0 | SF | | | Grey | | | 1 | No | 1/D | |

7020 Olney HS (ASPIRA) 2015 2016 AHERA Three-Year Report.xls

| | | School District of Philadelphia Aspira Olney Charter High School 100 E. Duncannon Street, Philadelphia, PA 19120 ULCS# 7029 Year Built: 1931 | | AHERA Three-Year Reinspection 2015-2016 Room by Room Location Log Report | | | | | | | | | | Reinspection Date: December 13, 2015 Building Inspector: James Madden Number: 030867 Management Planner: Megan Valia Number: 740728 | | | | | | |
|---------------------------------|-----------------------|--|-----------------|---|--------------------------|---|-----------------------|----|----|----|---------------------|----|----|---|------------------------------|--|----------------------------------|-----------------------------|--------------------------|-------------------------|
| E l e m e n t | F l o o r | On Site Room Name | System Affected | Material Description | HID# | Confirmed/Assumed/NAD/ Non Suspect ACM | Amount of Material | SF | LF | EA | Amount of Damage | SF | LF | EA | Color required for VAT | Comments/Description/Notes | Attic/ Crawl Space Ranking | Damage Potential (DP) | Newly Friable (NF) | Response Action (RA) |
| 3 | 1 | Music Practice Room C attached to Classroom A105 | N/A | Concrete Block Wall | | Non Suspect ACM | 456 | SF | 0 | SF | | | | | | | | N/A | N/A | N/A |
| 3 | 1 | Music Practice Room C attached to Classroom A105 | N/A | Ceiling Tile 2' x 4' | | NAD | 88 | SF | 0 | SF | | | | | | | | N/A | N/A | N/A |
| 3 | 1 | Music Practice Room C attached to Classroom A105 | M | Floor Tile VAT 9" x 9" | 7020/03/01/77 | Confirmed | 88 | SF | 0 | SF | | | | | Brown | | | 1 | No | 1/D |
| 3 | 1 | Music Practice Room B attached to Classroom A105 | N/A | Concrete Block Wall | | Non Suspect ACM | 456 | SF | 0 | SF | | | | | | | | N/A | N/A | N/A |
| 3 | 1 | Music Practice Room B attached to Classroom A105 | N/A | Ceiling Tile 2' x 4' | | NAD | 88 | SF | 0 | SF | | | | | | | | N/A | N/A | N/A |
| 3 | 1 | Music Practice Room B attached to Classroom A105 | M | Floor Tile VAT 9" x 9" | 7020/03/01/77 | Confirmed | 88 | SF | 0 | SF | | | | | Brown | | | 1 | No | 1/D |
| 3 | 1 | Music Practice Room A attached to Classroom A105 | N/A | Concrete Block Wall | | Non Suspect ACM | 456 | SF | 0 | SF | | | | | | | | N/A | N/A | N/A |
| 3 | 1 | Music Practice Room A attached to Classroom A105 | N/A | Ceiling Tile 2' x 4' | | NAD | 88 | SF | 0 | SF | | | | | | | | N/A | N/A | N/A |
| 3 | 1 | Music Practice Room A attached to Classroom A105 | M | Floor Tile VAT 9" x 9" | 7020/03/01/77 | Confirmed | 88 | SF | 0 | SF | | | | | | | | 1 | No | 1/D |
| 3 | 1 | Music Practice Room E attached to Classroom A105 | N/A | Concrete Block Wall | | Non Suspect ACM | 456 | SF | 0 | SF | | | | | | | | N/A | N/A | N/A |
| 3 | 1 | Music Practice Room E attached to Classroom A105 | N/A | Ceiling Tile 2' x 4' | | NAD | 88 | SF | 0 | SF | | | | | | | | N/A | N/A | N/A |
| 3 | 1 | Music Practice Room E attached to Classroom A105 | M | Floor Tile VAT 9" x 9" | 7020/03/01/77 | Confirmed | 88 | SF | 0 | SF | | | | | Brown | | | 1 | No | 1/D |
| 3 | 1 | Hallway leading to Music Practice Rooms | N/A | Concrete Block Wall | | Non Suspect ACM | 1056 | SF | 0 | SF | | | | | | | | N/A | N/A | N/A |
| 3 | 1 | Hallway leading to Music Practice Rooms | N/A | Ceiling Tile 2' x 4' | | NAD | 160 | SF | 0 | SF | | | | | | | | N/A | N/A | N/A |
| 3 | 1 | Hallway leading to Music Practice Rooms | M | Floor Tile VAT 9" x 9" | 7020/03/01/77 | Confirmed | 160 | SF | 0 | SF | | | | | Black | | | 1 | No | 1/D |
| 3 | 1 | Main Gym Storage Room | M | Floor Tile VAT 9" x 9" | 7020/03/01/77 | Confirmed | 150 | SF | 0 | SF | | | | | Blue | | | 1 | No | 1/D |
| 3 | 1 | Main Gym Storage Room | N/A | Concrete Block Wall | | Non Suspect ACM | 600 | SF | 0 | SF | | | | | | | | N/A | N/A | N/A |
| 3 | 1 | Main Gym Storage Room | N/A | Concrete Ceiling | | Non Suspect ACM | 150 | SF | 0 | SF | | | | | | | | N/A | N/A | N/A |
| 3 | 1 | Gym Teacher's Office | M | Floor Tile VAT 9" x 9" | 7020/03/01/77 | Confirmed | 266 | SF | 0 | SF | | | | | Blue | | | 1 | No | 1/D |
| 3 | 1 | Gym Teacher's Office | N/A | Concrete Block Wall | | Non Suspect ACM | 792 | SF | 0 | SF | | | | | | | | N/A | N/A | N/A |
| 3 | 1 | Gym Teacher's Office | N/A | Ceiling Tile 2' x 4' | | NAD | 266 | SF | 0 | SF | | | | | | | | N/A | N/A | N/A |
| 3 | 1 | Small Room attached To Gym Teachers Office | M | Floor Tile VAT 9" x 9" | 7020/03/01/77 | Confirmed | 120 | SF | 0 | SF | | | | | Brown | | | 1 | No | 1/D |
| 3 | 1 | Small Room attached To Gym Teachers Office | N/A | Concrete Block Wall | | Non Suspect ACM | 528 | SF | 0 | SF | | | | | | | | N/A | N/A | N/A |
| 3 | 1 | Small Room attached To Gym Teachers Office | N/A | Ceiling Tile 2' x 4' | | NAD | 120 | SF | 0 | SF | | | | | | | | N/A | N/A | N/A |
| 3 | 1 | Gym Teacher's Restroom | N/A | Cement Floor | | Non Suspect ACM | 48 | SF | 0 | SF | | | | | | | | N/A | N/A | N/A |
| 3 | 1 | Gym Teacher's Restroom | N/A | Concrete Block Wall | | Non Suspect ACM | 336 | SF | 0 | SF | | | | | | | | N/A | N/A | N/A |
| 3 | 1 | Gym Teacher's Restroom | N/A | Plaster Ceiling | | NAD | 48 | SF | 2 | SF | | | | | | | | N/A | N/A | N/A |
| 3 | 1 | Small Class Room next to Gym Teacher's Office | N/A | Concrete Block Wall | | Non Suspect ACM | 2254 | SF | 0 | SF | | | | | | | | N/A | N/A | N/A |
| 3 | 1 | Small Class Room next to Gym Teacher's Office | N/A | Concrete Ceiling | | Non Suspect ACM | 600 | SF | 0 | SF | | | | | | | | N/A | N/A | N/A |
| 3 | 1 | Small Class Room next to Gym Teacher's Office | M | Floor Tile VAT 9" x 9" | 7020/03/01/77 | Confirmed | 600 | SF | 0 | SF | | | | | Grey | | | 1 | No | 1/D |
| 3 | 1 | Small Class Room next to Gym Teacher's Office | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 20 | LF | 0 | LF | | | | | | | | N/A | N/A | N/A |
| 3 | 1 | Small Storage Room next to Athletic Director's Door | N/A | Concrete Block Wall | | Non Suspect ACM | 2254 | SF | 0 | SF | | | | | | | | N/A | N/A | N/A |
| 3 | 1 | Small Storage Room next to Athletic Director's Door | N/A | Concrete Ceiling | | Non Suspect ACM | 600 | SF | 0 | SF | | | | | | | | N/A | N/A | N/A |
| 3 | 1 | Small Storage Room next to Athletic Director's Door | M | Floor Tile VAT 9" x 9" | 7020/03/01/77 | Confirmed | 600 | SF | 0 | SF | | | | | Grey | | | 1 | No | 1/D |
| 3 | 1 | Athletic Director's Office | X | X | | X | X | X | X | X | | | | | | No Access | | X | X | X |
| 3 | 1 | Baseball Storage Room next to Men's Restroom in Old Gym Lobby | M | Floor Tile VAT 9" x 9" | 7020/03/01/77 | Confirmed | 168 | SF | 0 | SF | | | | | Brown | padlocked shut | | 1 | No | 1/D |
| 3 | 1 | Baseball Storage Room next to Men's Restroom in Old Gym Lobby | N/A | Concrete Block Wall | | Non Suspect ACM | 696 | SF | 0 | SF | | | | | | padlocked shut | | N/A | N/A | N/A |
| 3 | 1 | Baseball Storage Room next to Men's Restroom in Old Gym Lobby | N/A | Ceiling Tile 2' x 4' | | NAD | 168 | SF | 0 | SF | | | | | | padlocked shut | | N/A | N/A | N/A |
| 3 | 1 | Men's Restroom in Old Gym Lobby | N/A | Cement Floor | | Non Suspect ACM | 250 | SF | 0 | SF | | | | | | used for Baseball Storage - padlocked shut | | N/A | N/A | N/A |
| 3 | 1 | Men's Restroom in Old Gym Lobby | N/A | Concrete Block Wall | | Non Suspect ACM | 840 | SF | 0 | SF | | | | | | used for Baseball Storage - padlocked shut | | N/A | N/A | N/A |
| 3 | 1 | Men's Restroom in Old Gym Lobby | N/A | Plaster Ceiling | | NAD | 250 | SF | 0 | SF | | | | | | used for Baseball Storage - padlocked shut | | N/A | N/A | N/A |
| 3 | 1 | Old Gym Lobby | M | Floor Tile VAT 9" x 9" | 7020/03/01/77 | Confirmed | 2760 | SF | 0 | SF | | | | | | used for Baseball Storage | | 1 | No | 1/D |
| 3 | 1 | Old Gym Lobby | N/A | Concrete Block Wall | | Non Suspect ACM | 5450 | SF | 0 | SF | | | | | | used for Baseball Storage | | N/A | N/A | N/A |
| 3 | 1 | Old Gym Lobby | N/A | Ceiling Tile 2' x 4' | | NAD | 2760 | SF | 0 | SF | | | | | | used for Baseball Storage | | N/A | N/A | N/A |
| 3 | 1 | Old Gym Lobby | N/A | Cement Floor | | Non Suspect ACM | 88 | SF | 0 | SF | | | | | | used for Baseball Storage | | N/A | N/A | N/A |
| 3 | 1 | Old Gym Lobby | N/A | Concrete Block Wall | | Non Suspect ACM | 456 | SF | 0 | SF | | | | | | used for Baseball Storage | | N/A | N/A | N/A |
| 3 | 1 | Old Gym Lobby | N/A | Ceiling Tile 2' x 4' | | NAD | 88 | SF | 0 | SF | | | | | | used for Baseball Storage | | N/A | N/A | N/A |
| 3 | 1 | Women's Restroom in Old Gym Lobby | N/A | Cement Floor | | Non Suspect ACM | 250 | SF | 0 | SF | | | | | | used for Baseball Storage | | N/A | N/A | N/A |
| 3 | 1 | Women's Restroom in Old Gym Lobby | N/A | Concrete Block Wall | | Non Suspect ACM | 840 | SF | 0 | SF | | | | | | used for Baseball Storage | | N/A | N/A | N/A |
| 3 | 1 | Women's Restroom in Old Gym Lobby | N/A | Plaster Ceiling | | NAD | 250 | SF | 0 | SF | | | | | | used for Baseball Storage | | N/A | N/A | N/A |
| 3 | 1 | Main Hall around Gym leading to Locker Rooms and Cafeteria | M | Floor Tile VAT 9" x 9" | 7020/03/01/77 | Confirmed | 1600 | SF | 0 | SF | | | | | Black | | | 1 | No | 1/D |
| 3 | 1 | Main Hall around Gym leading to Locker Rooms and Cafeteria | N/A | Concrete Block Wall | | Non Suspect ACM | 6440 | SF | 0 | SF | | | | | | | | N/A | N/A | N/A |
| 3 | 1 | Main Hall around Gym leading to Locker Rooms and Cafeteria | N/A | Ceiling Tile 2' x 4' | | NAD | 2200 | SF | 0 | SF | | | | | | | | N/A | N/A | N/A |
| 3 | 1 | Main Hall around Gym leading to Locker Rooms and Cafeteria | M | Floor Tile VAT 9" x 9" | 7020/03/01/77 | Confirmed | 600 | SF | 0 | SF | | | | | White | | | 1 | No | 1/D |
| 3 | 1 | Girl's Restroom outside main Gym | N/A | Cement Floor | | Non Suspect ACM | 121 | SF | 0 | SF | | | | | | | | N/A | N/A | N/A |
| 3 | 1 | Girl's Restroom outside main Gym | N/A | Plaster Ceiling | | NAD | 121 | SF | 0 | SF | | | | | | | | N/A | N/A | N/A |
| 3 | 1 | Girl's Restroom outside main Gym | N/A | CMU | | Non Suspect ACM | 440 | SF | 0 | SF | | | | | | | | N/A | N/A | N/A |
| 3 | 1 | Boy's Restroom outside Main Gym | X | X | | X | X | X | X | X | | | | | | No Access | | X | X | X |
| 3 | 1 | Weight Room near Main Gym | M | Floor Tile VAT 9" x 9" | 7020/03/01/77 | Confirmed | 770 | SF | 0 | SF | | | | | Brown | | | 1 | No | 1/D |
| 3 | 1 | Weight Room near Main Gym | N/A | Concrete Block Wall | | Non Suspect ACM | 2052 | SF | 0 | SF | | | | | | | | N/A | N/A | N/A |
| 3 | 1 | Weight Room near Main Gym | N/A | Concrete Ceiling | | Non Suspect ACM | 770 | SF | 0 | SF | | | | | | | | N/A | N/A | N/A |
| 3 | 1 | Weight Room near Main Gym | N/A | Fiberglass Pipe Fitting Insulation | | Non Suspect ACM | 4 | EA | 1 | EA | | | | | | | | N/A | N/A | N/A |
| 3 | 1 | Weight Room near Main Gym | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 30 | LF | 0 | LF | | | | | | | | N/A | N/A | N/A |
| 3 | 1 | Cardio Room attached to Weight Room | M | Floor Tile VAT 9" x 9" | 7020/03/01/77 | Confirmed | 200 | SF | 0 | SF | | | | | | | | 1 | No | 1/D |
| 3 | 1 | Cardio Room attached to Weight Room | N/A | Concrete Block Wall | | Non Suspect ACM | 720 | SF | 0 | SF | | | | | | | | N/A | N/A | N/A |
| 3 | 1 | Cardio Room attached to Weight Room | N/A | Ceiling Tile 2' x 4' | | NAD | 200 | SF | 0 | SF | | | | | | | | N/A | N/A | N/A |
| 3 | 1 | Cardio Room attached to Weight Room | M | Blackboard Glue Dots | 7020/03/01/BATTA/AH/2600 | Assumed | X | SF | 0 | SF | | | | | | No material? - Inspector please verify | | 1 | No | 1/D |

7020 Olney HS (ASPIRA) 2015 2016 AHERA Three-Year Report.xls

| | | School District of Philadelphia Aspira Olney Charter High School 100 E. Duncannon Street, Philadelphia, PA 19120 ULCS# 7029 Year Built: 1931 | AHERA Three-Year Reinspection 2015-2016 Room by Room Location Log Report | | | | | | | | | | Reinspection Date: December 13, 2015 Building Inspector: James Madden Number: 030867 Management Planner: Megan Vala Number: 740728 | | | | | | | |
|---------------------------------|-----------------------|--|---|------------------------------------|--------------------------|---|-----------------------|-------------|---------------------|-------------|------------------------------|----------------------------|--|-----------------------------|--------------------------|-------------------------|--|--|--|--|
| E l e m e n t | F l o o r | On Site Room Name | System Affected | Material Description | HID# | Confirmed/Assumed/NAD/ Non Suspect ACM | Amount of Material | SF LF EA | Amount of Damage | SF LF EA | Color required for VAT | Comments/Description/Notes | Attic/ Crawl Space Ranking | Damage Potential (DP) | Newly Friable (NF) | Response Action (RA) | | | | |
| 3 | 1 | Cardio Room attached to Weight Room | N/A | Fiberglass Pipe Fitting Insulation | | Non Suspect ACM | 12 | EA | 0 | EA | | | | N/A | N/A | N/A | | | | |
| 3 | 1 | Cardio Room attached to Weight Room | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 20 | LF | 0 | LF | | | | N/A | N/A | N/A | | | | |
| 3 | 1 | Storage Room next to Catdio Room attached to Weight Room | M | Floor Tile VAT 9" x 9" | 7020/03/01/77 | Confirmed | 192 | SF | 0 | SF | Brown | | | 1 | No | 1/D | | | | |
| 3 | 1 | Storage Room next to Catdio Room attached to Weight Room | N/A | Concrete Block Wall | | Non Suspect ACM | 672 | SF | 0 | SF | | | | N/A | N/A | N/A | | | | |
| 3 | 1 | Storage Room next to Catdio Room attached to Weight Room | N/A | Ceiling Tile 2' x 4' | | NAD | 192 | SF | 0 | SF | | | | N/A | N/A | N/A | | | | |
| 3 | 1 | Trophy Storage Room attached to Weight Room | M | Floor Tile VAT 9" x 9" | 7020/03/01/77 | Confirmed | 100 | SF | 0 | SF | Blue | | | 1 | No | 1/D | | | | |
| 3 | 1 | Trophy Storage Room attached to Weight Room | N/A | Concrete Block Wall | | Non Suspect ACM | 480 | SF | 0 | SF | | | | N/A | N/A | N/A | | | | |
| 3 | 1 | Trophy Storage Room attached to Weight Room | N/A | Ceiling Tile 2' x 4' | | NAD | 100 | SF | 0 | SF | | | | N/A | N/A | N/A | | | | |
| 3 | 1 | Away Locker Room A102 | M | Floor Tile VAT 9" x 9" | 7020/03/01/77 | Confirmed | 756 | SF | 0 | SF | Brown | | | 1 | No | 1/D | | | | |
| 3 | 1 | Away Locker Room A102 | N/A | Concrete Block Wall | | Non Suspect ACM | 1710 | SF | 0 | SF | | | | N/A | N/A | N/A | | | | |
| 3 | 1 | Away Locker Room A102 | N/A | Ceiling Tile 2' x 4' | | NAD | 756 | SF | 0 | SF | | | | N/A | N/A | N/A | | | | |
| 3 | 1 | Away Locker Room A102 | N/A | Fiberglass Pipe Fitting Insulation | | Non Suspect ACM | 3 | EA | 0 | EA | | | | N/A | N/A | N/A | | | | |
| 3 | 1 | Away Locker Room A102 | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 75 | LF | 0 | LF | | | | N/A | N/A | N/A | | | | |
| 3 | 1 | Classroom A104 | M | Floor Tile VAT 9" x 9" | 7020/03/01/77 | Confirmed | 720 | SF | 0 | SF | | | | 1 | No | 1/D | | | | |
| 3 | 1 | Classroom A104 | N/A | Concrete Block Wall | | Non Suspect ACM | 1620 | SF | 0 | SF | | | | N/A | N/A | N/A | | | | |
| 3 | 1 | Classroom A104 | N/A | Ceiling Tile 2' x 4' | | NAD | 720 | SF | 0 | SF | | | | N/A | N/A | N/A | | | | |
| 3 | 1 | Classroom A104 | M | Blackboard Glue Dots | 7020/03/01/BATTA/AH/2600 | Assumed | 80 | SF | 0 | SF | | | | 1 | No | 1/D | | | | |
| 3 | 1 | Classroom A104 | N/A | Fiberglass Pipe Fitting Insulation | | Non Suspect ACM | 1 | EA | 0 | EA | | | | N/A | N/A | N/A | | | | |
| 3 | 1 | Classroom A104 | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 30 | LF | 0 | LF | | | | N/A | N/A | N/A | | | | |
| 3 | B | Basement Boy's Locker Room Storage | N/A | Cement Floor | | Non Suspect ACM | 300 | SF | 0 | SF | | | | N/A | N/A | N/A | | | | |
| 3 | B | Basement Boy's Locker Room Storage | N/A | Concrete Ceiling | | Non Suspect ACM | 300 | SF | 0 | SF | | | | N/A | N/A | N/A | | | | |
| 3 | B | Basement Boy's Locker Room Storage | N/A | Concrete Block Wall | | Non Suspect ACM | 600 | SF | 0 | SF | | | | N/A | N/A | N/A | | | | |
| 3 | B | Basement Boy's Locker Room Storage | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 50 | LF | 0 | LF | | | | N/A | N/A | N/A | | | | |
| 3 | B | Basement Boy's Locker Room Storage | N/A | Fiberglass Pipe Fitting Insulation | | Non Suspect ACM | 2 | EA | 0 | EA | | | | N/A | N/A | N/A | | | | |
| 3 | B | Basement Boy's Team Locker Room | N/A | Cement Floor | | Non Suspect ACM | 2250 | SF | 0 | SF | | | | N/A | N/A | N/A | | | | |
| 3 | B | Basement Boy's Team Locker Room | N/A | Concrete Ceiling | | Non Suspect ACM | 2250 | SF | 0 | SF | | | | N/A | N/A | N/A | | | | |
| 3 | B | Basement Boy's Team Locker Room | N/A | Concrete Block Wall | | Non Suspect ACM | 300 | SF | 0 | SF | | | | N/A | N/A | N/A | | | | |
| 3 | B | Basement Boy's Team Locker Room | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 300 | LF | 0 | LF | | | | N/A | N/A | N/A | | | | |
| 3 | B | Basement Boy's Team Locker Room | N/A | Fiberglass Pipe Fitting Insulation | | Non Suspect ACM | 20 | EA | 0 | EA | | | | N/A | N/A | N/A | | | | |
| 3 | B | Basement Boy's Locker Room | N/A | Cement Floor | | Non Suspect ACM | 6300 | SF | 0 | SF | | | | N/A | N/A | N/A | | | | |
| 3 | B | Basement Boy's Locker Room | N/A | Concrete Ceiling | | Non Suspect ACM | 6300 | SF | 0 | SF | | | | N/A | N/A | N/A | | | | |
| 3 | B | Basement Boy's Locker Room | N/A | Concrete Block Wall | | Non Suspect ACM | 400 | SF | 0 | SF | | | | N/A | N/A | N/A | | | | |
| 3 | B | Basement Boy's Locker Room | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 150 | LF | 25 | LF | | | | N/A | N/A | N/A | | | | |
| 3 | B | Basement Boy's Locker Room | N/A | Fiberglass Pipe Fitting Insulation | | Non Suspect ACM | 5 | EA | 0 | EA | | | | N/A | N/A | N/A | | | | |
| 3 | B | Basement Boy's Locker Room Restroom | N/A | Cement Floor | | Non Suspect ACM | 120 | SF | 0 | SF | | | | N/A | N/A | N/A | | | | |
| 3 | B | Basement Boy's Locker Room Restroom | N/A | Concrete Ceiling | | Non Suspect ACM | 120 | SF | 0 | SF | | | | N/A | N/A | N/A | | | | |
| 3 | B | Basement Boy's Locker Room Restroom | N/A | Concrete Block Wall | | Non Suspect ACM | 400 | SF | 0 | SF | | | | N/A | N/A | N/A | | | | |
| 3 | B | Basement Girl's Locker Room and associated | X | X | | X | X | X | X | X | | | | X | X | X | | | | |
| 1 | 2 | Office 211 | N/A | Wood Floor | | Non Suspect ACM | 750 | SF | 0 | SF | | | | N/A | N/A | N/A | | | | |
| 1 | 2 | Office 211 | N/A | Plaster Ceiling | | NAD | 750 | SF | 0 | SF | | | | N/A | N/A | N/A | | | | |
| 1 | 2 | Office 211 | N/A | Plaster Walls | | NAD | 1100 | SF | 0 | SF | | | | N/A | N/A | N/A | | | | |
| 1 | 2 | Office 211 | T | Pipe Insulation 2-6 inch | 7020/01/02/35 | Confirmed | 46 | LF | 0 | LF | | | | 1 | No | 1/D | | | | |
| 1 | 2 | Office 211 | T | Pipe Fitting Insulation | 7020/01/02/66 | Assumed | 10 | EA | 0 | EA | | | | 1 | No | 1/D | | | | |
| 1 | 2 | Office 211 | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 10 | LF | 0 | LF | | | | N/A | N/A | N/A | | | | |
| 1 | 2 | Office 211 | M | Blackboard Glue Dots | 7020/01/02/BATTA/AH/2600 | Assumed | 64 | SF | 0 | SF | | | | 1 | No | 1/D | | | | |
| 1 | 2 | Mailroom/Teacher's Lounge 213 Lobby | N/A | Wood Floor | | Non Suspect ACM | 36 | SF | 0 | SF | | | | N/A | N/A | N/A | | | | |
| 1 | 2 | Mailroom/Teacher's Lounge 213 Lobby | N/A | Plaster Ceiling | | NAD | 36 | SF | 0 | SF | | | | N/A | N/A | N/A | | | | |
| 1 | 2 | Mailroom/Teacher's Lounge 213 Lobby | N/A | Plaster Walls | | NAD | 336 | SF | 0 | SF | | | | N/A | N/A | N/A | | | | |
| 1 | 2 | Mailroom/Teacher's Lounge 213 Lobby | T | Pipe Insulation 2-6 inch | 7020/01/02/35 | Confirmed | 36 | LF | 0 | LF | | | | 1 | No | 1/D | | | | |
| 1 | 2 | Mailroom/Teacher's Lounge 213 Lobby | T | Pipe Fitting Insulation | 7020/01/02/66 | Assumed | 3 | EA | 0 | EA | | | | 1 | No | 1/D | | | | |
| 1 | 2 | Mailroom/Teacher's Lounge 213 Women's Restroom | N/A | Cement Floor | | Non Suspect ACM | 36 | SF | 0 | SF | | | | N/A | N/A | N/A | | | | |
| 1 | 2 | Mailroom/Teacher's Lounge 213 Women's Restroom | N/A | Ceiling Tile 2' x 4' | | NAD | 36 | SF | 0 | SF | | | | N/A | N/A | N/A | | | | |
| 1 | 2 | Mailroom/Teacher's Lounge 213 Women's Restroom | N/A | Plaster Walls | | NAD | 364 | SF | 0 | SF | | | | N/A | N/A | N/A | | | | |
| 1 | 2 | Mailroom/Teacher's Lounge 213 Women's Restroom | T | Pipe Insulation 2-6 inch | 7020/01/02/35 | Confirmed | 35 | LF | 0 | LF | | | | 1 | No | 1/D | | | | |
| 1 | 2 | Mailroom/Teacher's Lounge 213 Women's Restroom | T | Pipe Fitting Insulation | 7020/01/02/66 | Assumed | 1 | EA | 0 | EA | | | | 1 | No | 1/D | | | | |
| 1 | 2 | Mailroom/Teacher's Lounge 213 Women's Restroom Lounge | N/A | Cement Floor | | Non Suspect ACM | 25 | SF | 0 | SF | | | | N/A | N/A | N/A | | | | |
| 1 | 2 | Mailroom/Teacher's Lounge 213 Women's Restroom Lounge | N/A | Plaster Ceiling | | NAD | 25 | SF | 0 | SF | | | | N/A | N/A | N/A | | | | |
| 1 | 2 | Mailroom/Teacher's Lounge 213 Women's Restroom Lounge | N/A | Plaster Walls | | NAD | 200 | SF | 0 | SF | | | | N/A | N/A | N/A | | | | |
| 1 | 2 | Mailroom/Teacher's Lounge 213 Men's Restroom | N/A | Cement Floor | | Non Suspect ACM | 36 | SF | 0 | SF | | | | N/A | N/A | N/A | | | | |
| 1 | 2 | Mailroom/Teacher's Lounge 213 Men's Restroom | N/A | Plaster Ceiling | | NAD | 36 | SF | 5 | SF | | | | N/A | N/A | N/A | | | | |
| 1 | 2 | Mailroom/Teacher's Lounge 213 Men's Restroom | N/A | Plaster Walls | | NAD | 364 | SF | 0 | SF | | | | N/A | N/A | N/A | | | | |
| 1 | 2 | Mailroom/Teacher's Lounge 213 Men's Restroom | T | Pipe Insulation 2-6 inch | 7020/01/02/35 | Confirmed | 10 | LF | 0 | LF | | | | 1 | No | 1/D | | | | |
| 1 | 2 | Mailroom/Teacher's Lounge 213 Men's Restroom | T | Pipe Fitting Insulation | 7020/01/02/66 | Assumed | 6 | EA | 0 | EA | | | | 1 | No | 1/D | | | | |
| 1 | 2 | Mailroom/Teacher's Lounge 213 Men's Restroom | T | Pipe Insulation > 6 inch | 7020/01/02/36 | Confirmed | 3 | LF | 0 | LF | | | | 1 | No | 1/D | | | | |
| 1 | 2 | Mailroom/Teacher's Lounge 213, Main Lounge | M | Linoleum | 7020/01/02/KK | Assumed | 520 | SF | 0 | SF | Grey | Painted Grey | | 1 | No | 1/D | | | | |
| 1 | 2 | Mailroom/Teacher's Lounge 213, Main Lounge | N/A | Plaster Ceiling | | NAD | 520 | SF | 5 | SF | | | | N/A | N/A | N/A | | | | |
| 1 | 2 | Mailroom/Teacher's Lounge 213, Main Lounge | N/A | Plaster Walls | | NAD | 1288 | SF | 0 | SF | | | | N/A | N/A | N/A | | | | |
| 1 | 2 | Mailroom/Teacher's Lounge 213, Main Lounge | T | Pipe Insulation 2-6 inch | 7020/01/02/35 | Confirmed | 78 | LF | 0 | LF | | | | 1 | No | 1/D | | | | |

7020 Olney HS (ASPIRA) 2015 2016 AHERA Three-Year Report.xls

| | | School District of Philadelphia Aspira Olney Charter High School 100 E. Duncannon Street, Philadelphia, PA 19120 ULCS# 7029 Year Built: 1931 | | AHERA Three-Year Reinspection 2015-2016 Room by Room Location Log Report | | | | | | | | | | Reinspection Date: December 13, 2015 Building Inspector: James Madden Number: 030867 Management Planner: Megan Valia Number: 740728 | | | | | | |
|---------------------------------|-----------------------|--|-----------------|---|--------------------------|---|-----------------------|----|----|----|---------------------|----|----|---|------------------------------|--|----------------------------------|-----------------------------|--------------------------|-------------------------|
| E l e m e n t | F l o o r | On Site Room Name | System Affected | Material Description | HID# | Confirmed/Assumed/NAD/ Non Suspect ACM | Amount of Material | SF | LF | EA | Amount of Damage | SF | LF | EA | Color required for VAT | Comments/Description/Notes | Attic/ Crawl Space Ranking | Damage Potential (DP) | Newly Friable (NF) | Response Action (RA) |
| 1 | 2 | Mailroom/Teacher's Lounge 213, Main Lounge | T | Pipe Fitting Insulation | 7020/01/02/66 | Assumed | 17 | EA | 0 | EA | | | | | | | | | No | 1/D |
| 1 | 2 | Mailroom/Teacher's Lounge 213 Small Closet | N/A | Wood Floor | | Non Suspect ACM | 42 | SF | 0 | SF | | | | | | | | N/A | N/A | N/A |
| 1 | 2 | Mailroom/Teacher's Lounge 213 Small Closet | N/A | Plaster Ceiling | | NAD | 42 | SF | 0 | SF | | | | | | | | N/A | N/A | N/A |
| 1 | 2 | Mailroom/Teacher's Lounge 213 Small Closet | N/A | Plaster Walls | | NAD | 364 | SF | 5 | SF | | | | | | | | N/A | N/A | N/A |
| 1 | 2 | Mailroom/Teacher's Lounge 213 Small Closet | T | Pipe Insulation 2-6 inch | 7020/01/02/35 | Confirmed | 21 | LF | 0 | LF | | | | | | | | 1 | No | 1/D |
| 1 | 2 | Mailroom/Teacher's Lounge 213 Small Closet | T | Pipe Fitting Insulation | 7020/01/02/66 | Assumed | 3 | EA | 0 | EA | | | | | | | | 1 | No | 1/D |
| 1 | 2 | Counselor's Offices 215 | N/A | Wood Floor | | Non Suspect ACM | 720 | SF | 0 | SF | | | | | | | | N/A | N/A | N/A |
| 1 | 2 | Counselor's Offices 215 | N/A | Ceiling Tile 2' x 4' | | NAD | 720 | SF | 0 | SF | | | | | | | | N/A | N/A | N/A |
| 1 | 2 | Counselor's Offices 215 | N/A | Plaster Walls | | NAD | 1296 | SF | 0 | SF | | | | | | | | N/A | N/A | N/A |
| 1 | 2 | Counselor's Offices 215 | T | Pipe Insulation 2-6 inch | 7020/01/02/35 | Confirmed | 28 | LF | 0 | LF | | | | | | | | 1 | No | 1/D |
| 1 | 2 | Counselor's Offices 215 | T | Pipe Fitting Insulation | 7020/01/02/66 | Assumed | 4 | EA | 0 | EA | | | | | | | | 1 | No | 1/D |
| 1 | 2 | Counselor's Offices 215 | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 5 | LF | 0 | LF | | | | | | | | N/A | N/A | N/A |
| 1 | 2 | Small Room within Counselor's Office 215 | N/A | Wood Floor | | Non Suspect ACM | 225 | SF | 0 | SF | | | | | | | | N/A | N/A | N/A |
| 1 | 2 | Small Room within Counselor's Office 215 | N/A | Ceiling Tile 2' x 4' | | NAD | 225 | SF | 10 | SF | | | | | | water damage, Staining | | N/A | N/A | N/A |
| 1 | 2 | Small Room within Counselor's Office 215 | N/A | Plaster Walls | | NAD | 720 | SF | 0 | SF | | | | | | | | N/A | N/A | N/A |
| 1 | 2 | Small Room within Counselor's Office 215 | T | Pipe Insulation 2-6 inch | 7020/01/02/35 | Confirmed | 20 | LF | 0 | LF | | | | | | | | 1 | No | 1/D |
| 1 | 2 | Small Room within Counselor's Office 215 | T | Pipe Fitting Insulation | 7020/01/02/66 | Assumed | 4 | EA | 0 | EA | | | | | | | | 1 | No | 1/D |
| 1 | 2 | Small Room within Counselor's Office 215 | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 8 | LF | 0 | LF | | | | | | | | N/A | N/A | N/A |
| 1 | 2 | Office 217 | N/A | Wood Floor | | Non Suspect ACM | 270 | SF | 0 | SF | | | | | | | | N/A | N/A | N/A |
| 1 | 2 | Office 217 | N/A | Ceiling Tile 2' x 4' | | Non Suspect ACM | 270 | SF | 0 | SF | | | | | | | | N/A | N/A | N/A |
| 1 | 2 | Office 217 | N/A | Plaster Walls | | NAD | 792 | SF | 0 | SF | | | | | | | | N/A | N/A | N/A |
| 1 | 2 | Office 217 | T | Pipe Insulation 2-6 inch | 7020/01/02/35 | Confirmed | 12 | LF | 0 | LF | | | | | | | | 1 | No | 1/D |
| 1 | 2 | Office 217 | T | Pipe Fitting Insulation | 7020/01/02/66 | Assumed | 2 | EA | 0 | EA | | | | | | | | 1 | No | 1/D |
| 1 | 2 | Office 214 | N/A | Wood Floor | | Non Suspect ACM | 288 | SF | 0 | SF | | | | | | | | N/A | N/A | N/A |
| 1 | 2 | Office 214 | N/A | Concrete Ceiling | | Non Suspect ACM | 288 | SF | 0 | SF | | | | | | | | N/A | N/A | N/A |
| 1 | 2 | Office 214 | N/A | Plaster Walls | | NAD | 1008 | SF | 3 | SF | | | | | | Hole In Plaster | | N/A | N/A | N/A |
| 1 | 2 | Office 214 | T | Pipe Insulation 2-6 inch | 7020/01/02/35 | Confirmed | 18 | LF | 0 | LF | | | | | | | | 1 | No | 1/D |
| 1 | 2 | Office 214 | T | Pipe Fitting Insulation | 7020/01/02/66 | Assumed | 3 | EA | 0 | EA | | | | | | | | 1 | No | 1/D |
| 1 | 2 | Classroom 216 | M | Floor Tile VAT 9" x 9" | 7020/01/02/29 | Confirmed | 748 | SF | 0 | SF | | | | | Grey | | | 1 | No | 1/D |
| 1 | 2 | Classroom 216 | N/A | Ceiling Tile 2' x 4' | | NAD | 748 | SF | 0 | SF | | | | | | | | N/A | N/A | N/A |
| 1 | 2 | Classroom 216 | N/A | Plaster Walls | | NAD | 700 | SF | 0 | SF | | | | | | | | N/A | N/A | N/A |
| 1 | 2 | Classroom 216 | T | Pipe Insulation 2-6 inch | 7020/01/02/35 | Confirmed | 36 | LF | 0 | LF | | | | | | | | 1 | No | 1/D |
| 1 | 2 | Classroom 216 | T | Pipe Fitting Insulation | 7020/01/02/66 | Assumed | 3 | EA | 0 | EA | | | | | | | | 1 | No | 1/D |
| 1 | 2 | Classroom 216 | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 12 | LF | 4 | LF | | | | | | | | N/A | N/A | N/A |
| 1 | 2 | Classroom 216 | M | Blackboard Glue Dots | 7020/01/02/BATTA/AH/2600 | Assumed | 64 | SF | 0 | SF | | | | | | | | 1 | No | 1/D |
| 1 | 2 | Classroom 216 | N/A | Brick Wall | | Non Suspect ACM | 460 | SF | 0 | SF | | | | | | | | N/A | N/A | N/A |
| 1 | 2 | Classroom 216 | N/A | Sheetrock Wall | | Non Suspect ACM | 264 | SF | 0 | SF | | | | | | | | N/A | N/A | N/A |
| 1 | 2 | Classroom 218 | M | Floor Tile VAT 9" x 9" | 7020/01/02/29 | Confirmed | 748 | SF | 4 | SF | | | | | Grey | Spread Out Throughout Room | | 1 | Yes | 5/B |
| 1 | 2 | Classroom 218 | N/A | Ceiling Tile 2' x 4' | | NAD | 748 | SF | 0 | SF | | | | | | | | N/A | N/A | N/A |
| 1 | 2 | Classroom 218 | N/A | Plaster Walls | | NAD | 700 | SF | 6 | SF | | | | | | | | N/A | N/A | N/A |
| 1 | 2 | Classroom 218 | T | Pipe Insulation 2-6 inch | 7020/01/02/35 | Confirmed | 26 | LF | 0 | LF | | | | | | | | 1 | No | 1/D |
| 1 | 2 | Classroom 218 | T | Pipe Fitting Insulation | 7020/01/02/66 | Assumed | 4 | EA | 0 | EA | | | | | | | | 1 | No | 1/D |
| 1 | 2 | Classroom 218 | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 22 | LF | 0 | LF | | | | | | | | N/A | N/A | N/A |
| 1 | 2 | Classroom 218 | M | Blackboard Glue Dots | 7020/01/02/BATTA/AH/2600 | Assumed | 24 | SF | 0 | SF | | | | | | | | 1 | No | 1/D |
| 1 | 2 | Classroom 218 | N/A | Brick Wall | | Non Suspect ACM | 460 | SF | 0 | SF | | | | | | | | N/A | N/A | N/A |
| 1 | 2 | Classroom 218 | N/A | Sheetrock Wall | | Non Suspect ACM | 264 | SF | 0 | SF | | | | | | | | N/A | N/A | N/A |
| 1 | 2 | Classroom 218 | N/A | Brick Wall | | Non Suspect ACM | 32 | SF | 0 | SF | | | | | | | | N/A | N/A | N/A |
| 1 | 2 | Closet next to Classroom 218 | N/A | Sheetrock Wall | | Non Suspect ACM | 115 | SF | 0 | SF | | | | | | | | N/A | N/A | N/A |
| 1 | 2 | Closet next to Classroom 218 | M | Floor Tile VAT 9" x 9" | 7020/01/02/29 | Confirmed | 32 | SF | 0 | SF | | | | | Grey | | | 1 | No | 1/D |
| 1 | 2 | Closet next to Classroom 218 | N/A | Ceiling Tile 1' x 1' | | NAD | 32 | SF | 0 | SF | | | | | | | | N/A | N/A | N/A |
| 1 | 2 | Closet next to Classroom 218 | N/A | Plaster Walls | | NAD | 115 | SF | 0 | SF | | | | | | | | N/A | N/A | N/A |
| 1 | 2 | Office 219 | N/A | Wood Floor | | Non Suspect ACM | 270 | SF | 0 | SF | | | | | | | | N/A | N/A | N/A |
| 1 | 2 | Office 219 | N/A | Ceiling Tile 2' x 4' | | NAD | 270 | SF | 0 | SF | | | | | | | | N/A | N/A | N/A |
| 1 | 2 | Office 219 | N/A | Plaster Walls | | NAD | 792 | SF | 0 | SF | | | | | | | | N/A | N/A | N/A |
| 1 | 2 | Office 219 | T | Pipe Insulation 2-6 inch | 7020/01/02/35 | Confirmed | 26 | LF | 0 | LF | | | | | | | | 1 | No | 1/D |
| 1 | 2 | Office 219 | T | Pipe Fitting Insulation | 7020/01/02/66 | Assumed | 2 | EA | 0 | EA | | | | | | | | 1 | No | 1/D |
| 1 | 2 | Classroom 221 | N/A | Wood Floor | | Non Suspect ACM | 800 | SF | 0 | SF | | | | | | | | N/A | N/A | N/A |
| 1 | 2 | Classroom 221 | N/A | Ceiling Tile 2' x 4' | | NAD | 800 | SF | 0 | SF | | | | | | | | N/A | N/A | N/A |
| 1 | 2 | Classroom 221 | N/A | Plaster Walls | | NAD | 1100 | SF | 0 | SF | | | | | | | | N/A | N/A | N/A |
| 1 | 2 | Classroom 221 | T | Pipe Insulation 2-6 inch | 7020/01/02/35 | Confirmed | 56 | LF | 0 | LF | | | | | | | | 1 | No | 1/D |
| 1 | 2 | Classroom 221 | T | Pipe Fitting Insulation | 7020/01/02/66 | Assumed | 10 | EA | 1 | EA | | | | | | Cracked | | 1 | Yes | 5/A |
| 1 | 2 | Classroom 221 | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 10 | LF | 3 | LF | | | | | | | | N/A | N/A | N/A |
| 1 | 2 | Classroom 221 | M | Blackboard Glue Dots | 7020/01/02/BATTA/AH/2600 | Assumed | 128 | SF | 0 | SF | | | | | | | | 1 | No | 1/D |
| 1 | 2 | Classroom 221 | T | Pipe Insulation > 6 inch | 7020/01/02/36 | Confirmed | X | LF | 0 | LF | | | | | | No material? - Inspector please verify | | 1 | No | 1/D |
| 1 | 2 | Classroom 223 | N/A | Wood Floor | | Non Suspect ACM | 775 | SF | 0 | SF | | | | | | | | N/A | N/A | N/A |
| 1 | 2 | Classroom 223 | N/A | Plaster Ceiling | | NAD | 775 | SF | 0 | SF | | | | | | | | N/A | N/A | N/A |
| 1 | 2 | Classroom 223 | N/A | Plaster Walls | | NAD | 1568 | SF | 0 | SF | | | | | | | | N/A | N/A | N/A |
| 1 | 2 | Classroom 223 | T | Pipe Insulation 2-6 inch | 7020/01/02/35 | Confirmed | 20 | LF | 0 | LF | | | | | | | | 1 | No | 1/D |
| 1 | 2 | Classroom 223 | T | Pipe Fitting Insulation | 7020/01/02/66 | Assumed | 6 | EA | 0 | EA | | | | | | | | 1 | No | 1/D |
| 1 | 2 | Classroom 223 | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 28 | LF | 5 | LF | | | | | | | | N/A | N/A | N/A |
| 1 | 2 | Classroom 223 | M | Blackboard Glue Dots | 7020/01/02/BATTA/AH/2600 | Assumed | 64 | SF | 0 | SF | | | | | | | | 1 | No | 1/D |
| 1 | 2 | Hallway from Office 211 to Classroom 223 | N/A | Cement Floor | | Non Suspect ACM | 2040 | SF | 0 | SF | | | | | | | | N/A | N/A | N/A |

7020 Olney HS (ASPIRA) 2015 2016 AHERA Three-Year Report.xls

| | | School District of Philadelphia Aspira Olney Charter High School 100 E. Duncannon Street, Philadelphia, PA 19120 ULCS# 7029 Year Built: 1931 | AHERA Three-Year Reinspection 2015-2016 Room by Room Location Log Report | | | | | | | | | | Reinspection Date: December 13, 2015 Building Inspector: James Madden Number: 030867 Management Planner: Megan Vala Number: 740728 | | | | | |
|---------------------------------|-----------------------|--|---|----------------------------|--------------------------|---|-----------------------|----------------|---------------------|----------------|------------------------------|--|--|-----------------------------|--------------------------|-------------------------|--|--|
| E l e m e n t | F l o o r | On Site Room Name | System Affected | Material Description | HID# | Confirmed/Assumed/NAD/ Non Suspect ACM | Amount of Material | SF LF EA | Amount of Damage | SF LF EA | Color required for VAT | Comments/Description/Notes | Attic/ Crawl Space Ranking | Damage Potential (DP) | Newly Friable (NF) | Response Action (RA) | | |
| 1 | 2 | Hallway from Office 211 to Classroom 223 | N/A | Plaster Walls | | NAD | 3822 | SF | 0 | SF | | | | N/A | N/A | N/A | | |
| 1 | 2 | Hallway from Office 211 to Classroom 223 | N/A | Marble Walls | | Non Suspect ACM | 1274 | SF | 0 | SF | | | | N/A | N/A | N/A | | |
| 1 | 2 | Hallway from Office 211 to Classroom 223 | N/A | Ceiling Tile 2' x 4' | | NAD | 2040 | SF | 0 | SF | | | | N/A | N/A | N/A | | |
| 1 | 2 | Classroom 225 | N/A | Wood Floor | | Non Suspect ACM | 840 | SF | 0 | SF | | | | N/A | N/A | N/A | | |
| 1 | 2 | Classroom 225 | N/A | Plaster Ceiling | | NAD | 840 | SF | 5 | SF | | | | N/A | N/A | N/A | | |
| 1 | 2 | Classroom 225 | N/A | Plaster Walls | | NAD | 1652 | SF | 0 | SF | | | | N/A | N/A | N/A | | |
| 1 | 2 | Classroom 225 | T | Pipe Insulation 2-6 inch | 7020/01/02/35 | Confirmed | 32 | LF | 2 | LF | | | | 1 | Yes | 5/A | | |
| 1 | 2 | Classroom 225 | T | Pipe Fitting Insulation | 7020/01/02/66 | Assumed | 18 | EA | 0 | EA | | | | 1 | No | 1/D | | |
| 1 | 2 | Classroom 225 | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 18 | LF | 0 | LF | | | | N/A | N/A | N/A | | |
| 1 | 2 | Classroom 225 | M | Blackboard Glue Dots | 7020/01/02/BATTA/AH/2600 | Assumed | 200 | SF | 0 | SF | | | | 1 | No | 1/D | | |
| 1 | 2 | Office 227 | N/A | Wood Floor | | Non Suspect ACM | 408 | SF | 0 | SF | | | | N/A | N/A | N/A | | |
| 1 | 2 | Office 227 | N/A | Plaster Ceiling | | NAD | 408 | SF | 0 | SF | | | | N/A | N/A | N/A | | |
| 1 | 2 | Office 227 | N/A | Plaster Walls | | NAD | 1148 | SF | 0 | SF | | | | N/A | N/A | N/A | | |
| 1 | 2 | Office 227 | T | Pipe Insulation 2-6 inch | 7020/01/02/35 | Confirmed | 45 | LF | 0 | LF | | | | 1 | No | 1/D | | |
| 1 | 2 | Office 227 | T | Pipe Fitting Insulation | 7020/01/02/66 | Assumed | 15 | EA | 0 | EA | | | | 1 | No | 1/D | | |
| 1 | 2 | Office 227 | M | Blackboard Glue Dots | 7020/01/02/BATTA/AH/2600 | Assumed | 160 | SF | 0 | SF | | | | 1 | No | 1/D | | |
| 1 | 2 | Office 227 | T | Pipe Insulation > 6 inch | 7020/01/02/36 | Confirmed | 23 | LF | 2 | LF | | Cracks and Staining/Water Damage | | 1 | Yes | 5/A | | |
| 1 | 2 | Classroom 229 | N/A | Wood Floor | | Non Suspect ACM | 696 | SF | 0 | SF | | | | N/A | N/A | N/A | | |
| 1 | 2 | Classroom 229 | N/A | Plaster Ceiling | | NAD | 696 | SF | 0 | SF | | | | N/A | N/A | N/A | | |
| 1 | 2 | Classroom 229 | N/A | Plaster Walls | | NAD | 1484 | SF | 0 | SF | | | | N/A | N/A | N/A | | |
| 1 | 2 | Classroom 229 | T | Pipe Insulation 2-6 inch | 7020/01/02/35 | Confirmed | 27 | LF | 0 | LF | | | | 1 | No | 1/D | | |
| 1 | 2 | Classroom 229 | T | Pipe Fitting Insulation | 7020/01/02/66 | Assumed | 4 | EA | 0 | EA | | | | 1 | No | 1/D | | |
| 1 | 2 | Classroom 229 | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 28 | LF | 5 | LF | | Pen Holes and ripping | | N/A | N/A | N/A | | |
| 1 | 2 | Classroom 229 | M | Blackboard Glue Dots | 7020/01/02/BATTA/AH/2600 | Assumed | 100 | SF | 0 | SF | | | | 1 | No | 1/D | | |
| 1 | 2 | Classroom 231 | N/A | Wood Floor | | Non Suspect ACM | 720 | SF | 0 | SF | | | | N/A | N/A | N/A | | |
| 1 | 2 | Classroom 231 | N/A | Plaster Ceiling | | NAD | 720 | SF | 2 | SF | | | | N/A | N/A | N/A | | |
| 1 | 2 | Classroom 231 | N/A | Plaster Walls | | NAD | 1512 | SF | 0 | SF | | | | N/A | N/A | N/A | | |
| 1 | 2 | Classroom 231 | T | Pipe Insulation 2-6 inch | 7020/01/02/35 | Confirmed | 40 | LF | 0 | LF | | | | 1 | No | 1/D | | |
| 1 | 2 | Classroom 231 | T | Pipe Fitting Insulation | 7020/01/02/66 | Assumed | 10 | EA | 0 | EA | | | | 1 | No | 1/D | | |
| 1 | 2 | Classroom 231 | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 24 | LF | 0 | LF | | | | N/A | N/A | N/A | | |
| 1 | 2 | Classroom 231 | M | Blackboard Glue Dots | 7020/01/02/BATTA/AH/2600 | Assumed | 124 | SF | 0 | SF | | | | 1 | No | 1/D | | |
| 1 | 2 | Classroom 233 | N/A | Wood Floor | | Non Suspect ACM | 780 | SF | 0 | SF | | | | N/A | N/A | N/A | | |
| 1 | 2 | Classroom 233 | N/A | Plaster Ceiling | | NAD | 780 | SF | 0 | SF | | | | N/A | N/A | N/A | | |
| 1 | 2 | Classroom 233 | N/A | Plaster Walls | | NAD | 1568 | SF | 2 | SF | | | | N/A | N/A | N/A | | |
| 1 | 2 | Classroom 233 | T | Pipe Fitting Insulation | 7020/01/02/66 | Assumed | X | EA | 0 | EA | | No material? - Inspector please verify | | 1 | No | 1/D | | |
| 1 | 2 | Classroom 233 | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 34 | LF | 0 | LF | | Most Pipes uninsulated | | N/A | N/A | N/A | | |
| 1 | 2 | Classroom 233 | M | Blackboard Glue Dots | 7020/01/02/BATTA/AH/2600 | Assumed | 164 | SF | 0 | SF | | | | 1 | No | 1/D | | |
| 1 | 2 | Classroom 235 | N/A | Wood Floor | | Non Suspect ACM | 720 | SF | 0 | SF | | | | N/A | N/A | N/A | | |
| 1 | 2 | Classroom 235 | N/A | Plaster Ceiling | | NAD | 720 | SF | 0 | SF | | | | N/A | N/A | N/A | | |
| 1 | 2 | Classroom 235 | N/A | Plaster Walls | | NAD | 1512 | SF | 0 | SF | | | | N/A | N/A | N/A | | |
| 1 | 2 | Classroom 235 | T | Pipe Insulation 2-6 inch | 7020/01/02/35 | Confirmed | 45 | LF | 0 | LF | | | | 1 | No | 1/D | | |
| 1 | 2 | Classroom 235 | T | Pipe Fitting Insulation | 7020/01/02/66 | Assumed | 10 | EA | 0 | EA | | | | 1 | No | 1/D | | |
| 1 | 2 | Classroom 235 | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 40 | LF | 3 | LF | | Small Holes | | N/A | N/A | N/A | | |
| 1 | 2 | Classroom 235 | M | Blackboard Glue Dots | 7020/01/02/BATTA/AH/2600 | Assumed | 164 | SF | 0 | SF | | | | 1 | No | 1/D | | |
| 1 | 2 | Classroom 237 | N/A | Wood Floor | | Non Suspect ACM | 720 | SF | 0 | SF | | | | N/A | N/A | N/A | | |
| 1 | 2 | Classroom 237 | N/A | Plaster Ceiling | | NAD | 720 | SF | 0 | SF | | | | N/A | N/A | N/A | | |
| 1 | 2 | Classroom 237 | N/A | Plaster Walls | | NAD | 1512 | SF | 0 | SF | | | | N/A | N/A | N/A | | |
| 1 | 2 | Classroom 237 | T | Pipe Insulation 2-6 inch | 7020/01/02/35 | Confirmed | 36 | LF | 0 | LF | | Uninsulated Pipe | | 1 | No | 1/D | | |
| 1 | 2 | Classroom 237 | T | Pipe Fitting Insulation | 7020/01/02/66 | Assumed | 10 | EA | 0 | EA | | | | 1 | No | 1/D | | |
| 1 | 2 | Classroom 237 | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 25 | LF | 0 | LF | | | | N/A | N/A | N/A | | |
| 1 | 2 | Classroom 237 | M | Blackboard Glue Dots | 7020/01/02/BATTA/AH/2600 | Assumed | 100 | SF | 0 | SF | | | | 1 | No | 1/D | | |
| 1 | 2 | Classroom 239 | N/A | Wood Floor | | Non Suspect ACM | 720 | SF | 0 | SF | | | | N/A | N/A | N/A | | |
| 1 | 2 | Classroom 239 | N/A | Plaster Ceiling | | NAD | 720 | SF | 0 | SF | | | | N/A | N/A | N/A | | |
| 1 | 2 | Classroom 239 | N/A | Plaster Walls | | NAD | 1512 | SF | 0 | SF | | | | N/A | N/A | N/A | | |
| 1 | 2 | Classroom 239 | T | Pipe Insulation 2-6 inch | 7020/01/02/35 | Confirmed | 30 | LF | 0 | LF | | Cracked Fitting | | 1 | No | 1/D | | |
| 1 | 2 | Classroom 239 | T | Pipe Fitting Insulation | 7020/01/02/66 | Assumed | 10 | EA | 1 | EA | | | | 1 | Yes | 5/A | | |
| 1 | 2 | Classroom 239 | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 30 | LF | 0 | LF | | | | N/A | N/A | N/A | | |
| 1 | 2 | Classroom 239 | M | Blackboard Glue Dots | 7020/01/02/BATTA/AH/2600 | Assumed | 64 | SF | 0 | SF | | | | 1 | No | 1/D | | |
| 1 | 2 | Classroom 241 | N/A | Wood Floor | | Non Suspect ACM | 720 | SF | 0 | SF | | | | N/A | N/A | N/A | | |
| 1 | 2 | Classroom 241 | N/A | Plaster Ceiling | | NAD | 720 | SF | 5 | SF | | | | N/A | N/A | N/A | | |
| 1 | 2 | Classroom 241 | N/A | Plaster Walls | | NAD | 1512 | SF | 0 | SF | | | | N/A | N/A | N/A | | |
| 1 | 2 | Classroom 241 | T | Pipe Insulation 2-6 inch | 7020/01/02/35 | Confirmed | 66 | LF | 2 | LF | | Broken unencapsulated ends | | 1 | Yes | 5/A | | |
| 1 | 2 | Classroom 241 | T | Pipe Fitting Insulation | 7020/01/02/66 | Assumed | 10 | EA | 0 | EA | | | | 1 | No | 1/D | | |
| 1 | 2 | Classroom 241 | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 16 | LF | 0 | LF | | | | N/A | N/A | N/A | | |
| 1 | 2 | Classroom 241 | M | Blackboard Glue Dots | 7020/01/02/BATTA/AH/2600 | Assumed | 164 | SF | 0 | SF | | | | 1 | No | 1/D | | |
| 1 | 2 | Classroom 243 | N/A | Wood Floor | | Non Suspect ACM | 720 | SF | 0 | SF | | | | N/A | N/A | N/A | | |
| 1 | 2 | Classroom 243 | N/A | Plaster Ceiling | | NAD | 720 | SF | 2 | SF | | | | N/A | N/A | N/A | | |
| 1 | 2 | Classroom 243 | N/A | Plaster Walls | | NAD | 1512 | SF | 0 | SF | | | | N/A | N/A | N/A | | |
| 1 | 2 | Classroom 243 | T | Pipe Insulation 2-6 inch | 7020/01/02/35 | Confirmed | 87 | LF | 0 | LF | | | | 1 | No | 1/D | | |
| 1 | 2 | Classroom 243 | T | Pipe Fitting Insulation | 7020/01/02/66 | Assumed | 19 | EA | 0 | EA | | | | 1 | No | 1/D | | |
| 1 | 2 | Classroom 243 | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 40 | LF | 6 | LF | | | | N/A | N/A | N/A | | |
| 1 | 2 | Classroom 243 | M | Blackboard Glue Dots | 7020/01/02/BATTA/AH/2600 | Assumed | 164 | SF | 0 | SF | | | | 1 | No | 1/D | | |
| 1 | 2 | Hallway from Classrooms 225 to 243 | N/A | Cement Floor | | Non Suspect ACM | 3240 | SF | 0 | SF | | | | N/A | N/A | N/A | | |

7020 Olney HS (ASPIRA) 2015 2016 AHERA Three-Year Report.xls

| School District of Philadelphia Aspira Olney Charter High School 100 E. Duncannon Street, Philadelphia, PA 19120 ULCS# 7029 Year Built: 1931 | | | AHERA Three-Year Reinspection 2015-2016 Room by Room Location Log Report | | | | | | | | | | | Reinspection Date: December 13, 2015 Building Inspector: James Madden Number: 030867 Management Planner: Megan Vala Number: 740728 | | | | | | | |
|--|-----------------------|------------------------------------|---|----------------------------|--------------------------|---|-----------------------|----|----|----|---------------------|----|----|--|------------------------------|---|----------------------------------|-----------------------------|--------------------------|-------------------------|--|
| E l e m e n t | F l o o r | On Site Room Name | System Affected | Material Description | HID# | Confirmed/Assumed/NAD/ Non Suspect ACM | Amount of Material | SF | LF | EA | Amount of Damage | SF | LF | EA | Color required for VAT | Comments/Description/Notes | Attic/ Crawl Space Ranking | Damage Potential (DP) | Newly Friable (NF) | Response Action (RA) | |
| | | | | | | | | | | | | | | | | | | | | | |
| 1 | 2 | Hallway from Classrooms 225 to 243 | N/A | Plaster Walls | | NAD | 7896 | SF | 0 | SF | | | | | | | | N/A | N/A | N/A | |
| 1 | 2 | Hallway from Classrooms 225 to 243 | N/A | Ceiling Tile 2' x 4' | | NAD | 3240 | SF | 0 | SF | | | | | | | | N/A | N/A | N/A | |
| 1 | 2 | Hallway from Classrooms 225 to 243 | T | Pipe Insulation 2-6 inch | 7020/01/02/35 | Confirmed | 50 | LF | 0 | LF | | | | | | | | 1 | No | 1/D | |
| 1 | 2 | Hallway from Classrooms 225 to 243 | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 130 | LF | 15 | LF | | | | | | | | N/A | N/A | N/A | |
| 1 | 2 | Office 245 | N/A | Wood Floor | | Non Suspect ACM | 442 | SF | 0 | SF | | | | | | | | N/A | N/A | N/A | |
| 1 | 2 | Office 245 | N/A | Plaster Ceiling | | NAD | 442 | SF | 0 | SF | | | | | | | | N/A | N/A | N/A | |
| 1 | 2 | Office 245 | N/A | Plaster Walls | | NAD | 1204 | SF | 0 | SF | | | | | | | | N/A | N/A | N/A | |
| 1 | 2 | Office 245 | T | Pipe Insulation 2-6 inch | 7020/01/02/35 | Confirmed | 30 | LF | 0 | LF | | | | | | | | 1 | No | 1/D | |
| 1 | 2 | Office 245 | T | Pipe Fitting Insulation | 7020/01/02/66 | Assumed | 4 | EA | 0 | EA | | | | | | | | 1 | No | 1/D | |
| 1 | 2 | Computer Graphics Room 247 | N/A | Wood Floor | | Non Suspect ACM | 864 | SF | 0 | SF | | | | | | | | N/A | N/A | N/A | |
| 1 | 2 | Computer Graphics Room 247 | N/A | Plaster Ceiling | | NAD | 864 | SF | 0 | SF | | | | | | | | N/A | N/A | N/A | |
| 1 | 2 | Computer Graphics Room 247 | N/A | Plaster Walls | | NAD | 1680 | SF | 0 | SF | | | | | | | | N/A | N/A | N/A | |
| 1 | 2 | Computer Graphics Room 247 | T | Pipe Insulation 2-6 inch | 7020/01/02/35 | Confirmed | 105 | LF | 0 | LF | | | | | | | | 1 | No | 1/D | |
| 1 | 2 | Computer Graphics Room 247 | T | Pipe Fitting Insulation | 7020/01/02/66 | Assumed | 27 | EA | 0 | EA | | | | | | | | 1 | No | 1/D | |
| 1 | 2 | Computer Graphics Room 247 | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 48 | LF | 0 | LF | | | | | | | | N/A | N/A | N/A | |
| 1 | 2 | Computer Graphics Room 247 | M | Blackboard Glue Dots | 7020/01/02/BATTA/AH/2600 | Assumed | 200 | SF | 0 | SF | | | | | | | | 1 | No | 1/D | |
| 1 | 2 | Computer Graphics Room 247 | T | Pipe Insulation > 6 inch | 7020/01/02/36 | Confirmed | 45 | LF | 0 | LF | | | | | | | | 1 | No | 1/D | |
| 1 | 2 | Classroom 249 | M | Floor Tile VAT 12" x 12" | 7020/01/02/A5 | Assumed | 900 | SF | 0 | SF | | | | | Tan | | | 1 | No | 1/D | |
| 1 | 2 | Classroom 249 | N/A | Plaster Ceiling | | NAD | 900 | SF | 0 | SF | | | | | | | | N/A | N/A | N/A | |
| 1 | 2 | Classroom 249 | N/A | Plaster Walls | | NAD | 1680 | SF | 0 | SF | | | | | | | | N/A | N/A | N/A | |
| 1 | 2 | Classroom 249 | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 20 | LF | 0 | LF | | | | | | | | N/A | N/A | N/A | |
| 1 | 2 | Classroom 249 | M | Blackboard Glue Dots | 7020/01/02/BATTA/AH/2600 | Assumed | 128 | SF | 0 | SF | | | | | | | | 1 | No | 1/D | |
| 1 | 2 | Classroom 251 | N/A | Wood Floor | | Non Suspect ACM | 720 | SF | 0 | SF | | | | | | | | N/A | N/A | N/A | |
| 1 | 2 | Classroom 251 | N/A | Plaster Ceiling | | NAD | 720 | SF | 0 | SF | | | | | | | | N/A | N/A | N/A | |
| 1 | 2 | Classroom 251 | N/A | Plaster Walls | | NAD | 1512 | SF | 0 | SF | | | | | | | | N/A | N/A | N/A | |
| 1 | 2 | Classroom 251 | T | Pipe Insulation 2-6 inch | 7020/01/02/35 | Confirmed | 175 | LF | 0 | LF | | | | | | | | 1 | No | 1/D | |
| 1 | 2 | Classroom 251 | T | Pipe Fitting Insulation | 7020/01/02/66 | Assumed | 39 | EA | 5 | EA | | | | | | | | 1 | Yes | 5/A | |
| 1 | 2 | Classroom 251 | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 18 | LF | 0 | LF | | | | | | | | N/A | N/A | N/A | |
| 1 | 2 | Classroom 251 | M | Blackboard Glue Dots | 7020/01/02/BATTA/AH/2600 | Assumed | 128 | SF | 0 | SF | | | | | | | | 1 | No | 1/D | |
| 1 | 2 | Classroom 251 | T | Pipe Insulation > 6 inch | 7020/01/02/36 | Confirmed | 40 | LF | 0 | LF | | | | | | | | 1 | No | 1/D | |
| 1 | 2 | Girl's Restroom | X | X | | X | X | X | X | X | | | | | | Inspector did not list - please verify | | X | X | X | |
| 1 | 2 | School Psychologist Office 253 | N/A | Wood Floor | | Non Suspect ACM | 270 | SF | 0 | SF | | | | | | | | N/A | N/A | N/A | |
| 1 | 2 | School Psychologist Office 253 | N/A | Plaster Ceiling | | NAD | 270 | SF | 0 | SF | | | | | | | | N/A | N/A | N/A | |
| 1 | 2 | School Psychologist Office 253 | N/A | Plaster Walls | | NAD | 924 | SF | 0 | SF | | | | | | | | N/A | N/A | N/A | |
| 1 | 2 | School Psychologist Office 253 | T | Pipe Insulation 2-6 inch | 7020/01/02/35 | Confirmed | 12 | LF | 0 | LF | | | | | | | | 1 | No | 1/D | |
| 1 | 2 | Closet outside Office 253 | N/A | Wood Floor | | Non Suspect ACM | 63 | SF | 0 | SF | | | | | | No access (Fall 2016) | | N/A | N/A | N/A | |
| 1 | 2 | Closet outside Office 253 | N/A | Plaster Ceiling | | NAD | 63 | SF | 0 | SF | | | | | | | | N/A | N/A | N/A | |
| 1 | 2 | Closet outside Office 253 | N/A | Plaster Walls | | NAD | 448 | SF | 4 | SF | | | | | | Around Pipes | | N/A | N/A | N/A | |
| 1 | 2 | Closet outside Office 253 | T | Pipe Insulation 2-6 inch | 7020/01/02/35 | Confirmed | X | LF | 0 | LF | | | | | | No access (Fall 2016) - No material? - Inspector please verify | | 1 | No | 1/D | |
| 1 | 2 | Closet outside Office 253 | T | Pipe Fitting Insulation | 7020/01/02/66 | Assumed | X | EA | 0 | EA | | | | | | No access (Fall 2016) - No material? - Inspector please verify | | 1 | No | 1/D | |
| 1 | 2 | Closet outside Office 253 | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | X | LF | 0 | LF | | | | | | No material? - Inspector please verify - No access (Fall 2016) | | N/A | N/A | N/A | |
| 1 | 2 | Closet outside Office 253 | M | Blackboard Glue Dots | 7020/01/02/BATTA/AH/2600 | Assumed | X | SF | 0 | SF | | | | | | No access (Fall 2016) - No material? - Inspector please verify | | 1 | No | 1/D | |
| 1 | 2 | Closet outside Office 253 | T | Pipe Insulation > 6 inch | 7020/01/02/36 | Confirmed | X | LF | 0 | LF | | | | | | No access (Fall 2016) - No material? - Inspector please verify | | 1 | No | 1/D | |
| 1 | 2 | Classroom 254 | M | Floor Tile VAT 9" x 9" | 7020/01/02/29 | Confirmed | 750 | SF | 0 | SF | | | | | White | | | 1 | No | 1/D | |
| 1 | 2 | Classroom 254 | N/A | Ceiling Tile 2' x 4' | | NAD | 750 | SF | 0 | SF | | | | | | | | N/A | N/A | N/A | |
| 1 | 2 | Classroom 254 | N/A | Plaster Walls | | NAD | 1000 | SF | 0 | SF | | | | | | | | N/A | N/A | N/A | |
| 1 | 2 | Classroom 254 | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 25 | LF | 0 | LF | | | | | | | | N/A | N/A | N/A | |
| 1 | 2 | Office 255 | N/A | Wood Floor | | Non Suspect ACM | 270 | SF | 0 | SF | | | | | | | | N/A | N/A | N/A | |
| 1 | 2 | Office 255 | N/A | Plaster Ceiling | | NAD | 270 | SF | 0 | SF | | | | | | | | N/A | N/A | N/A | |
| 1 | 2 | Office 255 | N/A | Plaster Walls | | NAD | 924 | SF | 0 | SF | | | | | | | | N/A | N/A | N/A | |
| 1 | 2 | Office 255 | T | Pipe Insulation 2-6 inch | 7020/01/02/35 | Confirmed | 48 | LF | 0 | LF | | | | | | | | 1 | No | 1/D | |
| 1 | 2 | Office 255 | T | Pipe Fitting Insulation | 7020/01/02/66 | Assumed | 11 | EA | 0 | EA | | | | | | | | 1 | No | 1/D | |
| 1 | 2 | Office 255 | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | X | LF | 0 | LF | | | | | | No material? - Inspector please verify - No access (Fall 2016) | | N/A | N/A | N/A | |
| 1 | 2 | Office 255 | M | Blackboard Glue Dots | 7020/01/02/BATTA/AH/2600 | Assumed | X | SF | 0 | SF | | | | | | No access (Fall 2016) - No material? - Inspector please verify | | 1 | No | 1/D | |
| 1 | 2 | Office 255 | T | Pipe Insulation > 6 inch | 7020/01/02/36 | Confirmed | X | LF | 0 | LF | | | | | | No access (Fall 2016) - No material? - Inspector please verify | | 1 | No | 1/D | |
| 1 | 2 | Closet outside Office 255 | N/A | Wood Floor | | Non Suspect ACM | 63 | SF | 0 | SF | | | | | | | | N/A | N/A | N/A | |
| 1 | 2 | Closet outside Office 255 | N/A | Plaster Ceiling | | NAD | 63 | SF | 0 | SF | | | | | | | | N/A | N/A | N/A | |
| 1 | 2 | Closet outside Office 255 | N/A | Plaster Walls | | NAD | 448 | SF | 0 | SF | | | | | | | | N/A | N/A | N/A | |
| 1 | 2 | Classroom 256 | M | Floor Tile VAT 9" x 9" | 7020/01/02/29 | Confirmed | 750 | SF | 0 | SF | | | | | White | | | 1 | No | 1/D | |
| 1 | 2 | Classroom 256 | N/A | Ceiling Tile 2' x 4' | | NAD | 750 | SF | 0 | SF | | | | | | | | N/A | N/A | N/A | |
| 1 | 2 | Classroom 256 | N/A | Plaster Walls | | NAD | 750 | SF | 0 | SF | | | | | | | | N/A | N/A | N/A | |
| 1 | 2 | Classroom 256 | N/A | Brick Wall | | Non Suspect ACM | 250 | SF | 0 | SF | | | | | | | | N/A | N/A | N/A | |
| 1 | 2 | Classroom 256 | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 25 | LF | 0 | LF | | | | | | | | N/A | N/A | N/A | |
| 1 | 2 | Classroom 257 | N/A | Wood Floor | | Non Suspect ACM | 780 | SF | 0 | SF | | | | | | | | N/A | N/A | N/A | |
| 1 | 2 | Classroom 257 | N/A | Plaster Ceiling | | NAD | 780 | SF | 0 | SF | | | | | | | | N/A | N/A | N/A | |
| 1 | 2 | Classroom 257 | N/A | Plaster Walls | | NAD | 1568 | SF | 0 | SF | | | | | | | | N/A | N/A | N/A | |

7020 Olney HS (ASPIRA) 2015 2016 AHERA Three-Year Report.xls

| School District of Philadelphia Aspira Olney Charter High School 100 E. Duncannon Street, Philadelphia, PA 19120 ULCS# 7029 Year Built: 1931 | | | AHERA Three-Year Reinspection 2015-2016 Room by Room Location Log Report | | | | | | | | | | | Reinspection Date: December 13, 2015 Building Inspector: James Madden Number: 030867 Management Planner: Megan Vala Number: 740728 | | | | | | | | | |
|--|-----------------------|---|---|-----------------|----------------------------|--------------------------|---|--------------------|----------|------------------|----------|------------------------|----------------------------|--|--|--------------------|----------------------|-----|--|--|--|--|--|
| | | | | | | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | | | | | | |
| E l e m e n t | F l o o r | On Site Room Name | | System Affected | Material Description | HID# | Confirmed/Assumed/NAD/ Non Suspect ACM | Amount of Material | SF LF EA | Amount of Damage | SF LF EA | Color required for VAT | Comments/Description/Notes | Attic/ Crawl Space Ranking | Damage Potential (DP) | Newly Friable (NF) | Response Action (RA) | | | | | | |
| | | | | | | | | | | | | | | | | | | | | | | | |
| 1 | 2 | Classroom 257 | T | | Pipe Insulation 2-6 inch | 7020/01/02/35 | Confirmed | 120 | LF | 0 | LF | | | | 1 | No | 1/D | | | | | | |
| 1 | 2 | Classroom 257 | T | | Pipe Fitting Insulation | 7020/01/02/66 | Assumed | 18 | EA | 0 | EA | | | | 1 | No | 1/D | | | | | | |
| 1 | 2 | Classroom 257 | N/A | | Fiberglass Pipe Insulation | | Non Suspect ACM | 28 | LF | 0 | LF | | | | N/A | N/A | N/A | | | | | | |
| 1 | 2 | Classroom 257 | M | | Blackboard Glue Dots | 7020/01/02/BATTA/AH/2600 | Assumed | 200 | SF | 0 | SF | | | | 1 | No | 1/D | | | | | | |
| 2 over from Stairwell - Inspector did not list - please verify | | | | | | | | | | | | | | | | | | | | | | | |
| 1 | 2 | Dean's Office | X | | X | | X | X | X | X | X | | | | X | X | X | | | | | | |
| 1 | 2 | Storage Room 260 | X | | X | | X | X | X | X | X | | | | X | X | X | | | | | | |
| 1 | 2 | Storage Room 259 | X | | X | | X | X | X | X | X | | | | X | X | X | | | | | | |
| 1 | 2 | Office 261 | N/A | | Wood Floor | | Non Suspect ACM | 390 | SF | 0 | SF | | | | N/A | N/A | N/A | | | | | | |
| 1 | 2 | Office 261 | N/A | | Plaster Ceiling | | NAD | 390 | SF | 0 | SF | | | | N/A | N/A | N/A | | | | | | |
| 1 | 2 | Office 261 | N/A | | Plaster Walls | | NAD | 1148 | SF | 0 | SF | | | | N/A | N/A | N/A | | | | | | |
| 1 | 2 | Office 261 | N/A | | Fiberglass Pipe Insulation | | Non Suspect ACM | 12 | LF | 0 | LF | | | | N/A | N/A | N/A | | | | | | |
| 1 | 2 | Office 261 | M | | Blackboard Glue Dots | 7020/01/02/BATTA/AH/2600 | Assumed | 80 | SF | 0 | SF | | | | 1 | No | 1/D | | | | | | |
| 1 | 2 | Office 263 | N/A | | Wood Floor | | Non Suspect ACM | 240 | SF | 0 | SF | | | | N/A | N/A | N/A | | | | | | |
| 1 | 2 | Office 263 | N/A | | Plaster Ceiling | | NAD | 240 | SF | 0 | SF | | | | N/A | N/A | N/A | | | | | | |
| 1 | 2 | Office 263 | N/A | | Plaster Walls | | NAD | 600 | SF | 0 | SF | | | | N/A | N/A | N/A | | | | | | |
| 1 | 2 | Office 263 | T | | Pipe Insulation 2-6 inch | 7020/01/02/35 | Confirmed | 14 | LF | 2 | LF | | | | Small Holes 2 Cut unencapsulated ends | 1 | Yes | 5/A | | | | | |
| 1 | 2 | Classroom 265 | N/A | | Wood Floor | | Non Suspect ACM | 816 | SF | 0 | SF | | | | N/A | N/A | N/A | | | | | | |
| 1 | 2 | Classroom 265 | N/A | | Plaster Ceiling | | NAD | 816 | SF | 0 | SF | | | | N/A | N/A | N/A | | | | | | |
| 1 | 2 | Classroom 265 | N/A | | Plaster Walls | | NAD | 1624 | SF | 0 | SF | | | | N/A | N/A | N/A | | | | | | |
| 1 | 2 | Classroom 265 | T | | Pipe Insulation 2-6 inch | 7020/01/02/35 | Confirmed | 125 | LF | 0 | LF | | | | 1 | No | 1/D | | | | | | |
| 1 | 2 | Classroom 265 | T | | Pipe Fitting Insulation | 7020/01/02/66 | Assumed | 26 | EA | 0 | EA | | | | 1 | No | 1/D | | | | | | |
| 1 | 2 | Classroom 265 | N/A | | Fiberglass Pipe Insulation | | Non Suspect ACM | 40 | LF | 3 | LF | | | | N/A | N/A | N/A | | | | | | |
| 1 | 2 | Classroom 265 | M | | Blackboard Glue Dots | 7020/01/02/BATTA/AH/2600 | Assumed | 144 | SF | 0 | SF | | | | 1 | No | 1/D | | | | | | |
| 1 | 2 | Storage Room 267 | N/A | | Wood Floor | | Non Suspect ACM | 156 | SF | 0 | SF | | | | N/A | N/A | N/A | | | | | | |
| 1 | 2 | Storage Room 267 | N/A | | Plaster Ceiling | | NAD | 156 | SF | 0 | SF | | | | N/A | N/A | N/A | | | | | | |
| 1 | 2 | Storage Room 267 | N/A | | Plaster Walls | | NAD | 896 | SF | 0 | SF | | | | N/A | N/A | N/A | | | | | | |
| 1 | 2 | Storage Room 267 | T | | Pipe Insulation 2-6 inch | 7020/01/02/35 | Confirmed | 34 | LF | 0 | LF | | | | 1 | No | 1/D | | | | | | |
| 1 | 2 | Storage Room 267 | T | | Pipe Fitting Insulation | 7020/01/02/66 | Assumed | 4 | EA | 0 | EA | | | | 1 | No | 1/D | | | | | | |
| 1 | 2 | Storage Room 267 | T | | Pipe Insulation > 6 inch | 7020/01/02/36 | Confirmed | 20 | LF | 0 | LF | | | | 1 | No | 1/D | | | | | | |
| 1 | 2 | Hallway from Classrooms 247 to 265 | N/A | | Cement Floor | | Non Suspect ACM | 2040 | SF | 0 | SF | | | | N/A | N/A | N/A | | | | | | |
| 1 | 2 | Hallway from Classrooms 247 to 265 | N/A | | Plaster Walls | | NAD | 3822 | SF | 0 | SF | | | | N/A | N/A | N/A | | | | | | |
| 1 | 2 | Hallway from Classrooms 247 to 265 | N/A | | Marble Walls | | Non Suspect ACM | 1274 | SF | 0 | SF | | | | N/A | N/A | N/A | | | | | | |
| 1 | 2 | Hallway from Classrooms 247 to 265 | N/A | | Ceiling Tile 2' x 4' | | NAD | 2040 | SF | 0 | SF | | | | N/A | N/A | N/A | | | | | | |
| 1 | 2 | Classroom 269 | N/A | | Wood Floor | | Non Suspect ACM | 720 | SF | 0 | SF | | | | N/A | N/A | N/A | | | | | | |
| 1 | 2 | Classroom 269 | N/A | | Plaster Ceiling | | NAD | 720 | SF | 0 | SF | | | | N/A | N/A | N/A | | | | | | |
| 1 | 2 | Classroom 269 | N/A | | Plaster Walls | | NAD | 1296 | SF | 0 | SF | | | | N/A | N/A | N/A | | | | | | |
| 1 | 2 | Classroom 269 | N/A | | Fiberglass Pipe Insulation | | Non Suspect ACM | 40 | LF | 0 | LF | | | | N/A | N/A | N/A | | | | | | |
| 1 | 2 | Classroom 269 | M | | Blackboard Glue Dots | 7020/01/02/BATTA/AH/2600 | Assumed | 64 | SF | 0 | SF | | | | 1 | No | 1/D | | | | | | |
| 1 | 2 | Classroom 269 | T | | Pipe Insulation > 6 inch | 7020/01/02/36 | Confirmed | X | LF | 0 | LF | | | | No material? - Inspector please verify | 1 | No | 1/D | | | | | |
| 1 | 2 | Classroom 271 | N/A | | Wood Floor | | Non Suspect ACM | 750 | SF | 0 | SF | | | | N/A | N/A | N/A | | | | | | |
| 1 | 2 | Classroom 271 | N/A | | Ceiling Tile 2' x 4' | | NAD | 750 | SF | 0 | SF | | | | N/A | N/A | N/A | | | | | | |
| 1 | 2 | Classroom 271 | N/A | | Plaster Walls | | NAD | 1320 | SF | 0 | SF | | | | N/A | N/A | N/A | | | | | | |
| 1 | 2 | Classroom 271 | N/A | | Fiberglass Pipe Insulation | | Non Suspect ACM | 30 | LF | 0 | LF | | | | N/A | N/A | N/A | | | | | | |
| 1 | 2 | Classroom 271 | M | | Blackboard Glue Dots | 7020/01/02/BATTA/AH/2600 | Assumed | X | SF | 0 | SF | | | | No material? - Inspector please verify | 1 | No | 1/D | | | | | |
| 1 | 2 | Classroom 271 | T | | Pipe Insulation > 6 inch | 7020/01/02/36 | Confirmed | X | LF | 0 | LF | | | | No material? - Inspector please verify | 1 | No | 1/D | | | | | |
| 1 | 2 | Staff Lounge 273 | N/A | | Wood Floor | | Non Suspect ACM | 720 | SF | 0 | SF | | | | N/A | N/A | N/A | | | | | | |
| 1 | 2 | Staff Lounge 273 | N/A | | Ceiling Tile 2' x 4' | | NAD | 720 | SF | 0 | SF | | | | N/A | N/A | N/A | | | | | | |
| 1 | 2 | Staff Lounge 273 | N/A | | Plaster Walls | | NAD | 1296 | SF | 0 | SF | | | | N/A | N/A | N/A | | | | | | |
| 1 | 2 | Staff Lounge 273 | N/A | | Fiberglass Pipe Insulation | | Non Suspect ACM | 32 | LF | 0 | LF | | | | N/A | N/A | N/A | | | | | | |
| 1 | 2 | Women's Restroom Lounge at Main Entrance Stairwell | N/A | | Wood Floor | | Non Suspect ACM | 364 | SF | 0 | SF | | | | N/A | N/A | N/A | | | | | | |
| 1 | 2 | Women's Restroom Lounge at Main Entrance Stairwell | N/A | | Ceiling Tile 2' x 4' | | NAD | 364 | SF | 0 | SF | | | | N/A | N/A | N/A | | | | | | |
| 1 | 2 | Women's Restroom Lounge at Main Entrance Stairwell | N/A | | Plaster Walls | | NAD | 1120 | SF | 0 | SF | | | | N/A | N/A | N/A | | | | | | |
| 1 | 2 | Women's Restroom Lounge at Main Entrance Stairwell | T | | Pipe Insulation 2-6 inch | 7020/01/02/35 | Confirmed | 15 | LF | 0 | LF | | | | 1 | No | 1/D | | | | | | |
| 1 | 2 | Women's Restroom Lounge at Main Entrance Stairwell | T | | Pipe Fitting Insulation | 7020/01/02/66 | Assumed | 6 | EA | 0 | EA | | | | 1 | No | 1/D | | | | | | |
| 1 | 2 | Storage Room in Women's Restroom at Main Entrance Stairwell | N/A | | Wood Floor | | Non Suspect ACM | 36 | SF | 0 | SF | | | | N/A | N/A | N/A | | | | | | |
| 1 | 2 | Storage Room in Women's Restroom at Main Entrance Stairwell | N/A | | Ceiling Tile 2' x 4' | | NAD | 36 | SF | 0 | SF | | | | 4SF Flaking Paint | N/A | N/A | N/A | | | | | |
| 1 | 2 | Storage Room in Women's Restroom at Main Entrance Stairwell | N/A | | Plaster Walls | | NAD | 336 | SF | 0 | SF | | | | N/A | N/A | N/A | | | | | | |
| 1 | 2 | Women's Restroom at Main Entrance Stairwell | N/A | | Wood Floor | | Non Suspect ACM | 72 | SF | 0 | SF | | | | N/A | N/A | N/A | | | | | | |
| 1 | 2 | Women's Restroom at Main Entrance Stairwell | N/A | | Ceiling Tile 2' x 4' | | NAD | 72 | SF | 0 | SF | | | | N/A | N/A | N/A | | | | | | |
| 1 | 2 | Women's Restroom at Main Entrance Stairwell | N/A | | Plaster Walls | | NAD | 476 | SF | 0 | SF | | | | N/A | N/A | N/A | | | | | | |
| 1 | 2 | Women's Restroom at Main Entrance Stairwell | T | | Pipe Insulation 2-6 inch | 7020/01/02/35 | Confirmed | 64 | LF | 0 | LF | | | | 1 | No | 1/D | | | | | | |
| 1 | 2 | Women's Restroom at Main Entrance Stairwell | T | | Pipe Fitting Insulation | 7020/01/02/66 | Assumed | 16 | EA | 2 | EA | | | | Cracked Fittings | 1 | Yes | 5/A | | | | | |
| 1 | 2 | Storage across from Women's Restroom at Main Entrance Stairwell | N/A | | Cement Floor | | Non Suspect ACM | 24 | SF | 0 | SF | | | | 2nd Door to the Right of Wall of Fame Sign | N/A | N/A | N/A | | | | | |
| 1 | 2 | Storage across from Women's Restroom at Main Entrance Stairwell | N/A | | Plaster Ceiling | | NAD | 24 | SF | 0 | SF | | | | 2nd Door to the Right of Wall of Fame Sign | N/A | N/A | N/A | | | | | |
| 1 | 2 | Storage across from Women's Restroom at Main Entrance Stairwell | N/A | | Plaster Walls | | NAD | 160 | SF | 0 | SF | | | | 2nd Door to the Right of Wall of Fame Sign | N/A | N/A | N/A | | | | | |
| 1 | 2 | Storage across from Women's Restroom at Main Entrance Stairwell | N/A | | Cement Floor | | Non Suspect ACM | 264 | SF | 0 | SF | | | | Right of Wall of Fame Sign | N/A | N/A | N/A | | | | | |

7020 Olney HS (ASPIRA) 2015 2016 AHERA Three-Year Report.xls

| School District of Philadelphia Aspira Olney Charter High School 100 E. Duncannon Street, Philadelphia, PA 19120 ULCS# 7029 Year Built: 1931 | | | AHERA Three-Year Reinspection 2015-2016 Room by Room Location Log Report | | | | | | | | | Reinspection Date: December 13, 2015 Building Inspector: James Madden Number: 030867 Management Planner: Megan Vala Number: 740728 | | | | | | | |
|--|-----------------------|---|---|----------------------------|--------------------------|---|-----------------------|-------------|---------------------|-------------|------------------------------|--|----------------------------------|-----------------------------|--------------------------|-------------------------|--|--|--|
| E l e m e n t | F l o o r | | | | | | | | | | | | | | | | | | |
| On Site Room Name | | | System Affected | Material Description | HID# | Confirmed/Assumed/NAD/ Non Suspect ACM | Amount of Material | SF LF EA | Amount of Damage | SF LF EA | Color required for VAT | Comments/Description/Notes | Attic/ Crawl Space Ranking | Damage Potential (DP) | Newly Friable (NF) | Response Action (RA) | | | |
| 1 | 2 | Storage across from Women's Restroom at Main Entrance Stairwell | N/A | Plaster Ceiling | | NAD | 264 | SF | 0 | SF | | Right of Wall of Fame Sign | | N/A | N/A | N/A | | | |
| 1 | 2 | Storage across from Women's Restroom at Main Entrance Stairwell | N/A | Plaster Walls | | NAD | 544 | SF | 0 | SF | | Right of Wall of Fame Sign | | N/A | N/A | N/A | | | |
| 1 | 2 | Storage across from Main Entrance Stairwell | N/A | Cement Floor | | Non Suspect ACM | 264 | SF | 0 | SF | | Left of Wall of Fame Sign | | N/A | N/A | N/A | | | |
| 1 | 2 | Storage across from Main Entrance Stairwell | N/A | Plaster Ceiling | | NAD | 264 | SF | 0 | SF | | Left of Wall of Fame Sign | | N/A | N/A | N/A | | | |
| 1 | 2 | Storage across from Main Entrance Stairwell | N/A | Plaster Walls | | NAD | 544 | SF | 0 | SF | | Left of Wall of Fame Sign | | N/A | N/A | N/A | | | |
| 1 | 2 | Projector Room in Auditorium at the top of Balcony | N/A | Cement Floor | | Non Suspect ACM | 84 | SF | 0 | SF | | | | N/A | N/A | N/A | | | |
| 1 | 2 | Projector Room in Auditorium at the top of Balcony | N/A | Plaster Ceiling | | NAD | 84 | SF | 0 | SF | | | | N/A | N/A | N/A | | | |
| 1 | 2 | Projector Room in Auditorium at the top of Balcony | N/A | Plaster Walls | | NAD | 304 | SF | 0 | SF | | | | N/A | N/A | N/A | | | |
| 1 | 2 | Projector Room in Auditorium at the top of Balcony | N/A | Wood Floor | | Non Suspect ACM | 4400 | SF | 0 | SF | | | | N/A | N/A | N/A | | | |
| 1 | 2 | Projector Room in Auditorium at the top of Balcony | N/A | Plaster Ceiling | | NAD | 4400 | SF | 60 | SF | | 150sf Peeling Paint | | N/A | N/A | N/A | | | |
| 1 | 2 | Projector Room in Auditorium at the top of Balcony | N/A | Plaster Walls | | NAD | 5940 | SF | 130 | SF | | 130 peeling paint | | N/A | N/A | N/A | | | |
| 1 | 2 | Storage across from Main Entrance Stairwell by Main Office | N/A | Cement Floor | | Non Suspect ACM | 264 | SF | 0 | SF | | 2nd Door to the Left of Wall of Fame Sign | | N/A | N/A | N/A | | | |
| 1 | 2 | Storage across from Main Entrance Stairwell by Main Office | N/A | Plaster Ceiling | | NAD | 264 | SF | 0 | SF | | 2nd Door to the Left of Wall of Fame Sign | | N/A | N/A | N/A | | | |
| 1 | 2 | Storage across from Main Entrance Stairwell by Main Office | N/A | Plaster Walls | | NAD | 544 | SF | 0 | SF | | 2nd Door to the Left of Wall of Fame Sign | | N/A | N/A | N/A | | | |
| 1 | 2 | Main Office | M | Floor Tile VAT 12" x 12" | 7020/01/02/A5 | Assumed | 1104 | SF | 0 | SF | Tan | | | 1 | No | 1/D | | | |
| 1 | 2 | Main Office | N/A | Ceiling Tile 2' x 4' | | NAD | 1104 | SF | 0 | SF | | | | N/A | N/A | N/A | | | |
| 1 | 2 | Main Office | N/A | Plaster Walls | | NAD | 1680 | SF | 0 | SF | | | | N/A | N/A | N/A | | | |
| 1 | 2 | Main Office | T | Pipe Insulation 2-6 inch | 7020/01/02/35 | Confirmed | 12 | LF | 1 | LF | | Most Pipes Uninsulated | | 1 | Yes | 5/A | | | |
| 1 | 2 | Main Office | T | Pipe Fitting Insulation | 7020/01/02/66 | Assumed | 2 | EA | 0 | EA | | | | 1 | No | 1/D | | | |
| 1 | 2 | Main Office Storage Room | M | Floor Tile VAT 12" x 12" | 7020/01/02/A5 | Assumed | 63 | SF | 0 | SF | Tan | oppsite side of smaller Offices | | 1 | No | 1/D | | | |
| 1 | 2 | Main Office Storage Room | N/A | Plaster Ceiling | | NAD | 63 | SF | 0 | SF | | oppsite side of smaller Offices | | N/A | N/A | N/A | | | |
| 1 | 2 | Main Office Storage Room | N/A | Plaster Walls | | NAD | 448 | SF | 0 | SF | | oppsite side of smaller Offices | | N/A | N/A | N/A | | | |
| 1 | 2 | Main Office Storage Room | T | Pipe Insulation 2-6 inch | 7020/01/02/35 | Confirmed | 58 | LF | 0 | LF | | oppsite side of smaller Offices | | 1 | No | 1/D | | | |
| 1 | 2 | Main Office Storage Room | T | Pipe Fitting Insulation | 7020/01/02/66 | Assumed | 10 | EA | 0 | EA | | oppsite side of smaller Offices | | 1 | No | 1/D | | | |
| 1 | 2 | Main Office Storage Room attached to Larger Storage Room | M | Floor Tile VAT 12" x 12" | 7020/01/02/A5 | Assumed | 33 | SF | 0 | SF | Tan | | | 1 | No | 1/D | | | |
| 1 | 2 | Main Office Storage Room attached to Larger Storage Room | N/A | Plaster Ceiling | | NAD | 33 | SF | 0 | SF | | | | N/A | N/A | N/A | | | |
| 1 | 2 | Main Office Storage Room attached to Larger Storage Room | N/A | Plaster Walls | | NAD | 392 | SF | 0 | SF | | | | N/A | N/A | N/A | | | |
| 1 | 2 | Main Office Storage Room attached to Larger Storage Room | T | Pipe Insulation 2-6 inch | 7020/01/02/35 | Confirmed | 48 | LF | 2 | LF | | Large Holes | | 1 | Yes | 5/A | | | |
| 1 | 2 | Main Office Storage Room attached to Larger Storage Room | T | Pipe Fitting Insulation | 7020/01/02/66 | Assumed | 8 | EA | 0 | EA | | | | 1 | No | 1/D | | | |
| 1 | 2 | Principal's Office | M | Floor Tile VAT 12" x 12" | 7020/01/02/A5 | Assumed | 336 | SF | 0 | SF | White | | | 1 | No | 1/D | | | |
| 1 | 2 | Principal's Office | N/A | Ceiling Tile 2' x 2' | | NAD | 336 | SF | 0 | SF | | | | N/A | N/A | N/A | | | |
| 1 | 2 | Principal's Office | N/A | Plaster Walls | | NAD | 912 | SF | 0 | SF | | | | N/A | N/A | N/A | | | |
| 1 | 2 | Principal's Office Closet | M | Floor Tile VAT 12" x 12" | 7020/01/02/A5 | Assumed | 18 | SF | 0 | SF | White | | | 1 | No | 1/D | | | |
| 1 | 2 | Principal's Office Closet | N/A | Plaster Ceiling | | NAD | 18 | SF | 0 | SF | | | | N/A | N/A | N/A | | | |
| 1 | 2 | Principal's Office Closet | N/A | Plaster Walls | | NAD | 144 | SF | 0 | SF | | | | N/A | N/A | N/A | | | |
| 1 | 2 | Principal's Office Restroom | M | Floor Tile VAT 12" x 12" | 7020/01/02/A5 | Assumed | 20 | SF | 0 | SF | Tan | | | 1 | No | 1/D | | | |
| 1 | 2 | Principal's Office Restroom | N/A | Plaster Ceiling | | NAD | 20 | SF | 0 | SF | | | | N/A | N/A | N/A | | | |
| 1 | 2 | Principal's Office Restroom | N/A | Plaster Walls | | NAD | 252 | SF | 0 | SF | | | | N/A | N/A | N/A | | | |
| 1 | 2 | Principal's Office Conference Room | M | Floor Tile VAT 12" x 12" | 7020/01/02/A5 | Assumed | 300 | SF | 0 | SF | Blue | | | 1 | No | 1/D | | | |
| 1 | 2 | Principal's Office Conference Room | N/A | Ceiling Tile 2' x 4' | | NAD | 300 | SF | 0 | SF | | | | N/A | N/A | N/A | | | |
| 1 | 2 | Principal's Office Conference Room | N/A | Plaster Walls | | NAD | 840 | SF | 0 | SF | | | | N/A | N/A | N/A | | | |
| 1 | 2 | Principal's Office Conference Room | T | Pipe Insulation 2-6 inch | 7020/01/02/35 | Confirmed | 8 | LF | 0 | LF | | | | 1 | No | 1/D | | | |
| 1 | 2 | Conference 207 | M | Floor Tile VAT 12" x 12" | 7020/01/02/A5 | Assumed | 390 | SF | 0 | SF | Blue | | | 1 | No | 1/D | | | |
| 1 | 2 | Conference 207 | N/A | Ceiling Tile 2' x 4' | | NAD | 390 | SF | 0 | SF | | | | N/A | N/A | N/A | | | |
| 1 | 2 | Conference 207 | N/A | Plaster Walls | | NAD | 984 | SF | 0 | SF | | | | N/A | N/A | N/A | | | |
| 1 | 2 | Conference 207 | T | Pipe Insulation 2-6 inch | 7020/01/02/35 | Confirmed | 6 | LF | 0 | LF | | | | 1 | No | 1/D | | | |
| 1 | 2 | IT Closet Room 205 near Principal's Office | X | X | | X | X | X | X | X | | No Access | | X | X | X | | | |
| 1 | 2 | Office 209 | N/A | Wood Floor | | Non Suspect ACM | 504 | SF | 0 | SF | | | | N/A | N/A | N/A | | | |
| 1 | 2 | Office 209 | N/A | Ceiling Tile 2' x 4' | | NAD | 504 | SF | 0 | SF | | | | N/A | N/A | N/A | | | |
| 1 | 2 | Office 209 | N/A | Plaster Walls | | NAD | 1080 | SF | 0 | SF | | | | N/A | N/A | N/A | | | |
| 1 | 2 | Office 209 | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 12 | LF | 0 | LF | | | | N/A | N/A | N/A | | | |
| 1 | 2 | Office 209 | M | Blackboard Glue Dots | 7020/01/02/BATTA/AH/2600 | Assumed | 32 | SF | 0 | SF | | | | 1 | No | 1/D | | | |
| 1 | 2 | Boy's Restroom | N/A | Plaster Ceiling | | NAD | 546 | SF | 0 | SF | | Unknown location - inspector please verify | | N/A | N/A | N/A | | | |
| 1 | 2 | Boy's Restroom | N/A | Plaster Walls | | NAD | 1316 | SF | 0 | SF | | Unknown location - inspector please verify | | N/A | N/A | N/A | | | |
| 1 | 2 | Boy's Restroom | N/A | Cement Floor | | Non Suspect ACM | 546 | SF | 0 | SF | | Unknown location - inspector please verify | | N/A | N/A | N/A | | | |
| 1 | 2 | Boy's Restroom | T | Pipe Insulation 2-6 inch | 7020/01/02/35 | Confirmed | 38 | LF | 0 | LF | | | | 1 | No | 1/D | | | |
| 1 | 2 | Boy's Restroom | T | Pipe Fitting Insulation | 7020/01/02/66 | Assumed | 8 | EA | 0 | EA | | | | 1 | No | 1/D | | | |
| 1 | 2 | Custodial Closet next to Boy's Restroom | N/A | Plaster Ceiling | | NAD | 30 | SF | 0 | SF | | Unknown location - inspector please verify | | N/A | N/A | N/A | | | |
| 1 | 2 | Custodial Closet next to Boy's Restroom | N/A | Plaster Walls | | NAD | 220 | SF | 0 | SF | | Unknown location - inspector please verify | | N/A | N/A | N/A | | | |
| 1 | 2 | Custodial Closet next to Boy's Restroom | N/A | Cement Floor | | Non Suspect ACM | 30 | SF | 0 | SF | | Unknown location - inspector please verify | | N/A | N/A | N/A | | | |
| 1 | 2 | Custodial Closet next to Boy's Restroom | T | Pipe Insulation 2-6 inch | 7020/01/02/35 | Confirmed | 16 | LF | 0 | LF | | Cracks and Holes - Unknown location - inspector please verify | | 1 | No | 1/D | | | |
| 1 | 2 | Custodial Closet next to Boy's Restroom | T | Pipe Fitting Insulation | 7020/01/02/66 | Assumed | X | EA | 0 | EA | | | | 1 | No | 1/D | | | |
| 1 | 2 | Girl's Restroom | X | X | | X | X | X | X | X | | Unknown location - not listed - Inspector please verify | | X | X | X | | | |

7020 Olney HS (ASPIRA) 2015 2016 AHERA Three-Year Report.xls

| School District of Philadelphia | | | AHERA Three-Year Reinspection 2015-2016 | | | | | | | | | | | | | Reinspection Date: December 13, 2015 | | | | |
|---|-----------------------|--|---|----------------------------|--------------------------|---|-----------------------|----|----|----|---------------------|----|----|----|------------------------------|--------------------------------------|----------------------------------|-----------------------------|--------------------------|-------------------------|
| Aspira Olney Charter High School | | | Room by Room Location Log Report | | | | | | | | | | | | | Building Inspector: James Madden | | | | |
| 100 E. Duncannon Street, Philadelphia, PA 19120 | | | | | | | | | | | | | | | | Number: 030867 | | | | |
| ULCS# 7029 | | | | | | | | | | | | | | | | Management Planner: Megan Vala | | | | |
| Year Built: 1931 | | | | | | | | | | | | | | | | Number: 740728 | | | | |
| E l e m e n t | F l o o r | On Site Room Name | System Affected | Material Description | HID# | Confirmed/Assumed/NAD/ Non Suspect ACM | Amount of Material | SF | LF | EA | Amount of Damage | SF | LF | EA | Color required for VAT | Comments/Description/Notes | Attic/ Crawl Space Ranking | Damage Potential (DP) | Newly Friable (NF) | Response Action (RA) |
| | | | | | | | | | | | | | | | | | | | | |
| 1 | 2 | Hallway from Classroom 269 to Office 209 | N/A | Cement Floor | | Non Suspect ACM | 3240 | SF | | | 0 | SF | | | | | | N/A | N/A | N/A |
| 1 | 2 | Hallway from Classroom 269 to Office 209 | N/A | Plaster Walls | | NAD | 7896 | SF | | | 0 | SF | | | | | | N/A | N/A | N/A |
| 1 | 2 | Hallway from Classroom 269 to Office 209 | N/A | Ceiling Tile 2' x 4' | | NAD | 3240 | SF | | | 0 | SF | | | | | | N/A | N/A | N/A |
| 1 | 2 | Hallway from Classroom 269 to Office 209 | T | Pipe Insulation 2-6 inch | 7020/01/02/35 | Confirmed | 20 | LF | | | 0 | LF | | | | | | 1 | No | 1/D |
| 1 | 2 | Hallway from Classroom 269 to Office 209 | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 130 | LF | | | 0 | LF | | | | | | N/A | N/A | N/A |
| 1 | 3 | Classroom 349 | N/A | Wood Floor | | Non Suspect ACM | 1008 | SF | | | 0 | SF | | | | | | N/A | N/A | N/A |
| 1 | 3 | Classroom 349 | N/A | Plaster Walls | | NAD | 1848 | SF | | | 0 | SF | | | | | | N/A | N/A | N/A |
| 1 | 3 | Classroom 349 | N/A | Ceiling Tile 2' x 4' | | NAD | 1008 | SF | | | 0 | SF | | | | | | N/A | N/A | N/A |
| 1 | 3 | Classroom 349 | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 56 | LF | | | 0 | LF | | | | | | N/A | N/A | N/A |
| 1 | 3 | Classroom 349 | M | Blackboard Glue Dots | 7020/01/03/BATTA/AH/2600 | Assumed | 64 | SF | | | 0 | SF | | | | | | 1 | No | 1/D |
| 1 | 3 | Classroom 349 | M | Transite Sink | 7020/01/03/47 | Assumed | 18 | SF | | | 0 | SF | | | | | | 1 | No | 1/D |
| 1 | 3 | Classroom 349 | M | Transite Lab Tables | 7020/01/03/47 | Assumed | 190 | SF | | | 0 | SF | | | | | | 1 | No | 1/D |
| 1 | 3 | Office 347 | N/A | Wood Floor | | Non Suspect ACM | 384 | SF | | | 0 | SF | | | | | | N/A | N/A | N/A |
| 1 | 3 | Office 347 | N/A | Plaster Walls | | NAD | 1120 | SF | | | 0 | SF | | | | | | N/A | N/A | N/A |
| 1 | 3 | Office 347 | N/A | Plaster Ceiling | | NAD | 384 | SF | | | 0 | SF | | | | | | N/A | N/A | N/A |
| 1 | 3 | Office 347 | T | Pipe Insulation 2-6 inch | 7020/01/03/46 | Confirmed | 42 | LF | | | 0 | LF | | | | | | 1 | No | 1/D |
| 1 | 3 | Office 347 | M | Blackboard Glue Dots | 7020/01/03/BATTA/AH/2600 | Assumed | 128 | SF | | | 0 | SF | | | | | | 1 | No | 1/D |
| 1 | 3 | Office 347 | T | Pipe Fitting Insulation | 7020/01/03/67 | Assumed | 5 | EA | | | 0 | EA | | | | | | 1 | No | 1/D |
| 1 | 3 | Classroom 345 | N/A | Wood Floor | | Non Suspect ACM | 696 | SF | | | 0 | SF | | | | | | N/A | N/A | N/A |
| 1 | 3 | Classroom 345 | N/A | Plaster Walls | | NAD | 1484 | SF | | | 0 | SF | | | | | | N/A | N/A | N/A |
| 1 | 3 | Classroom 345 | N/A | Ceiling Tile 2' x 4' | | NAD | 696 | SF | | | 8 | SF | | | | | | N/A | N/A | N/A |
| 1 | 3 | Classroom 345 | T | Pipe Insulation 2-6 inch | 7020/01/03/46 | Confirmed | 42 | LF | | | 0 | LF | | | | | | 1 | No | 1/D |
| 1 | 3 | Classroom 345 | M | Blackboard Glue Dots | 7020/01/03/BATTA/AH/2600 | Assumed | 64 | SF | | | 0 | SF | | | | | | 1 | No | 1/D |
| 1 | 3 | Classroom 345 | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 14 | LF | | | 0 | LF | | | | | | N/A | N/A | N/A |
| 1 | 3 | Classroom 343 | N/A | Wood Floor | | Non Suspect ACM | 750 | SF | | | 0 | SF | | | | | | N/A | N/A | N/A |
| 1 | 3 | Classroom 343 | N/A | Plaster Walls | | NAD | 1540 | SF | | | 0 | SF | | | | | | N/A | N/A | N/A |
| 1 | 3 | Classroom 343 | N/A | Ceiling Tile 2' x 4' | | NAD | 750 | SF | | | 0 | SF | | | | | | N/A | N/A | N/A |
| 1 | 3 | Classroom 343 | T | Pipe Insulation 2-6 inch | 7020/01/03/46 | Confirmed | 32 | LF | | | 0 | LF | | | | | | 1 | No | 1/D |
| 1 | 3 | Classroom 343 | M | Blackboard Glue Dots | 7020/01/03/BATTA/AH/2600 | Assumed | 80 | SF | | | 0 | SF | | | | | | 1 | No | 1/D |
| 1 | 3 | Classroom 341 | T | Pipe Fitting Insulation | 7020/01/03/67 | Assumed | 8 | EA | | | 0 | EA | | | | | | 1 | No | 1/D |
| 1 | 3 | Classroom 341 | N/A | Wood Floor | | Non Suspect ACM | 720 | SF | | | 0 | SF | | | | | | N/A | N/A | N/A |
| 1 | 3 | Classroom 341 | N/A | Plaster Walls | | NAD | 1512 | SF | | | 0 | SF | | | | | | N/A | N/A | N/A |
| 1 | 3 | Classroom 341 | N/A | Ceiling Tile 2' x 4' | | NAD | 720 | SF | | | 0 | SF | | | | | | N/A | N/A | N/A |
| 1 | 3 | Classroom 341 | T | Pipe Insulation 2-6 inch | 7020/01/03/46 | Confirmed | 56 | LF | | | 2 | LF | | | | Small Holes | | 1 | Yes | 5/A |
| 1 | 3 | Classroom 341 | M | Blackboard Glue Dots | 7020/01/03/BATTA/AH/2600 | Assumed | 180 | SF | | | 0 | SF | | | | | | 1 | No | 1/D |
| 1 | 3 | Classroom 339 | N/A | Wood Floor | | Non Suspect ACM | 750 | SF | | | 0 | SF | | | | | | N/A | N/A | N/A |
| 1 | 3 | Classroom 339 | N/A | Plaster Walls | | NAD | 1540 | SF | | | 0 | SF | | | | | | N/A | N/A | N/A |
| 1 | 3 | Classroom 339 | N/A | Plaster Ceiling | | NAD | 750 | SF | | | 1 | SF | | | | | | N/A | N/A | N/A |
| 1 | 3 | Classroom 339 | M | Blackboard Glue Dots | 7020/01/03/BATTA/AH/2600 | Assumed | 64 | SF | | | 0 | SF | | | | | | 1 | No | 1/D |
| 1 | 3 | Classroom 339 | T | Pipe Insulation 2-6 inch | 7020/01/03/46 | Confirmed | 48 | LF | | | 0 | LF | | | | | | 1 | No | 1/D |
| 1 | 3 | Classroom 339 | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 12 | LF | | | 4 | LF | | | | | | N/A | N/A | N/A |
| 1 | 3 | Classroom 339 | T | Pipe Fitting Insulation | 7020/01/03/67 | Assumed | 3 | EA | | | 0 | EA | | | | | | 1 | No | 1/D |
| 1 | 3 | Classroom 337 | N/A | Wood Floor | | Non Suspect ACM | 720 | SF | | | 0 | SF | | | | | | N/A | N/A | N/A |
| 1 | 3 | Classroom 337 | N/A | Plaster Walls | | NAD | 1512 | SF | | | 0 | SF | | | | | | N/A | N/A | N/A |
| 1 | 3 | Classroom 337 | N/A | Plaster Ceiling | | NAD | 720 | SF | | | 0 | SF | | | | | | N/A | N/A | N/A |
| 1 | 3 | Classroom 337 | M | Blackboard Glue Dots | 7020/01/03/BATTA/AH/2600 | Assumed | 128 | SF | | | 0 | SF | | | | | | 1 | No | 1/D |
| 1 | 3 | Classroom 337 | T | Pipe Insulation 2-6 inch | 7020/01/03/46 | Confirmed | 51 | LF | | | 2 | LF | | | | Cut ends are not encapsulated | | 1 | Yes | 5/A |
| 1 | 3 | Classroom 337 | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 6 | LF | | | 0 | LF | | | | | | N/A | N/A | N/A |
| 1 | 3 | Classroom 337 | T | Pipe Fitting Insulation | 7020/01/03/67 | Assumed | 14 | EA | | | 0 | EA | | | | | | 1 | No | 1/D |
| 1 | 3 | Classroom 335 | N/A | Wood Floor | | Non Suspect ACM | 720 | SF | | | 0 | SF | | | | | | N/A | N/A | N/A |
| 1 | 3 | Classroom 335 | N/A | Plaster Walls | | NAD | 1512 | SF | | | 0 | SF | | | | | | N/A | N/A | N/A |
| 1 | 3 | Classroom 335 | N/A | Ceiling Tile 2' x 4' | | NAD | 720 | SF | | | 0 | SF | | | | | | N/A | N/A | N/A |
| 1 | 3 | Classroom 335 | M | Blackboard Glue Dots | 7020/01/03/BATTA/AH/2600 | Assumed | 128 | SF | | | 0 | SF | | | | | | 1 | No | 1/D |
| 1 | 3 | Classroom 335 | T | Pipe Insulation 2-6 inch | 7020/01/03/46 | Confirmed | 30 | LF | | | 0 | LF | | | | | | 1 | No | 1/D |
| 1 | 3 | Classroom 335 | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 6 | LF | | | 0 | LF | | | | | | N/A | N/A | N/A |
| 1 | 3 | Classroom 333 | N/A | Wood Floor | | Non Suspect ACM | 720 | SF | | | 0 | SF | | | | | | N/A | N/A | N/A |
| 1 | 3 | Classroom 333 | N/A | Plaster Walls | | NAD | 1512 | SF | | | 0 | SF | | | | | | N/A | N/A | N/A |
| 1 | 3 | Classroom 333 | N/A | Ceiling Tile 2' x 4' | | NAD | 720 | SF | | | 0 | SF | | | | | | N/A | N/A | N/A |
| 1 | 3 | Classroom 333 | M | Blackboard Glue Dots | 7020/01/03/BATTA/AH/2600 | Assumed | 164 | SF | | | 0 | SF | | | | | | 1 | No | 1/D |
| 1 | 3 | Classroom 333 | T | Pipe Insulation 2-6 inch | 7020/01/03/46 | Confirmed | 31 | LF | | | 0 | LF | | | | | | 1 | No | 1/D |
| 1 | 3 | Classroom 333 | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 10 | LF | | | 0 | LF | | | | | | N/A | N/A | N/A |
| 1 | 3 | Classroom 331 | N/A | Wood Floor | | Non Suspect ACM | 720 | SF | | | 0 | SF | | | | | | N/A | N/A | N/A |
| 1 | 3 | Classroom 331 | N/A | Plaster Walls | | NAD | 1512 | SF | | | 0 | SF | | | | | | N/A | N/A | N/A |
| 1 | 3 | Classroom 331 | N/A | Ceiling Tile 2' x 4' | | NAD | 720 | SF | | | 0 | SF | | | | | | N/A | N/A | N/A |
| 1 | 3 | Classroom 331 | M | Blackboard Glue Dots | 7020/01/03/BATTA/AH/2600 | Assumed | 120 | SF | | | 0 | SF | | | | | | 1 | No | 1/D |
| 1 | 3 | Classroom 331 | T | Pipe Insulation 2-6 inch | 7020/01/03/46 | Confirmed | 21 | LF | | | 0 | LF | | | | | | 1 | No | 1/D |
| 1 | 3 | Classroom 331 | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 24 | LF | | | 0 | LF | | | | | | N/A | N/A | N/A |
| 1 | 3 | Classroom 331 | T | Pipe Fitting Insulation | 7020/01/03/67 | Assumed | 2 | EA | | | 0 | EA | | | | | | 1 | No | 1/D |
| 1 | 3 | Custodial Closet next to Classroom 339 | N/A | Plaster Walls | | NAD | 532 | SF | | | 0 | SF | | | | | | N/A | N/A | N/A |
| 1 | 3 | Custodial Closet next to Classroom 339 | N/A | Wood Floor | | Non Suspect ACM | 60 | SF | | | 0 | SF | | | | | | N/A | N/A | N/A |
| 1 | 3 | Custodial Closet next to Classroom 339 | N/A | Plaster Ceiling | | NAD | 60 | SF | | | 0 | SF | | | | | | N/A | N/A | N/A |
| 1 | 3 | Custodial Closet next to Classroom 339 | T | Pipe Insulation 2-6 inch | 7020/01/03/46 | Confirmed | 30 | LF | | | 0 | LF | | | | | | 1 | No | 1/D |
| 1 | 3 | Custodial Closet next to Classroom 339 | T | Pipe Fitting Insulation | 7020/01/03/67 | Assumed | 2 | EA | | | 0 | EA | | | | | | 1 | No | 1/D |

7020 Olney HS (ASPIRA) 2015 2016 AHERA Three-Year Report.xls

| School District of Philadelphia Aspira Olney Charter High School 100 E. Duncannon Street, Philadelphia, PA 19120 ULCS# 7029 Year Built: 1931 | | | AHERA Three-Year Reinspection 2015-2016 Room by Room Location Log Report | | | | | | | | | | Reinspection Date: December 13, 2015 Building Inspector: James Madden Number: 030867 Management Planner: Megan Vala Number: 740728 | | | | | |
|--|-----------------------|--|---|----------------------------|--------------------------|---|-----------------------|-------------|---------------------|-------------|------------------------------|--|--|-----------------------------|--------------------------|-------------------------|--|--|
| E l e m e n t | F l o o r | On Site Room Name | System Affected | Material Description | HID# | Confirmed/Assumed/NAD/ Non Suspect ACM | Amount of Material | SF LF EA | Amount of Damage | SF LF EA | Color required for VAT | Comments/Description/Notes | Attic/ Crawl Space Ranking | Damage Potential (DP) | Newly Friable (NF) | Response Action (RA) | | |
| 1 | 3 | Staff Lounge and Copy Room 341 | N/A | Plaster Ceiling | | NAD | 338 | SF | 0 | SF | | | | N/A | N/A | N/A | | |
| 1 | 3 | Staff Lounge and Copy Room 341 | M | Linoleum | 7020/01/03/LL | Assumed | 338 | SF | 0 | SF | Grey | Painted Grey | | 1 | No | 1/D | | |
| 1 | 3 | Staff Lounge and Copy Room 341 | N/A | Plaster Walls | | NAD | 1092 | SF | 0 | SF | | | | N/A | N/A | N/A | | |
| 1 | 3 | Staff Lounge and Copy Room 341 | T | Pipe Insulation 2-6 inch | 7020/01/03/46 | Confirmed | 33 | LF | 0 | LF | | | | 1 | No | 1/D | | |
| 1 | 3 | Staff Lounge and Copy Room 341 | T | Pipe Fitting Insulation | 7020/01/03/67 | Assumed | 4 | EA | 0 | EA | | | | 1 | No | 1/D | | |
| 1 | 3 | Staff Lounge and Copy Room 341 Restroom | N/A | Plaster Walls | | NAD | 420 | SF | 0 | SF | | | | N/A | N/A | N/A | | |
| 1 | 3 | Staff Lounge and Copy Room 341 Restroom | M | Linoleum | 7020/01/03/LL | Assumed | 44 | SF | 0 | SF | Grey | Painted Grey | | 1 | No | 1/D | | |
| 1 | 3 | Staff Lounge and Copy Room 341 Restroom | N/A | Plaster Ceiling | | NAD | 44 | SF | 5 | SF | | | | N/A | N/A | N/A | | |
| 1 | 3 | Staff Lounge and Copy Room 341 Restroom | T | Pipe Insulation 2-6 inch | 7020/01/03/46 | Confirmed | 86 | LF | 0 | LF | | | | 1 | No | 1/D | | |
| 1 | 3 | Staff Lounge and Copy Room 341 Restroom | T | Pipe Fitting Insulation | 7020/01/03/67 | Assumed | 13 | EA | 0 | EA | | | | 1 | No | 1/D | | |
| 1 | 3 | Classroom 325 | N/A | Wood Floor | | Non Suspect ACM | 840 | SF | 0 | SF | | | | N/A | N/A | N/A | | |
| 1 | 3 | Classroom 325 | N/A | Plaster Walls | | NAD | 1652 | SF | 0 | SF | | | | N/A | N/A | N/A | | |
| 1 | 3 | Classroom 325 | N/A | Plaster Ceiling | | NAD | 840 | SF | 0 | SF | | | | N/A | N/A | N/A | | |
| 1 | 3 | Classroom 325 | M | Blackboard Glue Dots | 7020/01/03/BATTA/AH/2600 | Assumed | 240 | SF | 0 | SF | | | | 1 | No | 1/D | | |
| 1 | 3 | Classroom 325 | T | Pipe Insulation 2-6 inch | 7020/01/03/46 | Confirmed | 40 | LF | 2 | LF | | Small Holes, unencapsulated ends | | 1 | Yes | 5/A | | |
| 1 | 3 | Classroom 325 | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 28 | LF | 0 | LF | | | | N/A | N/A | N/A | | |
| 1 | 3 | Classroom 325 | T | Pipe Fitting Insulation | 7020/01/03/67 | Assumed | 10 | EA | 0 | EA | | | | 1 | No | 1/D | | |
| 1 | 3 | Classroom 323 | N/A | Wood Floor | | Non Suspect ACM | 780 | SF | 0 | SF | | | | N/A | N/A | N/A | | |
| 1 | 3 | Classroom 323 | N/A | Plaster Walls | | NAD | 1568 | SF | 0 | SF | | | | N/A | N/A | N/A | | |
| 1 | 3 | Classroom 323 | N/A | Plaster Ceiling | | NAD | 780 | SF | 10 | SF | | | | N/A | N/A | N/A | | |
| 1 | 3 | Classroom 323 | M | Blackboard Glue Dots | 7020/01/03/BATTA/AH/2600 | Assumed | 128 | SF | 0 | SF | | | | 1 | No | 1/D | | |
| 1 | 3 | Classroom 323 | T | Pipe Insulation 2-6 inch | 7020/01/03/46 | Confirmed | 15 | LF | 0 | LF | | | | 1 | No | 1/D | | |
| 1 | 3 | Classroom 323 | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 20 | LF | 0 | LF | | | | N/A | N/A | N/A | | |
| 1 | 3 | Classroom 323 | T | Pipe Fitting Insulation | 7020/01/03/67 | Assumed | 7 | EA | 0 | EA | | | | 1 | No | 1/D | | |
| 1 | 3 | Custodial Closet next to Girl's Restroom | N/A | Plaster Walls | | NAD | 160 | SF | 0 | SF | | | | N/A | N/A | N/A | | |
| 1 | 3 | Custodial Closet next to Girl's Restroom | N/A | Cement Floor | | Non Suspect ACM | 16 | SF | 0 | SF | | | | N/A | N/A | N/A | | |
| 1 | 3 | Custodial Closet next to Girl's Restroom | N/A | Plaster Ceiling | | NAD | 16 | SF | 0 | SF | | | | N/A | N/A | N/A | | |
| 1 | 3 | Custodial Closet next to Girl's Restroom | T | Pipe Insulation 2-6 inch | 7020/01/03/46 | Confirmed | 20 | LF | 0 | LF | | | | 1 | No | 1/D | | |
| 1 | 3 | Girl's Restroom | N/A | Cement Floor | | Non Suspect ACM | 520 | SF | 0 | SF | | | | N/A | N/A | N/A | | |
| 1 | 3 | Girl's Restroom | N/A | Plaster Ceiling | | NAD | 520 | SF | 0 | SF | | | | N/A | N/A | N/A | | |
| 1 | 3 | Girl's Restroom | T | Pipe Insulation 2-6 inch | 7020/01/03/46 | Confirmed | 67 | LF | 0 | LF | | | | 1 | No | 1/D | | |
| 1 | 3 | Girl's Restroom | T | Pipe Fitting Insulation | 7020/01/03/67 | Assumed | 9 | EA | 2 | EA | | Cracked Fitting | | 1 | Yes | 5/A | | |
| 1 | 3 | Girl's Restroom | N/A | Plaster Walls | | NAD | 1288 | SF | 0 | SF | | | | N/A | N/A | N/A | | |
| 1 | 3 | Classroom 321 | N/A | Wood Floor | | Non Suspect ACM | 720 | SF | 0 | SF | | | | N/A | N/A | N/A | | |
| 1 | 3 | Classroom 321 | N/A | Plaster Walls | | NAD | 1512 | SF | 0 | SF | | | | N/A | N/A | N/A | | |
| 1 | 3 | Classroom 321 | N/A | Plaster Ceiling | | NAD | 720 | SF | 0 | SF | | | | N/A | N/A | N/A | | |
| 1 | 3 | Classroom 321 | M | Blackboard Glue Dots | 7020/01/03/BATTA/AH/2600 | Assumed | 128 | SF | 0 | SF | | | | 1 | No | 1/D | | |
| 1 | 3 | Classroom 321 | T | Pipe Insulation 2-6 inch | 7020/01/03/46 | Confirmed | 68 | LF | 0 | LF | | | | 1 | No | 1/D | | |
| 1 | 3 | Classroom 321 | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 6 | LF | 0 | LF | | | | N/A | N/A | N/A | | |
| 1 | 3 | Classroom 321 | T | Pipe Fitting Insulation | 7020/01/03/67 | Assumed | 10 | EA | 0 | EA | | | | 1 | No | 1/D | | |
| 1 | 3 | Classroom 320 | N/A | Plaster Walls | | NAD | 952 | SF | 0 | SF | | | | N/A | N/A | N/A | | |
| 1 | 3 | Classroom 320 | M | Floor Tile VAT 9" x 9" | 7020/01/03/42 | Confirmed | 696 | SF | 0 | SF | Brown | | | 1 | No | 1/D | | |
| 1 | 3 | Classroom 320 | N/A | Ceiling Tile 2' x 4' | | NAD | 696 | SF | 0 | SF | | | | N/A | N/A | N/A | | |
| 1 | 3 | Classroom 320 | T | Pipe Insulation 2-6 inch | 7020/01/03/46 | Confirmed | 32 | LF | 0 | LF | | | | 1 | No | 1/D | | |
| 1 | 3 | Classroom 320 | T | Pipe Fitting Insulation | 7020/01/03/67 | Assumed | 6 | EA | 0 | EA | | | | 1 | No | 1/D | | |
| 1 | 3 | Classroom 320 | N/A | Brick Wall | | Non Suspect ACM | 320 | SF | 0 | SF | | | | N/A | N/A | N/A | | |
| 1 | 3 | Office 319 | N/A | Wood Floor | | Non Suspect ACM | 270 | SF | 0 | SF | | | | N/A | N/A | N/A | | |
| 1 | 3 | Office 319 | N/A | Plaster Walls | | NAD | 924 | SF | 0 | SF | | | | N/A | N/A | N/A | | |
| 1 | 3 | Office 319 | N/A | Plaster Ceiling | | NAD | 270 | SF | 0 | SF | | | | N/A | N/A | N/A | | |
| 1 | 3 | Office 319 | M | Blackboard Glue Dots | 7020/01/03/BATTA/AH/2600 | Assumed | 80 | SF | 0 | SF | | | | 1 | No | 1/D | | |
| 1 | 3 | Office 319 | T | Pipe Insulation 2-6 inch | 7020/01/03/46 | Confirmed | 82 | LF | 0 | LF | | | | 1 | No | 1/D | | |
| 1 | 3 | Office 319 | T | Pipe Fitting Insulation | 7020/01/03/67 | Assumed | 11 | EA | 0 | EA | | | | 1 | No | 1/D | | |
| 1 | 3 | Closet outside Office 319 | X | X | | X | X | X | X | X | | No Access | | X | X | X | | |
| 1 | 3 | Office 317 | N/A | Wood Floor | | Non Suspect ACM | 270 | SF | 0 | SF | | | | N/A | N/A | N/A | | |
| 1 | 3 | Office 317 | N/A | Plaster Walls | | NAD | 270 | SF | 0 | SF | | | | N/A | N/A | N/A | | |
| 1 | 3 | Office 317 | N/A | Plaster Ceiling | | NAD | 924 | SF | 0 | SF | | | | N/A | N/A | N/A | | |
| 1 | 3 | Office 317 | M | Blackboard Glue Dots | 7020/01/03/BATTA/AH/2600 | Assumed | 270 | SF | 0 | SF | | | | 1 | No | 1/D | | |
| 1 | 3 | Office 317 | T | Pipe Insulation 2-6 inch | 7020/01/03/46 | Confirmed | 46 | SF | 0 | SF | | | | 1 | No | 1/D | | |
| 1 | 3 | Office 317 | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | X | LF | 0 | LF | | No material? - Inspector please verify | | N/A | N/A | N/A | | |
| 1 | 3 | Office 317 | T | Pipe Fitting Insulation | 7020/01/03/67 | Assumed | 6 | LF | 0 | LF | | | | 1 | No | 1/D | | |
| 1 | 3 | Closet outside Office 317 | X | X | | X | X | X | X | X | | No Access | | X | X | X | | |
| 1 | 3 | Classroom 318 | N/A | Plaster Walls | | NAD | 1048 | SF | 0 | SF | | | | N/A | N/A | N/A | | |
| 1 | 3 | Classroom 318 | M | Floor Tile VAT 9" x 9" | 7020/01/03/42 | Confirmed | 667 | SF | 0 | SF | Brown | | | 1 | No | 1/D | | |
| 1 | 3 | Classroom 318 | N/A | Ceiling Tile 2' x 4' | | NAD | 667 | SF | 0 | SF | | | | N/A | N/A | N/A | | |
| 1 | 3 | Classroom 318 | T | Pipe Insulation 2-6 inch | 7020/01/03/46 | Confirmed | 62 | LF | 0 | LF | | | | 1 | No | 1/D | | |
| 1 | 3 | Classroom 318 | T | Pipe Fitting Insulation | 7020/01/03/67 | Assumed | 10 | EA | 0 | EA | | | | 1 | No | 1/D | | |
| 1 | 3 | Classroom 318 | N/A | Brick Wall | | Non Suspect ACM | 200 | SF | 0 | SF | | | | N/A | N/A | N/A | | |
| 1 | 3 | Classroom 318 | M | Blackboard Glue Dots | 7020/01/03/BATTA/AH/2600 | Assumed | 80 | SF | 0 | SF | | | | 1 | No | 1/D | | |
| 1 | 3 | Classroom 315 | N/A | Wood Floor | | Non Suspect ACM | 720 | SF | 0 | SF | | | | N/A | N/A | N/A | | |
| 1 | 3 | Classroom 315 | N/A | Plaster Walls | | NAD | 1512 | SF | 0 | SF | | | | N/A | N/A | N/A | | |
| 1 | 3 | Classroom 315 | N/A | Plaster Ceiling | | NAD | 720 | SF | 0 | SF | | | | N/A | N/A | N/A | | |
| 1 | 3 | Classroom 315 | M | Blackboard Glue Dots | 7020/01/03/BATTA/AH/2600 | Assumed | 164 | SF | 0 | SF | | | | 1 | No | 1/D | | |
| 1 | 3 | Classroom 315 | T | Pipe Insulation 2-6 inch | 7020/01/03/46 | Confirmed | 20 | LF | 0 | LF | | | | 1 | No | 1/D | | |

7020 Olney HS (ASPIRA) 2015 2016 AHERA Three-Year Report.xls

| School District of Philadelphia Aspira Olney Charter High School 100 E. Duncannon Street, Philadelphia, PA 19120 ULCS# 7029 Year Built: 1931 | | | AHERA Three-Year Reinspection 2015-2016 Room by Room Location Log Report | | | | | | | | | | Reinspection Date: December 13, 2015 Building Inspector: James Madden Number: 030867 Management Planner: Megan Vala Number: 740728 | | | | | | | |
|--|-----------------------|--|---|----------------------------|--------------------------|---|-----------------------|-------------|---------------------|-------------|------------------------------|-----------------------------|--|-----------------------------|--------------------------|-------------------------|--|--|--|--|
| E l e m e n t | F l o o r | On Site Room Name | System Affected | Material Description | HID# | Confirmed/Assumed/NAD/ Non Suspect ACM | Amount of Material | SF LF EA | Amount of Damage | SF LF EA | Color required for VAT | Comments/Description/Notes | Attic/ Crawl Space Ranking | Damage Potential (DP) | Newly Friable (NF) | Response Action (RA) | | | | |
| 1 | 3 | Classroom 315 | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 24 | LF | 0 | LF | | | | N/A | N/A | N/A | | | | |
| 1 | 3 | Classroom 315 | T | Pipe Fitting Insulation | 7020/01/03/67 | Assumed | 37 | EA | 0 | EA | | Cracked Fitting | | 1 | No | 1/D | | | | |
| 1 | 3 | Nurse's Office 313 Lobby | N/A | Wood Floor | | Non Suspect ACM | 56 | SF | 0 | SF | | | | N/A | N/A | N/A | | | | |
| 1 | 3 | Nurse's Office 313 Lobby | N/A | Plaster Ceiling | | NAD | 56 | SF | 0 | SF | | | | N/A | N/A | N/A | | | | |
| 1 | 3 | Nurse's Office 313 Lobby | N/A | Plaster Walls | | NAD | 420 | SF | 0 | SF | | | | N/A | N/A | N/A | | | | |
| 1 | 3 | Nurse's Office 313 next to Classroom 315 | M | Floor Tile VAT 12" x 12" | 7020/01/03/A2 | Assumed | 345 | SF | 0 | SF | Green | | | 1 | No | 1/D | | | | |
| 1 | 3 | Nurse's Office 313 next to Classroom 315 | N/A | Plaster Walls | | NAD | 1064 | SF | 0 | SF | | | | N/A | N/A | N/A | | | | |
| 1 | 3 | Nurse's Office 313 next to Classroom 315 | N/A | Plaster Ceiling | | NAD | 345 | SF | 0 | SF | | | | N/A | N/A | N/A | | | | |
| 1 | 3 | Nurse's Office 313 next to Classroom 315 | T | Pipe Insulation 2-6 inch | 7020/01/03/46 | Confirmed | 12 | LF | 0 | LF | | | | 1 | No | 1/D | | | | |
| 1 | 3 | Nurse's Office 313 next to Classroom 315 | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 6 | LF | 0 | LF | | | | N/A | N/A | N/A | | | | |
| 1 | 3 | Nurse's Office 320 next to Classroom 311 | M | Linoleum | 7020/01/03/LL | Assumed | 459 | SF | 0 | SF | Grey | Painted Grey | | 1 | No | 1/D | | | | |
| 1 | 3 | Nurse's Office 320 next to Classroom 311 | N/A | Plaster Walls | | NAD | 1232 | SF | 0 | SF | | | | N/A | N/A | N/A | | | | |
| 1 | 3 | Nurse's Office 320 next to Classroom 311 | N/A | Plaster Ceiling | | NAD | 459 | SF | 0 | SF | | | | N/A | N/A | N/A | | | | |
| 1 | 3 | Nurse's Office 320 next to Classroom 311 | T | Pipe Insulation > 6 inch | 7020/01/03/BATTA/AH/1110 | Assumed | 8 | LF | 0 | LF | | | | 1 | No | 1/D | | | | |
| 1 | 3 | Nurse's Office 320 next to Classroom 311 | T | Pipe Insulation 2-6 inch | 7020/01/03/46 | Confirmed | 29 | LF | 0 | LF | | | | 1 | No | 1/D | | | | |
| 1 | 3 | Nurse's Office 320 next to Classroom 311 | T | Pipe Fitting Insulation | 7020/01/03/67 | Assumed | 8 | EA | 0 | EA | | | | 1 | No | 1/D | | | | |
| 1 | 3 | Nurse's Office 320 next to Classroom 311 | M | Linoleum | 7020/01/03/LL | Assumed | 36 | SF | 0 | SF | Grey | Painted Grey | | 1 | No | 1/D | | | | |
| 1 | 3 | Nurse's Office Restroom | N/A | Plaster Walls | | NAD | 364 | SF | 0 | SF | | | | N/A | N/A | N/A | | | | |
| 1 | 3 | Nurse's Office Restroom | N/A | Plaster Ceiling | | NAD | 36 | SF | 0 | SF | | | | N/A | N/A | N/A | | | | |
| 1 | 3 | Nurse's Office Restroom | T | Pipe Insulation 2-6 inch | 7020/01/03/46 | Confirmed | 3 | LF | 0 | LF | | | | 1 | No | 1/D | | | | |
| 1 | 3 | Drug Storage in Nurse's Office 313 Lobby | N/A | Wood Floor | | Non Suspect ACM | 42 | SF | 0 | SF | | | | N/A | N/A | N/A | | | | |
| 1 | 3 | Drug Storage in Nurse's Office 313 Lobby | N/A | Plaster Walls | | NAD | 364 | SF | 0 | SF | | | | N/A | N/A | N/A | | | | |
| 1 | 3 | Drug Storage in Nurse's Office 313 Lobby | N/A | Plaster Ceiling | | NAD | 42 | SF | 0 | SF | | | | N/A | N/A | N/A | | | | |
| 1 | 3 | Classroom 311 | N/A | Wood Floor | | Non Suspect ACM | 816 | SF | 0 | SF | | | | N/A | N/A | N/A | | | | |
| 1 | 3 | Classroom 311 | N/A | Plaster Walls | | NAD | 1624 | SF | 0 | SF | | | | N/A | N/A | N/A | | | | |
| 1 | 3 | Classroom 311 | N/A | Plaster Ceiling | | NAD | 816 | SF | 4 | SF | | | | N/A | N/A | N/A | | | | |
| 1 | 3 | Classroom 311 | M | Blackboard Glue Dots | 7020/01/03/BATTA/AH/2600 | Assumed | 200 | SF | 0 | SF | | | | 1 | No | 1/D | | | | |
| 1 | 3 | Classroom 311 | T | Pipe Insulation 2-6 inch | 7020/01/03/46 | Confirmed | 46 | LF | 0 | LF | | | | 1 | No | 1/D | | | | |
| 1 | 3 | Classroom 311 | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 28 | LF | 0 | LF | | | | N/A | N/A | N/A | | | | |
| 1 | 3 | Classroom 311 | T | Pipe Fitting Insulation | 7020/01/03/67 | Assumed | 10 | EA | 1 | EA | | | | 1 | Yes | 5/A | | | | |
| 1 | 3 | Storage Room 309 | X | X | | X | X | X | X | X | | No access | | X | X | X | | | | |
| 1 | 3 | Classroom 307 | N/A | Wood Floor | | Non Suspect ACM | 750 | SF | 0 | SF | | | | N/A | N/A | N/A | | | | |
| 1 | 3 | Classroom 307 | N/A | Plaster Walls | | NAD | 1540 | SF | 0 | SF | | | | N/A | N/A | N/A | | | | |
| 1 | 3 | Classroom 307 | N/A | Ceiling Tile 2' x 4' | | NAD | 750 | SF | 0 | SF | | | | N/A | N/A | N/A | | | | |
| 1 | 3 | Classroom 307 | M | Blackboard Glue Dots | 7020/01/03/BATTA/AH/2600 | Assumed | 128 | SF | 0 | SF | | | | 1 | No | 1/D | | | | |
| 1 | 3 | Classroom 307 | T | Pipe Insulation 2-6 inch | 7020/01/03/46 | Confirmed | 14 | LF | 0 | LF | | | | 1 | No | 1/D | | | | |
| 1 | 3 | Classroom 307 | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 14 | LF | 0 | LF | | | | N/A | N/A | N/A | | | | |
| 1 | 3 | Classroom 305 | N/A | Wood Floor | | Non Suspect ACM | 750 | SF | 0 | SF | | | | N/A | N/A | N/A | | | | |
| 1 | 3 | Classroom 305 | N/A | Plaster Walls | | NAD | 1540 | SF | 0 | SF | | | | N/A | N/A | N/A | | | | |
| 1 | 3 | Classroom 305 | N/A | Ceiling Tile 2' x 4' | | NAD | 750 | SF | 0 | SF | | | | N/A | N/A | N/A | | | | |
| 1 | 3 | Classroom 305 | M | Blackboard Glue Dots | 7020/01/03/BATTA/AH/2600 | Assumed | 64 | SF | 0 | SF | | | | 1 | No | 1/D | | | | |
| 1 | 3 | Classroom 305 | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 12 | LF | 0 | LF | | Most Risers are Uninsulated | | N/A | N/A | N/A | | | | |
| 1 | 3 | Classroom 303 | N/A | Wood Floor | | Non Suspect ACM | 720 | SF | 0 | SF | | | | N/A | N/A | N/A | | | | |
| 1 | 3 | Classroom 303 | N/A | Plaster Walls | | NAD | 1512 | SF | 0 | SF | | | | N/A | N/A | N/A | | | | |
| 1 | 3 | Classroom 303 | N/A | Ceiling Tile 2' x 4' | | NAD | 720 | SF | 0 | SF | | | | N/A | N/A | N/A | | | | |
| 1 | 3 | Classroom 303 | M | Blackboard Glue Dots | 7020/01/03/BATTA/AH/2600 | Assumed | 128 | SF | 0 | SF | | | | 1 | No | 1/D | | | | |
| 1 | 3 | Classroom 303 | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 56 | LF | 0 | LF | | | | N/A | N/A | N/A | | | | |
| 1 | 3 | Copy Room 301 | M | Floor Tile VAT 12" x 12" | 7020/01/03/A2 | Assumed | 390 | SF | 0 | SF | Tan | | | 1 | No | 1/D | | | | |
| 1 | 3 | Copy Room 301 | N/A | Plaster Walls | | NAD | 1148 | SF | 0 | SF | | | | N/A | N/A | N/A | | | | |
| 1 | 3 | Copy Room 301 | N/A | Ceiling Tile 2' x 4' | | NAD | 390 | SF | 0 | SF | | | | N/A | N/A | N/A | | | | |
| 1 | 3 | Copy Room 301 | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 6 | LF | 0 | LF | | | | N/A | N/A | N/A | | | | |
| 1 | 3 | Copy Room 301 Closet | M | Floor Tile VAT 12" x 12" | 7020/01/03/A2 | Assumed | 40 | SF | 0 | SF | Tan | | | 1 | No | 1/D | | | | |
| 1 | 3 | Copy Room 301 Closet | N/A | Plaster Walls | | NAD | 392 | SF | 0 | SF | | | | N/A | N/A | N/A | | | | |
| 1 | 3 | Copy Room 301 Closet | N/A | Ceiling Tile 2' x 4' | | NAD | 40 | SF | 0 | SF | | | | N/A | N/A | N/A | | | | |
| 1 | 3 | Copy Room 301 Closet | T | Pipe Insulation 2-6 inch | 7020/01/03/46 | Confirmed | 42 | LF | 0 | LF | | | | 1 | No | 1/D | | | | |
| 1 | 3 | Classroom 371 | M | Floor Tile VAT 12" x 12" | 7020/01/03/A2 | Assumed | 840 | SF | 0 | SF | Blue | | | 1 | No | 1/D | | | | |
| 1 | 3 | Classroom 371 | N/A | Plaster Walls | | NAD | 1736 | SF | 0 | SF | | | | N/A | N/A | N/A | | | | |
| 1 | 3 | Classroom 371 | N/A | Ceiling Tile 2' x 4' | | NAD | 840 | SF | 0 | SF | | | | N/A | N/A | N/A | | | | |
| 1 | 3 | Classroom 371 | T | Pipe Insulation 2-6 inch | 7020/01/03/46 | Confirmed | 32 | LF | 0 | LF | | | | 1 | No | 1/D | | | | |
| 1 | 3 | Classroom 371 | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 6 | LF | 0 | LF | | | | N/A | N/A | N/A | | | | |
| 1 | 3 | Storage Room 369 | M | Floor Tile VAT 12" x 12" | 7020/01/03/A2 | Assumed | 882 | SF | 0 | SF | Tan | | | 1 | No | 1/D | | | | |
| 1 | 3 | Storage Room 369 | N/A | Plaster Walls | | NAD | 1764 | SF | 0 | SF | | | | N/A | N/A | N/A | | | | |
| 1 | 3 | Storage Room 369 | N/A | Ceiling Tile 2' x 4' | | NAD | 882 | SF | 0 | SF | | | | N/A | N/A | N/A | | | | |
| 1 | 3 | Storage Room 369 | T | Pipe Insulation 2-6 inch | 7020/01/03/46 | Confirmed | 21 | LF | 0 | LF | | | | 1 | No | 1/D | | | | |
| 1 | 3 | Storage Room 369 | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 21 | LF | 0 | LF | | | | N/A | N/A | N/A | | | | |
| 1 | 3 | Main Storage Room attached to Classroom 367 | N/A | Cement Floor | | Non Suspect ACM | 360 | SF | 0 | SF | | | | N/A | N/A | N/A | | | | |
| 1 | 3 | Main Storage Room attached to Classroom 367 | N/A | Ceiling Tile 2' x 4' | | NAD | 360 | SF | 32 | SF | | | | N/A | N/A | N/A | | | | |
| 1 | 3 | Main Storage Room attached to Classroom 367 | N/A | Plaster Walls | | NAD | 936 | SF | 0 | SF | | | | N/A | N/A | N/A | | | | |
| 1 | 3 | Main Storage Room attached to Classroom 367 | T | Pipe Insulation 2-6 inch | 7020/01/03/46 | Confirmed | 6 | LF | 0 | LF | | | | 1 | No | 1/D | | | | |
| 1 | 3 | Main Storage Room attached to Classroom 371 Closet Window Side | N/A | Cement Floor | | Non Suspect ACM | 36 | SF | 0 | SF | | | | N/A | N/A | N/A | | | | |
| 1 | 3 | Main Storage Room attached to Classroom 371 Closet Window Side | N/A | Concrete Ceiling | | Non Suspect ACM | 36 | SF | 0 | SF | | | | N/A | N/A | N/A | | | | |

7020 Olney HS (ASPIRA) 2015 2016 AHERA Three-Year Report.xls

| School District of Philadelphia | | | ASHERA Three-Year Reinspection 2015-2016 Room by Room Location Log Report | | | | | | | | | | Reinspection Date: December 13, 2015 | | | |
|---|-----------------------|---|--|----------------------------|--------------------------|---|-----------------------|-------------|---------------------|-------------|------------------------------|--|--------------------------------------|-----------------------------|--------------------------|-------------------------|
| Aspira Olney Charter High School | | | | | | | | | | | | | Building Inspector: James Madden | | | |
| 100 E. Duncannon Street, Philadelphia, PA 19120 | | | | | | | | | | | | | Number: 030867 | | | |
| ULCS# 7029 | | | | | | | | | | | | | Management Planner: Megan Vala | | | |
| Year Built: 1931 | | | | | | | | | | | | | Number: 740728 | | | |
| E l e m e n t | F l o o r | | System Affected | Material Description | HID# | Confirmed/Assumed/NAD/ Non Suspect ACM | Amount of Material | SF LF EA | Amount of Damage | SF LF EA | Color required for VAT | Comments/Description/Notes | Attic/ Crawl Space Ranking | Damage Potential (DP) | Newly Friable (NF) | Response Action (RA) |
| 1 | 3 | Main Storage Room attached to Classroom 371 Closet Window Side | N/A | Plaster Walls | | NAD | 336 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 3 | Main Storage Room attached to Classroom 371 Closet Window Side | T | Pipe Insulation 2-6 inch | 7020/01/03/46 | Confirmed | 12 | LF | 0 | LF | | | | 1 | No | 1/D |
| 1 | 3 | Main Storage Room attached to Classroom 371 Closet Window Side | T | Pipe Fitting Insulation | 7020/01/03/67 | Assumed | 3 | EA | 1 | EA | | Cracked Fitting | | 1 | Yes | 5/A |
| 1 | 3 | Main Storage Room attached to Classroom 371 Closet Hallway Side | N/A | Cement Floor | | Non Suspect ACM | 36 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 3 | Main Storage Room attached to Classroom 371 Closet Hallway Side | N/A | Ceiling Tile 2' x 4' | | NAD | 36 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 3 | Main Storage Room attached to Classroom 371 Closet Hallway Side | N/A | Plaster Walls | | NAD | 336 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 3 | Classroom 367 | N/A | Wood Floor | | Non Suspect ACM | 720 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 3 | Classroom 367 | N/A | Plaster Walls | | NAD | 1512 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 3 | Classroom 367 | N/A | Plaster Ceiling | | NAD | 720 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 3 | Classroom 367 | M | Blackboard Glue Dots | 7020/01/03/BATTA/AH/2600 | Assumed | 128 | SF | 0 | SF | | | | 1 | No | 1/D |
| 1 | 3 | Classroom 367 | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 28 | LF | 0 | LF | | | | N/A | N/A | N/A |
| 1 | 3 | Classroom 365 | N/A | Wood Floor | | Non Suspect ACM | 750 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 3 | Classroom 365 | N/A | Plaster Walls | | NAD | 1540 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 3 | Classroom 365 | N/A | Plaster Ceiling | | NAD | 750 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 3 | Classroom 365 | M | Blackboard Glue Dots | 7020/01/03/BATTA/AH/2600 | Assumed | 128 | SF | 0 | SF | | | | 1 | No | 1/D |
| 1 | 3 | Classroom 365 | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 35 | LF | 0 | LF | | | | N/A | N/A | N/A |
| 1 | 3 | Classroom 363 | N/A | Wood Floor | | Non Suspect ACM | 750 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 3 | Classroom 363 | N/A | Plaster Walls | | NAD | 1540 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 3 | Classroom 363 | N/A | Plaster Ceiling | | NAD | 750 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 3 | Classroom 363 | M | Blackboard Glue Dots | 7020/01/03/BATTA/AH/2600 | Assumed | 200 | SF | 0 | SF | | | | 1 | No | 1/D |
| 1 | 3 | Classroom 363 | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 35 | LF | 6 | LF | | | | N/A | N/A | N/A |
| 1 | 3 | Science Preparation Room between Classrooms 259 and 263 | N/A | Wood Floor | | Non Suspect ACM | 300 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 3 | Science Preparation Room between Classrooms 259 and 263 | N/A | Ceiling Tile 2' x 4' | | NAD | 300 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 3 | Science Preparation Room between Classrooms 259 and 263 | N/A | Plaster Walls | | NAD | 600 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 3 | Science Preparation Room between Classrooms 259 and 263 | M | Transite Counter Tops | 7020/01/03/47 | Assumed | 150 | SF | 0 | SF | | | | 1 | No | 1/D |
| 1 | 3 | Classroom 359 | N/A | Wood Floor | | Non Suspect ACM | 816 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 3 | Classroom 359 | N/A | Plaster Walls | | NAD | 1624 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 3 | Classroom 359 | N/A | Ceiling Tile 2' x 4' | | NAD | 816 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 3 | Classroom 359 | M | Blackboard Glue Dots | 7020/01/03/BATTA/AH/2600 | Assumed | 80 | SF | 0 | SF | | | | 1 | No | 1/D |
| 1 | 3 | Classroom 359 | T | Pipe Insulation 2-6 inch | 7020/01/03/46 | Confirmed | 14 | LF | 0 | LF | | | | 1 | No | 1/D |
| 1 | 3 | Classroom 359 | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 16 | LF | 0 | LF | | | | N/A | N/A | N/A |
| 1 | 3 | Classroom 359 | M | Transite Sink | 7020/01/03/47 | Assumed | 12 | SF | 0 | SF | | | | 1 | No | 1/D |
| 1 | 3 | Classroom 359 | M | Transite Counter Tops | 7020/01/03/47 | Assumed | 180 | SF | 0 | SF | | | | 1 | No | 1/D |
| 1 | 3 | Classroom 357 | M | Floor Tile VAT 9" x 9" | 7020/01/03/42 | Confirmed | 558 | SF | 3 | SF | Brown | | | 1 | Yes | 5/B |
| 1 | 3 | Classroom 357 | N/A | Plaster Walls | | NAD | 1176 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 3 | Classroom 357 | N/A | Ceiling Tile 2' x 4' | | NAD | 558 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 3 | Classroom 357 | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 6 | LF | 0 | LF | | | | N/A | N/A | N/A |
| 1 | 3 | Classroom 357 Closet on Right Side of Room | M | Floor Tile VAT 9" x 9" | 7020/01/03/42 | Confirmed | 27 | SF | 0 | SF | Brown | | | 1 | No | 1/D |
| 1 | 3 | Classroom 357 Closet on Right Side of Room | N/A | Plaster Walls | | NAD | 336 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 3 | Classroom 357 Closet on Right Side of Room | N/A | Plaster Ceiling | | NAD | 27 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 3 | Classroom 357 Closet on Right Side of Room | M | Floor Tile VAT 9" x 9" | 7020/01/03/42 | Confirmed | 56 | SF | 0 | SF | | No access (Fall 2016) | | 1 | No | 1/D |
| 1 | 3 | Classroom 357 Closet on Right Side of Room | N/A | Plaster Walls | | NAD | 360 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 3 | Classroom 357 Closet on Right Side of Room | N/A | Ceiling Tile 2' x 4' | | NAD | 56 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 3 | Classroom 355 | N/A | Wood Floor | | Non Suspect ACM | 832 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 3 | Classroom 355 | N/A | Plaster Walls | | NAD | 1392 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 3 | Classroom 355 | N/A | Ceiling Tile 2' x 4' | | NAD | 832 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 3 | Classroom 355 | M | Blackboard Glue Dots | 7020/01/03/BATTA/AH/2600 | Assumed | 64 | SF | 0 | SF | | | | 1 | No | 1/D |
| 1 | 3 | Classroom 355 | T | Pipe Insulation 2-6 inch | 7020/01/03/46 | Confirmed | 14 | LF | 2 | LF | | | | 1 | Yes | 5/A |
| 1 | 3 | Classroom 355 | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 18 | LF | 0 | LF | | | | N/A | N/A | N/A |
| 1 | 3 | Classroom 355 | M | Transite Sink | 7020/01/03/47 | Assumed | 12 | SF | 0 | SF | | | | 1 | No | 1/D |
| 1 | 3 | Classroom 355 | M | Transite Counter Tops | 7020/01/03/47 | Assumed | 165 | SF | 0 | SF | | | | 1 | No | 1/D |
| 1 | 3 | Chemical Storage in Classroom 355 | X | X | | X | X | X | X | X | | No Access | | X | X | X |
| 1 | 3 | Classroom 353 | N/A | Wood Floor | | Non Suspect ACM | 720 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 3 | Classroom 353 | N/A | Plaster Walls | | NAD | 1296 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 3 | Classroom 353 | N/A | Ceiling Tile 2' x 4' | | NAD | 720 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 3 | Classroom 353 | M | Blackboard Glue Dots | 7020/01/03/BATTA/AH/2600 | Assumed | 80 | SF | 0 | SF | | | | 1 | No | 1/D |
| 1 | 3 | Classroom 353 | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 15 | LF | 0 | LF | | | | N/A | N/A | N/A |
| 1 | 3 | Classroom 353 | M | Transite Counter Tops | 7020/01/03/47 | Assumed | 140 | SF | 0 | SF | | | | 1 | No | 1/D |
| 1 | 3 | Classroom 351 | N/A | Wood Floor | | Non Suspect ACM | 720 | SF | 0 | SF | | Not listed, possibly Library - Inspector please verify | | N/A | N/A | N/A |
| 1 | 3 | Classroom 351 | N/A | Ceiling Tile 2' x 4' | | NAD | 720 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 3 | Classroom 351 | N/A | Plaster Walls | | NAD | 1000 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 3 | Classroom 351 | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 20 | LF | 0 | LF | | | | N/A | N/A | N/A |
| 1 | 3 | Classroom 351 | M | Transite Counter Tops | 7020/01/03/47 | Assumed | 150 | SF | 0 | SF | | | | 1 | No | 1/D |
| 1 | 3 | Custodial Closet next to Boy's Restroom | N/A | Cement Floor | | Non Suspect ACM | 16 | SF | 0 | SF | | | | N/A | N/A | N/A |

7020 Olney HS (ASPIRA) 2015 2016 AHERA Three-Year Report.xls

| School District of Philadelphia | | | AHERA Three-Year Reinspection 2015-2016 | | | | | | | | | | Reinspection Date: December 13, 2015 | | | | | |
|---|-----------------------|---|---|----------------------------|--------------------------|---|-----------------------|-------------|---------------------|-------------|------------------------------|---|--------------------------------------|-----------------------------|--------------------------|-------------------------|--|--|
| Aspira Olney Charter High School | | | Room by Room Location Log Report | | | | | | | | | | Building Inspector: James Madden | | | | | |
| 100 E. Duncannon Street, Philadelphia, PA 19120 | | | | | | | | | | | | | Number: 030867 | | | | | |
| ULCS# 7029 | | | | | | | | | | | | | Management Planner: Megan Vala | | | | | |
| Year Built: 1931 | | | | | | | | | | | | | Number: 740728 | | | | | |
| E l e m e n t | F l o o r | On Site Room Name | System Affected | Material Description | HID# | Confirmed/Assumed/NAD/ Non Suspect ACM | Amount of Material | SF LF EA | Amount of Damage | SF LF EA | Color required for VAT | Comments/Description/Notes | Attic/ Crawl Space Ranking | Damage Potential (DP) | Newly Friable (NF) | Response Action (RA) | | |
| 1 | 3 | Custodial Closet next to Boy's Restroom | N/A | Plaster Walls | | NAD | 192 | SF | 0 | SF | | | | N/A | N/A | N/A | | |
| 1 | 3 | Custodial Closet next to Boy's Restroom | N/A | Plaster Ceiling | | NAD | 16 | SF | 0 | SF | | | | N/A | N/A | N/A | | |
| 1 | 3 | Custodial Closet next to Boy's Restroom | T | Pipe Insulation 2-6 inch | 7020/01/03/46 | Confirmed | 20 | LF | 0 | LF | | | | 1 | No | 1/D | | |
| 1 | 3 | Boy's Restroom | N/A | Cement Floor | | Non Suspect ACM | 520 | SF | 0 | SF | | | | N/A | N/A | N/A | | |
| 1 | 3 | Boy's Restroom | N/A | Plaster Walls | | NAD | 1288 | SF | 0 | SF | | | | N/A | N/A | N/A | | |
| 1 | 3 | Boy's Restroom | N/A | Plaster Ceiling | | NAD | 520 | SF | 5 | SF | | | | N/A | N/A | N/A | | |
| 1 | 3 | Boy's Restroom | T | Pipe Fitting Insulation | 7020/01/03/67 | Assumed | 44 | EA | 0 | EA | | | | 1 | No | 1/D | | |
| 1 | 3 | Boy's Restroom | T | Pipe Insulation 2-6 inch | 7020/01/03/46 | Confirmed | 8 | LF | 0 | LF | | | | 1 | No | 1/D | | |
| 1 | 3 | Science Closet 3 across from Olney Library Room 351 | M | Floor Tile VAT 9" x 9" | 7020/01/03/42 | Confirmed | 104 | SF | 0 | SF | Tan | | | 1 | No | 1/D | | |
| 1 | 3 | Science Closet 3 across from Olney Library Room 351 | N/A | Plaster Walls | | NAD | 155 | SF | 0 | SF | | | | N/A | N/A | N/A | | |
| 1 | 3 | Science Closet 3 across from Olney Library Room 351 | N/A | Ceiling Tile 2' x 4' | | NAD | 104 | SF | 0 | SF | | | | N/A | N/A | N/A | | |
| 1 | 3 | Science Closet 3 across from Olney Library Room 351 | N/A | Brick Wall | | Non Suspect ACM | 155 | SF | 0 | SF | | | | N/A | N/A | N/A | | |
| 1 | 3 | Science Closet 3 across from Olney Library Room 351 | N/A | Concrete Block Wall | | Non Suspect ACM | 310 | SF | 0 | SF | | | | N/A | N/A | N/A | | |
| 1 | 3 | Classroom 354 | M | Floor Tile VAT 9" x 9" | 7020/01/03/42 | Confirmed | 650 | SF | 0 | SF | Tan | | | 1 | No | 1/D | | |
| 1 | 3 | Classroom 354 | N/A | Plaster Walls | | NAD | 600 | SF | 0 | SF | | | | N/A | N/A | N/A | | |
| 1 | 3 | Classroom 354 | N/A | Ceiling Tile 2' x 4' | | NAD | 650 | SF | 0 | SF | | | | N/A | N/A | N/A | | |
| 1 | 3 | Classroom 354 | N/A | Brick Wall | | Non Suspect ACM | 300 | SF | 0 | SF | | | | N/A | N/A | N/A | | |
| 1 | 3 | Classroom 354 | N/A | Concrete Block Wall | | Non Suspect ACM | 400 | SF | 0 | SF | | | | N/A | N/A | N/A | | |
| 1 | 3 | Classroom 354 | M | Blackboard Glue Dots | 7020/01/03/BATTA/AH/2600 | Assumed | 144 | SF | 0 | SF | | | | 1 | No | 1/D | | |
| 1 | 3 | Classroom 354 | T | Pipe Insulation 2-6 inch | 7020/01/03/46 | Confirmed | 28 | LF | 0 | LF | | | | 1 | No | 1/D | | |
| 1 | 3 | Classroom 354 | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 7 | LF | 0 | LF | | | | N/A | N/A | N/A | | |
| 1 | 3 | Classroom 356 | M | Floor Tile VAT 9" x 9" | 7020/01/03/42 | Confirmed | 744 | SF | 0 | SF | Tan | | | 1 | No | 1/D | | |
| 1 | 3 | Classroom 356 | N/A | Plaster Walls | | NAD | 660 | SF | 0 | SF | | | | N/A | N/A | N/A | | |
| 1 | 3 | Classroom 356 | N/A | Ceiling Tile 2' x 4' | | NAD | 744 | SF | 0 | SF | | | | N/A | N/A | N/A | | |
| 1 | 3 | Classroom 356 | N/A | Brick Wall | | Non Suspect ACM | 250 | SF | 0 | SF | | | | N/A | N/A | N/A | | |
| 1 | 3 | Classroom 356 | N/A | Concrete Block Wall | | Non Suspect ACM | 400 | SF | 0 | SF | | | | N/A | N/A | N/A | | |
| 1 | 3 | Classroom 356 | M | Blackboard Glue Dots | 7020/01/03/BATTA/AH/2600 | Assumed | 144 | SF | 0 | SF | | | | 1 | No | 1/D | | |
| 1 | 3 | Classroom 356 | T | Pipe Insulation 2-6 inch | 7020/01/03/46 | Confirmed | 35 | LF | 0 | LF | | | | 1 | No | 1/D | | |
| 1 | 3 | Classroom 358 | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 7 | LF | 0 | LF | | | | N/A | N/A | N/A | | |
| 1 | 3 | Classroom 358 | X | X | | X | X | X | X | X | | Not listed - Inspector please verify | | X | X | X | | |
| 1 | 3 | Staff Restroom across from Classroom 355 | N/A | Cement Floor | | Non Suspect ACM | 338 | SF | 0 | SF | | | | N/A | N/A | N/A | | |
| 1 | 3 | Staff Restroom across from Classroom 355 | N/A | Concrete Ceiling | | Non Suspect ACM | 338 | SF | 0 | SF | | | | N/A | N/A | N/A | | |
| 1 | 3 | Staff Restroom across from Classroom 355 | T | Pipe Insulation 2-6 inch | 7020/01/03/46 | Confirmed | 14 | LF | 0 | LF | | | | 1 | No | 1/D | | |
| 1 | 3 | Staff Restroom across from Classroom 355 | N/A | Plaster Walls | | NAD | 1092 | SF | 0 | SF | | | | N/A | N/A | N/A | | |
| 1 | 3 | Storage Room attached to Classroom 318 | N/A | Plaster Walls | | NAD | 1092 | SF | 9 | SF | | | | N/A | N/A | N/A | | |
| 1 | 3 | Storage Room attached to Classroom 318 | N/A | Wood Floor | | Non Suspect ACM | 338 | SF | 0 | SF | | | | N/A | N/A | N/A | | |
| 1 | 3 | Storage Room attached to Classroom 318 | N/A | Concrete Ceiling | | Non Suspect ACM | 338 | SF | 0 | SF | | | | N/A | N/A | N/A | | |
| 1 | 3 | Storage Room attached to Classroom 318 | T | Pipe Insulation 2-6 inch | 7020/01/03/46 | Confirmed | 18 | LF | 0 | LF | | | | 1 | No | 1/D | | |
| 1 | 3 | Hallway from Classrooms 325 to 345 | N/A | Cement Floor | | Non Suspect ACM | 3240 | SF | 0 | SF | | | | N/A | N/A | N/A | | |
| 1 | 3 | Hallway from Classrooms 325 to 345 | N/A | Plaster Walls | | NAD | 7896 | SF | 0 | SF | | | | N/A | N/A | N/A | | |
| 1 | 3 | Hallway from Classrooms 325 to 345 | N/A | Ceiling Tile 1' x 1' | | NAD | 3240 | SF | 0 | SF | | | | N/A | N/A | N/A | | |
| 1 | 3 | Hallway from Classrooms 325 to 345 | N/A | Ceiling Tile 2' x 4' | | NAD | 3240 | SF | 0 | SF | | | | N/A | N/A | N/A | | |
| 1 | 3 | Hallway from Classrooms 325 to 345 | T | Pipe Insulation 2-6 inch | 7020/01/03/46 | Confirmed | 50 | LF | 0 | LF | | | | 1 | No | 1/D | | |
| 1 | 3 | Hallway from Classrooms 325 to 345 | T | Pipe Fitting Insulation | 7020/01/03/67 | Assumed | 10 | EA | 0 | EA | | | | 1 | No | 1/D | | |
| 1 | 3 | Hallway from Classrooms 325 to 345 | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 120 | LF | 20 | LF | | No amounts listed - Inspector please verify | | N/A | N/A | N/A | | |
| 1 | 3 | Hallway from Classrooms 349 to 359 | N/A | Cement Floor | | Non Suspect ACM | 2040 | SF | 0 | SF | | | | N/A | N/A | N/A | | |
| 1 | 3 | Hallway from Classrooms 349 to 359 | N/A | Plaster Walls | | NAD | 5096 | SF | 0 | SF | | | | N/A | N/A | N/A | | |
| 1 | 3 | Hallway from Classrooms 349 to 359 | N/A | Ceiling Tile 2' x 4' | | NAD | 2040 | SF | 0 | SF | | | | N/A | N/A | N/A | | |
| 1 | 3 | Hallway from Classrooms 363 to 307 | N/A | Cement Floor | | Non Suspect ACM | 3240 | SF | 0 | SF | | | | N/A | N/A | N/A | | |
| 1 | 3 | Hallway from Classrooms 363 to 307 | N/A | Plaster Walls | | NAD | 5922 | SF | 0 | SF | | | | N/A | N/A | N/A | | |
| 1 | 3 | Hallway from Classrooms 363 to 307 | N/A | Marble Walls | | Non Suspect ACM | 1974 | SF | 0 | SF | | | | N/A | N/A | N/A | | |
| 1 | 3 | Hallway from Classrooms 363 to 307 | N/A | Ceiling Tile 1' x 1' | | NAD | 3240 | SF | 0 | SF | | | | N/A | N/A | N/A | | |
| 1 | 3 | Hallway from Classrooms 363 to 307 | N/A | Ceiling Tile 2' x 4' | | NAD | 3240 | SF | 0 | SF | | | | N/A | N/A | N/A | | |
| 1 | 3 | Hallway from Classrooms 363 to 307 | T | Pipe Insulation 2-6 inch | 7020/01/03/46 | Confirmed | 40 | LF | 0 | LF | | | | 1 | No | 1/D | | |
| 1 | 3 | Hallway from Classrooms 363 to 307 | T | Pipe Fitting Insulation | 7020/01/03/67 | Assumed | 9 | EA | 0 | EA | | | | 1 | No | 1/D | | |
| 1 | 3 | Hallway from Classrooms 363 to 307 | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 120 | LF | 5 | LF | | No amounts listed - Inspector please verify | | N/A | N/A | N/A | | |
| 1 | 3 | Hallway from Classrooms 311 to 325 | N/A | Cement Floor | | Non Suspect ACM | 2040 | SF | 0 | SF | | | | N/A | N/A | N/A | | |
| 1 | 3 | Hallway from Classrooms 311 to 325 | N/A | Plaster Walls | | NAD | 3822 | SF | 0 | SF | | | | N/A | N/A | N/A | | |
| 1 | 3 | Hallway from Classrooms 311 to 325 | N/A | Marble Walls | | Non Suspect ACM | 1274 | SF | 0 | SF | | | | N/A | N/A | N/A | | |
| 1 | 3 | Hallway from Classrooms 311 to 325 | N/A | Ceiling Tile 2' x 4' | | NAD | 2040 | SF | 0 | SF | | | | N/A | N/A | N/A | | |
| 1 | 4 | Classroom 463 | N/A | Wood Floor | | Non Suspect ACM | 720 | SF | 0 | SF | | | | N/A | N/A | N/A | | |
| 1 | 4 | Classroom 463 | N/A | Plaster Walls | | NAD | 1512 | SF | 1 | SF | | | | N/A | N/A | N/A | | |
| 1 | 4 | Classroom 463 | N/A | Plaster Ceiling | | NAD | 720 | SF | 0 | SF | | | | N/A | N/A | N/A | | |
| 1 | 4 | Classroom 463 | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 28 | LF | 0 | LF | | | | N/A | N/A | N/A | | |
| 1 | 4 | Classroom 463 | M | Blackboard Glue Dots | 7020/01/04/BATTA/AH/2600 | Assumed | 192 | SF | 0 | SF | | | | 1 | No | 1/D | | |
| 1 | 4 | Classroom 461 | N/A | Wood Floor | | Non Suspect ACM | 720 | SF | 0 | SF | | | | N/A | N/A | N/A | | |
| 1 | 4 | Classroom 461 | N/A | Plaster Walls | | NAD | 1512 | SF | 0 | SF | | | | N/A | N/A | N/A | | |
| 1 | 4 | Classroom 461 | N/A | Plaster Ceiling | | NAD | 720 | SF | 0 | SF | | | | N/A | N/A | N/A | | |
| 1 | 4 | Classroom 461 | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 6 | LF | 0 | LF | | | | N/A | N/A | N/A | | |
| 1 | 4 | Classroom 461 | M | Blackboard Glue Dots | 7020/01/04/BATTA/AH/2600 | Assumed | 192 | SF | 0 | SF | | | | 1 | No | 1/D | | |
| 1 | 4 | Classroom 461 | T | Pipe Insulation 2-6 inch | 7020/01/04/60 | Confirmed | 12 | LF | 0 | LF | | | | 1 | No | 1/D | | |
| 1 | 4 | Classroom 457 | N/A | Wood Floor | | Non Suspect ACM | 1008 | SF | 0 | SF | | | | N/A | N/A | N/A | | |
| 1 | 4 | Classroom 457 | N/A | Plaster Walls | | NAD | 1848 | SF | 0 | SF | | | | N/A | N/A | N/A | | |

7020 Olney HS (ASPIRA) 2015 2016 AHERA Three-Year Report.xls

| School District of Philadelphia Aspira Olney Charter High School 100 E. Duncannon Street, Philadelphia, PA 19120 ULCS# 7029 Year Built: 1931 | | | AHERA Three-Year Reinspection 2015-2016 Room by Room Location Log Report | | | | | | | | | | Reinspection Date: December 13, 2015 Building Inspector: James Madden Number: 030867 Management Planner: Megan Vala Number: 740728 | | | |
|--|-----------------------|---|---|----------------------------|--------------------------|---|-----------------------|-------------|---------------------|-------------|------------------------------|----------------------------|--|-----------------------------|--------------------------|-------------------------|
| E l e m e n t | F l o o r | On Site Room Name | System Affected | Material Description | HID# | Confirmed/Assumed/NAD/ Non Suspect ACM | Amount of Material | SF LF EA | Amount of Damage | SF LF EA | Color required for VAT | Comments/Description/Notes | Attic/ Crawl Space Ranking | Damage Potential (DP) | Newly Friable (NF) | Response Action (RA) |
| 1 | 4 | Classroom 457 | N/A | Plaster Ceiling | | NAD | 1008 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 4 | Classroom 457 | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 30 | LF | 0 | LF | | | | N/A | N/A | N/A |
| 1 | 4 | Classroom 457 | M | Blackboard Glue Dots | 7020/01/04/BATTA/AH/2600 | Assumed | 136 | SF | 0 | SF | | | | 1 | No | 1/D |
| 1 | 4 | Classroom 457 | T | Pipe Insulation 2-6 inch | 7020/01/04/60 | Confirmed | 12 | LF | 0 | LF | | | | 1 | No | 1/D |
| 1 | 4 | Storage Room 459 | N/A | Wood Floor | | Non Suspect ACM | 150 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 4 | Storage Room 459 | N/A | Plaster Walls | | NAD | 868 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 4 | Storage Room 459 | N/A | Plaster Ceiling | | NAD | 150 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 4 | Storage Room 459 | T | Pipe Insulation 2-6 inch | 7020/01/04/60 | Confirmed | 46 | LF | 0 | LF | | | | 1 | No | 1/D |
| 1 | 4 | Storage Room 459 | T | Pipe Fitting Insulation | 7020/01/04/68 | Assumed | 4 | EA | 0 | EA | | | | 1 | No | 1/D |
| 1 | 4 | Office 455 | N/A | Wood Floor | | Non Suspect ACM | 390 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 4 | Office 455 | N/A | Plaster Walls | | NAD | 1148 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 4 | Office 455 | N/A | Plaster Ceiling | | NAD | 390 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 4 | Office 455 | T | Pipe Insulation 2-6 inch | 7020/01/04/60 | Confirmed | 6 | LF | 0 | LF | | | | 1 | No | 1/D |
| 1 | 4 | Office 455 | M | Blackboard Glue Dots | 7020/01/04/BATTA/AH/2600 | Assumed | 128 | SF | 0 | SF | | | | 1 | No | 1/D |
| 1 | 4 | Computer Room 453 | N/A | Wood Floor | | Non Suspect ACM | 960 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 4 | Computer Room 453 | N/A | Plaster Walls | | NAD | 1792 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 4 | Computer Room 453 | N/A | Plaster Ceiling | | NAD | 960 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 4 | Computer Room 453 | T | Pipe Insulation 2-6 inch | 7020/01/04/60 | Confirmed | 28 | LF | 2 | LF | | | | 1 | Yes | 5/A |
| 1 | 4 | Computer Room 453 | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 10 | LF | 0 | LF | | | | N/A | N/A | N/A |
| 1 | 4 | Computer Room 453 | M | Blackboard Glue Dots | 7020/01/04/BATTA/AH/2600 | Assumed | 120 | SF | 0 | SF | | | | 1 | No | 1/D |
| 1 | 4 | Classroom 451 | N/A | Wood Floor | | Non Suspect ACM | 1125 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 4 | Classroom 451 | N/A | Plaster Walls | | NAD | 1960 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 4 | Classroom 451 | N/A | Plaster Ceiling | | NAD | 1125 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 4 | Classroom 451 | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 30 | LF | 0 | LF | | | | N/A | N/A | N/A |
| 1 | 4 | Classroom 451 | T | Pipe Insulation 2-6 inch | 7020/01/04/60 | Confirmed | 6 | LF | 0 | LF | | | | 1 | No | 1/D |
| 1 | 4 | Classroom 449 | N/A | Wood Floor | | Non Suspect ACM | 1014 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 4 | Classroom 449 | N/A | Plaster Walls | | NAD | 1820 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 4 | Classroom 449 | N/A | Plaster Ceiling | | NAD | 1014 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 4 | Classroom 449 | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 14 | LF | 2 | LF | | | | N/A | N/A | N/A |
| 1 | 4 | Classroom 447 | N/A | Wood Floor | | Non Suspect ACM | 1344 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 4 | Classroom 447 | N/A | Plaster Walls | | NAD | 2072 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 4 | Classroom 447 | N/A | Plaster Ceiling | | NAD | 1344 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 4 | Classroom 447 | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 14 | LF | 0 | LF | | | | N/A | N/A | N/A |
| 1 | 4 | Classroom 447 | T | Pipe Insulation 2-6 inch | 7020/01/04/60 | Confirmed | 12 | LF | 0 | LF | | | | 1 | No | 1/D |
| 1 | 4 | Classroom 439 | N/A | Wood Floor | | Non Suspect ACM | 960 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 4 | Classroom 439 | N/A | Plaster Walls | | NAD | 1792 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 4 | Classroom 439 | N/A | Plaster Ceiling | | NAD | 960 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 4 | Classroom 439 | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 6 | LF | 0 | LF | | | | N/A | N/A | N/A |
| 1 | 4 | Classroom 439 | T | Pipe Insulation 2-6 inch | 7020/01/04/60 | Confirmed | 14 | LF | 0 | LF | | | | 1 | No | 1/D |
| 1 | 4 | Classroom 439 | M | Blackboard Glue Dots | 7020/01/04/BATTA/AH/2600 | Assumed | 128 | SF | 0 | SF | | | | 1 | No | 1/D |
| 1 | 4 | Classroom 437 | N/A | Wood Floor | | Non Suspect ACM | 960 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 4 | Classroom 437 | N/A | Plaster Walls | | NAD | 1792 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 4 | Classroom 437 | N/A | Plaster Ceiling | | NAD | 960 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 4 | Classroom 437 | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 12 | LF | 0 | LF | | | | N/A | N/A | N/A |
| 1 | 4 | Classroom 437 | T | Pipe Insulation 2-6 inch | 7020/01/04/60 | Confirmed | 28 | LF | 0 | LF | | | | 1 | No | 1/D |
| 1 | 4 | Classroom 437 | M | Blackboard Glue Dots | 7020/01/04/BATTA/AH/2600 | Assumed | 128 | SF | 0 | SF | | | | 1 | No | 1/D |
| 1 | 4 | Computer Room 435 | N/A | Wood Floor | | Non Suspect ACM | 960 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 4 | Computer Room 435 | N/A | Plaster Walls | | NAD | 1792 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 4 | Computer Room 435 | N/A | Plaster Ceiling | | NAD | 960 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 4 | Computer Room 435 | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 3 | LF | 0 | LF | | | | N/A | N/A | N/A |
| 1 | 4 | Computer Room 435 | T | Pipe Insulation 2-6 inch | 7020/01/04/60 | Confirmed | 28 | LF | 0 | LF | | | | 1 | No | 1/D |
| 1 | 4 | Computer Room 435 | M | Blackboard Glue Dots | 7020/01/04/BATTA/AH/2600 | Assumed | 80 | SF | 0 | SF | | | | 1 | No | 1/D |
| 1 | 4 | Dean's Office Room 445 | N/A | Wood Floor | | Non Suspect ACM | 336 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 4 | Dean's Office Room 445 | N/A | Plaster Walls | | NAD | 1064 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 4 | Dean's Office Room 445 | N/A | Plaster Ceiling | | NAD | 336 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 4 | Dean's Office Room 445 | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 11 | LF | 0 | LF | | | | N/A | N/A | N/A |
| 1 | 4 | Dean's Office Room 445 | T | Pipe Insulation 2-6 inch | 7020/01/04/60 | Confirmed | 11 | LF | 0 | LF | | | | 1 | No | 1/D |
| 1 | 4 | Dean's Office Room 445 | M | Blackboard Glue Dots | 7020/01/04/BATTA/AH/2600 | Assumed | 160 | SF | 0 | SF | | | | 1 | No | 1/D |
| 1 | 4 | Storage Room next to Classrooms 445 and 443 | N/A | Wood Floor | | Non Suspect ACM | 45 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 4 | Storage Room next to Classrooms 445 and 443 | N/A | Plaster Walls | | NAD | 392 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 4 | Storage Room next to Classrooms 445 and 443 | N/A | Plaster Ceiling | | NAD | 45 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 4 | Storage Room next to Classrooms 445 and 443 | N/A | Wood Floor | | Non Suspect ACM | 1125 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 4 | Classroom 433 | N/A | Plaster Walls | | NAD | 1960 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 4 | Classroom 433 | N/A | Plaster Ceiling | | NAD | 1125 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 4 | Classroom 433 | T | Pipe Insulation 2-6 inch | 7020/01/04/60 | Confirmed | 42 | LF | 0 | LF | | | | 1 | No | 1/D |
| 1 | 4 | Classroom 433 | M | Blackboard Glue Dots | 7020/01/04/BATTA/AH/2600 | Assumed | 120 | SF | 0 | SF | | | | 1 | No | 1/D |
| 1 | 4 | Classroom 431 | N/A | Wood Floor | | Non Suspect ACM | 720 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 4 | Classroom 431 | N/A | Plaster Walls | | NAD | 1512 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 4 | Classroom 431 | N/A | Plaster Ceiling | | NAD | 720 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 4 | Classroom 431 | T | Pipe Insulation 2-6 inch | 7020/01/04/60 | Confirmed | 28 | LF | 0 | LF | | | | 1 | No | 1/D |
| 1 | 4 | Classroom 431 | M | Blackboard Glue Dots | 7020/01/04/BATTA/AH/2600 | Assumed | 128 | SF | 0 | SF | | | | 1 | No | 1/D |
| 1 | 4 | Classroom 429 | N/A | Wood Floor | | Non Suspect ACM | 720 | SF | 0 | SF | | | | N/A | N/A | N/A |

7020 Olney HS (ASPIRA) 2015 2016 AHERA Three-Year Report.xls

| School District of Philadelphia Aspira Olney Charter High School 100 E. Duncannon Street, Philadelphia, PA 19120 ULCS# 7029 Year Built: 1931 | | | AHERA Three-Year Reinspection 2015-2016 Room by Room Location Log Report | | | | | | | | | | Reinspection Date: December 13, 2015 Building Inspector: James Madden Number: 030867 Management Planner: Megan Vala Number: 740728 | | | | |
|--|-----------------------|---|---|----------------------------|---------------------------|---|-----------------------|-------------|---------------------|-------------|------------------------------|----------------------------|--|-----------------------------|--------------------------|-------------------------|--|
| E l e m e n t | F l o o r | On Site Room Name | System Affected | Material Description | HID# | Confirmed/Assumed/NAD/ Non Suspect ACM | Amount of Material | SF LF EA | Amount of Damage | SF LF EA | Color required for VAT | Comments/Description/Notes | Attic/ Crawl Space Ranking | Damage Potential (DP) | Newly Friable (NF) | Response Action (RA) | |
| 1 | 4 | Classroom 429 | N/A | Plaster Walls | | NAD | 1512 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 4 | Classroom 429 | N/A | Plaster Ceiling | | NAD | 720 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 4 | Classroom 429 | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 10 | LF | 5 | LF | | | | N/A | N/A | N/A | |
| 1 | 4 | Classroom 429 | T | Pipe Insulation 2-6 inch | 7020/01/04/60 | Confirmed | 14 | LF | 0 | LF | | | | 1 | No | 1/D | |
| 1 | 4 | Classroom 429 | M | Blackboard Glue Dots | 7020/01/04/BATT A/AH/2600 | Assumed | 120 | SF | 0 | SF | | | | 1 | No | 1/D | |
| 1 | 4 | Storage Room two Doors Down from Classroom 423 | N/A | Wood Floor | | Non Suspect ACM | 60 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 4 | Storage Room two Doors Down from Classroom 423 | N/A | Plaster Walls | | NAD | 532 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 4 | Storage Room two Doors Down from Classroom 423 | N/A | Plaster Ceiling | | NAD | 60 | SF | 5 | SF | | | | N/A | N/A | N/A | |
| 1 | 4 | Teacher Copy Room next to Classroom 423 | M | Linoleum | 7020/01/04/OO | Assumed | 338 | SF | 0 | SF | Grey | Painted Grey | | 1 | No | 1/D | |
| 1 | 4 | Teacher Copy Room next to Classroom 423 | N/A | Plaster Walls | | NAD | 1092 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 4 | Teacher Copy Room next to Classroom 423 | N/A | Plaster Ceiling | | NAD | 338 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 4 | Restroom in Teacher Copy Room next to Classroom 426 | N/A | Cement Floor | | Non Suspect ACM | 75 | SF | 0 | SF | | Door Screwed Shut | | N/A | N/A | N/A | |
| 1 | 4 | Restroom in Teacher Copy Room next to Classroom 426 | N/A | Plaster Ceiling | | NAD | 75 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 4 | Restroom in Teacher Copy Room next to Classroom 426 | N/A | Plaster Walls | | NAD | 200 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 4 | Restroom in Teacher Copy Room next to Classroom 426 | T | Pipe Insulation 2-6 inch | 7020/01/04/60 | Confirmed | 15 | LF | 0 | LF | | | | 1 | No | 1/D | |
| 1 | 4 | Classroom 423 | N/A | Plaster Walls | | NAD | 1792 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 4 | Classroom 423 | N/A | Plaster Ceiling | | NAD | 960 | SF | 5 | SF | | | | N/A | N/A | N/A | |
| 1 | 4 | Classroom 423 | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 6 | LF | 2 | LF | | | | N/A | N/A | N/A | |
| 1 | 4 | Classroom 423 | T | Pipe Insulation 2-6 inch | 7020/01/04/60 | Confirmed | 14 | LF | 0 | LF | | | | 1 | No | 1/D | |
| 1 | 4 | Classroom 423 | M | Blackboard Glue Dots | 7020/01/04/BATT A/AH/2600 | Assumed | 64 | SF | 0 | SF | | | | 1 | No | 1/D | |
| 1 | 4 | Classroom 423 | N/A | Wood Floor | | Non Suspect ACM | 960 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 4 | Classroom 421 | N/A | Plaster Walls | | NAD | 1456 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 4 | Classroom 421 | N/A | Plaster Ceiling | | NAD | 675 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 4 | Classroom 421 | T | Pipe Insulation 2-6 inch | 7020/01/04/60 | Confirmed | 28 | LF | 2 | LF | | | | 1 | Yes | 5/A | |
| 1 | 4 | Classroom 421 | M | Blackboard Glue Dots | 7020/01/04/BATT A/AH/2600 | Assumed | 120 | SF | 0 | SF | | | | 1 | No | 1/D | |
| 1 | 4 | Classroom 421 | N/A | Wood Floor | | Non Suspect ACM | 675 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 4 | Resource Room 419 | N/A | Wood Floor | | Non Suspect ACM | 576 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 4 | Resource Room 419 | N/A | Plaster Walls | | NAD | 1344 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 4 | Resource Room 419 | N/A | Plaster Ceiling | | NAD | 576 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 4 | Resource Room 419 | T | Pipe Insulation 2-6 inch | 7020/01/04/60 | Confirmed | 14 | LF | 0 | LF | | | | 1 | No | 1/D | |
| 1 | 4 | Resource Room 419 | M | Blackboard Glue Dots | 7020/01/04/BATT A/AH/2600 | Assumed | 64 | SF | 0 | SF | | | | 1 | No | 1/D | |
| 1 | 4 | Guidance Office Room 417 | N/A | Wood Floor | | Non Suspect ACM | 416 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 4 | Guidance Office Room 417 | N/A | Plaster Walls | | NAD | 1176 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 4 | Guidance Office Room 417 | N/A | Plaster Ceiling | | NAD | 416 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 4 | Guidance Office Room 417 | T | Pipe Insulation 2-6 inch | 7020/01/04/60 | Confirmed | 14 | LF | 0 | LF | | | | 1 | No | 1/D | |
| 1 | 4 | Guidance Office Room 417 Closet Closest to Door | N/A | Wood Floor | | Non Suspect ACM | 21 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 4 | Guidance Office Room 417 Closet Closest to Door | N/A | Plaster Walls | | NAD | 280 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 4 | Guidance Office Room 417 Closet Closest to Door | N/A | Plaster Ceiling | | NAD | 21 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 4 | Guidance Office Room 417 Closet Second from Door | N/A | Wood Floor | | Non Suspect ACM | 21 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 4 | Guidance Office Room 417 Closet Second from Door | N/A | Plaster Walls | | NAD | 280 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 4 | Guidance Office Room 417 Closet Second from Door | N/A | Plaster Ceiling | | NAD | 21 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 4 | Office Room 415 | N/A | Wood Floor | | Non Suspect ACM | 336 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 4 | Office Room 415 | N/A | Plaster Walls | | NAD | 1064 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 4 | Office Room 415 | N/A | Plaster Ceiling | | NAD | 336 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 4 | Office Room 415 | T | Pipe Insulation 2-6 inch | 7020/01/04/60 | Confirmed | 14 | LF | 0 | LF | | | | 1 | No | 1/D | |
| 1 | 4 | Drama Room 413 | N/A | Wood Floor | | Non Suspect ACM | 1248 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 4 | Drama Room 413 | N/A | Plaster Walls | | NAD | 2072 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 4 | Drama Room 413 | N/A | Plaster Ceiling | | NAD | 1248 | SF | 5 | SF | | | | N/A | N/A | N/A | |
| 1 | 4 | Drama Room 413 | T | Pipe Insulation 2-6 inch | 7020/01/04/60 | Confirmed | 56 | LF | 0 | LF | | | | 1 | No | 1/D | |
| 1 | 4 | Drama Room 413 | M | Blackboard Glue Dots | 7020/01/04/BATT A/AH/2600 | Assumed | 120 | SF | 0 | SF | | | | 1 | No | 1/D | |
| 1 | 4 | Classroom 411 | N/A | Wood Floor | | Non Suspect ACM | 1472 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 4 | Classroom 411 | N/A | Plaster Walls | | NAD | 2184 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 4 | Classroom 411 | N/A | Plaster Ceiling | | NAD | 1472 | SF | 10 | SF | | | | N/A | N/A | N/A | |
| 1 | 4 | Classroom 411 | T | Pipe Insulation 2-6 inch | 7020/01/04/60 | Confirmed | 46 | LF | 0 | LF | | | | 1 | No | 1/D | |
| 1 | 4 | Classroom 411 | T | Pipe Insulation > 6 inch | 7020/01/04/BATT A/AH/1110 | Confirmed | 2 | LF | 0 | LF | | | | 1 | No | 1/D | |
| 1 | 4 | Classroom 411 | M | Pipe Fitting Insulation | 7020/01/04/68 | Confirmed | 4 | EA | 0 | EA | | | | 1 | No | 1/D | |
| 1 | 4 | Classroom 411 | M | Blackboard Glue Dots | 7020/01/04/BATT A/AH/2600 | Assumed | 128 | SF | 0 | SF | | | | 1 | No | 1/D | |
| 1 | 4 | Classroom 409 | N/A | Wood Floor | | Non Suspect ACM | 650 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 4 | Classroom 409 | N/A | Plaster Walls | | NAD | 1428 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 4 | Classroom 409 | N/A | Plaster Ceiling | | NAD | 650 | SF | 5 | SF | | | | N/A | N/A | N/A | |
| 1 | 4 | Classroom 409 | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 6 | LF | 0 | LF | | | | N/A | N/A | N/A | |
| 1 | 4 | Classroom 409 | M | Blackboard Glue Dots | 7020/01/04/BATT A/AH/2600 | Assumed | 64 | SF | 0 | SF | | | | 1 | No | 1/D | |
| 1 | 4 | Classroom 405 | N/A | Wood Floor | | Non Suspect ACM | 500 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 4 | Classroom 405 | N/A | Plaster Walls | | NAD | 1000 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 4 | Classroom 405 | N/A | Plaster Ceiling | | NAD | 500 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 4 | Classroom 405 | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 24 | LF | 5 | LF | | | | N/A | N/A | N/A | |
| 1 | 4 | Classroom 405 | M | Blackboard Glue Dots | 7020/01/04/BATT A/AH/2600 | Assumed | 80 | SF | 0 | SF | | | | 1 | No | 1/D | |
| 1 | 4 | Classroom 405 | N/A | Sheetrock Wall | | Non Suspect ACM | 336 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 4 | Music Room 467 | N/A | Wood Floor | | Non Suspect ACM | 1681 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 4 | Music Room 467 | N/A | Plaster Walls | | NAD | 2296 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 4 | Music Room 467 | N/A | Plaster Ceiling | | NAD | 800 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | 4 | Music Room 467 | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 30 | LF | 5 | LF | | | | N/A | N/A | N/A | |

7020 Olney HS (ASPIRA) 2015 2016 AHERA Three-Year Report.xls

| | | School District of Philadelphia Aspira Olney Charter High School 100 E. Duncannon Street, Philadelphia, PA 19120 ULCS# 7029 Year Built: 1931 | AHERA Three-Year Reinspection 2015-2016 Room by Room Location Log Report | | | | | | | | | | Reinspection Date: December 13, 2015 Building Inspector: James Madden Number: 030867 Management Planner: Megan Vala Number: 740728 | | | | | | | |
|---------------------------------|-----------------------|--|---|--------------------------|--------------------------|---|-----------------------|----------------|---------------------|----------------|------------------------------|--|--|-----------------------------|--------------------------|-------------------------|--|--|--|--|
| E l e m e n t | F l o o r | On Site Room Name | System Affected | Material Description | HID# | Confirmed/Assumed/NAD/ Non Suspect ACM | Amount of Material | SF LF EA | Amount of Damage | SF LF EA | Color required for VAT | Comments/Description/Notes | Attic/ Crawl Space Ranking | Damage Potential (DP) | Newly Friable (NF) | Response Action (RA) | | | | |
| 1 | 4 | Music Room 467 | T | Pipe Insulation 2-6 inch | 7020/01/04/60 | Confirmed | 36 | LF | 0 | LF | | | | 1 | No | 1/D | | | | |
| 1 | 4 | Music Room 467 | N/A | Ceiling Tile 2' x 4' | | NAD | 800 | SF | 0 | SF | | | | N/A | N/A | N/A | | | | |
| 1 | 4 | Stairwell #3 | N/A | Cement Floor | | Non Suspect ACM | 312 | SF | 0 | SF | | | | N/A | N/A | N/A | | | | |
| 1 | 4 | Stairwell #3 | N/A | Plaster Walls | | NAD | 1480 | SF | 0 | SF | | | | N/A | N/A | N/A | | | | |
| 1 | 4 | Stairwell #3 | N/A | Concrete Ceiling | | Non Suspect ACM | 312 | SF | 0 | SF | | | | N/A | N/A | N/A | | | | |
| 1 | 4 | Stairwell #3 | T | Pipe Insulation 2-6 inch | 7020/01/04/60 | Confirmed | 28 | LF | 0 | LF | | | | 1 | No | 1/D | | | | |
| 1 | 4 | Staff Restroom and Storage Room across from Office 455 | N/A | Cement Floor | | Non Suspect ACM | 338 | SF | 0 | SF | | | | N/A | N/A | N/A | | | | |
| 1 | 4 | Staff Restroom and Storage Room across from Office 455 | N/A | Plaster Walls | | NAD | 1092 | SF | 0 | SF | | | | N/A | N/A | N/A | | | | |
| 1 | 4 | Staff Restroom and Storage Room across from Office 455 | N/A | Concrete Ceiling | | Non Suspect ACM | 338 | SF | 0 | SF | | | | N/A | N/A | N/A | | | | |
| 1 | 4 | Staff Restroom and Storage Room across from Office 455 | T | Pipe Insulation 2-6 inch | 7020/01/04/60 | Confirmed | 16 | LF | 0 | LF | | | | 1 | No | 1/D | | | | |
| 1 | 4 | Staff Restroom and Storage Room across from Office 455 | T | Pipe Insulation > 6 inch | 7020/01/04/BATTA/AH/1110 | Assumed | 14 | LF | 0 | LF | | | | 1 | No | 1/D | | | | |
| 1 | 4 | Staff Restroom and Storage Room across from Office 455 | T | Pipe Fitting Insulation | 7020/01/04/68 | Assumed | 6 | EA | 0 | EA | | | | 1 | No | 1/D | | | | |
| 1 | 4 | Copy Room across from Computer Room 453 | M | Floor Tile VAT 9" x 9" | 7020/01/04/63 | Confirmed | 234 | SF | 1 | SF | Tan | | | 1 | Yes | 5/B | | | | |
| 1 | 4 | Copy Room across from Computer Room 453 | N/A | Plaster Walls | | NAD | 420 | SF | 0 | SF | | | | N/A | N/A | N/A | | | | |
| 1 | 4 | Copy Room across from Computer Room 453 | N/A | Ceiling Tile 2' x 4' | | NAD | 234 | SF | 40 | SF | | | | N/A | N/A | N/A | | | | |
| 1 | 4 | Copy Room across from Computer Room 453 | N/A | Concrete Block Wall | | Non Suspect ACM | 420 | SF | 0 | SF | | | | N/A | N/A | N/A | | | | |
| 1 | 4 | Copy Room across from Computer Room 453 | T | Pipe Insulation 2-6 inch | 7020/01/04/60 | Confirmed | 14 | LF | 0 | LF | | | | 1 | No | 1/D | | | | |
| 1 | 4 | Classroom 454 | M | Floor Tile VAT 9" x 9" | 7020/01/04/63 | Confirmed | 713 | SF | 0 | SF | Tan | | | 1 | No | 1/D | | | | |
| 1 | 4 | Classroom 454 | N/A | Plaster Walls | | NAD | 1296 | SF | 0 | SF | | | | N/A | N/A | N/A | | | | |
| 1 | 4 | Classroom 454 | N/A | Ceiling Tile 2' x 4' | | NAD | 713 | SF | 0 | SF | | | | N/A | N/A | N/A | | | | |
| 1 | 4 | Classroom 454 | N/A | Concrete Block Wall | | Non Suspect ACM | 896 | SF | 0 | SF | | | | N/A | N/A | N/A | | | | |
| 1 | 4 | Classroom 454 | T | Pipe Insulation 2-6 inch | 7020/01/04/60 | Confirmed | 28 | LF | 0 | LF | | | | 1 | No | 1/D | | | | |
| 1 | 4 | Classroom 454 | N/A | Brick Wall | | Non Suspect ACM | 400 | SF | 0 | SF | | | | N/A | N/A | N/A | | | | |
| 1 | 4 | Classroom 454 | M | Partition Room Dividers | 7020/01/04/BATTA/AH/2607 | Assumed | 240 | SF | 0 | SF | | | | 1 | No | 1/D | | | | |
| 1 | 4 | Room attached to Classroom 452 | M | Floor Tile VAT 9" x 9" | 7020/01/04/63 | Confirmed | 550 | SF | 0 | SF | Tan | Empty; Through a partition | | 1 | No | 1/D | | | | |
| 1 | 4 | Room attached to Classroom 452 | N/A | Plaster Walls | | NAD | 1024 | SF | 0 | SF | | Empty; Through a partition | | N/A | N/A | N/A | | | | |
| 1 | 4 | Room attached to Classroom 452 | N/A | Ceiling Tile 2' x 4' | | NAD | 650 | SF | 0 | SF | | Empty; Through a partition | | N/A | N/A | N/A | | | | |
| 1 | 4 | Room attached to Classroom 452 | N/A | Concrete Block Wall | | Non Suspect ACM | 1224 | SF | 0 | SF | | Empty; Through a partition | | N/A | N/A | N/A | | | | |
| 1 | 4 | Room attached to Classroom 452 | T | Pipe Insulation 2-6 inch | 7020/01/04/60 | Confirmed | 24 | LF | 0 | LF | | Empty; Through a partition | | 1 | No | 1/D | | | | |
| 1 | 4 | Room attached to Classroom 452 | N/A | Brick Wall | | Non Suspect ACM | 400 | SF | 0 | SF | | Empty; Through a partition | | N/A | N/A | N/A | | | | |
| 1 | 4 | Room attached to Classroom 452 | M | Partition Room Dividers | 7020/01/04/BATTA/AH/2607 | Assumed | 240 | SF | 0 | SF | | Empty; Through a partition | | 1 | No | 1/D | | | | |
| 1 | 4 | Room attached to Classroom 452 | M | Blackboard Glue Dots | 7020/01/04/BATTA/AH/2600 | Assumed | 128 | SF | 0 | SF | | Empty; Through a partition | | 1 | No | 1/D | | | | |
| 1 | 4 | Room attached to Classroom 452 Closet | M | Floor Tile VAT 9" x 9" | 7020/01/04/63 | Confirmed | 40 | SF | 0 | SF | Tan | Empty; Through a partition | | 1 | No | 1/D | | | | |
| 1 | 4 | Room attached to Classroom 452 Closet | N/A | Plaster Walls | | NAD | 280 | SF | 0 | SF | | Empty; Through a partition | | N/A | N/A | N/A | | | | |
| 1 | 4 | Room attached to Classroom 452 Closet | N/A | Ceiling Tile 2' x 4' | | NAD | 40 | SF | 0 | SF | | Empty; Through a partition | | N/A | N/A | N/A | | | | |
| 1 | 4 | Art Supply Closet across from Classroom 449 | M | Floor Tile VAT 9" x 9" | 7020/01/04/63 | Confirmed | 64 | SF | 0 | SF | | No access (Fall 2016) | | 1 | No | 1/D | | | | |
| 1 | 4 | Art Supply Closet across from Classroom 449 | N/A | Concrete Block Wall | | Non Suspect ACM | 150 | SF | 0 | SF | | | | N/A | N/A | N/A | | | | |
| 1 | 4 | Art Supply Closet across from Classroom 449 | N/A | Plaster Walls | | NAD | 150 | SF | 0 | SF | | | | N/A | N/A | N/A | | | | |
| 1 | 4 | Art Supply Closet across from Classroom 449 | N/A | Brick Wall | | Non Suspect ACM | 60 | SF | 0 | SF | | | | N/A | N/A | N/A | | | | |
| 1 | 4 | Art Supply Closet across from Classroom 449 | N/A | Ceiling Tile 2' x 4' | | NAD | 64 | SF | 0 | SF | | | | N/A | N/A | N/A | | | | |
| 1 | 4 | Custodial Closet across from Room 449 and next to Girl's Restroom | N/A | Cement Floor | | Non Suspect ACM | 16 | SF | 0 | SF | | | | N/A | N/A | N/A | | | | |
| 1 | 4 | Custodial Closet across from Room 449 and next to Girl's Restroom | N/A | Plaster Walls | | NAD | 224 | SF | 0 | SF | | | | N/A | N/A | N/A | | | | |
| 1 | 4 | Custodial Closet across from Room 449 and next to Girl's Restroom | N/A | Concrete Ceiling | | Non Suspect ACM | 16 | SF | 0 | SF | | | | N/A | N/A | N/A | | | | |
| 1 | 4 | Girl's Restroom | N/A | Cement Floor | | Non Suspect ACM | 520 | SF | 0 | SF | | No access (Fall 2016) | | N/A | N/A | N/A | | | | |
| 1 | 4 | Girl's Restroom | N/A | Plaster Walls | | NAD | 1288 | SF | 0 | SF | | | | N/A | N/A | N/A | | | | |
| 1 | 4 | Girl's Restroom | N/A | Plaster Ceiling | | NAD | 520 | SF | 4 | SF | | Cracking Forming across Room, some discoloration from water damage | | N/A | N/A | N/A | | | | |
| 1 | 4 | Girl's Restroom | T | Pipe Fitting Insulation | 7020/01/04/68 | Assumed | 8 | EA | 0 | EA | | | | 1 | No | 1/D | | | | |
| 1 | 4 | Girl's Restroom | T | Pipe Insulation > 6 inch | 7020/01/04/BATTA/AH/1110 | Assumed | 25 | LF | 0 | LF | | | | 1 | No | 1/D | | | | |
| 1 | 4 | Girl's Restroom | T | Pipe Insulation 2-6 inch | 7020/01/04/60 | Confirmed | 36 | LF | 0 | LF | | | | 1 | No | 1/D | | | | |
| 1 | 4 | Custodial Closet across from Classroom 421 | N/A | Cement Floor | | Non Suspect ACM | 16 | SF | 0 | SF | | | | N/A | N/A | N/A | | | | |
| 1 | 4 | Custodial Closet across from Classroom 421 | N/A | Plaster Walls | | NAD | 224 | SF | 0 | SF | | | | N/A | N/A | N/A | | | | |
| 1 | 4 | Custodial Closet across from Classroom 421 | N/A | Concrete Ceiling | | Non Suspect ACM | 16 | SF | 0 | SF | | | | N/A | N/A | N/A | | | | |
| 1 | 4 | Boy's Restroom | N/A | Cement Floor | | Non Suspect ACM | 546 | SF | 0 | SF | | | | N/A | N/A | N/A | | | | |
| 1 | 4 | Boy's Restroom | N/A | Plaster Walls | | NAD | 1316 | SF | 0 | SF | | | | N/A | N/A | N/A | | | | |
| 1 | 4 | Boy's Restroom | N/A | Plaster Ceiling | | NAD | 546 | SF | 0 | SF | | | | N/A | N/A | N/A | | | | |
| 1 | 4 | Boy's Restroom | T | Pipe Fitting Insulation | 7020/01/04/68 | Assumed | 11 | EA | 0 | EA | | | | 1 | No | 1/D | | | | |
| 1 | 4 | Boy's Restroom | T | Pipe Insulation > 6 inch | 7020/01/04/BATTA/AH/1110 | Assumed | 25 | LF | 0 | LF | | | | 1 | No | 1/D | | | | |
| 1 | 4 | Boy's Restroom | T | Pipe Insulation 2-6 inch | 7020/01/04/60 | Confirmed | 33 | LF | 0 | LF | | | | 1 | No | 1/D | | | | |
| 1 | 4 | Classroom 418 | M | Floor Tile VAT 9" x 9" | 7020/01/04/63 | Confirmed | 754 | SF | 0 | SF | Brown | | | 1 | No | 1/D | | | | |
| 1 | 4 | Classroom 418 | N/A | Plaster Walls | | NAD | 920 | SF | 0 | SF | | | | N/A | N/A | N/A | | | | |
| 1 | 4 | Classroom 418 | N/A | Ceiling Tile 2' x 4' | | NAD | 754 | SF | 0 | SF | | | | N/A | N/A | N/A | | | | |
| 1 | 4 | Classroom 418 | T | Pipe Fitting Insulation | 7020/01/04/68 | Assumed | 8 | EA | 0 | EA | | | | 1 | No | 1/D | | | | |
| 1 | 4 | Classroom 418 | T | Pipe Insulation 2-6 inch | 7020/01/04/60 | Confirmed | 33 | LF | 0 | LF | | | | 1 | No | 1/D | | | | |
| 1 | 4 | Classroom 418 | N/A | Brick Wall | | Non Suspect ACM | 400 | SF | 0 | SF | | | | N/A | N/A | N/A | | | | |
| 1 | 4 | Classroom 416 | M | Blackboard Glue Dots | 7020/01/04/BATTA/AH/2600 | Assumed | 64 | SF | 0 | SF | | | | 1 | No | 1/D | | | | |

7020 Olney HS (ASPIRA) 2015 2016 AHERA Three-Year Report.xls

| | | School District of Philadelphia Aspira Olney Charter High School 100 E. Duncannon Street, Philadelphia, PA 19120 ULCS# 7029 Year Built: 1931 | AHERA Three-Year Reinspection 2015-2016 Room by Room Location Log Report | | | | | | | | | | Reinspection Date: December 13, 2015 Building Inspector: James Madden Number: 030867 Management Planner: Megan Vala Number: 740728 | | | | | | | |
|---------------------------------|-----------------------|--|---|----------------------------|--------------------------|---|-----------------------|----------------|---------------------|----------------|------------------------------|--|--|-----------------------------|--------------------------|-------------------------|--|--|--|--|
| E l e m e n t | F l o o r | On Site Room Name | System Affected | Material Description | HID# | Confirmed/Assumed/NAD/ Non Suspect ACM | Amount of Material | SF LF EA | Amount of Damage | SF LF EA | Color required for VAT | Comments/Description/Notes | Attic/ Crawl Space Ranking | Damage Potential (DP) | Newly Friable (NF) | Response Action (RA) | | | | |
| 1 | 4 | Classroom 416 | N/A | Ceiling Tile 2' x 4' | | NAD | 780 | SF | 0 | SF | | | | N/A | N/A | N/A | | | | |
| 1 | 4 | Classroom 416 | T | Pipe Fitting Insulation | 7020/01/04/68 | Assumed | 10 | EA | 0 | EA | | | | 1 | No | 1/D | | | | |
| 1 | 4 | Classroom 416 | T | Pipe Insulation 2-6 inch | 7020/01/04/60 | Confirmed | 56 | LF | 0 | LF | | | | 1 | No | 1/D | | | | |
| 1 | 4 | Classroom 416 | N/A | Brick Wall | | Non Suspect ACM | 1344 | SF | 0 | SF | | | | N/A | N/A | N/A | | | | |
| 1 | 4 | Classroom 416 | M | Floor Tile VAT 9" x 9" | 7020/01/04/63 | Confirmed | 780 | SF | 0 | SF | brown | | | 1 | No | 1/D | | | | |
| 1 | 4 | Office 414 | N/A | Ceiling Tile 2' x 4' | | NAD | 250 | SF | 0 | SF | | | | N/A | N/A | N/A | | | | |
| 1 | 4 | Office 414 | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 15 | LF | 2 | LF | | | | N/A | N/A | N/A | | | | |
| 1 | 4 | Office 414 | N/A | Brick Wall | | Non Suspect ACM | 150 | SF | 0 | SF | | | | N/A | N/A | N/A | | | | |
| 1 | 4 | Office 414 | M | Floor Tile VAT 9" x 9" | 7020/01/04/63 | Confirmed | 250 | SF | 0 | SF | brown | | | 1 | No | 1/D | | | | |
| 1 | 4 | Storage Closet across from Room 411 | X | X | | X | X | X | X | X | | Sealed shut | | X | X | X | | | | |
| 1 | 4 | Hallway from Classrooms 429 to 439 | N/A | Cement Floor | | Non Suspect ACM | 3240 | SF | 0 | SF | | | | N/A | N/A | N/A | | | | |
| 1 | 4 | Hallway from Classrooms 429 to 439 | N/A | Plaster Walls | | NAD | 7896 | SF | 0 | SF | | | | N/A | N/A | N/A | | | | |
| 1 | 4 | Hallway from Classrooms 429 to 439 | N/A | Ceiling Tile 2' x 4' | | NAD | 3240 | SF | 0 | SF | | | | N/A | N/A | N/A | | | | |
| 1 | 4 | Hallway from Classrooms 429 to 439 | N/A | Ceiling Tile 1' x 1' | | NAD | 3240 | SF | 0 | SF | | | | N/A | N/A | N/A | | | | |
| 1 | 4 | Hallway from Classrooms 429 to 439 | T | Pipe Insulation 2-6 inch | 7020/01/04/60 | Confirmed | 105 | SF | 0 | SF | | | | 1 | No | 1/D | | | | |
| 1 | 4 | Hallway from Classrooms 429 to 439 | T | Pipe Fitting Insulation | 7020/01/04/68 | Assumed | 8 | SF | 0 | SF | | | | 1 | No | 1/D | | | | |
| 1 | 4 | Hallway from Classrooms 429 to 439 | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 25 | SF | 0 | SF | | | | N/A | N/A | N/A | | | | |
| 1 | 4 | Hallway from Classrooms 447 to 457 | N/A | Cement Floor | | Non Suspect ACM | 3240 | LF | 0 | LF | | | | N/A | N/A | N/A | | | | |
| 1 | 4 | Hallway from Classrooms 447 to 457 | N/A | Plaster Walls | | NAD | 7896 | EA | 0 | EA | | | | N/A | N/A | N/A | | | | |
| 1 | 4 | Hallway from Classrooms 447 to 457 | N/A | Ceiling Tile 2' x 4' | | NAD | 3240 | LF | 0 | LF | | | | N/A | N/A | N/A | | | | |
| 1 | 4 | Hallway from Classrooms 461 to 409 | N/A | Cement Floor | | Non Suspect ACM | 7896 | LF | 0 | LF | | | | N/A | N/A | N/A | | | | |
| 1 | 4 | Hallway from Classrooms 461 to 409 | N/A | Plaster Walls | | NAD | 2430 | SF | 0 | SF | | | | N/A | N/A | N/A | | | | |
| 1 | 4 | Hallway from Classrooms 461 to 409 | N/A | Marble Walls | | Non Suspect ACM | 810 | SF | 0 | SF | | | | N/A | N/A | N/A | | | | |
| 1 | 4 | Hallway from Classrooms 461 to 409 | N/A | Ceiling Tile 2' x 4' | | NAD | 3240 | LF | 0 | LF | | | | N/A | N/A | N/A | | | | |
| 1 | 4 | Hallway from Classrooms 461 to 409 | T | Pipe Insulation 2-6 inch | 7020/01/04/60 | Confirmed | 60 | SF | 0 | SF | | | | 1 | No | 1/D | | | | |
| 1 | 4 | Hallway from Classrooms 461 to 409 | T | Pipe Fitting Insulation | 7020/01/04/68 | Assumed | 6 | SF | 0 | SF | | | | 1 | No | 1/D | | | | |
| 1 | 4 | Hallway from Classrooms 461 to 409 | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 120 | SF | 0 | SF | | | | N/A | N/A | N/A | | | | |
| 1 | 4 | Hallway from Classrooms 411 to 423 | N/A | Cement Floor | | Non Suspect ACM | 2000 | SF | 0 | SF | | | | N/A | N/A | N/A | | | | |
| 1 | 4 | Hallway from Classrooms 411 to 423 | N/A | Plaster Walls | | NAD | 3000 | SF | 0 | SF | | | | N/A | N/A | N/A | | | | |
| 1 | 4 | Hallway from Classrooms 411 to 423 | N/A | Marble Walls | | Non Suspect ACM | 1000 | SF | 0 | SF | | | | N/A | N/A | N/A | | | | |
| 1 | 4 | Hallway from Classrooms 411 to 423 | N/A | Ceiling Tile 2' x 4' | | NAD | 2040 | LF | 40 | LF | | | | N/A | N/A | N/A | | | | |
| 1 | 5 | Secured Hallway | N/A | Cement Floor | | Non Suspect ACM | 1300 | SF | 0 | SF | | No access (Fall 2016) | | N/A | N/A | N/A | | | | |
| 1 | 5 | Secured Hallway | N/A | Plaster Walls | | NAD | 2800 | SF | 0 | SF | | | | N/A | N/A | N/A | | | | |
| 1 | 5 | Secured Hallway | N/A | Plaster Ceiling | | NAD | 1300 | SF | 40 | SF | | | | N/A | N/A | N/A | | | | |
| 1 | 5 | Secured Hallway | N/A | Ceiling Tile 1' x 1' | | NAD | 1300 | SF | 70 | SF | | | | N/A | N/A | N/A | | | | |
| 1 | 5 | Secured Hallway | N/A | Ceiling Tile 2' x 4' | | NAD | 1300 | SF | 0 | SF | | | | N/A | N/A | N/A | | | | |
| 1 | 5 | Secured Hallway | T | Pipe Insulation > 6 inch | 7020/01/05/51 | Confirmed | 95 | LF | 0 | LF | | | | 1 | No | 1/D | | | | |
| 1 | 5 | Secured Hallway | T | Pipe Insulation 2-6 inch | 7020/01/05/52 | Confirmed | 60 | LF | 0 | LF | | | | 1 | No | 1/D | | | | |
| 1 | 5 | Secured Hallway | T | Pipe Fitting Insulation | 7020/01/05/71 | Assumed | 19 | EA | 0 | EA | | | | 1 | No | 1/D | | | | |
| 1 | 5 | Fan Room attached to Secured Hallway 5th Floor | N/A | Concrete Ceiling | | Non Suspect ACM | 350 | SF | 0 | SF | | No access this inspection | | N/A | N/A | N/A | | | | |
| 1 | 5 | Fan Room attached to Secured Hallway 5th Floor | N/A | Brick Wall | | Non Suspect ACM | 1170 | SF | 0 | SF | | | | N/A | N/A | N/A | | | | |
| 1 | 5 | Fan Room attached to Secured Hallway 5th Floor | N/A | Cement Floor | | Non Suspect ACM | 350 | SF | 0 | SF | | | | N/A | N/A | N/A | | | | |
| 1 | 5 | Fan Room attached to Secured Hallway 5th Floor | M | Vibration Damper Cloth | 7020/01/05/55 | Assumed | 12 | SF | 0 | SF | | | | 1 | No | 1/D | | | | |
| 1 | 5 | Fan Room attached to Secured Hallway 5th Floor | M | Transite Electrical Panel | 7020/01/05/BATTA/AH/2350 | Assumed | 16 | SF | 0 | SF | | | | 1 | No | 1/D | | | | |
| 1 | 5 | Dry Sandpipe For Fire Department Use Only, Access located at the top of 5th floor stairwell | N/A | Concrete Ceiling | | Non Suspect ACM | 375 | SF | 0 | SF | | No access (Fall 2016) | | N/A | N/A | N/A | | | | |
| 1 | 5 | Dry Sandpipe For Fire Department Use Only, Access located at the top of 5th floor stairwell | N/A | Cement Floor | | Non Suspect ACM | 375 | SF | 0 | SF | | | | N/A | N/A | N/A | | | | |
| 1 | 5 | Dry Sandpipe For Fire Department Use Only, Access located at the top of 5th floor stairwell | N/A | Brick Wall | | Non Suspect ACM | 960 | SF | 0 | SF | | | | N/A | N/A | N/A | | | | |
| 1 | 5 | Dry Sandpipe For Fire Department Use Only, Access located at the top of 5th floor stairwell | T | Pipe Insulation 2-6 inch | 7020/01/05/52 | Confirmed | 12 | LF | 0 | LF | | | | 1 | No | 1/D | | | | |
| 1 | 5 | Dry Sandpipe For Fire Department Use Only, Access located at the top of 5th floor stairwell | T | Pipe Fitting Insulation | 7020/01/05/71 | Assumed | 4 | EA | 0 | EA | | | | 1 | No | 1/D | | | | |
| 1 | 5 | Stairwell leading to abandoned 5th Floor | N/A | Plaster Ceiling | | NAD | X | SF | 0 | SF | | No material? - Inspector please verify - No access (Fall 2016) | | N/A | N/A | N/A | | | | |
| 1 | 5 | Stairwell leading to abandoned 5th Floor | N/A | Cement Floor | | Non Suspect ACM | X | SF | 0 | SF | | No material? - Inspector please verify | | N/A | N/A | N/A | | | | |
| 1 | 5 | Stairwell leading to abandoned 5th Floor | N/A | Plaster Walls | | NAD | X | SF | 4 | SF | | No material? - Inspector please verify | | N/A | N/A | N/A | | | | |
| 1 | 5 | Stairwell leading to abandoned 5th Floor | T | Pipe Insulation 2-6 inch | 7020/01/05/52 | Confirmed | 25 | LF | 0 | LF | | | | 1 | No | 1/D | | | | |
| 1 | 5 | Stairwell leading to abandoned 5th Floor | T | Pipe Fitting Insulation | 7020/01/05/71 | Assumed | 4 | EA | 4 | EA | | | | 1 | Yes | 5/B | | | | |
| 1 | 5 | Stairwell leading to abandoned 5th Floor | T | Pipe Insulation > 6 inch | 7020/01/05/51 | Confirmed | 20 | LF | 1 | LF | | | | 1 | Yes | 5/B | | | | |
| 1 | 5 | Classroom 506 | N/A | Wood Floor | | Non Suspect ACM | 1020 | SF | 0 | SF | | Currently used for Storage | | N/A | N/A | N/A | | | | |
| 1 | 5 | Classroom 506 | N/A | Plaster Walls | | NAD | 1536 | SF | 0 | SF | | Currently used for Storage | | N/A | N/A | N/A | | | | |
| 1 | 5 | Classroom 506 | N/A | Ceiling Tile 2' x 4' | | NAD | 1020 | SF | 0 | SF | | Currently used for Storage | | N/A | N/A | N/A | | | | |
| 1 | 5 | Classroom 506 | M | Transite Sink | 7020/01/05/BATTA/AH/2340 | Assumed | 24 | SF | 0 | SF | | Currently used for Storage | | 1 | No | 1/D | | | | |
| 1 | 5 | Classroom 506 | M | Transite Counter Tops | 7020/01/05/QQ | Assumed | 270 | SF | 0 | SF | | Currently used for Storage | | 1 | No | 1/D | | | | |
| 1 | 5 | Classroom 506 | M | Blackboard Glue Dots | 7020/01/05/BATTA/AH/2600 | Assumed | 60 | SF | 0 | SF | | Currently used for Storage | | 1 | No | 1/D | | | | |
| 1 | 5 | Classroom 506 | T | Pipe Insulation 2-6 inch | 7020/01/05/52 | Confirmed | 24 | LF | 0 | LF | | Currently used for Storage | | 1 | No | 1/D | | | | |
| 1 | 5 | Classroom 506 Closet | N/A | Wood Floor | | Non Suspect ACM | #REF! | SF | 0 | SF | | | | N/A | N/A | N/A | | | | |
| 1 | 5 | Classroom 506 Closet | N/A | Plaster Walls | | NAD | 728 | SF | 0 | SF | | | | N/A | N/A | N/A | | | | |
| 1 | 5 | Classroom 506 Closet | N/A | Plaster Ceiling | | NAD | 133 | SF | 0 | SF | | | | N/A | N/A | N/A | | | | |
| 1 | 5 | Classroom 506 Closet | T | Pipe Insulation 2-6 inch | 7020/01/05/52 | Confirmed | 14 | LF | 0 | LF | | | | 1 | No | 1/D | | | | |
| 1 | 5 | Classroom 505 | N/A | Wood Floor | | Non Suspect ACM | 1152 | SF | 0 | SF | | | | N/A | N/A | N/A | | | | |
| 1 | 5 | Classroom 505 | N/A | Plaster Walls | | NAD | 1728 | SF | 0 | SF | | | | N/A | N/A | N/A | | | | |

7020 Olney HS (ASPIRA) 2015 2016 AHERA Three-Year Report.xls

| School District of Philadelphia | | | AHERA Three-Year Reinspection 2015-2016 | | | | | | | | | | Reinspection Date: December 13, 2015 | | | |
|---|-----------------------|---|---|---------------------------------|--------------------------|---|-----------------------|-------------|---------------------|-------------|------------------------------|----------------------------|--------------------------------------|-----------------------------|--------------------------|-------------------------|
| Aspira Olney Charter High School | | | Room by Room Location Log Report | | | | | | | | | | Building Inspector: James Madden | | | |
| 100 E. Duncannon Street, Philadelphia, PA 19120 | | | | | | | | | | | | | Number: 030867 | | | |
| ULCS# 7029 | | | | | | | | | | | | | Management Planner: Megan Vala | | | |
| Year Built: 1931 | | | | | | | | | | | | | Number: 740728 | | | |
| E l e m e n t | F l o o r | On Site Room Name | System Affected | Material Description | HID# | Confirmed/Assumed/NAD/ Non Suspect ACM | Amount of Material | SF LF EA | Amount of Damage | SF LF EA | Color required for VAT | Comments/Description/Notes | Attic/ Crawl Space Ranking | Damage Potential (DP) | Newly Friable (NF) | Response Action (RA) |
| | | | | | | | | | | | | | | | | |
| 1 | 5 | Classroom 505 | N/A | Ceiling Tile 2' x 4' | | NAD | 1152 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 5 | Classroom 505 | M | Transite Sink | 7020/01/05/BATTA/AH/2340 | Assumed | 24 | SF | 0 | SF | | | | 1 | No | 1/D |
| 1 | 5 | Classroom 505 | M | Transite Counter Tops | 7020/01/05/QQ | Assumed | 220 | SF | 0 | SF | | | | 1 | No | 1/D |
| 1 | 5 | Classroom 505 | M | Blackboard Glue Dots | 7020/01/05/BATTA/AH/2600 | Assumed | 48 | SF | 0 | SF | | | | 1 | No | 1/D |
| 1 | 5 | Classroom 505 | T | Pipe Insulation 2-6 inch | 7020/01/05/52 | Confirmed | 36 | LF | 0 | LF | | | | 1 | No | 1/D |
| 1 | 5 | Classroom 504 | N/A | Wood Floor | | Non Suspect ACM | 780 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 5 | Classroom 504 | N/A | Plaster Walls | | NAD | 1344 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 5 | Classroom 504 | N/A | Ceiling Tile 2' x 4' | | NAD | 780 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 5 | Classroom 504 | M | Transite Sink | 7020/01/05/BATTA/AH/2340 | Assumed | 18 | SF | 0 | SF | | | | 1 | No | 1/D |
| 1 | 5 | Classroom 504 | M | Transite Counter Tops | 7020/01/05/QQ | Assumed | 135 | SF | 0 | SF | | | | 1 | No | 1/D |
| 1 | 5 | Classroom 504 | M | Blackboard Glue Dots | 7020/01/05/BATTA/AH/2600 | Assumed | 48 | SF | 0 | SF | | | | 1 | No | 1/D |
| 1 | 5 | Classroom 504 | T | Pipe Insulation 2-6 inch | 7020/01/05/52 | Confirmed | 24 | LF | 0 | LF | | | | 1 | No | 1/D |
| 1 | 5 | Classroom 503 | N/A | Wood Floor | | Non Suspect ACM | 975 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 5 | Classroom 503 | N/A | Plaster Walls | | NAD | 1536 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 5 | Classroom 503 | N/A | Ceiling Tile 2' x 4' | | NAD | 975 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 5 | Classroom 503 | M | Transite Sink | 7020/01/05/BATTA/AH/2340 | Assumed | 18 | SF | 0 | SF | | | | 1 | No | 1/D |
| 1 | 5 | Classroom 503 | M | Transite Counter Tops | 7020/01/05/QQ | Assumed | 225 | SF | 0 | SF | | | | 1 | No | 1/D |
| 1 | 5 | Classroom 503 | M | Blackboard Glue Dots | 7020/01/05/BATTA/AH/2600 | Assumed | 48 | SF | 0 | SF | | | | 1 | No | 1/D |
| 1 | 5 | Classroom 503 | T | Pipe Insulation 2-6 inch | 7020/01/05/52 | Confirmed | 24 | LF | 0 | LF | | | | 1 | No | 1/D |
| 1 | 5 | Classroom 503 Closet | N/A | Wood Floor | | Non Suspect ACM | 198 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 5 | Classroom 503 Closet | N/A | Plaster Walls | | NAD | 696 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 5 | Classroom 503 Closet | N/A | Ceiling Tile 2' x 4' | | NAD | 198 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 5 | Classroom 503 Closet | T | Pipe Insulation 2-6 inch | 7020/01/05/52 | Confirmed | 15 | LF | 0 | LF | | | | 1 | No | 1/D |
| 1 | 5 | Classroom 503 Closet | T | Pipe Fitting Insulation | 7020/01/05/71 | Assumed | 2 | EA | 0 | EA | | | | 1 | No | 1/D |
| 1 | 5 | Green House attached to Classroom 503 | N/A | Cement Floor | | Non Suspect ACM | 590 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 5 | Green House attached to Classroom 503 | N/A | Brick Wall | | Non Suspect ACM | 1656 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 5 | Green House attached to Classroom 503 | N/A | Glass Ceiling | | Non Suspect ACM | 590 | SF | 0 | SF | | glass roof | | N/A | N/A | N/A |
| 1 | 5 | Classroom 501 | N/A | Wood Floor | | Non Suspect ACM | 672 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 5 | Classroom 501 | N/A | Plaster Walls | | NAD | 1248 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 5 | Classroom 501 | N/A | Fiberglass Ceiling Tile 2' x 4' | | Non Suspect ACM | 672 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 5 | Classroom 501 | M | Transite Sink | 7020/01/05/BATTA/AH/2340 | Assumed | 18 | SF | 0 | SF | | | | 1 | No | 1/D |
| 1 | 5 | Classroom 501 | M | Transite Counter Tops | 7020/01/05/QQ | Assumed | 108 | SF | 0 | SF | | | | 1 | No | 1/D |
| 1 | 5 | Classroom 501 | M | Blackboard Glue Dots | 7020/01/05/BATTA/AH/2600 | Assumed | 48 | SF | 0 | SF | | | | 1 | No | 1/D |
| 1 | 5 | Classroom 501 | T | Pipe Insulation 2-6 inch | 7020/01/05/52 | Confirmed | 24 | LF | 0 | LF | | | | 1 | No | 1/D |
| 1 | 5 | Classroom 502 | N/A | Wood Floor | | Non Suspect ACM | 1104 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 5 | Classroom 502 | N/A | Plaster Walls | | NAD | 1680 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 5 | Classroom 502 | N/A | Ceiling Tile 2' x 4' | | NAD | 1104 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 5 | Classroom 502 | M | Transite Sink | 7020/01/05/BATTA/AH/2340 | Assumed | 24 | SF | 0 | SF | | | | 1 | No | 1/D |
| 1 | 5 | Classroom 502 | M | Transite Counter Tops | 7020/01/05/QQ | Assumed | 240 | SF | 0 | SF | | | | 1 | No | 1/D |
| 1 | 5 | Classroom 502 | M | Blackboard Glue Dots | 7020/01/05/BATTA/AH/2600 | Assumed | 48 | SF | 0 | SF | | | | 1 | No | 1/D |
| 1 | 5 | Classroom 502 | T | Pipe Insulation 2-6 inch | 7020/01/05/52 | Confirmed | 36 | LF | 0 | LF | | | | 1 | No | 1/D |
| 1 | 5 | Classroom 502 Closet | N/A | Wood Floor | | Non Suspect ACM | 312 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 5 | Classroom 502 Closet | N/A | Plaster Walls | | NAD | 1064 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 5 | Classroom 502 Closet | N/A | Plaster Ceiling | | NAD | 312 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 5 | Classroom 502 Closet | T | Pipe Insulation 2-6 inch | 7020/01/05/52 | Confirmed | 14 | LF | 0 | LF | | | | 1 | No | 1/D |
| 1 | 5 | Small Room attached to Classroom 502 Closet | N/A | Wood Floor | | Non Suspect ACM | 108 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 5 | Small Room attached to Classroom 502 Closet | N/A | Plaster Walls | | NAD | 504 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 5 | Small Room attached to Classroom 502 Closet | N/A | Plaster Ceiling | | NAD | 108 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 5 | Small Room attached to Classroom 502 Closet | T | Pipe Insulation 2-6 inch | 7020/01/05/52 | Confirmed | 12 | LF | 0 | LF | | | | 1 | No | 1/D |
| 1 | 5 | Small Room attached to Classroom 502 Closet | T | Pipe Insulation 2-6 inch | 7020/01/05/52 | Confirmed | 12 | LF | 0 | LF | | | | 1 | No | 1/D |
| 1 | 5 | Small Room attached to Classroom 502 Closet | T | Pipe Fitting Insulation | 7020/01/05/71 | Assumed | 2 | EA | 0 | EA | | | | 1 | No | 1/D |
| 1 | 5 | Hallway from Classrooms 501 to 506 | N/A | Cement Floor | | Non Suspect ACM | 1200 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 5 | Hallway from Classrooms 501 to 506 | N/A | Plaster Walls | | NAD | 3120 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 5 | Hallway from Classrooms 501 to 506 | N/A | Fiberglass Ceiling Tile 2' x 4' | | Non Suspect ACM | 1200 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 5 | Hallway from Classrooms 501 to 506 | T | Pipe Insulation 2-6 inch | 7020/01/05/52 | Confirmed | 30 | LF | 0 | LF | | | | 1 | No | 1/D |
| 1 | 5 | Stairwell next to Classroom 505 | N/A | Cement Floor | | Non Suspect ACM | 528 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 5 | Stairwell next to Classroom 505 | N/A | Plaster Walls | | NAD | 1840 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 5 | Stairwell next to Classroom 505 | N/A | Fiberglass Ceiling Tile 2' x 4' | | Non Suspect ACM | 528 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 5 | Stairwell next to Classroom 502 | N/A | Cement Floor | | Non Suspect ACM | 500 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 5 | Stairwell next to Classroom 502 | N/A | Plaster Ceiling | | NAD | 250 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 5 | Stairwell next to Classroom 502 | N/A | Ceiling Tile 1' x 1' | | NAD | 250 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 5 | Stairwell next to Classroom 502 | N/A | Plaster Walls | | NAD | 1000 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | 5 | Stairwell next to Classroom 502 | T | Pipe Insulation 2-6 inch | 7020/01/05/52 | Confirmed | 10 | LF | 0 | LF | | | | 1 | No | 1/D |
| 1 | B | Hallway outside Classroom G35 | N/A | Cement Floor | | Non Suspect ACM | 3240 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | B | Hallway outside Classroom G35 | N/A | Brick Wall | | Non Suspect ACM | 7896 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | B | Hallway outside Classroom G35 | N/A | Concrete Ceiling | | Non Suspect ACM | 3240 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | B | Hallway outside Classroom G35 | T | Pipe Insulation 2-6 inch | 7020/01/05/01 | Confirmed | 700 | LF | 0 | LF | | | | 1 | No | 1/D |
| 1 | B | Hallway outside Classroom G35 | T | Pipe Fitting Insulation | 7020/01/05/11 | Assumed | 35 | EA | 0 | EA | | | | 1 | No | 1/D |
| 1 | B | Hallway outside Classroom 2 | N/A | Cement Floor | | Non Suspect ACM | 2040 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | B | Hallway outside Classroom 2 | N/A | Brick Wall | | Non Suspect ACM | 5096 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | B | Hallway outside Classroom 2 | N/A | Concrete Ceiling | | Non Suspect ACM | 2040 | SF | 0 | SF | | | | N/A | N/A | N/A |
| 1 | B | Hallway outside Classroom 2 | T | Pipe Insulation 2-6 inch | 7020/01/05/01 | Confirmed | 700 | LF | 0 | LF | | | | 1 | No | 1/D |
| 1 | B | Hallway outside Classroom 2 | T | Pipe Fitting Insulation | 7020/01/05/11 | Assumed | 35 | EA | 0 | EA | | | | 1 | No | 1/D |

7020 Olney HS (ASPIRA) 2015 2016 AHERA Three-Year Report.xls

| School District of Philadelphia Aspira Olney Charter High School 100 E. Duncannon Street, Philadelphia, PA 19120 ULCS# 7029 Year Built: 1931 | | | AHERA Three-Year Reinspection 2015-2016 Room by Room Location Log Report | | | | | | | | | | Reinspection Date: December 13, 2015 Building Inspector: James Madden Number: 030867 Management Planner: Megan Vala Number: 740728 | | | | | | | |
|--|-----------------------|---|---|----------------------------|--------------------------|---|-----------------------|----|----|----|---------------------|----|--|----|------------------------------|----------------------------|----------------------------------|-----------------------------|--------------------------|-------------------------|
| E l e m e n t | F l o o r | On Site Room Name | System Affected | Material Description | HID# | Confirmed/Assumed/NAD/ Non Suspect ACM | Amount of Material | SF | LF | EA | Amount of Damage | SF | LF | EA | Color required for VAT | Comments/Description/Notes | Attic/ Crawl Space Ranking | Damage Potential (DP) | Newly Friable (NF) | Response Action (RA) |
| | | | | | | | | | | | | | | | | | | | | |
| 1 | B | Hallway outside Classroom E7 | N/A | Cement Floor | | Non Suspect ACM | 3240 | SF | 0 | SF | | | | | | | | N/A | N/A | N/A |
| 1 | B | Hallway outside Classroom E7 | N/A | Brick Wall | | Non Suspect ACM | 7896 | SF | 0 | SF | | | | | | | | N/A | N/A | N/A |
| 1 | B | Hallway outside Classroom E7 | N/A | Concrete Ceiling | | Non Suspect ACM | 3240 | SF | 0 | SF | | | | | | | | N/A | N/A | N/A |
| 1 | B | Hallway outside Classroom E7 | T | Pipe Insulation 2-6 inch | 7020/01/0B/01 | Confirmed | 700 | LF | 0 | LF | | | | | | | | 1 | No | 1/D |
| 1 | B | Hallway outside Classroom E7 | T | Pipe Fitting Insulation | 7020/01/0B/11 | Assumed | 35 | EA | 0 | EA | | | | | | | | 1 | No | 1/D |
| 1 | B | Hallway outside Boiler Room Access Points | N/A | Cement Floor | | Non Suspect ACM | 2040 | SF | 0 | SF | | | | | | | | N/A | N/A | N/A |
| 1 | B | Hallway outside Boiler Room Access Points | N/A | Brick Wall | | Non Suspect ACM | 5096 | SF | 0 | SF | | | | | | | | N/A | N/A | N/A |
| 1 | B | Hallway outside Boiler Room Access Points | N/A | Concrete Ceiling | | Non Suspect ACM | 2040 | SF | 0 | SF | | | | | | | | N/A | N/A | N/A |
| 1 | B | Hallway outside Boiler Room Access Points | T | Pipe Insulation 2-6 inch | 7020/01/0B/01 | Confirmed | 700 | LF | 0 | LF | | | | | | | | 1 | No | 1/D |
| 1 | B | Hallway outside Boiler Room Access Points | T | Pipe Fitting Insulation | 7020/01/0B/11 | Assumed | 35 | EA | 0 | EA | | | | | | | | 1 | No | 1/D |
| 1 | B | Classroom E7 | M | Floor Tile VAT 12" x 12" | 7020/01/0B/A3 | Assumed | 754 | SF | 0 | SF | | | | | Tan | | | 1 | No | 1/D |
| 1 | B | Classroom E7 | N/A | Sheetrock Wall | | Non Suspect ACM | 800 | SF | 0 | SF | | | | | | | | N/A | N/A | N/A |
| 1 | B | Classroom E7 | N/A | Concrete Ceiling | | Non Suspect ACM | 754 | SF | 0 | SF | | | | | | | | N/A | N/A | N/A |
| 1 | B | Classroom E7 | N/A | Brick Wall | | Non Suspect ACM | 800 | SF | 0 | SF | | | | | | | | N/A | N/A | N/A |
| 1 | B | Classroom E7 | T | Pipe Insulation 2-6 inch | 7020/01/0B/01 | Confirmed | 46 | LF | 0 | LF | | | | | | | | 1 | No | 1/D |
| 1 | B | Classroom E7 | T | Pipe Fitting Insulation | 7020/01/0B/11 | Assumed | 6 | EA | 0 | EA | | | | | | | | 1 | No | 1/D |
| 1 | B | Team Leader and Behavior Specialist Office next to Classroom E7 | M | Floor Tile VAT 12" x 12" | 7020/01/0B/A3 | Assumed | 575 | SF | 0 | SF | | | | | Tan | | | 1 | No | 1/D |
| 1 | B | Team Leader and Behavior Specialist Office next to Classroom E7 | N/A | Sheetrock Wall | | Non Suspect ACM | 1344 | SF | 0 | SF | | | | | | | | N/A | N/A | N/A |
| 1 | B | Team Leader and Behavior Specialist Office next to Classroom E7 | N/A | Concrete Ceiling | | Non Suspect ACM | 575 | SF | 0 | SF | | | | | | | | N/A | N/A | N/A |
| 1 | B | Team Leader and Behavior Specialist Office next to Classroom E7 | N/A | Brick Wall | | Non Suspect ACM | 1344 | SF | 0 | SF | | | | | | | | N/A | N/A | N/A |
| 1 | B | Team Leader and Behavior Specialist Office next to Classroom E7 | T | Pipe Insulation 2-6 inch | 7020/01/0B/01 | Confirmed | 85 | LF | 0 | LF | | | | | | | | 1 | No | 1/D |
| 1 | B | Team Leader and Behavior Specialist Office next to Classroom E7 | T | Pipe Fitting Insulation | 7020/01/0B/11 | Assumed | 12 | EA | 0 | EA | | | | | | | | 1 | No | 1/D |
| 1 | B | Team Leader and Behavior Specialist Office next to Classroom E7 | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 20 | LF | 3 | LF | | | | | | | | N/A | N/A | N/A |
| 1 | B | Team Leader and Behavior Specialist Office next to Classroom E7 | M | Transite Electrical Panel | 7020/01/0B/10 | Assumed | 16 | SF | 0 | SF | | | | | | | | 1 | No | 1/D |
| 1 | B | Classroom G35 | M | Floor Tile VAT 12" x 12" | 7020/01/0B/A3 | Assumed | 1421 | SF | 0 | SF | | | | | Blue | | | 1 | No | 1/D |
| 1 | B | Classroom G35 | N/A | Concrete Ceiling | | Non Suspect ACM | 1421 | SF | 0 | SF | | | | | | | | N/A | N/A | N/A |
| 1 | B | Classroom G35 | N/A | Brick Wall | | Non Suspect ACM | 2184 | SF | 0 | SF | | | | | | | | N/A | N/A | N/A |
| 1 | B | Classroom G35 | T | Pipe Insulation 2-6 inch | 7020/01/0B/01 | Confirmed | 92 | LF | 0 | LF | | | | | | | | 1 | No | 1/D |
| 1 | B | Classroom G35 | T | Pipe Fitting Insulation | 7020/01/0B/11 | Assumed | 25 | EA | 0 | EA | | | | | | | | 1 | No | 1/D |
| 1 | B | Classroom G35 | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 40 | LF | 0 | LF | | | | | | | | N/A | N/A | N/A |
| 1 | B | Classroom G35 | M | Blackboard Glue Dots | 7020/01/0B/BATTA/AH/2600 | Assumed | 32 | SF | 0 | SF | | | | | | | | 1 | No | 1/D |
| 1 | B | Storage attached to Classroom G35 | M | Floor Tile VAT 12" x 12" | 7020/01/0B/A3 | Assumed | 120 | SF | 0 | SF | | | | | Blue | | | 1 | No | 1/D |
| 1 | B | Storage attached to Classroom G35 | N/A | Sheetrock Wall | | Non Suspect ACM | 368 | SF | 0 | SF | | | | | | | | N/A | N/A | N/A |
| 1 | B | Storage attached to Classroom G35 | N/A | Concrete Ceiling | | Non Suspect ACM | 120 | SF | 0 | SF | | | | | | | | N/A | N/A | N/A |
| 1 | B | Storage attached to Classroom G35 | N/A | Brick Wall | | Non Suspect ACM | 368 | SF | 0 | SF | | | | | | | | N/A | N/A | N/A |
| 1 | B | Storage Room to the left of Women's Restroom | N/A | Cement Floor | | Non Suspect ACM | 176 | SF | 0 | SF | | | | | | | | N/A | N/A | N/A |
| 1 | B | Storage Room to the left of Women's Restroom | N/A | Brick Wall | | Non Suspect ACM | 900 | SF | 0 | SF | | | | | | | | N/A | N/A | N/A |
| 1 | B | Storage Room to the left of Women's Restroom | N/A | Concrete Ceiling | | Non Suspect ACM | 176 | SF | 0 | SF | | | | | | | | N/A | N/A | N/A |
| 1 | B | Women's Restroom near Classroom G35 | N/A | Cement Floor | | Non Suspect ACM | 270 | SF | 0 | SF | | | | | | | | N/A | N/A | N/A |
| 1 | B | Women's Restroom near Classroom G35 | N/A | Brick Wall | | Non Suspect ACM | 1036 | SF | 0 | SF | | | | | | | | N/A | N/A | N/A |
| 1 | B | Women's Restroom near Classroom G35 | N/A | Concrete Ceiling | | Non Suspect ACM | 270 | SF | 0 | SF | | | | | | | | N/A | N/A | N/A |
| 1 | B | Women's Restroom near Classroom G35 | T | Pipe Insulation 2-6 inch | 7020/01/0B/01 | Confirmed | 112 | LF | 0 | LF | | | | | | | | 1 | No | 1/D |
| 1 | B | Women's Restroom near Classroom G35 | T | Pipe Fitting Insulation | 7020/01/0B/11 | Assumed | 21 | EA | 0 | EA | | | | | | | | 1 | No | 1/D |
| 1 | B | Storage Room to the left of Women's Restroom | N/A | Cement Floor | | Non Suspect ACM | 176 | SF | 0 | SF | | | | | | | | N/A | N/A | N/A |
| 1 | B | Storage Room to the left of Women's Restroom | N/A | Brick Wall | | Non Suspect ACM | 900 | SF | 0 | SF | | | | | | | | N/A | N/A | N/A |
| 1 | B | Storage Room to the left of Women's Restroom | N/A | Concrete Ceiling | | Non Suspect ACM | 176 | SF | 0 | SF | | | | | | | | N/A | N/A | N/A |
| 1 | B | Storage Room to the left of Women's Restroom | T | Pipe Insulation 2-6 inch | 7020/01/0B/01 | Confirmed | 20 | LF | 0 | LF | | | | | | | | 1 | No | 1/D |
| 1 | B | Storage Room to the left of Women's Restroom | T | Pipe Fitting Insulation | 7020/01/0B/11 | Assumed | 3 | EA | 0 | EA | | | | | | | | 1 | No | 1/D |
| 1 | B | Women's Restroom near Classroom 2 | N/A | Cement Floor | | Non Suspect ACM | 280 | SF | 0 | SF | | | | | | | | N/A | N/A | N/A |
| 1 | B | Women's Restroom near Classroom 2 | N/A | Brick Wall | | Non Suspect ACM | 1064 | SF | 0 | SF | | | | | | | | N/A | N/A | N/A |
| 1 | B | Women's Restroom near Classroom 2 | N/A | Concrete Ceiling | | Non Suspect ACM | 280 | SF | 0 | SF | | | | | | | | N/A | N/A | N/A |
| 1 | B | Women's Restroom near Classroom 2 | T | Pipe Insulation 2-6 inch | 7020/01/0B/01 | Confirmed | 81 | LF | 0 | LF | | | | | | | | 1 | No | 1/D |
| 1 | B | Women's Restroom near Classroom 2 | T | Pipe Fitting Insulation | 7020/01/0B/11 | Assumed | 24 | EA | 0 | EA | | | | | | | | 1 | No | 1/D |
| 1 | B | Classroom 2 or T9 | M | Floor Tile VAT 12" x 12" | 7020/01/0B/A3 | Assumed | 1176 | SF | 0 | SF | | | | | Tan | | | 1 | No | 1/D |
| 1 | B | Classroom 2 or T9 | N/A | Brick Wall | | Non Suspect ACM | 1280 | SF | 0 | SF | | | | | | | | N/A | N/A | N/A |
| 1 | B | Classroom 2 or T9 | N/A | Sheetrock Wall | | Non Suspect ACM | 400 | SF | 0 | SF | | | | | | | | N/A | N/A | N/A |
| 1 | B | Classroom 2 or T9 | N/A | Ceiling Tile 2' x 4' | | NAD | 1176 | SF | 0 | SF | | | | | | | | N/A | N/A | N/A |
| 1 | B | Classroom 2 or T9 | T | Pipe Insulation 2-6 inch | 7020/01/0B/01 | Confirmed | 110 | LF | 0 | LF | | | | | | | | 1 | No | 1/D |
| 1 | B | Classroom 2 or T9 | T | Pipe Fitting Insulation | 7020/01/0B/11 | Assumed | 8 | EA | 0 | EA | | | | | | | | 1 | No | 1/D |
| 1 | B | Classroom 2 or T9 | M | Blackboard Glue Dots | 7020/01/0B/BATTA/AH/2600 | Assumed | 64 | SF | 0 | SF | | | | | | | | 1 | No | 1/D |
| 1 | B | Classroom 2 or T9 | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 24 | LF | 0 | LF | | | | | | | | N/A | N/A | N/A |
| 1 | B | Vacant Classroom Directly across from door labeled T10 | M | Floor Tile VAT 12" x 12" | 7020/01/0B/A3 | Assumed | 624 | SF | 3 | SF | | | | | Tan | | | 1 | Yes | 5/C |
| 1 | B | Vacant Classroom Directly across from door labeled T10 | N/A | Brick Wall | | Non Suspect ACM | 700 | SF | 0 | SF | | | | | | | | N/A | N/A | N/A |
| 1 | B | Vacant Classroom Directly across from door labeled T10 | N/A | Sheetrock Wall | | Non Suspect ACM | 700 | SF | 0 | SF | | | | | | | | N/A | N/A | N/A |
| 1 | B | Vacant Classroom Directly across from door labeled T10 | N/A | Concrete Ceiling | | Non Suspect ACM | 624 | SF | 0 | SF | | | | | | | | N/A | N/A | N/A |
| 1 | B | Vacant Classroom Directly across from door labeled T10 | M | Blackboard Glue Dots | 7020/01/0B/BATTA/AH/2600 | Assumed | 128 | SF | 0 | SF | | | | | | | | 1 | No | 1/D |

7020 Olney HS (ASPIRA) 2015 2016 AHERA Three-Year Report.xls

| School District of Philadelphia | | | AHERA Three-Year Reinspection 2015-2016 | | | | | | | | | | Reinspection Date: December 13, 2015 | | | | | |
|---|-----------------------|---|---|---------------------------------|--------------------------|---|-----------------------|-------------|---------------------|-------------|------------------------------|----------------------------|--------------------------------------|-----------------------------|--------------------------|-------------------------|--|--|
| Aspira Olney Charter High School | | | Room by Room Location Log Report | | | | | | | | | | Building Inspector: James Madden | | | | | |
| 100 E. Duncannon Street, Philadelphia, PA 19120 | | | | | | | | | | | | | Number: 030867 | | | | | |
| ULCS# 7029 | | | | | | | | | | | | | Management Planner: Megan Vala | | | | | |
| Year Built: 1931 | | | | | | | | | | | | | Number: 740728 | | | | | |
| E l e m e n t | F l o o r | On Site Room Name | System Affected | Material Description | HID# | Confirmed/Assumed/NAD/ Non Suspect ACM | Amount of Material | SF LF EA | Amount of Damage | SF LF EA | Color required for VAT | Comments/Description/Notes | Attic/ Crawl Space Ranking | Damage Potential (DP) | Newly Friable (NF) | Response Action (RA) | | |
| 1 | B | Vacant Classroom Directly across from door labeled T10 | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 8 | LF | 3 | LF | | | | N/A | N/A | N/A | | |
| | | Vacant Classroom inside door labeled T10 and down Hallway on the Right | N/A | Brick Wall | | Non Suspect ACM | 658 | SF | 0 | SF | | | | N/A | N/A | N/A | | |
| 1 | B | Vacant Classroom inside door labeled T10 and down Hallway on the Right | N/A | Sheetrock Wall | | Non Suspect ACM | 658 | SF | 0 | SF | | | | N/A | N/A | N/A | | |
| 1 | B | Vacant Classroom inside door labeled T10 and down Hallway on the Right | N/A | Concrete Ceiling | | Non Suspect ACM | 540 | SF | 0 | SF | | | | N/A | N/A | N/A | | |
| 1 | B | Vacant Classroom inside door labeled T10 and down Hallway on the Right | T | Pipe Insulation 2-6 inch | 7020/01/0B/01 | Confirmed | 40 | LF | 0 | LF | | | | 1 | No | 1/D | | |
| 1 | B | Vacant Classroom inside door labeled T10 and down Hallway on the Right | T | Pipe Fitting Insulation | 7020/01/0B/11 | Assumed | 12 | EA | 0 | EA | | | | 1 | No | 1/D | | |
| 1 | B | Vacant Classroom inside door labeled T10 and down Hallway on the Right | M | Floor Tile VAT 12" x 12" | 7020/01/0B/A3 | Assumed | 540 | SF | 0 | SF | Tan | | | 1 | No | 1/D | | |
| 1 | B | Vacant Classroom inside door labeled T10 and down Hallway on the Right | M | Blackboard Glue Dots | 7020/01/0B/BATTA/AH/2600 | Assumed | 64 | SF | 0 | SF | | | | 1 | No | 1/D | | |
| 1 | B | Hallway just inside door labeled T10 | N/A | Brick Wall | | Non Suspect ACM | 598 | SF | 0 | SF | | | | N/A | N/A | N/A | | |
| 1 | B | Hallway just inside door labeled T10 | N/A | Sheetrock Wall | | Non Suspect ACM | 598 | SF | 0 | SF | | | | N/A | N/A | N/A | | |
| 1 | B | Hallway just inside door labeled T10 | N/A | Concrete Ceiling | | Non Suspect ACM | 216 | SF | 0 | SF | | | | N/A | N/A | N/A | | |
| 1 | B | Hallway just inside door labeled T10 | T | Pipe Insulation 2-6 inch | 7020/01/0B/01 | Confirmed | 86 | LF | 0 | LF | | | | 1 | No | 1/D | | |
| 1 | B | Hallway just inside door labeled T10 | T | Pipe Fitting Insulation | 7020/01/0B/11 | Assumed | 7 | EA | 0 | EA | | | | 1 | No | 1/D | | |
| 1 | B | Hallway just inside door labeled T10 | M | Floor Tile VAT 12" x 12" | 7020/01/0B/A3 | Assumed | 216 | SF | 4 | SF | Tan | | | 1 | Yes | 5/B | | |
| 1 | B | Vacant Office attached to hallway through door T10 | N/A | Brick Wall | | Non Suspect ACM | 980 | SF | 0 | SF | | | | N/A | N/A | N/A | | |
| 1 | B | Vacant Office attached to hallway through door T10 | N/A | Fiberglass Ceiling Tile 2' x 4' | | Non Suspect ACM | 286 | SF | 0 | SF | | | | N/A | N/A | N/A | | |
| 1 | B | Vacant Office attached to hallway through door T10 | M | Floor Tile VAT 12" x 12" | 7020/01/0B/A3 | Assumed | 286 | SF | 0 | SF | Tan | | | 1 | No | 1/D | | |
| 1 | B | Vacant Office attached to hallway through door T10 | N/A | Concrete Ceiling | | Non Suspect ACM | 286 | SF | 0 | SF | | | | N/A | N/A | N/A | | |
| 1 | B | Small Storage Room across from Vacant Office attached to Hallway through Door Marked T10 | N/A | Wood Floor | | Non Suspect ACM | 60 | SF | 0 | SF | | | | N/A | N/A | N/A | | |
| 1 | B | Small Storage Room across from Vacant Office attached to Hallway through Door Marked T10 | N/A | Brick Wall | | Non Suspect ACM | 448 | SF | 0 | SF | | | | N/A | N/A | N/A | | |
| 1 | B | Small Storage Room across from Vacant Office attached to Hallway through Door Marked T10 | N/A | Concrete Ceiling | | Non Suspect ACM | 60 | SF | 0 | SF | | | | N/A | N/A | N/A | | |
| 1 | B | Classroom T11 or B.I.R. or 7 | N/A | Brick Wall | | Non Suspect ACM | 2016 | SF | 0 | SF | | | | N/A | N/A | N/A | | |
| 1 | B | Classroom T11 or B.I.R. or 7 | N/A | Concrete Ceiling | | Non Suspect ACM | 1292 | SF | 0 | SF | | | | N/A | N/A | N/A | | |
| 1 | B | Classroom T11 or B.I.R. or 7 | M | Floor Tile VAT 12" x 12" | 7020/01/0B/A3 | Assumed | 1292 | SF | 0 | SF | Tan | | | 1 | No | 1/D | | |
| 1 | B | Classroom T11 or B.I.R. or 7 | T | Pipe Insulation 2-6 inch | 7020/01/0B/01 | Confirmed | 45 | LF | 0 | LF | | | | 1 | No | 1/D | | |
| 1 | B | Classroom T11 or B.I.R. or 7 | T | Pipe Fitting Insulation | 7020/01/0B/11 | Assumed | 6 | EA | 0 | EA | | | | 1 | No | 1/D | | |
| 1 | B | Classroom T11 or B.I.R. or 7 | M | Blackboard Glue Dots | 7020/01/0B/BATTA/AH/2600 | Assumed | 64 | SF | 0 | SF | | | | 1 | No | 1/D | | |
| 1 | B | Classroom T12 or 8 or ELL Support | N/A | Brick Wall | | Non Suspect ACM | 1736 | SF | 0 | SF | | | | N/A | N/A | N/A | | |
| 1 | B | Classroom T12 or 8 or ELL Support | N/A | Concrete Ceiling | | Non Suspect ACM | 957 | SF | 0 | SF | | | | N/A | N/A | N/A | | |
| 1 | B | Classroom T12 or 8 or ELL Support | M | Floor Tile VAT 12" x 12" | 7020/01/0B/A3 | Assumed | 957 | SF | 0 | SF | Tan | | | 1 | No | 1/D | | |
| 1 | B | Classroom T12 or 8 or ELL Support | T | Pipe Insulation 2-6 inch | 7020/01/0B/01 | Confirmed | 40 | LF | 0 | LF | | | | 1 | No | 1/D | | |
| 1 | B | Classroom T12 or 8 or ELL Support | M | Blackboard Glue Dots | 7020/01/0B/BATTA/AH/2600 | Assumed | 64 | SF | 0 | SF | | | | 1 | No | 1/D | | |
| 1 | B | Classroom T12 or 8 or ELL Support | N/A | Sheetrock Wall | | Non Suspect ACM | 300 | SF | 0 | SF | | | | N/A | N/A | N/A | | |
| 1 | B | History Classroom T13 | N/A | Plaster Walls | | NAD | 1764 | SF | 0 | SF | | | | N/A | N/A | N/A | | |
| 1 | B | History Classroom T13 | N/A | Concrete Ceiling | | Non Suspect ACM | 990 | SF | 0 | SF | | | | N/A | N/A | N/A | | |
| 1 | B | History Classroom T13 | N/A | Wood Floor | | Non Suspect ACM | 990 | SF | 0 | SF | | | | N/A | N/A | N/A | | |
| 1 | B | History Classroom T13 | T | Pipe Insulation 2-6 inch | 7020/01/0B/01 | Confirmed | 32 | LF | 0 | LF | | | | 1 | No | 1/D | | |
| 1 | B | History Classroom T13 | M | Blackboard Glue Dots | 7020/01/0B/BATTA/AH/2600 | Assumed | 80 | SF | 0 | SF | | | | 1 | No | 1/D | | |
| 1 | B | History Classroom T13 | N/A | Sheetrock Wall | | Non Suspect ACM | 1764 | SF | 0 | SF | | | | N/A | N/A | N/A | | |
| 1 | B | History Classroom T13 | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 11 | LF | 0 | LF | | | | N/A | N/A | N/A | | |
| 1 | B | Science Classroom E2 | N/A | Brick Wall | | Non Suspect ACM | 1792 | SF | 0 | SF | | | | N/A | N/A | N/A | | |
| 1 | B | Science Classroom E2 | N/A | Concrete Ceiling | | Non Suspect ACM | 1023 | SF | 0 | SF | | | | N/A | N/A | N/A | | |
| 1 | B | Science Classroom E2 | N/A | Wood Floor | | Non Suspect ACM | 1023 | SF | 0 | SF | | | | N/A | N/A | N/A | | |
| 1 | B | Science Classroom E2 | T | Pipe Insulation 2-6 inch | 7020/01/0B/01 | Confirmed | 16 | LF | 0 | LF | | | | 1 | No | 1/D | | |
| 1 | B | Science Classroom E2 | M | Blackboard Glue Dots | 7020/01/0B/BATTA/AH/2600 | Assumed | 64 | SF | 0 | SF | | | | 1 | No | 1/D | | |
| 1 | B | Science Classroom E2 | N/A | Sheetrock Wall | | Non Suspect ACM | 350 | SF | 0 | SF | | | | N/A | N/A | N/A | | |
| 1 | B | Science Classroom E2 | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 42 | LF | 0 | LF | | | | N/A | N/A | N/A | | |
| 1 | B | Classroom 11 or E3 | N/A | Brick Wall | | Non Suspect ACM | 854 | SF | 0 | SF | | | | N/A | N/A | N/A | | |
| 1 | B | Classroom 11 or E3 | N/A | Concrete Ceiling | | Non Suspect ACM | 928 | SF | 0 | SF | | | | N/A | N/A | N/A | | |
| 1 | B | Classroom 11 or E3 | N/A | Wood Floor | | Non Suspect ACM | 928 | SF | 0 | SF | | | | N/A | N/A | N/A | | |
| 1 | B | Classroom 11 or E3 | T | Pipe Insulation 2-6 inch | 7020/01/0B/01 | Confirmed | 90 | LF | 0 | LF | | | | 1 | No | 1/D | | |
| 1 | B | Classroom 11 or E3 | T | Pipe Fitting Insulation | 7020/01/0B/11 | Assumed | 21 | EA | 0 | EA | | | | 1 | No | 1/D | | |
| 1 | B | Classroom 11 or E3 | M | Blackboard Glue Dots | 7020/01/0B/BATTA/AH/2600 | Assumed | 128 | SF | 0 | SF | | | | 1 | No | 1/D | | |
| 1 | B | Classroom 11 or E3 | N/A | Sheetrock Wall | | Non Suspect ACM | 854 | SF | 0 | SF | | | | N/A | N/A | N/A | | |
| 1 | B | Classroom 11 or E3 | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 16 | LF | 4 | LF | | | | N/A | N/A | N/A | | |
| 1 | B | Classroom 11 or E3 | T | Pipe Insulation > 6 inch | 7020/01/0B/04 | Confirmed | 40 | LF | 0 | LF | | | | 1 | No | 1/D | | |
| 1 | B | Custodial attached to Classroom E3 | N/A | Cement Floor | | Non Suspect ACM | 78 | SF | 0 | SF | | | | N/A | N/A | N/A | | |
| 1 | B | Custodial attached to Classroom E3 | N/A | Brick Wall | | Non Suspect ACM | 532 | SF | 0 | SF | | | | N/A | N/A | N/A | | |
| 1 | B | Custodial attached to Classroom E3 | T | Pipe Insulation 2-6 inch | 7020/01/0B/01 | Confirmed | 40 | LF | 0 | LF | | | | 1 | No | 1/D | | |
| 1 | B | Custodial attached to Classroom E3 | T | Pipe Fitting Insulation | 7020/01/0B/11 | Assumed | 11 | EA | 0 | EA | | | | 1 | No | 1/D | | |
| 1 | B | Custodial attached to Classroom E3 | N/A | Concrete Ceiling | | Non Suspect ACM | 78 | SF | 0 | SF | | | | N/A | N/A | N/A | | |
| 1 | B | Custodial attached to Classroom E3 | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 60 | LF | 0 | LF | | | | N/A | N/A | N/A | | |
| 1 | B | Director of Operation's Office E4 | N/A | Wood Floor | | Non Suspect ACM | 420 | SF | 0 | SF | | | | N/A | N/A | N/A | | |
| 1 | B | Director of Operation's Office E4 | N/A | Concrete Ceiling | | Non Suspect ACM | 420 | SF | 0 | SF | | | | N/A | N/A | N/A | | |
| 1 | B | Director of Operation's Office E4 | N/A | Brick Wall | | Non Suspect ACM | 1204 | SF | 0 | SF | | | | N/A | N/A | N/A | | |

7020 Olney HS (ASPIRA) 2015 2016 AHERA Three-Year Report.xls

| School District of Philadelphia Aspira Olney Charter High School 100 E. Duncannon Street, Philadelphia, PA 19120 ULCS# 7029 Year Built: 1931 | | | AHERA Three-Year Reinspection 2015-2016 Room by Room Location Log Report | | | | | | | | | | Reinspection Date: December 13, 2015 Building Inspector: James Madden Number: 030867 Management Planner: Megan Vala Number: 740728 | | | | |
|--|-----------------------|--|---|---------------------------------|--------------------------|---|-----------------------|-------------|---------------------|-------------|------------------------------|----------------------------|--|-----------------------------|--------------------------|-------------------------|--|
| E l e m e n t | F l o o r | On Site Room Name | System Affected | Material Description | HID# | Confirmed/Assumed/NAD/ Non Suspect ACM | Amount of Material | SF LF EA | Amount of Damage | SF LF EA | Color required for VAT | Comments/Description/Notes | Attic/ Crawl Space Ranking | Damage Potential (DP) | Newly Friable (NF) | Response Action (RA) | |
| 1 | B | Director of Operation's Office E4 | T | Pipe Insulation 2-6 inch | 7020/01/0B/01 | Confirmed | 35 | LF | 0 | LF | | | | 1 | No | 1/D | |
| 1 | B | Director of Operation's Office E4 | T | Pipe Fitting Insulation | 7020/01/0B/11 | Assumed | 16 | EA | 0 | EA | | | | 1 | No | 1/D | |
| 1 | B | Director of Operation's Office E4 | T | Pipe Insulation > 6 inch | 7020/01/0B/04 | Confirmed | 20 | LF | 0 | LF | | | | 1 | No | 1/D | |
| 1 | B | Classroom E6 | M | Floor Tile VAT 12" x 12" | 7020/01/0B/A3 | Assumed | 1015 | SF | 0 | SF | Tan | | | 1 | No | 1/D | |
| 1 | B | Classroom E6 | N/A | Concrete Ceiling | | Non Suspect ACM | 1015 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | B | Classroom E6 | N/A | Brick Wall | | Non Suspect ACM | 900 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | B | Classroom E6 | T | Pipe Insulation 2-6 inch | 7020/01/0B/01 | Confirmed | 148 | LF | 0 | LF | | | | 1 | No | 1/D | |
| 1 | B | Classroom E6 | T | Pipe Fitting Insulation | 7020/01/0B/11 | Assumed | 12 | EA | 0 | EA | | | | 1 | No | 1/D | |
| 1 | B | Classroom E6 | T | Pipe Insulation > 6 inch | 7020/01/0B/04 | Confirmed | 30 | LF | 0 | LF | | | | 1 | No | 1/D | |
| 1 | B | Classroom E6 | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 8 | LF | 0 | LF | | | | N/A | N/A | N/A | |
| 1 | B | Classroom E6 | N/A | Sheetrock Wall | | Non Suspect ACM | 900 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | B | Classroom E6 | M | Blackboard Glue Dots | 7020/01/0B/BATTA/AH/2600 | Assumed | 64 | SF | 0 | SF | | | | 1 | No | 1/D | |
| 1 | B | Classroom E6 Restroom | M | Floor Tile VAT 12" x 12" | 7020/01/0B/A3 | Assumed | 66 | SF | 0 | SF | Tan | | | 1 | No | 1/D | |
| 1 | B | Classroom E6 Restroom | N/A | Ceiling Tile 2' x 4' | | NAD | 66 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | B | Classroom E6 Restroom | N/A | Brick Wall | | Non Suspect ACM | 160 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | B | Classroom E6 Restroom | N/A | Sheetrock Wall | | Non Suspect ACM | 160 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | B | Classroom E6 Restroom | N/A | Ceramic Tile Walls | | Non Suspect ACM | 50 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | B | Classroom E5 | M | Floor Tile VAT 12" x 12" | 7020/01/0B/A3 | Assumed | 728 | SF | 0 | SF | Tan | | | 1 | No | 1/D | |
| 1 | B | Classroom E5 | N/A | Ceiling Tile 2' x 4' | | NAD | 728 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | B | Classroom E5 | N/A | Brick Wall | | Non Suspect ACM | 756 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | B | Classroom E5 | M | Blackboard Glue Dots | 7020/01/0B/BATTA/AH/2600 | Assumed | 64 | SF | 0 | SF | | | | 1 | No | 1/D | |
| 1 | B | Classroom E5 | T | Pipe Insulation 2-6 inch | 7020/01/0B/01 | Confirmed | 65 | LF | 0 | LF | | | | 1 | No | 1/D | |
| 1 | B | Classroom E5 | T | Pipe Fitting Insulation | 7020/01/0B/11 | Assumed | 12 | EA | 0 | EA | | | | 1 | No | 1/D | |
| 1 | B | Classroom E5 | N/A | Sheetrock Wall | | Non Suspect ACM | 756 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | B | Student Restroom next to Classroom E6 | N/A | Cement Floor | | Non Suspect ACM | 420 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | B | Student Restroom next to Classroom E6 | N/A | Plaster Walls | | NAD | 1232 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | B | Student Restroom next to Classroom E6 | N/A | Concrete Ceiling | | Non Suspect ACM | 420 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | B | Student Restroom next to Classroom E6 | T | Pipe Insulation 2-6 inch | 7020/01/0B/01 | Confirmed | 145 | LF | 0 | LF | | | | 1 | No | 1/D | |
| 1 | B | Student Restroom next to Classroom E6 | T | Pipe Fitting Insulation | 7020/01/0B/11 | Assumed | 27 | EA | 0 | EA | | | | 1 | No | 1/D | |
| 1 | B | Student Restroom next to Classroom E6 | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 4 | LF | 3 | LF | | | | N/A | N/A | N/A | |
| 1 | B | Student Services Room E1 | N/A | Wood Floor | | Non Suspect ACM | 450 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | B | Student Services Room E1 | N/A | Plaster Walls | | NAD | 1260 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | B | Student Services Room E1 | N/A | Concrete Ceiling | | Non Suspect ACM | 450 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | B | Small Staff Lounge next to Room 1 in Library | M | Floor Tile VAT 12" x 12" | 7020/01/0B/A3 | Assumed | 625 | SF | 0 | SF | Tan | | | 1 | No | 1/D | |
| 1 | B | Small Staff Lounge next to Room 1 in Library | N/A | Fiberglass Ceiling Tile 2' x 4' | | Non Suspect ACM | 625 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | B | Small Staff Lounge next to Room 1 in Library | N/A | Concrete Block Wall | | Non Suspect ACM | 1200 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | B | Storage Room 1 in Library | M | Floor Tile VAT 9" x 9" | 7020/01/0B/72 | Confirmed | 144 | SF | 0 | SF | Blue | | | 1 | No | 1/D | |
| 1 | B | Storage Room 1 in Library | N/A | Fiberglass Ceiling Tile 2' x 4' | | Non Suspect ACM | 144 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | B | Storage Room 1 in Library | N/A | Concrete Block Wall | | Non Suspect ACM | 576 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | B | Storage Room 2 in Library | M | Floor Tile VAT 9" x 9" | 7020/01/0B/72 | Confirmed | 300 | SF | 0 | SF | Blue | | | 1 | No | 1/D | |
| 1 | B | Storage Room 2 in Library | N/A | Ceiling Tile 2' x 4' | | NAD | 300 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | B | Storage Room 2 in Library | N/A | Concrete Block Wall | | Non Suspect ACM | 840 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | B | Storage Room 3 in Library Sealed | X | X | | X | X | X | X | X | | Broken door knob | | X | X | X | |
| 1 | B | Small Book Room near Room 3 in Library and Library Exit to Main Hall | M | Floor Tile VAT 9" x 9" | 7020/01/0B/72 | Confirmed | 168 | SF | 0 | SF | Blue | | | 1 | No | 1/D | |
| 1 | B | Small Book Room near Room 3 in Library and Library Exit to Main Hall | N/A | Plaster Ceiling | | NAD | 168 | SF | 6 | SF | | | | N/A | N/A | N/A | |
| 1 | B | Small Book Room near Room 3 in Library and Library Exit to Main Hall | N/A | Concrete Block Wall | | Non Suspect ACM | 812 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | B | Storage Room 5 in Library | N/A | Carpet | | Non Suspect ACM | 315 | SF | 0 | SF | | Possibly Over 9" FT | | N/A | N/A | N/A | |
| 1 | B | Storage Room 5 in Library | N/A | Plaster Ceiling | | NAD | 315 | SF | 10 | SF | | | | N/A | N/A | N/A | |
| 1 | B | Storage Room 5 in Library | N/A | Concrete Block Wall | | Non Suspect ACM | 720 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | B | Storage Room 5 in Library | M | Floor Tile VAT 9" x 9" | 7020/01/0B/72 | Confirmed | 440 | SF | 0 | SF | Blue | | | 1 | No | 1/D | |
| 1 | B | Storage Room 5 in Library | N/A | Plaster Ceiling | | NAD | 440 | SF | 10 | SF | | | | N/A | N/A | N/A | |
| 1 | B | Storage Room 5 in Library | N/A | Concrete Block Wall | | Non Suspect ACM | 840 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | B | Room 7 in Library Restroom | M | Floor Tile VAT 9" x 9" | 7020/01/0B/72 | Confirmed | 35 | SF | 0 | SF | Tan | | | 1 | No | 1/D | |
| 1 | B | Room 7 in Library Restroom | N/A | Plaster Ceiling | | NAD | 35 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | B | Room 7 in Library Restroom | N/A | Brick Wall | | Non Suspect ACM | 240 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | B | Library | M | Floor Tile VAT 9" x 9" | 7020/01/0B/72 | Confirmed | 3000 | SF | 0 | SF | Blue | | | 1 | No | 1/D | |
| 1 | B | Library | N/A | Plaster Ceiling | | NAD | 3000 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | B | Library | N/A | Ceiling Tile 2' x 4' | | NAD | 6400 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | B | Library | N/A | Concrete Block Wall | | Non Suspect ACM | 6400 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | B | Library | M | Floor Tile VAT 12" x 12" | 7020/01/0B/A3 | Assumed | 6600 | SF | 0 | SF | White | | | 1 | No | 1/D | |
| 1 | B | Library | N/A | Carpet | | Non Suspect ACM | 250 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | B | Library | M | Floor Tile VAT 12" x 12" | 7020/01/0B/A3 | Assumed | 100 | SF | 0 | SF | Tan | | | 1 | No | 1/D | |
| 1 | B | Library | M | Floor Tile VAT 12" x 12" | 7020/01/0B/A3 | Assumed | 160 | SF | 0 | SF | Brown | | | 1 | No | 1/D | |
| 1 | B | Library | M | Blackboard Glue Dots | 7020/01/0B/BATTA/AH/2600 | Assumed | 64 | SF | 0 | SF | | | | 1 | No | 1/D | |
| 1 | B | Storage Room across from Classroom G35 | N/A | Cement Floor | | Non Suspect ACM | 100 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | B | Storage Room across from Classroom G35 | N/A | Plaster Ceiling | | NAD | 100 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | B | Storage Room across from Classroom G35 | N/A | Plaster Walls | | NAD | 400 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 1 | B | Storage Room across from Classroom G35 | T | Pipe Insulation 2-6 inch | 7020/01/0B/01 | Confirmed | 12 | LF | 0 | LF | | | | 1 | No | 1/D | |
| 1 | B | Storage Room across from Classroom G35 | T | Pipe Fitting Insulation | 7020/01/0B/11 | Assumed | 11 | EA | 0 | EA | | | | 1 | No | 1/D | |
| 1 | B | Storage Room across from Classroom G35 | T | Pipe Insulation > 6 inch | 7020/01/0B/04 | Confirmed | 10 | LF | 0 | LF | | | | 1 | No | 1/D | |

7020 Olney HS (ASPIRA) 2015 2016 AHERA Three-Year Report.xls

| School District of Philadelphia Aspira Olney Charter High School 100 E. Duncannon Street, Philadelphia, PA 19120 ULCS# 7029 Year Built: 1931 | | | AHERA Three-Year Reinspection 2015-2016 Room by Room Location Log Report | | | | | | | | | | | Reinspection Date: December 13, 2015 Building Inspector: James Madden Number: 030867 Management Planner: Megan Vala Number: 740728 | | | | | | | | | |
|--|--|--|---|-------|-------------------|-----------------|----------------------|------|---|--------------------|----|----|----|--|----|----|----|------------------------|----------------------------|----------------------------|-----------------------|--------------------|----------------------|
| | | | Element | Floor | On Site Room Name | System Affected | Material Description | HID# | Confirmed/Assumed/NAD/ Non Suspect ACM | Amount of Material | SF | LF | EA | Amount of Damage | SF | LF | EA | Color required for VAT | Comments/Description/Notes | Attic/ Crawl Space Ranking | Damage Potential (DP) | Newly Friable (NF) | Response Action (RA) |
| | | | | | | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | | | | | | |

| | | | | | | | | | | | | | | | | | | | | | |
|---|---|---|-----|---------------------------------|--------------------------|-----------------|------|----|--|--|----|----|--|--|--------|---------------|--|--|-----|-----|-----|
| 1 | B | Special Education Gym | N/A | Wood Floor | | Non Suspect ACM | 2756 | SF | | | 0 | SF | | | | | | | N/A | N/A | N/A |
| 1 | B | Special Education Gym | N/A | Concrete Ceiling | | Non Suspect ACM | 2756 | SF | | | 0 | SF | | | | | | | N/A | N/A | N/A |
| 1 | B | Special Education Gym | N/A | Brick Wall | | Non Suspect ACM | 7140 | SF | | | 0 | SF | | | | | | | N/A | N/A | N/A |
| 1 | B | Special Education Gym | M | Vibration Damper Cloth | 7020/01/0B/09 | Assumed | 14 | SF | | | 0 | SF | | | | | | | 1 | No | 1/D |
| 1 | B | Special Education Gym Office | N/A | Wood Floor | | Non Suspect ACM | 170 | SF | | | 0 | SF | | | | | | | N/A | N/A | N/A |
| 1 | B | Special Education Gym Office | N/A | Plaster Walls | | NAD | 756 | SF | | | 0 | SF | | | | | | | N/A | N/A | N/A |
| 1 | B | Special Education Gym Office | N/A | Plaster Ceiling | | NAD | 170 | SF | | | 25 | SF | | | | | | | N/A | N/A | N/A |
| 1 | B | Special Education Gym Office | T | Pipe Insulation 2-6 inch | 7020/01/0B/01 | Confirmed | 32 | LF | | | 0 | LF | | | | | | | 1 | No | 1/D |
| 1 | B | Special Education Gym Office | T | Pipe Fitting Insulation | 7020/01/0B/11 | Assumed | 5 | EA | | | 0 | EA | | | | | | | 1 | No | 1/D |
| 1 | B | Special Education Gym Office | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 22 | LF | | | 0 | LF | | | | | | | N/A | N/A | N/A |
| 1 | B | Special Education Gym Office | N/A | Cement Floor | | Non Suspect ACM | 40 | SF | | | 0 | SF | | | | | | | N/A | N/A | N/A |
| 1 | B | Special Education Gym Office | N/A | Plaster Walls | | NAD | 336 | SF | | | 0 | SF | | | | | | | N/A | N/A | N/A |
| 1 | B | Special Education Gym Office | N/A | Plaster Ceiling | | NAD | 40 | SF | | | 5 | SF | | | | | | | N/A | N/A | N/A |
| 1 | B | Special Education Gym Office | T | Pipe Insulation 2-6 inch | 7020/01/0B/01 | Confirmed | 20 | LF | | | 0 | LF | | | | | | | 1 | No | 1/D |
| 1 | B | Special Education Gym Office | T | Pipe Fitting Insulation | 7020/01/0B/11 | Assumed | 13 | EA | | | 0 | EA | | | | | | | 1 | No | 1/D |
| 1 | B | Small Room attached To Special Education Gym Offices | M | Floor Tile VAT 12" x 12" | 7020/01/0B/A3 | Assumed | 112 | SF | | | 0 | SF | | | Yellow | | | | 1 | No | 1/D |
| 1 | B | Small Room attached To Special Education Gym Offices | N/A | Plaster Walls | | NAD | 552 | SF | | | 0 | SF | | | | | | | N/A | N/A | N/A |
| 1 | B | Small Room attached To Special Education Gym Offices | N/A | Plaster Ceiling | | NAD | 112 | SF | | | 0 | SF | | | | | | | N/A | N/A | N/A |
| 2 | 1 | Small Mechanical Room next to T7 and Building Exit | M | Floor Tile VAT 12" x 12" | 7020/02/01/A4 | Assumed | 200 | SF | | | 0 | SF | | | Tan | | | | 1 | No | 1/D |
| 2 | 1 | Small Mechanical Room next to T7 and Building Exit | N/A | Concrete Block Wall | | Non Suspect ACM | 562 | SF | | | 0 | SF | | | | | | | N/A | N/A | N/A |
| 2 | 1 | Small Mechanical Room next to T7 and Building Exit | N/A | Sheetrock Wall | | Non Suspect ACM | 562 | SF | | | 0 | SF | | | | | | | N/A | N/A | N/A |
| 2 | 1 | Small Mechanical Room next to T7 and Building Exit | N/A | Concrete Ceiling | | Non Suspect ACM | 200 | SF | | | 0 | SF | | | | | | | N/A | N/A | N/A |
| 2 | 1 | Small Mechanical Room next to T7 and Building Exit | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 125 | LF | | | 0 | LF | | | | | | | N/A | N/A | N/A |
| 2 | 1 | Small Mechanical Room next to T7 and Building Exit | T | Pipe Fitting Insulation | 7020/02/01/75 | Assumed | 18 | EA | | | 0 | EA | | | | | | | 1 | No | 1/D |
| 2 | 1 | Storage Room T7, Former Classroom | M | Floor Tile VAT 12" x 12" | 7020/02/01/A4 | Assumed | 1000 | SF | | | 0 | SF | | | Tan | | | | 1 | No | 1/D |
| 2 | 1 | Storage Room T7, Former Classroom | N/A | Concrete Block Wall | | Non Suspect ACM | 1105 | SF | | | 0 | SF | | | | | | | N/A | N/A | N/A |
| 2 | 1 | Storage Room T7, Former Classroom | N/A | Sheetrock Wall | | Non Suspect ACM | 1105 | SF | | | 0 | SF | | | | | | | N/A | N/A | N/A |
| 2 | 1 | Storage Room T7, Former Classroom | N/A | Concrete Ceiling | | Non Suspect ACM | 1000 | SF | | | 0 | SF | | | | | | | N/A | N/A | N/A |
| 2 | 1 | Storage Room T7, Former Classroom | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 120 | LF | | | 0 | LF | | | | | | | N/A | N/A | N/A |
| 2 | 1 | Storage Room T7, Former Classroom | M | Blackboard Glue Dots | 7020/02/01/BATTA/AH/2600 | Assumed | 80 | SF | | | 0 | SF | | | | | | | 1 | No | 1/D |
| 2 | 1 | Storage Room next to Former Classroom T5 | M | Floor Tile VAT 12" x 12" | 7020/02/01/A4 | Assumed | 576 | SF | | | 4 | SF | | | Tan | Missing Tiles | | | 1 | Yes | 5/B |
| 2 | 1 | Storage Room next to Former Classroom T5 | N/A | Concrete Block Wall | | Non Suspect ACM | 816 | SF | | | 0 | SF | | | | | | | N/A | N/A | N/A |
| 2 | 1 | Storage Room next to Former Classroom T5 | N/A | Sheetrock Wall | | Non Suspect ACM | 816 | SF | | | 0 | SF | | | | | | | N/A | N/A | N/A |
| 2 | 1 | Storage Room next to Former Classroom T5 | N/A | Concrete Ceiling | | Non Suspect ACM | 576 | SF | | | 0 | SF | | | | | | | N/A | N/A | N/A |
| 2 | 1 | Storage Room next to Former Classroom T5 | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 120 | LF | | | 0 | LF | | | | | | | N/A | N/A | N/A |
| 2 | 1 | Storage Room next to Former Classroom T5 | T | Pipe Fitting Insulation | 7020/02/01/75 | Assumed | 12 | EA | | | 0 | EA | | | | | | | 1 | No | 1/D |
| 2 | 1 | Storage Room next to Former Classroom T5 | M | Blackboard Glue Dots | 7020/02/01/BATTA/AH/2600 | Assumed | 64 | SF | | | 0 | SF | | | | | | | 1 | No | 1/D |
| 2 | 1 | Storage Room T5 | M | Floor Tile VAT 12" x 12" | 7020/02/01/A4 | Assumed | 768 | SF | | | 0 | SF | | | Tan | | | | 1 | No | 1/D |
| 2 | 1 | Storage Room T5 | N/A | Concrete Block Wall | | Non Suspect ACM | 1904 | SF | | | 0 | SF | | | | | | | N/A | N/A | N/A |
| 2 | 1 | Storage Room T5 | N/A | Sheetrock Wall | | Non Suspect ACM | 1904 | SF | | | 0 | SF | | | | | | | N/A | N/A | N/A |
| 2 | 1 | Storage Room T5 | N/A | Concrete Ceiling | | Non Suspect ACM | 768 | SF | | | 0 | SF | | | | | | | N/A | N/A | N/A |
| 2 | 1 | Storage Room T5 | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 80 | LF | | | 0 | LF | | | | | | | N/A | N/A | N/A |
| 2 | 1 | Storage Room T5 | T | Pipe Fitting Insulation | 7020/02/01/75 | Assumed | 7 | EA | | | 0 | EA | | | | | | | 1 | No | 1/D |
| 2 | 1 | Hallway outside Classroom T5 | M | Floor Tile VAT 12" x 12" | 7020/02/01/A4 | Assumed | 520 | SF | | | 0 | SF | | | Tan | | | | 1 | No | 1/D |
| 2 | 1 | Hallway outside Classroom T5 | N/A | Concrete Block Wall | | Non Suspect ACM | 400 | SF | | | 0 | SF | | | | | | | N/A | N/A | N/A |
| 2 | 1 | Hallway outside Classroom T5 | N/A | Sheetrock Wall | | Non Suspect ACM | 2482 | SF | | | 0 | SF | | | | | | | N/A | N/A | N/A |
| 2 | 1 | Hallway outside Classroom T5 | N/A | Concrete Ceiling | | Non Suspect ACM | 520 | SF | | | 0 | SF | | | | | | | N/A | N/A | N/A |
| 2 | 1 | Hallway outside Classroom T5 | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 90 | LF | | | 0 | LF | | | | | | | N/A | N/A | N/A |
| 2 | 1 | Hallway outside Classroom T5 | T | Pipe Fitting Insulation | 7020/02/01/75 | Assumed | 14 | EA | | | 0 | EA | | | | | | | 1 | No | 1/D |
| 2 | 1 | Small single person Restroom down hallway through the door to the left of Storage Room T5 | N/A | Cement Floor | | Non Suspect ACM | 100 | SF | | | 0 | SF | | | | | | | N/A | N/A | N/A |
| 2 | 1 | Small single person Restroom down hallway through the door to the left of Storage Room T5 | N/A | Concrete Block Wall | | Non Suspect ACM | 160 | SF | | | 0 | SF | | | | | | | N/A | N/A | N/A |
| 2 | 1 | Small single person Restroom down hallway through the door to the left of Storage Room T5 | N/A | Sheetrock Wall | | Non Suspect ACM | 160 | SF | | | 0 | SF | | | | | | | N/A | N/A | N/A |
| 2 | 1 | Small single person Restroom down hallway through the door to the left of Storage Room T5 | N/A | Fiberglass Ceiling Tile 2' x 4' | | Non Suspect ACM | 100 | SF | | | 0 | SF | | | | | | | N/A | N/A | N/A |
| 2 | 1 | Storage Room down hallway through the door to the left of Storage Room T9, next to small bathroom | M | Floor Tile VAT 12" x 12" | 7020/02/01/A4 | Assumed | 126 | SF | | | 0 | SF | | | Tan | | | | 1 | No | 1/D |
| 2 | 1 | Storage Room down hallway through the door to the left of Storage Room T9, next to small bathroom | N/A | Concrete Block Wall | | Non Suspect ACM | 322 | SF | | | 0 | SF | | | | | | | N/A | N/A | N/A |
| 2 | 1 | Storage Room down hallway through the door to the left of Storage Room T9, next to small bathroom | N/A | Sheetrock Wall | | Non Suspect ACM | 322 | SF | | | 0 | SF | | | | | | | N/A | N/A | N/A |
| 2 | 1 | Storage Room down hallway through the door to the left of Storage Room T9, next to small bathroom | N/A | Concrete Ceiling | | Non Suspect ACM | 126 | SF | | | 0 | SF | | | | | | | N/A | N/A | N/A |
| 2 | 1 | Hallway through door to the left of Storage Room T5 | M | Floor Tile VAT 12" x 12" | 7020/02/01/A4 | Assumed | 174 | SF | | | 0 | SF | | | Tan | | | | 1 | No | 1/D |
| 2 | 1 | Hallway through door to the left of Storage Room T5 | N/A | Concrete Block Wall | | Non Suspect ACM | 490 | SF | | | 0 | SF | | | | | | | N/A | N/A | N/A |
| 2 | 1 | Hallway through door to the left of Storage Room T5 | N/A | Sheetrock Wall | | Non Suspect ACM | 490 | SF | | | 3 | SF | | | | | | | N/A | N/A | N/A |
| 2 | 1 | Hallway through door to the left of Storage Room T5 | N/A | Ceiling Tile 1' x 1' | | NAD | 174 | SF | | | 0 | SF | | | | | | | N/A | N/A | N/A |
| 2 | 1 | Restroom down Hallway through the door next to Storage Room T5 with laundry machines | M | Floor Tile VAT 12" x 12" | 7020/02/01/A4 | Assumed | 180 | SF | | | 0 | SF | | | Tan | | | | 1 | No | 1/D |
| 2 | 1 | Restroom down Hallway through the door next to Storage Room T5 with laundry machines | N/A | Concrete Block Wall | | Non Suspect ACM | 648 | SF | | | 0 | SF | | | | | | | N/A | N/A | N/A |
| 2 | 1 | Restroom down Hallway through the door next to Storage Room T5 with laundry machines | N/A | Sheetrock Wall | | Non Suspect ACM | 648 | SF | | | 0 | SF | | | | | | | N/A | N/A | N/A |

7020 Olney HS (ASPIRA) 2015 2016 AHERA Three-Year Report.xls

| School District of Philadelphia Aspira Olney Charter High School 100 E. Duncannon Street, Philadelphia, PA 19120 ULCS# 7029 Year Built: 1931 | | | AHERA Three-Year Reinspection 2015-2016 Room by Room Location Log Report | | | | | | | | Reinspection Date: December 13, 2015 Building Inspector: James Madden Number: 030867 Management Planner: Megan Vala Number: 740728 | | | | | | |
|--|-----------------------|--|---|------------------------------------|--------------------------|---|-----------------------|-------------|---------------------|-------------|--|--|----------------------------------|-----------------------------|--------------------------|-------------------------|--|
| E l e m e n t | F l o o r | On Site Room Name | System Affected | Material Description | HID# | Confirmed/Assumed/NAD/ Non Suspect ACM | Amount of Material | SF LF EA | Amount of Damage | SF LF EA | Color required for VAT | Comments/Description/Notes | Attic/ Crawl Space Ranking | Damage Potential (DP) | Newly Friable (NF) | Response Action (RA) | |
| 2 | 1 | Restroom down Hallway through the door next to Storage Room T5 with laundry machines | N/A | Ceiling Tile 1' x 1' | | NAD | 180 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 2 | 1 | Restroom down Hallway through the door next to Storage Room T5 with laundry machines | M | Floor Tile VAT 12" x 12" | 7020/02/01/A4 | Assumed | 180 | SF | 0 | SF | Tan | | | 1 | No | 1/D | |
| 2 | 1 | Restroom down Hallway through the door next to Storage Room T5 with laundry machines | T | Pipe Insulation 2-6 inch | 7020/02/01/74 | Assumed | 82 | LF | 0 | LF | | | | 1 | No | 1/D | |
| 2 | 1 | Restroom down Hallway through the door next to Storage Room T5 with laundry machines | T | Pipe Fitting Insulation | 7020/02/01/75 | Assumed | 12 | EA | 0 | EA | | | | 1 | No | 1/D | |
| 2 | 1 | Restroom down Hallway through the door next to Storage Room T5 with laundry machines | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 35 | LF | 0 | LF | | | | N/A | N/A | N/A | |
| 2 | 1 | Small Kitchen near Storage Room T5 | M | Floor Tile VAT 12" x 12" | 7020/02/01/A4 | Assumed | 140 | SF | 0 | SF | Tan | | | 1 | No | 1/D | |
| 2 | 1 | Small Kitchen near Storage Room T5 | N/A | Concrete Block Wall | | Non Suspect ACM | 816 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 2 | 1 | Small Kitchen near Storage Room T5 | N/A | Ceiling Tile 1' x 1' | | NAD | 140 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 2 | 1 | Small Kitchen near Storage Room T5 | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 30 | LF | 0 | LF | | | | N/A | N/A | N/A | |
| 2 | 1 | Small Kitchen near Storage Room T5 | N/A | Fiberglass Pipe Fitting Insulation | | Non Suspect ACM | 5 | EA | 0 | EA | | | | N/A | N/A | N/A | |
| 2 | 1 | Small Closet next to Storage Room's T4 and near T5 | N/A | Cement Floor | | Non Suspect ACM | 24 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 2 | 1 | Small Closet next to Storage Room's T4 and near T5 | N/A | Concrete Block Wall | | Non Suspect ACM | 160 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 2 | 1 | Small Closet next to Storage Room's T4 and near T5 | N/A | Concrete Ceiling | | Non Suspect ACM | 24 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 2 | 1 | Small Closet next to Storage Room's T4 and near T5 | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 75 | LF | 0 | LF | | | | N/A | N/A | N/A | |
| 2 | 1 | Small Closet next to Storage Room's T4 and near T5 | N/A | Fiberglass Pipe Fitting Insulation | | Non Suspect ACM | 10 | EA | 0 | EA | | | | N/A | N/A | N/A | |
| 2 | 1 | Custodial Closet T3 | N/A | Cement Floor | | Non Suspect ACM | 96 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 2 | 1 | Custodial Closet T3 | N/A | Concrete Block Wall | | Non Suspect ACM | 400 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 2 | 1 | Custodial Closet T3 | N/A | Concrete Ceiling | | Non Suspect ACM | 96 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 2 | 1 | Women's Restroom near Custodial Closet T3 | N/A | Ceramic Tile Floors | | Non Suspect ACM | 21 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 2 | 1 | Women's Restroom near Custodial Closet T3 | N/A | Concrete Block Wall | | Non Suspect ACM | 240 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 2 | 1 | Women's Restroom near Custodial Closet T3 | N/A | Concrete Ceiling | | Non Suspect ACM | 21 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 2 | 1 | Women's Restroom near Custodial Closet T3 | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 24 | LF | 0 | LF | | | | N/A | N/A | N/A | |
| 2 | 1 | Women's Restroom near Custodial Closet T3 | T | Pipe Fitting Insulation | | Assumed | 6 | EA | 0 | EA | | | | 1 | No | 1/D | |
| 2 | 1 | Women's Restroom near Custodial Closet T3 | T | Unit Ventilator Insulation | 7020/02/01/BATTA/AH/1645 | Assumed | 4 | SF | 0 | SF | | | | 1 | No | 1/D | |
| 2 | 1 | Men's Restroom near Custodial Closet T4 | N/A | Ceramic Tile Floors | | Non Suspect ACM | 21 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 2 | 1 | Men's Restroom near Custodial Closet T4 | N/A | Concrete Block Wall | | Non Suspect ACM | 240 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 2 | 1 | Men's Restroom near Custodial Closet T4 | N/A | Concrete Ceiling | | Non Suspect ACM | 21 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 2 | 1 | Men's Restroom near Custodial Closet T4 | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 30 | LF | 0 | LF | | | | N/A | N/A | N/A | |
| 2 | 1 | Men's Restroom near Custodial Closet T4 | T | Pipe Fitting Insulation | 7020/02/01/75 | Assumed | 4 | EA | 0 | EA | | | | 1 | No | 1/D | |
| 2 | 1 | Men's Restroom near Custodial Closet T4 | T | Unit Ventilator Insulation | 7020/02/01/BATTA/AH/1645 | Assumed | 4 | SF | 0 | SF | | | | 1 | No | 1/D | |
| 2 | 1 | Men's Restroom near Custodial Closet T4 | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 30 | LF | 0 | LF | | | | N/A | N/A | N/A | |
| 2 | 1 | Men's Restroom near Custodial Closet T4 | N/A | Fiberglass Pipe Fitting Insulation | | Non Suspect ACM | 4 | EA | 0 | EA | | | | N/A | N/A | N/A | |
| 2 | 1 | Custodial Storage Room T4 | M | Floor Tile VAT 12" x 12" | 7020/02/01/A4 | Assumed | 340 | SF | 0 | SF | Tan | | | 1 | No | 1/D | |
| 2 | 1 | Custodial Storage Room T4 | N/A | Concrete Ceiling | | Non Suspect ACM | 340 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 2 | 1 | Custodial Storage Room T4 | N/A | Concrete Block Wall | | Non Suspect ACM | 1258 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 2 | 1 | Custodial Storage Room T4 | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 140 | LF | 0 | LF | | | | N/A | N/A | N/A | |
| 2 | 1 | Custodial Storage Room T4 | N/A | Fiberglass Pipe Fitting Insulation | | Non Suspect ACM | 12 | EA | 0 | EA | | | | N/A | N/A | N/A | |
| 2 | 1 | Classroom T2 | M | Floor Tile VAT 12" x 12" | 7020/02/01/A4 | Assumed | 612 | SF | 0 | SF | Tan | | | 1 | No | 1/D | |
| 2 | 1 | Classroom T2 | N/A | Ceiling Tile 2' x 4' | | NAD | 612 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 2 | 1 | Classroom T2 | N/A | Concrete Block Wall | | Non Suspect ACM | 1248 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 2 | 1 | Classroom T2 | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 50 | LF | 0 | LF | | | | N/A | N/A | N/A | |
| 2 | 1 | Classroom T2 | N/A | Sheetrock Wall | | Non Suspect ACM | 300 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 2 | 1 | Classroom T2 | M | Blackboard Glue Dots | 7020/02/01/BATTA/AH/2600 | Assumed | 64 | SF | 0 | SF | | | | 1 | No | 1/D | |
| 2 | 1 | Classroom T1 used for Storage | M | Floor Tile VAT 12" x 12" | 7020/02/01/A4 | Assumed | 648 | SF | 0 | SF | Tan | | | 1 | No | 1/D | |
| 2 | 1 | Classroom T1 used for Storage | N/A | Ceiling Tile 2' x 4' | | NAD | 648 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 2 | 1 | Classroom T1 used for Storage | N/A | Concrete Block Wall | | Non Suspect ACM | 1272 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 2 | 1 | Classroom T1 used for Storage | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 80 | LF | 0 | LF | | | | N/A | N/A | N/A | |
| 2 | 1 | Classroom T1 used for Storage | N/A | Fiberglass Pipe Fitting Insulation | | Non Suspect ACM | 29 | EA | 0 | EA | | | | N/A | N/A | N/A | |
| 2 | 1 | Classroom T1 used for Storage | N/A | Sheetrock Wall | | Non Suspect ACM | 300 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 2 | 1 | Classroom T1 used for Storage | T | Pipe Insulation > 6 inch | 7020/02/01/BATTA/AH/1110 | Confirmed | 15 | LF | 0 | LF | | | | 1 | No | 1/D | |
| 2 | 1 | Custodial Closet to the Left of Classroom T1 | N/A | Cement Floor | | Non Suspect ACM | 50 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 2 | 1 | Custodial Closet to the Left of Classroom T1 | N/A | Concrete Ceiling | | Non Suspect ACM | 50 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 2 | 1 | Custodial Closet to the Left of Classroom T1 | N/A | Concrete Block Wall | | Non Suspect ACM | 200 | SF | 0 | SF | | | | N/A | N/A | N/A | |
| 2 | 1 | Custodial Closet to the Left of Classroom T1 | N/A | Fiberglass Pipe Insulation | | Non Suspect ACM | 75 | LF | 0 | LF | | | | N/A | N/A | N/A | |
| 2 | 1 | Custodial Closet to the Left of Classroom T1 | N/A | Fiberglass Pipe Fitting Insulation | | Non Suspect ACM | 8 | EA | 0 | EA | | | | N/A | N/A | N/A | |
| 1 | A | Attic - access by 5th Floor Stairwell #5 | X | X | | X | X | X | X | X | | Sealed Shut w/asbestos sign | D | X | X | X | |
| 1 | A | Attic - access by 5th Floor Hallway | X | X | | X | X | X | X | X | | 300 Air Cell/50 Hard Fittings/600 Mag Blck | D | X | X | X | |
| 1 | C | Crawl Space - access by Basement Fan Room | X | X | | X | X | X | X | X | | 300 LF 2"-6" Mag Block undamaged | B | X | X | X | |
| 1 | C | Crawl Space - access by Storage Room near Time clock | X | X | | X | X | X | X | X | | Likely duplicated entry/See additional entries below | A | X | X | X | |
| 1 | C | Crawl Space - access by Hall across from Fan Room | X | X | | X | X | X | X | X | | Door Screwed shut | ? | X | X | X | |
| 1 | C | Crawl Space - access by Storage Room near Time Clock (lower) | X | X | | X | X | X | X | X | | Access blocked by equipment/Upper/Lower CS likely mixed up from prior inspection 11/16/10. Inspector could not inspect | ? | X | X | X | |
| 1 | C | Crawl Space - access by Storage Rm near Time Clock (upper) | X | X | | X | X | X | X | X | | No spray on insulation in Upper CS/Upper/Lower likely mixed up from prior inspection 11/16/10 | C to A | X | X | X | |

Section III Certificates

A. Management Planner/Building Inspector Certificates

Section III – A

Management Planner/Building Inspector Certificates

These charts indicate the Name, Course Date, Expiration Date and Corresponding Certificate Number of the Management Planner and Building Inspector of individuals that participated in the AHERA 3 Year Inspection and Management Plan process of 2015/2016.

| Management Planner | Date Granted | Expiration Date | Certificate Number |
|--------------------|--------------|-----------------|--------------------|
| Monique Causley | 2/15/2015 | 2/16/2016 | ACC-0215-8-010 |
| Monique Causley | 2/16/2016 | 2/17/2017 | ACC-0216-8-001 |
| Megan Vala | 5/22/2015 | 6/22/2016 | 740728 |
| Mary Anne Lerro | 4/5/2016 | 4/5/2017 | 742327 |

| Building Inspector | Date Granted | Expiration Date | Certificate Number |
|--------------------|--------------|-----------------|--------------------|
| Scott Magee | 8/15/2015 | 8/15/2016 | 70016699C |
| William Garrity | 8/15/2015 | 8/15/2016 | 70016699A |
| Bernard Brunner | 10/2/2015 | 8/2/2016 | 45397 |
| Mary Anne Lerro | 3/3/2015 | 3/3/2016 | 740092 |
| Mary Anne Lerro | 4/5/2016 | 4/5/2017 | 742322 |
| James Madden | 12/11/2014 | 12/11/2015 | ACC-1214-6-010 |
| James Madden | 12/3/2015 | 12/3/2016 | ACC-1215-6-018 |
| Troy Ray | 3/15/2015 | 3/19/2016 | ACC-0355-6-011 |
| Ananth Vinjamuri | 9/29/2015 | 9/29/2016 | 374 |
| Shelton Williams | 9/29/2015 | 9/29/2016 | 375 |
| Paul Davis | 2/12/2015 | 2/12/2016 | ACC-0215-6-015 |
| Paul Davis | 2/2/2016 | 2/2/2017 | 741836 |
| Bernard Bryson | 2/16/2015 | 2/16/2016 | ACC-0125-6-031 |
| Bernard Bryson | 2/15/2016 | 2/15/2017 | ACC-0216-6-005 |
| Alexander Roman | 9/18/2015 | 9/18/2016 | EHSBIR-150619-008 |
| Norm Harrison | 9/2/2015 | 9/2/2016 | ACC-0915-6-011 |
| Kelly Mayberry | 2/20/2015 | 2/20/2016 | EHSBIR-150220-005 |
| Kelly Mayberry | 2/18/2016 | 2/18/2017 | EHSBIR-160218-006 |
| Andrew Hine | 5/6/2015 | 5/6/2016 | AI05042015-3 |
| Maryellen Leotta | 2/12/2015 | 2/12/2016 | ACC-0215-6-024 |

Certificate of Completion

awarded to

Monique Causley

for successfully completing the prescribed course of study in

Pennsylvania Asbestos Management Planner Refresher Course

under TSCA Title II

presented by

ACCESS TRAINING SERVICES, INC.
7921 River Road, Pennsauken, NJ 08110
(856) 665-3449

2/16/15

Course Date

N/A

Exam Date

2/16/16

Expiration Date

Not Provided

Social Security Number

ACC-0215-8-010

Certificate Number

Mark K. Schlager
Training Director

Certificate of Completion

awarded to

Monique Causley

for successfully completing the prescribed course of study in

Pennsylvania Asbestos Management Planner Refresher Course

under TSCA Title II

presented by

ACCESS TRAINING SERVICES, INC.
7921 River Road, Pennsauken, NJ 08110
(856) 665-3449

2/15/16

Course Date

N/A

Exam Date

2/15/17

Expiration Date

Not Provided

Social Security Number

ACC-0216-8-001

Certificate Number

Mark K. Schlüger
Training Director

Certificate of Training

CRITERION LABORATORIES, INC.

HEREBY CERTIFIES THAT

Megan Vala

HAS SUCCESSFULLY COMPLETED A 16 HOUR COURSE ENTITLED

Asbestos Management Planner Initial

INCLUDING CLASSROOM INSTRUCTION

05/21/2015 to 05/22/2015


Exam passed on this 22nd day of May 2015 - Score - 94

Approved for AHERA Accreditation Under TSCA Title II

3370 Progress Drive, Suite J
Bensalem, PA 19020
(215) 244-1300 - Phone
(215) 244-4349 - Fax
www.criterionlabs.com

Course is conducted in English

DIRECTOR:


James A. Welte, CIH, President

Certificate of Training

CRITERION LABORATORIES, INC.

HEREBY CERTIFIES THAT

Mary Anne Lerro

HAS SUCCESSFULLY COMPLETED A 4 HOUR COURSE ENTITLED
Asbestos Management Planner Refresher

INCLUDING CLASSROOM INSTRUCTION

on this 5th day of April 2016

Approved for AHERA Accreditation Under TSCA Title II

3370 Progress Drive, Suite J
Bensalem, PA 19020
(215) 244-1300 - Phone
(215) 244-4349 - Fax
www.criterionlabs.com

Course is conducted in English

DIRECTOR:

James A. Welts
James A. Welts, CIH, President

EMSL ANALYTICAL, INC.

Certifies that

Scott Magee

has successfully completed the course of study for the

Asbestos Building Inspector Refresher Course

for Accreditation under TSCA Title II

EMSL Certificate No. 70016699C


Approved by:

PA Dept. of Labor and Industry
Accreditation # 137

Course Date: 8/15/2015
Granted: 8/15/2015
Expiration Date: 8/15/2016

Sponsored by:

EMSL Analytical, Inc.
200 Route 130 North
Cinnaminson, NJ 08077
Phone: (800) 220-3675
Fax: (856) 786-5973
www.emsl.com



Michael P. Menz

Michael P. Menz, CIH
Training Director

Environmental, Mold, Bacteria, IAQ, Asbestos, Lead, Forensic and Materials Testing Since 1981

EMSL ANALYTICAL, INC.

Certifies that

William Garrity

has successfully completed the course of study for the

Asbestos Building Inspector Refresher Course

for Accreditation under TSCA Title II

EMSL Certificate No. 70016699A


Approved by:

PA Dept. of Labor and Industry
Accreditation # 137

Course Date: 8/15/2015
Granted: 8/15/2015
Expiration Date: 8/15/2016

Sponsored by:

EMSL Analytical, Inc.
200 Route 130 North
Cinnaminson, NJ 08077
Phone: (800) 220-3675
Fax: (856) 786-5973
www.emsl.com



Michael P. Menz

Michael P. Menz, CIH
Training Director

Environmental, Mold, Bacteria, IAQ, Asbestos, Lead, Forensic and Materials Testing Since 1981

45397

National Asbestos & Environmental Training Institute

CERTIFICATE OF COMPLETION

AHERA/EPA Accredited Per 40 CFR Part 763
Asbestos Accreditation under TSCA Title II

This is to certify that


Bernard Brunner, Jr.

Successfully completed the course entitled

**1/2-Day New York State/EPA/AHERA Asbestos Building Inspector Annual Refresher on
October 2, 2015**

Examination Passed October 2, 2015

Expiration Date on October 2, 2016


Doris L. Adler
President, NAEETI

Per 10 NYCRR Part 73.2 (L) (1), DOH 2832 Certificate of Completion of Asbestos
Safety Training is the only official record of training for N.Y.S. students.

Language: English

ABIH 1/2 CM POINT

3321 Doris Avenue, Building B, Ocean, NJ 07712

Phone (732) 531-5571

Fax (732) 531-5956

www.naeti.com

Number 740092

Expiration Date:
03/03/2016

Certificate of Training

CRITERION LABORATORIES, INC.

HEREBY CERTIFIES THAT

Mary Anne Lerro

HAS SUCCESSFULLY COMPLETED A 4 HOUR COURSE ENTITLED

Asbestos Building Inspector Refresher

on this 3rd day of March 2015

Exam passed on this 3rd day of March 2015 - Score - 84

Approved for AHERA Accreditation Under TSCA Title II

3370 Progress Drive, Suite J
Bensalem, PA 19020
(215) 244-1300 - Phone
(215) 244-4349 - Fax
www.criterionlabs.com

Course is conducted in English

DIRECTOR:

James A. Welts

James A. Welts, CIH, President

Number 742322

Expiration Date:
04/05/2017

Certificate of Training

CRITERION LABORATORIES, INC.

HEREBY CERTIFIES THAT

Mary Anne Lerro

HAS SUCCESSFULLY COMPLETED A 4 HOUR COURSE ENTITLED

Asbestos Building Inspector Refresher

INCLUDING CLASSROOM INSTRUCTION

on this 5th day of April 2016

Exam passed on this 5th day of April 2016 - Score - 88

Approved for AHERA Accreditation Under TSCA Title II

3370 Progress Drive, Suite J
Bensalem, PA 19020
(215) 244-1300 - Phone
(215) 244-4349 - Fax
www.criterionlabs.com

Course is conducted in English

DIRECTOR:

James A. Welts

James A. Welts, CIH, President

Certificate of Completion

James Madden

for successfully completing the prescribed course of study in

Pennsylvania Asbestos Building Inspector Refresher Course

under TSCA Title II

presented by

ACCESS TRAINING SERVICES, INC.
7921 River Road, Pennsauken, NJ 08110
(856) 665-3449

12/11/14

Course Date

N/A

Exam Date

12/11/15

Expiration Date

Not Provided

Social Security Number

ACC-1214-6-010

Certificate Number

Mark K. Schlager
Training Director

Certificate of Completion

James Madden

for successfully completing the prescribed course of study in

Pennsylvania Asbestos Building Inspector Refresher Course

under TSCA Title II

presented by

ACCESS TRAINING SERVICES, INC.
7921 River Road, Pennsauken, NJ 08110
(856) 665-3449

12/3/15

Course Date

N/A

Exam Date

12/3/16

Expiration Date

Not Provided

Social Security Number

ACC-1215-6-018

Certificate Number

Mark K. Schlager
Mark K. Schlager
Training Director

Certificate of Completion

Troy A. Ray

for successfully completing the prescribed course of study in

Pennsylvania Asbestos Building Inspector Refresher Course

under TSCA Title II

presented by

**ACCESS TRAINING SERVICES, INC.
7921 River Road, Pennsauken, NJ 08110
(856) 665-3449**

3/19/15

Course Date

N/A

Exam Date

3/19/16

Expiration Date

Not Provided

Social Security Number

ACC-0355-6-011

Certificate Number

Mark K. Schlager
Training Director

CERTIFICATE NO 374

G&C Environmental Services, Inc. (#294)

2 Street Road, Newtown Square, Pennsylvania 19073

Telephone: (610) 993-9202 Facsimile: (610) 993-9232

Email: Training@gcenviro.com

www.GCenviro.com

This document certifies that Ananth K. Vinjamuri has successfully completed this State of New York Department of Health Approved AHERA BUILDING INSPECTOR

REFRESHER COURSE, completed as required for asbestos accreditation under the Toxic

Substances Control Act, Title II. This course was held from 09/29/2015 to 09/29/2015.

The examination date was 09/29/2015. This certificate expires one year from the date of
successful completion of the examination 09/29/2016.

The official record of successful training completion is the New York State Department of Health certificate of asbestos safety training completion (DPH 2832).

Gail M. Conner
Training Director

Gail M. Conner

CERTIFICATE NO 375

G&C Environmental Services, Inc. (#294)

2 Street Road, Newtown Square, Pennsylvania 19073

Telephone: (610) 993-9202 Facsimile: (610) 993-9232

Email: Training@gcenviro.com

www.GCenviro.com

This document certifies that Shelton Williams has successfully completed this State of New York Department of Health Approved AHERA BUILDING INSPECTOR

REFRESHER COURSE, completed as required for asbestos accreditation under the Toxic

Substances Control Act, Title II. This course was held from 09/29/2015 to 09/29/2015.
MM DD YR MM DD YR

The examination date was 09/29/2015. This certificate expires one year from the date of
MM DD YR MM DD YR
successful completion of the examination 09/29/2016.
MM DD YR

The official record of successful training completion is the New York State Department of Health certificate of asbestos safety training completion (DPH 2832).

Gail M. Conner
Training Director

Gail M. Conner

Certificate of Completion

Paul M. Davis

for successfully completing the prescribed course of study in

Pennsylvania Asbestos Building Inspector Refresher Course

under TSCA Title II

presented by

ACCESS TRAINING SERVICES, INC.
7921 River Road, Pennsauken, NJ 08110
(856) 665-3449

2/12/15

Course Date

N/A

Exam Date

2/12/16

Expiration Date

Not Provided

Social Security Number

ACC-0215-6-015

Certificate Number

Mark K. Schlager
Training Director

Certificate of Training

CRITERION LABORATORIES, INC.

HEREBY CERTIFIES THAT

Paul M. Davis

HAS SUCCESSFULLY COMPLETED A 4 HOUR COURSE ENTITLED
Asbestos Building Inspector Refresher

INCLUDING CLASSROOM INSTRUCTION

on this 2nd day of February 2016

Exam passed on this 2nd day of February 2016 - Score - 92

Approved for AHERA Accreditation Under ISCA Title II

3370 Progress Drive, Suite J
Bensalem, PA 19020
(215) 244-1300 - Phone
(215) 244-4349 - Fax
www.criterionlabs.com

Course is conducted in English

DIRECTOR:

James A. Wells

James A. Wells, CIH, President

Certificate of Completion

Bernard J. Bryson

for successfully completing the prescribed course of study in

Pennsylvania Asbestos Building Inspector Refresher Course

under TSCA Title II

presented by

ACCESS TRAINING SERVICES, INC.
7921 River Road, Pennsauken, NJ 08110
(856) 665-3449

2/16/15
Course Date

N/A

Exam Date

2/16/16

Expiration Date

Not Provided

Social Security Number

ACC-0125-6-031

Certificate Number

Mark K. Schlager
Training Director

Certificate of Completion

Bernard J. Bryson

for successfully completing the prescribed course of study in

Pennsylvania Asbestos Building Inspector Refresher Course

under TSCA Title II

presented by

ACCESS TRAINING SERVICES, INC.
7921 River Road, Pennsauken, NJ 08110
(856) 665-3449

2/15/16

Course Date

N/A

Exam Date

2/15/17

Expiration Date

Not Provided

Social Security Number

ACC-0216-6-005

Certificate Number

Mark K. Schlager
Training Director

EHS TRAINING INSTITUTE, INC.

A Division of BATTI, Inc.

Certificate of Completion

AHERA Building Inspector

(Refresher)

Awarded To:

Alexander Roman

SS#:XXX-XX-1743

Who has completed this 4-hour course and examination,

EPA Approved under TSCA Title II

AHERA / ASHARA Rule

40 CFR Part 763.

EHS TRAINING INSTITUTE, INC.

A Division of BATTI, Inc.

Delaware Industrial Park • 6 Garfield Way

Newark, DE 19713-5817

(302) 737-3376 • Fax (302) 737-5764

Course Date: September 18, 2015

Date of Expiration: September 18, 201

Certification Number : EHSBIR 150619-008


Todd K. Zeisloff, Instructor


Neeraj K. Batta, President

Certificate of Completion

Norman Harrison

for successfully completing the prescribed course of study in

Pennsylvania Asbestos Building Inspector Refresher Course

under TSCA Title II

presented by

ACCESS TRAINING SERVICES, INC.
7921 River Road, Pennsauken, NJ 08109
(856) 665-3449

9/2/15

Course Date

N/A

Exam Date

9/2/16

Expiration Date

Not Provided

Social Security Number

ACC-0915-6-011

Certificate Number

Mark A. Schlenger
Training Director

EHS TRAINING INSTITUTE, INC.
A Division of BATTI, Inc.

Certificate of Completion

AHERA Building Inspector

(Refresher)

Awarded To:

Kelly Mayberry

SS#:XXX-XX-1551

Who has completed this 4-hour course and examination,
EPA Approved under TSCA Title II
AHERA / ASHARA Rule
40 CFR Part 763.

EHS TRAINING INSTITUTE, INC.

A Division of BATTI, Inc.

Delaware Industrial Park • 6 Garfield Way

Newark, DE 19713-5817

(302) 737-3376 • Fax (302) 737-5764

Course Date: February 20, 2015

Date of Expiration: February 20, 2016

Certification Number : EHSBIR 150220-005


Todd K. Zeisloft, Instructor


Neeraj K. Batta, President

EHS TRAINING INSTITUTE, INC.
A Division of BATTI, Inc.

Certificate of Completion

AHERA Building Inspector

(Refresher)

Awarded To:

Kelly Mayberry

SS#:XXX-XX-1551

Who has completed this 4-hour course and examination,

EPA Approved under TSCA Title II

AHERA / ASHARA Rule

40 CFR Part 763.

EHS TRAINING INSTITUTE, INC.

A Division of BATTI, Inc.

Delaware Industrial Park • 6 Garfield Way

Newark, DE 19713-5817

(302) 737-3376 • Fax (302) 737-5764

Course Date: February 18, 2016

Date of Expiration: February 18, 2017

Certification Number : EHSBIR 160218-006



Todd K. Zeisloft, Instructor



Neeraj K. Batta, President

AEROSOL MONITORING & ANALYSIS, INC.

This is to certify that
ANDREW HINE

*has met the attendance requirements and successfully completed
the course entitled*

3-DAY EPA AHERA INSPECTOR
For Accreditation Under TSCA Title II

05/04/2015 to 05/06/2015

Course Date

05/06/2015

Exam Date

5/6/2016

Expiration Date

STEVE SIERAGI

Principal Instructor

Steve Sieragi

A105042015-3

Certification No.

E. Rush Barnett

Course Director

E. Rush Barnett

1331 Ashton Road

P.O.Box 646

Hanover, MD 21076

P: 410-684-3327

F: 410-684-3724

www.amatraining.com

Certificate of Completion

Maryellen Leotta

for successfully completing the prescribed course of study in

Pennsylvania Asbestos Building Inspector Refresher Course

under TSCA Title II

presented by

ACCESS TRAINING SERVICES, INC.
7921 River Road, Pennsauken, NJ 08110
(856) 665-3449

2/12/15

Course Date

N/A

Exam Date

2/12/16

Expiration Date

Not Provided

Social Security Number

ACC-0215-6-024

Certificate Number

Mark K. Schlüger
Training Director

Asbestos Hazard Emergency Response Act (AHERA) Environmental Compliance Audit Cross Reference Table

In response to the AHERA Environmental Compliance Audit a Cross Reference Table has been prepared for inclusion into the Environmental Management Plan. The purpose of this Cross Reference Table is to link the following documents to the AHERA Management Plan.

| Cross Reference Table | |
|--|--|
| 3 Year Reinspection Report follows this Cross Reference Table documentation. | |
| Subject Matter | Location of Required Documents |
| Designated Person | Pages 1 - 3 |
| Annual Notification | Pages 4 - 5 |
| 6 Month Periodic Surveillance Outline of Events | Page 6 |
| 3 Year Re-inspections Outline of Events | Page 7 |
| Asbestos Management Program (operations and maintenance) | Pages 8 - 19 |
| Asbestos Investigation Report (AIR) | Attachment 1 Letter Dated August 4, 2006 |
| Training (included in the Asbestos Management Program) | <p>The original records are centralized at the School District's Environmental Library. Copies are maintained on staff and are required to be maintained in the latest Reinspection Report.</p> <p>2 hour awareness training records for all Building Engineers, Custodian Assistants and maintenance personnel</p> <p>40 hour worker/supervisor training records for the OEMS A-Team and various AST tradesmen.</p> |
| Response Actions (monthly mailings if applicable) | <p>The original documents are on file at the School District's Environmental Library.</p> <p>Copies of the original are mailed to the Schools Main Office for retention with the Management Plan documentation. These documents are typically kept separate from the management plan in an update binder due to the potential volume of response action reports.</p> |

SCHOOL DISTRICT OF PHILADELPHIA

ASBESTOS DESIGNATED PERSON

Gerald F Junod
Office of Capital Programs
Environmental Management & Services
440 N Broad Street, 3rd Floor
Philadelphia, PA 19130
Telephone: 215 400 6738
Fax: 215 400 4751

| | |
|--|-------------------------------------|
| Drexel University- Asbestos Building Inspector Course | January 9-11, 1989 24 Hours |
| Drexel University- Asbestos Management Planner Course | January 12-13, 1989 16 Hours |
| Criterion Laboratories, Inc. - Asbestos Management Planner Course | October 11-12, 2012 16 Hours |

| | |
|--|------------------------|
| <u>Annual Building Inspector Refreshers</u> | 1990 to Present |
| 4 Hours | |
| Drexel University | |
| Criterion Laboratories, Inc | |
| Access Training Services, Inc. | |

| | |
|---|------------------------|
| <u>Annual Building Management Planner Refreshers</u> | 1990 to 1994 |
| 4 Hours | |
| Drexel University | |
| Criterion Laboratories, Inc | 2013 to Present |
| 4 Hours | |

Environmental Manager, School District of Philadelphia

Manages the design and implementation of asbestos and lead projects for the Capital Improvement Program and other District Departments including Facilities & Operations and Information Technology. Ensures that asbestos abatement and lead remediation projects are expertly designed and executed in accordance with industry best management practice standards and regulations.

Manager, City of Philadelphia Asbestos Control Program

Served as the Asbestos Control Program Manager for the City of Philadelphia, Department of Public Health, Air Management Services, Asbestos Control Unit from August 1, 2003 through October 23, 2006.

Mid Atlantic Regional Environmental Consortium (MAREC)

Former member with attendance and participation commitments of all quarterly EPA Region III and yearly National Asbestos Regulatory Conferences sponsored by the EPA and the National Conference of State Legislators respectively as a representative for the City of Philadelphia Department of Public Health Air Management Services from 1994 through 2006.

Philadelphia Environmental Task Force


Former member of the Philadelphia Environmental Task force as a representative and point of contact for the City of Philadelphia Department of Public Health Air Management Services Asbestos Control Unit from 2002 through 2006.

Asbestos Instructor

Worked as the primary instructor for the initial and annual Asbestos Project Inspector training and licensing program as mandated by City of Philadelphia Department of Public Health Asbestos Control Regulations from August 1994 through October 2006.

Worked as a lead instructor with an Environmental Consulting Firm and approved by the US EPA for the initial and annual refresher training courses for various asbestos occupational disciplines such as the Building Inspector, Management Planner and Worker/Supervisor from 1991 through 1994.

I certify that the general, local agency responsibilities as stipulated in Section 763.84 will be met.



Gerald F. Junod
Asbestos Designated Person
Environmental Manager
Office of Environmental Management and Services

SCHOOL DISTRICT OF PHILADELPHIA

Accreditation Information Statement

All persons who inspect for Asbestos Containing Building Materials (ACBM) and who will design or carry out response actions with respect to assumed and confirmed ACBM, will be accredited by an EPA approved course and/or a State Contractors Accreditation Program under Sections 206 (c) and 206 (b) of Title II of the ACT.

A handwritten signature in black ink, appearing to read 'Gerald F. Junod', is written over the printed name and title.

**Gerald F. Junod
Asbestos Designated Person
Environmental Manager
Office of Environmental Management and Services**

SCHOOL DISTRICT OF PHILADELPHIA
OFFICE OF CAPITAL PROGRAMS
440 NORTH BROAD STREET, SUITE 373
PHILADELPHIA, PENNSYLVANIA 19130

OFFICE OF ENVIRONMENTAL MANAGEMENT AND SERVICES

PHONE (215)-400-4750

September 2015

TO: Principals
Building Administrators/Occupants
Parents/Guardians

FROM: Fran Burns
Chief Operating Officer

Francine Locke, M.S., Director
Office of Environmental Management and Services

SUBJECT: Annual EPA Notification Letter

Pursuant to the Federal Environmental Protection Agency (EPA) mandate, as required by 40 C.F.R. 763.84 (c)(d) of public access to environmental records, this letter is to acknowledge the availability of your facility's Asbestos Hazard Emergency Response Act (AHERA) Management Plan.

Each member of the school staff, parents/guardians, temporary workers and/or contractors, are required to receive a copy of the Notification Letter. At the direction of the Principal, a copy is to be posted on the bulletin boards and an appropriate amount of copies are to be generated for distribution.


Note: The AHERA Three-Year Reinspection reports, in colored binders; White with Pink, Tan, Black, Red, Dark Blue, Green, Yellow and White, are Federal EPA mandated inspection documents. The School District of Philadelphia is subject to severe monetary penalties if the reports and associated paperwork are not available to the EPA and the public upon request.

It is incumbent on designated school personnel to gather and retain this data as it is delivered, in one location for future review. Acceptable locations include the Principal's Office or Main Office for the primary data. The Building Engineer should maintain any secondary or duplicate copies.

If you have any questions, please call 215-400-4750. Thank you for your cooperation.



Fran Burns
Chief Operating Officer



Francine Locke, M.S., Director
Office of Environmental Management
and Services

c: Danielle Floyd

AHERA-4
8/21/15



School District of Philadelphia
OFFICIAL NOTICE

PLEASE POST

September 2015

TO: Principals
Building Administrators
Building Engineers
Building Occupants
Parents/Guardians

FROM: Fran Burns
Chief Operating Officer

Francine Locke, M.S., Director
Office of Environmental Management and Services

SUBJECT: Annual Notification Letter: Asbestos Hazard Emergency Response Act

The Federal Register published on October 30, 1987, Subpart E, in Schools: Final Rule and Notice, 763.84 (c)(d) states that each local education agency shall ensure that workers and building occupants or guardians are to be informed at least once each school year about inspections, response actions and post-response action activities including re-inspections and periodic surveillance activities. The School District as the Local Education Agency (LEA), retains such reports that are available for public inspection in the Office of the Principal or Building Administrator.

The Principal or Building Administrator is required to do the following with this notification:

- 1) Post in a Public Place or Main Office
- 2) Inform Building Occupants
- 3) Send a copy of this notification to Parents or Guardians
- 4) Insert a copy into the latest AHERA Three-Year Reinspection report (white/pink binder) in your office or facility.

A handwritten signature of Fran Burns in black ink.

Fran Burns
Chief Operating Officer

A handwritten signature of Francine Locke in black ink.

Francine Locke, M.S., Director
Office of Environmental Management
and Services

c: Danielle Floyd

AHERA-4a
8/21/15

SCHOOL DISTRICT OF PHILADELPHIA
Education Center
440 North Broad Street
Philadelphia, Pennsylvania 19130

Office of Environmental Management and Services

215-400-4750

AHERA
Six Month Surveillance
Outline of Events

- Pursuant to the Federal Environmental Protection Agency (EPA) mandate, as required by 40 CFR 763.92(b), the following procedure is to be implemented. At least once every six (6) months after a Management Plan is in effect, each Local Education Agency (LEA) shall conduct a periodic surveillance in each building that it owns or leases that contains Asbestos Containing Building Materials (ACBM) or is assumed to contain ACBM.
- The first Bi-Annual Inspection starts in the Spring (March, April, May) and again in the Fall (October, November, December) of each year. The Building Engineer/Assistant should assist the Building Inspector with appropriate access to all areas including (Crawlspaces/Attics) and rooms in the facility. There is no action required of the Principal.
- The Building Inspector shall visually inspect all areas that are identified in the Management Plan as ACBM or assumed ACBM. The date of the surveillance is recorded, the inspectors name and any changes in the conditions of the materials.
- The Building Inspector shall make a copy of the inspection document and insert into the front of the latest Management Plan (AHERA Three Year Reinspection report). The original document is returned to the LEA's Environmental Library and filed.

SCHOOL DISTRICT OF PHILADELPHIA
Education Center
440 North Broad Street
Philadelphia, Pennsylvania 19130

Office of Environmental Management and Services

215-400-4750

AHERA
Three Year Reinspection
Outline of Events

- Pursuant to the Federal Environmental Protection Agency (EPA) mandate, as required by 40 CFR 763.85(b) the following procedure is to be implemented. At least once every three (3) years after a Management Plan is in effect, each Local Education Agency (LEA) shall conduct a reinspection of each building that it owns or leases that contains Asbestos Containing Building Material's (ACBM's) or is assumed to contain ACBM.
- Subsequent Three Year Re-inspections (2009, 2012, 2015, etc) shall start in the Fall (October, November, December, January). The Building Engineer/Assistant should assist the Building Inspector with appropriate access to all areas including (Crawlspaces/Attics) and rooms in the facility. There is no action required of the Principal.
- An accredited Building Inspector shall visually inspect and touch to determine friability, all areas that are identified in the Management Plan as ACBM or assumed ACBM. The date of the surveillance is recorded, the inspectors name and any changes in the conditions of the materials. The Building Inspectors state of accreditation and license number is required.
- After the inspection, the Building Inspector shall make a copy of the inspection documents and insert into the front of the latest Management Plan (AHERA Three Year Reinspection report). The original document is returned to the LEA's Environmental Library and filed.
- The Building Inspector shall return the reinspection data to the Management Planner to be assessed and determine appropriate response actions and a report issued (AHERA Three Year Reinspection report). One copy of the report is delivered to the schools Principal to be permanently retained with all previous environmental data. Another copy is retained in the LEA's Environmental Library.



School District of Philadelphia
Office of Environmental Management & Services
440 North Broad Street
Philadelphia, PA 19130
(215) 400-4750

School District of Philadelphia
Asbestos Management Program

TABLE OF CONTENTS

| | |
|--|---------|
| Definitions..... | Page 9 |
| 1. Introduction..... | Page 10 |
| 2. Summary of Asbestos Management Plan | |
| 3. Asbestos Management Plan Execution..... | Page 11 |
| a. General Execution | |
| 4. Summary of Program Execution | |
| a. Asbestos Management Plan Execution | |
| 5. Responsibilities | |
| a. OEMS | |
| b. Asbestos Worker/Supervisor "A-TEAM"..... | Page 12 |
| c. Asbestos Designated Person | |
| d. Supervisor or Project Manager (Capital, Maintenance & Facilities) | |
| e. Employee Capital..... | Page 13 |
| f. Employee Maintenance | |
| g. Employee Facilities and Custodial | |
| 6. Requirements..... | Page 14 |
| a. Employee Exposure Monitoring | |
| b. Employee Notification | |
| c. Observation of Monitoring | |
| d. Training Program | |
| e. Access of Information | |
| f. Record Keeping | |
| 7. AHERA O&M Plan..... | Page 15 |
| a. Controls | |
| 8. O&M Response Actions..... | Page 16 |
| a. Facility Maintenance Isolation of Area | |
| b. Unlikely Contact with ACM/PACM | |
| c. Accidental Disturbance of ACM/PACM | |
| d. Planned Disturbance of ACM/PACM | |
| e. Miscellaneous ACM/PACM..... | Page 17 |
| f. Vinyl Asbestos Floor Tile | |
| g. Mastic/Adhesives | |
| h. Woven Vibration Dampers | |
| i. Other Work Practices | |
| j. Fiber Release Episodes | |
| 9. References and Resources..... | Page 18 |

DEFINITIONS / ACRONYMS

| | |
|-----------------------------------|--|
| ACM/PACM: | Asbestos Containing Material/Potential Asbestos Containing Material |
| AHERA: | Asbestos Hazard Emergency Response Act |
| AIR FORM: | Asbestos Inspection Report Form |
| Amended Water: | Water to which a surfactant (soap) has been added |
| AMP: | Asbestos Management Program/Asbestos Management Plan |
| Asbestos Designate Person: | Individual assigned by the district to oversee asbestos related issues. |
| Asbestos Regulated Area: | Location that is posted as an asbestos work area in which only approved and accredited personnel are permitted to enter |
| AST: | Asbestos Support Team involving approved and accredited school district tradespersons personnel that are school district person |
| A-TEAM: | School District of Philadelphia asbestos workers |
| CIP: | Capital Improvement Program |
| Consultant: | Asbestos consulting firm hired by the District |
| Demolition Directive: | Memorandum – August 4, 2006 from Patrick Henwood |
| EPA: | Environmental Protection Agency |
| In House Personnel: | School District of Philadelphia asbestos workers |
| LEA: | Local Education Agency |
| O&M: | Operations and Maintenance |
| OEMS: | Office of Environmental Management and Services |
| OSHA: | Occupational Safety and Health Administration |
| PEL: | Permissible Exposure Limit |
| PSD or SDP: | Philadelphia School District/School District of Philadelphia |
| PSIT: | Philadelphia School Improvement Team |
| STEL: | Short Term Exposure Limit |

1. Introduction

The School District of Philadelphia, Asbestos Policy Statement:

“The School District of Philadelphia is dedicated to providing a safe and healthful work environment for its employees, students, faculty, contractors and visitors. In recognition of the potential health problems associated with asbestos, the School District of Philadelphia is committed to a comprehensive asbestos control program. This program is implemented and maintained through the School District of Philadelphia's Office of Environmental Management and Services (OEMS).”

OEMS has the responsibility of establishing procedures for asbestos abatement, asbestos inspection, air monitoring, renovation and demolition activities within all School District of Philadelphia owned or leased facilities.

These procedures are developed to ensure that:

- (1) People are not exposed to significant levels of asbestos fibers
- (2) Asbestos waste is handled and disposed of properly
- (3) Members of the School District of Philadelphia community have access to the Office of Environmental Management and Services for information, assistance, guidance, and interpretation regarding asbestos related matters.
- (4) Members of the School District of Philadelphia community have access to the Asbestos Management Plans as required and outlined in the US EPA AHERA regulations including annual written notification to all parents.
- (5) Compliance with all applicable Federal, State and Local Asbestos Regulations

Requirements outlined in this manual are mandatory in nature where the word “SHALL” is used and are advisory in nature where the word “SHOULD” is used.

2. Summary of Asbestos Management Program

The School District of Philadelphia’s Asbestos Management Program was established to meet the requirements of Federal, State, and Local Regulations.

These regulations include, but are not limited to:

- US Environmental Protection Agency Asbestos Hazard Emergency Response Act (US EPA AHERA) and National Emissions Standard for Hazardous Air Pollutants subpart M, Part 61 (NESHAP);
- US Department of Labor, Occupational Safety and Health Administration (OSHA) General Industry Standard (29 CFR 1910.1001) and the OSHA Asbestos Standard for the Construction Industry (29 CFR 1926.1101);
- The Commonwealth of Pennsylvania, Department of Labor and Industry, Asbestos Occupations, Accreditation and Certification Act;
- The City of Philadelphia, Department of Public Health, Asbestos Control Regulations.

3. Asbestos Management Program Execution

a) General Execution

The Office of Environmental Management and Services (OEMS) develops, implements and manages safety and health programs for the School District of Philadelphia faculty, staff and students and assists with ensuring that all contractors comply with Federal, State and Local Environmental Regulations. The OEMS provides the oversight of School District of Philadelphia employees (Asbestos A-Team), environmental consultants, and asbestos abatement contractors for all projects within the School District of Philadelphia concerning Asbestos Containing Materials.

The control of safety and health hazards at the School District of Philadelphia is primarily through the implementation of engineering, work practice and administrative controls. Personal Protective Equipment (PPE) is used to supplement these controls or whenever the controls are not feasible or are in the process of being implemented. PPE is also recommended whenever exposures to chemical, physical or biological agents can be prevented or reduced by its use.

This written program establishes the procedures necessary to:

- 1) meet established standards and federal regulations for occupational exposure to asbestos fibers;
- 2) meet the requirements of the City of Philadelphia Asbestos Control Regulations which encompasses the disturbance and/or abatement of asbestos containing building materials;
- 3) provide the necessary health and safety protection to the School District of Philadelphia staff, faculty, students, contractors and visitors.

This program is strengthened by input and cooperation with the Philadelphia Federation of Teachers (PFT), Health and Welfare Fund.

4. Summary of Program Execution

a) Asbestos Management Program Execution

The Asbestos Management Program is administered by the Office of Environmental Management and Services (OEMS). OEMS provides the following services primarily through professional consultants:

- (1) exposure monitoring services;
- (2) building inspection/surveys (bulk sampling) for the identification of asbestos containing materials;
- (3) asbestos project design services;
- (4) asbestos abatement project and air monitoring services;
- (5) emergency response to fiber release episodes;
- (6) education/information;
- (7) medical monitoring;
- (8) training for School District of Philadelphia personnel

5. Responsibilities

a) Office of Environmental Management and Services

OEMS is responsible for performing the following functions:

- (1) Developing and administering of the Asbestos Management Program.
- (2) Providing asbestos-related services to all School District of Philadelphia departments.
- (3) Conducting required training of the Asbestos Management Program and working jointly with departments to schedule training.
- (4) Identifying and posting areas where labeling/signage are required.
- (5) Medical Monitoring of OEMS "A-TEAM" and other departments "AST" Asbestos Program staff.

- (6) Certification and training as required for OEMS "A-TEAM" and other departments "AST" Asbestos program staff.
- (7) Record keeping as outlined in Section 3.5 and all records as by required by US EPA AHERA regulations.

b) Asbestos Worker/Supervisor - "A-TEAM"

- (1) OEMS shall ensure that all "A-TEAM" workers/supervisors adhere to the following requirements:
 - a) Attend an initial Worker/Supervisor Asbestos Course;
 - b) Maintain the annual re-certification per EPA AHERA requirements and Commonwealth of Pennsylvania Asbestos Occupations, Accreditation and Certifications Act;
 - c) Undergo an annual Asbestos Medical Evaluation;
 - d) Undergo an annual Respirator Medical Clearance;
 - e) Undergo an annual Respirator Fit Testing.

c) Asbestos Designated Person

The Asbestos Designated Person is responsible for:

- (1) Assuring the health and safety of employees, students and visitors in the School District of Philadelphia facilities under his/her control.
- (2) Being kept informed of all areas under his or her jurisdiction where potential asbestos exposures exist and initiating protection programs that adhere to the Asbestos Management Program requirements of this manual.
- (3) Assuring that Asbestos Management Program requirements are adhered to by principal investigators, project managers, supervisors, or division heads, and School District of Philadelphia personnel under their supervision.
- (4) Ensuring that all employees within the Asbestos Management Program comply with (OSHA 1910.1001 (j) (7) (iv)) and the US EPA AHERA regulations by attending the required training.
- (5) Ensure the posting of:
 - a) Warning labels/signage
 - b) Commonwealth of Pennsylvania Asbestos Abatement and Demolition/Renovation Notification form
 - c) Asbestos Inspection Reports (AIR) form (where required)
 - d) Ensuring that Construction Projects follow the Demolition Directive procedures as outlined in the August 4, 2006 letter.

d) Supervisor or Project Manager (Capital, Maintenance and Facilities)

Each person in charge of a project, maintenance/repair, renovation/demolition, or other activity from the Departments of Capital, Maintenance, and/or Facilities, where asbestos containing material may be present is responsible for:

Identifying, with the assistance of OEMS, asbestos containing building materials prior to any disturbance of these materials. Various Federal (EPA and OSHA) and Local (City of Philadelphia Asbestos Control Regulations) require Asbestos Inspections prior to renovation/demolition activities. This shall be accomplished by always following the Asbestos Management Program Procedures as follows:

- (1) Ensure that the requirements of the Asbestos Management Program Procedures are followed by all personnel, trades, and contractors who are involved with the project;

- (2) Review of the required Asbestos Inspection Report (AIR) form (Attachment 1) and AHERA Management Plan documents prior to activities that may disturb any Asbestos Containing Materials;
- (3) Perform all project related duties as outlined in the Project Management Responsibilities;
- (4) Keep the department chairperson or director informed on any actions proposed or taken regarding the Asbestos Management Plan;
- (5) Ensuring that Construction Projects follow the Demolition Directive procedure outlined in the August 4, 2006 letter.

e) Employee – Capital

School District of Philadelphia Capital employees and/or consultants shall:

- (1) Ensure that no suspect or asbestos containing building materials are disturbed in the course of the projects they are performing or managing. This shall be accomplished by notifying their supervisor and OEMS by issuance of a work order permit (a.k.a PSIT Service Request Form) and verifying that the materials which may be disturbed are non-asbestos containing. If this information is not available or verification has not been made, these materials should not be disturbed.
- (2) Immediately notify OEMS and their supervisor in the event of a potential fiber release episode upon discovery of visible damage to asbestos containing materials.
- (3) Ensuring that Construction Projects follow the Demolition Directive procedures as outlined in the August 4, 2006 letter.

The types of projects represented as part of the Capital Improvement Program are as follows:

- (1) Complete Renovation of an existing building that addresses all facility component concerns and educational program needs;
- (2) Major Renovation of an existing building addressing significant facility component and educational improvements;
- (3) Addition to an existing building (either as an attachment or stand-alone structure) to accommodate needed program space;
- (4) Conversion of an existing facility to accommodate a change in educational program;
- (5) Facility Component Improvement of specific facility needs (i.e. electrical or HVAC system upgrades, ADA improvements, life safety improvements, exterior renovations, etc.)

f) Employee – Maintenance

School District of Philadelphia Maintenance employees shall:

- (1) Ensure that no suspect or asbestos containing building materials are disturbed in the course of their duties or work they are performing. This shall be accomplished by notifying their supervisor and OEMS by issuance of a work order permit and verifying that the materials which may be disturbed are non-asbestos containing. If this information is not available or verification has not been made, these materials should not be disturbed.
- (2) Immediately notify OEMS and their supervisor in the event of a potential fiber release episode or upon discovery of visible damage to asbestos containing materials.
- (3) All employees involved in maintenance activities shall attend required Asbestos Awareness training program within 60 days of employment.

g) Employee – Facilities & Custodial

School District of Philadelphia Facilities and Custodial employees shall:

- (1) Ensure that no suspect or asbestos containing building materials are disturbed in the course of their duties or work they are performing. This shall be accomplished by notifying their supervisor and OEMS by issuance of a work permit and verifying that the materials which may be disturbed are non-asbestos containing. If this information is not available or verification has not been made, these materials should not be disturbed;
- (2) Immediately notify OEMS and their supervisor in the event of a potential fiber release episode or upon discovery of visible damage to asbestos containing materials.
- (3) All employees involved in Facilities and Custodial activities shall attend require Asbestos Awareness training program within 60 days of employment.

6. Requirements

a) Employee Exposure Monitoring

When information indicates that an employee's exposure to asbestos fibers may equal or exceed an 8-hour time-weighted average of 0.1 f/cc * (per OSHA 1910.1001 & 1926.1101), OEMS shall develop and implement an asbestos exposure monitoring program. The sampling strategy shall be designed to identify employees by work task (job classification) that is exposed to asbestos fibers that exceed an 8-hour time-weighted average of 0.1 f/cc.

b) Employee Notification

OEMS shall notify in writing, each employee exposed to asbestos fibers at or above an 8-hour time weighted average of 0.1 f/cc.

c) Observation and Monitoring

OEMS shall provide employees or their representatives with an opportunity to observe any exposure measurements conducted.

d) Training Program

OEMS shall institute a training program which meets the requirements of AHERA for all employees who perform maintenance operations in a facility/school which contains asbestos containing materials or presumed asbestos containing materials and 1910.1001 (j), and the Commonwealth of Pennsylvania Department of Labor and Industry and the City of Philadelphia Asbestos Control Regulations. The affected departments shall ensure employee participation in this program. The OEMS "A-TEAM" and other departments "AST" Asbestos Program staff training shall be conducted annually for each employee as required by all Federal, State and Local for each asbestos discipline.

All Asbestos Awareness training as required by AHERA shall be performed within 60 days of employment and shall include:

- Health effects of asbestos
- Locations of ACM and PACM in the building/facility
- Recognition of CM and PACM damage and deterioration
- Requirements of the OSHA 1910.1001 standard relating to maintenance
- Proper response to fiber release episodes
- Procedure to be followed to isolate areas affected by fiber release

e) Access to Information

OEMS shall make available to affected employees or their representative's copies of the Occupational Safety and Health Administration (OSHA) General Industry Standard Part 1910.1001 and the department shall post a copy in the workplace.

f) Record Keeping

OEMS shall maintain an accurate record of all employee exposure measurements. OEMS and/or the School District of Philadelphia Human Resources Department shall maintain records of employee medical monitoring program. OEMS shall maintain all employee training records. All records shall be provided upon request to employees, former employees, representatives designated by the individual employee.

7. AHERA OPERATIONS AND MAINTENANCE PLAN

a) CONTROLS

i. Work Order System

Minimizing disruption of ACM/PACM during maintenance and renovation activities is the primary goal and task encountered by OEMS. Operations and maintenance employees and contractors should be warned to avoid conducting any maintenance work which may disturb ACM/PACM. Initiating a work order system, where all work orders or requests are channeled through the Office of Environmental Management and Services (OEMS), will be the method used to control and minimize disruption of ACM/PACM.

Any work performed by in-house personnel or contractors that could or will impact ACM/PACM shall be coordinated by OEMS. A completed Asbestos Inspection Report Form (Attachment 1) shall be issued to in-house personnel and/or all contractors whose work could impact ACM/PACM. This form should accompany each contract issued to an outside contractor and posted on the jobsite.

All work order requests for maintenance and renovation activities in areas where ACM/PACM is suspected or known to be present are to be submitted to OEMS prior to proceeding with work. OEMS is responsible for reviewing asbestos survey records for information about the presence of ACM/PACM in the area where the work is to be performed. OEMS should physically inspect the area to ensure existing records reflect actual conditions. If no asbestos is present, a work order is not necessary and the planned actions can proceed. If ACM/PACM is found to be present in the area, OEMS will sign the work order application and obtain an approved and accredited asbestos contractor or assign OEMS "A-TEAM" to abate the ACM/PACM.

ii. Regulated Areas

The owner will identify and regulate all areas where airborne concentrations of ACM/PACM exceed the Permissible Exposure Limit (PEL)* (Per OSHA determined to be 0.1 f/cc) and/or short term exposure limit (STEL) (Per OSHA determined to be 0.1 f/cc), or there is reasonable possibility that the (PEL) and/or (STEL) may be exceeded. All ACM/PACM removal activities involving thermal system insulation ACM/PACM (Class I), surfacing ACM/PACM (Class I), and miscellaneous ACM/PACM such as floor tile, roofing, and siding mastic, etc. (Class II), and repair and maintenance operations where thermal system insulation and surfacing ACM/PACM is likely to be disturbed (Class III) will be performed in accordance with federal, state, and local regulations. All asbestos abatement work and activities will be designed and managed as asbestos regulated areas. These areas will be demarcated and labeled.

iii. Warning Signs

Warning signs shall be displayed at all approaches to each asbestos regulated area. The asbestos abatement contractor will provide OSHA warning signs in all regulated areas during removal, repair, and other maintenance activities. OEMS will provide AIRs to all contractors who must inform all employees and supervisors working in locations contiguous to asbestos regulated areas of the potential hazards and work practices required.

iv. Warning Labels

Warning labels and/or signage shall be affixed to all raw materials, mixtures, scrap, waste, debris, and other products containing asbestos fibers, or to their containers. Generally, the asbestos abatement contractor or OEMS A-Team personnel will provide all warning labels for ACM/PACM containment.

8. O & M RESPONSE ACTIONS

The Asbestos Management Program general O&M procedures are outlined in this section. Additional requirements specific to asbestos abatement activities are included in the Project Design documents for all Asbestos Abatement Work. Regular cleaning, inspection, and reporting of ACM/PACM deterioration or other problems must be diligently practiced by all employees including custodial and maintenance personnel.

a) Facility Maintenance Isolation of Area Responsibilities

Maintenance personnel are often required to work in areas where ACM/PACM may potentially be disturbed. Most maintenance activities are conducted by in-house staff, outside contractors, or a combination.

Emergency fiber release episodes, such as pipe fitting or valve breaks, emergency boiler work, or mechanical equipment repair will be responded to by OEMS A-Team personnel or asbestos abatement contractor personnel. The owner's maintenance staff will: (1) isolate the emergency fiber release area; (2) post warning signs to prevent unauthorized access, and (3) notify their supervisor and OEMS. OEMS will ensure that the fiber release area remains isolated and is properly cleaned by and approved and accredited abatement contractor or by OEMS A-TEAM personnel.

b) Unlikely Contact with ACM/PACM

Maintenance activities or repairs which can be performed without contacting or disturbing the ACM/PACM require little more than normal care and good workmanship. For example, valves which are either uncovered or covered with non-asbestos insulation can be packed or repaired without disturbing asbestos insulation on nearby pipes. The major precaution is to ensure that maintenance and custodial personnel are familiar with procedures such as isolating the area, posting warning signs, and notifying OEMS in the event of any accidental ACM/PACM disturbance.

c) Accidental Disturbance of ACM/PACM

Maintenance and facilities personnel shall notify OEMS any time a fiber release is suspected. If friable ACM/PACM becomes airborne in the building,

d) Planned Disturbance of ACM/PACM

Maintenance activities that may impact ACM/PACM include access to a valve, flange, duct, or related system component.

Where asbestos-containing insulation must be removed to maintain or repair the thermal system, the ACM/PACM will imminently be disturbed. ACM/PACM removal work shall be conducted by OEMS A-Team personnel or an approved and accredited asbestos abatement contractor.

If friable ACM/PACM becomes airborne in the building, maintenance and facilities personnel shall secure the area and contact OEMS. OEMS shall respond accordingly.

e) Miscellaneous ACM/PACM

Miscellaneous types of ACM/PACM may include vinyl asbestos floor tiles, mastics/adhesives and woven vibration dampers. Disturbance of these materials should be avoided. Routine maintenance activities involving these materials should not pose a problem if handled properly. Questions on the proper removal and disposal of miscellaneous ACM/PACM should be directed to OEMS. OEMS will contact an approved and accredited asbestos abatement contractor or utilize OEMS A-TEAM personnel to assist with miscellaneous ACM/PACM clean-up activities.

f) Vinyl Asbestos Floor Tile

Asbestos-containing floor tiles in good condition are considered non-friable unless they are crushed, drilled, sawed, sanded or disturbed by any activity that breaks up the material. Routine maintenance of these materials should employ the use of non-abrasive buffers and wet cleaning technique. Broken or loose floor tiles should be removed and disposed of as asbestos waste by OEMS. Remaining debris should be vacuumed with a HEPA vacuum and the area wet mopped using amended water.

g) Mastics/Adhesives

Mastics and adhesives containing asbestos in good condition are considered non-friable and do not pose a potential health concern unless crushed, drilled, sawed, sanded, or otherwise abraded. Questions on the proper removal should be directed to OEMS.

h) Woven Vibration Dampers

Woven vibration dampers in good condition are considered non-friable and do not pose a potential health concern unless cut, crushed, drilled, sawed, sanded, or otherwise abraded. Questions on the proper removal should be directed to OEMS.

i) Other Work Practices

Any special work not included in this section should be addressed to OEMS for review prior to the initiation of work that may involve the disturbance of ACM/PACM.

j) Fiber Release Episodes

Facilities and maintenance staff should report to OEMS the presence of asbestos debris, water or physical damage to ACM/PACM, or any other evidence of possible fiber release. OEMS should have the OEMS A-Team personnel or an approved and accredited abatement contractor respond to the site to clean up debris and make repairs as soon as possible. OEMS will also contact a consultant to conduct air monitoring and prepare a report and submit at project completion to OEMS for each episode. OEMS will forward the reports for each site location AHERA Management Plan accordingly.

9. REFERENCES and RESOURCES

Applicable regulations for asbestos projects impacted by renovation, demolition, and maintenance activities.

- **Philadelphia Air Management Services – Asbestos Control Unit**
<http://www.phila.gov/health/units/ams/Asbestos/asbestos.html>
- **Pennsylvania Asbestos Occupations, Accreditation and Certification Act**
<http://www.dli.state.pa.us/landi/cwp/view.asp?a=185&q=56262&landiNav=>
- **United States Environmental Protection Agency Asbestos Home Page**
<http://www.epa.gov/asbestos/>
- **Occupational Safety and Health Administration (OSHA) Asbestos Home**
<http://www.osha.gov/SLTC/asbestos>