

# SCHOOL DISTRICT OF PHILADELPHIA



## Asbestos Hazard Emergency Response Act “AHERA”

### THREE-YEAR RE-INSPECTION 2015-2016 and ASBESTOS MANAGEMENT PLAN for the

**Laura H. Carnell Elementary School**

**ULCS# 7220  
Building # B722001-1  
1100 Devereaux Avenue  
Philadelphia, Pennsylvania  
19111**

**Year Built: 1931**

October 2015

*Conducted by:*

Accredited Environmental Technologies, Incorporated  
Batta Environmental Associates, Incorporated  
Criterion Laboratories, Incorporated  
Environmental Testing Consultants, LLC  
G & C Environmental Services, Incorporated  
KEM Partners, Incorporated  
Synertech, Inc.  
TTI Environmental, Inc.  
USA Environmental Management, Inc.  
The Vertex Companies, Inc.

*Management Plan Prepared by:*  
Criterion Labs, Inc and Synertech Inc.

*This report must remain in the Main Office as mandated by the US EPA AHERA Regulations.*

# **AHERA THREE-YEAR REINSPECTION VOLUME IX**

## **Table of Contents**

### **Transmittal Letter**

### **Executive Summary**

- I. Summary list of Confirmed Asbestos Containing Building Materials
- II. Summary list of Assumed Asbestos Contain Building Materials
- III. Summary list of Non-Asbestos Containing Building Materials
- IV. Summary list of Non Suspect Asbestos Containing Building Materials
- V. Summary List of Auditorium DATA for this location
- VI. Summary list of Attic and/or Crawlspace DATA for this location
- VII. Summary list of Pipe Chase/Pipe Shaft DATA for this location

### **Section I Report of Re-Inspection**

- A. Introduction
- B. Three-Year Re-inspection IX Overview
- C. Post- Management Plan Activities and Changes
  - C.1 - Sampling and Analysis
  - C.2 - New Floor Tile Sampling
  - C.3 - Abatement Activity
  - C.4 - Periodic (Six-Month) Surveillance (Damaged Materials)

### **Section II Re-Inspection Data**

- A. Introduction
- B. Re-Inspection Key Definitions
- C. Room by Room Location Log Report

### **Section III Certificates**

- A. Management Planner/Building Inspector Certificates

|                   |                              |           |
|-------------------|------------------------------|-----------|
| <b>Section IV</b> | <b>Cross Reference Table</b> | Page 1-8  |
|                   | Asbestos Management Program  | Page 9-19 |

SCHOOL DISTRICT OF PHILADELPHIA  
EDUCATIONAL CENTER  
440 NORTH BROAD STREET  
PHILADELPHIA, PENNSYLVANIA 19130

OFFICE OF ENVIRONMENTAL MANAGEMENT AND SERVICES

PHONE (215)-400-4750

January 2016

TO: All Principals  
All Building Administrators

FROM: Fran Burns  
Chief Operating Officer

Francine Locke, M.S., Director  
Office of Environmental Management and Services

SUBJECT: AHERA Three (3) Year Re-inspection IX report

In order to comply with the provisions of the Asbestos Hazard Emergency Response Act (AHERA) the attached report is submitted to you. The law requires that this report be kept in the Main/Principal's office. It cannot be removed from these locations. *If the school (program) is relocated to a different building, these environmental documents are to be safely retained for the next school/building occupants.* All asbestos reports must be available to the public and Federal EPA upon request.

  
\_\_\_\_\_  
Fran Burns  
Chief Operation Officer  
\_\_\_\_\_  
Francine Locke, M.S., Director  
Office of Environmental Management  
and Services

## **Executive Summary**

This Asbestos Hazard Emergency Response Act (AHERA) Three-Year Re-inspection “Volume # IX” Management Plan at this location, has been completed and the report of re-inspection submitted to the School District of Philadelphia. The re-inspections in all School District of Philadelphia buildings of 2015-2016 were conducted and completed between October 5<sup>th</sup>, 2015 through March 30<sup>th</sup>, 2016 as a joint project by Accredited Environmental Technologies, Inc., Batta Environmental Associates, Inc., Criterion Laboratories, Inc., Environmental Testing Consultants, LLC, G & C Environmental Services, Inc., KEM Partners, Inc., Synertech, Inc., TTI Environmental, Inc., USA Environmental Management, Inc. and The Vertex Companies, Inc.

In general, the School District of Philadelphia Office of Environmental Management and Services conducts Environmental Impact Evaluations and provides Asbestos Inspection Reports prior to any renovation, demolition and/or maintenance activities. The AHERA report must be reviewed prior to any renovation, demolition and/or maintenance activities in order to avoid the unknowing disturbance to Asbestos Containing Building Materials identified within this location. In addition, prior to work activities above all drop ceilings this report should be reviewed to avoid potential disturbances to Asbestos Containing Materials. Refer to Section IV of the Cross Reference Table, for additional Asbestos Management Program information. Contact the Office of Environmental Management and Services to have an Environmental Impact Evaluation conducted prior to any renovation, demolition and/or maintenance activities within this facility.

The information contained in this report was obtained from the original Asbestos Management Plan for the school, from update reports on changes and activities since the completion of the 1<sup>st</sup> Management Plan for each location and from all prior inspections performed and documented in Volume # I through Volume VIII (dated respectively 1992, 1995, 1998, 2001, 2004, 2007, 2010 or 2013) (if applicable) - and by this Three-Year Re-inspection of this school. The re-inspection report/Management Plan of 2015-2016 were reviewed and prepared collectively by Management Planner Megan Vala, Mary Anne Lerro of Criterion Laboratories, Inc. and/or Monique Causley, of Synertech Inc.

The 2015-2016 inspection process included the addition of a comprehensive Room by Room Inventory of all Thermal (T), Surfacing (S) and Miscellaneous (M) Materials specific to each room of this facility. Inspections of each room's thermal, ceilings, walls, floors and miscellaneous items regardless of Asbestos Content are categorized on the Room by Room Location Log Report for this location. Rooms or areas of the facility that were not accessible at the time of the inspection are marked with an "X". The Room by Room Location Log Report is found in Section II C of this Management Plan.

All Presumed or Suspect Asbestos Containing Building Materials (ACBMs), listed in the following summary charts are categorized as Confirmed, Assumed, Non-Asbestos, and/or Non-Suspect (ACBMs) were identified in the original Management Plan, or in the Volume I through Volume VIII AHERA Three-Year Re-inspection reports, and were re-inspected as part of this project.

As mandated by the U S EPA AHERA regulations, periodic Six-Month inspections and Three-Year Re-inspections of this location will be performed and the Inspection Data in this report will be updated accordingly.

Please feel free to contact the School District of Philadelphia's Office of Environmental Management and Services (OEMS) regarding any comments, questions, or concerns regarding this report or any Environmental related topic. OEMS staff can be reached at (215) 400 4750, via fax at (215) 400 4751 or via e-mail at [flocke@philasd.org](mailto:flocke@philasd.org) and/or [gfunod@philasd.org](mailto:gfunod@philasd.org).

Additional information can be found on our website. Here is the link to the OEMS website.  
<http://webgui.phila.k12.pa.us/offices/e/environmental>

## **I. Summary list of Confirmed Asbestos Containing Building Materials within this facility**

These charts are to be used for a quick reference\* in order to avoid the unknowing disturbance of Asbestos Containing Materials during any and all Operations, Maintenance, Renovation, and/or Demolition activities at this location. *These materials have been sampled and Laboratory Analysis has CONFIRMED the presence of Asbestos. Contact OEMS prior to the disturbance of any of the following materials.*

### **Confirmed Asbestos Containing Building Materials for this location**

|                          |                          |                         |
|--------------------------|--------------------------|-------------------------|
| Duct Insulation          | Floor Tile VAT 9" x 9"   | Pipe Fitting Insulation |
| Pipe Insulation > 6 inch | Pipe Insulation 2-6 inch |                         |

*\* Always refer to the Room by Room Logs for each specific material classification as the material classification findings may be different in various rooms throughout this facility.*

*\*\* Some Materials may have multiple classifications (Confirmed, Assumed, NAD and Non Suspect) within this facility.*

## II. Summary list of Assumed Asbestos Containing Building Materials within this facility

These charts are to be used for a quick reference\* in order to avoid the unknowing disturbance of Asbestos Containing Materials during any and all Operations, Maintenance, Renovation, and/or Demolition activities at this location. These materials have not been sampled and should not be disturbed until verification of Asbestos Content. Contact OEMS for assessment and sampling prior to the disturbance of these materials.

### Assumed Asbestos Containing Building Materials for this location

|                      |                    |                          |
|----------------------|--------------------|--------------------------|
| Blackboard Glue Dots | Decorative Plaster | Floor Tile VAT 12" x 12" |
| Plaster Ceiling      | Stage Curtain      | Transite Closet          |

*\* Always refer to the Room by Room Logs for each specific material classification as the material classification findings may be different in various rooms throughout this facility.*

*\*\* Some Materials may have multiple classifications (Confirmed, Assumed, NAD and Non Suspect) within this facility.*

### III. Summary list of Non-Asbestos Containing Building Materials within this facility

These charts are to be used for a quick reference\* in order to avoid the unknowing disturbance of Asbestos Containing Materials during any and all Operations, Maintenance, Renovation, and/or Demolition activities at this location. *These materials have been sampled and Laboratory Analysis has indicated NO Asbestos present or NO ASBESTOS DETECTED (NAD).*

#### Non- Asbestos Containing Building Materials for this location

|                                   |                         |                 |
|-----------------------------------|-------------------------|-----------------|
| Ceiling Tile 1' x 1'              | Pipe Fitting Insulation | Plaster Ceiling |
| Plaster Walls                     | Radiator Insulation     | Sheetrock Wall  |
| Tar Paper a/w Radiator Insualtion |                         |                 |

\* *Always refer to the Room by Room Logs for each specific material classification as the material classification findings may be different in various rooms throughout this facility.*

\*\* *Some Materials may have multiple classifications (Confirmed, Assumed, NAD and Non Suspect) within this facility.*



#### **IV. Summary list of Non-Suspect Asbestos Containing Building Materials within this facility**

These charts are to be used for a quick reference\* in order to avoid the unknowing disturbance of Asbestos Containing Materials during any and all Operations, Maintenance, Renovation, and/or Demolition activities at this location. These materials are not typically known to contain Asbestos.

##### **Non-Suspect Asbestos Containing Building Materials for this location**

|                    |                                 |                            |
|--------------------|---------------------------------|----------------------------|
| Brick Wall         | Cement Floor                    | Ceramic Tile Floors        |
| Ceramic Tile Walls | CMU                             | Concrete Block Wall        |
| Concrete Ceiling   | Fiberglass Ceiling Tile 2' x 4' | Fiberglass Pipe Insulation |
| Marble Walls       | Wood Floor                      |                            |

*\* Always refer to the Room by Room Logs for each specific material classification as the material classification findings may be different in various rooms throughout this facility.*

*\*\* Some Materials may have multiple classifications (Confirmed, Assumed, NAD and Non Suspect) within this facility.*

## V. Summary list of Auditorium DATA for this location

These charts are to be used for a quick reference of the Auditorium DATA within this facility. Sampling of the Auditorium Ceilings throughout the District is more difficult because of the various ceiling heights. As sampling occurs this information is updated on a case by case basis for each specific location and facility.

### This is a list of known materials for this location's Auditorium

| Auditorium       |                    |                 |
|------------------|--------------------|-----------------|
| Auditorium       | Decorative Plaster | Assumed         |
| Auditorium       | Plaster Ceiling    | Assumed         |
| Auditorium       | Plaster Walls      | NAD             |
| Auditorium       | Wood Floor         | Non Suspect ACM |
| Auditorium Stage | Plaster Ceiling    | Assumed         |
| Auditorium Stage | Plaster Walls      | NAD             |
| Auditorium Stage | Stage Curtain      | Assumed         |
| Auditorium Stage | Wood Floor         | Non Suspect ACM |

*\* Always refer to the Room by Room Logs for each specific material classification as the material classification findings may be different in various rooms throughout this facility.*

*\*\* Some Materials may have multiple classifications (Confirmed, Assumed, NAD and Non Suspect) within this facility.*

## VI. Summary list of Attic and/or Crawlspace DATA for this location

These charts are to be used for a quick reference regarding the Attics and/or Crawlspaces inspection DATA within this facility. Contact OEMS prior to entering any attic or crawlspace within this facility and refer to the below chart and legend for Category Rank determination. The Data relative to these spaces is updated as conditions change regarding Abatement or Renovation activity on a case by case basis for each specific location and facility. In general, Crawlspaces are below the basement or 1<sup>st</sup> floor and Attics are above the floor space.

### *Category Rank Legend*

|   |
|---|
| "A" - No Asbestos Containing Materials - Sample Results indicate NO ACM on pipes, fittings, elbows, or equipment located within this functional space, and NO VISIBLE DEBRIS or DAMAGE observed at time of this inspection.                     |
| "B" - Asbestos Containing Materials Exist - Sample Results indicate ACM on pipes, fittings, elbows, or equipment located within this functional space, HOWEVER, NO VISIBLE DEBRIS or DAMAGE observed at time of this inspection.                |
| "C" - Asbestos Containing Materials Exist - Sample Results indicate ACM on pipes, fittings, elbows, or equipment located within this functional space, and LOCALIZED VISIBLE DEBRIS or DAMAGE observed at time of this inspection.              |
| "D" - Asbestos Containing Materials Exist - Sample Results indicate ACM on pipes, fittings, elbows, or equipment located within this functional space and DISTRIBUTED VISIBLE DEBRIS or SIGNIFICANT DAMAGE observed at time of this inspection. |
| "E" - No Bulk Sample Results Available SUSPECT ACM OBSERVED. Contact OEMS immediately for additional instructions.  |

| Attic/Crawlspace | Access Area         | Floor Surface | Category Rank | Comments                       |
|------------------|---------------------|---------------|---------------|--------------------------------|
| Attic            | 3rd Floor Stairwell | Wire Lathe    | "C"           | 1750 LF Air Cell, Exposed Ends |
| Crawl Space      | X                   | X             | X             | No Crawl Space                 |

## VII. Summary list of Pipe Chase/Pipe Shaft DATA for this location

These charts are to be used for a quick reference regarding the information known about the Pipe Chases and/or Pipe Shafts inspection DATA within this facility. Contact OEMS prior to performing renovation activities any Pipe Chase and/or Pipe Shaft within this facility and refer to the below chart and legend for Asbestos Content of various materials identified within each space. The Data relative to these spaces is updated as conditions change regarding Inspection, Abatement and/or Renovation activity on a case by case basis for each specific location and facility. In general, Pipe Chases are horizontal spaces and Pipe Shafts are vertical spaces.

| <i>Element</i> | <i>Floor</i> | <i>On Site Room Name</i>                  | <i>Material</i>           | <i>Confirmed /Assumed<br/>NAD/Non Suspect</i> | <i>Amount<br/>of<br/>Material</i> | <i>Amount<br/>of<br/>Damage</i> |
|----------------|--------------|---|---------------------------|---|-----------------------------------|---------------------------------|
| 1              | 2            | Teacher's Lounge Pipe Chase               | Pipe Insulation >6 inches | Confirmed                                     | 50 LF                             | 4 LF                            |
| 1              | B            | Boy's Restroom Pipe Chase – No Access     | X                         | X   | X                                 | X                               |
| 1              | 3            | Student Lunch Room Pipe Chase – No Access | X                         | X   | X                                 | X                               |

## **Section I**

### **Report of Re-Inspection**

#### **A. Introduction**

#### **B. Three-Year Re-Inspection IX Overview**

#### **C. Post-Management Plan Activities and Changes**

##### **C.1 Sampling and Analysis**

##### **C.2 New Floor Tile Sampling**

##### **C.3 Abatement Activity**

##### **C.4 Periodic Six-Month Surveillance (Damaged Materials)**

## **Section I - A**

### **Report of Re-inspection**

#### **Introduction**

The Three-Year Re-inspection IX was performed to fulfill the requirements of 40 CFR Part 763 - the Asbestos Hazard Emergency Response Act (AHERA). As required by AHERA, each Local Education Agency (LEA) must re-inspect all known confirmed or assumed Asbestos Containing Building Material (ACBM) located in the LEA's facilities. This re-inspection is intended to update the original Asbestos Management Plan for the LEA's facilities.

Multiple Building Inspectors of several firms performed the 2015/2016 re-inspection. The re-inspection report/Management Plan of 2015-2016 were reviewed and prepared collectively by Management Planner Megan Vala, Mary Anne Lerro of Criterion Laboratories, Inc. and Monique Causley, of Synertech Inc.

All of the certificates can be found in Section III.

During the re-inspection of each School District of Philadelphia facility, all of the Management Plans for that facility were reviewed. Information from the conclusions section of that report is included in this report. Additionally, information on activities such as abatements, cleanings, sampling and inspections, which have taken place since the completion of the original Management Plan, were reviewed during the re-inspection. Information on those activities is included in this report.

As mandated by the U S EPA AHERA regulations, all future periodic Six-Month inspections and Three-Year Re-inspections of this location will be performed and the Inspection Data in this report will be updated accordingly.

## **Section I - B**

### **Three-Year Re-inspection IX Overview**

Each homogeneous area of Asbestos Containing Building Material (ACBM) listed in the original Management Plan or in the 1992, 1995, 1998, 2001, etc., Three-Year Re-inspection reports were inspected for the AHERA Three-Year Re-inspection Volume IX, and the information for that material verified. Any changes to a homogeneous area listed in the updates to the Management Plans were verified. Any area of suspected ACBM found in the course of the re-inspection, and not listed in the Management Plan or updates, were either assumed to contain asbestos or sampled and analyzed to determine their asbestos content. Any such new areas either assumed to contain asbestos or determined through analysis to contain asbestos were included in the report of the Three-Year Re-inspection. The results of the AHERA Three-Year Re-inspection IX are tabulated in the Room by Room log reports located in *Section II-C* of this report.

As previously noted, all future periodic Six-Month inspections and Three-Year Re-inspections of this location will be performed and the Inspection Data in this report will be updated accordingly.

## Section I – C.1

### **Post Management Plan Activities/Changes**

Information on activities affecting Asbestos Containing Building Materials (ACBMs) at this location is contained in updates to the Management Plan. These updates are kept on file by the School District of Philadelphia and were reviewed for this project. Updates to the Management Plan include the following: *Sampling and Analysis, New Tile Installation, Abatement Activity and Periodic Six-Month Surveillance Data.*

#### **Sampling and Analysis**

| <b>Date</b> | <b>Floor</b> | <b>Room Type</b> | <b>Location</b> | <b>Material</b>                               | <b>Color</b> | <b>Results</b> |
|-------------|--------------|------------------|-----------------|---|--------------|----------------|
| 11/12/2015  | Basement     | Classroom        | Classroom 005   | Radiator Insulation                           | Gray         | NAD            |
| 11/12/2015  | Basement     | Classroom        | Classroom 006   | Radiator Insulation                           | Gray         | NAD            |
| 11/12/2015  | Basement     | Classroom        | Classroom 007   | Radiator Insulation                           | Gray         | NAD            |
| 11/12/2015  | 1st          | Classroom        | Classroom 111   | Radiator Insulation                           | Gray         | NAD            |
| 11/12/2015  | 1st          | Classroom        | Classroom 112   | Radiator Insulation                           | Gray         | NAD            |
| 11/12/2015  | 1st          | Classroom        | Classroom 113   | Radiator Insulation                           | Gray         | NAD            |
| 11/12/2015  | 3rd          | Classroom        | Classroom 312   | Radiator Insulation                           | Gray         | NAD            |
| 11/12/2015  | 3rd          | Classroom        | Classroom 313   | Radiator Insulation                           | Gray         | NAD            |
| 11/12/2015  | 3rd          | Classroom        | Classroom 313   | Tar Paper Associated With Radiator Insulation | Gray         | NAD            |
| 11/12/2015  | 3rd          | Classroom        | Classroom 314   | Radiator Insulation                           | Gray         | NAD            |
| 11/12/2015  | 3rd          | Classroom        | Classroom 314   | Tar Paper Associated With Radiator Insulation | Gray         | NAD            |



## **Section I – C.2**

Information on the installation of new floor tiles/renovation activities affecting Asbestos Containing Building Materials (ACBMs) at this location is contained in updates to the Management Plan. These updates are kept on file by the School District of Philadelphia and were reviewed for this project. Updates to the Management Plan include the following:

### **New Floor Tile Sampling**

*In the event that new tile is installed, the material must be tested prior to installation.*

## Section I – C.3

Information on the Asbestos Abatement and renovation activities affecting Asbestos Containing Building Materials (ACBMs) at this location is contained in updates to the Management Plan. These updates are kept on file by the School District of Philadelphia and were reviewed for this project. Updates to the Management Plan include the following:

### **Abatement Activity**

| <i><b>Date</b></i> | <i><b>Floor</b></i> | <i><b>Location</b></i>                            | <i><b>Material</b></i>          | <i><b>Color</b></i> | <i><b>Removed or Encapsulated</b></i> | <i><b>Quantity</b></i> |
|--------------------|---------------------|---|---------------------------------|---------------------|---------------------------------------|------------------------|
| 11/17/2015         | Basement            | Boiler Room - Lounge Area by Ramp in Back         | Pipe Insulation >6 inches       |                     | Encapsulated                          | 4 LF                   |
| 11/17/2015         | 1st                 | Storage Room - Last Room Back Right of Auditorium | Pipe Insulation >6 inches       |                     | Encapsulated                          | 8 LF                   |
| 11/18/2015         | Basement            | Boiler Room - Behind 1st Boiler                   | Pipe Insulation >6 inches       |                     | Encapsulated                          | 10 LF                  |
| 11/18/2015         | Basement            | Boiler Room - First right storage area            | Pipe Insulation >6 inches       |                     | Encapsulated                          | 2 LF                   |
| 11/19/2015         | Basement            | Boiler Room - First right storage area            | Pipe Insulation >6 inches       |                     | Encapsulated                          | 15 LF                  |
| 11/19/2015         | 2nd                 | Teacher's Lounge 217B                             | Pipe Insulation >6 inches       |                     | Encapsulated                          | 6 LF                   |
| 11/20/2015         | Ground              | Hallway outside Girl's Restroom                   | Pipe Insulation >6 inches       |                     | Encapsulated                          | 3 LF                   |
| 11/23/2015         | Basement            | Hallway near Boiler Room Door at Gym              | Pipe Insulation 2-6 inch        |                     | Encapsulated                          | 1 LF                   |
| 4/1/2016           | 1st                 | Principal's Office                                | Pipe Insulation 2-6 inch        |                     | Removed                               | 15 LF                  |
| 4/29/2016          | 1st                 | Room 111  | Floor Tile VAT 9" x 9"          | Multi               | Removed                               | 500 SF                 |
| 5/1/2016           | 1st                 | Principal's Office                                | Pipe Insulation 2-6 inch        |                     | Removed                               | 15 LF                  |
| 11/3/2016          | 1st                 | Main Office Copy Room                             | Pipe Insulation 2-6 inch        |                     | Removed                               | 1 LF                   |
| 11/3/2016          | 1st                 | Main Office Copy Room                             | Pipe Insulation 2-6 inch Debris |                     | Removed                               | 1 LF                   |

## Section I – C.4

Information on the AHERA inspection that noted damage to various Building Materials at this location is contained in updates to the Management Plan. These updates are kept on file by the School District of Philadelphia and were reviewed for this project. Work orders are created for Corrective Action responses and tracked for completion. Updates to the Management Plan include the following:

### **Periodic (Six-Month) Surveillance (Damaged Materials)**

| <i>Date</i> | <i>Element</i> | <i>Floor</i> | <i>On Site Room Name</i>    | <i>Material</i>          | <i>Amount of Material</i> | <i>Amount of Damage</i> |
|-------------|----------------|--------------|-----------------------------|--------------------------|---------------------------|-------------------------|
| 11/3/2016   | 1              | 1            | Classroom 105               | Pipe Insulation 2-6 inch | 12 LF                     | 2 LF                    |
| 11/3/2016   | 1              | 1            | Auditorium                  | Plaster Ceiling          | 3360 SF                   | 80 SF                   |
| 11/3/2016   | 1              | 2            | Teacher's Lounge Pipe Chase | Pipe Insulation > 6 inch | 50 LF                     | 4 LF                    |
| 11/3/2016   | 1              | 3            | Classroom 310               | Pipe Insulation 2-6 inch | 6 LF                      | 1 LF                    |
| 11/3/2016   | 1              | 3            | Staff Restroom              | Pipe Insulation 2-6 inch | 12 LF                     | 1 LF                    |
| 11/3/2016   | 1              | B            | Classroom B2                | Floor Tile VAT 12" x 12" | 1020 SF                   | 10 SF                   |
| 11/3/2016   | 1              | B            | Gym                         | Pipe Insulation 2-6 inch | 175 LF                    | 1 LF                    |
| 11/3/2016   | 1              | B            | Student Lunch Room          | Floor Tile VAT 9" x 9"   | 1350 SF                   | 3 SF                    |
| 11/3/2016   | 1              | B            | Student Lunch Room          | Pipe Insulation 2-6 inch | 60 LF                     | 1 LF                    |
| 11/3/2016   | 1              | B            | Boiler Room                 | Duct Insulation          | 600 SF                    | 100 SF                  |
| 11/3/2016   | 1              | B            | Gym Storage                 | Pipe Insulation 2-6 inch | 130 LF                    | 8 LF                    |
| 11/3/2016   | 2              | B            | Classroom 5 Closet          | Pipe Insulation 2-6 inch | 18 LF                     | 1 LF                    |

## **Section II**

### **Re-Inspection Data**

#### **A. Introduction**

#### **B. Re-Inspection Key Definitions**

#### **C. Room by Room Location Log Report**

## **Section II - A**

### **Re-inspection Data**

#### Introduction

The following information documents the Three-Year Re-inspection IX of the subject school/facility. The Homogeneous Area Reports were produced using the building inspector's field data on the facility. The key to the Homogeneous Area Report is outlined in the following pages of this report.

**Section II - B**  
**(page 1 of 4)**

**SCHOOL DISTRICT OF PHILADELPHIA**  
**AHERA THREE YEAR RE-INSPECTION IX**

| <b>ITEM</b>                     | <b>DEFINITION</b>   |
|---------------------------------|---|
| <b>ULCS#</b>                    | Individual identification number assigned to each school within the School District of Philadelphia.  |
| <b>HOMOGENEOUS AREA ID#</b>     | Identification number assigned to each homogeneous area in a school/facility. Each section of the homogeneous area ID is significant.<br><br>1010/01/01/01<br><b>A B C D</b><br><br><b>A.</b> Is the ULCS# for the school.<br><b>B.</b> Designates the specific building/building area within the school.<br><b>C.</b> Designates the floor or level within the building/building area.<br><b>D.</b> Designates the homogeneous material within that floor or level.<br>Note: Item D may be a number or a letter. |
| <b>SYSTEM AFFECTED</b>          | Corresponds to the AHERA system for classifying materials.<br><br><b>T</b> : Thermal System<br><b>S</b> : Surfacing System<br><b>M</b> : Miscellaneous  |
| <b>ITEM AFFECTED</b>            | Is a description of the homogeneous material.   |
| <b>ORIGINAL INSPECTION DATA</b> | This section contains the information found in the original Management Plan (1988-1989).  |
| <b>AMOUNT OF MATERIAL/ UNIT</b> | Quantity of material, and measuring unit.<br>Units include: Square Feet (SF) Each (EA) Linear Feet (LF) Cubic Feet (CF).  |

**SCHOOL DISTRICT OF PHILADELPHIA  
AHERA THREE YEAR RE-INSPECTION IX**

**RE-INSPECTION FORM KEY**

| <b>ITEM</b>                          | <b>DEFINITION</b>   |
|--------------------------------------|---|
| <b>CND<br/>Condition</b>             | Corresponds to AHERA condition rating for materials.<br><br><b>0</b> : No Damage<br><b>1</b> : Damage<br><b>2</b> : Significant Damage  |
| <b>DP<br/>Damage Potential</b>       | Corresponds to the AHERA material assessment system.<br><br><b>1</b> : Potential for Damage<br><b>2</b> : Potential for Significant Damage  |
| <b>ASMD<br/>Assumed<br/>Asbestos</b> | This means that a material was not sampled for asbestos content during the original Management Plan inspection.   |
| <b>RA<br/>Response<br/>Action</b>    | This corresponds to the AHERA system of response action rating for materials.<br><br><b>1</b> : Establish O&M Program<br><b>2</b> : Repair and Establish O&M Program<br><b>3</b> : Enclose<br><b>4</b> : Encapsulate<br><b>5</b> : Remove<br><b>6</b> : Partial Removal and Establish O&M Program   |
| <b>CHANGES</b>                       | This section describes changes to the homogeneous material in the twenty-four years since the original AHERA inspection. The abbreviations are defined below.<br><br><b>RMVD</b> : Removed<br><b>ENCL</b> : Enclosed<br><b>ENCP</b> : Encapsulated<br><b>DMGD</b> : Damaged<br><b>SMPLD</b> : Sampled<br><b>MTRL</b> : Material<br><b>RPRD</b> : Repaired<br><b>N/L</b> : None Located<br><b>RPLCD</b> : Replaced |

**SCHOOL DISTRICT OF PHILADELPHIA  
AHERA THREE-YEAR RE-INSPECTION IX**

**RE-INSPECTION FORM KEY**

| <b>ITEM</b>                         | <b>DEFINITION</b>   |    |                       |    |                                  |    |         |    |             |    |        |    |   |
|-------------------------------------|---|----|-----------------------|----|----------------------------------|----|---------|----|-------------|----|--------|----|---|
| <b>THREE YEAR<br/>RE-INSPECTION</b> | <p>This section contains the information obtained from the Three-Year Re-inspection IX. With three exceptions, the information categories are identical in format and meaning to those found in the original inspection data section. The three exceptions are defined below.</p>   |    |                       |    |                                  |    |         |    |             |    |        |    |   |
| <b>DMGD AMT<br/>Amount Damaged</b>  | <p>This section gives the quantity of damaged material in a homogeneous area. The quantity is shown in the same format as the amount of material/unit section.</p>  |    |                       |    |                                  |    |         |    |             |    |        |    |   |
| <b>NF<br/>Newly Friable</b>         | <p>This section identifies materials in the original Management Plan which have since become friable.</p>   |    |                       |    |                                  |    |         |    |             |    |        |    |   |
| <b>RA<br/>Response Action</b>       | <p>This rating is based on the AHERA regulations, and is comparable to the RA rating found in the "Original Inspection Data" section. The following table details the response actions.</p> <table><tr><td>1.</td><td>Establish O&amp;M Program</td></tr><tr><td>2.</td><td>Repair and Establish O&amp;M Program</td></tr><tr><td>3.</td><td>Enclose</td></tr><tr><td>4.</td><td>Encapsulate</td></tr><tr><td>5.</td><td>Remove</td></tr><tr><td>6.</td><td>Partial Removal and Establish O&amp;M Program</td></tr></table> <p>a.    <b>High Priority Response</b><br/>The homogeneous material has been scheduled for abatement or other response action.</p> <p>b.    <b>Medium Priority Response</b><br/>The homogeneous material will be scheduled for abatement or other response action as soon as the high priority responses have been addressed.</p> <p>c.    <b>Low Priority Response</b><br/>The homogeneous material will be scheduled for abatement or other response action as soon as the medium priority responses have been addressed.</p> <p>d.    <b>On-Going Response/Operations and Maintenance</b><br/>The homogeneous material does not require abatement or other response action at present, and should be included in the facility's on-going operations and maintenance program.</p> | 1. | Establish O&M Program | 2. | Repair and Establish O&M Program | 3. | Enclose | 4. | Encapsulate | 5. | Remove | 6. | Partial Removal and Establish O&M Program |
| 1.                                  | Establish O&M Program   |    |                       |    |                                  |    |         |    |             |    |        |    |   |
| 2.                                  | Repair and Establish O&M Program  |    |                       |    |                                  |    |         |    |             |    |        |    |   |
| 3.                                  | Enclose   |    |                       |    |                                  |    |         |    |             |    |        |    |   |
| 4.                                  | Encapsulate   |    |                       |    |                                  |    |         |    |             |    |        |    |   |
| 5.                                  | Remove  |    |                       |    |                                  |    |         |    |             |    |        |    |   |
| 6.                                  | Partial Removal and Establish O&M Program   |    |                       |    |                                  |    |         |    |             |    |        |    |   |



**SCHOOL DISTRICT OF PHILADELPHIA  
AHERA THREE-YEAR RE-INSPECTION IX**

**RE-INSPECTION FORM KEY**

---

The information presented in the changes section has been compiled from a variety of sources, including the Re-inspection and the following:

- \* Quality Control/Quality Assurance Reports of asbestos abatement projects, prepared by consultants to the School District.
- \* Permit and Notification Forms for asbestos abatement projects.
- \* Periodic Surveillance Forms
- \* Operations and Maintenance activities performed by School District personnel.
- \* Verbal information from School District personnel.
- \* Reports of sampling and analysis of suspected materials by both School District personnel and outside consultants.

**ROOM BY  
ROOM  
LOCATION LOG  
REPORT**

This section gives information, including damage amount and location, for a specific homogeneous material on a room-by-room basis and follows the Re-inspection form.

*NOTE:* The disparate nature of the above sources of information prohibits the verification of much information within the scope of the AHERA Three-Year Re-inspection. Discrepancies and omissions may exist in this information, and therefore is included on an "as is" basis. The inspectors for the Three-Year Re-inspection IX evaluated homogeneous areas based on the materials current condition and location, as evidenced during the inspector's site visit.

## Section II - C

### Room by Room Location Log Report

These charts are to be used for a quick reference\* in order to avoid the unknowing disturbance of Asbestos Containing Materials during any and all Operations, Maintenance, Renovation, and/or Demolition activities at this location.

*NOTE:*

*Contact OEMS prior to the disturbance of any of the materials that are listed as Confirmed and/or Assumed.*

*The quantities listed for (NAD) non-asbestos containing materials and/or Non-Suspect Materials are only estimated and were not measured for the purpose of this report. Field verification of quantities for renovation purposes would be necessary.*

# 7220 Carnell ES 2015 2016 AHERA Three-Year Report.xls

|   |                       | School District of Philadelphia               |                 | AHERA Three-Year Reinspection 2015-2016<br>Room by Room Location Log Report |                         |  |                       |    |    |                     |    |    |                              | Reinspection Date: October 21-26, 2015 |                                 |                             |                          |                         |
|---|-----------------------|---|-----------------|---|-------------------------|--|-----------------------|----|----|---------------------|----|----|------------------------------|--|---------------------------------|-----------------------------|--------------------------|-------------------------|
|   |                       | Laura H. Carnell Elementary School            |                 |   |                         |  |                       |    |    |                     |    |    |                              | Building Inspector: Scott Magee        |                                 |                             |                          |                         |
|   |                       | 1100 Devereaux Avenue, Philadelphia, PA 19111 |                 |   |                         |  |                       |    |    |                     |    |    |                              | Number: 70016699C                      |                                 |                             |                          |                         |
|   |                       | ULCS# 7220                                    |                 |   |                         |  |                       |    |    |                     |    |    |                              | Management Planner: Megan Vala         |                                 |                             |                          |                         |
|   |                       | Year Built: 1931                              |                 |   |                         |  |                       |    |    |                     |    |    |                              | Number: 740728                         |                                 |                             |                          |                         |
| E<br>l<br>e<br>m<br>e<br>n<br>t<br>r<br>y | F<br>l<br>o<br>o<br>r | On-Site Room Name                             | System Affected | Material Description  | HID#                    | Confirmed/Assumed/NAD<br>Non Suspect ACM | Amount of<br>Material | SF | LF | Amount of<br>Damage | SF | LF | Color<br>required for<br>VAT | Comments/Description/Notes             | Attic Crawl<br>Space<br>Ranking | Damage<br>Potential<br>(DP) | Newly<br>Friable<br>(NF) | Response<br>Action (RA) |
| 1   | 1                     | Classroom 101                                 | M               | Blackboard Glue Dots  | 7220/01/01/ACER/SM/2600 | Assumed                                  | 2                     | EA | 0  | EA                  | 0  | EA |                              |  |                                 | 1                           | No                       | 1/D                     |
| 1   | 1                     | Classroom 101                                 | M               | Floor Tile VAT 12" x 12"  | 7220/01/01/KK           | Assumed                                  | 1160                  | SF | 0  | SF                  | 0  | SF |                              |  |                                 | 1                           | No                       | 1/D                     |
| 1   | 1                     | Classroom 101                                 | N/A             | Pipe Fitting Insulation   |                         | NAD                                      | 12                    | EA | 0  | EA                  | 0  | EA | Grey                         |  |                                 | N/A                         | N/A                      | N/A                     |
| 1   | 1                     | Classroom 101                                 | T               | Pipe Insulation 2-6 inch  | 7220/01/01/28           | Confirmed                                | 60                    | LF | 0  | LF                  | 0  | LF |                              |  |                                 | 1                           | No                       | 1/D                     |
| 1   | 1                     | Classroom 101                                 | N/A             | Plaster Ceiling   |                         | NAD                                      | 1160                  | SF | 0  | SF                  | 0  | SF |                              |  |                                 | N/A                         | N/A                      | N/A                     |
| 1   | 1                     | Classroom 101                                 | N/A             | Plaster Walls   |                         | NAD                                      | 2320                  | SF | 0  | SF                  | 0  | SF |                              |  |                                 | N/A                         | N/A                      | N/A                     |
| 1   | 1                     | Classroom 101                                 | N/A             | Wood Floor  |                         | Non Suspect ACM                          | 1160                  | SF | 0  | SF                  | 0  | SF |                              |  |                                 | N/A                         | N/A                      | N/A                     |
| 1   | 1                     | Classroom 101 Restroom                        | N/A             | Ceramic Tile Floors   |                         | Non Suspect ACM                          | 54                    | SF | 0  | SF                  | 0  | SF |                              |  |                                 | N/A                         | N/A                      | N/A                     |
| 1   | 1                     | Classroom 101 Restroom                        | N/A             | Fiberglass Pipe Insulation  |                         | Non Suspect ACM                          | 8                     | LF | 0  | LF                  | 0  | LF |                              |  |                                 | N/A                         | N/A                      | N/A                     |
| 1   | 1                     | Classroom 101 Restroom                        | N/A             | Marble Walls  |                         | Non Suspect ACM                          | 50                    | SF | 0  | SF                  | 0  | SF |                              |  |                                 | N/A                         | N/A                      | N/A                     |
| 1   | 1                     | Classroom 101 Restroom                        | N/A             | Pipe Fitting Insulation   |                         | NAD                                      | 4                     | EA | 0  | EA                  | 0  | EA |                              |  |                                 | N/A                         | N/A                      | N/A                     |
| 1   | 1                     | Classroom 101 Restroom                        | T               | Pipe Insulation 2-6 inch  | 7220/01/01/28           | Confirmed                                | 12                    | LF | 0  | LF                  | 0  | LF |                              |  |                                 | 1                           | No                       | 1/D                     |
| 1   | 1                     | Classroom 101 Restroom                        | N/A             | Plaster Ceiling   |                         | NAD                                      | 54                    | SF | 0  | SF                  | 0  | SF |                              |  |                                 | N/A                         | N/A                      | N/A                     |
| 1   | 1                     | Classroom 101 Restroom                        | N/A             | Plaster Walls   |                         | NAD                                      | 108                   | SF | 0  | SF                  | 0  | SF |                              |  |                                 | N/A                         | N/A                      | N/A                     |
| 1   | 1                     | Classroom 101 Closet                          | M               | Floor Tile VAT 12" x 12"  | 7220/01/01/KK           | Assumed                                  | 180                   | SF | 0  | SF                  | 0  | SF | Grey                         |  |                                 | 1                           | No                       | 1/D                     |
| 1   | 1                     | Classroom 101 Closet                          | N/A             | Plaster Ceiling   |                         | NAD                                      | 180                   | SF | 0  | SF                  | 0  | SF |                              |  |                                 | N/A                         | N/A                      | N/A                     |
| 1   | 1                     | Classroom 101 Closet                          | N/A             | Plaster Walls   |                         | NAD                                      | 260                   | SF | 0  | SF                  | 0  | SF |                              |  |                                 | N/A                         | N/A                      | N/A                     |
| 1   | 1                     | Classroom 101 Closet                          | N/A             | Wood Floor  |                         | Non Suspect ACM                          | 180                   | SF | 0  | SF                  | 0  | SF |                              |  |                                 | N/A                         | N/A                      | N/A                     |
| 1   | 1                     | Classroom 101 Closet                          | M               | Floor Tile VAT 9" x 9"  | 7220/01/01/34           | Confirmed                                | 30                    | SF | 0  | SF                  | 0  | SF | Brown                        |  |                                 | 1                           | No                       | 1/D                     |
| 1   | 1                     | Classroom 101 Closet                          | N/A             | Plaster Ceiling   |                         | NAD                                      | 30                    | SF | 0  | SF                  | 0  | SF |                              |  |                                 | N/A                         | N/A                      | N/A                     |
| 1   | 1                     | Classroom 101 Closet                          | N/A             | Plaster Walls   |                         | NAD                                      | 60                    | SF | 0  | SF                  | 0  | SF |                              |  |                                 | N/A                         | N/A                      | N/A                     |
| 1   | 1                     | Classroom 101 Closet                          | N/A             | Wood Floor  |                         | Non Suspect ACM                          | 30                    | SF | 0  | SF                  | 0  | SF |                              |  |                                 | N/A                         | N/A                      | N/A                     |
| 1   | 1                     | Classroom 102                                 | M               | Blackboard Glue Dots  | 7220/01/01/ACER/SM/2600 | Assumed                                  | 3                     | EA | 0  | EA                  | 0  | EA |                              |  |                                 | 1                           | No                       | 1/D                     |
| 1   | 1                     | Classroom 102                                 | N/A             | Fiberglass Pipe Insulation  |                         | Non Suspect ACM                          | 12                    | LF | 0  | LF                  | 0  | LF |                              |  |                                 | N/A                         | N/A                      | N/A                     |
| 1   | 1                     | Classroom 102                                 | N/A             | Plaster Ceiling   |                         | NAD                                      | 870                   | SF | 0  | SF                  | 0  | SF |                              |  |                                 | N/A                         | N/A                      | N/A                     |
| 1   | 1                     | Classroom 102                                 | N/A             | Plaster Walls   |                         | NAD                                      | 1740                  | SF | 0  | SF                  | 0  | SF |                              |  |                                 | N/A                         | N/A                      | N/A                     |
| 1   | 1                     | Classroom 102                                 | N/A             | Wood Floor  |                         | Non Suspect ACM                          | 870                   | SF | 0  | SF                  | 0  | SF |                              |  |                                 | N/A                         | N/A                      | N/A                     |
| 1   | 1                     | Classroom 102 Closet                          | N/A             | Plaster Ceiling   |                         | NAD                                      | 180                   | SF | 0  | SF                  | 0  | SF |                              |  |                                 | N/A                         | N/A                      | N/A                     |
| 1   | 1                     | Classroom 102 Closet                          | N/A             | Plaster Walls   |                         | NAD                                      | 360                   | SF | 0  | SF                  | 0  | SF |                              |  |                                 | N/A                         | N/A                      | N/A                     |
| 1   | 1                     | Classroom 102 Closet                          | N/A             | Wood Floor  |                         | Non Suspect ACM                          | 180                   | SF | 0  | SF                  | 0  | SF |                              |  |                                 | N/A                         | N/A                      | N/A                     |
| 1   | 1                     | Classroom 102 Closet                          | N/A             | Plaster Ceiling   |                         | NAD                                      | 20                    | SF | 0  | SF                  | 0  | SF |                              |  |                                 | N/A                         | N/A                      | N/A                     |
| 1   | 1                     | Classroom 102 Closet                          | N/A             | Plaster Walls   |                         | NAD                                      | 40                    | SF | 0  | SF                  | 0  | SF |                              |  |                                 | N/A                         | N/A                      | N/A                     |
| 1   | 1                     | Classroom 103                                 | N/A             | Pipe Fitting Insulation   |                         | NAD                                      | 15                    | EA | 0  | EA                  | 0  | EA |                              |  |                                 | N/A                         | N/A                      | N/A                     |
| 1   | 1                     | Classroom 103                                 | T               | Pipe Insulation 2-6 inch  | 7220/01/01/28           | Confirmed                                | 60                    | LF | 0  | LF                  | 0  | LF |                              |  |                                 | 1                           | No                       | 1/D                     |
| 1   | 1                     | Classroom 103                                 | N/A             | Plaster Ceiling   |                         | NAD                                      | 928                   | SF | 0  | SF                  | 0  | SF |                              |  |                                 | N/A                         | N/A                      | N/A                     |
| 1   | 1                     | Classroom 103                                 | N/A             | Plaster Walls   |                         | NAD                                      | 1856                  | SF | 0  | SF                  | 0  | SF |                              |  |                                 | N/A                         | N/A                      | N/A                     |
| 1   | 1                     | Classroom 103                                 | N/A             | Wood Floor  |                         | Non Suspect ACM                          | 928                   | SF | 0  | SF                  | 0  | SF |                              |  |                                 | N/A                         | N/A                      | N/A                     |
| 1   | 1                     | Classroom 103 Restroom                        | N/A             | Ceramic Tile Floors   |                         | Non Suspect ACM                          | 54                    | SF | 0  | SF                  | 0  | SF |                              |  |                                 | N/A                         | N/A                      | N/A                     |
| 1   | 1                     | Classroom 103 Restroom                        | N/A             | Fiberglass Pipe Insulation  |                         | Non Suspect ACM                          | 4                     | LF | 0  | LF                  | 0  | LF |                              |  |                                 | N/A                         | N/A                      | N/A                     |
| 1   | 1                     | Classroom 103 Restroom                        | N/A             | Marble Walls  |                         | Non Suspect ACM                          | 27                    | SF | 0  | SF                  | 0  | SF |                              |  |                                 | N/A                         | N/A                      | N/A                     |
| 1   | 1                     | Classroom 103 Restroom                        | N/A             | Plaster Ceiling   |                         | NAD                                      | 54                    | SF | 0  | SF                  | 0  | SF |                              |  |                                 | N/A                         | N/A                      | N/A                     |
| 1   | 1                     | Classroom 103 Restroom                        | N/A             | Plaster Walls   |                         | NAD                                      | 108                   | SF | 0  | SF                  | 0  | SF |                              |  |                                 | N/A                         | N/A                      | N/A                     |
| 1   | 1                     | Classroom 103 Closet                          | N/A             | Fiberglass Pipe Insulation  |                         | Non Suspect ACM                          | 12                    | LF | 0  | LF                  | 0  | LF |                              |  |                                 | N/A                         | N/A                      | N/A                     |
| 1   | 1                     | Classroom 103 Closet                          | N/A             | Plaster Ceiling   |                         | NAD                                      | 180                   | SF | 0  | SF                  | 0  | SF |                              |  |                                 | N/A                         | N/A                      | N/A                     |
| 1   | 1                     | Classroom 103 Closet                          | N/A             | Plaster Walls   |                         | NAD                                      | 360                   | SF | 0  | SF                  | 0  | SF |                              |  |                                 | N/A                         | N/A                      | N/A                     |
| 1   | 1                     | Classroom 103 Closet                          | N/A             | Wood Floor  |                         | Non Suspect ACM                          | 180                   | SF | 0  | SF                  | 0  | SF |                              |  |                                 | N/A                         | N/A                      | N/A                     |
| 1   | 1                     | Classroom 104                                 | M               | Blackboard Glue Dots  | 7220/01/01/ACER/SM/2600 | Assumed                                  | 1                     | EA | 0  | EA                  | 0  | EA |                              |  |                                 | 1                           | No                       | 1/D                     |
| 1   | 1                     | Classroom 104                                 | N/A             | Fiberglass Pipe Insulation  |                         | Non Suspect ACM                          | 25                    | LF | 0  | LF                  | 0  | LF |                              |  |                                 | N/A                         | N/A                      | N/A                     |
| 1   | 1                     | Classroom 104                                 | N/A             | Pipe Fitting Insulation   |                         | NAD                                      | 8                     | EA | 0  | EA                  | 0  | EA |                              |  |                                 | N/A                         | N/A                      | N/A                     |
| 1   | 1                     | Classroom 104                                 | T               | Pipe Insulation 2-6 inch  | 7220/01/01/28           | Confirmed                                | 24                    | LF | 0  | LF                  | 0  | LF |                              |  |                                 | 1                           | No                       | 1/D                     |
| 1   | 1                     | Classroom 104                                 | N/A             | Plaster Ceiling   |                         | NAD                                      | 870                   | SF | 0  | SF                  | 0  | SF |                              |  |                                 | N/A                         | N/A                      | N/A                     |
| 1   | 1                     | Classroom 104                                 | N/A             | Plaster Walls   |                         | NAD                                      | 1740                  | SF | 0  | SF                  | 0  | SF |                              |  |                                 | N/A                         | N/A                      | N/A                     |
| 1   | 1                     | Classroom 104                                 | N/A             | Wood Floor  |                         | Non Suspect ACM                          | 870                   | SF | 0  | SF                  | 0  | SF |                              |  |                                 | N/A                         | N/A                      | N/A                     |
| 1   | 1                     | Classroom 104 Closet                          | N/A             | Fiberglass Pipe Insulation  |                         | Non Suspect ACM                          | 12                    | LF | 0  | LF                  | 0  | LF |                              |  |                                 | N/A                         | N/A                      | N/A                     |
| 1   | 1                     | Classroom 104 Closet                          | N/A             | Plaster Ceiling   |                         | NAD                                      | 180                   | SF | 0  | SF                  | 0  | SF |                              |  |                                 | N/A                         | N/A                      | N/A                     |
| 1   | 1                     | Classroom 104 Closet                          | N/A             | Plaster Walls   |                         | NAD                                      | 360                   | SF | 0  | SF                  | 0  | SF |                              |  |                                 | N/A                         | N/A                      | N/A                     |
| 1   | 1                     | Classroom 104 Closet                          | N/A             | Wood Floor  |                         | Non Suspect ACM                          | 180                   | SF | 0  | SF                  | 0  | SF |                              |  |                                 | N/A                         | N/A                      | N/A                     |
| 1   | 1                     | Classroom 104 Restroom                        | N/A             | Ceramic Tile Floors   |                         | Non Suspect ACM                          | 144                   | SF | 0  | SF                  | 0  | SF |                              |  |                                 | N/A                         | N/A                      | N/A                     |
| 1   | 1                     | Classroom 104 Restroom                        | N/A             | Fiberglass Pipe Insulation  |                         | Non Suspect ACM                          | 7                     | LF | 0  | LF                  | 0  | LF |                              |  |                                 | N/A                         | N/A                      | N/A                     |
| 1   | 1                     | Classroom 104 Restroom                        | N/A             | Marble Walls  |                         | Non Suspect ACM                          | 72                    | SF | 0  | SF                  | 0  | SF |                              |  |                                 | N/A                         | N/A                      | N/A                     |
| 1   | 1                     | Classroom 104 Restroom                        | N/A             | Plaster Ceiling   |                         | NAD                                      | 144                   | SF | 0  | SF                  | 0  | SF |                              |  |                                 | N/A                         | N/A                      | N/A                     |
| 1   | 1                     | Classroom 104 Restroom                        | N/A             | Plaster Walls   |                         | NAD                                      | 288                   | SF | 0  | SF                  | 0  | SF |                              |  |                                 | N/A                         | N/A                      | N/A                     |
| 1   | 1                     | Classroom 105                                 | M               | Blackboard Glue Dots  | 7220/01/01/ACER/SM/2600 | Assumed                                  | 1                     | EA | 0  | EA                  | 0  | EA |                              |  |                                 | 1                           | No                       | 1/D                     |
| 1   | 1                     | Classroom 105                                 | N/A             | Fiberglass Pipe Insulation  |                         | Non Suspect ACM                          | 6                     | LF | 0  | LF                  | 0  | LF |                              |  |                                 | N/A                         | N/A                      | N/A                     |
| 1   | 1                     | Classroom 105                                 | T               | Pipe Insulation 2-6 inch  | 7220/01/01/28           | Confirmed                                | 12                    | LF | 2  | LF                  | 2  | LF |                              |  |                                 | 1                           | Yes                      | 5A                      |
| 1   | 1                     | Classroom 105                                 | N/A             | Plaster Ceiling   |                         | NAD                                      | 870                   | SF | 0  | SF                  | 0  | SF |                              |  |                                 | N/A                         | N/A                      | N/A                     |
| 1   | 1                     | Classroom 105                                 | N/A             | Plaster Walls   |                         | NAD                                      | 1740                  | SF | 0  | SF                  | 0  | SF |                              |  |                                 | N/A                         | N/A                      | N/A                     |
| 1   | 1                     | Classroom 105                                 | N/A             | Wood Floor  |                         | Non Suspect ACM                          | 870                   | SF | 0  | SF                  | 0  | SF |                              |  |                                 | N/A                         | N/A                      | N/A                     |
| 1   | 1                     | Classroom 105 Closet                          | N/A             | Plaster Ceiling   |                         | NAD                                      | 120                   | SF | 0  | SF                  | 0  | SF |                              |  |                                 | N/A                         | N/A                      | N/A                     |
| 1   | 1                     | Classroom 105 Closet                          | N/A             | Plaster Walls   |                         | NAD                                      | 240                   | SF | 0  | SF                  | 0  | SF |                              |  |                                 | N/A                         | N/A                      | N/A                     |
| 1   | 1                     | Classroom 105 Closet                          | N/A             | Wood Floor  |                         | Non Suspect ACM                          | 120                   | SF | 0  | SF                  | 0  | SF |                              |  |                                 | N/A                         | N/A                      | N/A                     |
| 1   | 1                     | Classroom 106                                 | T               | Pipe Insulation > 6 inch  | 7220/01/01/26           | Confirmed                                | 4                     | LF | 0  | LF                  | 0  | LF |                              |  |                                 | 1                           | No                       | 1/D                     |
| 1   | 1                     | Classroom 106                                 | T               | Pipe Insulation 2-6 inch  | 7220/01/01/28           | Confirmed                                | 6                     | LF | 0  | LF                  | 0  | LF |                              |  |                                 | 1                           | No                       | 1/D                     |
| 1   | 1                     | Classroom 106                                 | N/A             | Plaster Ceiling   |                         | NAD                                      | 870                   | SF | 0  | SF                  | 0  | SF |                              |  |                                 | N/A                         | N/A                      | N/A                     |
| 1   | 1                     | Classroom 106                                 | N/A             | Plaster Walls   |                         | NAD                                      | 1740                  | SF | 0  | SF                  | 0  | SF |                              |  |                                 | N/A                         | N/A                      | N/A                     |

# 7220 Carnell ES 2015 2016 AHERA Three-Year Report.xls

| School District of Philadelphia               |                       |                          | AHERA Three-Year Reinspection 2015-2016 |                                 |                         |  |                       |          |          |                     |          |          |                              |                            |                                 | Reinspection Date: October 21-26, 2015 |                          |                         |  |  |
|---|-----------------------|--------------------------|---|---------------------------------|-------------------------|--|-----------------------|----------|----------|---------------------|----------|----------|------------------------------|----------------------------|---------------------------------|--|--------------------------|-------------------------|--|--|
| Laura H. Carnell Elementary School            |                       |                          | Room by Room Location Log Report        |                                 |                         |  |                       |          |          |                     |          |          |                              |                            |                                 | Building Inspector: Scott Magee        |                          |                         |  |  |
| 1100 Devereaux Avenue, Philadelphia, PA 19111 |                       |                          |   |                                 |                         |  |                       |          |          |                     |          |          |                              |                            |                                 | Number: 70016699C                      |                          |                         |  |  |
| ULCS# 7220                                    |                       |                          |   |                                 |                         |  |                       |          |          |                     |          |          |                              |                            |                                 | Management Planner: Megan Vala         |                          |                         |  |  |
| Year Built: 1931                              |                       |                          |   |                                 |                         |  |                       |          |          |                     |          |          |                              |                            |                                 | Number: 740728                         |                          |                         |  |  |
| E<br>l<br>e<br>m<br>e<br>n<br>t               | F<br>l<br>o<br>o<br>r | On-Site Room Name        | System Affected                         | Material Description            | HID#                    | Confirmed/Assumed/NAD<br>Non Suspect ACM | Amount of<br>Material | SF<br>EA | LF<br>EA | Amount of<br>Damage | SF<br>EA | LF<br>EA | Color<br>required for<br>VAT | Comments/Description/Notes | Attic Crawl<br>Space<br>Ranking | Damage<br>Potential<br>(DP)            | Newly<br>Friable<br>(NF) | Response<br>Action (RA) |  |  |
| 1   | 1                     | Classroom 106            | N/A                                     | Wood Floor                      |                         | Non Suspect ACM                          | 870                   | SF       | 0        | SF                  |          |          |                              |                            |                                 | N/A                                    | N/A                      | N/A                     |  |  |
| 1   | 1                     | Classroom 106 Closet     | N/A                                     | Plaster Ceiling                 |                         | NAD                                      | 120                   | SF       | 0        | SF                  |          |          |                              |                            |                                 | N/A                                    | N/A                      | N/A                     |  |  |
| 1   | 1                     | Classroom 106 Closet     | N/A                                     | Plaster Walls                   |                         | NAD                                      | 240                   | SF       | 0        | SF                  |          |          |                              |                            |                                 | N/A                                    | N/A                      | N/A                     |  |  |
| 1   | 1                     | Classroom 106 Closet     | N/A                                     | Wood Floor                      |                         | Non Suspect ACM                          | 120                   | SF       | 0        | SF                  |          |          |                              |                            |                                 | N/A                                    | N/A                      | N/A                     |  |  |
| 1   | 1                     | Classroom 107            | M                                       | Blackboard Glue Dots            | 7220/01/01/ACER/SM/2600 | Assumed                                  | 2                     | EA       | 0        | EA                  |          |          |                              |                            |                                 | 1                                      | No                       | 1/D                     |  |  |
| 1   | 1                     | Classroom 107            | N/A                                     | Fiberglass Pipe Insulation      |                         | Non Suspect ACM                          | 8                     | LF       | 0        | LF                  |          |          |                              |                            |                                 | N/A                                    | N/A                      | N/A                     |  |  |
| 1   | 1                     | Classroom 107            | T                                       | Pipe Insulation 2-6 inch        | 7220/01/01/28           | Confirmed                                | 12                    | LF       | 0        | LF                  |          |          |                              |                            |                                 | 1                                      | No                       | 1/D                     |  |  |
| 1   | 1                     | Classroom 107            | N/A                                     | Plaster Ceiling                 |                         | NAD                                      | 870                   | SF       | 0        | SF                  |          |          |                              |                            |                                 | N/A                                    | N/A                      | N/A                     |  |  |
| 1   | 1                     | Classroom 107            | N/A                                     | Plaster Walls                   |                         | NAD                                      | 1740                  | SF       | 0        | SF                  |          |          |                              |                            |                                 | N/A                                    | N/A                      | N/A                     |  |  |
| 1   | 1                     | Classroom 107            | N/A                                     | Wood Floor                      |                         | Non Suspect ACM                          | 870                   | SF       | 0        | SF                  |          |          |                              |                            |                                 | N/A                                    | N/A                      | N/A                     |  |  |
| 1   | 1                     | Classroom 107 Closet     | N/A                                     | Fiberglass Pipe Insulation      |                         | Non Suspect ACM                          | 12                    | LF       | 0        | LF                  |          |          |                              |                            |                                 | N/A                                    | N/A                      | N/A                     |  |  |
| 1   | 1                     | Classroom 107 Closet     | N/A                                     | Pipe Fitting Insulation         |                         | NAD                                      | 2                     | EA       | 0        | EA                  |          |          |                              |                            |                                 | N/A                                    | N/A                      | N/A                     |  |  |
| 1   | 1                     | Classroom 107 Closet     | N/A                                     | Plaster Ceiling                 |                         | NAD                                      | 120                   | SF       | 0        | SF                  |          |          |                              |                            |                                 | N/A                                    | N/A                      | N/A                     |  |  |
| 1   | 1                     | Classroom 107 Closet     | N/A                                     | Plaster Walls                   |                         | NAD                                      | 240                   | SF       | 0        | SF                  |          |          |                              |                            |                                 | N/A                                    | N/A                      | N/A                     |  |  |
| 1   | 1                     | Classroom 107 Closet     | N/A                                     | Wood Floor                      |                         | Non Suspect ACM                          | 120                   | SF       | 0        | SF                  |          |          |                              |                            |                                 | N/A                                    | N/A                      | N/A                     |  |  |
| 1   | 1                     | Boy's Restroom           | N/A                                     | Cement Floor                    |                         | Non Suspect ACM                          | 198                   | SF       | 0        | SF                  |          |          |                              |                            |                                 | N/A                                    | N/A                      | N/A                     |  |  |
| 1   | 1                     | Boy's Restroom           | N/A                                     | Fiberglass Pipe Insulation      |                         | Non Suspect ACM                          | 30                    | LF       | 0        | LF                  |          |          |                              |                            |                                 | N/A                                    | N/A                      | N/A                     |  |  |
| 1   | 1                     | Boy's Restroom           | N/A                                     | Marble Walls                    |                         | Non Suspect ACM                          | 198                   | SF       | 0        | SF                  |          |          |                              |                            |                                 | N/A                                    | N/A                      | N/A                     |  |  |
| 1   | 1                     | Boy's Restroom           | N/A                                     | Plaster Ceiling                 |                         | NAD                                      | 198                   | SF       | 0        | SF                  |          |          |                              |                            |                                 | N/A                                    | N/A                      | N/A                     |  |  |
| 1   | 1                     | Boy's Restroom           | N/A                                     | Plaster Walls                   |                         | NAD                                      | 396                   | SF       | 0        | SF                  |          |          |                              |                            |                                 | N/A                                    | N/A                      | N/A                     |  |  |
| 1   | 1                     | Classroom 108            | M                                       | Blackboard Glue Dots            | 7220/01/01/ACER/SM/2600 | Assumed                                  | 3                     | EA       | 0        | EA                  |          |          |                              |                            |                                 | 1                                      | No                       | 1/D                     |  |  |
| 1   | 1                     | Classroom 108            | T                                       | Pipe Insulation > 6 inch        | 7220/01/01/26           | Confirmed                                | 34                    | LF       | 0        | LF                  |          |          |                              |                            |                                 | 1                                      | No                       | 1/D                     |  |  |
| 1   | 1                     | Classroom 108            | T                                       | Pipe Insulation 2-6 inch        | 7220/01/01/28           | Confirmed                                | 6                     | LF       | 0        | LF                  |          |          |                              |                            |                                 | 1                                      | No                       | 1/D                     |  |  |
| 1   | 1                     | Classroom 108            | N/A                                     | Plaster Ceiling                 |                         | NAD                                      | 952                   | SF       | 0        | SF                  |          |          |                              |                            |                                 | N/A                                    | N/A                      | N/A                     |  |  |
| 1   | 1                     | Classroom 108            | N/A                                     | Plaster Walls                   |                         | NAD                                      | 1914                  | SF       | 0        | SF                  |          |          |                              |                            |                                 | N/A                                    | N/A                      | N/A                     |  |  |
| 1   | 1                     | Classroom 108            | N/A                                     | Wood Floor                      |                         | Non Suspect ACM                          | 952                   | SF       | 0        | SF                  |          |          |                              |                            |                                 | N/A                                    | N/A                      | N/A                     |  |  |
| 1   | 1                     | Classroom 108 Closet     | N/A                                     | Plaster Ceiling                 |                         | NAD                                      | 108                   | SF       | 0        | SF                  |          |          |                              |                            |                                 | N/A                                    | N/A                      | N/A                     |  |  |
| 1   | 1                     | Classroom 108 Closet     | N/A                                     | Plaster Walls                   |                         | NAD                                      | 216                   | SF       | 0        | SF                  |          |          |                              |                            |                                 | N/A                                    | N/A                      | N/A                     |  |  |
| 1   | 1                     | Classroom 108 Closet     | N/A                                     | Wood Floor                      |                         | Non Suspect ACM                          | 108                   | SF       | 0        | SF                  |          |          |                              |                            |                                 | N/A                                    | N/A                      | N/A                     |  |  |
| 1   | 1                     | Classroom 108 Closet     | N/A                                     | Pipe Fitting Insulation         |                         | NAD                                      | 1                     | EA       | 0        | EA                  |          |          |                              |                            |                                 | N/A                                    | N/A                      | N/A                     |  |  |
| 1   | 1                     | Classroom 108 Closet     | T                                       | Pipe Insulation 2-6 inch        | 7220/01/01/28           | Confirmed                                | 14                    | LF       | 0        | LF                  |          |          |                              |                            |                                 | 1                                      | No                       | 1/D                     |  |  |
| 1   | 1                     | Classroom 108 Closet     | N/A                                     | Plaster Ceiling                 |                         | NAD                                      | 60                    | SF       | 0        | SF                  |          |          |                              |                            |                                 | N/A                                    | N/A                      | N/A                     |  |  |
| 1   | 1                     | Classroom 108 Closet     | N/A                                     | Plaster Walls                   |                         | NAD                                      | 120                   | SF       | 0        | SF                  |          |          |                              |                            |                                 | N/A                                    | N/A                      | N/A                     |  |  |
| 1   | 1                     | Classroom 108 Closet     | N/A                                     | Wood Floor                      |                         | Non Suspect ACM                          | 60                    | SF       | 0        | SF                  |          |          |                              |                            |                                 | N/A                                    | N/A                      | N/A                     |  |  |
| 1   | 1                     | Classroom 109            | M                                       | Blackboard Glue Dots            | 7220/01/01/ACER/SM/2600 | Assumed                                  | 3                     | EA       | 0        | EA                  |          |          |                              |                            |                                 | 1                                      | No                       | 1/D                     |  |  |
| 1   | 1                     | Classroom 109            | N/A                                     | Fiberglass Pipe Insulation      |                         | Non Suspect ACM                          | 8                     | LF       | 0        | LF                  |          |          |                              |                            |                                 | N/A                                    | N/A                      | N/A                     |  |  |
| 1   | 1                     | Classroom 109            | T                                       | Pipe Insulation 2-6 inch        | 7220/01/01/28           | Confirmed                                | 12                    | LF       | 0        | LF                  |          |          |                              |                            |                                 | 1                                      | No                       | 1/D                     |  |  |
| 1   | 1                     | Classroom 109            | N/A                                     | Plaster Ceiling                 |                         | NAD                                      | 952                   | SF       | 0        | SF                  |          |          |                              |                            |                                 | N/A                                    | N/A                      | N/A                     |  |  |
| 1   | 1                     | Classroom 109            | N/A                                     | Plaster Walls                   |                         | NAD                                      | 1914                  | SF       | 0        | SF                  |          |          |                              |                            |                                 | N/A                                    | N/A                      | N/A                     |  |  |
| 1   | 1                     | Classroom 109            | N/A                                     | Wood Floor                      |                         | Non Suspect ACM                          | 952                   | SF       | 0        | SF                  |          |          |                              |                            |                                 | N/A                                    | N/A                      | N/A                     |  |  |
| 1   | 1                     | Classroom 109 Closet     | N/A                                     | Plaster Ceiling                 |                         | NAD                                      | 108                   | SF       | 0        | SF                  |          |          |                              |                            |                                 | N/A                                    | N/A                      | N/A                     |  |  |
| 1   | 1                     | Classroom 109 Closet     | N/A                                     | Plaster Walls                   |                         | NAD                                      | 216                   | SF       | 0        | SF                  |          |          |                              |                            |                                 | N/A                                    | N/A                      | N/A                     |  |  |
| 1   | 1                     | Classroom 109 Closet     | N/A                                     | Wood Floor                      |                         | Non Suspect ACM                          | 108                   | SF       | 0        | SF                  |          |          |                              |                            |                                 | N/A                                    | N/A                      | N/A                     |  |  |
| 1   | 1                     | Computer Room 110        | M                                       | Blackboard Glue Dots            | 7220/01/01/ACER/SM/2600 | Assumed                                  | 3                     | EA       | 0        | EA                  |          |          |                              |                            |                                 | 1                                      | No                       | 1/D                     |  |  |
| 1   | 1                     | Computer Room 110        | N/A                                     | Fiberglass Pipe Insulation      |                         | Non Suspect ACM                          | 16                    | LF       | 0        | LF                  |          |          |                              |                            |                                 | N/A                                    | N/A                      | N/A                     |  |  |
| 1   | 1                     | Computer Room 110        | T                                       | Pipe Insulation 2-6 inch        | 7220/01/01/28           | Confirmed                                | 24                    | LF       | 0        | LF                  |          |          |                              |                            |                                 | 1                                      | No                       | 1/D                     |  |  |
| 1   | 1                     | Computer Room 110        | N/A                                     | Plaster Ceiling                 |                         | NAD                                      | 957                   | SF       | 0        | SF                  |          |          |                              |                            |                                 | N/A                                    | N/A                      | N/A                     |  |  |
| 1   | 1                     | Computer Room 110        | N/A                                     | Plaster Walls                   |                         | NAD                                      | 1914                  | SF       | 0        | SF                  |          |          |                              |                            |                                 | N/A                                    | N/A                      | N/A                     |  |  |
| 1   | 1                     | Computer Room 110        | N/A                                     | Wood Floor                      |                         | Non Suspect ACM                          | 957                   | SF       | 0        | SF                  |          |          |                              |                            |                                 | N/A                                    | N/A                      | N/A                     |  |  |
| 1   | 1                     | Computer Room 110 Closet | N/A                                     | Wood Floor                      |                         | Non Suspect ACM                          | 108                   | SF       | 0        | SF                  |          |          |                              |                            |                                 | N/A                                    | N/A                      | N/A                     |  |  |
| 1   | 1                     | Computer Room 110 Closet | N/A                                     | Plaster Ceiling                 |                         | NAD                                      | 216                   | SF       | 0        | SF                  |          |          |                              |                            |                                 | N/A                                    | N/A                      | N/A                     |  |  |
| 1   | 1                     | Computer Room 110 Closet | N/A                                     | Plaster Walls                   |                         | NAD                                      | 108                   | SF       | 0        | SF                  |          |          |                              |                            |                                 | N/A                                    | N/A                      | N/A                     |  |  |
| 1   | 1                     | Computer Room 110 Closet | N/A                                     | Wood Floor                      |                         | Non Suspect ACM                          | 40                    | SF       | 0        | SF                  |          |          |                              |                            |                                 | N/A                                    | N/A                      | N/A                     |  |  |
| 1   | 1                     | Computer Room 110 Closet | N/A                                     | Plaster Ceiling                 |                         | NAD                                      | 40                    | SF       | 0        | SF                  |          |          |                              |                            |                                 | N/A                                    | N/A                      | N/A                     |  |  |
| 1   | 1                     | Computer Room 110 Closet | N/A                                     | Plaster Walls                   |                         | NAD                                      | 100                   | SF       | 0        | SF                  |          |          |                              |                            |                                 | N/A                                    | N/A                      | N/A                     |  |  |
| 1   | 1                     | Counselor's Office       | X                                       | X                               |                         | X  | X                     | X        | 0        | X                   |          |          |                              | No Access                  |                                 | X                                      | X                        | X                       |  |  |
| 1   | 1                     | Women's Restroom         | X                                       | X                               |                         | X  | X                     | X        | 0        | X                   |          |          |                              | No Access                  |                                 | X                                      | X                        | X                       |  |  |
| 1   | 1                     | Storage Closet           | X                                       | X                               |                         | X  | X                     | X        | 0        | X                   |          |          |                              | No Access                  |                                 | X                                      | X                        | X                       |  |  |
| 1   | 1                     | School Police Office     | N/A                                     | Fiberglass Ceiling Tile 2' x 4' |                         | Non Suspect ACM                          | 120                   | SF       | 0        | SF                  |          |          |                              |                            |                                 | N/A                                    | N/A                      | N/A                     |  |  |
| 1   | 1                     | School Police Office     | N/A                                     | Fiberglass Pipe Insulation      |                         | Non Suspect ACM                          | 4                     | LF       | 0        | LF                  |          |          |                              |                            |                                 | N/A                                    | N/A                      | N/A                     |  |  |
| 1   | 1                     | School Police Office     | N/A                                     | Plaster Ceiling                 |                         | NAD                                      | 120                   | SF       | 0        | SF                  |          |          |                              |                            |                                 | N/A                                    | N/A                      | N/A                     |  |  |
| 1   | 1                     | School Police Office     | N/A                                     | Plaster Walls                   |                         | NAD                                      | 240                   | SF       | 0        | SF                  |          |          |                              |                            |                                 | N/A                                    | N/A                      | N/A                     |  |  |
| 1   | 1                     | School Police Office     | N/A                                     | Wood Floor                      |                         | Non Suspect ACM                          | 120                   | SF       | 0        | SF                  |          |          |                              |                            |                                 | N/A                                    | N/A                      | N/A                     |  |  |
| 1   | 1                     | Main Office              | M                                       | Floor Tile VAT 12" x 12"        | 7220/01/01/KK           | Assumed                                  | 336                   | SF       | 0        | SF                  |          |          | Grey                         |                            |                                 | 1                                      | No                       | 1/D                     |  |  |
| 1   | 1                     | Main Office              | N/A                                     | Pipe Fitting Insulation         |                         | NAD                                      | 6                     | EA       | 0        | EA                  |          |          |                              |                            |                                 | N/A                                    | N/A                      | N/A                     |  |  |
| 1   | 1                     | Main Office              | T                                       | Pipe Insulation 2-6 inch        | 7220/01/01/28           | Confirmed                                | 14                    | LF       | 0        | LF                  |          |          |                              |                            |                                 | 1                                      | No                       | 1/D                     |  |  |
| 1   | 1                     | Main Office              | N/A                                     | Plaster Ceiling                 |                         | NAD                                      | 336                   | SF       | 0        | SF                  |          |          |                              |                            |                                 | N/A                                    | N/A                      | N/A                     |  |  |
| 1   | 1                     | Main Office              | N/A                                     | Plaster Walls                   |                         | NAD                                      | 672                   | SF       | 0        | SF                  |          |          |                              |                            |                                 | N/A                                    | N/A                      | N/A                     |  |  |
| 1   | 1                     | Main Office              | N/A                                     | Wood Floor                      |                         | Non Suspect ACM                          | 336                   | SF       | 0        | SF                  |          |          |                              |                            |                                 | N/A                                    | N/A                      | N/A                     |  |  |
| 1   | 1                     | Main Office Closet       | M                                       | Floor Tile VAT 12" x 12"        | 7220/01/01/KK           | Assumed                                  | 70                    | SF       | 0        | SF                  |          |          | Tan                          |                            |                                 | 1                                      | No                       | 1/D                     |  |  |
| 1   | 1                     | Main Office Closet       | N/A                                     | Pipe Fitting Insulation         |                         | NAD                                      | 6                     | EA       | 0        | EA                  |          |          |                              |                            |                                 | N/A                                    | N/A                      | N/A                     |  |  |
| 1   | 1                     | Main Office Closet       | T                                       | Pipe Insulation 2-6 inch        | 7220/01/01/28           | Confirmed                                | 14                    | LF       | 0        | LF                  |          |          |                              |                            |                                 | 1                                      | No                       | 1/D                     |  |  |
| 1   | 1                     | Main Office Closet       | N/A                                     | Plaster Ceiling                 |                         | NAD                                      | 70                    | SF       | 0        | SF                  |          |          |                              |                            |                                 | N/A                                    | N/A                      | N/A                     |  |  |
| 1   | 1                     | Main Office Closet       | N/A                                     | Plaster Walls                   |                         | NAD                                      | 140                   | SF       | 0        | SF                  |          |          |                              |                            |                                 | N/A                                    | N/A                      | N/A                     |  |  |
| 1   | 1                     | Main Office Closet       | N/A                                     | Wood Floor                      |                         | Non Suspect ACM                          | 70                    | SF       | 0        | SF                  |          |          | Grey                         |                            |                                 | N/A                                    | N/A                      | N/A                     |  |  |
| 1   | 1                     | Main Office Closet       | M                                       | Floor Tile VAT 12" x 12"        | 7220/01/01/KK           | Assumed                                  | 24                    | SF       | 0        | SF                  |          |          | Tan                          |                            |                                 | 1                                      | No                       | 1/D                     |  |  |

# 7220 Carnell ES 2015 2016 AHERA Three-Year Report.xls

| School District of Philadelphia               |                       |   | AHERA Three-Year Reinspection 2015-2016 |                            |                         |  |                       |          |                     |          |                              |  | Reinspection Date: October 21-26, 2015 |                             |                          |                         |  |  |
|---|-----------------------|---|---|----------------------------|-------------------------|--|-----------------------|----------|---------------------|----------|------------------------------|--|--|-----------------------------|--------------------------|-------------------------|--|--|
| Laura H. Carnell Elementary School            |                       |   | Room by Room Location Log Report        |                            |                         |  |                       |          |                     |          |                              |  | Building Inspector: Scott Magee        |                             |                          |                         |  |  |
| 1100 Devereaux Avenue, Philadelphia, PA 19111 |                       |   |   |                            |                         |  |                       |          |                     |          |                              |  | Number: 70016699C                      |                             |                          |                         |  |  |
| ULCS# 7220                                    |                       |   |   |                            |                         |  |                       |          |                     |          |                              |  | Management Planner: Megan Vala         |                             |                          |                         |  |  |
| Year Built: 1931                              |                       |   |   |                            |                         |  |                       |          |                     |          |                              |  | Number: 740728                         |                             |                          |                         |  |  |
| E<br>l<br>e<br>m<br>e<br>n<br>t               | F<br>l<br>o<br>o<br>r | On-Site Room Name                                     | System Affected                         | Material Description       | HID#                    | Confirmed/Assumed/NAD<br>Non Suspect ACM | Amount of<br>Material | SF<br>EA | Amount of<br>Damage | SF<br>EA | Color<br>required for<br>VAT | Comments/Description/Notes                       | Attic Crawl<br>Space<br>Ranking        | Damage<br>Potential<br>(DP) | Newly<br>Friable<br>(NF) | Response<br>Action (RA) |  |  |
| 1   | 1                     | Main Office Closet                                    | N/A                                     | Plaster Ceiling            |                         | NAD                                      | 24                    | SF       | 0                   | SF       |                              |  |  | N/A                         | N/A                      | N/A                     |  |  |
| 1   | 1                     | Main Office Closet                                    | N/A                                     | Plaster Walls              |                         | NAD                                      | 48                    | SF       | 0                   | SF       |                              |  |  | N/A                         | N/A                      | N/A                     |  |  |
| 1   | 1                     | Main Office Closet                                    | N/A                                     | Wood Floor                 |                         | Non Suspect ACM                          | 24                    | SF       | 0                   | SF       |                              |  |  | N/A                         | N/A                      | N/A                     |  |  |
| 1   | 1                     | Principal's Office                                    | M                                       | Floor Tile VAT 12" x 12"   | 7220/01/01/KK           | Assumed                                  | 256                   | SF       | 0                   | SF       | Grey                         |  |  | 1                           | No                       | 1/D                     |  |  |
| 1   | 1                     | Principal's Office                                    | N/A                                     | Pipe Fitting Insulation    |                         | NAD                                      | 8                     | EA       | 0                   | EA       |                              |  |  | N/A                         | N/A                      | N/A                     |  |  |
| 1   | 1                     | Principal's Office                                    | T                                       | Pipe Insulation 2-6 inch   | 7220/01/01/28           | Confirmed                                | 36                    | LF       | 0                   | LF       |                              |  |  | 1                           | No                       | 1/D                     |  |  |
| 1   | 1                     | Principal's Office                                    | N/A                                     | Plaster Ceiling            |                         | NAD                                      | 256                   | SF       | 0                   | SF       |                              |  |  | N/A                         | N/A                      | N/A                     |  |  |
| 1   | 1                     | Principal's Office                                    | N/A                                     | Plaster Walls              |                         | NAD                                      | 512                   | SF       | 0                   | SF       |                              |  |  | N/A                         | N/A                      | N/A                     |  |  |
| 1   | 1                     | Principal's Office                                    | N/A                                     | Wood Floor                 |                         | Non Suspect ACM                          | 256                   | SF       | 0                   | SF       |                              |  |  | N/A                         | N/A                      | N/A                     |  |  |
| 1   | 1                     | Principal's Office Restroom                           | N/A                                     | Fiberglass Pipe Insulation |                         | Non Suspect ACM                          | 12                    | LF       | 0                   | LF       |                              |  |  | N/A                         | N/A                      | N/A                     |  |  |
| 1   | 1                     | Principal's Office Restroom                           | M                                       | Floor Tile VAT 12" x 12"   | 7220/01/01/KK           | Assumed                                  | 36                    | SF       | 0                   | SF       | Grey                         |  |  | 1                           | No                       | 1/D                     |  |  |
| 1   | 1                     | Principal's Office Restroom                           | N/A                                     | Pipe Fitting Insulation    |                         | NAD                                      | 6                     | EA       | 0                   | EA       |                              |  |  | N/A                         | N/A                      | N/A                     |  |  |
| 1   | 1                     | Principal's Office Restroom                           | T                                       | Pipe Insulation 2-6 inch   | 7220/01/01/28           | Confirmed                                | 20                    | LF       | 0                   | LF       |                              |  |  | 1                           | No                       | 1/D                     |  |  |
| 1   | 1                     | Principal's Office Restroom                           | N/A                                     | Plaster Ceiling            |                         | NAD                                      | 36                    | SF       | 0                   | SF       |                              |  |  | N/A                         | N/A                      | N/A                     |  |  |
| 1   | 1                     | Principal's Office Restroom                           | N/A                                     | Plaster Walls              |                         | NAD                                      | 72                    | SF       | 0                   | SF       |                              |  |  | N/A                         | N/A                      | N/A                     |  |  |
| 1   | 1                     | Auditorium  | S                                       | Decorative Plaster         | 7220/01/01/NN           | Assumed                                  | 400                   | SF       | 0                   | SF       |                              |  |  | 1                           | No                       | 1/D                     |  |  |
| 1   | 1                     | Auditorium  | S                                       | Plaster Ceiling            | 7220/01/01/NN           | Assumed                                  | 3360                  | SF       | 80                  | SF       |                              |  |  | 1                           | Yes                      | 5/B                     |  |  |
| 1   | 1                     | Auditorium  | N/A                                     | Plaster Walls              |                         | NAD                                      | 6720                  | SF       | 0                   | SF       |                              | A full compliment of samples were taken May 2012 |  | N/A                         | N/A                      | N/A                     |  |  |
| 1   | 1                     | Auditorium  | N/A                                     | Wood Floor                 |                         | Non Suspect ACM                          | 3360                  | SF       | 0                   | SF       |                              |  |  | N/A                         | N/A                      | N/A                     |  |  |
| 1   | 1                     | Auditorium Stage                                      | S                                       | Plaster Ceiling            | 7220/01/01/NN           | Assumed                                  | 540                   | SF       | 0                   | SF       |                              |  |  | 1                           | No                       | 1/D                     |  |  |
| 1   | 1                     | Auditorium Stage                                      | N/A                                     | Plaster Walls              |                         | NAD                                      | 1080                  | SF       | 10                  | SF       |                              | A full compliment of samples were taken May 2012 |  | N/A                         | N/A                      | N/A                     |  |  |
| 1   | 1                     | Auditorium Stage                                      | M                                       | Stage Curtain              | 7220/01/01/ACER/SM/2606 | Assumed                                  | 810                   | SF       | 0                   | SF       |                              |  |  | 1                           | No                       | 1/D                     |  |  |
| 1   | 1                     | Auditorium Stage                                      | N/A                                     | Wood Floor                 |                         | Non Suspect ACM                          | 540                   | SF       | 0                   | SF       |                              |  |  | N/A                         | N/A                      | N/A                     |  |  |
| 1   | 1                     | Stage Closet  | N/A                                     | Plaster Ceiling            |                         | NAD                                      | 126                   | SF       | 10                  | SF       |                              |  |  | N/A                         | N/A                      | N/A                     |  |  |
| 1   | 1                     | Stage Closet  | N/A                                     | Plaster Walls              |                         | NAD                                      | 252                   | SF       | 20                  | SF       |                              |  |  | N/A                         | N/A                      | N/A                     |  |  |
| 1   | 1                     | Stage Closet  | N/A                                     | Wood Floor                 |                         | Non Suspect ACM                          | 126                   | SF       | 0                   | SF       |                              |  |  | N/A                         | N/A                      | N/A                     |  |  |
| 1   | 1                     | Stage Restroom  | N/A                                     | Fiberglass Pipe Insulation |                         | Non Suspect ACM                          | 2                     | LF       | 0                   | LF       |                              |  |  | N/A                         | N/A                      | N/A                     |  |  |
| 1   | 1                     | Stage Restroom  | M                                       | Floor Tile VAT 12" x 12"   | 7220/01/01/KK           | Assumed                                  | 15                    | SF       | 0                   | SF       | White                        |  |  | 1                           | No                       | 1/D                     |  |  |
| 1   | 1                     | Stage Restroom  | N/A                                     | Plaster Ceiling            |                         | NAD                                      | 15                    | SF       | 0                   | SF       |                              |  |  | N/A                         | N/A                      | N/A                     |  |  |
| 1   | 1                     | Stage Restroom  | N/A                                     | Plaster Walls              |                         | NAD                                      | 30                    | SF       | 0                   | SF       |                              |  |  | N/A                         | N/A                      | N/A                     |  |  |
| 1   | 1                     | Stage Restroom  | N/A                                     | Wood Floor                 |                         | Non Suspect ACM                          | 15                    | SF       | 0                   | SF       |                              |  |  | N/A                         | N/A                      | N/A                     |  |  |
| 1   | 1                     | Stage Closet  | N/A                                     | Plaster Ceiling            |                         | NAD                                      | 126                   | SF       | 0                   | SF       |                              |  |  | N/A                         | N/A                      | N/A                     |  |  |
| 1   | 1                     | Stage Closet  | N/A                                     | Plaster Walls              |                         | NAD                                      | 252                   | SF       | 20                  | SF       |                              |  |  | N/A                         | N/A                      | N/A                     |  |  |
| 1   | 1                     | Stage Closet  | N/A                                     | Wood Floor                 |                         | Non Suspect ACM                          | 126                   | SF       | 0                   | SF       |                              |  |  | N/A                         | N/A                      | N/A                     |  |  |
| 1   | 1                     | Stage Restroom  | M                                       | Floor Tile VAT 12" x 12"   | 7220/01/01/KK           | Assumed                                  | 15                    | SF       | 0                   | SF       | White                        |  |  | 1                           | No                       | 1/D                     |  |  |
| 1   | 1                     | Stage Restroom  | N/A                                     | Plaster Ceiling            |                         | NAD                                      | 15                    | SF       | 5                   | SF       |                              |  |  | N/A                         | N/A                      | N/A                     |  |  |
| 1   | 1                     | Stage Restroom  | N/A                                     | Plaster Walls              |                         | NAD                                      | 30                    | SF       | 0                   | SF       |                              |  |  | N/A                         | N/A                      | N/A                     |  |  |
| 1   | 1                     | Stage Restroom  | N/A                                     | Wood Floor                 |                         | Non Suspect ACM                          | 15                    | SF       | 0                   | SF       |                              |  |  | N/A                         | N/A                      | N/A                     |  |  |
| 1   | 1                     | First Floor Hallway                                   | N/A                                     | Cement Floor               |                         | Non Suspect ACM                          | 996                   | SF       | 0                   | SF       |                              |  |  | N/A                         | N/A                      | N/A                     |  |  |
| 1   | 1                     | First Floor Hallway                                   | N/A                                     | Marble Walls               |                         | Non Suspect ACM                          | 996                   | SF       | 0                   | SF       |                              |  |  | N/A                         | N/A                      | N/A                     |  |  |
| 1   | 1                     | First Floor Hallway                                   | N/A                                     | Pipe Fitting Insulation    |                         | NAD                                      | 16                    | EA       | 0                   | EA       |                              |  |  | N/A                         | N/A                      | N/A                     |  |  |
| 1   | 1                     | First Floor Hallway                                   | T                                       | Pipe Insulation 2-6 inch   | 7220/01/01/28           | Confirmed                                | 64                    | LF       | 0                   | LF       |                              |  |  | 1                           | No                       | 1/D                     |  |  |
| 1   | 1                     | First Floor Hallway                                   | N/A                                     | Plaster Ceiling            |                         | NAD                                      | 996                   | SF       | 0                   | SF       |                              |  |  | N/A                         | N/A                      | N/A                     |  |  |
| 1   | 1                     | First Floor Hallway                                   | N/A                                     | Plaster Walls              |                         | NAD                                      | 1992                  | SF       | 0                   | SF       |                              |  |  | N/A                         | N/A                      | N/A                     |  |  |
| 1   | 1                     | First Floor Hallway                                   | N/A                                     | Cement Floor               |                         | Non Suspect ACM                          | 1518                  | SF       | 0                   | SF       |                              |  |  | N/A                         | N/A                      | N/A                     |  |  |
| 1   | 1                     | First Floor Hallway                                   | N/A                                     | Marble Walls               |                         | Non Suspect ACM                          | 1518                  | SF       | 0                   | SF       |                              |  |  | N/A                         | N/A                      | N/A                     |  |  |
| 1   | 1                     | First Floor Hallway                                   | N/A                                     | Plaster Ceiling            |                         | NAD                                      | 1518                  | SF       | 0                   | SF       |                              |  |  | N/A                         | N/A                      | N/A                     |  |  |
| 1   | 1                     | First Floor Hallway                                   | N/A                                     | Plaster Walls              |                         | NAD                                      | 3036                  | SF       | 0                   | SF       |                              |  |  | N/A                         | N/A                      | N/A                     |  |  |
| 1   | 1                     | First Floor Hallway                                   | N/A                                     | Cement Floor               |                         | Non Suspect ACM                          | 726                   | SF       | 0                   | SF       |                              |  |  | N/A                         | N/A                      | N/A                     |  |  |
| 1   | 1                     | First Floor Hallway                                   | N/A                                     | Marble Walls               |                         | Non Suspect ACM                          | 726                   | SF       | 0                   | SF       |                              |  |  | N/A                         | N/A                      | N/A                     |  |  |
| 1   | 1                     | First Floor Hallway                                   | N/A                                     | Plaster Ceiling            |                         | NAD                                      | 726                   | SF       | 0                   | SF       |                              |  |  | N/A                         | N/A                      | N/A                     |  |  |
| 1   | 1                     | First Floor Hallway                                   | N/A                                     | Plaster Walls              |                         | NAD                                      | 1452                  | SF       | 0                   | SF       |                              |  |  | N/A                         | N/A                      | N/A                     |  |  |
| 1   | 1                     | Custodial Closet adjacent to Classroom 101 in Hallway | N/A                                     | Cement Floor               |                         | Non Suspect ACM                          | 60                    | SF       | 0                   | SF       |                              |  |  | N/A                         | N/A                      | N/A                     |  |  |
| 1   | 1                     | Custodial Closet adjacent to Classroom 101 in Hallway | N/A                                     | Plaster Ceiling            |                         | NAD                                      | 60                    | SF       | 2                   | SF       |                              |  |  | N/A                         | N/A                      | N/A                     |  |  |
| 1   | 1                     | Custodial Closet adjacent to Classroom 101 in Hallway | N/A                                     | Plaster Walls              |                         | NAD                                      | 180                   | SF       | 0                   | SF       |                              |  |  | N/A                         | N/A                      | N/A                     |  |  |
| 1   | 1                     | Custodial Closet adjacent to Classroom 101 in Hallway | N/A                                     | Pipe Fitting Insulation    |                         | NAD                                      | 8                     | EA       | 0                   | EA       |                              |  |  | N/A                         | N/A                      | N/A                     |  |  |
| 1   | 1                     | Custodial Closet adjacent to Classroom 101 in Hallway | T                                       | Pipe Insulation 2-6 inch   | 7220/01/02/11           | Confirmed                                | 20                    | LF       | 0                   | LF       |                              |  |  | 1                           | No                       | 1/D                     |  |  |
| 1   | 2                     | Classroom 201   | M                                       | Blackboard Glue Dots       | 7220/01/02/ACER/SM/2600 | Assumed                                  | 3                     | EA       | 0                   | EA       |                              |  |  | 1                           | No                       | 1/D                     |  |  |
| 1   | 2                     | Classroom 201   | T                                       | Pipe Insulation 2-6 inch   | 7220/01/02/11           | Confirmed                                | 58                    | LF       | 0                   | LF       |                              |  |  | 1                           | No                       | 1/D                     |  |  |
| 1   | 2                     | Classroom 201   | N/A                                     | Plaster Ceiling            |                         | NAD                                      | 928                   | SF       | 0                   | SF       |                              |  |  | N/A                         | N/A                      | N/A                     |  |  |
| 1   | 2                     | Classroom 201   | N/A                                     | Plaster Walls              |                         | NAD                                      | 1856                  | SF       | 0                   | SF       |                              |  |  | N/A                         | N/A                      | N/A                     |  |  |
| 1   | 2                     | Classroom 201   | N/A                                     | Wood Floor                 |                         | Non Suspect ACM                          | 928                   | SF       | 0                   | SF       |                              |  |  | N/A                         | N/A                      | N/A                     |  |  |
| 1   | 2                     | Classroom 201 Closet                                  | N/A                                     | Plaster Ceiling            |                         | NAD                                      | 192                   | SF       | 0                   | SF       |                              |  |  | N/A                         | N/A                      | N/A                     |  |  |
| 1   | 2                     | Classroom 201 Closet                                  | N/A                                     | Plaster Walls              |                         | NAD                                      | 384                   | SF       | 0                   | SF       |                              |  |  | N/A                         | N/A                      | N/A                     |  |  |
| 1   | 2                     | Classroom 201 Closet                                  | N/A                                     | Wood Floor                 |                         | Non Suspect ACM                          | 192                   | SF       | 0                   | SF       |                              |  |  | N/A                         | N/A                      | N/A                     |  |  |
| 1   | 2                     | Classroom 201 Closet                                  | X                                       | X                          |                         | X  | X                     | X        | 0                   | X        |                              | No Access  |  | X                           | X                        | X                       |  |  |
| 1   | 2                     | Hallway Closet Adj. to Classroom 201                  | N/A                                     | Pipe Fitting Insulation    |                         | NAD                                      | 8                     | EA       | 2                   | EA       |                              |  |  | N/A                         | N/A                      | N/A                     |  |  |
| 1   | 2                     | Classroom 202   | M                                       | Blackboard Glue Dots       | 7220/01/02/ACER/SM/2600 | Assumed                                  | 3                     | EA       | 0                   | EA       |                              |  |  | 1                           | No                       | 1/D                     |  |  |
| 1   | 2                     | Classroom 202   | T                                       | Pipe Insulation 2-6 inch   | 7220/01/02/11           | Confirmed                                | 30                    | LF       | 0                   | LF       |                              |  |  | 1                           | No                       | 1/D                     |  |  |
| 1   | 2                     | Classroom 202   | N/A                                     | Plaster Ceiling            |                         | NAD                                      | 870                   | SF       | 0                   | SF       |                              |  |  | N/A                         | N/A                      | N/A                     |  |  |
| 1   | 2                     | Classroom 202   | N/A                                     | Plaster Walls              |                         | NAD                                      | 1740                  | SF       | 0                   | SF       |                              |  |  | N/A                         | N/A                      | N/A                     |  |  |
| 1   | 2                     | Classroom 202   | N/A                                     | Wood Floor                 |                         | Non Suspect ACM                          | 870                   | SF       | 0                   | SF       |                              |  |  | N/A                         | N/A                      | N/A                     |  |  |
| 1   | 2                     | Classroom 202 Closet                                  | N/A                                     | Plaster Ceiling            |                         | NAD                                      | 180                   | SF       | 0                   | SF       |                              |  |  | N/A                         | N/A                      | N/A                     |  |  |
| 1   | 2                     | Classroom 202 Closet                                  | N/A                                     | Plaster Walls              |                         | NAD                                      | 360                   | SF       | 0                   | SF       |                              |  |  | N/A                         | N/A                      | N/A                     |  |  |
| 1   | 2                     | Classroom 202 Closet                                  | N/A                                     | Wood Floor                 |                         | Non Suspect ACM                          | 180                   | SF       | 0                   | SF       |                              |  |  | N/A                         | N/A                      | N/A                     |  |  |
| 1   | 2                     | Classroom 201   | N/A                                     | Pipe Fitting Insulation    |                         | NAD                                      | 16                    | EA       | 0                   | EA       |                              |  |  | N/A                         | N/A                      | N/A                     |  |  |

# 7220 Carnell ES 2015 2016 AHERA Three-Year Report.xls

| School District of Philadelphia               |                       |  | AHERA Three-Year Reinspection 2015-2016<br>Room by Room Location Log Report |                                 |                         |  |                       |    |    |    |                     |    |    |    |                              | Reinspection Date: October 21-26, 2015 |                                 |                             |                          |                         |  |
|---|-----------------------|--|---|---------------------------------|-------------------------|--|-----------------------|----|----|----|---------------------|----|----|----|------------------------------|--|---------------------------------|-----------------------------|--------------------------|-------------------------|--|
| Laura H. Carnell Elementary School            |                       |  |   |                                 |                         |  |                       |    |    |    |                     |    |    |    |                              | Building Inspector: Scott Magee        |                                 |                             |                          |                         |  |
| 1100 Devereaux Avenue, Philadelphia, PA 19111 |                       |  |   |                                 |                         |  |                       |    |    |    |                     |    |    |    |                              | Number: 70016699C                      |                                 |                             |                          |                         |  |
| ULCS# 7220                                    |                       |  |   |                                 |                         |  |                       |    |    |    |                     |    |    |    |                              | Management Planner: Megan Vala         |                                 |                             |                          |                         |  |
| Year Built: 1931                              |                       |  |   |                                 |                         |  |                       |    |    |    |                     |    |    |    |                              | Number: 740728                         |                                 |                             |                          |                         |  |
| E<br>l<br>e<br>m<br>e<br>n<br>t               | F<br>l<br>o<br>o<br>r | On-Site Room Name                        | System Affected   | Material Description            | HID#                    | Confirmed/Assumed/NAD<br>Non Suspect ACM | Amount of<br>Material | SF | LF | EA | Amount of<br>Damage | SF | LF | EA | Color<br>required for<br>VAT | Comments/Description/Notes             | Attic Crawl<br>Space<br>Ranking | Damage<br>Potential<br>(DP) | Newly<br>Friable<br>(NF) | Response<br>Action (RA) |  |
| 1   | 2                     | Classroom 203                            | T   | Pipe Insulation 2-6 inch        | 7220/01/02/11           | Confirmed                                | 60                    | LF | 0  | LF |                     |    |    |    |                              |  |                                 | 1                           | No                       | 1/D                     |  |
| 1   | 2                     | Classroom 203                            | N/A   | Plaster Ceiling                 |                         | NAD                                      | 928                   | SF | 0  | SF |                     |    |    |    |                              |  |                                 | N/A                         | N/A                      | N/A                     |  |
| 1   | 2                     | Classroom 203                            | N/A   | Plaster Walls                   |                         | NAD                                      | 1856                  | SF | 0  | SF |                     |    |    |    |                              |  |                                 | N/A                         | N/A                      | N/A                     |  |
| 1   | 2                     | Classroom 203                            | N/A   | Wood Floor                      |                         | Non Suspect ACM                          | 1856                  | SF | 0  | SF |                     |    |    |    |                              |  |                                 | N/A                         | N/A                      | N/A                     |  |
| 1   | 2                     | Classroom 203                            | N/A   | Pipe Fitting Insulation         |                         | NAD                                      | 16                    | EA | 0  | EA |                     |    |    |    |                              |  |                                 | N/A                         | N/A                      | N/A                     |  |
| 1   | 2                     | Classroom 203 Closet                     | N/A   | Plaster Ceiling                 |                         | NAD                                      | 228                   | SF | 0  | SF |                     |    |    |    |                              |  |                                 | N/A                         | N/A                      | N/A                     |  |
| 1   | 2                     | Classroom 203 Closet                     | N/A   | Plaster Walls                   |                         | NAD                                      | 456                   | SF | 0  | SF |                     |    |    |    |                              |  |                                 | N/A                         | N/A                      | N/A                     |  |
| 1   | 2                     | Classroom 203 Closet                     | N/A   | Wood Floor                      |                         | Non Suspect ACM                          | 228                   | SF | 0  | SF |                     |    |    |    |                              |  |                                 | N/A                         | N/A                      | N/A                     |  |
| 1   | 2                     | IMC Library                              | N/A   | Fiberglass Ceiling Tile 2' x 4' |                         | Non Suspect ACM                          | 2262                  | SF | 0  | SF |                     |    |    |    |                              |  |                                 | N/A                         | N/A                      | N/A                     |  |
| 1   | 2                     | IMC Library                              | N/A   | Fiberglass Pipe Insulation      |                         | Non Suspect ACM                          | 12                    | LF | 0  | LF |                     |    |    |    |                              |  |                                 | N/A                         | N/A                      | N/A                     |  |
| 1   | 2                     | IMC Library                              | M   | Floor Tile VAT 12" x 12"        | 7220/01/02/0RR          | Assumed                                  | 2262                  | SF | 0  | SF | Brown               |    |    |    |                              |  |                                 | 1                           | No                       | 1/D                     |  |
| 1   | 2                     | IMC Library                              | T   | Pipe Insulation 2-6 inch        | 7220/01/02/11           | Confirmed                                | 18                    | LF | 0  | LF |                     |    |    |    |                              |  |                                 | 1                           | No                       | 1/D                     |  |
| 1   | 2                     | IMC Library                              | N/A   | Plaster Ceiling                 |                         | NAD                                      | 2262                  | SF | 0  | SF |                     |    |    |    |                              |  |                                 | N/A                         | N/A                      | N/A                     |  |
| 1   | 2                     | IMC Library                              | N/A   | Plaster Walls                   |                         | NAD                                      | 4524                  | SF | 0  | SF |                     |    |    |    |                              |  |                                 | N/A                         | N/A                      | N/A                     |  |
| 1   | 2                     | IMC Library                              | N/A   | Wood Floor                      |                         | Non Suspect ACM                          | 2262                  | SF | 0  | SF |                     |    |    |    |                              |  |                                 | N/A                         | N/A                      | N/A                     |  |
| 1   | 2                     | IMC Library Closet                       | N/A   | Fiberglass Ceiling Tile 2' x 4' |                         | Non Suspect ACM                          | 90                    | SF | 0  | SF |                     |    |    |    |                              |  |                                 | N/A                         | N/A                      | N/A                     |  |
| 1   | 2                     | IMC Library Closet                       | M   | Floor Tile VAT 12" x 12"        | 7220/01/02/0RR          | Assumed                                  | 90                    | SF | 0  | SF | Brown               |    |    |    |                              |  |                                 | 1                           | No                       | 1/D                     |  |
| 1   | 2                     | IMC Library Closet                       | N/A   | Plaster Ceiling                 |                         | NAD                                      | 90                    | SF | 0  | SF |                     |    |    |    |                              |  |                                 | N/A                         | N/A                      | N/A                     |  |
| 1   | 2                     | IMC Library Closet                       | N/A   | Plaster Walls                   |                         | NAD                                      | 180                   | SF | 0  | SF |                     |    |    |    |                              |  |                                 | N/A                         | N/A                      | N/A                     |  |
| 1   | 2                     | IMC Library Closet                       | N/A   | Wood Floor                      |                         | Non Suspect ACM                          | 90                    | SF | 0  | SF |                     |    |    |    |                              |  |                                 | N/A                         | N/A                      | N/A                     |  |
| 1   | 2                     | IMC Library Office (Dean's Office)       | M   | Floor Tile VAT 12" x 12"        | 7220/01/02/0RR          | Assumed                                  | 182                   | SF | 0  | SF | Brown               |    |    |    |                              |  |                                 | N/A                         | N/A                      | N/A                     |  |
| 1   | 2                     | IMC Library Office (Dean's Office)       | N/A   | Plaster Ceiling                 |                         | NAD                                      | 182                   | SF | 0  | SF |                     |    |    |    |                              |  |                                 | N/A                         | N/A                      | N/A                     |  |
| 1   | 2                     | IMC Library Office (Dean's Office)       | N/A   | Plaster Walls                   |                         | NAD                                      | 364                   | SF | 0  | SF |                     |    |    |    |                              |  |                                 | N/A                         | N/A                      | N/A                     |  |
| 1   | 2                     | IMC Library Office (Dean's Office)       | N/A   | Wood Floor                      |                         | Non Suspect ACM                          | 182                   | SF | 0  | SF |                     |    |    |    |                              |  |                                 | N/A                         | N/A                      | N/A                     |  |
| 1   | 2                     | Girl's Restroom                          | X   | X                               |                         | X  | X                     | X  | 0  | X  | No Access           |    |    |    |                              |  |                                 | X                           | X                        | X                       |  |
| 1   | 2                     | IMC Library Closet                       | M   | Floor Tile VAT 12" x 12"        | 7220/01/02/0RR          | Assumed                                  | 90                    | SF | 0  | SF | Brown               |    |    |    |                              |  |                                 | 1                           | No                       | 1/D                     |  |
| 1   | 2                     | IMC Library Closet                       | N/A   | Plaster Ceiling                 |                         | NAD                                      | 90                    | SF | 0  | SF |                     |    |    |    |                              |  |                                 | N/A                         | N/A                      | N/A                     |  |
| 1   | 2                     | IMC Library Closet                       | N/A   | Plaster Walls                   |                         | NAD                                      | 180                   | SF | 0  | SF |                     |    |    |    |                              |  |                                 | N/A                         | N/A                      | N/A                     |  |
| 1   | 2                     | IMC Library Closet                       | N/A   | Wood Floor                      |                         | Non Suspect ACM                          | 90                    | SF | 0  | SF |                     |    |    |    |                              |  |                                 | N/A                         | N/A                      | N/A                     |  |
| 1   | 2                     | IMC Library Office                       | N/A   | Fiberglass Ceiling Tile 2' x 4' |                         | Non Suspect ACM                          | 180                   | SF | 0  | SF |                     |    |    |    |                              |  |                                 | N/A                         | N/A                      | N/A                     |  |
| 1   | 2                     | IMC Library Office                       | M   | Floor Tile VAT 12" x 12"        | 7220/01/02/0RR          | Assumed                                  | 180                   | SF | 0  | SF | Brown               |    |    |    |                              |  |                                 | 1                           | No                       | 1/D                     |  |
| 1   | 2                     | IMC Library Office                       | T   | Pipe Insulation 2-6 inch        | 7220/01/02/11           | Confirmed                                | 6                     | LF | 0  | LF |                     |    |    |    |                              |  |                                 | 1                           | No                       | 1/D                     |  |
| 1   | 2                     | IMC Library Office                       | N/A   | Plaster Ceiling                 |                         | NAD                                      | 180                   | SF | 0  | SF |                     |    |    |    |                              |  |                                 | N/A                         | N/A                      | N/A                     |  |
| 1   | 2                     | IMC Library Office                       | N/A   | Plaster Walls                   |                         | NAD                                      | 360                   | SF | 0  | SF |                     |    |    |    |                              |  |                                 | N/A                         | N/A                      | N/A                     |  |
| 1   | 2                     | IMC Library Office                       | N/A   | Wood Floor                      |                         | Non Suspect ACM                          | 180                   | SF | 0  | SF |                     |    |    |    |                              |  |                                 | N/A                         | N/A                      | N/A                     |  |
| 1   | 2                     | Classroom 206                            | N/A   | Fiberglass Pipe Insulation      |                         | Non Suspect ACM                          | 10                    | LF | 0  | LF |                     |    |    |    |                              |  |                                 | N/A                         | N/A                      | N/A                     |  |
| 1   | 2                     | Classroom 206                            | T   | Pipe Insulation 2-6 inch        | 7220/01/02/11           | Confirmed                                | 6                     | LF | 0  | LF |                     |    |    |    |                              |  |                                 | 1                           | No                       | 1/D                     |  |
| 1   | 2                     | Classroom 206                            | N/A   | Plaster Ceiling                 |                         | NAD                                      | 870                   | SF | 0  | SF |                     |    |    |    |                              |  |                                 | N/A                         | N/A                      | N/A                     |  |
| 1   | 2                     | Classroom 206                            | N/A   | Plaster Walls                   |                         | NAD                                      | 1740                  | SF | 0  | SF |                     |    |    |    |                              |  |                                 | N/A                         | N/A                      | N/A                     |  |
| 1   | 2                     | Classroom 206                            | N/A   | Wood Floor                      |                         | Non Suspect ACM                          | 870                   | SF | 0  | SF |                     |    |    |    |                              |  |                                 | N/A                         | N/A                      | N/A                     |  |
| 1   | 2                     | Classroom 206 Closet                     | N/A   | Plaster Ceiling                 |                         | NAD                                      | 150                   | SF | 0  | SF |                     |    |    |    |                              |  |                                 | N/A                         | N/A                      | N/A                     |  |
| 1   | 2                     | Classroom 206 Closet                     | N/A   | Plaster Walls                   |                         | NAD                                      | 300                   | SF | 0  | SF |                     |    |    |    |                              |  |                                 | N/A                         | N/A                      | N/A                     |  |
| 1   | 2                     | Classroom 206 Closet                     | N/A   | Wood Floor                      |                         | Non Suspect ACM                          | 150                   | SF | 0  | SF |                     |    |    |    |                              |  |                                 | N/A                         | N/A                      | N/A                     |  |
| 1   | 2                     | Classroom 207                            | M   | Blackboard Glue Dots            | 7220/01/02/ACER/SM/2600 | Assumed                                  | 2                     | EA | 0  | EA |                     |    |    |    |                              |  |                                 | 1                           | No                       | 1/D                     |  |
| 1   | 2                     | Classroom 207                            | N/A   | Fiberglass Pipe Insulation      |                         | Non Suspect ACM                          | 12                    | LF | 0  | LF |                     |    |    |    |                              |  |                                 | N/A                         | N/A                      | N/A                     |  |
| 1   | 2                     | Classroom 202                            | N/A   | Pipe Fitting Insulation         |                         | NAD                                      | 8                     | EA | 0  | EA |                     |    |    |    |                              |  |                                 | N/A                         | N/A                      | N/A                     |  |
| 1   | 2                     | Classroom 207                            | T   | Pipe Insulation 2-6 inch        | 7220/01/02/11           | Confirmed                                | 8                     | LF | 0  | LF |                     |    |    |    |                              |  |                                 | 1                           | No                       | 1/D                     |  |
| 1   | 2                     | Classroom 207                            | N/A   | Plaster Ceiling                 |                         | NAD                                      | 870                   | SF | 0  | SF |                     |    |    |    |                              |  |                                 | N/A                         | N/A                      | N/A                     |  |
| 1   | 2                     | Classroom 207                            | N/A   | Plaster Walls                   |                         | NAD                                      | 1740                  | SF | 0  | SF |                     |    |    |    |                              |  |                                 | N/A                         | N/A                      | N/A                     |  |
| 1   | 2                     | Classroom 207                            | N/A   | Wood Floor                      |                         | Non Suspect ACM                          | 870                   | SF | 0  | SF |                     |    |    |    |                              |  |                                 | N/A                         | N/A                      | N/A                     |  |
| 1   | 2                     | Classroom 207                            | N/A   | Pipe Fitting Insulation         |                         | NAD                                      | 6                     | EA | 0  | EA |                     |    |    |    |                              |  |                                 | N/A                         | N/A                      | N/A                     |  |
| 1   | 2                     | Classroom 207 Closet                     | N/A   | Pipe Fitting Insulation         |                         | NAD                                      | 2                     | EA | 0  | EA |                     |    |    |    |                              |  |                                 | N/A                         | N/A                      | N/A                     |  |
| 1   | 2                     | Classroom 207 Closet                     | N/A   | Fiberglass Pipe Insulation      |                         | Non Suspect ACM                          | 6                     | LF | 0  | LF |                     |    |    |    |                              |  |                                 | N/A                         | N/A                      | N/A                     |  |
| 1   | 2                     | Classroom 207 Closet                     | T   | Pipe Insulation 2-6 inch        | 7220/01/02/11           | Confirmed                                | 31                    | LF | 0  | LF |                     |    |    |    |                              |  |                                 | 1                           | No                       | 1/D                     |  |
| 1   | 2                     | Classroom 207 Closet                     | N/A   | Plaster Ceiling                 |                         | NAD                                      | 150                   | SF | 0  | SF |                     |    |    |    |                              |  |                                 | N/A                         | N/A                      | N/A                     |  |
| 1   | 2                     | Classroom 207 Closet                     | N/A   | Plaster Walls                   |                         | NAD                                      | 300                   | SF | 0  | SF |                     |    |    |    |                              |  |                                 | N/A                         | N/A                      | N/A                     |  |
| 1   | 2                     | Classroom 207 Closet                     | N/A   | Wood Floor                      |                         | Non Suspect ACM                          | 150                   | SF | 0  | SF |                     |    |    |    |                              |  |                                 | N/A                         | N/A                      | N/A                     |  |
| 1   | 2                     | Storage Closet across from Classroom 207 | X   | X                               |                         | X  | X                     | X  | 0  | X  | No Access           |    |    |    |                              |  |                                 | X                           | X                        | X                       |  |
| 1   | 2                     | Storage Closet across from Classroom 207 | X   | X                               |                         | X  | X                     | X  | 0  | X  | No Access           |    |    |    |                              |  |                                 | X                           | X                        | X                       |  |
| 1   | 2                     | Boy's Restroom                           | N/A   | Cement Floor                    |                         | Non Suspect ACM                          | 175                   | SF | 0  | SF |                     |    |    |    |                              |  |                                 | N/A                         | N/A                      | N/A                     |  |
| 1   | 2                     | Boy's Restroom                           | N/A   | Fiberglass Pipe Insulation      |                         | Non Suspect ACM                          | 30                    | LF | 0  | LF |                     |    |    |    |                              |  |                                 | N/A                         | N/A                      | N/A                     |  |
| 1   | 2                     | Boy's Restroom                           | N/A   | Marble Walls                    |                         | Non Suspect ACM                          | 195                   | SF | 0  | SF |                     |    |    |    |                              |  |                                 | N/A                         | N/A                      | N/A                     |  |
| 1   | 2                     | Boy's Restroom                           | N/A   | Plaster Ceiling                 |                         | NAD                                      | 175                   | SF | 0  | SF |                     |    |    |    |                              |  |                                 | N/A                         | N/A                      | N/A                     |  |
| 1   | 2                     | Boy's Restroom                           | N/A   | Plaster Walls                   |                         | NAD                                      | 350                   | SF | 0  | SF |                     |    |    |    |                              |  |                                 | N/A                         | N/A                      | N/A                     |  |
| 1   | 2                     | Classroom 208                            | T   | Pipe Insulation 2-6 inch        | 7220/01/02/11           | Confirmed                                | 18                    | LF | 0  | LF |                     |    |    |    |                              |  |                                 | 1                           | No                       | 1/D                     |  |
| 1   | 2                     | Classroom 208                            | N/A   | Plaster Ceiling                 |                         | NAD                                      | 928                   | SF | 0  | SF |                     |    |    |    |                              |  |                                 | N/A                         | N/A                      | N/A                     |  |
| 1   | 2                     | Classroom 208                            | N/A   | Plaster Walls                   |                         | NAD                                      | 1856                  | SF | 0  | SF |                     |    |    |    |                              |  |                                 | N/A                         | N/A                      | N/A                     |  |
| 1   | 2                     | Classroom 208                            | N/A   | Wood Floor                      |                         | Non Suspect ACM                          | 928                   | SF | 0  | SF |                     |    |    |    |                              |  |                                 | N/A                         | N/A                      | N/A                     |  |
| 1   | 2                     | Classroom 208 Closet                     | N/A   | Plaster Ceiling                 |                         | NAD                                      | 228                   | SF | 0  | SF |                     |    |    |    |                              |  |                                 | N/A                         | N/A                      | N/A                     |  |
| 1   | 2                     | Classroom 208 Closet                     | N/A   | Plaster Walls                   |                         | NAD                                      | 456                   | SF | 0  | SF |                     |    |    |    |                              |  |                                 | N/A                         | N/A                      | N/A                     |  |
| 1   | 2                     | Classroom 208 Closet                     | N/A   | Wood Floor                      |                         | Non Suspect ACM                          | 228                   | SF | 0  | SF |                     |    |    |    |                              |  |                                 | N/A                         | N/A                      | N/A                     |  |
| 1   | 2                     | Classroom 208 Closet                     | T   | Pipe Insulation 2-6 inch        | 7220/01/02/11           | Confirmed                                | 13                    | LF | 0  | LF |                     |    |    |    |                              |  |                                 | 1                           | No                       | 1/D                     |  |
| 1   | 2                     | Classroom 208 Closet                     | N/A   | Plaster Ceiling                 |                         | NAD                                      | 54                    | SF | 0  | SF |                     |    |    |    |                              |  |                                 | N/A                         | N/A                      | N/A                     |  |
| 1   | 2                     | Classroom 208 Closet                     | N/A   | Plaster Walls                   |                         | NAD                                      | 108                   | SF | 3  | SF |                     |    |    |    |                              |  |                                 | N/A                         | N/A                      | N/A                     |  |
| 1   | 2                     | Classroom 208 Closet                     | N/A   | Wood Floor                      |                         | Non Suspect ACM                          | 54                    | SF | 0  | SF |                     |    |    |    |                              |  |                                 | N/A                         | N/A                      | N/A                     |  |
| 1   | 2                     | Classroom 209                            | N/A   | Fiberglass Pipe Insulation      |                         | Non Suspect ACM                          | 8                     | LF | 0  | LF |                     |    |    |    |                              |  |                                 | N/A                         | N/A                      | N/A                     |  |

# 7220 Carnell ES 2015 2016 AHERA Three-Year Report.xls

| School District of Philadelphia               |                       |  | AHERA Three-Year Reinspection 2015-2016 |                                 |                         |  |                       |          |    |                     |          |    |                              |  |                                 | Reinspection Date: October 21-26, 2015 |                          |                         |  |  |
|---|-----------------------|--|---|---------------------------------|-------------------------|--|-----------------------|----------|----|---------------------|----------|----|------------------------------|--|---------------------------------|--|--------------------------|-------------------------|--|--|
| Laura H. Carnell Elementary School            |                       |  | Room by Room Location Log Report        |                                 |                         |  |                       |          |    |                     |          |    |                              |  |                                 | Building Inspector: Scott Magee        |                          |                         |  |  |
| 1100 Devereaux Avenue, Philadelphia, PA 19111 |                       |  |   |                                 |                         |  |                       |          |    |                     |          |    |                              |  |                                 | Number: 70016699C                      |                          |                         |  |  |
| ULCS# 7220                                    |                       |  |   |                                 |                         |  |                       |          |    |                     |          |    |                              |  |                                 | Management Planner: Megan Vala         |                          |                         |  |  |
| Year Built: 1931                              |                       |  |   |                                 |                         |  |                       |          |    |                     |          |    |                              |  |                                 | Number: 740728                         |                          |                         |  |  |
| E<br>l<br>e<br>m<br>e<br>n<br>t               | F<br>l<br>o<br>o<br>r | On-Site Room Name                        | System Affected                         | Material Description            | HID#                    | Confirmed/Assumed/NAD<br>Non Suspect ACM | Amount of<br>Material | SF<br>LF | EA | Amount of<br>Damage | SF<br>LF | EA | Color<br>required for<br>VAT | Comments/Description/Notes                     | Attic Crawl<br>Space<br>Ranking | Damage<br>Potential<br>(DP)            | Newly<br>Friable<br>(NF) | Response<br>Action (RA) |  |  |
| 1   | 2                     | Classroom 209                            | T                                       | Pipe Insulation 2-6 inch        | 7220/01/02/11           | Confirmed                                | 4                     | LF       | 0  | LF                  |          |    |                              |  |                                 | 1                                      | No                       | 1/D                     |  |  |
| 1   | 2                     | Classroom 209                            | N/A                                     | Plaster Ceiling                 |                         | NAD                                      | 870                   | SF       | 0  | SF                  |          |    |                              |  |                                 | N/A                                    | N/A                      | N/A                     |  |  |
| 1   | 2                     | Classroom 209                            | N/A                                     | Plaster Walls                   |                         | NAD                                      | 1740                  | SF       | 2  | SF                  |          |    |                              |  |                                 | N/A                                    | N/A                      | N/A                     |  |  |
| 1   | 2                     | Classroom 209                            | N/A                                     | Wood Floor                      |                         | Non Suspect ACM                          | 870                   | SF       | 0  | SF                  |          |    |                              |  |                                 | N/A                                    | N/A                      | N/A                     |  |  |
| 1   | 2                     | Classroom 209 Closet                     | N/A                                     | Plaster Ceiling                 |                         | NAD                                      | 180                   | SF       | 0  | SF                  |          |    |                              |  |                                 | N/A                                    | N/A                      | N/A                     |  |  |
| 1   | 2                     | Classroom 209 Closet                     | N/A                                     | Plaster Walls                   |                         | NAD                                      | 360                   | SF       | 0  | SF                  |          |    |                              |  |                                 | N/A                                    | N/A                      | N/A                     |  |  |
| 1   | 2                     | Classroom 209 Closet                     | N/A                                     | Wood Floor                      |                         | Non Suspect ACM                          | 180                   | SF       | 0  | SF                  |          |    |                              |  |                                 | N/A                                    | N/A                      | N/A                     |  |  |
| 1   | 2                     | Computer Room                            | X                                       | X                               |                         | X  | X                     | X        | 0  | X                   |          |    |                              | No Access                                      |                                 | X                                      | X                        | X                       |  |  |
| 1   | 2                     | Nurse's Office                           | N/A                                     | Fiberglass Pipe Insulation      |                         | Non Suspect ACM                          | 5                     | LF       | 0  | LF                  |          |    |                              |  |                                 | N/A                                    | N/A                      | N/A                     |  |  |
| 1   | 2                     | Nurse's Office                           | M                                       | Floor Tile VAT 9" x 9"          | 7220/01/02/14           | Confirmed                                | 198                   | SF       | 0  | SF                  |          |    |                              |  |                                 | 1                                      | No                       | 1/D                     |  |  |
| 1   | 2                     | Nurse's Office                           | T                                       | Pipe Insulation 2-6 inch        | 7220/01/02/11           | Confirmed                                | 130                   | LF       | 0  | LF                  |          |    |                              |  |                                 | 1                                      | No                       | 1/D                     |  |  |
| 1   | 2                     | Nurse's Office                           | N/A                                     | Plaster Ceiling                 |                         | NAD                                      | 198                   | SF       | 0  | SF                  |          |    |                              |  |                                 | N/A                                    | N/A                      | N/A                     |  |  |
| 1   | 2                     | Nurse's Office                           | N/A                                     | Plaster Walls                   |                         | NAD                                      | 396                   | SF       | 0  | SF                  |          |    |                              |  |                                 | N/A                                    | N/A                      | N/A                     |  |  |
| 1   | 2                     | Nurse's Office                           | N/A                                     | Wood Floor                      |                         | Non Suspect ACM                          | 198                   | SF       | 0  | SF                  |          |    |                              |  |                                 | N/A                                    | N/A                      | N/A                     |  |  |
| 1   | 2                     | Nurse's Restroom                         | T                                       | Pipe Insulation 2-6 inch        | 7220/01/02/11           | Confirmed                                | 25                    | LF       | 0  | LF                  |          |    |                              |  |                                 | 1                                      | No                       | 1/D                     |  |  |
| 1   | 2                     | Nurse's Restroom                         | N/A                                     | Plaster Ceiling                 |                         | NAD                                      | 36                    | SF       | 0  | SF                  |          |    |                              |  |                                 | N/A                                    | N/A                      | N/A                     |  |  |
| 1   | 2                     | Nurse's Restroom                         | N/A                                     | Plaster Walls                   |                         | NAD                                      | 72                    | SF       | 0  | SF                  |          |    |                              |  |                                 | N/A                                    | N/A                      | N/A                     |  |  |
| 1   | 2                     | Nurse's Restroom                         | N/A                                     | Fiberglass Pipe Insulation      |                         | Non Suspect ACM                          | 25                    | LF       | 0  | LF                  |          |    |                              |  |                                 | N/A                                    | N/A                      | N/A                     |  |  |
| 1   | 2                     | Nurse's Restroom                         | M                                       | Floor Tile VAT 12" x 12"        | 7220/01/02/0RR          | Assumed                                  | 36                    | SF       | 0  | SF                  |          |    |                              | White  |                                 | 1                                      | No                       | 1/D                     |  |  |
| 1   | 2                     | Teacher's Lounge                         | M                                       | Floor Tile VAT 12" x 12"        | 7220/01/02/0RR          | Assumed                                  | 368                   | SF       | 0  | SF                  |          |    |                              | White  |                                 | 1                                      | No                       | 1/D                     |  |  |
| 1   | 2                     | Teacher's Lounge                         | N/A                                     | Plaster Ceiling                 |                         | NAD                                      | 368                   | SF       | 0  | SF                  |          |    |                              |  |                                 | N/A                                    | N/A                      | N/A                     |  |  |
| 1   | 2                     | Teacher's Lounge                         | N/A                                     | Plaster Walls                   |                         | NAD                                      | 736                   | SF       | 0  | SF                  |          |    |                              |  |                                 | N/A                                    | N/A                      | N/A                     |  |  |
| 1   | 2                     | Nurse's Office                           | N/A                                     | Pipe Fitting Insulation         |                         | NAD                                      | 23                    | EA       | 0  | EA                  |          |    |                              |  |                                 | N/A                                    | N/A                      | N/A                     |  |  |
| 1   | 2                     | Teacher's Lounge Closet                  | T                                       | Pipe Insulation 2-6 inch        | 7220/01/02/11           | Confirmed                                | 50                    | LF       | 0  | LF                  |          |    |                              |  |                                 | 1                                      | No                       | 1/D                     |  |  |
| 1   | 2                     | Teacher's Lounge Closet                  | N/A                                     | Plaster Ceiling                 |                         | NAD                                      | 84                    | SF       | 0  | SF                  |          |    |                              |  |                                 | N/A                                    | N/A                      | N/A                     |  |  |
| 1   | 2                     | Teacher's Lounge Closet                  | N/A                                     | Plaster Walls                   |                         | NAD                                      | 168                   | SF       | 0  | SF                  |          |    |                              |  |                                 | N/A                                    | N/A                      | N/A                     |  |  |
| 1   | 2                     | Teacher's Lounge Closet                  | M                                       | Floor Tile VAT 12" x 12"        | 7220/01/02/0RR          | Assumed                                  | 84                    | SF       | 0  | SF                  |          |    |                              | White  |                                 | 1                                      | No                       | 1/D                     |  |  |
| 1   | 2                     | Teacher's Lounge Closet                  | N/A                                     | Pipe Fitting Insulation         |                         | NAD                                      | 4                     | EA       | 0  | EA                  |          |    |                              |  |                                 | N/A                                    | N/A                      | N/A                     |  |  |
| 1   | 2                     | Teacher's Lounge Pipe Chase              | T                                       | Pipe Insulation > 6 inch        | 7220/01/02/010          | Confirmed                                | 50                    | LF       | 4  | LF                  |          |    |                              | Door should be locked until damage is repaired |                                 | 1                                      | Yes                      | 5/C                     |  |  |
| 1   | 2                     | Assistant Principal's Office             | X                                       | X                               |                         | X  | X                     | X        | 0  | X                   |          |    |                              | No Access                                      |                                 | X                                      | X                        | X                       |  |  |
| 1   | 2                     | Room inside Assistant Principal's Office | X                                       | X                               |                         | X  | X                     | X        | 0  | X                   |          |    |                              | No Access                                      |                                 | X                                      | X                        | X                       |  |  |
| 1   | 2                     | Second Floor Hallway                     | N/A                                     | Cement Floor                    |                         | Non Suspect ACM                          | 1350                  | SF       | 0  | SF                  |          |    |                              |  |                                 | N/A                                    | N/A                      | N/A                     |  |  |
| 1   | 2                     | Second Floor Hallway                     | N/A                                     | Marble Walls                    |                         | Non Suspect ACM                          | 1350                  | SF       | 0  | SF                  |          |    |                              |  |                                 | N/A                                    | N/A                      | N/A                     |  |  |
| 1   | 2                     | Second Floor Hallway                     | N/A                                     | Plaster Ceiling                 |                         | NAD                                      | 1350                  | SF       | 0  | SF                  |          |    |                              |  |                                 | N/A                                    | N/A                      | N/A                     |  |  |
| 1   | 2                     | Second Floor Hallway                     | N/A                                     | Plaster Walls                   |                         | NAD                                      | 2700                  | SF       | 0  | SF                  |          |    |                              |  |                                 | N/A                                    | N/A                      | N/A                     |  |  |
| 1   | 2                     | Second Floor Hallway                     | N/A                                     | Cement Floor                    |                         | Non Suspect ACM                          | 820                   | SF       | 0  | SF                  |          |    |                              |  |                                 | N/A                                    | N/A                      | N/A                     |  |  |
| 1   | 2                     | Second Floor Hallway                     | N/A                                     | Marble Walls                    |                         | Non Suspect ACM                          | 820                   | SF       | 0  | SF                  |          |    |                              |  |                                 | N/A                                    | N/A                      | N/A                     |  |  |
| 1   | 2                     | Nurse's Restroom                         | N/A                                     | Pipe Fitting Insulation         |                         | NAD                                      | 10                    | EA       | 0  | EA                  |          |    |                              |  |                                 | N/A                                    | N/A                      | N/A                     |  |  |
| 1   | 2                     | Second Floor Hallway                     | T                                       | Pipe Insulation 2-6 inch        | 7220/01/02/11           | Confirmed                                | 59                    | LF       | 0  | LF                  |          |    |                              |  |                                 | 1                                      | No                       | 1/D                     |  |  |
| 1   | 2                     | Second Floor Hallway                     | N/A                                     | Plaster Ceiling                 |                         | NAD                                      | 820                   | SF       | 0  | SF                  |          |    |                              |  |                                 | N/A                                    | N/A                      | N/A                     |  |  |
| 1   | 2                     | Second Floor Hallway                     | N/A                                     | Plaster Walls                   |                         | NAD                                      | 1640                  | SF       | 0  | SF                  |          |    |                              |  |                                 | N/A                                    | N/A                      | N/A                     |  |  |
| 1   | 2                     | Second Floor Hallway                     | N/A                                     | Pipe Fitting Insulation         |                         | NAD                                      | 12                    | EA       | 0  | EA                  |          |    |                              |  |                                 | N/A                                    | N/A                      | N/A                     |  |  |
| 1   | 2                     | Second Floor Hallway                     | N/A                                     | Cement Floor                    |                         | Non Suspect ACM                          | 650                   | SF       | 0  | SF                  |          |    |                              |  |                                 | N/A                                    | N/A                      | N/A                     |  |  |
| 1   | 2                     | Second Floor Hallway                     | N/A                                     | Marble Walls                    |                         | Non Suspect ACM                          | 650                   | SF       | 0  | SF                  |          |    |                              |  |                                 | N/A                                    | N/A                      | N/A                     |  |  |
| 1   | 2                     | Second Floor Hallway                     | N/A                                     | Plaster Ceiling                 |                         | NAD                                      | 650                   | SF       | 0  | SF                  |          |    |                              |  |                                 | N/A                                    | N/A                      | N/A                     |  |  |
| 1   | 2                     | Second Floor Hallway                     | N/A                                     | Plaster Walls                   |                         | NAD                                      | 1300                  | SF       | 0  | SF                  |          |    |                              |  |                                 | N/A                                    | N/A                      | N/A                     |  |  |
| 1   | 2                     | Hallway Closet adjacent to Classroom 201 | N/A                                     | Cement Floor                    |                         | Non Suspect ACM                          | 48                    | SF       | 0  | SF                  |          |    |                              |  |                                 | N/A                                    | N/A                      | N/A                     |  |  |
| 1   | 2                     | Hallway Closet adjacent to Classroom 201 | T                                       | Pipe Insulation 2-6 inch        | 7220/01/02/11           | Confirmed                                | 30                    | LF       | 0  | LF                  |          |    |                              |  |                                 | 1                                      | No                       | 1/D                     |  |  |
| 1   | 2                     | Hallway Closet adjacent to Classroom 201 | N/A                                     | Plaster Ceiling                 |                         | NAD                                      | 48                    | SF       | 0  | SF                  |          |    |                              |  |                                 | N/A                                    | N/A                      | N/A                     |  |  |
| 1   | 2                     | Hallway Closet adjacent to Classroom 201 | N/A                                     | Plaster Walls                   |                         | NAD                                      | 96                    | SF       | 0  | SF                  |          |    |                              |  |                                 | N/A                                    | N/A                      | N/A                     |  |  |
| 1   | 2                     | Entrance Stairs Second Floor             | N/A                                     | Marble Walls                    |                         | Non Suspect ACM                          | 264                   | SF       | 0  | SF                  |          |    |                              |  |                                 | N/A                                    | N/A                      | N/A                     |  |  |
| 1   | 2                     | Entrance Stairs Second Floor             | N/A                                     | Plaster Walls                   |                         | NAD                                      | 528                   | SF       | 0  | SF                  |          |    |                              |  |                                 | N/A                                    | N/A                      | N/A                     |  |  |
| 1   | 2                     | Entrance Stairs Second Floor             | N/A                                     | Plaster Walls                   |                         | NAD                                      | 528                   | SF       | 0  | SF                  |          |    |                              |  |                                 | N/A                                    | N/A                      | N/A                     |  |  |
| 1   | 2                     | Stairs Second Floor                      | N/A                                     | Marble Walls                    |                         | Non Suspect ACM                          | 341                   | SF       | 0  | SF                  |          |    |                              |  |                                 | N/A                                    | N/A                      | N/A                     |  |  |
| 1   | 2                     | Stairs Second Floor                      | N/A                                     | Plaster Ceiling                 |                         | NAD                                      | 341                   | SF       | 10 | SF                  |          |    |                              |  |                                 | N/A                                    | N/A                      | N/A                     |  |  |
| 1   | 2                     | Stairs Second Floor                      | N/A                                     | Plaster Walls                   |                         | NAD                                      | 682                   | SF       | 0  | SF                  |          |    |                              |  |                                 | N/A                                    | N/A                      | N/A                     |  |  |
| 1   | 3                     | Classroom 301                            | M                                       | Blackboard Glue Dots            | 7220/01/03/ACER/SM/2600 | Assumed                                  | 3                     | EA       | 0  | EA                  |          |    |                              |  |                                 | 1                                      | No                       | 1/D                     |  |  |
| 1   | 3                     | Classroom 301                            | T                                       | Pipe Insulation 2-6 inch        | 7220/01/03/18           | Confirmed                                | 36                    | LF       | 0  | LF                  |          |    |                              |  |                                 | 1                                      | No                       | 1/D                     |  |  |
| 1   | 3                     | Classroom 301                            | N/A                                     | Plaster Ceiling                 |                         | NAD                                      | 928                   | SF       | 0  | SF                  |          |    |                              |  |                                 | N/A                                    | N/A                      | N/A                     |  |  |
| 1   | 3                     | Classroom 301                            | N/A                                     | Plaster Walls                   |                         | NAD                                      | 1856                  | SF       | 0  | SF                  |          |    |                              |  |                                 | N/A                                    | N/A                      | N/A                     |  |  |
| 1   | 3                     | Classroom 301                            | N/A                                     | Wood Floor                      |                         | Non Suspect ACM                          | 928                   | SF       | 0  | SF                  |          |    |                              |  |                                 | N/A                                    | N/A                      | N/A                     |  |  |
| 1   | 3                     | Classroom 301 Closet                     | N/A                                     | Plaster Ceiling                 |                         | NAD                                      | 168                   | SF       | 0  | SF                  |          |    |                              |  |                                 | N/A                                    | N/A                      | N/A                     |  |  |
| 1   | 3                     | Classroom 301 Closet                     | N/A                                     | Plaster Walls                   |                         | NAD                                      | 336                   | SF       | 0  | SF                  |          |    |                              |  |                                 | N/A                                    | N/A                      | N/A                     |  |  |
| 1   | 3                     | Classroom 301 Closet                     | N/A                                     | Wood Floor                      |                         | Non Suspect ACM                          | 168                   | SF       | 0  | SF                  |          |    |                              |  |                                 | N/A                                    | N/A                      | N/A                     |  |  |
| 1   | 3                     | Classroom 301 Closet                     | T                                       | Pipe Insulation 2-6 inch        | 7220/01/03/18           | Confirmed                                | 12                    | LF       | 0  | LF                  |          |    |                              |  |                                 | 1                                      | No                       | 1/D                     |  |  |
| 1   | 3                     | Classroom 301 Closet                     | N/A                                     | Plaster Ceiling                 |                         | NAD                                      | 24                    | SF       | 0  | SF                  |          |    |                              |  |                                 | N/A                                    | N/A                      | N/A                     |  |  |
| 1   | 3                     | Classroom 301 Closet                     | N/A                                     | Plaster Walls                   |                         | NAD                                      | 48                    | SF       | 0  | SF                  |          |    |                              |  |                                 | N/A                                    | N/A                      | N/A                     |  |  |
| 1   | 3                     | Classroom 301 Closet                     | N/A                                     | Wood Floor                      |                         | Non Suspect ACM                          | 24                    | SF       | 0  | SF                  |          |    |                              |  |                                 | N/A                                    | N/A                      | N/A                     |  |  |
| 1   | 3                     | Classroom 302                            | X                                       | X                               |                         | X  | X                     | X        | 0  | X                   |          |    |                              | No Access                                      |                                 | X                                      | X                        | X                       |  |  |
| 1   | 3                     | Classroom 302 Closet                     | X                                       | X                               |                         | X  | X                     | X        | 0  | X                   |          |    |                              | No Access                                      |                                 | X                                      | X                        | X                       |  |  |
| 1   | 3                     | Classroom 303                            | M                                       | Blackboard Glue Dots            | 7220/01/03/ACER/SM/2600 | Assumed                                  | 2                     | EA       | 0  | EA                  |          |    |                              |  |                                 | 1                                      | No                       | 1/D                     |  |  |
| 1   | 3                     | Classroom 303                            | T                                       | Pipe Insulation 2-6 inch        | 7220/01/03/18           | Confirmed                                | 24                    | LF       | 0  | LF                  |          |    |                              |  |                                 | 1                                      | No                       | 1/D                     |  |  |
| 1   | 3                     | Classroom 303                            | N/A                                     | Plaster Ceiling                 |                         | NAD                                      | 928                   | SF       | 0  | SF                  |          |    |                              |  |                                 | N/A                                    | N/A                      | N/A                     |  |  |
| 1   | 3                     | Classroom 303                            | N/A                                     | Plaster Walls                   |                         | NAD                                      | 1856                  | SF       | 5  | SF                  |          |    |                              |  |                                 | N/A                                    | N/A                      | N/A                     |  |  |
| 1   | 3                     | Classroom 303                            | N/A                                     | Wood Floor                      |                         | Non Suspect ACM                          | 928                   | SF       | 0  | SF                  |          |    |                              |  |                                 | N/A                                    | N/A                      | N/A                     |  |  |
| 1   | 3                     | Classroom 303 Closet                     | N/A                                     | Fiberglass Ceiling Tile 2' x 4' |                         | Non Suspect ACM                          | 228                   | SF       | 0  | SF                  |          |    |                              |  |                                 | N/A                                    | N/A                      | N/A                     |  |  |

# 7220 Carnell ES 2015 2016 AHERA Three-Year Report.xls

| School District of Philadelphia               |                       |                      | AHERA Three-Year Reinspection 2015-2016 |                            |                         |  |                       |                |                     |                |                              |                            |                                 |                             |                          | Reinspection Date: October 21-26, 2015 |  |  |  |  |
|---|-----------------------|----------------------|---|----------------------------|-------------------------|--|-----------------------|----------------|---------------------|----------------|------------------------------|----------------------------|---------------------------------|-----------------------------|--------------------------|--|--|--|--|--|
| Laura H. Carnell Elementary School            |                       |                      | Room by Room Location Log Report        |                            |                         |  |                       |                |                     |                |                              |                            |                                 |                             |                          | Building Inspector: Scott Magee        |  |  |  |  |
| 1100 Devereaux Avenue, Philadelphia, PA 19111 |                       |                      |   |                            |                         |  |                       |                |                     |                |                              |                            |                                 |                             |                          | Number: 70016699C                      |  |  |  |  |
| ULCS# 7220                                    |                       |                      |   |                            |                         |  |                       |                |                     |                |                              |                            |                                 |                             |                          | Management Planner: Megan Vala         |  |  |  |  |
| Year Built: 1931                              |                       |                      |   |                            |                         |  |                       |                |                     |                |                              |                            |                                 |                             |                          | Number: 740728                         |  |  |  |  |
| E<br>l<br>e<br>m<br>e<br>n<br>t               | F<br>l<br>o<br>o<br>r | On-Site Room Name    | System Affected                         | Material Description       | HID#                    | Confirmed/Assumed/NAD<br>Non Suspect ACM | Amount of<br>Material | SF<br>LF<br>EA | Amount of<br>Damage | SF<br>LF<br>EA | Color<br>required for<br>VAT | Comments/Description/Notes | Attic Crawl<br>Space<br>Ranking | Damage<br>Potential<br>(DP) | Newly<br>Friable<br>(NF) | Response<br>Action (RA)                |  |  |  |  |
| 1   | 3                     | Classroom 303 Closet | N/A                                     | Plaster Ceiling            |                         | NAD                                      | 228                   | SF             | 5                   | SF             |                              |                            |                                 | N/A                         | N/A                      | N/A                                    |  |  |  |  |
| 1   | 3                     | Classroom 303 Closet | N/A                                     | Plaster Walls              |                         | NAD                                      | 456                   | SF             | 0                   | SF             |                              |                            |                                 | N/A                         | N/A                      | N/A                                    |  |  |  |  |
| 1   | 3                     | Classroom 303 Closet | N/A                                     | Wood Floor                 |                         | Non Suspect ACM                          | 228                   | SF             | 0                   | SF             |                              |                            |                                 | N/A                         | N/A                      | N/A                                    |  |  |  |  |
| 1   | 3                     | Girl's Restroom      | X                                       | X                          |                         | X  | X                     | X              | 0                   | X              |                              | No Access                  |                                 | X                           | X                        | X                                      |  |  |  |  |
| 1   | 3                     | Classroom 304        | M                                       | Blackboard Glue Dots       | 7220/01/03/ACER/SM/2600 | Assumed                                  | 2                     | EA             | 0                   | EA             |                              |                            |                                 | 1                           | No                       | 1/D                                    |  |  |  |  |
| 1   | 3                     | Classroom 304        | N/A                                     | Fiberglass Pipe Insulation |                         | Non Suspect ACM                          | 4                     | LF             | 1                   | LF             |                              |                            |                                 | N/A                         | N/A                      | N/A                                    |  |  |  |  |
| 1   | 3                     | Classroom 304        | T                                       | Pipe Insulation 2-6 inch   | 7220/01/03/18           | Confirmed                                | 6                     | LF             | 0                   | LF             |                              |                            |                                 | 1                           | No                       | 1/D                                    |  |  |  |  |
| 1   | 3                     | Classroom 304        | N/A                                     | Plaster Ceiling            |                         | NAD                                      | 870                   | SF             | 0                   | SF             |                              |                            |                                 | N/A                         | N/A                      | N/A                                    |  |  |  |  |
| 1   | 3                     | Classroom 304        | N/A                                     | Plaster Walls              |                         | NAD                                      | 1740                  | SF             | 0                   | SF             |                              |                            |                                 | N/A                         | N/A                      | N/A                                    |  |  |  |  |
| 1   | 3                     | Classroom 304        | N/A                                     | Wood Floor                 |                         | Non Suspect ACM                          | 870                   | SF             | 0                   | SF             |                              |                            |                                 | N/A                         | N/A                      | N/A                                    |  |  |  |  |
| 1   | 3                     | Classroom 304 Closet | N/A                                     | Plaster Ceiling            |                         | NAD                                      | 180                   | SF             | 0                   | SF             |                              |                            |                                 | N/A                         | N/A                      | N/A                                    |  |  |  |  |
| 1   | 3                     | Classroom 304 Closet | N/A                                     | Plaster Walls              |                         | NAD                                      | 360                   | SF             | 0                   | SF             |                              |                            |                                 | N/A                         | N/A                      | N/A                                    |  |  |  |  |
| 1   | 3                     | Classroom 304 Closet | N/A                                     | Wood Floor                 |                         | Non Suspect ACM                          | 180                   | SF             | 0                   | SF             |                              |                            |                                 | N/A                         | N/A                      | N/A                                    |  |  |  |  |
| 1   | 3                     | Classroom 304 Closet | N/A                                     | Plaster Ceiling            |                         | NAD                                      | 20                    | SF             | 0                   | SF             |                              |                            |                                 | N/A                         | N/A                      | N/A                                    |  |  |  |  |
| 1   | 3                     | Classroom 304 Closet | N/A                                     | Plaster Walls              |                         | NAD                                      | 40                    | SF             | 0                   | SF             |                              |                            |                                 | N/A                         | N/A                      | N/A                                    |  |  |  |  |
| 1   | 3                     | Classroom 304 Closet | N/A                                     | Wood Floor                 |                         | Non Suspect ACM                          | 20                    | SF             | 0                   | SF             |                              |                            |                                 | N/A                         | N/A                      | N/A                                    |  |  |  |  |
| 1   | 3                     | Classroom 305        | M                                       | Blackboard Glue Dots       | 7220/01/03/ACER/SM/2600 | Assumed                                  | 2                     | EA             | 0                   | EA             |                              |                            |                                 | 1                           | No                       | 1/D                                    |  |  |  |  |
| 1   | 3                     | Classroom 305        | N/A                                     | Fiberglass Pipe Insulation |                         | Non Suspect ACM                          | 4                     | LF             | 0                   | LF             |                              |                            |                                 | N/A                         | N/A                      | N/A                                    |  |  |  |  |
| 1   | 3                     | Classroom 305        | T                                       | Pipe Insulation 2-6 inch   | 7220/01/03/18           | Confirmed                                | 6                     | LF             | 0                   | LF             |                              |                            |                                 | 1                           | No                       | 1/D                                    |  |  |  |  |
| 1   | 3                     | Classroom 305        | N/A                                     | Plaster Ceiling            |                         | NAD                                      | 870                   | SF             | 0                   | SF             |                              |                            |                                 | N/A                         | N/A                      | N/A                                    |  |  |  |  |
| 1   | 3                     | Classroom 305        | N/A                                     | Plaster Walls              |                         | NAD                                      | 1740                  | SF             | 0                   | SF             |                              |                            |                                 | N/A                         | N/A                      | N/A                                    |  |  |  |  |
| 1   | 3                     | Classroom 305        | N/A                                     | Wood Floor                 |                         | Non Suspect ACM                          | 870                   | SF             | 0                   | SF             |                              |                            |                                 | N/A                         | N/A                      | N/A                                    |  |  |  |  |
| 1   | 3                     | Classroom 305 Closet | N/A                                     | Plaster Ceiling            |                         | NAD                                      | 180                   | SF             | 0                   | SF             |                              |                            |                                 | N/A                         | N/A                      | N/A                                    |  |  |  |  |
| 1   | 3                     | Classroom 305 Closet | N/A                                     | Plaster Walls              |                         | NAD                                      | 360                   | SF             | 0                   | SF             |                              |                            |                                 | N/A                         | N/A                      | N/A                                    |  |  |  |  |
| 1   | 3                     | Classroom 305 Closet | N/A                                     | Wood Floor                 |                         | Non Suspect ACM                          | 180                   | SF             | 0                   | SF             |                              |                            |                                 | N/A                         | N/A                      | N/A                                    |  |  |  |  |
| 1   | 3                     | Classroom 306        | M                                       | Blackboard Glue Dots       | 7220/01/03/ACER/SM/2600 | Assumed                                  | 1                     | EA             | 0                   | EA             |                              |                            |                                 | 1                           | No                       | 1/D                                    |  |  |  |  |
| 1   | 3                     | Classroom 306        | T                                       | Pipe Insulation 2-6 inch   | 7220/01/03/18           | Confirmed                                | 6                     | LF             | 0                   | LF             |                              |                            |                                 | 1                           | No                       | 1/D                                    |  |  |  |  |
| 1   | 3                     | Classroom 306        | N/A                                     | Plaster Ceiling            |                         | NAD                                      | 870                   | SF             | 0                   | SF             |                              |                            |                                 | N/A                         | N/A                      | N/A                                    |  |  |  |  |
| 1   | 3                     | Classroom 306        | N/A                                     | Plaster Walls              |                         | NAD                                      | 1740                  | SF             | 0                   | SF             |                              |                            |                                 | N/A                         | N/A                      | N/A                                    |  |  |  |  |
| 1   | 3                     | Classroom 306        | N/A                                     | Wood Floor                 |                         | Non Suspect ACM                          | 870                   | SF             | 0                   | SF             |                              |                            |                                 | N/A                         | N/A                      | N/A                                    |  |  |  |  |
| 1   | 3                     | Classroom 306 Closet | N/A                                     | Plaster Ceiling            |                         | NAD                                      | 180                   | SF             | 0                   | SF             |                              |                            |                                 | N/A                         | N/A                      | N/A                                    |  |  |  |  |
| 1   | 3                     | Classroom 306 Closet | N/A                                     | Plaster Walls              |                         | NAD                                      | 360                   | SF             | 0                   | SF             |                              |                            |                                 | N/A                         | N/A                      | N/A                                    |  |  |  |  |
| 1   | 3                     | Classroom 306 Closet | N/A                                     | Plaster Ceiling            |                         | NAD                                      | 20                    | SF             | 0                   | SF             |                              |                            |                                 | N/A                         | N/A                      | N/A                                    |  |  |  |  |
| 1   | 3                     | Classroom 306 Closet | N/A                                     | Plaster Walls              |                         | NAD                                      | 40                    | SF             | 0                   | SF             |                              |                            |                                 | N/A                         | N/A                      | N/A                                    |  |  |  |  |
| 1   | 3                     | Classroom 307        | M                                       | Blackboard Glue Dots       | 7220/01/03/ACER/SM/2600 | Assumed                                  | 1                     | EA             | 0                   | EA             |                              |                            |                                 | 1                           | No                       | 1/D                                    |  |  |  |  |
| 1   | 3                     | Classroom 307        | N/A                                     | Plaster Ceiling            |                         | NAD                                      | 870                   | SF             | 0                   | SF             |                              |                            |                                 | N/A                         | N/A                      | N/A                                    |  |  |  |  |
| 1   | 3                     | Classroom 307        | N/A                                     | Plaster Walls              |                         | NAD                                      | 1740                  | SF             | 0                   | SF             |                              |                            |                                 | N/A                         | N/A                      | N/A                                    |  |  |  |  |
| 1   | 3                     | Classroom 307        | N/A                                     | Wood Floor                 |                         | Non Suspect ACM                          | 870                   | SF             | 0                   | SF             |                              |                            |                                 | N/A                         | N/A                      | N/A                                    |  |  |  |  |
| 1   | 3                     | Classroom 307 Closet | N/A                                     | Plaster Ceiling            |                         | NAD                                      | 150                   | SF             | 0                   | SF             |                              |                            |                                 | N/A                         | N/A                      | N/A                                    |  |  |  |  |
| 1   | 3                     | Classroom 307 Closet | N/A                                     | Plaster Walls              |                         | NAD                                      | 300                   | SF             | 0                   | SF             |                              |                            |                                 | N/A                         | N/A                      | N/A                                    |  |  |  |  |
| 1   | 3                     | Classroom 307 Closet | X                                       | X                          |                         | X  | X                     | X              | 0                   | X              |                              | No Access                  |                                 | X                           | X                        | X                                      |  |  |  |  |
| 1   | 3                     | Boy's Restroom       | N/A                                     | Cement Floor               |                         | Non Suspect ACM                          | 210                   | SF             | 0                   | SF             |                              |                            |                                 | N/A                         | N/A                      | N/A                                    |  |  |  |  |
| 1   | 3                     | Boy's Restroom       | N/A                                     | Fiberglass Pipe Insulation |                         | Non Suspect ACM                          | 4                     | LF             | 0                   | LF             |                              |                            |                                 | N/A                         | N/A                      | N/A                                    |  |  |  |  |
| 1   | 3                     | Boy's Restroom       | N/A                                     | Marble Walls               |                         | Non Suspect ACM                          | 210                   | SF             | 0                   | SF             |                              |                            |                                 | N/A                         | N/A                      | N/A                                    |  |  |  |  |
| 1   | 3                     | Boy's Restroom       | N/A                                     | Plaster Ceiling            |                         | NAD                                      | 210                   | SF             | 0                   | SF             |                              |                            |                                 | N/A                         | N/A                      | N/A                                    |  |  |  |  |
| 1   | 3                     | Boy's Restroom       | N/A                                     | Plaster Walls              |                         | NAD                                      | 420                   | SF             | 0                   | SF             |                              |                            |                                 | N/A                         | N/A                      | N/A                                    |  |  |  |  |
| 1   | 3                     | Classroom 308        | M                                       | Blackboard Glue Dots       | 7220/01/03/ACER/SM/2600 | Assumed                                  | 3                     | EA             | 0                   | EA             |                              |                            |                                 | 1                           | No                       | 1/D                                    |  |  |  |  |
| 1   | 3                     | Classroom 308        | N/A                                     | Fiberglass Pipe Insulation |                         | Non Suspect ACM                          | 12                    | LF             | 0                   | LF             |                              |                            |                                 | N/A                         | N/A                      | N/A                                    |  |  |  |  |
| 1   | 3                     | Classroom 308        | N/A                                     | Plaster Ceiling            |                         | NAD                                      | 928                   | SF             | 0                   | SF             |                              |                            |                                 | N/A                         | N/A                      | N/A                                    |  |  |  |  |
| 1   | 3                     | Classroom 308        | N/A                                     | Plaster Walls              |                         | NAD                                      | 1856                  | SF             | 0                   | SF             |                              |                            |                                 | N/A                         | N/A                      | N/A                                    |  |  |  |  |
| 1   | 3                     | Classroom 308        | N/A                                     | Wood Floor                 |                         | Non Suspect ACM                          | 928                   | SF             | 0                   | SF             |                              |                            |                                 | N/A                         | N/A                      | N/A                                    |  |  |  |  |
| 1   | 3                     | Classroom 308 Closet | N/A                                     | Plaster Ceiling            |                         | NAD                                      | 228                   | SF             | 0                   | SF             |                              |                            |                                 | N/A                         | N/A                      | N/A                                    |  |  |  |  |
| 1   | 3                     | Classroom 308 Closet | N/A                                     | Plaster Walls              |                         | NAD                                      | 456                   | SF             | 0                   | SF             |                              |                            |                                 | N/A                         | N/A                      | N/A                                    |  |  |  |  |
| 1   | 3                     | Classroom 308 Closet | N/A                                     | Wood Floor                 |                         | Non Suspect ACM                          | 228                   | SF             | 0                   | SF             |                              |                            |                                 | N/A                         | N/A                      | N/A                                    |  |  |  |  |
| 1   | 3                     | Classroom 309        | M                                       | Blackboard Glue Dots       | 7220/01/03/ACER/SM/2600 | Assumed                                  | 3                     | EA             | 0                   | EA             |                              |                            |                                 | 1                           | No                       | 1/D                                    |  |  |  |  |
| 1   | 3                     | Classroom 309        | N/A                                     | Plaster Ceiling            |                         | NAD                                      | 870                   | SF             | 0                   | SF             |                              |                            |                                 | N/A                         | N/A                      | N/A                                    |  |  |  |  |
| 1   | 3                     | Classroom 309        | N/A                                     | Plaster Walls              |                         | NAD                                      | 1740                  | SF             | 0                   | SF             |                              |                            |                                 | N/A                         | N/A                      | N/A                                    |  |  |  |  |
| 1   | 3                     | Classroom 309        | N/A                                     | Wood Floor                 |                         | Non Suspect ACM                          | 870                   | SF             | 0                   | SF             |                              |                            |                                 | N/A                         | N/A                      | N/A                                    |  |  |  |  |
| 1   | 3                     | Classroom 309 Closet | N/A                                     | Plaster Ceiling            |                         | NAD                                      | 180                   | SF             | 0                   | SF             |                              |                            |                                 | N/A                         | N/A                      | N/A                                    |  |  |  |  |
| 1   | 3                     | Classroom 309 Closet | N/A                                     | Plaster Walls              |                         | NAD                                      | 360                   | SF             | 0                   | SF             |                              |                            |                                 | N/A                         | N/A                      | N/A                                    |  |  |  |  |
| 1   | 3                     | Classroom 309 Closet | N/A                                     | Wood Floor                 |                         | Non Suspect ACM                          | 180                   | SF             | 0                   | SF             |                              |                            |                                 | N/A                         | N/A                      | N/A                                    |  |  |  |  |
| 1   | 3                     | Classroom 310        | M                                       | Blackboard Glue Dots       | 7220/01/03/ACER/SM/2600 | Assumed                                  | 3                     | EA             | 0                   | EA             |                              |                            |                                 | 1                           | No                       | 1/D                                    |  |  |  |  |
| 1   | 3                     | Classroom 310        | N/A                                     | Fiberglass Pipe Insulation |                         | Non Suspect ACM                          | 10                    | LF             | 0                   | LF             |                              |                            |                                 | N/A                         | N/A                      | N/A                                    |  |  |  |  |
| 1   | 3                     | Classroom 310        | T                                       | Pipe Insulation 2-6 inch   | 7220/01/03/18           | Confirmed                                | 6                     | LF             | 1                   | LF             |                              |                            |                                 | 1                           | Yes                      | 5/A                                    |  |  |  |  |
| 1   | 3                     | Classroom 310        | N/A                                     | Plaster Ceiling            |                         | NAD                                      | 928                   | SF             | 0                   | SF             |                              |                            |                                 | N/A                         | N/A                      | N/A                                    |  |  |  |  |
| 1   | 3                     | Classroom 310        | N/A                                     | Plaster Walls              |                         | NAD                                      | 1856                  | SF             | 0                   | SF             |                              |                            |                                 | N/A                         | N/A                      | N/A                                    |  |  |  |  |
| 1   | 3                     | Classroom 310        | N/A                                     | Wood Floor                 |                         | Non Suspect ACM                          | 928                   | SF             | 0                   | SF             |                              |                            |                                 | N/A                         | N/A                      | N/A                                    |  |  |  |  |
| 1   | 3                     | Classroom 310 Closet | N/A                                     | Plaster Ceiling            |                         | NAD                                      | 192                   | SF             | 0                   | SF             |                              |                            |                                 | N/A                         | N/A                      | N/A                                    |  |  |  |  |
| 1   | 3                     | Classroom 310 Closet | N/A                                     | Plaster Walls              |                         | NAD                                      | 384                   | SF             | 0                   | SF             |                              |                            |                                 | N/A                         | N/A                      | N/A                                    |  |  |  |  |
| 1   | 3                     | X                    | X                                       | X                          |                         | X  | X                     | X              | 0                   | X              |                              | No Access                  |                                 | X                           | X                        | X                                      |  |  |  |  |
| 1   | 3                     | Storage Closet 300   | N/A                                     | Plaster Ceiling            |                         | NAD                                      | 144                   | SF             | 0                   | SF             |                              |                            |                                 | N/A                         | N/A                      | N/A                                    |  |  |  |  |
| 1   | 3                     | Storage Closet 300   | N/A                                     | Plaster Walls              |                         | NAD                                      | 288                   | SF             | 0                   | SF             |                              |                            |                                 | N/A                         | N/A                      | N/A                                    |  |  |  |  |
| 1   | 3                     | Women's Restroom     | M                                       | Floor Tile VAT 9" x 9"     | 7220/01/03/AA           | Confirmed                                | 108                   | SF             | 0                   | SF             |                              | Brown                      |                                 | 1                           | No                       | 1/D                                    |  |  |  |  |
| 1   | 3                     | Women's Restroom     | T                                       | Pipe Insulation 2-6 inch   | 7220/01/03/18           | Confirmed                                | 24                    | LF             | 0                   | LF             |                              |                            |                                 | 1                           | No                       | 1/D                                    |  |  |  |  |
| 1   | 3                     | Women's Restroom     | N/A                                     | Plaster Ceiling            |                         | NAD                                      | 108                   | SF             | 0                   | SF             |                              |                            |                                 | N/A                         | N/A                      | N/A                                    |  |  |  |  |
| 1   | 3                     | Women's Restroom     | N/A                                     | Plaster Walls              |                         | NAD                                      | 300                   | SF             | 0                   | SF             |                              |                            |                                 | N/A                         | N/A                      | N/A                                    |  |  |  |  |



# 7220 Carnell ES 2015 2016 AHERA Three-Year Report.xls

| School District of Philadelphia               |                       |  | AHERA Three-Year Reinspection 2015-2016 |                            |                         |  |                       |          |                     |          |                              |   |  | Reinspection Date: October 21-26, 2015 |                          |                         |  |
|---|-----------------------|--|---|----------------------------|-------------------------|--|-----------------------|----------|---------------------|----------|------------------------------|---|--|--|--------------------------|-------------------------|--|
| Laura H. Carnell Elementary School            |                       |  | Room by Room Location Log Report        |                            |                         |  |                       |          |                     |          |                              |   |  | Building Inspector: Scott Magee        |                          |                         |  |
| 1100 Devereaux Avenue, Philadelphia, PA 19111 |                       |  |   |                            |                         |  |                       |          |                     |          |                              |   |  | Number: 70016699C                      |                          |                         |  |
| ULCS# 7220                                    |                       |  |   |                            |                         |  |                       |          |                     |          |                              |   |  | Management Planner: Megan Vala         |                          |                         |  |
| Year Built: 1931                              |                       |  |   |                            |                         |  |                       |          |                     |          |                              |   |  | Number: 740728                         |                          |                         |  |
| E<br>l<br>e<br>m<br>e<br>n<br>t               | F<br>l<br>o<br>o<br>r | On-Site Room Name                        | System Affected                         | Material Description       | HID#                    | Confirmed/Assumed/NAD<br>Non Suspect ACM | Amount of<br>Material | SF<br>EA | Amount of<br>Damage | SF<br>EA | Color<br>required for<br>VAT | Comments/Description/Notes                        | Attic Crawl<br>Space<br>Ranking                | Damage<br>Potential<br>(DP)            | Newly<br>Friable<br>(NF) | Response<br>Action (RA) |  |
|   |                       |  |   |                            |                         |  |                       |          |                     |          |                              |   |  |  |                          |                         |  |
| 1   | 3                     | Staff Restroom                           | M                                       | Floor Tile VAT 12" x 12"   | 7220/01/03/LL           | Assumed                                  | 45                    | SF       | 0                   | SF       | Tan                          |   |  | 1                                      | No                       | 1/D                     |  |
| 1   | 3                     | Staff Restroom                           | T                                       | Pipe Insulation 2-6 inch   | 7220/01/03/18           | Confirmed                                | 12                    | LF       | 1                   | LF       |                              |   |  | 1                                      | Yes                      | 5/A                     |  |
| 1   | 3                     | Staff Restroom                           | N/A                                     | Plaster Ceiling            |                         | NAD                                      | 45                    | SF       | 0                   | SF       |                              |   |  | N/A                                    | N/A                      | N/A                     |  |
| 1   | 3                     | Staff Restroom                           | N/A                                     | Plaster Walls              |                         | NAD                                      | 90                    | SF       | 0                   | SF       |                              |   |  | N/A                                    | N/A                      | N/A                     |  |
| 1   | 3                     | Speech Room Office                       | M                                       | Blackboard Glue Dots       | 7220/01/03/ACER/SM/2600 | Assumed                                  | 2                     | EA       | 0                   | EA       |                              |   |  | 1                                      | No                       | 1/D                     |  |
| 1   | 3                     | Speech Room Office                       | N/A                                     | Plaster Ceiling            |                         | NAD                                      | 108                   | SF       | 4                   | SF       |                              |   |  | N/A                                    | N/A                      | N/A                     |  |
| 1   | 3                     | Speech Room Office                       | N/A                                     | Plaster Walls              |                         | NAD                                      | 216                   | SF       | 2                   | SF       |                              |   |  | N/A                                    | N/A                      | N/A                     |  |
| 1   | 3                     | Speech Room Office                       | N/A                                     | Wood Floor                 |                         | Non Suspect ACM                          | 108                   | SF       | 0                   | SF       |                              |   |  | N/A                                    | N/A                      | N/A                     |  |
| 1   | 3                     | Third Floor Hallway                      | N/A                                     | Marble Walls               |                         | Non Suspect ACM                          | 820                   | SF       | 0                   | SF       |                              |   |  | N/A                                    | N/A                      | N/A                     |  |
| 1   | 3                     | Third Floor Hallway                      | T                                       | Pipe Insulation 2-6 inch   | 7220/01/03/18           | Confirmed                                | 12                    | LF       | 0                   | LF       |                              |   |  | 1                                      | No                       | 1/D                     |  |
| 1   | 3                     | Third Floor Hallway                      | N/A                                     | Plaster Ceiling            |                         | NAD                                      | 820                   | SF       | 0                   | SF       |                              |   |  | N/A                                    | N/A                      | N/A                     |  |
| 1   | 3                     | Third Floor Hallway                      | N/A                                     | Plaster Walls              |                         | NAD                                      | 1640                  | SF       | 0                   | SF       |                              |   |  | N/A                                    | N/A                      | N/A                     |  |
| 1   | 3                     | Third Floor Hallway                      | T                                       | Pipe Fitting Insulation    | 7220/01/03/22           | Confirmed                                | 1                     | EA       | 0                   | EA       |                              |   |  | 1                                      | No                       | 1/D                     |  |
| 1   | 3                     | Third Floor Hallway                      | N/A                                     | Marble Walls               |                         | Non Suspect ACM                          | 1350                  | SF       | 0                   | SF       |                              |   |  | N/A                                    | N/A                      | N/A                     |  |
| 1   | 3                     | Third Floor Hallway                      | N/A                                     | Plaster Ceiling            |                         | NAD                                      | 1350                  | SF       | 0                   | SF       |                              |   |  | N/A                                    | N/A                      | N/A                     |  |
| 1   | 3                     | Third Floor Hallway                      | N/A                                     | Plaster Walls              |                         | NAD                                      | 2700                  | SF       | 0                   | SF       |                              |   |  | N/A                                    | N/A                      | N/A                     |  |
| 1   | 3                     | Third Floor Hallway                      | N/A                                     | Marble Walls               |                         | Non Suspect ACM                          | 660                   | SF       | 0                   | SF       |                              |   |  | N/A                                    | N/A                      | N/A                     |  |
| 1   | 3                     | Third Floor Hallway                      | N/A                                     | Plaster Ceiling            |                         | NAD                                      | 660                   | SF       | 0                   | SF       |                              |   |  | N/A                                    | N/A                      | N/A                     |  |
| 1   | 3                     | Third Floor Hallway                      | N/A                                     | Plaster Walls              |                         | NAD                                      | 1320                  | SF       | 0                   | SF       |                              |   |  | N/A                                    | N/A                      | N/A                     |  |
| 1   | 3                     | Hallway Closet adjacent to Classroom 301 | N/A                                     | Cement Floor               |                         | Non Suspect ACM                          | 84                    | SF       | 0                   | SF       |                              |   |  | N/A                                    | N/A                      | N/A                     |  |
| 1   | 3                     | Hallway Closet adjacent to Classroom 301 | N/A                                     | Plaster Ceiling            |                         | NAD                                      | 84                    | SF       | 0                   | SF       |                              |   |  | N/A                                    | N/A                      | N/A                     |  |
| 1   | 3                     | Hallway Closet adjacent to Classroom 301 | N/A                                     | Plaster Walls              |                         | NAD                                      | 168                   | SF       | 12                  | SF       |                              |   |  | N/A                                    | N/A                      | N/A                     |  |
| 1   | 3                     | Stairs Third Floor                       | N/A                                     | Marble Walls               |                         | Non Suspect ACM                          | 341                   | SF       | 0                   | SF       |                              |   |  | N/A                                    | N/A                      | N/A                     |  |
| 1   | 3                     | Stairs Third Floor                       | T                                       | Pipe Insulation 2-6 inch   | 7220/01/03/18           | Confirmed                                | 20                    | LF       | 0                   | LF       |                              |   |  | 1                                      | No                       | 1/D                     |  |
| 1   | 3                     | Stairs Third Floor                       | N/A                                     | Plaster Ceiling            |                         | NAD                                      | 341                   | SF       | 0                   | SF       |                              |   |  | N/A                                    | N/A                      | N/A                     |  |
| 1   | 3                     | Entrance Stairs Third Floor              | N/A                                     | Marble Walls               |                         | Non Suspect ACM                          | 264                   | SF       | 0                   | SF       |                              |   |  | N/A                                    | N/A                      | N/A                     |  |
| 1   | 3                     | Entrance Stairs Third Floor              | N/A                                     | Plaster Ceiling            |                         | NAD                                      | 264                   | SF       | 0                   | SF       |                              |   |  | N/A                                    | N/A                      | N/A                     |  |
| 1   | 1                     | Entrance Stairs First Floor              | N/A                                     | Marble Walls               |                         | Non Suspect ACM                          | 264                   | SF       | 0                   | SF       |                              |   |  | N/A                                    | N/A                      | N/A                     |  |
| 1   | 1                     | Entrance Stairs First Floor              | N/A                                     | Pipe Fitting Insulation    |                         | NAD                                      | 2                     | EA       | 0                   | EA       |                              |   |  | N/A                                    | N/A                      | N/A                     |  |
| 1   | 1                     | Entrance Stairs First Floor              | T                                       | Pipe Insulation 2-6 inch   | 7220/01/01/28           | Confirmed                                | 4                     | LF       | 0                   | LF       |                              |   |  | 1                                      | No                       | 1/D                     |  |
| 1   | 1                     | Entrance Stairs First Floor              | N/A                                     | Plaster Ceiling            |                         | NAD                                      | 264                   | SF       | 0                   | SF       |                              |   |  | N/A                                    | N/A                      | N/A                     |  |
| 1   | 1                     | Entrance Stairs First Floor              | N/A                                     | Plaster Walls              |                         | NAD                                      | 528                   | SF       | 0                   | SF       |                              |   |  | N/A                                    | N/A                      | N/A                     |  |
| 1   | 1                     | Stairs First Floor                       | N/A                                     | Pipe Fitting Insulation    |                         | NAD                                      | 4                     | EA       | 0                   | EA       |                              |   |  | N/A                                    | N/A                      | N/A                     |  |
| 1   | 1                     | Stairs First Floor                       | N/A                                     | Marble Walls               |                         | Non Suspect ACM                          | 308                   | SF       | 0                   | SF       |                              |   |  | N/A                                    | N/A                      | N/A                     |  |
| 1   | 1                     | Stairs First Floor                       | T                                       | Pipe Insulation 2-6 inch   | 7220/01/01/28           | Confirmed                                | 25                    | LF       | 0                   | LF       |                              |   |  | 1                                      | No                       | 1/D                     |  |
| 1   | 1                     | Stairs First Floor                       | N/A                                     | Plaster Ceiling            |                         | NAD                                      | 308                   | SF       | 0                   | SF       |                              |   |  | N/A                                    | N/A                      | N/A                     |  |
| 1   | 1                     | Stairs First Floor                       | N/A                                     | Plaster Walls              |                         | NAD                                      | 616                   | SF       | 0                   | SF       |                              |   |  | N/A                                    | N/A                      | N/A                     |  |
| 1   | B                     | Stairs Basement                          | N/A                                     | Marble Walls               |                         | Non Suspect ACM                          | 264                   | SF       | 0                   | SF       |                              |   |  | N/A                                    | N/A                      | N/A                     |  |
| 1   | B                     | Stairs Basement                          | T                                       | Pipe Insulation 2-6 inch   | 7220/01/0B/01           | Confirmed                                | 30                    | LF       | 0                   | LF       |                              |   |  | 1                                      | No                       | 1/D                     |  |
| 1   | B                     | Stairs Basement                          | N/A                                     | Plaster Ceiling            |                         | NAD                                      | 264                   | SF       | 0                   | SF       |                              |   |  | N/A                                    | N/A                      | N/A                     |  |
| 1   | B                     | Stairs Basement                          | N/A                                     | Plaster Walls              |                         | NAD                                      | 528                   | SF       | 0                   | SF       |                              |   |  | N/A                                    | N/A                      | N/A                     |  |
| 1   | B                     | Stairs Basement                          | T                                       | Pipe Fitting Insulation    | 7220/01/0B/06           | Confirmed                                | 8                     | EA       | 0                   | EA       |                              |   |  | 1                                      | No                       | 1/D                     |  |
| 1   | B                     | Entrance Stairs Basement                 | N/A                                     | Plaster Walls              |                         | NAD                                      | 528                   | SF       | 0                   | SF       |                              |   |  | N/A                                    | N/A                      | N/A                     |  |
| 1   | B                     | Classroom B1                             | T                                       | Pipe Fitting Insulation    | 7220/01/0B/06           | Confirmed                                | 10                    | EA       | 0                   | EA       |                              |   |  | 1                                      | No                       | 1/D                     |  |
| 1   | B                     | Classroom B1                             | T                                       | Pipe Insulation 2-6 inch   | 7220/01/0B/01           | Confirmed                                | 40                    | LF       | 0                   | LF       |                              |   |  | 1                                      | No                       | 1/D                     |  |
| 1   | B                     | Classroom B1                             | N/A                                     | Plaster Ceiling            |                         | NAD                                      | 638                   | SF       | 0                   | SF       |                              |   |  | N/A                                    | N/A                      | N/A                     |  |
| 1   | B                     | Classroom B1                             | N/A                                     | Plaster Walls              |                         | NAD                                      | 1276                  | SF       | 15                  | SF       |                              |   | Damage to Plaster Wall an Paint Around Windows | N/A                                    | N/A                      | N/A                     |  |
| 1   | B                     | Classroom B1                             | N/A                                     | Wood Floor                 |                         | Non Suspect ACM                          | 638                   | SF       | 0                   | SF       |                              |   |  | N/A                                    | N/A                      | N/A                     |  |
| 1   | B                     | Classroom B2                             | N/A                                     | Cement Floor               |                         | Non Suspect ACM                          | 1020                  | SF       | 0                   | SF       |                              |   |  | N/A                                    | N/A                      | N/A                     |  |
| 1   | B                     | Classroom B2                             | N/A                                     | Fiberglass Pipe Insulation |                         | Non Suspect ACM                          | 45                    | LF       | 0                   | LF       |                              |   |  | N/A                                    | N/A                      | N/A                     |  |
| 1   | B                     | Classroom B2                             | M                                       | Floor Tile VAT 12" x 12"   | 7220/01/0B/MM           | Assumed                                  | 1020                  | SF       | 10                  | SF       | Tan                          | Distributed Damage/Carnell Family Resource Center |  | 1                                      | Yes                      | 5/B                     |  |
| 1   | B                     | Classroom B2                             | N/A                                     | Plaster Ceiling            |                         | NAD                                      | 1020                  | SF       | 0                   | SF       |                              |   |  | N/A                                    | N/A                      | N/A                     |  |
| 1   | B                     | Classroom B2                             | N/A                                     | Plaster Walls              |                         | NAD                                      | 2040                  | SF       | 20                  | SF       |                              |   |  | N/A                                    | N/A                      | N/A                     |  |
| 1   | B                     | Classroom B2                             | N/A                                     | Sheetrock Wall             |                         | NAD                                      | 288                   | SF       | 0                   | SF       |                              |   |  | N/A                                    | N/A                      | N/A                     |  |
| 1   | B                     | Classroom 2 Closet                       | N/A                                     | Cement Floor               |                         | Non Suspect ACM                          | 85                    | SF       | 0                   | SF       |                              |   |  | N/A                                    | N/A                      | N/A                     |  |
| 1   | B                     | Classroom 2 Closet                       | N/A                                     | Plaster Ceiling            |                         | NAD                                      | 85                    | SF       | 0                   | SF       |                              |   |  | N/A                                    | N/A                      | N/A                     |  |
| 1   | B                     | Classroom 2 Closet                       | N/A                                     | Plaster Walls              |                         | NAD                                      | 170                   | SF       | 0                   | SF       |                              |   |  | N/A                                    | N/A                      | N/A                     |  |
| 1   | B                     | Classroom 2 Closet                       | N/A                                     | Cement Floor               |                         | Non Suspect ACM                          | 65                    | SF       | 0                   | SF       |                              |   |  | N/A                                    | N/A                      | N/A                     |  |
| 1   | B                     | Classroom 2 Closet                       | N/A                                     | Plaster Ceiling            |                         | NAD                                      | 65                    | SF       | 0                   | SF       |                              |   |  | N/A                                    | N/A                      | N/A                     |  |
| 1   | B                     | Classroom 2 Closet                       | N/A                                     | Plaster Walls              |                         | NAD                                      | 130                   | SF       | 0                   | SF       |                              |   |  | N/A                                    | N/A                      | N/A                     |  |
| 1   | B                     | Art Room                                 | N/A                                     | Brick Wall                 |                         | Non Suspect ACM                          | 920                   | SF       | 0                   | SF       |                              |   |  | N/A                                    | N/A                      | N/A                     |  |
| 1   | B                     | Art Room                                 | N/A                                     | Fiberglass Pipe Insulation |                         | Non Suspect ACM                          | 40                    | LF       | 0                   | LF       |                              |   |  | N/A                                    | N/A                      | N/A                     |  |
| 1   | B                     | Art Room                                 | T                                       | Pipe Fitting Insulation    | 7220/01/0B/06           | Confirmed                                | 18                    | EA       | 0                   | EA       |                              |   |  | 1                                      | No                       | 1/D                     |  |
| 1   | B                     | Art Room                                 | T                                       | Pipe Insulation 2-6 inch   | 7220/01/0B/01           | Confirmed                                | 70                    | LF       | 0                   | LF       |                              |   |  | 1                                      | No                       | 1/D                     |  |
| 1   | B                     | Art Room                                 | N/A                                     | Plaster Ceiling            |                         | NAD                                      | 920                   | SF       | 0                   | SF       |                              |   |  | N/A                                    | N/A                      | N/A                     |  |
| 1   | B                     | Art Room                                 | N/A                                     | Plaster Walls              |                         | NAD                                      | 920                   | SF       | 0                   | SF       |                              |   |  | N/A                                    | N/A                      | N/A                     |  |
| 1   | B                     | Art Room                                 | N/A                                     | Wood Floor                 |                         | Non Suspect ACM                          | 920                   | SF       | 0                   | SF       |                              |   |  | N/A                                    | N/A                      | N/A                     |  |
| 1   | B                     | Art Room Closet                          | T                                       | Pipe Fitting Insulation    | 7220/01/0B/06           | Confirmed                                | 6                     | EA       | 0                   | EA       |                              |   |  | 1                                      | No                       | 1/D                     |  |
| 1   | B                     | Art Room Closet                          | T                                       | Pipe Insulation 2-6 inch   | 7220/01/0B/01           | Confirmed                                | 27                    | LF       | 0                   | LF       |                              |   |  | 1                                      | No                       | 1/D                     |  |
| 1   | B                     | Art Room Closet                          | N/A                                     | Plaster Ceiling            |                         | NAD                                      | 150                   | SF       | 30                  | SF       |                              |   |  | N/A                                    | N/A                      | N/A                     |  |
| 1   | B                     | Art Room Closet                          | N/A                                     | Plaster Walls              |                         | NAD                                      | 300                   | SF       | 0                   | SF       |                              |   |  | N/A                                    | N/A                      | N/A                     |  |
| 1   | B                     | Art Room Closet                          | N/A                                     | Wood Floor                 |                         | Non Suspect ACM                          | 150                   | SF       | 0                   | SF       |                              |   |  | N/A                                    | N/A                      | N/A                     |  |
| 1   | B                     | Classroom 004                            | T                                       | Pipe Fitting Insulation    | 7220/01/0B/06           | Confirmed                                | 9                     | EA       | 0                   | EA       |                              |   |  | 1                                      | No                       | 1/D                     |  |
| 1   | B                     | Classroom 004                            | T                                       | Pipe Insulation 2-6 inch   | 7220/01/0B/01           | Confirmed                                | 45                    | LF       | 0                   | LF       |                              |   |  | 1                                      | No                       | 1/D                     |  |
| 1   | B                     | Classroom 004                            | N/A                                     | Plaster Ceiling            |                         | NAD                                      | 690                   | SF       | 0                   | SF       |                              |   |  | N/A                                    | N/A                      | N/A                     |  |
| 1   | B                     | Classroom 004                            | N/A                                     | Plaster Walls              |                         | NAD                                      | 1380                  | SF       | 0                   | SF       |                              |   |  | N/A                                    | N/A                      | N/A                     |  |

# 7220 Carnell ES 2015 2016 AHERA Three-Year Report.xls

| School District of Philadelphia               |                       |                    | AHERA Three-Year Reinspection 2015-2016<br>Room by Room Location Log Report |                            |                         |  |                       |    |     |    |                     |    |    |    |                              | Reinspection Date: October 21-26, 2015          |                                 |                             |                          |                         |  |
|---|-----------------------|--------------------|---|----------------------------|-------------------------|--|-----------------------|----|-----|----|---------------------|----|----|----|------------------------------|---|---------------------------------|-----------------------------|--------------------------|-------------------------|--|
| Laura H. Carnell Elementary School            |                       |                    |   |                            |                         |  |                       |    |     |    |                     |    |    |    |                              | Building Inspector: Scott Magee                 |                                 |                             |                          |                         |  |
| 1100 Devereaux Avenue, Philadelphia, PA 19111 |                       |                    |   |                            |                         |  |                       |    |     |    |                     |    |    |    |                              | Number: 70016699C                               |                                 |                             |                          |                         |  |
| ULCS# 7220                                    |                       |                    |   |                            |                         |  |                       |    |     |    |                     |    |    |    |                              | Management Planner: Megan Vala                  |                                 |                             |                          |                         |  |
| Year Built: 1931                              |                       |                    |   |                            |                         |  |                       |    |     |    |                     |    |    |    |                              | Number: 740728                                  |                                 |                             |                          |                         |  |
| E<br>l<br>e<br>m<br>e<br>n<br>t               | F<br>l<br>o<br>o<br>r | On-Site Room Name  | System Affected   | Material Description       | HID#                    | Confirmed/Assumed/NAD<br>Non Suspect ACM | Amount of<br>Material | SF | LF  | EA | Amount of<br>Damage | SF | LF | EA | Color<br>required for<br>VAT | Comments/Description/Notes                      | Attic Crawl<br>Space<br>Ranking | Damage<br>Potential<br>(DP) | Newly<br>Friable<br>(NF) | Response<br>Action (RA) |  |
| 1   | B                     | Classroom 004      | N/A   | Wood Floor                 |                         | Non Suspect ACM                          | 690                   | SF |     |    | 0                   | SF |    |    |                              |   |                                 | N/A                         | N/A                      | N/A                     |  |
| 1   | B                     | Classroom 4 Closet | N/A   | Plaster Ceiling            |                         | NAD                                      | 90                    | SF | 0   | SF |                     |    |    |    |                              |   |                                 | N/A                         | N/A                      | N/A                     |  |
| 1   | B                     | Classroom 4 Closet | N/A   | Plaster Walls              |                         | NAD                                      | 180                   | SF | 0   | SF |                     |    |    |    |                              |   |                                 | N/A                         | N/A                      | N/A                     |  |
| 1   | B                     | Classroom 4 Closet | N/A   | Wood Floor                 |                         | Non Suspect ACM                          | 90                    | SF | 0   | SF |                     |    |    |    |                              |   |                                 | N/A                         | N/A                      | N/A                     |  |
| 1   | B                     | Boy's Restroom     | N/A   | Brick Wall                 |                         | Non Suspect ACM                          | 1288                  | SF | 0   | SF |                     |    |    |    |                              |   |                                 | N/A                         | N/A                      | N/A                     |  |
| 1   | B                     | Boy's Restroom     | N/A   | Cement Floor               |                         | Non Suspect ACM                          | 644                   | SF | 0   | SF |                     |    |    |    |                              |   |                                 | N/A                         | N/A                      | N/A                     |  |
| 1   | B                     | Boy's Restroom     | N/A   | Fiberglass Pipe Insulation |                         | Non Suspect ACM                          | 15                    | LF | 0   | LF |                     |    |    |    |                              |   |                                 | N/A                         | N/A                      | N/A                     |  |
| 1   | B                     | Boy's Restroom     | N/A   | Plaster Ceiling            |                         | NAD                                      | 644                   | SF | 0   | SF |                     |    |    |    |                              |   |                                 | N/A                         | N/A                      | N/A                     |  |
| 1   | B                     | Pipe Chase         | X   | X                          |                         | X  | X                     | X  | X   | X  |                     |    |    |    |                              |   |                                 | X                           | X                        | X                       |  |
| 1   | B                     | Gym                | N/A   | Brick Wall                 |                         | Non Suspect ACM                          | 7040                  | SF | 0   | SF |                     |    |    |    |                              |   |                                 | N/A                         | N/A                      | N/A                     |  |
| 1   | B                     | Gym                | N/A   | Fiberglass Pipe Insulation |                         | Non Suspect ACM                          | 100                   | LF | 0   | LF |                     |    |    |    |                              |   |                                 | N/A                         | N/A                      | N/A                     |  |
| 1   | B                     | Gym                | T   | Pipe Fitting Insulation    | 7220/01/0B/06           | Confirmed                                | 65                    | EA | 0   | EA |                     |    |    |    |                              |   |                                 | 1                           | No                       | 1/D                     |  |
| 1   | B                     | Gym                | T   | Pipe Insulation 2-6 inch   | 7220/01/0B/01           | Confirmed                                | 175                   | LF | 1   | LF |                     |    |    |    |                              |   |                                 | 1                           | Yes                      | 5/A                     |  |
| 1   | B                     | Gym                | N/A   | Plaster Ceiling            |                         | NAD                                      | 3520                  | SF | 15  | SF |                     |    |    |    |                              |   |                                 | N/A                         | N/A                      | N/A                     |  |
| 1   | B                     | Gym                | N/A   | Wood Floor                 |                         | Non Suspect ACM                          | 3520                  | SF | 0   | SF |                     |    |    |    |                              |   |                                 | N/A                         | N/A                      | N/A                     |  |
| 1   | B                     | Student Lunch Room | M   | Blackboard Glue Dots       | 7220/01/0B/ACER/SM/2600 | Assumed                                  | 40                    | SF | 0   | SF |                     |    |    |    |                              | Glue Dots Exposed                               |                                 | 1                           | No                       | 1/D                     |  |
| 1   | B                     | Student Lunch Room | N/A   | Brick Wall                 |                         | Non Suspect ACM                          | 2700                  | SF | 0   | SF |                     |    |    |    |                              |   |                                 | N/A                         | N/A                      | N/A                     |  |
| 1   | B                     | Student Lunch Room | N/A   | Cement Floor               |                         | Non Suspect ACM                          | 1350                  | SF | 0   | SF |                     |    |    |    |                              |   |                                 | N/A                         | N/A                      | N/A                     |  |
| 1   | B                     | Student Lunch Room | N/A   | Fiberglass Pipe Insulation |                         | Non Suspect ACM                          | 20                    | LF | 0   | LF |                     |    |    |    |                              |   |                                 | N/A                         | N/A                      | N/A                     |  |
| 1   | B                     | Student Lunch Room | M   | Floor Tile VAT 9" x 9"     | 7220/01/0B/07           | Confirmed                                | 1350                  | SF | 3   | SF |                     |    |    |    | Tan                          | Minor Chips and Cracks                          |                                 | 1                           | Yes                      | 5/B                     |  |
| 1   | B                     | Student Lunch Room | T   | Pipe Fitting Insulation    | 7220/01/0B/06           | Confirmed                                | 17                    | EA | 0   | EA |                     |    |    |    |                              |   |                                 | 1                           | No                       | 1/D                     |  |
| 1   | B                     | Student Lunch Room | T   | Pipe Insulation 2-6 inch   | 7220/01/0B/01           | Confirmed                                | 60                    | LF | 1   | LF |                     |    |    |    |                              |   |                                 | 1                           | Yes                      | 5/A                     |  |
| 1   | B                     | Student Lunch Room | N/A   | Plaster Ceiling            |                         | NAD                                      | 1350                  | SF | 150 | SF |                     |    |    |    |                              |   |                                 | N/A                         | N/A                      | N/A                     |  |
| 1   | B                     | Pipe Chase         | X   | X                          |                         | X  | X                     | X  | X   | X  |                     |    |    |    |                              | No Access                                       |                                 | X                           | X                        | X                       |  |
| 1   | B                     | Custodial Closet   | X   | X                          |                         | X  | X                     | X  | X   | X  |                     |    |    |    |                              | No Access                                       |                                 | X                           | X                        | X                       |  |
| 1   | B                     | Custodial Closet   | N/A   | Brick Wall                 |                         | Non Suspect ACM                          | 40                    | SF | 0   | SF |                     |    |    |    |                              |   |                                 | N/A                         | N/A                      | N/A                     |  |
| 1   | B                     | Custodial Closet   | N/A   | Cement Floor               |                         | Non Suspect ACM                          | 20                    | SF | 0   | SF |                     |    |    |    |                              |   |                                 | N/A                         | N/A                      | N/A                     |  |
| 1   | B                     | Custodial Closet   | N/A   | Concrete Ceiling           |                         | Non Suspect ACM                          | 10                    | SF | 0   | SF |                     |    |    |    |                              |   |                                 | N/A                         | N/A                      | N/A                     |  |
| 1   | B                     | Custodial Closet   | N/A   | Plaster Ceiling            |                         | NAD                                      | 10                    | SF | 0   | SF |                     |    |    |    |                              |   |                                 | N/A                         | N/A                      | N/A                     |  |
| 1   | B                     | Boiler Room        | N/A   | Cement Floor               |                         | Non Suspect ACM                          | 1584                  | SF | 0   | SF |                     |    |    |    |                              |   |                                 | N/A                         | N/A                      | N/A                     |  |
| 1   | B                     | Boiler Room        | N/A   | Concrete Block Wall        |                         | Non Suspect ACM                          | 3168                  | SF | 0   | SF |                     |    |    |    |                              |   |                                 | N/A                         | N/A                      | N/A                     |  |
| 1   | B                     | Boiler Room        | N/A   | Concrete Ceiling           |                         | Non Suspect ACM                          | 1584                  | SF | 0   | SF |                     |    |    |    |                              |   |                                 | N/A                         | N/A                      | N/A                     |  |
| 1   | B                     | Boiler Room        | T   | Duct Insulation            | 7220/01/0B/05           | Confirmed                                | 600                   | SF | 100 | SF |                     |    |    |    |                              | Duct Insulation is becoming detached            |                                 | 1                           | Yes                      | 5/C                     |  |
| 1   | B                     | Boiler Room        | N/A   | Fiberglass Pipe Insulation |                         | Non Suspect ACM                          | 100                   | LF | 0   | LF |                     |    |    |    |                              |   |                                 | N/A                         | N/A                      | N/A                     |  |
| 1   | B                     | Boiler Room        | T   | Pipe Fitting Insulation    | 7220/01/0B/06           | Confirmed                                | 50                    | EA | 0   | EA |                     |    |    |    |                              | <1 SF of Debris Associated with Damaged Fitting |                                 | 1                           | No                       | 1/D                     |  |
| 1   | B                     | Boiler Room        | T   | Pipe Insulation > 6 inch   | 7220/01/0B/03           | Confirmed                                | 50                    | LF | 0   | LF |                     |    |    |    |                              |   |                                 | 1                           | No                       | 1/D                     |  |
| 1   | B                     | Boiler Room        | T   | Pipe Insulation 2-6 inch   | 7220/01/0B/01           | Confirmed                                | 225                   | LF | 0   | LF |                     |    |    |    |                              |   |                                 | 1                           | No                       | 1/D                     |  |
| 1   | B                     | Boiler Room        | N/A   | Cement Floor               |                         | Non Suspect ACM                          | 1080                  | SF | 0   | SF |                     |    |    |    |                              |   |                                 | N/A                         | N/A                      | N/A                     |  |
| 1   | B                     | Boiler Room        | N/A   | Concrete Block Wall        |                         | Non Suspect ACM                          | 2160                  | SF | 0   | SF |                     |    |    |    |                              |   |                                 | N/A                         | N/A                      | N/A                     |  |
| 1   | B                     | Boiler Room        | N/A   | Concrete Ceiling           |                         | Non Suspect ACM                          | 1080                  | SF | 0   | SF |                     |    |    |    |                              |   |                                 | N/A                         | N/A                      | N/A                     |  |
| 1   | B                     | Boiler Room        | N/A   | Fiberglass Pipe Insulation |                         | Non Suspect ACM                          | 90                    | LF | 0   | LF |                     |    |    |    |                              |   |                                 | N/A                         | N/A                      | N/A                     |  |
| 1   | B                     | Boiler Room        | T   | Pipe Fitting Insulation    | 7220/01/0B/06           | Confirmed                                | 75                    | EA | 0   | EA |                     |    |    |    |                              |   |                                 | 1                           | No                       | 1/D                     |  |
| 1   | B                     | Boiler Room        | T   | Pipe Insulation > 6 inch   | 7220/01/0B/03           | Confirmed                                | 110                   | LF | 0   | LF |                     |    |    |    |                              |   |                                 | 1                           | No                       | 1/D                     |  |
| 1   | B                     | Boiler Room        | T   | Pipe Insulation 2-6 inch   | 7220/01/0B/01           | Confirmed                                | 100                   | LF | 0   | LF |                     |    |    |    |                              |   |                                 | 1                           | No                       | 1/D                     |  |
| 1   | B                     | Boiler Room        | N/A   | Cement Floor               |                         | Non Suspect ACM                          | 1071                  | SF | 0   | SF |                     |    |    |    |                              |   |                                 | N/A                         | N/A                      | N/A                     |  |
| 1   | B                     | Boiler Room        | N/A   | Concrete Block Wall        |                         | Non Suspect ACM                          | 2142                  | SF | 0   | SF |                     |    |    |    |                              |   |                                 | N/A                         | N/A                      | N/A                     |  |
| 1   | B                     | Boiler Room        | N/A   | Concrete Ceiling           |                         | Non Suspect ACM                          | 1071                  | SF | 0   | SF |                     |    |    |    |                              |   |                                 | N/A                         | N/A                      | N/A                     |  |
| 1   | B                     | Boiler Room        | N/A   | Fiberglass Pipe Insulation |                         | Non Suspect ACM                          | 200                   | LF | 0   | LF |                     |    |    |    |                              |   |                                 | N/A                         | N/A                      | N/A                     |  |
| 1   | B                     | Boiler Room        | T   | Pipe Fitting Insulation    | 7220/01/0B/06           | Confirmed                                | 20                    | EA | 0   | EA |                     |    |    |    |                              |   |                                 | 1                           | No                       | 1/D                     |  |
| 1   | B                     | Boiler Room        | T   | Pipe Insulation 2-6 inch   | 7220/01/0B/01           | Confirmed                                | 150                   | LF | 0   | LF |                     |    |    |    |                              |   |                                 | 1                           | No                       | 1/D                     |  |
| 1   | B                     | Girl's Restroom    | N/A   | Brick Wall                 |                         | Non Suspect ACM                          | 1680                  | SF | 0   | SF |                     |    |    |    |                              |   |                                 | N/A                         | N/A                      | N/A                     |  |
| 1   | B                     | Girl's Restroom    | N/A   | Cement Floor               |                         | Non Suspect ACM                          | 840                   | SF | 0   | SF |                     |    |    |    |                              |   |                                 | N/A                         | N/A                      | N/A                     |  |
| 1   | B                     | Girl's Restroom    | N/A   | Fiberglass Pipe Insulation |                         | Non Suspect ACM                          | 25                    | LF | 0   | LF |                     |    |    |    |                              |   |                                 | N/A                         | N/A                      | N/A                     |  |
| 1   | B                     | Girl's Restroom    | N/A   | Plaster Ceiling            |                         | NAD                                      | 840                   | SF | 0   | SF |                     |    |    |    |                              |   |                                 | N/A                         | N/A                      | N/A                     |  |
| 1   | B                     | Basement Hallway   | N/A   | Brick Wall                 |                         | Non Suspect ACM                          | 2240                  | SF | 0   | SF |                     |    |    |    |                              |   |                                 | N/A                         | N/A                      | N/A                     |  |
| 1   | B                     | Basement Hallway   | N/A   | Cement Floor               |                         | Non Suspect ACM                          | 1120                  | SF | 0   | SF |                     |    |    |    |                              |   |                                 | N/A                         | N/A                      | N/A                     |  |
| 1   | B                     | Basement Hallway   | N/A   | Fiberglass Pipe Insulation |                         | Non Suspect ACM                          | 30                    | LF | 0   | LF |                     |    |    |    |                              |   |                                 | N/A                         | N/A                      | N/A                     |  |
| 1   | B                     | Basement Hallway   | T   | Pipe Fitting Insulation    | 7220/01/0B/06           | Confirmed                                | 56                    | EA | 0   | EA |                     |    |    |    |                              |   |                                 | 1                           | No                       | 1/D                     |  |
| 1   | B                     | Basement Hallway   | T   | Pipe Insulation 2-6 inch   | 7220/01/0B/01           | Confirmed                                | 300                   | LF | 0   | LF |                     |    |    |    |                              |   |                                 | 1                           | No                       | 1/D                     |  |
| 1   | B                     | Basement Hallway   | N/A   | Plaster Ceiling            |                         | NAD                                      | 1120                  | SF | 0   | SF |                     |    |    |    |                              |   |                                 | N/A                         | N/A                      | N/A                     |  |
| 1   | B                     | Basement Hallway   | N/A   | Brick Wall                 |                         | Non Suspect ACM                          | 1980                  | SF | 0   | SF |                     |    |    |    |                              |   |                                 | N/A                         | N/A                      | N/A                     |  |
| 1   | B                     | Basement Hallway   | N/A   | Cement Floor               |                         | Non Suspect ACM                          | 990                   | SF | 0   | SF |                     |    |    |    |                              |   |                                 | N/A                         | N/A                      | N/A                     |  |
| 1   | B                     | Basement Hallway   | N/A   | Fiberglass Pipe Insulation |                         | Non Suspect ACM                          | 20                    | LF | 0   | LF |                     |    |    |    |                              |   |                                 | N/A                         | N/A                      | N/A                     |  |
| 1   | B                     | Basement Hallway   | T   | Pipe Fitting Insulation    | 7220/01/0B/06           | Confirmed                                | 56                    | EA | 0   | EA |                     |    |    |    |                              |   |                                 | 1                           | No                       | 1/D                     |  |
| 1   | B                     | Basement Hallway   | T   | Pipe Insulation 2-6 inch   | 7220/01/0B/01           | Confirmed                                | 350                   | LF | 0   | LF |                     |    |    |    |                              |   |                                 | 1                           | No                       | 1/D                     |  |
| 1   | B                     | Basement Hallway   | N/A   | Plaster Ceiling            |                         | NAD                                      | 990                   | SF | 0   | SF |                     |    |    |    |                              |   |                                 | N/A                         | N/A                      | N/A                     |  |
| 1   | B                     | Gym Storage        | N/A   | Brick Wall                 |                         | Non Suspect ACM                          | 400                   | SF | 0   | SF |                     |    |    |    |                              |   |                                 | N/A                         | N/A                      | N/A                     |  |
| 1   | B                     | Gym Storage        | N/A   | Fiberglass Pipe Insulation |                         | Non Suspect ACM                          | 5                     | LF | 0   | LF |                     |    |    |    |                              |   |                                 | N/A                         | N/A                      | N/A                     |  |
| 1   | B                     | Gym Storage        | T   | Pipe Fitting Insulation    | 7220/01/0B/06           | Confirmed                                | 30                    | EA | 0   | EA |                     |    |    |    |                              |   |                                 | 1                           | No                       | 1/D                     |  |
| 1   | B                     | Gym Storage        | T   | Pipe Insulation 2-6 inch   | 7220/01/0B/01           | Confirmed                                | 130                   | LF | 8   | LF |                     |    |    |    |                              |   |                                 | 1                           | Yes                      | 5/A                     |  |
| 1   | B                     | Gym Storage        | N/A   | Plaster Ceiling            |                         | NAD                                      | 200                   | SF | 0   | SF |                     |    |    |    |                              |   |                                 | N/A                         | N/A                      | N/A                     |  |
| 1   | B                     | Gym Storage        | N/A   | Wood Floor                 |                         | Non Suspect ACM                          | 200                   | SF | 0   | SF |                     |    |    |    |                              |   |                                 | N/A                         | N/A                      | N/A                     |  |
| 1   | B                     | Gym Coaches Office | X   | X                          |                         | X  | X                     | X  | X   | X  |                     |    |    |    |                              | No Access                                       |                                 | X                           | X                        | X                       |  |
| 2   | 1                     | Classroom 111      | M   | Blackboard Glue Dots       | 7220/02/01/ACER/SM/2600 | Assumed                                  | 2                     | EA | 0   | EA |                     |    |    |    |                              |   |                                 | 1                           | No                       | 1/D                     |  |
| 2   | 1                     | Classroom 111      | N/A   | CMU                        |                         | Non Suspect ACM                          | 1600                  | SF | 0   | SF |                     |    |    |    |                              |   |                                 | N/A                         | N/A                      | N/A                     |  |
| 2   | 1                     | Classroom 111      | N/A   | Concrete Ceiling           |                         | Non Suspect ACM                          | 800                   | SF | 0   | SF |                     |    |    |    |                              |   |                                 | N/A                         | N/A                      | N/A                     |  |

# 7220 Carnell ES 2015 2016 AHERA Three-Year Report.xls

| School District of Philadelphia<br>Laura H. Carnell Elementary School<br>1100 Devereaux Avenue, Philadelphia, PA 19111<br>ULCS# 7220<br>Year Built: 1931 |                       |                      | AHERA Three-Year Reinspection 2015-2016<br>Room by Room Location Log Report |                          |                         |  |                       |    |    |    |                     |    |    |    |                              | Reinspection Date: October 21-26, 2015 |                                 |                             |                          |                         |                                |  |  |  |  |
|--|-----------------------|----------------------|---|--------------------------|-------------------------|--|-----------------------|----|----|----|---------------------|----|----|----|------------------------------|--|---------------------------------|-----------------------------|--------------------------|-------------------------|--------------------------------|--|--|--|--|
|  |                       |                      |   |                          |                         |  |                       |    |    |    |                     |    |    |    |                              | Building Inspector: Scott Magee        |                                 |                             |                          |                         |                                |  |  |  |  |
|  |                       |                      |   |                          |                         |  |                       |    |    |    |                     |    |    |    |                              | Number: 70016699C                      |                                 |                             |                          |                         |                                |  |  |  |  |
|  |                       |                      |   |                          |                         |  |                       |    |    |    |                     |    |    |    |                              |  |                                 |                             |                          |                         | Management Planner: Megan Vala |  |  |  |  |
|  |                       |                      |   |                          |                         |  |                       |    |    |    |                     |    |    |    |                              |  |                                 |                             |                          |                         | Number: 740728                 |  |  |  |  |
| E<br>l<br>e<br>m<br>e<br>n<br>t  | F<br>l<br>o<br>o<br>r | On-Site Room Name    | System Affected   | Material Description     | HID#                    | Confirmed/Assumed/NAD<br>Non Suspect ACM | Amount of<br>Material | SF | LF | EA | Amount of<br>Damage | SF | LF | EA | Color<br>required for<br>VAT | Comments/Description/Notes             | Attic Crawl<br>Space<br>Ranking | Damage<br>Potential<br>(DP) | Newly<br>Friable<br>(NF) | Response<br>Action (RA) |                                |  |  |  |  |
| 2  | 1                     | Classroom 111        | M   | Floor Tile VAT 9" x 9"   | 7220/02/01/23           | Confirmed                                | 800                   | SF |    |    | 0                   | SF |    |    | Multi                        |  |                                 |                             | 1                        | No                      | 1/D                            |  |  |  |  |
| 2  | 1                     | Classroom 111        | T   | Pipe Fitting Insulation  | 7220/02/01/38           | Confirmed                                | 6                     | EA |    |    | 0                   | EA |    |    |                              |  |                                 |                             | 1                        | No                      | 1/D                            |  |  |  |  |
| 2  | 1                     | Classroom 111        | T   | Pipe Insulation 2-6 inch | 7220/02/01/52           | Confirmed                                | 39                    | LF |    |    | 0                   | LF |    |    |                              |  |                                 |                             | 1                        | No                      | 1/D                            |  |  |  |  |
| 2  | 1                     | Classroom 111        | N/A   | Radiator Insulation      |                         | NAD                                      | 32                    | SF |    |    | 0                   | SF |    |    |                              | Sampled NAD on 11/12/15 (KEM/SM)       |                                 | N/A                         | N/A                      | N/A                     |                                |  |  |  |  |
| 2  | 1                     | Classroom 111 Closet | N/A   | CMU                      |                         | Non Suspect ACM                          | 108                   | SF |    |    | 0                   | SF |    |    |                              |  |                                 | N/A                         | N/A                      | N/A                     |                                |  |  |  |  |
| 2  | 1                     | Classroom 111 Closet | N/A   | Concrete Ceiling         |                         | Non Suspect ACM                          | 54                    | SF |    |    | 0                   | SF |    |    |                              |  |                                 | N/A                         | N/A                      | N/A                     |                                |  |  |  |  |
| 2  | 1                     | Classroom 111 Closet | T   | Floor Tile VAT 9" x 9"   | 7220/02/01/23           | Confirmed                                | 54                    | SF |    |    | 0                   | SF |    |    | Multi                        |  |                                 | 1                           | No                       | 1/D                     |                                |  |  |  |  |
| 2  | 1                     | Classroom 111 Closet | T   | Pipe Insulation 2-6 inch | 7220/02/01/52           | Confirmed                                | 14                    | LF |    |    | 0                   | LF |    |    |                              |  |                                 | 1                           | No                       | 1/D                     |                                |  |  |  |  |
| 2  | 1                     | Classroom 111 Closet | M   | Transite Closet          | 7220/02/01/39           | Assumed                                  | 54                    | SF |    |    | 0                   | SF |    |    |                              |  |                                 | 1                           | No                       | 1/D                     |                                |  |  |  |  |
| 2  | 1                     | Classroom 111 Closet | N/A   | Ceiling Tile 1' x 1'     |                         | NAD                                      | 20                    | SF |    |    | 0                   | SF |    |    |                              |  |                                 | N/A                         | N/A                      | N/A                     |                                |  |  |  |  |
| 2  | 1                     | Classroom 111 Closet | N/A   | CMU                      |                         | Non Suspect ACM                          | 40                    | SF |    |    | 0                   | SF |    |    |                              |  |                                 | N/A                         | N/A                      | N/A                     |                                |  |  |  |  |
| 2  | 1                     | Classroom 111 Closet | N/A   | Concrete Ceiling         |                         | Non Suspect ACM                          | 20                    | SF |    |    | 0                   | SF |    |    |                              |  |                                 | N/A                         | N/A                      | N/A                     |                                |  |  |  |  |
| 2  | 1                     | Classroom 111 Closet | M   | Floor Tile VAT 9" x 9"   | 7220/02/01/23           | Confirmed                                | 20                    | SF |    |    | 0                   | SF |    |    | Black                        |  |                                 | 1                           | No                       | 1/D                     |                                |  |  |  |  |
| 2  | 1                     | Classroom 112        | M   | Blackboard Glue Dots     | 7220/02/01/ACER/SM/2600 | Assumed                                  | 2                     | EA |    |    | 0                   | EA |    |    |                              |  |                                 | 1                           | No                       | 1/D                     |                                |  |  |  |  |
| 2  | 1                     | Classroom 112        | N/A   | CMU                      |                         | Non Suspect ACM                          | 1600                  | SF |    |    | 0                   | SF |    |    |                              |  |                                 | N/A                         | N/A                      | N/A                     |                                |  |  |  |  |
| 2  | 1                     | Classroom 112        | N/A   | Concrete Ceiling         |                         | Non Suspect ACM                          | 800                   | SF |    |    | 0                   | SF |    |    |                              |  |                                 | N/A                         | N/A                      | N/A                     |                                |  |  |  |  |
| 2  | 1                     | Classroom 112        | M   | Floor Tile VAT 9" x 9"   | 7220/02/01/23           | Confirmed                                | 800                   | SF |    |    | 0                   | SF |    |    | Multi                        |  |                                 | 1                           | No                       | 1/D                     |                                |  |  |  |  |
| 2  | 1                     | Classroom 112        | T   | Pipe Fitting Insulation  | 7220/02/01/38           | Confirmed                                | 7                     | EA |    |    | 0                   | EA |    |    |                              |  |                                 | 1                           | No                       | 1/D                     |                                |  |  |  |  |
| 2  | 1                     | Classroom 112        | T   | Pipe Insulation 2-6 inch | 7220/02/01/52           | Confirmed                                | 48                    | LF |    |    | 0                   | LF |    |    |                              |  |                                 | 1                           | No                       | 1/D                     |                                |  |  |  |  |
| 2  | 1                     | Classroom 112        | N/A   | Radiator Insulation      |                         | NAD                                      | 32                    | SF |    |    | 0                   | SF |    |    |                              | Sampled NAD on 11/12/15 (KEM/SM)       |                                 | N/A                         | N/A                      | N/A                     |                                |  |  |  |  |
| 2  | 1                     | Classroom 112 Closet | N/A   | CMU                      |                         | Non Suspect ACM                          | 84                    | SF |    |    | 0                   | SF |    |    |                              |  |                                 | N/A                         | N/A                      | N/A                     |                                |  |  |  |  |
| 2  | 1                     | Classroom 112 Closet | N/A   | Concrete Ceiling         |                         | Non Suspect ACM                          | 42                    | SF |    |    | 0                   | SF |    |    |                              |  |                                 | N/A                         | N/A                      | N/A                     |                                |  |  |  |  |
| 2  | 1                     | Classroom 112 Closet | M   | Floor Tile VAT 9" x 9"   | 7220/02/01/23           | Confirmed                                | 42                    | SF |    |    | 0                   | SF |    |    | Multi                        |  |                                 | 1                           | No                       | 1/D                     |                                |  |  |  |  |
| 2  | 1                     | Classroom 112 Closet | M   | Transite Closet          | 7220/02/01/39           | Assumed                                  | 42                    | SF |    |    | 0                   | SF |    |    |                              |  |                                 | 1                           | No                       | 1/D                     |                                |  |  |  |  |
| 2  | 1                     | Classroom 113        | M   | Blackboard Glue Dots     | 7220/02/01/ACER/SM/2600 | Assumed                                  | 2                     | EA |    |    | 0                   | EA |    |    |                              |  |                                 | 1                           | No                       | 1/D                     |                                |  |  |  |  |
| 2  | 1                     | Classroom 113        | N/A   | CMU                      |                         | Non Suspect ACM                          | 1600                  | SF |    |    | 0                   | SF |    |    |                              |  |                                 | N/A                         | N/A                      | N/A                     |                                |  |  |  |  |
| 2  | 1                     | Classroom 113        | N/A   | Concrete Ceiling         |                         | Non Suspect ACM                          | 800                   | SF |    |    | 0                   | SF |    |    |                              |  |                                 | N/A                         | N/A                      | N/A                     |                                |  |  |  |  |
| 2  | 1                     | Classroom 113        | M   | Floor Tile VAT 9" x 9"   | 7220/02/01/23           | Confirmed                                | 800                   | SF |    |    | 0                   | SF |    |    | Multi                        |  |                                 | 1                           | No                       | 1/D                     |                                |  |  |  |  |
| 2  | 1                     | Classroom 113        | T   | Pipe Fitting Insulation  | 7220/02/01/38           | Confirmed                                | 6                     | EA |    |    | 0                   | EA |    |    |                              |  |                                 | 1                           | No                       | 1/D                     |                                |  |  |  |  |
| 2  | 1                     | Classroom 113        | T   | Pipe Insulation 2-6 inch | 7220/02/01/52           | Confirmed                                | 38                    | LF |    |    | 0                   | LF |    |    |                              |  |                                 | 1                           | No                       | 1/D                     |                                |  |  |  |  |
| 2  | 1                     | Classroom 113        | N/A   | Radiator Insulation      |                         | NAD                                      | 32                    | SF |    |    | 0                   | SF |    |    |                              | Sampled NAD on 11/12/15 (KEM/SM)       |                                 | N/A                         | N/A                      | N/A                     |                                |  |  |  |  |
| 2  | 1                     | Classroom 113 Closet | N/A   | CMU                      |                         | Non Suspect ACM                          | 108                   | SF |    |    | 0                   | SF |    |    |                              |  |                                 | N/A                         | N/A                      | N/A                     |                                |  |  |  |  |
| 2  | 1                     | Classroom 113 Closet | N/A   | Concrete Ceiling         |                         | Non Suspect ACM                          | 54                    | SF |    |    | 0                   | SF |    |    |                              |  |                                 | N/A                         | N/A                      | N/A                     |                                |  |  |  |  |
| 2  | 1                     | Classroom 113 Closet | M   | Floor Tile VAT 9" x 9"   | 7220/02/01/23           | Confirmed                                | 54                    | SF |    |    | 0                   | SF |    |    | Multi                        |  |                                 | 1                           | No                       | 1/D                     |                                |  |  |  |  |
| 2  | 1                     | Classroom 113 Closet | M   | Transite Closet          | 7220/02/01/39           | Assumed                                  | 54                    | SF |    |    | 0                   | SF |    |    |                              |  |                                 | 1                           | No                       | 1/D                     |                                |  |  |  |  |
| 2  | 1                     | Classroom 113 Closet | N/A   | CMU                      |                         | Non Suspect ACM                          | 36                    | SF |    |    | 0                   | SF |    |    |                              |  |                                 | N/A                         | N/A                      | N/A                     |                                |  |  |  |  |
| 2  | 1                     | Classroom 113 Closet | N/A   | Concrete Ceiling         |                         | Non Suspect ACM                          | 18                    | SF |    |    | 0                   | SF |    |    |                              |  |                                 | N/A                         | N/A                      | N/A                     |                                |  |  |  |  |
| 2  | 1                     | Classroom 113 Closet | M   | Floor Tile VAT 9" x 9"   | 7220/02/01/23           | Confirmed                                | 18                    | SF |    |    | 0                   | SF |    |    | Black                        |  |                                 | 1                           | No                       | 1/D                     |                                |  |  |  |  |
| 2  | 1                     | Classroom 113 Closet | T   | Pipe Insulation 2-6 inch | 7220/02/01/52           | Confirmed                                | 24                    | LF |    |    | 0                   | LF |    |    |                              |  |                                 | 1                           | No                       | 1/D                     |                                |  |  |  |  |
| 2  | 1                     | Classroom 113 Closet | N/A   | Ceiling Tile 1' x 1'     |                         | NAD                                      | 18                    | SF |    |    | 2                   | SF |    |    |                              |  |                                 | N/A                         | N/A                      | N/A                     |                                |  |  |  |  |
| 2  | 1                     | Classroom 113 Closet | N/A   | CMU                      |                         | Non Suspect ACM                          | 36                    | SF |    |    | 0                   | SF |    |    |                              |  |                                 | N/A                         | N/A                      | N/A                     |                                |  |  |  |  |
| 2  | 1                     | Classroom 113 Closet | N/A   | Concrete Ceiling         |                         | Non Suspect ACM                          | 18                    | SF |    |    | 0                   | SF |    |    |                              |  |                                 | N/A                         | N/A                      | N/A                     |                                |  |  |  |  |
| 2  | 1                     | Classroom 113 Closet | M   | Floor Tile VAT 9" x 9"   | 7220/02/01/23           | Confirmed                                | 18                    | SF |    |    | 0                   | SF |    |    | Black                        |  |                                 | 1                           | No                       | 1/D                     |                                |  |  |  |  |
| 2  | 1                     | First Floor Hallway  | N/A   | Ceiling Tile 1' x 1'     |                         | NAD                                      | 700                   | SF |    |    | 0                   | SF |    |    |                              |  |                                 | N/A                         | N/A                      | N/A                     |                                |  |  |  |  |
| 2  | 1                     | First Floor Hallway  | N/A   | Ceramic Tile Walls       |                         | Non Suspect ACM                          | 700                   | SF |    |    | 0                   | SF |    |    |                              |  |                                 | N/A                         | N/A                      | N/A                     |                                |  |  |  |  |
| 2  | 1                     | First Floor Hallway  | N/A   | CMU                      |                         | Non Suspect ACM                          | 1400                  | SF |    |    | 0                   | SF |    |    |                              |  |                                 | N/A                         | N/A                      | N/A                     |                                |  |  |  |  |
| 2  | 1                     | First Floor Hallway  | N/A   | Concrete Ceiling         |                         | Non Suspect ACM                          | 700                   | SF |    |    | 0                   | SF |    |    |                              |  |                                 | N/A                         | N/A                      | N/A                     |                                |  |  |  |  |
| 2  | 1                     | First Floor Hallway  | M   | Floor Tile VAT 9" x 9"   | 7220/02/01/23           | Confirmed                                | 700                   | SF |    |    | 0                   | SF |    |    | Multi                        |  |                                 | 1                           | No                       | 1/D                     |                                |  |  |  |  |
| 2  | 1                     | First Floor Hallway  | T   | Pipe Insulation 2-6 inch | 7220/02/01/52           | Confirmed                                | 24                    | LF |    |    | 0                   | LF |    |    |                              |  |                                 | 1                           | No                       | 1/D                     |                                |  |  |  |  |
| 2  | 1                     | First Floor Hallway  | N/A   | Ceiling Tile 1' x 1'     |                         | NAD                                      | 200                   | SF |    |    | 0                   | SF |    |    |                              |  |                                 | N/A                         | N/A                      | N/A                     |                                |  |  |  |  |
| 2  | 1                     | First Floor Hallway  | N/A   | Ceramic Tile Walls       |                         | Non Suspect ACM                          | 200                   | SF |    |    | 0                   | SF |    |    |                              |  |                                 | N/A                         | N/A                      | N/A                     |                                |  |  |  |  |
| 2  | 1                     | First Floor Hallway  | N/A   | CMU                      |                         | Non Suspect ACM                          | 400                   | SF |    |    | 0                   | SF |    |    |                              |  |                                 | N/A                         | N/A                      | N/A                     |                                |  |  |  |  |
| 2  | 1                     | First Floor Hallway  | N/A   | Concrete Ceiling         |                         | Non Suspect ACM                          | 200                   | SF |    |    | 0                   | SF |    |    |                              |  |                                 | N/A                         | N/A                      | N/A                     |                                |  |  |  |  |
| 2  | 1                     | First Floor Hallway  | M   | Floor Tile VAT 9" x 9"   | 7220/02/01/23           | Confirmed                                | 200                   | SF |    |    | 0                   | SF |    |    | Multi                        |  |                                 | 1                           | No                       | 1/D                     |                                |  |  |  |  |
| 2  | 2                     | Classroom 211        | M   | Blackboard Glue Dots     | 7220/02/02/ACER/SM/2600 | Assumed                                  | 2                     | EA |    |    | 0                   | EA |    |    |                              |  |                                 | 1                           | No                       | 1/D                     |                                |  |  |  |  |
| 2  | 2                     | Classroom 211        | N/A   | CMU                      |                         | Non Suspect ACM                          | 1600                  | SF |    |    | 0                   | SF |    |    |                              |  |                                 | N/A                         | N/A                      | N/A                     |                                |  |  |  |  |
| 2  | 2                     | Classroom 211        | N/A   | Concrete Ceiling         |                         | Non Suspect ACM                          | 800                   | SF |    |    | 0                   | SF |    |    |                              |  |                                 | N/A                         | N/A                      | N/A                     |                                |  |  |  |  |
| 2  | 2                     | Classroom 211        | M   | Floor Tile VAT 9" x 9"   | 7220/02/02/46           | Confirmed                                | 800                   | SF |    |    | 0                   | SF |    |    | Multi                        |  |                                 | 1                           | No                       | 1/D                     |                                |  |  |  |  |
| 2  | 2                     | Classroom 211        | T   | Pipe Fitting Insulation  | 7220/02/02/45           | Confirmed                                | 5                     | EA |    |    | 0                   | EA |    |    |                              |  |                                 | 1                           | No                       | 1/D                     |                                |  |  |  |  |
| 2  | 2                     | Classroom 211        | T   | Pipe Insulation 2-6 inch | 7220/02/02/41           | Confirmed                                | 36                    | LF |    |    | 0                   | LF |    |    |                              |  |                                 | 1                           | No                       | 1/D                     |                                |  |  |  |  |
| 2  | 2                     | Classroom 211        | N/A   | Radiator Insulation      |                         | NAD                                      | 32                    | SF |    |    | 3                   | SF |    |    |                              | Sampled NAD on 11/12/15 (KEM/SM)       |                                 | N/A                         | N/A                      | N/A                     |                                |  |  |  |  |
| 2  | 2                     | Classroom 211 Closet | N/A   | CMU                      |                         | Non Suspect ACM                          | 108                   | SF |    |    | 0                   | SF |    |    |                              |  |                                 | N/A                         | N/A                      | N/A                     |                                |  |  |  |  |
| 2  | 2                     | Classroom 211 Closet | N/A   | Concrete Ceiling         |                         | Non Suspect ACM                          | 54                    | SF |    |    | 0                   | SF |    |    |                              |  |                                 | N/A                         | N/A                      | N/A                     |                                |  |  |  |  |
| 2  | 2                     | Classroom 211 Closet | M   | Floor Tile VAT 9" x 9"   | 7220/02/02/46           | Confirmed                                | 54                    | SF |    |    | 0                   | SF |    |    | Multi                        |  |                                 | 1                           | No                       | 1/D                     |                                |  |  |  |  |
| 2  | 2                     | Classroom 211 Closet | T   | Pipe Insulation 2-6 inch | 7220/02/02/41           | Confirmed                                | 12                    | LF |    |    | 0                   | LF |    |    |                              |  |                                 | 1                           | No                       | 1/D                     |                                |  |  |  |  |
| 2  | 2                     | Classroom 211 Closet | M   | Transite Closet          | 7220/02/02/44           | Assumed                                  | 54                    | SF |    |    | 0                   | SF |    |    |                              |  |                                 | 1                           | No                       | 1/D                     |                                |  |  |  |  |
| 2  | 2                     | Classroom 211 Closet | N/A   | Ceiling Tile 1' x 1'     |                         | NAD                                      | 10                    | SF |    |    | 0                   | SF |    |    |                              |  |                                 | N/A                         | N/A                      | N/A                     |                                |  |  |  |  |
| 2  | 2                     | Classroom 211 Closet | N/A   | CMU                      |                         | Non Suspect ACM                          | 40                    | SF |    |    | 0                   | SF |    |    |                              |  |                                 | N/A                         | N/A                      | N/A                     |                                |  |  |  |  |
| 2  | 2                     | Classroom 211 Closet | N/A   | Concrete Ceiling         |                         | Non Suspect ACM                          | 20                    | SF |    |    | 0                   | SF |    |    |                              |  |                                 | N/A                         | N/A                      | N/A                     |                                |  |  |  |  |
| 2  | 2                     | Classroom 211 Closet | M   | Floor Tile VAT 9" x 9"   | 7220/02/02/46           | Confirmed                                | 20                    | SF |    |    | 0                   | SF |    |    | Black                        |  |                                 | 1                           | No                       | 1/D                     |                                |  |  |  |  |
| 2  | 2                     | Classroom 212        | M   | Blackboard Glue Dots     | 7220/02/02/ACER/SM/2600 | Assumed                                  | 2                     | EA |    |    | 0                   | EA |    |    |                              |  |                                 | 1                           | No                       | 1/D                     |                                |  |  |  |  |
| 2  | 2                     | Classroom 212        | N/A   | CMU                      |                         | Non Suspect ACM                          | 1600                  | SF |    |    | 0                   | SF |    |    |                              |  |                                 | N/A                         | N/A                      | N/A                     |                                |  |  |  |  |
| 2  | 2                     | Classroom 212        | N/A   | Concrete Ceiling         |                         | Non Suspect ACM                          | 800                   | SF |    |    | 0                   | SF |    |    |                              |  |                                 | N/A                         | N/A                      | N/A                     |                                |  |  |  |  |
| 2  | 2                     | Classroom 212        | M   | Floor Tile VAT 9" x 9"   | 7220/02/02/46           | Confirmed                                | 800                   | SF |    |    | 0                   | SF |    |    | Multi                        |  |                                 | 1                           | No                       | 1/D                     |                                |  |  |  |  |
| 2  | 2                     | Classroom 212        | T   | Pipe Fitting Insulation  | 7220/02/02/45           | Confirmed                                | 8                     | EA |    |    | 0                   | EA |    |    |                              |  |                                 | 1                           | No                       | 1/D                     |                                |  |  |  |  |
| 2  | 2                     | Classroom 212        | T   | Pipe Insulation 2-6 inch | 7220/02/02/41           | Confirmed                                | 48                    | LF |    |    | 0                   | LF |    |    |                              |  |                                 |                             |                          |                         |                                |  |  |  |  |

# 7220 Carnell ES 2015 2016 AHERA Three-Year Report.xls

| School District of Philadelphia               |                       |                      | AHERA Three-Year Reinspection 2015-2016 |                                   |                         |  |                       |          |                     |          |                              |                                  |                                 |                             |                          | Reinspection Date: October 21-26, 2015 |  |  |  |  |
|---|-----------------------|----------------------|---|-----------------------------------|-------------------------|--|-----------------------|----------|---------------------|----------|------------------------------|----------------------------------|---------------------------------|-----------------------------|--------------------------|--|--|--|--|--|
| Laura H. Carnell Elementary School            |                       |                      | Room by Room Location Log Report        |                                   |                         |  |                       |          |                     |          |                              |                                  |                                 |                             |                          | Building Inspector: Scott Magee        |  |  |  |  |
| 1100 Devereaux Avenue, Philadelphia, PA 19111 |                       |                      |   |                                   |                         |  |                       |          |                     |          |                              |                                  |                                 |                             |                          | Number: 70016699C                      |  |  |  |  |
| ULCS# 7220                                    |                       |                      |   |                                   |                         |  |                       |          |                     |          |                              |                                  |                                 |                             |                          | Management Planner: Megan Vala         |  |  |  |  |
| Year Built: 1931                              |                       |                      |   |                                   |                         |  |                       |          |                     |          |                              |                                  |                                 |                             |                          | Number: 740728                         |  |  |  |  |
| E<br>l<br>e<br>m<br>e<br>n<br>t               | F<br>l<br>o<br>o<br>r | On-Site Room Name    | System Affected                         | Material Description              | HID#                    | Confirmed/Assumed/NAD<br>Non Suspect ACM | Amount of<br>Material | SF<br>EA | Amount of<br>Damage | SF<br>EA | Color<br>required for<br>VAT | Comments/Description/Notes       | Attic Crawl<br>Space<br>Ranking | Damage<br>Potential<br>(DP) | Newly<br>Friable<br>(NF) | Response<br>Action (RA)                |  |  |  |  |
| 2   | 2                     | Classroom 212        | N/A                                     | Radiator Insulation               |                         | NAD                                      | 32                    | SF       | 3                   | SF       |                              | Sampled NAD on 11/12/15 (KEM/SM) |                                 | N/A                         | N/A                      | N/A                                    |  |  |  |  |
| 2   | 2                     | Classroom 212 Closet | N/A                                     | CMU                               |                         | Non Suspect ACM                          | 108                   | SF       | 0                   | SF       |                              |                                  |                                 | N/A                         | N/A                      | N/A                                    |  |  |  |  |
| 2   | 2                     | Classroom 212 Closet | N/A                                     | Concrete Ceiling                  |                         | Non Suspect ACM                          | 54                    | SF       | 0                   | SF       |                              |                                  |                                 | N/A                         | N/A                      | N/A                                    |  |  |  |  |
| 2   | 2                     | Classroom 212 Closet | M                                       | Floor Tile VAT 9" x 9"            | 7220/02/02/46           | Confirmed                                | 54                    | SF       | 0                   | SF       | Multi                        |                                  |                                 | 1                           | No                       | 1/D                                    |  |  |  |  |
| 2   | 2                     | Classroom 212 Closet | M                                       | Transite Closet                   | 7220/02/02/44           | Assumed                                  | 54                    | SF       | 0                   | SF       |                              |                                  |                                 | 1                           | No                       | 1/D                                    |  |  |  |  |
| 2   | 2                     | Classroom 212 Closet | N/A                                     | Ceiling Tile 1' x 1'              |                         | NAD                                      | 20                    | SF       | 0                   | SF       |                              |                                  |                                 | N/A                         | N/A                      | N/A                                    |  |  |  |  |
| 2   | 2                     | Classroom 212 Closet | N/A                                     | CMU                               |                         | Non Suspect ACM                          | 40                    | SF       | 0                   | SF       |                              |                                  |                                 | N/A                         | N/A                      | N/A                                    |  |  |  |  |
| 2   | 2                     | Classroom 212 Closet | N/A                                     | Concrete Ceiling                  |                         | Non Suspect ACM                          | 20                    | SF       | 0                   | SF       |                              |                                  |                                 | N/A                         | N/A                      | N/A                                    |  |  |  |  |
| 2   | 2                     | Classroom 212 Closet | M                                       | Floor Tile VAT 9" x 9"            | 7220/02/02/46           | Confirmed                                | 20                    | SF       | 0                   | SF       | Black                        |                                  |                                 | 1                           | No                       | 1/D                                    |  |  |  |  |
| 2   | 2                     | Classroom 212 Closet | N/A                                     | Ceiling Tile 1' x 1'              |                         | NAD                                      | 20                    | SF       | 0                   | SF       |                              |                                  |                                 | N/A                         | N/A                      | N/A                                    |  |  |  |  |
| 2   | 2                     | Classroom 212 Closet | N/A                                     | CMU                               |                         | Non Suspect ACM                          | 40                    | SF       | 0                   | SF       |                              |                                  |                                 | N/A                         | N/A                      | N/A                                    |  |  |  |  |
| 2   | 2                     | Classroom 212 Closet | N/A                                     | Concrete Ceiling                  |                         | Non Suspect ACM                          | 20                    | SF       | 0                   | SF       |                              |                                  |                                 | N/A                         | N/A                      | N/A                                    |  |  |  |  |
| 2   | 2                     | Classroom 212 Closet | M                                       | Floor Tile VAT 9" x 9"            | 7220/02/02/46           | Confirmed                                | 20                    | SF       | 0                   | SF       | Black                        |                                  |                                 | 1                           | No                       | 1/D                                    |  |  |  |  |
| 2   | 2                     | Classroom 213        | M                                       | Blackboard Glue Dots              | 7220/02/02/ACER/SM/2600 | Assumed                                  | 2                     | EA       | 0                   | EA       |                              |                                  |                                 | 1                           | No                       | 1/D                                    |  |  |  |  |
| 2   | 2                     | Classroom 213        | N/A                                     | CMU                               |                         | Non Suspect ACM                          | 1600                  | SF       | 0                   | SF       |                              |                                  |                                 | N/A                         | N/A                      | N/A                                    |  |  |  |  |
| 2   | 2                     | Classroom 213        | N/A                                     | Concrete Ceiling                  |                         | Non Suspect ACM                          | 800                   | SF       | 0                   | SF       |                              |                                  |                                 | N/A                         | N/A                      | N/A                                    |  |  |  |  |
| 2   | 2                     | Classroom 213        | M                                       | Floor Tile VAT 9" x 9"            | 7220/02/02/46           | Confirmed                                | 800                   | SF       | 0                   | SF       | Multi                        |                                  |                                 | 1                           | No                       | 1/D                                    |  |  |  |  |
| 2   | 2                     | Classroom 213        | T                                       | Pipe Fitting Insulation           | 7220/02/02/45           | Confirmed                                | 6                     | EA       | 0                   | EA       |                              |                                  |                                 | 1                           | No                       | 1/D                                    |  |  |  |  |
| 2   | 2                     | Classroom 213        | T                                       | Pipe Insulation 2-6 inch          | 7220/02/02/41           | Confirmed                                | 36                    | LF       | 0                   | LF       |                              |                                  |                                 | 1                           | No                       | 1/D                                    |  |  |  |  |
| 2   | 2                     | Classroom 213        | N/A                                     | Radiator Insulation               |                         | NAD                                      | 32                    | SF       | 32                  | SF       |                              | Sampled NAD on 11/12/15 (KEM/SM) |                                 | N/A                         | N/A                      | N/A                                    |  |  |  |  |
| 2   | 2                     | Classroom 213 Closet | N/A                                     | CMU                               |                         | Non Suspect ACM                          | 108                   | SF       | 0                   | SF       |                              |                                  |                                 | N/A                         | N/A                      | N/A                                    |  |  |  |  |
| 2   | 2                     | Classroom 213 Closet | N/A                                     | Concrete Ceiling                  |                         | Non Suspect ACM                          | 54                    | SF       | 0                   | SF       |                              |                                  |                                 | N/A                         | N/A                      | N/A                                    |  |  |  |  |
| 2   | 2                     | Classroom 213 Closet | M                                       | Floor Tile VAT 9" x 9"            | 7220/02/02/46           | Confirmed                                | 54                    | SF       | 0                   | SF       | Multi                        |                                  |                                 | 1                           | No                       | 1/D                                    |  |  |  |  |
| 2   | 2                     | Classroom 213 Closet | M                                       | Transite Closet                   | 7220/02/02/44           | Assumed                                  | 54                    | SF       | 0                   | SF       |                              |                                  |                                 | 1                           | No                       | 1/D                                    |  |  |  |  |
| 2   | 2                     | Storage Room         | N/A                                     | CMU                               |                         | Non Suspect ACM                          | 192                   | SF       | 0                   | SF       |                              |                                  |                                 | N/A                         | N/A                      | N/A                                    |  |  |  |  |
| 2   | 2                     | Storage Room         | N/A                                     | Concrete Ceiling                  |                         | Non Suspect ACM                          | 96                    | SF       | 0                   | SF       |                              |                                  |                                 | N/A                         | N/A                      | N/A                                    |  |  |  |  |
| 2   | 2                     | Storage Room         | M                                       | Floor Tile VAT 9" x 9"            | 7220/02/02/46           | Confirmed                                | 96                    | SF       | 0                   | SF       | Brown                        |                                  |                                 | 1                           | No                       | 1/D                                    |  |  |  |  |
| 2   | 2                     | Storage Room         | T                                       | Pipe Fitting Insulation           | 7220/02/02/45           | Confirmed                                | 4                     | EA       | 0                   | EA       |                              |                                  |                                 | 1                           | No                       | 1/D                                    |  |  |  |  |
| 2   | 2                     | Storage Room         | T                                       | Pipe Insulation 2-6 inch          | 7220/02/02/41           | Confirmed                                | 26                    | LF       | 0                   | LF       |                              |                                  |                                 | 1                           | No                       | 1/D                                    |  |  |  |  |
| 2   | 3                     | Classroom 312        | M                                       | Blackboard Glue Dots              | 7220/02/03/ACER/SM/2600 | Assumed                                  | 2                     | EA       | 0                   | EA       |                              |                                  |                                 | 1                           | No                       | 1/D                                    |  |  |  |  |
| 2   | 3                     | Classroom 312        | N/A                                     | CMU                               |                         | Non Suspect ACM                          | 1600                  | SF       | 0                   | SF       |                              |                                  |                                 | N/A                         | N/A                      | N/A                                    |  |  |  |  |
| 2   | 3                     | Classroom 312        | N/A                                     | Concrete Ceiling                  |                         | Non Suspect ACM                          | 800                   | SF       | 0                   | SF       |                              |                                  |                                 | N/A                         | N/A                      | N/A                                    |  |  |  |  |
| 2   | 3                     | Classroom 312        | M                                       | Floor Tile VAT 9" x 9"            | 7220/02/03/60           | Confirmed                                | 800                   | SF       | 0                   | SF       | Multi                        |                                  |                                 | 1                           | No                       | 1/D                                    |  |  |  |  |
| 2   | 3                     | Classroom 312        | T                                       | Pipe Fitting Insulation           | 7220/02/03/61           | Confirmed                                | 1                     | EA       | 0                   | EA       |                              |                                  |                                 | 1                           | No                       | 1/D                                    |  |  |  |  |
| 2   | 3                     | Classroom 312        | T                                       | Pipe Insulation > 6 inch          | 7220/02/03/ACER/SM/1110 | Confirmed                                | 37                    | LF       | 0                   | LF       |                              |                                  |                                 | 1                           | No                       | 1/D                                    |  |  |  |  |
| 2   | 3                     | Classroom 312        | N/A                                     | Radiator Insulation               |                         | NAD                                      | 32                    | SF       | 0                   | SF       |                              | Sampled NAD on 11/12/15 (KEM/SM) |                                 | N/A                         | N/A                      | N/A                                    |  |  |  |  |
| 2   | 3                     | Classroom 312 Closet | N/A                                     | CMU                               |                         | Non Suspect ACM                          | 108                   | SF       | 0                   | SF       |                              |                                  |                                 | N/A                         | N/A                      | N/A                                    |  |  |  |  |
| 2   | 3                     | Classroom 312 Closet | N/A                                     | Concrete Ceiling                  |                         | Non Suspect ACM                          | 54                    | SF       | 0                   | SF       |                              |                                  |                                 | N/A                         | N/A                      | N/A                                    |  |  |  |  |
| 2   | 3                     | Classroom 312 Closet | M                                       | Floor Tile VAT 9" x 9"            | 7220/02/03/60           | Confirmed                                | 54                    | SF       | 0                   | SF       | Multi                        |                                  |                                 | 1                           | No                       | 1/D                                    |  |  |  |  |
| 2   | 3                     | Classroom 312 Closet | T                                       | Pipe Insulation 2-6 inch          | 7220/02/03/56           | Confirmed                                | 6                     | LF       | 0                   | LF       |                              |                                  |                                 | 1                           | No                       | 1/D                                    |  |  |  |  |
| 2   | 3                     | Classroom 312 Closet | M                                       | Transite Closet                   | 7220/02/03/59           | Assumed                                  | 54                    | SF       | 0                   | SF       |                              |                                  |                                 | 1                           | No                       | 1/D                                    |  |  |  |  |
| 2   | 3                     | Classroom 312 Closet | N/A                                     | CMU                               |                         | Non Suspect ACM                          | 40                    | SF       | 0                   | SF       |                              |                                  |                                 | N/A                         | N/A                      | N/A                                    |  |  |  |  |
| 2   | 3                     | Classroom 312 Closet | N/A                                     | Concrete Ceiling                  |                         | Non Suspect ACM                          | 20                    | SF       | 0                   | SF       |                              |                                  |                                 | N/A                         | N/A                      | N/A                                    |  |  |  |  |
| 2   | 3                     | Classroom 312 Closet | M                                       | Floor Tile VAT 9" x 9"            | 7220/02/03/60           | Confirmed                                | 20                    | SF       | 0                   | SF       | Black                        |                                  |                                 | 1                           | No                       | 1/D                                    |  |  |  |  |
| 2   | 3                     | Classroom 312 Closet | N/A                                     | CMU                               |                         | Non Suspect ACM                          | 40                    | SF       | 0                   | SF       |                              |                                  |                                 | N/A                         | N/A                      | N/A                                    |  |  |  |  |
| 2   | 3                     | Classroom 312 Closet | N/A                                     | Concrete Ceiling                  |                         | Non Suspect ACM                          | 20                    | SF       | 0                   | SF       |                              |                                  |                                 | N/A                         | N/A                      | N/A                                    |  |  |  |  |
| 2   | 3                     | Classroom 312 Closet | M                                       | Floor Tile VAT 9" x 9"            | 7220/02/03/60           | Confirmed                                | 20                    | SF       | 0                   | SF       | Black                        |                                  |                                 | 1                           | No                       | 1/D                                    |  |  |  |  |
| 2   | 3                     | Classroom 313        | M                                       | Blackboard Glue Dots              | 7220/02/03/ACER/SM/2600 | Assumed                                  | 2                     | EA       | 0                   | EA       |                              |                                  |                                 | 1                           | No                       | 1/D                                    |  |  |  |  |
| 2   | 3                     | Classroom 313        | N/A                                     | CMU                               |                         | Non Suspect ACM                          | 1600                  | SF       | 0                   | SF       |                              |                                  |                                 | N/A                         | N/A                      | N/A                                    |  |  |  |  |
| 2   | 3                     | Classroom 313        | N/A                                     | Concrete Ceiling                  |                         | Non Suspect ACM                          | 800                   | SF       | 0                   | SF       |                              |                                  |                                 | N/A                         | N/A                      | N/A                                    |  |  |  |  |
| 2   | 3                     | Classroom 313        | M                                       | Floor Tile VAT 9" x 9"            | 7220/02/03/60           | Confirmed                                | 800                   | SF       | 0                   | SF       | Multi                        |                                  |                                 | 1                           | No                       | 1/D                                    |  |  |  |  |
| 2   | 3                     | Classroom 313        | T                                       | Pipe Fitting Insulation           | 7220/02/03/61           | Confirmed                                | 3                     | EA       | 0                   | EA       |                              |                                  |                                 | 1                           | No                       | 1/D                                    |  |  |  |  |
| 2   | 3                     | Classroom 313        | T                                       | Pipe Insulation > 6 inch          | 7220/02/03/ACER/SM/1110 | Confirmed                                | 37                    | LF       | 0                   | LF       |                              |                                  |                                 | 1                           | No                       | 1/D                                    |  |  |  |  |
| 2   | 3                     | Classroom 313        | N/A                                     | Radiator Insulation               |                         | NAD                                      | 32                    | SF       | 2                   | SF       |                              | Sampled NAD on 11/12/15 (KEM/SM) |                                 | N/A                         | N/A                      | N/A                                    |  |  |  |  |
| 2   | 3                     | Classroom 313        | N/A                                     | Tar Paper a/w Radiator Insualtion |                         | NAD                                      | X                     | X        | X                   | X        |                              | Sampled NAD on 11/12/15 (KEM/SM) |                                 | N/A                         | N/A                      | N/A                                    |  |  |  |  |
| 2   | 3                     | Men's Restroom       | N/A                                     | Cement Floor                      |                         | Non Suspect ACM                          | 162                   | SF       | 0                   | SF       |                              |                                  |                                 | N/A                         | N/A                      | N/A                                    |  |  |  |  |
| 2   | 3                     | Men's Restroom       | N/A                                     | Ceramic Tile Walls                |                         | Non Suspect ACM                          | 324                   | SF       | 0                   | SF       |                              |                                  |                                 | N/A                         | N/A                      | N/A                                    |  |  |  |  |
| 2   | 3                     | Men's Restroom       | N/A                                     | CMU                               |                         | Non Suspect ACM                          | 324                   | SF       | 0                   | SF       |                              |                                  |                                 | N/A                         | N/A                      | N/A                                    |  |  |  |  |
| 2   | 3                     | Men's Restroom       | N/A                                     | Concrete Ceiling                  |                         | Non Suspect ACM                          | 162                   | SF       | 0                   | SF       |                              |                                  |                                 | N/A                         | N/A                      | N/A                                    |  |  |  |  |
| 2   | 3                     | Men's Restroom       | T                                       | Pipe Fitting Insulation           | 7220/02/03/61           | Confirmed                                | 10                    | EA       | 0                   | EA       |                              |                                  |                                 | 1                           | No                       | 1/D                                    |  |  |  |  |
| 2   | 3                     | Men's Restroom       | T                                       | Pipe Insulation 2-6 inch          | 7220/02/03/56           | Confirmed                                | 53                    | LF       | 0                   | LF       |                              |                                  |                                 | 1                           | No                       | 1/D                                    |  |  |  |  |
| 2   | 3                     | Classroom 313 Closet | N/A                                     | CMU                               |                         | Non Suspect ACM                          | 108                   | SF       | 0                   | SF       |                              |                                  |                                 | N/A                         | N/A                      | N/A                                    |  |  |  |  |
| 2   | 3                     | Classroom 313 Closet | N/A                                     | Concrete Ceiling                  |                         | Non Suspect ACM                          | 54                    | SF       | 0                   | SF       |                              |                                  |                                 | N/A                         | N/A                      | N/A                                    |  |  |  |  |
| 2   | 3                     | Classroom 313 Closet | M                                       | Floor Tile VAT 9" x 9"            | 7220/02/03/60           | Confirmed                                | 54                    | SF       | 0                   | SF       | Multi                        |                                  |                                 | 1                           | No                       | 1/D                                    |  |  |  |  |
| 2   | 3                     | Classroom 313 Closet | M                                       | Transite Closet                   | 7220/02/03/59           | Assumed                                  | 54                    | SF       | 0                   | SF       |                              |                                  |                                 | 1                           | No                       | 1/D                                    |  |  |  |  |
| 2   | 3                     | Classroom 313 Closet | N/A                                     | Ceiling Tile 1' x 1'              |                         | NAD                                      | 20                    | SF       | 0                   | SF       |                              |                                  |                                 | N/A                         | N/A                      | N/A                                    |  |  |  |  |
| 2   | 3                     | Classroom 313 Closet | N/A                                     | CMU                               |                         | Non Suspect ACM                          | 40                    | SF       | 0                   | SF       |                              |                                  |                                 | N/A                         | N/A                      | N/A                                    |  |  |  |  |
| 2   | 3                     | Classroom 313 Closet | N/A                                     | Concrete Ceiling                  |                         | Non Suspect ACM                          | 20                    | SF       | 0                   | SF       |                              |                                  |                                 | N/A                         | N/A                      | N/A                                    |  |  |  |  |
| 2   | 3                     | Classroom 313 Closet | M                                       | Floor Tile VAT 9" x 9"            | 7220/02/03/60           | Confirmed                                | 20                    | SF       | 0                   | SF       | Black                        |                                  |                                 | 1                           | No                       | 1/D                                    |  |  |  |  |
| 2   | 3                     | Classroom 313 Closet | N/A                                     | Ceiling Tile 1' x 1'              |                         | NAD                                      | 20                    | SF       | 0                   | SF       |                              |                                  |                                 | N/A                         | N/A                      | N/A                                    |  |  |  |  |
| 2   | 3                     | Classroom 313 Closet | N/A                                     | CMU                               |                         | Non Suspect ACM                          | 40                    | SF       | 0                   | SF       |                              |                                  |                                 | N/A                         | N/A                      | N/A                                    |  |  |  |  |
| 2   | 3                     | Classroom 313 Closet | N/A                                     | Concrete Ceiling                  |                         | Non Suspect ACM                          | 20                    | SF       | 0                   | SF       |                              |                                  |                                 | N/A                         | N/A                      | N/A                                    |  |  |  |  |
| 2   | 3                     | Classroom 313 Closet | M                                       | Floor Tile VAT 9" x 9"            | 7220/02/03/60           | Confirmed                                | 20                    | SF       | 0                   | SF       | Black                        |                                  |                                 | 1                           | No                       | 1/D                                    |  |  |  |  |
| 2   | 3                     | Classroom 313 Closet | T                                       | Pipe Insulation > 6 inch          | 7220/02/03/ACER/SM/1110 | Confirmed                                | 4                     | LF       | 0                   | LF       |                              |                                  |                                 | 1                           | No                       | 1/D                                    |  |  |  |  |
| 2   | 3                     | Classroom 314        | M                                       | Blackboard Glue Dots              | 7220/02/03/ACER/SM/2600 | Assumed                                  | 2                     | EA       | 0                   | EA       |                              |                                  |                                 | 1                           | No                       | 1/D                                    |  |  |  |  |
| 2   | 3                     | Classroom 314        | N/A                                     | CMU                               |                         | Non Suspect ACM                          | 1600                  | SF       | 0                   | SF       |                              |                                  |                                 | N/A                         | N/A                      | N/A                                    |  |  |  |  |

# 7220 Carnell ES 2015 2016 AHERA Three-Year Report.xls

| School District of Philadelphia               |                       |                        | AHERA Three-Year Reinspection 2015-2016 |                                   |                         |  |                       |    |    |    |                     |    |    |    |                              | Reinspection Date: October 21-26, 2015 |                                 |                             |                          |                         |     |
|---|-----------------------|------------------------|---|-----------------------------------|-------------------------|--|-----------------------|----|----|----|---------------------|----|----|----|------------------------------|--|---------------------------------|-----------------------------|--------------------------|-------------------------|-----|
| Laura H. Carnell Elementary School            |                       |                        | Room by Room Location Log Report        |                                   |                         |  |                       |    |    |    |                     |    |    |    |                              | Building Inspector: Scott Magee        |                                 |                             |                          |                         |     |
| 1100 Devereaux Avenue, Philadelphia, PA 19111 |                       |                        |   |                                   |                         |  |                       |    |    |    |                     |    |    |    |                              | Number: 70016699C                      |                                 |                             |                          |                         |     |
| ULCS# 7220                                    |                       |                        |   |                                   |                         |  |                       |    |    |    |                     |    |    |    |                              | Management Planner: Megan Vala         |                                 |                             |                          |                         |     |
| Year Built: 1931                              |                       |                        |   |                                   |                         |  |                       |    |    |    |                     |    |    |    |                              | Number: 740728                         |                                 |                             |                          |                         |     |
| E<br>l<br>e<br>m<br>e<br>n<br>t               | F<br>l<br>o<br>o<br>r | On-Site Room Name      | System Affected                         | Material Description              | HID#                    | Confirmed/Assumed/NAD<br>Non Suspect ACM | Amount of<br>Material | SF | LF | EA | Amount of<br>Damage | SF | LF | EA | Color<br>required for<br>VAT | Comments/Description/Notes             | Attic Crawl<br>Space<br>Ranking | Damage<br>Potential<br>(DP) | Newly<br>Friable<br>(NF) | Response<br>Action (RA) |     |
|   |                       |                        |   |                                   |                         |  |                       |    |    |    |                     |    |    |    |                              |  |                                 |                             |                          |                         |     |
| 2   | 3                     | Classroom 314          | N/A                                     | Concrete Ceiling                  |                         | Non Suspect ACM                          | 800                   | SF |    |    | 0                   | SF |    |    |                              |  |                                 |                             | N/A                      | N/A                     | N/A |
| 2   | 3                     | Classroom 314          | M                                       | Floor Tile VAT 9" x 9"            | 7220/02/03/60           | Confirmed                                | 800                   | SF |    |    | 0                   | SF |    |    | Multi                        |  |                                 |                             | 1                        | No                      | 1/D |
| 2   | 3                     | Classroom 314          | N/A                                     | Radiator Insulation               |                         | NAD                                      | 32                    | SF |    |    | 0                   | SF |    |    |                              | Sampled NAD on 11/12/15 (KEM/SM)       |                                 |                             | N/A                      | N/A                     | N/A |
| 2   | 3                     | Classroom 314          | N/A                                     | Tar Paper a/w Radiator Insulation |                         | NAD                                      | X                     | X  | X  | X  |                     |    |    |    |                              | Sampled NAD on 11/12/15 (KEM/SM)       |                                 |                             | N/A                      | N/A                     | N/A |
| 2   | 3                     | Classroom 314 Closet   | N/A                                     | CMU                               |                         | Non Suspect ACM                          | 108                   | SF |    |    | 0                   | SF |    |    |                              |  |                                 |                             | N/A                      | N/A                     | N/A |
| 2   | 3                     | Classroom 314 Closet   | N/A                                     | Concrete Ceiling                  |                         | Non Suspect ACM                          | 54                    | SF |    |    | 0                   | SF |    |    |                              |  |                                 |                             | N/A                      | N/A                     | N/A |
| 2   | 3                     | Classroom 314 Closet   | M                                       | Floor Tile VAT 9" x 9"            | 7220/02/03/60           | Confirmed                                | 54                    | SF |    |    | 0                   | SF |    |    | Multi                        |  |                                 |                             | 1                        | No                      | 1/D |
| 2   | 3                     | Classroom 314 Closet   | M                                       | Transite Closet                   | 7220/02/03/59           | Assumed                                  | 54                    | SF |    |    | 0                   | SF |    |    |                              |  |                                 |                             | 1                        | No                      | 1/D |
| 2   | 3                     | Classroom 314 Closet   | N/A                                     | Ceiling Tile 1' x 1'              |                         | NAD                                      | 20                    | SF |    |    | 0                   | SF |    |    |                              |  |                                 |                             | N/A                      | N/A                     | N/A |
| 2   | 3                     | Classroom 314 Closet   | N/A                                     | CMU                               |                         | Non Suspect ACM                          | 40                    | SF |    |    | 0                   | SF |    |    |                              |  |                                 |                             | N/A                      | N/A                     | N/A |
| 2   | 3                     | Classroom 314 Closet   | N/A                                     | Concrete Ceiling                  |                         | Non Suspect ACM                          | 20                    | SF |    |    | 0                   | SF |    |    |                              |  |                                 |                             | N/A                      | N/A                     | N/A |
| 2   | 3                     | Classroom 314 Closet   | M                                       | Floor Tile VAT 9" x 9"            | 7220/02/03/60           | Confirmed                                | 20                    | SF |    |    | 0                   | SF |    |    | Black                        |  |                                 |                             | 1                        | No                      | 1/D |
| 2   | 3                     | Classroom 314 Closet   | T                                       | Pipe Insulation 2-6 inch          | 7220/02/03/56           | Confirmed                                | 8                     | LF |    |    | 0                   | LF |    |    |                              |  |                                 |                             | 1                        | No                      | 1/D |
| 2   | 3                     | Classroom 314 Closet   | N/A                                     | Ceiling Tile 1' x 1'              |                         | NAD                                      | 20                    | SF |    |    | 0                   | SF |    |    |                              |  |                                 |                             | N/A                      | N/A                     | N/A |
| 2   | 3                     | Classroom 314 Closet   | N/A                                     | CMU                               |                         | Non Suspect ACM                          | 40                    | SF |    |    | 0                   | SF |    |    |                              |  |                                 |                             | N/A                      | N/A                     | N/A |
| 2   | 3                     | Classroom 314 Closet   | N/A                                     | Concrete Ceiling                  |                         | Non Suspect ACM                          | 20                    | SF |    |    | 0                   | SF |    |    |                              |  |                                 |                             | N/A                      | N/A                     | N/A |
| 2   | 3                     | Classroom 314 Closet   | M                                       | Floor Tile VAT 9" x 9"            | 7220/02/03/60           | Confirmed                                | 20                    | SF |    |    | 0                   | SF |    |    | Black                        |  |                                 |                             | 1                        | No                      | 1/D |
| 2   | 3                     | Storage Room           | N/A                                     | CMU                               |                         | Non Suspect ACM                          | 126                   | SF |    |    | 0                   | SF |    |    |                              |  |                                 |                             | N/A                      | N/A                     | N/A |
| 2   | 3                     | Storage Room           | N/A                                     | Concrete Ceiling                  |                         | Non Suspect ACM                          | 63                    | SF |    |    | 0                   | SF |    |    |                              |  |                                 |                             | N/A                      | N/A                     | N/A |
| 2   | 3                     | Storage Room           | M                                       | Floor Tile VAT 9" x 9"            | 7220/02/03/60           | Confirmed                                | 63                    | SF |    |    | 0                   | SF |    |    | Brown                        |  |                                 |                             | 1                        | No                      | 1/D |
| 2   | 3                     | Storage Room           | N/A                                     | CMU                               |                         | Non Suspect ACM                          | 126                   | SF |    |    | 0                   | SF |    |    |                              |  |                                 |                             | N/A                      | N/A                     | N/A |
| 2   | 3                     | Storage Room           | N/A                                     | Concrete Ceiling                  |                         | Non Suspect ACM                          | 63                    | SF |    |    | 0                   | SF |    |    |                              |  |                                 |                             | N/A                      | N/A                     | N/A |
| 2   | 3                     | Storage Room           | M                                       | Floor Tile VAT 9" x 9"            | 7220/02/03/60           | Confirmed                                | 63                    | SF |    |    | 0                   | SF |    |    | Brown                        |  |                                 |                             | 1                        | No                      | 1/D |
| 2   | 3                     | Storage Room           | N/A                                     | CMU                               |                         | Non Suspect ACM                          | 126                   | SF |    |    | 0                   | SF |    |    |                              |  |                                 |                             | N/A                      | N/A                     | N/A |
| 2   | 3                     | Storage Room           | N/A                                     | Concrete Ceiling                  |                         | Non Suspect ACM                          | 63                    | SF |    |    | 0                   | SF |    |    |                              |  |                                 |                             | N/A                      | N/A                     | N/A |
| 2   | 3                     | Storage Room           | M                                       | Floor Tile VAT 9" x 9"            | 7220/02/03/60           | Confirmed                                | 63                    | SF |    |    | 0                   | SF |    |    | Brown                        |  |                                 |                             | 1                        | No                      | 1/D |
| 2   | 3                     | Third Floor Hallway    | N/A                                     | Ceiling Tile 1' x 1'              |                         | NAD                                      | 700                   | SF |    |    | 0                   | SF |    |    |                              |  |                                 |                             | N/A                      | N/A                     | N/A |
| 2   | 3                     | Third Floor Hallway    | N/A                                     | Ceramic Tile Walls                |                         | Non Suspect ACM                          | 700                   | SF |    |    | 0                   | SF |    |    |                              |  |                                 |                             | N/A                      | N/A                     | N/A |
| 2   | 3                     | Third Floor Hallway    | N/A                                     | CMU                               |                         | Non Suspect ACM                          | 1400                  | SF |    |    | 0                   | SF |    |    |                              |  |                                 |                             | N/A                      | N/A                     | N/A |
| 2   | 3                     | Third Floor Hallway    | N/A                                     | Concrete Ceiling                  |                         | Non Suspect ACM                          | 700                   | SF |    |    | 0                   | SF |    |    |                              |  |                                 |                             | N/A                      | N/A                     | N/A |
| 2   | 3                     | Third Floor Hallway    | T                                       | Floor Tile VAT 9" x 9"            | 7220/02/03/60           | Confirmed                                | 700                   | SF |    |    | 0                   | SF |    |    | Multi                        |  |                                 |                             | 1                        | No                      | 1/D |
| 2   | 3                     | Third Floor Hallway    | M                                       | Pipe Insulation 2-6 inch          | 7220/02/03/56           | Confirmed                                | 12                    | LF |    |    | 0                   | LF |    |    |                              |  |                                 |                             | 1                        | No                      | 1/D |
| 2   | 3                     | Third Floor Hallway    | N/A                                     | Ceiling Tile 1' x 1'              |                         | NAD                                      | 200                   | SF |    |    | 0                   | SF |    |    |                              |  |                                 |                             | N/A                      | N/A                     | N/A |
| 2   | 3                     | Third Floor Hallway    | N/A                                     | Ceramic Tile Walls                |                         | Non Suspect ACM                          | 200                   | SF |    |    | 0                   | SF |    |    |                              |  |                                 |                             | N/A                      | N/A                     | N/A |
| 2   | 3                     | Third Floor Hallway    | N/A                                     | CMU                               |                         | Non Suspect ACM                          | 400                   | SF |    |    | 0                   | SF |    |    |                              |  |                                 |                             | N/A                      | N/A                     | N/A |
| 2   | 3                     | Third Floor Hallway    | N/A                                     | Concrete Ceiling                  |                         | Non Suspect ACM                          | 200                   | SF |    |    | 0                   | SF |    |    |                              |  |                                 |                             | N/A                      | N/A                     | N/A |
| 2   | 3                     | Third Floor Hallway    | M                                       | Floor Tile VAT 9" x 9"            | 7220/02/03/60           | Confirmed                                | 200                   | SF |    |    | 0                   | SF |    |    | Multi                        |  |                                 |                             | 1                        | No                      | 1/D |
| 2   | 3                     | Custodial Closet       | N/A                                     | CMU                               |                         | Non Suspect ACM                          | 100                   | SF |    |    | 0                   | SF |    |    |                              |  |                                 |                             | N/A                      | N/A                     | N/A |
| 2   | 3                     | Custodial Closet       | N/A                                     | Concrete Ceiling                  |                         | Non Suspect ACM                          | 50                    | SF |    |    | 0                   | SF |    |    |                              |  |                                 |                             | N/A                      | N/A                     | N/A |
| 2   | 3                     | Custodial Closet       | M                                       | Floor Tile VAT 9" x 9"            | 7220/02/03/60           | Confirmed                                | 50                    | SF |    |    | 0                   | SF |    |    | Brown                        |  |                                 |                             | 1                        | No                      | 1/D |
| 2   | B                     | Classroom 005          | M                                       | Blackboard Glue Dots              | 7220/02/08/ACER/SM/2600 | Assumed                                  | 2                     | EA |    |    | 0                   | EA |    |    |                              |  |                                 |                             | 1                        | No                      | 1/D |
| 2   | B                     | Classroom 005          | N/A                                     | CMU                               |                         | Non Suspect ACM                          | 1600                  | SF |    |    | 0                   | SF |    |    |                              |  |                                 |                             | N/A                      | N/A                     | N/A |
| 2   | B                     | Classroom 005          | N/A                                     | Concrete Ceiling                  |                         | Non Suspect ACM                          | 800                   | SF |    |    | 0                   | SF |    |    |                              |  |                                 |                             | N/A                      | N/A                     | N/A |
| 2   | B                     | Classroom 005          | N/A                                     | Fiberglass Pipe Insulation        |                         | Non Suspect ACM                          | 106                   | LF |    |    | 0                   | LF |    |    |                              |  |                                 |                             | N/A                      | N/A                     | N/A |
| 2   | B                     | Classroom 005          | M                                       | Floor Tile VAT 9" x 9"            | 7220/02/08/31           | Confirmed                                | 800                   | SF |    |    | 0                   | SF |    |    | Multi                        |  |                                 |                             | 1                        | No                      | 1/D |
| 2   | B                     | Classroom 005          | T                                       | Pipe Fitting Insulation           | 7220/02/08/51           | Confirmed                                | 6                     | EA |    |    | 0                   | EA |    |    |                              |  |                                 |                             | 1                        | No                      | 1/D |
| 2   | B                     | Classroom 005          | T                                       | Pipe Insulation 2-6 inch          | 7220/02/08/40           | Confirmed                                | 32                    | LF |    |    | 0                   | LF |    |    |                              |  |                                 |                             | 1                        | No                      | 1/D |
| 2   | B                     | Classroom 005          | N/A                                     | Radiator Insulation               |                         | NAD                                      | 32                    | SF |    |    | 0                   | SF |    |    |                              | Sampled NAD on 11/12/15 (KEM/SM)       |                                 |                             | N/A                      | N/A                     | N/A |
| 2   | B                     | Classroom 5 Closet     | N/A                                     | CMU                               |                         | Non Suspect ACM                          | 108                   | SF |    |    | 0                   | SF |    |    |                              |  |                                 |                             | N/A                      | N/A                     | N/A |
| 2   | B                     | Classroom 5 Closet     | N/A                                     | Concrete Ceiling                  |                         | Non Suspect ACM                          | 54                    | SF |    |    | 0                   | SF |    |    |                              |  |                                 |                             | N/A                      | N/A                     | N/A |
| 2   | B                     | Classroom 5 Closet     | M                                       | Floor Tile VAT 9" x 9"            | 7220/02/08/31           | Confirmed                                | 54                    | SF |    |    | 0                   | SF |    |    | Multi                        |  |                                 |                             | 1                        | No                      | 1/D |
| 2   | B                     | Classroom 5 Closet     | T                                       | Pipe Fitting Insulation           | 7220/02/08/51           | Confirmed                                | 3                     | EA |    |    | 0                   | EA |    |    |                              |  |                                 |                             | 1                        | No                      | 1/D |
| 2   | B                     | Classroom 5 Closet     | T                                       | Pipe Insulation 2-6 inch          | 7220/02/08/40           | Confirmed                                | 18                    | LF |    |    | 1                   | LF |    |    |                              |  |                                 |                             | 1                        | Yes                     | 5/A |
| 2   | B                     | Classroom 5 Closet     | M                                       | Transite Closet                   | 7220/02/08/33           | Assumed                                  | 54                    | SF |    |    | 0                   | SF |    |    |                              |  |                                 |                             | 1                        | No                      | 1/D |
| 2   | B                     | Classroom 5 Closet     | N/A                                     | Ceiling Tile 1' x 1'              |                         | NAD                                      | 20                    | SF |    |    | 20                  | SF |    |    |                              |  |                                 |                             | N/A                      | N/A                     | N/A |
| 2   | B                     | Classroom 5 Closet     | N/A                                     | CMU                               |                         | Non Suspect ACM                          | 40                    | SF |    |    | 0                   | SF |    |    |                              |  |                                 |                             | N/A                      | N/A                     | N/A |
| 2   | B                     | Classroom 5 Closet     | N/A                                     | Concrete Ceiling                  |                         | Non Suspect ACM                          | 20                    | SF |    |    | 0                   | SF |    |    |                              |  |                                 |                             | N/A                      | N/A                     | N/A |
| 2   | B                     | Classroom 5 Closet     | M                                       | Floor Tile VAT 9" x 9"            | 7220/02/08/31           | Confirmed                                | 20                    | SF |    |    | 0                   | SF |    |    | Multi                        |  |                                 |                             | 1                        | No                      | 1/D |
| 2   | B                     | Classroom 005 Restroom | N/A                                     | Ceramic Tile Floors               |                         | Non Suspect ACM                          | 42                    | SF |    |    | 0                   | SF |    |    |                              |  |                                 |                             | N/A                      | N/A                     | N/A |
| 2   | B                     | Classroom 005 Restroom | N/A                                     | CMU                               |                         | Non Suspect ACM                          | 42                    | SF |    |    | 0                   | SF |    |    |                              |  |                                 |                             | N/A                      | N/A                     | N/A |
| 2   | B                     | Classroom 005 Restroom | N/A                                     | Concrete Ceiling                  |                         | Non Suspect ACM                          | 42                    | SF |    |    | 0                   | SF |    |    |                              |  |                                 |                             | N/A                      | N/A                     | N/A |
| 2   | B                     | Classroom 005 Restroom | N/A                                     | Fiberglass Pipe Insulation        |                         | Non Suspect ACM                          | 48                    | LF |    |    | 0                   | LF |    |    |                              |  |                                 |                             | N/A                      | N/A                     | N/A |
| 2   | B                     | Classroom 005 Restroom | T                                       | Pipe Insulation 2-6 inch          | 7220/02/08/40           | Confirmed                                | 7                     | LF |    |    | 0                   | LF |    |    |                              |  |                                 |                             | 1                        | No                      | 1/D |
| 2   | B                     | Classroom 005 Restroom | N/A                                     | Sheetrock Wall                    |                         | NAD                                      | 84                    | SF |    |    | 0                   | SF |    |    |                              |  |                                 |                             | N/A                      | N/A                     | N/A |
| 2   | B                     | Classroom 006          | M                                       | Blackboard Glue Dots              | 7220/02/08/ACER/SM/2600 | Assumed                                  | 2                     | EA |    |    | 0                   | EA |    |    |                              |  |                                 |                             | 1                        | No                      | 1/D |
| 2   | B                     | Classroom 006          | N/A                                     | CMU                               |                         | Non Suspect ACM                          | 1600                  | SF |    |    | 0                   | SF |    |    |                              |  |                                 |                             | N/A                      | N/A                     | N/A |
| 2   | B                     | Classroom 006          | N/A                                     | Concrete Ceiling                  |                         | Non Suspect ACM                          | 800                   | SF |    |    | 0                   | SF |    |    |                              |  |                                 |                             | N/A                      | N/A                     | N/A |
| 2   | B                     | Classroom 006          | N/A                                     | Fiberglass Pipe Insulation        |                         | Non Suspect ACM                          | 68                    | LF |    |    | 0                   | LF |    |    |                              |  |                                 |                             | N/A                      | N/A                     | N/A |
| 2   | B                     | Classroom 006          | M                                       | Floor Tile VAT 12" x 12"          | 7220/02/08/PP           | Assumed                                  | 800                   | SF |    |    | 0                   | SF |    |    | Tan                          |  |                                 |                             | 1                        | No                      | 1/D |
| 2   | B                     | Classroom 006          | T                                       | Pipe Fitting Insulation           | 7220/02/08/51           | Confirmed                                | 7                     | EA |    |    | 0                   | EA |    |    |                              |  |                                 |                             | 1                        | No                      | 1/D |
| 2   | B                     | Classroom 006          | T                                       | Pipe Insulation 2-6 inch          | 7220/02/08/40           | Confirmed                                | 29                    | LF |    |    | 0                   | LF |    |    |                              |  |                                 |                             | 1                        | No                      | 1/D |
| 2   | B                     | Classroom 006          | N/A                                     | Radiator Insulation               |                         | NAD                                      | 32                    | SF |    |    | 0                   | SF |    |    |                              | Sampled NAD on 11/12/15 (KEM/SM)       |                                 |                             | N/A                      | N/A                     | N/A |
| 2   | B                     | Classroom 6 Closet     | N/A                                     | CMU                               |                         | Non Suspect ACM                          | 108                   | SF |    |    | 0                   | SF |    |    |                              |  |                                 |                             | N/A                      | N/A                     | N/A |
| 2   | B                     | Classroom 6 Closet     | N/A                                     | Concrete Ceiling                  |                         | Non Suspect ACM                          | 54                    | SF |    |    | 0                   | SF |    |    |                              |  |                                 |                             | N/A                      | N/A                     | N/A |
| 2   | B                     | Classroom 6 Closet     | M                                       | Floor Tile VAT 12" x 12"          | 7220/02/08/PP           | Assumed                                  | 54                    | SF |    |    | 0                   | SF |    |    | Tan                          |  |                                 |                             | 1                        | No                      | 1/D |
| 2   | B                     | Classroom 6 Closet     | M                                       | Transite Closet                   | 7220/02/08/33           | Assumed                                  | 54                    | SF |    |    | 0                   | SF |    |    |                              |  |                                 |                             | 1                        | No                      | 1/D |

## 7220 Carnell ES 2015 2016 AHERA Three-Year Report.xls

| School District of Philadelphia               |                       |                                | AHERA Three-Year Reinspection 2015-2016 |                            |                         |  |                    |          |                  |          |                        |                                   | Reinspection Date: October 21-26, 2015 |                       |                    |                      |  |  |
|---|-----------------------|--------------------------------|---|----------------------------|-------------------------|--|--------------------|----------|------------------|----------|------------------------|-----------------------------------|--|-----------------------|--------------------|----------------------|--|--|
| Laura H. Carnell Elementary School            |                       |                                | Room by Room Location Log Report        |                            |                         |  |                    |          |                  |          |                        |                                   | Building Inspector: Scott Magee        |                       |                    |                      |  |  |
| 1100 Devereaux Avenue, Philadelphia, PA 19111 |                       |                                |   |                            |                         |  |                    |          |                  |          |                        |                                   | Number: 70016699C                      |                       |                    |                      |  |  |
| ULCS# 7220                                    |                       |                                |   |                            |                         |  |                    |          |                  |          |                        |                                   | Management Planner: Megan Vala         |                       |                    |                      |  |  |
| Year Built: 1931                              |                       |                                |   |                            |                         |  |                    |          |                  |          |                        |                                   | Number: 740728                         |                       |                    |                      |  |  |
| E<br>l<br>e<br>m<br>e<br>n<br>t               | F<br>l<br>o<br>o<br>r | On-Site Room Name              | System Affected                         | Material Description       | HID#                    | Confirmed/Assumed/NAD<br>Non Suspect ACM | Amount of Material | SF LF EA | Amount of Damage | SF LF EA | Color required for VAT | Comments/Description/Notes        | Attic Crawl Space Ranking              | Damage Potential (DP) | Newly Friable (NF) | Response Action (RA) |  |  |
|   |                       |                                |   |                            |                         |  |                    |          |                  |          |                        |                                   |  |                       |                    |                      |  |  |
| 2   | B                     | Classroom 6 Closet             | N/A                                     | Ceiling Tile 1' x 1'       |                         | NAD                                      | 18                 | SF       | 0                | SF       |                        |                                   |  | N/A                   | N/A                | N/A                  |  |  |
| 2   | B                     | Classroom 6 Closet             | N/A                                     | CMU                        |                         | Non Suspect ACM                          | 36                 | SF       | 0                | SF       |                        |                                   |  | N/A                   | N/A                | N/A                  |  |  |
| 2   | B                     | Classroom 6 Closet             | N/A                                     | Concrete Ceiling           |                         | Non Suspect ACM                          | 18                 | SF       | 0                | SF       |                        |                                   |  | N/A                   | N/A                | N/A                  |  |  |
| 2   | B                     | Classroom 6 Closet             | M                                       | Floor Tile VAT 12" x 12"   | 7220/02/0B/PP           | Assumed                                  | 18                 | SF       | 0                | SF       | Tan                    |                                   |  | 1                     | No                 | 1/D                  |  |  |
| 2   | B                     | Classroom 006 Restroom         | N/A                                     | Ceramic Tile Floors        |                         | Non Suspect ACM                          | 54                 | SF       | 0                | SF       |                        |                                   |  | N/A                   | N/A                | N/A                  |  |  |
| 2   | B                     | Classroom 006 Restroom         | N/A                                     | CMU                        |                         | Non Suspect ACM                          | 54                 | SF       | 0                | SF       |                        |                                   |  | N/A                   | N/A                | N/A                  |  |  |
| 2   | B                     | Classroom 006 Restroom         | N/A                                     | Concrete Ceiling           |                         | Non Suspect ACM                          | 54                 | SF       | 0                | SF       |                        |                                   |  | N/A                   | N/A                | N/A                  |  |  |
| 2   | B                     | Classroom 006 Restroom         | N/A                                     | Fiberglass Pipe Insulation |                         | Non Suspect ACM                          | 27                 | LF       | 1                | LF       |                        |                                   |  | N/A                   | N/A                | N/A                  |  |  |
| 2   | B                     | Classroom 006 Restroom         | T                                       | Pipe Fitting Insulation    | 7220/02/0B/51           | Confirmed                                | 3                  | EA       | 0                | EA       |                        |                                   |  | 1                     | No                 | 1/D                  |  |  |
| 2   | B                     | Classroom 006 Restroom         | T                                       | Pipe Insulation 2-6 inch   | 7220/02/0B/40           | Confirmed                                | 22                 | LF       | 0                | LF       |                        |                                   |  | 1                     | No                 | 1/D                  |  |  |
| 2   | B                     | Classroom 006 Restroom         | N/A                                     | Sheetrock Wall             |                         | NAD                                      | 108                | SF       | 0                | SF       |                        |                                   |  | 1                     | No                 | N/A                  |  |  |
| 2   | B                     | Classroom 007                  | M                                       | Blackboard Glue Dots       | 7220/02/0B/ACER/SM/2600 | Assumed                                  | 2                  | EA       | 0                | EA       |                        |                                   |  | 1                     | No                 | 1/D                  |  |  |
| 2   | B                     | Classroom 007                  | N/A                                     | CMU                        |                         | Non Suspect ACM                          | 1600               | SF       | 0                | SF       |                        |                                   |  | N/A                   | N/A                | N/A                  |  |  |
| 2   | B                     | Classroom 007                  | N/A                                     | Concrete Ceiling           |                         | Non Suspect ACM                          | 800                | SF       | 0                | SF       |                        |                                   |  | N/A                   | N/A                | N/A                  |  |  |
| 2   | B                     | Classroom 007                  | M                                       | Floor Tile VAT 12" x 12"   | 7220/02/0B/PP           | Assumed                                  | 800                | SF       | 0                | SF       | Green                  |                                   |  | 1                     | No                 | 1/D                  |  |  |
| 2   | B                     | Classroom 007                  | T                                       | Pipe Fitting Insulation    | 7220/02/0B/51           | Confirmed                                | 6                  | EA       | 0                | EA       |                        |                                   |  | 1                     | No                 | 1/D                  |  |  |
| 2   | B                     | Classroom 007                  | T                                       | Pipe Insulation 2-6 inch   | 7220/02/0B/40           | Confirmed                                | 19                 | LF       | 0                | LF       |                        |                                   |  | 1                     | No                 | 1/D                  |  |  |
| 2   | B                     | Classroom 007                  | N/A                                     | Radiator Insulation        |                         | NAD                                      | 32                 | SF       | 0                | SF       |                        | Sampled NAD on 11/12/15 (KEM/SM)  |  | N/A                   | N/A                | N/A                  |  |  |
| 2   | B                     | Classroom 7 Closet             | N/A                                     | CMU                        |                         | Non Suspect ACM                          | 108                | SF       | 0                | SF       |                        |                                   |  | N/A                   | N/A                | N/A                  |  |  |
| 2   | B                     | Classroom 7 Closet             | N/A                                     | Concrete Ceiling           |                         | Non Suspect ACM                          | 54                 | SF       | 0                | SF       |                        |                                   |  | N/A                   | N/A                | N/A                  |  |  |
| 2   | B                     | Classroom 7 Closet             | M                                       | Floor Tile VAT 12" x 12"   | 7220/02/0B/PP           | Assumed                                  | 54                 | SF       | 0                | SF       | Grey                   |                                   |  | 1                     | No                 | 1/D                  |  |  |
| 2   | B                     | Classroom 7 Closet             | M                                       | Transite Closet            | 7220/02/0B/33           | Assumed                                  | 54                 | SF       | 0                | SF       |                        |                                   |  | 1                     | No                 | 1/D                  |  |  |
| 2   | B                     | Classroom 007 Restroom         | N/A                                     | Ceramic Tile Floors        |                         | Non Suspect ACM                          | 42                 | SF       | 0                | SF       |                        |                                   |  | N/A                   | N/A                | N/A                  |  |  |
| 2   | B                     | Classroom 007 Restroom         | N/A                                     | CMU                        |                         | Non Suspect ACM                          | 42                 | SF       | 0                | SF       |                        |                                   |  | N/A                   | N/A                | N/A                  |  |  |
| 2   | B                     | Classroom 007 Restroom         | N/A                                     | Concrete Ceiling           |                         | Non Suspect ACM                          | 42                 | SF       | 0                | SF       |                        |                                   |  | N/A                   | N/A                | N/A                  |  |  |
| 2   | B                     | Classroom 007 Restroom         | N/A                                     | Fiberglass Pipe Insulation |                         | Non Suspect ACM                          | 24                 | LF       | 1                | LF       |                        |                                   |  | N/A                   | N/A                | N/A                  |  |  |
| 2   | B                     | Classroom 007 Restroom         | T                                       | Pipe Insulation 2-6 inch   | 7220/02/0B/40           | Confirmed                                | 7                  | LF       | 0                | LF       |                        |                                   |  | 1                     | No                 | 1/D                  |  |  |
| 2   | B                     | Classroom 007 Restroom         | N/A                                     | Sheetrock Wall             |                         | NAD                                      | 84                 | SF       | 0                | SF       |                        |                                   |  | N/A                   | N/A                | N/A                  |  |  |
| 2   | B                     | Storage Room                   | N/A                                     | CMU                        |                         | Non Suspect ACM                          | 100                | SF       | 0                | SF       |                        |                                   |  | N/A                   | N/A                | N/A                  |  |  |
| 2   | B                     | Storage Room                   | N/A                                     | Concrete Ceiling           |                         | Non Suspect ACM                          | 50                 | SF       | 0                | SF       |                        |                                   |  | N/A                   | N/A                | N/A                  |  |  |
| 2   | B                     | Storage Room                   | M                                       | Floor Tile VAT 9" x 9"     | 7220/02/0B/31           | Confirmed                                | 50                 | SF       | 0                | SF       | Brown                  |                                   |  | 1                     | No                 | 1/D                  |  |  |
| 2   | B                     | Basement Hallway               | N/A                                     | Ceiling Tile 1' x 1'       |                         | NAD                                      | 140                | SF       | 0                | SF       |                        |                                   |  | N/A                   | N/A                | N/A                  |  |  |
| 2   | B                     | Basement Hallway               | N/A                                     | Ceramic Tile Walls         |                         | Non Suspect ACM                          | 140                | SF       | 0                | SF       |                        |                                   |  | N/A                   | N/A                | N/A                  |  |  |
| 2   | B                     | Basement Hallway               | N/A                                     | CMU                        |                         | Non Suspect ACM                          | 280                | SF       | 0                | SF       |                        |                                   |  | N/A                   | N/A                | N/A                  |  |  |
| 2   | B                     | Basement Hallway               | N/A                                     | Concrete Ceiling           |                         | Non Suspect ACM                          | 140                | SF       | 0                | SF       |                        |                                   |  | N/A                   | N/A                | N/A                  |  |  |
| 2   | B                     | Basement Hallway               | N/A                                     | Fiberglass Pipe Insulation |                         | Non Suspect ACM                          | 5                  | LF       | 0                | LF       |                        |                                   |  | N/A                   | N/A                | N/A                  |  |  |
| 2   | B                     | Basement Hallway               | M                                       | Floor Tile VAT 12" x 12"   | 7220/02/0B/PP           | Assumed                                  | 544                | SF       | 0                | SF       | Tan                    |                                   |  | 1                     | No                 | 1/D                  |  |  |
| 2   | B                     | Basement Hallway               | N/A                                     | Ceiling Tile 1' x 1'       |                         | NAD                                      | 520                | SF       | 0                | SF       |                        |                                   |  | N/A                   | N/A                | N/A                  |  |  |
| 2   | B                     | Basement Hallway               | N/A                                     | Ceramic Tile Walls         |                         | Non Suspect ACM                          | 520                | SF       | 0                | SF       |                        |                                   |  | N/A                   | N/A                | N/A                  |  |  |
| 2   | B                     | Basement Hallway               | N/A                                     | CMU                        |                         | Non Suspect ACM                          | 1040               | SF       | 0                | SF       |                        |                                   |  | N/A                   | N/A                | N/A                  |  |  |
| 2   | B                     | Basement Hallway               | N/A                                     | Concrete Ceiling           |                         | Non Suspect ACM                          | 520                | SF       | 0                | SF       |                        |                                   |  | N/A                   | N/A                | N/A                  |  |  |
| 2   | B                     | Basement Hallway               | M                                       | Floor Tile VAT 12" x 12"   | 7220/02/0B/PP           | Assumed                                  | 544                | SF       | 0                | SF       | Tan                    |                                   |  | 1                     | No                 | 1/D                  |  |  |
| 2   | B                     | Basement Hallway               | T                                       | Floor Tile VAT 9" x 9"     | 7220/02/0B/31           | Confirmed                                | 12                 | SF       | 0                | SF       | Multi                  |                                   |  | 1                     | No                 | 1/D                  |  |  |
| 2   | B                     | Basement Hallway               | T                                       | Pipe Insulation 2-6 inch   | 7220/02/0B/40           | Confirmed                                | 24                 | LF       | 0                | LF       |                        |                                   |  | 1                     | No                 | 1/D                  |  |  |
| 2   | B                     | Custodial Closet               | N/A                                     | CMU                        |                         | Non Suspect ACM                          | 80                 | SF       | 0                | SF       |                        |                                   |  | N/A                   | N/A                | N/A                  |  |  |
| 2   | B                     | Custodial Closet               | M                                       | Concrete Ceiling           |                         | Non Suspect ACM                          | 40                 | SF       | 0                | SF       |                        |                                   |  | N/A                   | N/A                | N/A                  |  |  |
| 2   | B                     | Custodial Closet               | N/A                                     | Floor Tile VAT 9" x 9"     | 7220/02/0B/31           | Confirmed                                | 40                 | SF       | 0                | SF       | Brown                  |                                   |  | 1                     | No                 | 1/D                  |  |  |
| 2   | B                     | Custodial Closet               | T                                       | Pipe Fitting Insulation    | 7220/02/0B/51           | Confirmed                                | 6                  | EA       | 0                | EA       |                        |                                   |  | 1                     | No                 | 1/D                  |  |  |
| 2   | B                     | Custodial Closet               | T                                       | Pipe Insulation 2-6 inch   | 7220/02/0B/40           | Confirmed                                | 23                 | LF       | 0                | LF       |                        |                                   |  | 1                     | No                 | 1/D                  |  |  |
| 1   | A                     | Attic at Third Floor Stairwell | X                                       | X                          |                         | X  | X                  | X        | X                | X        |                        | 1750 LF of Air Cell, Exposed Ends | C                                      | X                     | X                  | X                    |  |  |
| 1   | C                     | Crawl Space                    | X                                       | X                          |                         | X  | X                  | X        | X                | X        |                        | None                              | None                                   | X                     | X                  | X                    |  |  |

### **Section III    Certificates**

#### **A. Management Planner/Building Inspector Certificates**

### Section III – A

#### Management Planner/Building Inspector Certificates

These charts indicate the Name, Course Date, Expiration Date and Corresponding Certificate Number of the Management Planner and Building Inspector of individuals that participated in the AHERA 3 Year Inspection and Management Plan process of 2015/2016.

| Management Planner | Date Granted | Expiration Date | Certificate Number |
|--------------------|--------------|-----------------|--------------------|
| Monique Causley    | 2/15/2015    | 2/16/2016       | ACC-0215-8-010     |
| Monique Causley    | 2/16/2016    | 2/17/2017       | ACC-0216-8-001     |
| Megan Vala         | 5/22/2015    | 6/22/2016       | 740728             |
| Mary Anne Lerro    | 4/5/2016     | 4/5/2017        | 742327             |

| Building Inspector | Date Granted | Expiration Date | Certificate Number |
|--------------------|--------------|-----------------|--------------------|
| Scott Magee        | 8/15/2015    | 8/15/2016       | 70016699C          |
| William Garrity    | 8/15/2015    | 8/15/2016       | 70016699A          |
| Bernard Brunner    | 10/2/2015    | 8/2/2016        | 45397              |
| Mary Anne Lerro    | 3/3/2015     | 3/3/2016        | 740092             |
| Mary Anne Lerro    | 4/5/2016     | 4/5/2017        | 742322             |
| James Madden       | 12/11/2014   | 12/11/2015      | ACC-1214-6-010     |
| James Madden       | 12/3/2015    | 12/3/2016       | ACC-1215-6-018     |
| Troy Ray           | 3/15/2015    | 3/19/2016       | ACC-0355-6-011     |
| Ananth Vinjamuri   | 9/29/2015    | 9/29/2016       | 374                |
| Shelton Williams   | 9/29/2015    | 9/29/2016       | 375                |
| Paul Davis         | 2/12/2015    | 2/12/2016       | ACC-0215-6-015     |
| Paul Davis         | 2/2/2016     | 2/2/2017        | 741836             |
| Bernard Bryson     | 2/16/2015    | 2/16/2016       | ACC-0125-6-031     |
| Bernard Bryson     | 2/15/2016    | 2/15/2017       | ACC-0216-6-005     |
| Alexander Roman    | 9/18/2015    | 9/18/2016       | EHSBIR-150619-008  |
| Norm Harrison      | 9/2/2015     | 9/2/2016        | ACC-0915-6-011     |
| Kelly Mayberry     | 2/20/2015    | 2/20/2016       | EHSBIR-150220-005  |
| Kelly Mayberry     | 2/18/2016    | 2/18/2017       | EHSBIR-160218-006  |
| Andrew Hine        | 5/6/2015     | 5/6/2016        | AI05042015-3       |
| Maryellen Leotta   | 2/12/2015    | 2/12/2016       | ACC-0215-6-024     |



# Certificate of Completion

*awarded to*

**Monique Causley**

*for successfully completing the prescribed course of study in*

## **Pennsylvania Asbestos Management Planner Refresher Course**

*under TSCA Title II*

*presented by*

**ACCESS TRAINING SERVICES, INC.**  
7921 River Road, Pennsauken, NJ 08110  
(856) 665-3449

**2/16/15**

*Course Date*

**N/A**

*Exam Date*

**2/16/16**

*Expiration Date*

**Not Provided**

*Social Security Number*

**ACC-0215-8-010**

*Certificate Number*

**Mark K. Schlager**  
*Training Director*

# Certificate of Completion

*awarded to*

**Monique Causley**

*for successfully completing the prescribed course of study in*

## **Pennsylvania Asbestos Management Planner Refresher Course**

**under TSCA Title II**

*presented by*

**ACCESS TRAINING SERVICES, INC.  
7921 River Road, Pennsauken, NJ 08110  
(856) 665-3449**

**2/15/16**

*Course Date*

**N/A**

*Exam Date*

**2/15/17**

*Expiration Date*

**Not Provided**

*Social Security Number*

**ACC-0216-8-001**

*Certificate Number*

**Mark K. Schlüger**  
*Training Director*

# *Certificate of Training*

CRITERION LABORATORIES, INC.

HEREBY CERTIFIES THAT

Megan Vala

HAS SUCCESSFULLY COMPLETED A 16 HOUR COURSE ENTITLED

Asbestos Management Planner Initial

INCLUDING CLASSROOM INSTRUCTION

05/21/2015 to 05/22/2015


Exam passed on this 22nd day of May 2015 - Score - 94

Approved for AHERA Accreditation Under TSCA Title II

3370 Progress Drive, Suite J  
Bensalem, PA 19020  
(215) 244-1300 - Phone  
(215) 244-4349 - Fax  
www.criterionlabs.com

Course is conducted in English

DIRECTOR:

  
James A. Welte, CIH, President

# *Certificate of Training*

**CRITERION LABORATORIES, INC.**

HEREBY CERTIFIES THAT

**Mary Anne Lerro**

HAS SUCCESSFULLY COMPLETED A 4 HOUR COURSE ENTITLED  
**Asbestos Management Planner Refresher**

INCLUDING CLASSROOM INSTRUCTION

on this 5th day of April 2016

Approved for AHERA Accreditation Under TSCA Title II

3370 Progress Drive, Suite J  
Bensalem, PA 19020  
(215) 244-1300 - Phone  
(215) 244-4349 - Fax  
www.criterionlabs.com

*Course is conducted in English*

DIRECTOR:

*James A. Welts*  
*James A. Welts, CIH, President*

# EMSL ANALYTICAL, INC.

Certifies that

Scott Magee

has successfully completed the course of study for the

## Asbestos Building Inspector Refresher Course

for Accreditation under TSCA Title II

EMSL Certificate No. 70016699C


### Approved by:

PA Dept. of Labor and Industry  
Accreditation # 137

Course Date: 8/15/2015  
Granted: 8/15/2015  
Expiration Date: 8/15/2016

### Sponsored by:

EMSL Analytical, Inc.  
200 Route 130 North  
Cinnaminson, NJ 08077  
Phone: (800) 220-3675  
Fax: (856) 786-5973  
[www.emsl.com](http://www.emsl.com)



*Michael P. Menz*

Michael P. Menz, CIH  
Training Director

Environmental, Mold, Bacteria, IAQ, Asbestos, Lead, Forensic and Materials Testing Since 1981

# EMSL ANALYTICAL, INC.

Certifies that

William Garrity

has successfully completed the course of study for the

## Asbestos Building Inspector Refresher Course

for Accreditation under TSCA Title II

EMSL Certificate No. 70016699A


Approved by:

PA Dept. of Labor and Industry  
Accreditation # 137

Course Date: 8/15/2015  
Granted: 8/15/2015  
Expiration Date: 8/15/2016

Sponsored by:

EMSL Analytical, Inc.  
200 Route 130 North  
Cinnaminson, NJ 08077  
Phone: (800) 220-3675  
Fax: (856) 786-5973  
[www.emsl.com](http://www.emsl.com)



*Michael P. Menz*  
\_\_\_\_\_  
Michael P. Menz, CIH  
Training Director

Environmental, Mold, Bacteria, IAQ, Asbestos, Lead, Forensic and Materials Testing Since 1981



45397

# *National Asbestos & Environmental Training Institute*

## **CERTIFICATE OF COMPLETION**

AHERA/EPA Accredited Per 40 CFR Part 763  
Asbestos Accreditation under TSCA Title II

*This is to certify that*

***Bernard Brunner, Jr.***

*Successfully completed the course entitled*

**1/2-Day New York State/EP A/AHERA Asbestos Building Inspector Annual Refresher on  
October 2, 2015**

*Examination Passed October 2, 2015*

*Expiration Date on October 2, 2016*

  
**Doris L. Adler**  
*President, NAEETI*

Per 10 NYCRR Part 73.2 (L) (1), DOH 2832 Certificate of Completion of Asbestos  
Safety Training is the only official record of training for N.Y.S. students.

Language: English

ABIH 1/2 CM POINT

3321 Doris Avenue, Building B, Ocean, NJ 07712

Phone (732) 531-5571

Fax (732) 531-5956

[www.naeti.com](http://www.naeti.com)

Number 740092

Expiration Date:  
03/03/2016

# *Certificate of Training*

CRITERION LABORATORIES, INC.

HEREBY CERTIFIES THAT

Mary Anne Lerro

HAS SUCCESSFULLY COMPLETED A 4 HOUR COURSE ENTITLED

Asbestos Building Inspector Refresher

on this 3rd day of March 2015

Exam passed on this 3rd day of March 2015 - Score - 84

Approved for AHERA Accreditation Under TSCA Title II

3370 Progress Drive, Suite J  
Bensalem, PA 19020  
(215) 244-1300 - Phone  
(215) 244-4349 - Fax  
[www.criterionlabs.com](http://www.criterionlabs.com)

*Course is conducted in English*

DIRECTOR:

*James A. Welts*

*James A. Welts, CIH, President*



# *Certificate of Training*

**CRITERION LABORATORIES, INC.**

**HEREBY CERTIFIES THAT**

**Mary Anne Lerro**

**HAS SUCCESSFULLY COMPLETED A 4 HOUR COURSE ENTITLED**

**Asbestos Building Inspector Refresher**

**INCLUDING CLASSROOM INSTRUCTION**

**on this 5th day of April 2016**

**Exam passed on this 5th day of April 2016 - Score - 88**

**Approved for AHERA Accreditation Under TSCA Title II**

3370 Progress Drive, Suite J  
Bensalem, PA 19020  
(215) 244-1300 - Phone  
(215) 244-4349 - Fax  
www.criterionlabs.com

*Course is conducted in English*

**DIRECTOR:**

*James A. Welts*

*James A. Welts, CIH, President*

# Certificate of Completion

**James Madden**

*for successfully completing the prescribed course of study in*

## **Pennsylvania Asbestos Building Inspector Refresher Course**

under TSCA Title II

*presented by*

**ACCESS TRAINING SERVICES, INC.**  
7921 River Road, Pennsauken, NJ 08110  
(856) 665-3449

**12/11/14**

*Course Date*

**N/A**

*Exam Date*

**12/11/15**

*Expiration Date*

**Not Provided**

*Social Security Number*

**ACC-1214-6-010**

*Certificate Number*

**Mark K. Schlager**  
*Training Director*

# Certificate of Completion

**James Madden**

*for successfully completing the prescribed course of study in*

## **Pennsylvania Asbestos Building Inspector Refresher Course**

under TSCA Title II

*presented by*

**ACCESS TRAINING SERVICES, INC.**  
7921 River Road, Pennsauken, NJ 08110  
(856) 665-3449

**12/3/15**

*Course Date*

**N/A**

*Exam Date*

**12/3/16**

*Expiration Date*

**Not Provided**

*Social Security Number*

**ACC-1215-6-018**

*Certificate Number*

*Mark K. Schlager*  
**Mark K. Schlager**  
Training Director

# Certificate of Completion

**Troy A. Ray**

*for successfully completing the prescribed course of study in*

## **Pennsylvania Asbestos Building Inspector Refresher Course**

under TSCA Title II

*presented by*

**ACCESS TRAINING SERVICES, INC.  
7921 River Road, Pennsauken, NJ 08110  
(856) 665-3449**

**3/19/15**

*Course Date*

**N/A**

*Exam Date*

**3/19/16**

*Expiration Date*

**Not Provided**

*Social Security Number*

**ACC-0355-6-011**

*Certificate Number*

**Mark K. Schlager**  
*Training Director*

# CERTIFICATE NO 374

G&C Environmental Services, Inc. (#294)

2 Street Road, Newtown Square, Pennsylvania 19073

Telephone: (610) 993-9202 Facsimile: (610) 993-9232

Email: Training@gcenviro.com

www.GCenviro.com

This document certifies that Ananth K. Vinjamuri has successfully completed this State of New York Department of Health Approved AHERA BUILDING INSPECTOR

REFRESHER COURSE, completed as required for asbestos accreditation under the Toxic

Substances Control Act, Title II. This course was held from 09/29/2015 to 09/29/2015.

The examination date was 09/29/2015. This certificate expires one year from the date of

successful completion of the examination 09/29/2016.

*The official record of successful training completion is the New York State Department of Health certificate of asbestos safety training completion (DPH 2832).*

Gail M. Conner  
Training Director

Gail M. Conner

# CERTIFICATE NO 375

G&C Environmental Services, Inc. (#294)

2 Street Road, Newtown Square, Pennsylvania 19073

Telephone: (610) 993-9202 Facsimile: (610) 993-9232

Email: Training@gcenviro.com

www.GCenviro.com

This document certifies that Shelton Williams has successfully completed this  
State of New York Department of Health Approved AHERA BUILDING INSPECTOR

REFRESHER COURSE, completed as required for asbestos accreditation under the Toxic

Substances Control Act, Title II. This course was held from 09/29/2015 to 09/29/2015.  
MM DD YR MM DD YR

The examination date was 09/29/2015. This certificate expires one year from the date of  
MM DD YR MM DD YR  
successful completion of the examination 09/29/2016.  
MM DD YR

*The official record of successful training completion is the New York State Department of  
Health certificate of asbestos safety training completion (DPH 2832).*

Gail M. Conner  
Training Director

Gail M. Conner

# Certificate of Completion

**Paul M. Davis**

*for successfully completing the prescribed course of study in*

## **Pennsylvania Asbestos Building Inspector Refresher Course**

under TSCA Title II

*presented by*

**ACCESS TRAINING SERVICES, INC.**  
7921 River Road, Pennsauken, NJ 08110  
(856) 665-3449

**2/12/15**

*Course Date*

**N/A**

*Exam Date*

**2/12/16**


*Expiration Date*

**Not Provided**

*Social Security Number*

**ACC-0215-6-015**

*Certificate Number*

  
**Mark K. Schlager**  
*Training Director*



# Certificate of Training

CRITERION LABORATORIES, INC.

HEREBY CERTIFIES THAT

Paul M. Davis

HAS SUCCESSFULLY COMPLETED A 4 HOUR COURSE ENTITLED  
Asbestos Building Inspector Refresher

INCLUDING CLASSROOM INSTRUCTION

on this 2nd day of February 2016

Exam passed on this 2nd day of February 2016 - Score - 92

Approved for AHERA Accreditation Under ISCA Title II

3370 Progress Drive, Suite J  
Bensalem, PA 19020  
(215) 244-1300 - Phone  
(215) 244-4349 - Fax  
www.criterionlabs.com

Course is conducted in English

DIRECTOR:

*James A. Wells*

James A. Wells, CIH, President



# Certificate of Completion

**Bernard J. Bryson**

*for successfully completing the prescribed course of study in*

## **Pennsylvania Asbestos Building Inspector Refresher Course**

under TSCA Title II

*presented by*

**ACCESS TRAINING SERVICES, INC.**  
7921 River Road, Pennsauken, NJ 08110  
(856) 665-3449

**2/16/15**  
*Course Date*

**N/A**

*Exam Date*

**2/16/16**

*Expiration Date*

**Not Provided**

*Social Security Number*

**ACC-0125-6-031**

*Certificate Number*

**Mark K. Schlager**  
*Training Director*

# Certificate of Completion

**Bernard J. Bryson**

*for successfully completing the prescribed course of study in*

## **Pennsylvania Asbestos Building Inspector Refresher Course**

under TSCA Title II

*presented by*

**ACCESS TRAINING SERVICES, INC.**  
7921 River Road, Pennsauken, NJ 08110  
(856) 665-3449

**2/15/16**

*Course Date*

**N/A**

*Exam Date*

**2/15/17**

*Expiration Date*

**Not Provided**

*Social Security Number*

**ACC-0216-6-005**

*Certificate Number*

**Mark K. Schlager**  
*Training Director*

**EHS TRAINING INSTITUTE, INC.**

A Division of BATTI, Inc.

# **Certificate of Completion**

## **AHERA Building Inspector**

**(Refresher)**

**Awarded To:**

**Alexander Roman**

SS#:XXX-XX-1743

Who has completed this 4-hour course and examination,

EPA Approved under TSCA Title II

AHERA / ASHARA Rule

40 CFR Part 763.

**EHS TRAINING INSTITUTE, INC.**

A Division of BATTI, Inc.

**Delaware Industrial Park • 6 Garfield Way**

**Newark, DE 19713-5817**

**(302) 737-3376 • Fax (302) 737-5764**

**Course Date: September 18, 2015**

**Date of Expiration: September 18, 201**

**Certification Number : EHSBIR 150619-008**

  
**Todd K. Zeisloff, Instructor**

  
**Neeraj K. Batta, President**

# Certificate of Completion

**Norman Harrison**

*for successfully completing the prescribed course of study in*

## **Pennsylvania Asbestos Building Inspector Refresher Course**

under TSCA Title II

*presented by*

**ACCESS TRAINING SERVICES, INC.**  
7921 River Road, Pennsauken, NJ 08109  
(856) 665-3449

**9/2/15**

*Course Date*

**N/A**

*Exam Date*

**9/2/16**


*Expiration Date*

**Not Provided**

*Social Security Number*

**ACC-0915-6-011**

*Certificate Number*

  
**Mark A. Schlenger**  
*Training Director*

**EHS TRAINING INSTITUTE, INC.**  
A Division of BATTI, Inc.

# **Certificate of Completion**

## **AHERA Building Inspector**

**(Refresher)**

**Awarded To:**

**Kelly Mayberry**

SS#:XXX-XX-1551

Who has completed this 4-hour course and examination,  
EPA Approved under TSCA Title II  
AHERA / ASHARA Rule  
40 CFR Part 763.

**EHS TRAINING INSTITUTE, INC.**

A Division of BATTI, Inc.

*Delaware Industrial Park • 6 Garfield Way*

*Newark, DE 19713-5817*

*(302) 737-3376 • Fax (302) 737-5764*

**Course Date: February 20, 2015**

**Date of Expiration: February 20, 2016**

**Certification Number : EHSBIR 150220-005**

  
Todd K. Zeisloft, Instructor

  
Neeraj K. Batta, President

**EHS TRAINING INSTITUTE, INC.**  
A Division of BATTI, Inc.

# **Certificate of Completion**

## **AHERA Building Inspector**

**(Refresher)**

**Awarded To:**

**Kelly Mayberry**

SS#:XXX-XX-1551  
Who has completed this 4-hour course and examination,  
EPA Approved under TSCA Title II  
AHERA / ASHARA Rule  
40 CFR Part 763.

**EHS TRAINING INSTITUTE, INC.**

A Division of BATTI, Inc.

Delaware Industrial Park • 6 Garfield Way  
Newark, DE 19713-5817  
(302) 737-3376 • Fax (302) 737-5764

Course Date: February 18, 2016  
Date of Expiration: February 18, 2017  
Certification Number : EHSBIR 160218-006

  
Todd K. Zeisloft, Instructor

  
Neeraj K. Batta, President



# AEROSOL MONITORING & ANALYSIS, INC.

*This is to certify that*  
**ANDREW HINE**

*has met the attendance requirements and successfully completed  
the course entitled*

**3-DAY EPA AHERA INSPECTOR**  
*For Accreditation Under TSCA Title II*

05/04/2015 to 05/06/2015

**Course Date**

05/06/2015

**Exam Date**

5/6/2016

**Expiration Date**

STEVE SIERAGI

**Principal Instructor**

*Steve Sieragi*

A105042015-3

**Certification No.**

E. Rush Barnett

**Course Director**

*E. Rush Barnett*

1331 Ashton Road

P.O.Box 646

Hanover, MD 21076

P: 410-684-3327

F: 410-684-3724

[www.amatraining.com](http://www.amatraining.com)

# Certificate of Completion

**Maryellen Leotta**

*for successfully completing the prescribed course of study in*

## **Pennsylvania Asbestos Building Inspector Refresher Course**

under TSCA Title II

*presented by*

**ACCESS TRAINING SERVICES, INC.**  
7921 River Road, Pennsauken, NJ 08110  
(856) 665-3449

**2/12/15**

*Course Date*

**N/A**

*Exam Date*

**2/12/16**

*Expiration Date*

**Not Provided**

*Social Security Number*

**ACC-0215-6-024**

*Certificate Number*

**Mark K. Schlüger**  
*Training Director*



# Asbestos Hazard Emergency Response Act (AHERA) Environmental Compliance Audit Cross Reference Table

In response to the AHERA Environmental Compliance Audit a Cross Reference Table has been prepared for inclusion into the Environmental Management Plan. The purpose of this Cross Reference Table is to link the following documents to the AHERA Management Plan.

| <b>Cross Reference Table</b>   |  |
|--|--|
| 3 Year Reinspection Report follows this Cross Reference Table documentation. |  |
| <b>Subject Matter</b>  | <b>Location of Required Documents</b>  |
| Designated Person  | Pages 1 - 3  |
| Annual Notification  | Pages 4 - 5  |
| 6 Month Periodic Surveillance<br>Outline of Events                           | Page 6   |
| 3 Year Re-inspections<br>Outline of Events                                   | Page 7   |
| Asbestos Management Program<br>(operations and maintenance)                  | Pages 8 - 19   |
| Asbestos Investigation Report<br>(AIR)                                       | Attachment 1<br>Letter Dated August 4, 2006  |
| Training<br>(included in the Asbestos<br>Management Program)                 | <p>The original records are centralized at the School District's Environmental Library. Copies are maintained on staff and are required to be maintained in the latest Reinspection Report.</p> <p>2 hour awareness training records for all Building Engineers, Custodian Assistants and maintenance personnel</p> <p>40 hour worker/supervisor training records for the OEMS A-Team and various AST tradesmen.</p> |
| Response Actions<br>(monthly mailings if applicable)                         | <p>The original documents are on file at the School District's Environmental Library.</p> <p>Copies of the original are mailed to the Schools Main Office for retention with the Management Plan documentation. These documents are typically kept separate from the management plan in an update binder due to the potential volume of response action reports.</p>   |

## **SCHOOL DISTRICT OF PHILADELPHIA**

### **ASBESTOS DESIGNATED PERSON**

**Gerald F Junod**  
**Office of Capital Programs**  
**Environmental Management & Services**  
**440 N Broad Street, 3<sup>rd</sup> Floor**  
**Philadelphia, PA 19130**  
**Telephone: 215 400 6738**  
**Fax: 215 400 4751**

|  |                                     |
|--|-------------------------------------|
| <b>Drexel University- Asbestos Building Inspector Course</b>             | <b>January 9-11, 1989 24 Hours</b>  |
| <b>Drexel University- Asbestos Management Planner Course</b>             | <b>January 12-13, 1989 16 Hours</b> |
| <b>Criterion Laboratories, Inc. - Asbestos Management Planner Course</b> | <b>October 11-12, 2012 16 Hours</b> |

|  |                        |
|--|------------------------|
| <b><u>Annual Building Inspector Refreshers</u></b> | <b>1990 to Present</b> |
| <b>4 Hours</b>                                     |                        |
| <b>Drexel University</b>                           |                        |
| <b>Criterion Laboratories, Inc</b>                 |                        |
| <b>Access Training Services, Inc.</b>              |                        |

|   |                        |
|---|------------------------|
| <b><u>Annual Building Management Planner Refreshers</u></b> | <b>1990 to 1994</b>    |
| <b>4 Hours</b>  |                        |
| <b>Drexel University</b>                                    |                        |
| <b>Criterion Laboratories, Inc</b>                          | <b>2013 to Present</b> |
| <b>4 Hours</b>  |                        |

#### **Environmental Manager, School District of Philadelphia**

**Manages the design and implementation of asbestos and lead projects for the Capital Improvement Program and other District Departments including Facilities & Operations and Information Technology. Ensures that asbestos abatement and lead remediation projects are expertly designed and executed in accordance with industry best management practice standards and regulations.**

#### **Manager, City of Philadelphia Asbestos Control Program**

**Served as the Asbestos Control Program Manager for the City of Philadelphia, Department of Public Health, Air Management Services, Asbestos Control Unit from August 1, 2003 through October 23, 2006.**

#### **Mid Atlantic Regional Environmental Consortium (MAREC)**

**Former member with attendance and participation commitments of all quarterly EPA Region III and yearly National Asbestos Regulatory Conferences sponsored by the EPA and the National Conference of State Legislators respectively as a representative for the City of Philadelphia Department of Public Health Air Management Services from 1994 through 2006.**

#### **Philadelphia Environmental Task Force**

**Former member of the Philadelphia Environmental Task force as a representative and point of contact for the City of Philadelphia Department of Public Health Air Management Services Asbestos Control Unit from 2002 through 2006.**

**Asbestos Instructor**

Worked as the primary instructor for the initial and annual Asbestos Project Inspector training and licensing program as mandated by City of Philadelphia Department of Public Health Asbestos Control Regulations from August 1994 through October 2006.

Worked as a lead instructor with an Environmental Consulting Firm and approved by the US EPA for the initial and annual refresher training courses for various asbestos occupational disciplines such as the Building Inspector, Management Planner and Worker/Supervisor from 1991 through 1994.

I certify that the general, local agency responsibilities as stipulated in Section 763.84 will be met.



Gerald F. Junod  
Asbestos Designated Person  
Environmental Manager  
Office of Environmental Management and Services

## **SCHOOL DISTRICT OF PHILADELPHIA**

### **Accreditation Information Statement**

**All persons who inspect for Asbestos Containing Building Materials (ACBM) and who will design or carry out response actions with respect to assumed and confirmed ACBM, will be accredited by an EPA approved course and/or a State Contractors Accreditation Program under Sections 206 (c) and 206 (b) of Title II of the ACT.**

A handwritten signature in black ink, appearing to read 'Gerald F. Junod', is written over the printed name and title.

**Gerald F. Junod  
Asbestos Designated Person  
Environmental Manager  
Office of Environmental Management and Services**

SCHOOL DISTRICT OF PHILADELPHIA  
OFFICE OF CAPITAL PROGRAMS  
440 NORTH BROAD STREET, SUITE 373  
PHILADELPHIA, PENNSYLVANIA 19130

OFFICE OF ENVIRONMENTAL MANAGEMENT AND SERVICES

PHONE (215)-400-4750

September 2015

TO: Principals  
Building Administrators/Occupants  
Parents/Guardians

FROM: Fran Burns  
Chief Operating Officer

Francine Locke, M.S., Director  
Office of Environmental Management and Services

SUBJECT: Annual EPA Notification Letter

Pursuant to the Federal Environmental Protection Agency (EPA) mandate, as required by 40 C.F.R. 763.84 (c)(d) of public access to environmental records, this letter is to acknowledge the availability of your facility's Asbestos Hazard Emergency Response Act (AHERA) Management Plan.

Each member of the school staff, parents/guardians, temporary workers and/or contractors, are required to receive a copy of the Notification Letter. At the direction of the Principal, a copy is to be posted on the bulletin boards and an appropriate amount of copies are to be generated for distribution.


Note: The AHERA Three-Year Reinspection reports, in colored binders; White with Pink, Tan, Black, Red, Dark Blue, Green, Yellow and White, are Federal EPA mandated inspection documents. The School District of Philadelphia is subject to severe monetary penalties if the reports and associated paperwork are not available to the EPA and the public upon request.

It is incumbent on designated school personnel to gather and retain this data as it is delivered, in one location for future review. Acceptable locations include the Principal's Office or Main Office for the primary data. The Building Engineer should maintain any secondary or duplicate copies.

If you have any questions, please call 215-400-4750. Thank you for your cooperation.



Fran Burns  
Chief Operating Officer



Francine Locke, M.S., Director  
Office of Environmental Management  
and Services

c: Danielle Floyd

AHERA-4  
8/21/15



**School District of Philadelphia**  
**OFFICIAL NOTICE**

**PLEASE POST**

September 2015

TO: Principals  
Building Administrators  
Building Engineers  
Building Occupants  
Parents/Guardians

FROM: Fran Burns  
Chief Operating Officer

Francine Locke, M.S., Director  
Office of Environmental Management and Services

SUBJECT: Annual Notification Letter: Asbestos Hazard Emergency Response Act

The Federal Register published on October 30, 1987, Subpart E, in Schools: Final Rule and Notice, 763.84 (c)(d) states that each local education agency shall ensure that workers and building occupants or guardians are to be informed at least once each school year about inspections, response actions and post-response action activities including re-inspections and periodic surveillance activities. The School District as the Local Education Agency (LEA), retains such reports that are available for public inspection in the Office of the Principal or Building Administrator.

The Principal or Building Administrator is required to do the following with this notification:

- 1) Post in a Public Place or Main Office
- 2) Inform Building Occupants
- 3) Send a copy of this notification to Parents or Guardians
- 4) Insert a copy into the latest AHERA Three-Year Reinspection report (white/pink binder) in your office or facility.

Handwritten signature of Fran Burns in black ink.

Fran Burns  
Chief Operating Officer

Handwritten signature of Francine Locke in black ink.

Francine Locke, M.S., Director  
Office of Environmental Management  
and Services

c: Danielle Floyd

AHERA-4a  
8/21/15

SCHOOL DISTRICT OF PHILADELPHIA  
Education Center  
440 North Broad Street  
Philadelphia, Pennsylvania 19130

Office of Environmental Management and Services

215-400-4750

AHERA  
Six Month Surveillance  
Outline of Events

- Pursuant to the Federal Environmental Protection Agency (EPA) mandate, as required by 40 CFR 763.92(b), the following procedure is to be implemented. At least once every six (6) months after a Management Plan is in effect, each Local Education Agency (LEA) shall conduct a periodic surveillance in each building that it owns or leases that contains Asbestos Containing Building Materials (ACBM) or is assumed to contain ACBM.
- The first Bi-Annual Inspection starts in the Spring (March, April, May) and again in the Fall (October, November, December) of each year. The Building Engineer/Assistant should assist the Building Inspector with appropriate access to all areas including (Crawlspaces/Attics) and rooms in the facility. There is no action required of the Principal.
- The Building Inspector shall visually inspect all areas that are identified in the Management Plan as ACBM or assumed ACBM. The date of the surveillance is recorded, the inspectors name and any changes in the conditions of the materials.
- The Building Inspector shall make a copy of the inspection document and insert into the front of the latest Management Plan (AHERA Three Year Reinspection report). The original document is returned to the LEA's Environmental Library and filed.

SCHOOL DISTRICT OF PHILADELPHIA  
Education Center  
440 North Broad Street  
Philadelphia, Pennsylvania 19130

Office of Environmental Management and Services

215-400-4750

AHERA  
Three Year Reinspection  
Outline of Events

- Pursuant to the Federal Environmental Protection Agency (EPA) mandate, as required by 40 CFR 763.85(b) the following procedure is to be implemented. At least once every three (3) years after a Management Plan is in effect, each Local Education Agency (LEA) shall conduct a reinspection of each building that it owns or leases that contains Asbestos Containing Building Material's (ACBM's) or is assumed to contain ACBM.
- Subsequent Three Year Re-inspections (2009, 2012, 2015, etc) shall start in the Fall (October, November, December, January). The Building Engineer/Assistant should assist the Building Inspector with appropriate access to all areas including (Crawlspaces/Attics) and rooms in the facility. There is no action required of the Principal.
- An accredited Building Inspector shall visually inspect and touch to determine friability, all areas that are identified in the Management Plan as ACBM or assumed ACBM. The date of the surveillance is recorded, the inspectors name and any changes in the conditions of the materials. The Building Inspectors state of accreditation and license number is required.
- After the inspection, the Building Inspector shall make a copy of the inspection documents and insert into the front of the latest Management Plan (AHERA Three Year Reinspection report). The original document is returned to the LEA's Environmental Library and filed.
- The Building Inspector shall return the reinspection data to the Management Planner to be assessed and determine appropriate response actions and a report issued (AHERA Three Year Reinspection report). One copy of the report is delivered to the schools Principal to be permanently retained with all previous environmental data. Another copy is retained in the LEA's Environmental Library.





**School District of Philadelphia**  
Office of Environmental Management & Services  
440 North Broad Street  
Philadelphia, PA 19130  
(215) 400-4750

**School District of Philadelphia  
Asbestos Management Program**

## TABLE OF CONTENTS

|  |         |
|--|---------|
| Definitions.....   | Page 9  |
| 1. Introduction.....   | Page 10 |
| 2. Summary of Asbestos Management Plan                               |         |
| 3. Asbestos Management Plan Execution.....                           | Page 11 |
| a. General Execution   |         |
| 4. Summary of Program Execution                                      |         |
| a. Asbestos Management Plan Execution                                |         |
| 5. Responsibilities  |         |
| a. OEMS  |         |
| b. Asbestos Worker/Supervisor "A-TEAM".....                          | Page 12 |
| c. Asbestos Designated Person  |         |
| d. Supervisor or Project Manager (Capital, Maintenance & Facilities) |         |
| e. Employee Capital.....   | Page 13 |
| f. Employee Maintenance  |         |
| g. Employee Facilities and Custodial                                 |         |
| 6. Requirements.....   | Page 14 |
| a. Employee Exposure Monitoring                                      |         |
| b. Employee Notification   |         |
| c. Observation of Monitoring   |         |
| d. Training Program  |         |
| e. Access of Information   |         |
| f. Record Keeping  |         |
| 7. AHERA O&M Plan.....   | Page 15 |
| a. Controls  |         |
| 8. O&M Response Actions.....   | Page 16 |
| a. Facility Maintenance Isolation of Area                            |         |
| b. Unlikely Contact with ACM/PACM                                    |         |
| c. Accidental Disturbance of ACM/PACM                                |         |
| d. Planned Disturbance of ACM/PACM                                   |         |
| e. Miscellaneous ACM/PACM.....                                       | Page 17 |
| f. Vinyl Asbestos Floor Tile   |         |
| g. Mastic/Adhesives  |         |
| h. Woven Vibration Dampers   |         |
| i. Other Work Practices  |         |
| j. Fiber Release Episodes  |         |
| 9. References and Resources.....                                     | Page 18 |

## **DEFINITIONS / ACRONYMS**

|                                   |  |
|-----------------------------------|--|
| <b>ACM/PACM:</b>                  | <b>Asbestos Containing Material/Potential Asbestos Containing Material</b>   |
| <b>AHERA:</b>                     | <b>Asbestos Hazard Emergency Response Act</b>  |
| <b>AIR FORM:</b>                  | <b>Asbestos Inspection Report Form</b>   |
| <b>Amended Water:</b>             | <b>Water to which a surfactant (soap) has been added</b>   |
| <b>AMP:</b>                       | <b>Asbestos Management Program/Asbestos Management Plan</b>  |
| <b>Asbestos Designate Person:</b> | <b>Individual assigned by the district to oversee asbestos related issues.</b>   |
| <b>Asbestos Regulated Area:</b>   | <b>Location that is posted as an asbestos work area in which only approved and accredited personnel are permitted to enter</b>         |
| <b>AST:</b>                       | <b>Asbestos Support Team involving approved and accredited school district tradespersons personnel that are school district person</b> |
| <b>A-TEAM:</b>                    | <b>School District of Philadelphia asbestos workers</b>  |
| <b>CIP:</b>                       | <b>Capital Improvement Program</b>   |
| <b>Consultant:</b>                | <b>Asbestos consulting firm hired by the District</b>  |
| <b>Demolition Directive:</b>      | <b>Memorandum – August 4, 2006 from Patrick Henwood</b>  |
| <b>EPA:</b>                       | <b>Environmental Protection Agency</b>   |
| <b>In House Personnel:</b>        | <b>School District of Philadelphia asbestos workers</b>  |
| <b>LEA:</b>                       | <b>Local Education Agency</b>  |
| <b>O&amp;M:</b>                   | <b>Operations and Maintenance</b>  |
| <b>OEMS:</b>                      | <b>Office of Environmental Management and Services</b>   |
| <b>OSHA:</b>                      | <b>Occupational Safety and Health Administration</b>   |
| <b>PEL:</b>                       | <b>Permissible Exposure Limit</b>  |
| <b>PSD or SDP:</b>                | <b>Philadelphia School District/School District of Philadelphia</b>  |
| <b>PSIT:</b>                      | <b>Philadelphia School Improvement Team</b>  |
| <b>STEL:</b>                      | <b>Short Term Exposure Limit</b>   |

## **1. Introduction**

The School District of Philadelphia, Asbestos Policy Statement:

“The School District of Philadelphia is dedicated to providing a safe and healthful work environment for its employees, students, faculty, contractors and visitors. In recognition of the potential health problems associated with asbestos, the School District of Philadelphia is committed to a comprehensive asbestos control program. This program is implemented and maintained through the School District of Philadelphia's Office of Environmental Management and Services (OEMS).”

OEMS has the responsibility of establishing procedures for asbestos abatement, asbestos inspection, air monitoring, renovation and demolition activities within all School District of Philadelphia owned or leased facilities.

These procedures are developed to ensure that:

- (1) People are not exposed to significant levels of asbestos fibers
- (2) Asbestos waste is handled and disposed of properly
- (3) Members of the School District of Philadelphia community have access to the Office of Environmental Management and Services for information, assistance, guidance, and interpretation regarding asbestos related matters.
- (4) Members of the School District of Philadelphia community have access to the Asbestos Management Plans as required and outlined in the US EPA AHERA regulations including annual written notification to all parents.
- (5) Compliance with all applicable Federal, State and Local Asbestos Regulations

Requirements outlined in this manual are mandatory in nature where the word “SHALL” is used and are advisory in nature where the word “SHOULD” is used.

## **2. Summary of Asbestos Management Program**

The School District of Philadelphia’s Asbestos Management Program was established to meet the requirements of Federal, State, and Local Regulations.

These regulations include, but are not limited to:

- US Environmental Protection Agency Asbestos Hazard Emergency Response Act (US EPA AHERA) and National Emissions Standard for Hazardous Air Pollutants subpart M, Part 61 (NESHAP);
- US Department of Labor, Occupational Safety and Health Administration (OSHA) General Industry Standard (29 CFR 1910.1001) and the OSHA Asbestos Standard for the Construction Industry (29 CFR 1926.1101);
- The Commonwealth of Pennsylvania, Department of Labor and Industry, Asbestos Occupations, Accreditation and Certification Act;
- The City of Philadelphia, Department of Public Health, Asbestos Control Regulations.

### **3. Asbestos Management Program Execution**

#### **a) General Execution**

The Office of Environmental Management and Services (OEMS) develops, implements and manages safety and health programs for the School District of Philadelphia faculty, staff and students and assists with ensuring that all contractors comply with Federal, State and Local Environmental Regulations. The OEMS provides the oversight of School District of Philadelphia employees (Asbestos A-Team), environmental consultants, and asbestos abatement contractors for all projects within the School District of Philadelphia concerning Asbestos Containing Materials.

The control of safety and health hazards at the School District of Philadelphia is primarily through the implementation of engineering, work practice and administrative controls. Personal Protective Equipment (PPE) is used to supplement these controls or whenever the controls are not feasible or are in the process of being implemented. PPE is also recommended whenever exposures to chemical, physical or biological agents can be prevented or reduced by its use.

This written program establishes the procedures necessary to:

- 1) meet established standards and federal regulations for occupational exposure to asbestos fibers;
- 2) meet the requirements of the City of Philadelphia Asbestos Control Regulations which encompasses the disturbance and/or abatement of asbestos containing building materials;
- 3) provide the necessary health and safety protection to the School District of Philadelphia staff, faculty, students, contractors and visitors.

This program is strengthened by input and cooperation with the Philadelphia Federation of Teachers (PFT), Health and Welfare Fund.

### **4. Summary of Program Execution**

#### **a) Asbestos Management Program Execution**

The Asbestos Management Program is administered by the Office of Environmental Management and Services (OEMS). OEMS provides the following services primarily through professional consultants:

- (1) exposure monitoring services;
- (2) building inspection/surveys (bulk sampling) for the identification of asbestos containing materials;
- (3) asbestos project design services;
- (4) asbestos abatement project and air monitoring services;
- (5) emergency response to fiber release episodes;
- (6) education/information;
- (7) medical monitoring;
- (8) training for School District of Philadelphia personnel

### **5. Responsibilities**

#### **a) Office of Environmental Management and Services**

OEMS is responsible for performing the following functions:

- (1) Developing and administering of the Asbestos Management Program.
- (2) Providing asbestos-related services to all School District of Philadelphia departments.
- (3) Conducting required training of the Asbestos Management Program and working jointly with departments to schedule training.
- (4) Identifying and posting areas where labeling/signage are required.
- (5) Medical Monitoring of OEMS "A-TEAM" and other departments "AST" Asbestos Program staff.

- (6) Certification and training as required for OEMS "A-TEAM" and other departments "AST" Asbestos program staff.
- (7) Record keeping as outlined in Section 3.5 and all records as by required by US EPA AHERA regulations.

**b) Asbestos Worker/Supervisor - "A-TEAM"**

- (1) OEMS shall ensure that all "A-TEAM" workers/supervisors adhere to the following requirements:
  - a) Attend an initial Worker/Supervisor Asbestos Course;
  - b) Maintain the annual re-certification per EPA AHERA requirements and Commonwealth of Pennsylvania Asbestos Occupations, Accreditation and Certifications Act;
  - c) Undergo an annual Asbestos Medical Evaluation;
  - d) Undergo an annual Respirator Medical Clearance;
  - e) Undergo an annual Respirator Fit Testing.

**c) Asbestos Designated Person**

The Asbestos Designated Person is responsible for:

- (1) Assuring the health and safety of employees, students and visitors in the School District of Philadelphia facilities under his/her control.
- (2) Being kept informed of all areas under his or her jurisdiction where potential asbestos exposures exist and initiating protection programs that adhere to the Asbestos Management Program requirements of this manual.
- (3) Assuring that Asbestos Management Program requirements are adhered to by principal investigators, project managers, supervisors, or division heads, and School District of Philadelphia personnel under their supervision.
- (4) Ensuring that all employees within the Asbestos Management Program comply with (OSHA 1910.1001 (j) (7) (iv)) and the US EPA AHERA regulations by attending the required training.
- (5) Ensure the posting of:
  - a) Warning labels/signage
  - b) Commonwealth of Pennsylvania Asbestos Abatement and Demolition/Renovation Notification form
  - c) Asbestos Inspection Reports (AIR) form (where required)
  - d) Ensuring that Construction Projects follow the Demolition Directive procedures as outlined in the August 4, 2006 letter.

**d) Supervisor or Project Manager (Capital, Maintenance and Facilities)**

Each person in charge of a project, maintenance/repair, renovation/demolition, or other activity from the Departments of Capital, Maintenance, and/or Facilities, where asbestos containing material may be present is responsible for:

Identifying, with the assistance of OEMS, asbestos containing building materials prior to any disturbance of these materials. Various Federal (EPA and OSHA) and Local (City of Philadelphia Asbestos Control Regulations) require Asbestos Inspections prior to renovation/demolition activities. This shall be accomplished by always following the Asbestos Management Program Procedures as follows:

- (1) Ensure that the requirements of the Asbestos Management Program Procedures are followed by all personnel, trades, and contractors who are involved with the project;

- (2) Review of the required Asbestos Inspection Report (AIR) form (Attachment 1) and AHERA Management Plan documents prior to activities that may disturb any Asbestos Containing Materials;
- (3) Perform all project related duties as outlined in the Project Management Responsibilities;
- (4) Keep the department chairperson or director informed on any actions proposed or taken regarding the Asbestos Management Plan;
- (5) Ensuring that Construction Projects follow the Demolition Directive procedure outlined in the August 4, 2006 letter.

**e) Employee – Capital**

School District of Philadelphia Capital employees and/or consultants shall:

- (1) Ensure that no suspect or asbestos containing building materials are disturbed in the course of the projects they are performing or managing. This shall be accomplished by notifying their supervisor and OEMS by issuance of a work order permit (a.k.a PSIT Service Request Form) and verifying that the materials which may be disturbed are non-asbestos containing. If this information is not available or verification has not been made, these materials should not be disturbed.
- (2) Immediately notify OEMS and their supervisor in the event of a potential fiber release episode upon discovery of visible damage to asbestos containing materials.
- (3) Ensuring that Construction Projects follow the Demolition Directive procedures as outlined in the August 4, 2006 letter.

The types of projects represented as part of the Capital Improvement Program are as follows:

- (1) Complete Renovation of an existing building that addresses all facility component concerns and educational program needs;
- (2) Major Renovation of an existing building addressing significant facility component and educational improvements;
- (3) Addition to an existing building (either as an attachment or stand-alone structure) to accommodate needed program space;
- (4) Conversion of an existing facility to accommodate a change in educational program;
- (5) Facility Component Improvement of specific facility needs (i.e. electrical or HVAC system upgrades, ADA improvements, life safety improvements, exterior renovations, etc.)

**f) Employee – Maintenance**

School District of Philadelphia Maintenance employees shall:

- (1) Ensure that no suspect or asbestos containing building materials are disturbed in the course of their duties or work they are performing. This shall be accomplished by notifying their supervisor and OEMS by issuance of a work order permit and verifying that the materials which may be disturbed are non-asbestos containing. If this information is not available or verification has not been made, these materials should not be disturbed.
- (2) Immediately notify OEMS and their supervisor in the event of a potential fiber release episode or upon discovery of visible damage to asbestos containing materials.
- (3) All employees involved in maintenance activities shall attend required Asbestos Awareness training program within 60 days of employment.

**g) Employee – Facilities & Custodial**

School District of Philadelphia Facilities and Custodial employees shall:



- (1) Ensure that no suspect or asbestos containing building materials are disturbed in the course of their duties or work they are performing. This shall be accomplished by notifying their supervisor and OEMS by issuance of a work permit and verifying that the materials which may be disturbed are non-asbestos containing. If this information is not available or verification has not been made, these materials should not be disturbed;
- (2) Immediately notify OEMS and their supervisor in the event of a potential fiber release episode or upon discovery of visible damage to asbestos containing materials.
- (3) All employees involved in Facilities and Custodial activities shall attend require Asbestos Awareness training program within 60 days of employment.

## **6. Requirements**

### **a) Employee Exposure Monitoring**

When information indicates that an employee's exposure to asbestos fibers may equal or exceed an 8-hour time-weighted average of 0.1 f/cc \* (per OSHA 1910.1001 & 1926.1101), OEMS shall develop and implement an asbestos exposure monitoring program. The sampling strategy shall be designed to identify employees by work task (job classification) that is exposed to asbestos fibers that exceed an 8-hour time-weighted average of 0.1 f/cc.

### **b) Employee Notification**

OEMS shall notify in writing, each employee exposed to asbestos fibers at or above an 8-hour time weighted average of 0.1 f/cc.

### **c) Observation and Monitoring**

OEMS shall provide employees or their representatives with an opportunity to observe any exposure measurements conducted.

### **d) Training Program**

OEMS shall institute a training program which meets the requirements of AHERA for all employees who perform maintenance operations in a facility/school which contains asbestos containing materials or presumed asbestos containing materials and 1910.1001 (j), and the Commonwealth of Pennsylvania Department of Labor and Industry and the City of Philadelphia Asbestos Control Regulations. The affected departments shall ensure employee participation in this program. The OEMS "A-TEAM" and other departments "AST" Asbestos Program staff training shall be conducted annually for each employee as required by all Federal, State and Local for each asbestos discipline.

All Asbestos Awareness training as required by AHERA shall be performed within 60 days of employment and shall include:

- Health effects of asbestos
- Locations of ACM and PACM in the building/facility
- Recognition of CM and PACM damage and deterioration
- Requirements of the OSHA 1910.1001 standard relating to maintenance
- Proper response to fiber release episodes
- Procedure to be followed to isolate areas affected by fiber release

### **e) Access to Information**

OEMS shall make available to affected employees or their representative's copies of the Occupational Safety and Health Administration (OSHA) General Industry Standard Part 1910.1001 and the department shall post a copy in the workplace.

### **f) Record Keeping**

OEMS shall maintain an accurate record of all employee exposure measurements. OEMS and/or the School District of Philadelphia Human Resources Department shall maintain records of employee medical monitoring program. OEMS shall maintain all employee training records. All records shall be provided upon request to employees, former employees, representatives designated by the individual employee.



## **7. AHERA OPERATIONS AND MAINTENANCE PLAN**

### **a) CONTROLS**

#### **i. Work Order System**

Minimizing disruption of ACM/PACM during maintenance and renovation activities is the primary goal and task encountered by OEMS. Operations and maintenance employees and contractors should be warned to avoid conducting any maintenance work which may disturb ACM/PACM. Initiating a work order system, where all work orders or requests are channeled through the Office of Environmental Management and Services (OEMS), will be the method used to control and minimize disruption of ACM/PACM.

Any work performed by in-house personnel or contractors that could or will impact ACM/PACM shall be coordinated by OEMS. A completed Asbestos Inspection Report Form (Attachment 1) shall be issued to in-house personnel and/or all contractors whose work could impact ACM/PACM. This form should accompany each contract issued to an outside contractor and posted on the jobsite.

All work order requests for maintenance and renovation activities in areas where ACM/PACM is suspected or known to be present are to be submitted to OEMS prior to proceeding with work. OEMS is responsible for reviewing asbestos survey records for information about the presence of ACM/PACM in the area where the work is to be performed. OEMS should physically inspect the area to ensure existing records reflect actual conditions. If no asbestos is present, a work order is not necessary and the planned actions can proceed. If ACM/PACM is found to be present in the area, OEMS will sign the work order application and obtain an approved and accredited asbestos contractor or assign OEMS "A-TEAM" to abate the ACM/PACM.

#### **ii. Regulated Areas**

The owner will identify and regulate all areas where airborne concentrations of ACM/PACM exceed the Permissible Exposure Limit (PEL)\* (Per OSHA determined to be 0.1 f/cc) and/or short term exposure limit (STEL) (Per OSHA determined to be 0.1 f/cc), or there is reasonable possibility that the (PEL) and/or (STEL) may be exceeded. All ACM/PACM removal activities involving thermal system insulation ACM/PACM (Class I), surfacing ACM/PACM (Class I), and miscellaneous ACM/PACM such as floor tile, roofing, and siding mastic, etc. (Class II), and repair and maintenance operations where thermal system insulation and surfacing ACM/PACM is likely to be disturbed (Class III) will be performed in accordance with federal, state, and local regulations. All asbestos abatement work and activities will be designed and managed as asbestos regulated areas. These areas will be demarcated and labeled.

#### **iii. Warning Signs**

Warning signs shall be displayed at all approaches to each asbestos regulated area. The asbestos abatement contractor will provide OSHA warning signs in all regulated areas during removal, repair, and other maintenance activities. OEMS will provide AIRs to all contractors who must inform all employees and supervisors working in locations contiguous to asbestos regulated areas of the potential hazards and work practices required.

#### **iv. Warning Labels**

Warning labels and/or signage shall be affixed to all raw materials, mixtures, scrap, waste, debris, and other products containing asbestos fibers, or to their containers. Generally, the asbestos abatement contractor or OEMS A-Team personnel will provide all warning labels for ACM/PACM containment.

## **8. O & M RESPONSE ACTIONS**

The Asbestos Management Program general O&M procedures are outlined in this section. Additional requirements specific to asbestos abatement activities are included in the Project Design documents for all Asbestos Abatement Work. Regular cleaning, inspection, and reporting of ACM/PACM deterioration or other problems must be diligently practiced by all employees including custodial and maintenance personnel.

### **a) Facility Maintenance Isolation of Area Responsibilities**

Maintenance personnel are often required to work in areas where ACM/PACM may potentially be disturbed. Most maintenance activities are conducted by in-house staff, outside contractors, or a combination.

Emergency fiber release episodes, such as pipe fitting or valve breaks, emergency boiler work, or mechanical equipment repair will be responded to by OEMS A-Team personnel or asbestos abatement contractor personnel. The owner's maintenance staff will: (1) isolate the emergency fiber release area; (2) post warning signs to prevent unauthorized access, and (3) notify their supervisor and OEMS. OEMS will ensure that the fiber release area remains isolated and is properly cleaned by and approved and accredited abatement contractor or by OEMS A-TEAM personnel.

### **b) Unlikely Contact with ACM/PACM**

Maintenance activities or repairs which can be performed without contacting or disturbing the ACM/PACM require little more than normal care and good workmanship. For example, valves which are either uncovered or covered with non-asbestos insulation can be packed or repaired without disturbing asbestos insulation on nearby pipes. The major precaution is to ensure that maintenance and custodial personnel are familiar with procedures such as isolating the area, posting warning signs, and notifying OEMS in the event of any accidental ACM/PACM disturbance.

### **c) Accidental Disturbance of ACM/PACM**

Maintenance and facilities personnel shall notify OEMS any time a fiber release is suspected. If friable ACM/PACM becomes airborne in the building,

### **d) Planned Disturbance of ACM/PACM**

Maintenance activities that may impact ACM/PACM include access to a valve, flange, duct, or related system component.

Where asbestos-containing insulation must be removed to maintain or repair the thermal system, the ACM/PACM will imminently be disturbed. ACM/PACM removal work shall be conducted by OEMS A-Team personnel or an approved and accredited asbestos abatement contractor.

If friable ACM/PACM becomes airborne in the building, maintenance and facilities personnel shall secure the area and contact OEMS. OEMS shall respond accordingly.

**e) Miscellaneous ACM/PACM**

Miscellaneous types of ACM/PACM may include vinyl asbestos floor tiles, mastics/adhesives and woven vibration dampers. Disturbance of these materials should be avoided. Routine maintenance activities involving these materials should not pose a problem if handled properly. Questions on the proper removal and disposal of miscellaneous ACM/PACM should be directed to OEMS. OEMS will contact an approved and accredited asbestos abatement contractor or utilize OEMS A-TEAM personnel to assist with miscellaneous ACM/PACM clean-up activities.

**f) Vinyl Asbestos Floor Tile**

Asbestos-containing floor tiles in good condition are considered non-friable unless they are crushed, drilled, sawed, sanded or disturbed by any activity that breaks up the material. Routine maintenance of these materials should employ the use of non-abrasive buffers and wet cleaning technique. Broken or loose floor tiles should be removed and disposed of as asbestos waste by OEMS. Remaining debris should be vacuumed with a HEPA vacuum and the area wet mopped using amended water.

**g) Mastics/Adhesives**

Mastics and adhesives containing asbestos in good condition are considered non-friable and do not pose a potential health concern unless crushed, drilled, sawed, sanded, or otherwise abraded. Questions on the proper removal should be directed to OEMS.

**h) Woven Vibration Dampers**

Woven vibration dampers in good condition are considered non-friable and do not pose a potential health concern unless cut, crushed, drilled, sawed, sanded, or otherwise abraded. Questions on the proper removal should be directed to OEMS.

**i) Other Work Practices**

Any special work not included in this section should be addressed to OEMS for review prior to the initiation of work that may involve the disturbance of ACM/PACM.

**j) Fiber Release Episodes**

Facilities and maintenance staff should report to OEMS the presence of asbestos debris, water or physical damage to ACM/PACM, or any other evidence of possible fiber release. OEMS should have the OEMS A-Team personnel or an approved and accredited abatement contractor respond to the site to clean up debris and make repairs as soon as possible. OEMS will also contact a consultant to conduct air monitoring and prepare a report and submit at project completion to OEMS for each episode. OEMS will forward the reports for each site location AHERA Management Plan accordingly.

## 9. REFERENCES and RESOURCES

Applicable regulations for asbestos projects impacted by renovation, demolition, and maintenance activities.

- **Philadelphia Air Management Services – Asbestos Control Unit**  
<http://www.phila.gov/health/units/ams/Asbestos/asbestos.html>
- **Pennsylvania Asbestos Occupations, Accreditation and Certification Act**  
<http://www.dli.state.pa.us/landi/cwp/view.asp?a=185&q=56262&landiNav=>
- **United States Environmental Protection Agency Asbestos Home Page**  
<http://www.epa.gov/asbestos/>
- **Occupational Safety and Health Administration (OSHA) Asbestos Home**  
<http://www.osha.gov/SLTC/asbestos>