

# SCHOOL DISTRICT OF PHILADELPHIA



## Asbestos Hazard Emergency Response Act “AHERA”

### THREE-YEAR RE-INSPECTION 2015-2016 and ASBESTOS MANAGEMENT PLAN for the

**Aloysius L. Fitzpatrick Elementary School**

**ULCS# 8390  
Building # B839001-1  
11061 Knights Road  
Philadelphia, Pennsylvania  
19154**

**Year Built: 1960**

November 2015

*Conducted by:*

Accredited Environmental Technologies, Incorporated  
Batta Environmental Associates, Incorporated  
Criterion Laboratories, Incorporated  
Environmental Testing Consultants, LLC  
G & C Environmental Services, Incorporated  
KEM Partners, Incorporated  
Synertech, Inc.  
TTI Environmental, Inc.  
USA Environmental Management, Inc.  
The Vertex Companies, Inc.

*Management Plan Prepared by:*

Criterion Labs, Inc and Synertech Inc.

*This report must remain in the Main Office as mandated by the US EPA AHERA Regulations.*

# **AHERA THREE-YEAR REINSPECTION VOLUME IX**

## **Table of Contents**

### **Transmittal Letter**

### **Executive Summary**

- I. Summary list of Confirmed Asbestos Containing Building Materials
- II. Summary list of Assumed Asbestos Contain Building Materials
- III. Summary list of Non-Asbestos Containing Building Materials
- IV. Summary list of Non Suspect Asbestos Containing Building Materials
- V. Summary List of Auditorium DATA for this location
- VI. Summary list of Attic and/or Crawlspace DATA for this location
- VII. Summary list of Pipe Chase/Pipe Shaft DATA for this location

### **Section I Report of Re-Inspection**

- A. Introduction
- B. Three-Year Re-inspection IX Overview
- C. Post- Management Plan Activities and Changes
  - C.1 - Sampling and Analysis
  - C.2 - New Floor Tile Sampling
  - C.3 - Abatement Activity
  - C.4 - Periodic (Six-Month) Surveillance (Damaged Materials)

### **Section II Re-Inspection Data**

- A. Introduction
- B. Re-Inspection Key Definitions
- C. Room by Room Location Log Report

### **Section III Certificates**

- A. Management Planner/Building Inspector Certificates

<b>Section IV</b>	<b>Cross Reference Table</b>	Page 1-8
	Asbestos Management Program	Page 9-19

SCHOOL DISTRICT OF PHILADELPHIA  
EDUCATIONAL CENTER  
440 NORTH BROAD STREET  
PHILADELPHIA, PENNSYLVANIA 19130

OFFICE OF ENVIRONMENTAL MANAGEMENT AND SERVICES

PHONE (215)-400-4750

January 2016

TO: All Principals  
All Building Administrators

FROM: Fran Burns  
Chief Operating Officer

Francine Locke, M.S., Director  
Office of Environmental Management and Services

SUBJECT: AHERA Three (3) Year Re-inspection IX report

In order to comply with the provisions of the Asbestos Hazard Emergency Response Act (AHERA) the attached report is submitted to you. The law requires that this report be kept in the Main/Principal's office. It cannot be removed from these locations. *If the school (program) is relocated to a different building, these environmental documents are to be safely retained for the next school/building occupants.* All asbestos reports must be available to the public and Federal EPA upon request.

  
\_\_\_\_\_  
Fran Burns  
Chief Operation Officer  
\_\_\_\_\_  
Francine Locke, M.S., Director  
Office of Environmental Management  
and Services

## **Executive Summary**

This Asbestos Hazard Emergency Response Act (AHERA) Three-Year Re-inspection “Volume # IX” Management Plan at this location, has been completed and the report of re-inspection submitted to the School District of Philadelphia. The re-inspections in all School District of Philadelphia buildings of 2015-2016 were conducted and completed between October 5<sup>th</sup>, 2015 through March 30<sup>th</sup>, 2016 as a joint project by Accredited Environmental Technologies, Inc., Batta Environmental Associates, Inc., Criterion Laboratories, Inc., Environmental Testing Consultants, LLC, G & C Environmental Services, Inc., KEM Partners, Inc., Synertech, Inc., TTI Environmental, Inc., USA Environmental Management, Inc. and The Vertex Companies, Inc.

In general, the School District of Philadelphia Office of Environmental Management and Services conducts Environmental Impact Evaluations and provides Asbestos Inspection Reports prior to any renovation, demolition and/or maintenance activities. The AHERA report must be reviewed prior to any renovation, demolition and/or maintenance activities in order to avoid the unknowing disturbance to Asbestos Containing Building Materials identified within this location. In addition, prior to work activities above all drop ceilings this report should be reviewed to avoid potential disturbances to Asbestos Containing Materials. Refer to Section IV of the Cross Reference Table, for additional Asbestos Management Program information. Contact the Office of Environmental Management and Services to have an Environmental Impact Evaluation conducted prior to any renovation, demolition and/or maintenance activities within this facility.

The information contained in this report was obtained from the original Asbestos Management Plan for the school, from update reports on changes and activities since the completion of the 1<sup>st</sup> Management Plan for each location and from all prior inspections performed and documented in Volume # I through Volume VIII (dated respectively 1992, 1995, 1998, 2001, 2004, 2007, 2010 or 2013) (if applicable) - and by this Three-Year Re-inspection of this school. The re-inspection report/Management Plan of 2015-2016 were reviewed and prepared collectively by Management Planner Megan Vala, Mary Anne Lerro of Criterion Laboratories, Inc. and/or Monique Causley, of Synertech Inc.

The 2015-2016 inspection process included the addition of a comprehensive Room by Room Inventory of all Thermal (T), Surfacing (S) and Miscellaneous (M) Materials specific to each room of this facility. Inspections of each room's thermal, ceilings, walls, floors and miscellaneous items regardless of Asbestos Content are categorized on the Room by Room Location Log Report for this location. Rooms or areas of the facility that were not accessible at the time of the inspection are marked with an "X". The Room by Room Location Log Report is found in Section II C of this Management Plan.

All Presumed or Suspect Asbestos Containing Building Materials (ACBMs), listed in the following summary charts are categorized as Confirmed, Assumed, Non-Asbestos, and/or Non-Suspect (ACBMs) were identified in the original Management Plan, or in the Volume I through Volume VIII AHERA Three-Year Re-inspection reports, and were re-inspected as part of this project.

As mandated by the U S EPA AHERA regulations, periodic Six-Month inspections and Three-Year Re-inspections of this location will be performed and the Inspection Data in this report will be updated accordingly.

Please feel free to contact the School District of Philadelphia's Office of Environmental Management and Services (OEMS) regarding any comments, questions, or concerns regarding this report or any Environmental related topic. OEMS staff can be reached at (215) 400 4750, via fax at (215) 400 4751 or via e-mail at [flocke@philasd.org](mailto:flocke@philasd.org) and/or [gfunod@philasd.org](mailto:gfunod@philasd.org).

Additional information can be found on our website. Here is the link to the OEMS website.  
<http://webgui.phila.k12.pa.us/offices/e/environmental>

## **I. Summary list of Confirmed Asbestos Containing Building Materials within this facility**

These charts are to be used for a quick reference\* in order to avoid the unknowing disturbance of Asbestos Containing Materials during any and all Operations, Maintenance, Renovation, and/or Demolition activities at this location. *These materials have been sampled and Laboratory Analysis has CONFIRMED the presence of Asbestos. Contact OEMS prior to the disturbance of any of the following materials.*

### **Confirmed Asbestos Containing Building Materials for this location**

Floor Tile VAT 9" x 9"	Pipe Fitting Insulation	Transite Closet
------------------------	-------------------------	-----------------

\* *Always refer to the Room by Room Logs for each specific material classification as the material classification findings may be different in various rooms throughout this facility.*

\*\* *Some Materials may have multiple classifications (Confirmed, Assumed, NAD and Non Suspect) within this facility.*

## II. Summary list of Assumed Asbestos Containing Building Materials within this facility

These charts are to be used for a quick reference\* in order to avoid the unknowing disturbance of Asbestos Containing Materials during any and all Operations, Maintenance, Renovation, and/or Demolition activities at this location. These materials have not been sampled and should not be disturbed until verification of Asbestos Content. Contact OEMS for assessment and sampling prior to the disturbance of these materials.

### Assumed Asbestos Containing Building Materials for this location

Duct Work	Emergency Generator Piping	Floor Tile VAT 12" x 12"
Sink Undercoat Mastic	Spline Ceiling Tile Glue Dots	Spline Wall Tile Glue Dots
Transite Closet	Vibration Damper Cloth	

*\* Always refer to the Room by Room Logs for each specific material classification as the material classification findings may be different in various rooms throughout this facility.*

*\*\* Some Materials may have multiple classifications (Confirmed, Assumed, NAD and Non Suspect) within this facility.*

### III. Summary list of Non-Asbestos Containing Building Materials within this facility

These charts are to be used for a quick reference\* in order to avoid the unknowing disturbance of Asbestos Containing Materials during any and all Operations, Maintenance, Renovation, and/or Demolition activities at this location. *These materials have been sampled and Laboratory Analysis has indicated NO Asbestos present or NO ASBESTOS DETECTED (NAD).*

#### Non- Asbestos Containing Building Materials for this location

Ceiling Tile 1' x 1'	Ceiling Tile 2' x 2'	Wall Tile 1' x 1'
----------------------	----------------------	-------------------

\* *Always refer to the Room by Room Logs for each specific material classification as the material classification findings may be different in various rooms throughout this facility.*

\*\* *Some Materials may have multiple classifications (Confirmed, Assumed, NAD and Non Suspect) within this facility.*



#### **IV. Summary list of Non-Suspect Asbestos Containing Building Materials within this facility**

These charts are to be used for a quick reference\* in order to avoid the unknowing disturbance of Asbestos Containing Materials during any and all Operations, Maintenance, Renovation, and/or Demolition activities at this location. These materials are not typically known to contain Asbestos.

##### **Non-Suspect Asbestos Containing Building Materials for this location**

Brick Wall	Carpet	Cement Floor
CMU	Concrete Block Wall	Concrete Ceiling
Fiberglass Ceiling Tile 2' x 4'	Fiberglass Pipe Fitting Insulation	Fiberglass Pipe Insulation
Metal Ceiling	Metal Walls	Partition Room Dividers
Sheetrock Wall	Steel Stair Deck	

*\* Always refer to the Room by Room Logs for each specific material classification as the material classification findings may be different in various rooms throughout this facility.*

*\*\* Some Materials may have multiple classifications (Confirmed, Assumed, NAD and Non Suspect) within this facility.*

## V. Summary list of Auditorium DATA for this location

These charts are to be used for a quick reference of the Auditorium DATA within this facility. Sampling of the Auditorium Ceilings throughout the District is more difficult because of the various ceiling heights. As sampling occurs this information is updated on a case by case basis for each specific location and facility.

### This is a list of known materials for this location's Auditorium

Auditorium		
Auditorium	Ceiling Tile 1' x 1'	NAD
Auditorium	Ceiling Tile 2' x 2'	NAD
Auditorium	Wall Tile 1' x 1'	NAD
Auditorium	Spline Ceiling/Wall Tile Glue Dots	Assumed
Auditorium	CMU	Non Suspect ACM
Auditorium	Floor Tile VAT 9" x 9"	Confirmed
Auditorium	Floor Tile VAT 9" x 9"	Confirmed
Auditorium	Floor Tile VAT 12" x 12"	Assumed
Auditorium Stage	Pipe Fitting Insulation	Confirmed
Auditorium Stage	Fiberglass Pipe Insulation	Non Suspect ACM
Auditorium Stage	Concrete Ceiling	Non Suspect ACM
Auditorium Stage	CMU	Non Suspect ACM
Auditorium Stage	Floor Tile VAT 9" x 9"	Confirmed
Auditorium Stage	Vibration Damper Cloth	Assumed

*\* Always refer to the Room by Room Logs for each specific material classification as the material classification findings may be different in various rooms throughout this facility.*

*\*\* Some Materials may have multiple classifications (Confirmed, Assumed, NAD and Non Suspect) within this facility.*

## VI. Summary list of Attic and/or Crawlspace DATA for this location

These charts are to be used for a quick reference regarding the Attics and/or Crawlspaces inspection DATA within this facility. Contact OEMS prior to entering any attic or crawlspace within this facility and refer to the below chart and legend for Category Rank determination. The Data relative to these spaces is updated as conditions change regarding Abatement or Renovation activity on a case by case basis for each specific location and facility. In general, Crawlspaces are below the basement or 1<sup>st</sup> floor and Attics are above the floor space.

### *Category Rank Legend*

"A" - No Asbestos Containing Materials - Sample Results indicate NO ACM on pipes, fittings, elbows, or equipment located within this functional space, and NO VISIBLE DEBRIS or DAMAGE observed at time of this inspection.
"B" - Asbestos Containing Materials Exist - Sample Results indicate ACM on pipes, fittings, elbows, or equipment located within this functional space, HOWEVER, NO VISIBLE DEBRIS or DAMAGE observed at time of this inspection.
"C" - Asbestos Containing Materials Exist - Sample Results indicate ACM on pipes, fittings, elbows, or equipment located within this functional space, and LOCALIZED VISIBLE DEBRIS or DAMAGE observed at time of this inspection.
"D" - Asbestos Containing Materials Exist - Sample Results indicate ACM on pipes, fittings, elbows, or equipment located within this functional space and DISTRIBUTED VISIBLE DEBRIS or SIGNIFICANT DAMAGE observed at time of this inspection.
"E" - No Bulk Sample Results Available SUSPECT ACM OBSERVED. Contact OEMS immediately for additional instructions.

Attic/Crawlspace	Access Area	Floor Surface	Category Rank	Comments
Attic above Pump Room	Pump Room Ladder	Concrete	"B"	VDC
Crawl Space	1 <sup>st</sup> Floor	Dirt	"A"	

## VII. Summary list of Pipe Chase/Pipe Shaft DATA for this location

These charts are to be used for a quick reference regarding the information known about the Pipe Chases and/or Pipe Shafts inspection DATA within this facility. Contact OEMS prior to performing renovation activities any Pipe Chase and/or Pipe Shaft within this facility and refer to the below chart and legend for Asbestos Content of various materials identified within each space. The Data relative to these spaces is updated as conditions change regarding Inspection, Abatement and/or Renovation activity on a case by case basis for each specific location and facility. In general, Pipe Chases are horizontal spaces and Pipe Shafts are vertical spaces.

<i>Element</i>	<i>Floor</i>	<i>On Site Room Name</i>	<i>Material</i>	<i>Confirmed / Assumed / NAD / Non Suspect</i>	<i>Amount of Material</i>	<i>Amount of Damage</i>
1	1	Pipe Chase in Custodial Closet near Classroom 106	Pipe Fitting Insulation	Confirmed	30 EA	0
1	1	Pipe Chase in Custodial Closet near Classroom 106	Fiberglass Pipe Insulation	Non Suspect ACM	100 LF	0
1	1	Pipe Chase in Custodial Closet near Classroom 106	Concrete Ceiling	Non Suspect ACM	60 SF	0
1	1	Pipe Chase in Custodial Closet near Classroom 106	CMU	Non Suspect ACM	460 SF	0
1	1	Pipe Chase in Custodial Closet near Classroom 106	Cement Floor	Non Suspect ACM	60 SF	0
1	2	Pipe Chase in Custodial Closet across from Classroom 212	Pipe Fitting Insulation	Confirmed	25 EA	0
1	2	Pipe Chase in Custodial Closet across from Classroom 212	Fiberglass Pipe Insulation	Non Suspect ACM	100 LF	0
1	2	Pipe Chase in Custodial Closet across from Classroom 212	Concrete Ceiling	Non Suspect ACM	45 SF	0
1	2	Pipe Chase in Custodial Closet across from Classroom 212	CMU	Non Suspect ACM	360 SF	0
1	2	Pipe Chase in Custodial Closet across from Classroom 212	Cement Floor	Non Suspect ACM	45 SF	0
1	3	Pipe Chase in Custodial Closet across from Classroom 312	No access	X	X	X

## **Section I**

### **Report of Re-Inspection**

#### **A. Introduction**

#### **B. Three-Year Re-Inspection IX Overview**

#### **C. Post-Management Plan Activities and Changes**

##### **C.1 Sampling and Analysis**

##### **C.2 New Floor Tile Sampling**

##### **C.3 Abatement Activity**

##### **C.4 Periodic Six-Month Surveillance (Damaged Materials)**

## **Section I - A**

### **Report of Re-inspection**

#### **Introduction**

The Three-Year Re-inspection IX was performed to fulfill the requirements of 40 CFR Part 763 - the Asbestos Hazard Emergency Response Act (AHERA). As required by AHERA, each Local Education Agency (LEA) must re-inspect all known confirmed or assumed Asbestos Containing Building Material (ACBM) located in the LEA's facilities. This re-inspection is intended to update the original Asbestos Management Plan for the LEA's facilities.

Multiple Building Inspectors of several firms performed the 2015/2016 re-inspection. The re-inspection report/Management Plan of 2015-2016 were reviewed and prepared collectively by Management Planner Megan Vala, Mary Anne Lerro of Criterion Laboratories, Inc. and Monique Causley, of Synertech Inc.

All of the certificates can be found in Section III.

During the re-inspection of each School District of Philadelphia facility, all of the Management Plans for that facility were reviewed. Information from the conclusions section of that report is included in this report. Additionally, information on activities such as abatements, cleanings, sampling and inspections, which have taken place since the completion of the original Management Plan, were reviewed during the re-inspection. Information on those activities is included in this report.

As mandated by the U S EPA AHERA regulations, all future periodic Six-Month inspections and Three-Year Re-inspections of this location will be performed and the Inspection Data in this report will be updated accordingly.

## **Section I - B**

### **Three-Year Re-inspection IX Overview**

Each homogeneous area of Asbestos Containing Building Material (ACBM) listed in the original Management Plan or in the 1992, 1995, 1998, 2001, etc., Three-Year Re-inspection reports were inspected for the AHERA Three-Year Re-inspection Volume IX, and the information for that material verified. Any changes to a homogeneous area listed in the updates to the Management Plans were verified. Any area of suspected ACBM found in the course of the re-inspection, and not listed in the Management Plan or updates, were either assumed to contain asbestos or sampled and analyzed to determine their asbestos content. Any such new areas either assumed to contain asbestos or determined through analysis to contain asbestos were included in the report of the Three-Year Re-inspection. The results of the AHERA Three-Year Re-inspection IX are tabulated in the Room by Room log reports located in *Section II-C* of this report.

As previously noted, all future periodic Six-Month inspections and Three-Year Re-inspections of this location will be performed and the Inspection Data in this report will be updated accordingly.

## Section I – C.1

### **Post Management Plan Activities/Changes**

Information on activities affecting Asbestos Containing Building Materials (ACBMs) at this location is contained in updates to the Management Plan. These updates are kept on file by the School District of Philadelphia and were reviewed for this project. Updates to the Management Plan include the following: *Sampling and Analysis, New Tile Installation, Abatement Activity and Periodic Six-Month Surveillance Data.*

#### **Sampling and Analysis**

*In the event Sampling occurs, data will be listed here.*



## **Section I – C.2**

Information on the installation of new floor tiles/renovation activities affecting Asbestos Containing Building Materials (ACBMs) at this location is contained in updates to the Management Plan. These updates are kept on file by the School District of Philadelphia and were reviewed for this project. Updates to the Management Plan include the following:

### **New Floor Tile Sampling**

*In the event that new tile is installed, the material must be tested prior to installation.*

## Section I – C.3

Information on the Asbestos Abatement and renovation activities affecting Asbestos Containing Building Materials (ACBMs) at this location is contained in updates to the Management Plan. These updates are kept on file by the School District of Philadelphia and were reviewed for this project. Updates to the Management Plan include the following:

### **Abatement Activity**

<i><b>Date</b></i>	<i><b>Floor</b></i>	<i><b>Location</b></i>	<i><b>Material</b></i>	<i><b>Color</b></i>	<i><b>Removed or Encapsulated</b></i>	<i><b>Quantity</b></i>
9/17/2015	B	Hallway between Cafeteria and Gym	Floor Tile 9" x 9"	Gray	Removed	13 SF
9/17/2015	1st	Auditorium (Rows K-P)	Floor Tile 9" x 9"	Gray	Removed	10 SF
9/17/2015	1st	Classroom 104	Floor Tile 9" x 9"	Gray	Removed	72 SF
9/17/2015	2nd	Hallway by South Stairwell	Floor Tile 9" x 9"	Gray	Removed	3 SF
9/17/2015	2nd	Classroom 218	Floor Tile 9" x 9"	Gray	Removed	6 SF
5/9/2016	3rd	Stairwell near Classrooms 307 and 318	Pipe Fitting Insulation	N/A	Encapsulated	1 EA
5/9/2016	2nd	Stairwell near Classrooms 207 and 218	Pipe Fitting Insulation	N/A	Encapsulated	<1 EA
5/9/2016	1st	Classroom 104	Pipe Fitting Insulation	N/A	Encapsulated	1 EA
5/9/2016	1st	Psychologist's Office 119	Pipe Fitting Insulation	N/A	Encapsulated	1 EA
5/9/2016	1st	Auditorium Stage	Pipe Fitting Insulation	N/A	Encapsulated	<1 EA
5/9/2016	B	School Police Office Restroom	Pipe Fitting Insulation	N/A	Encapsulated	<1 EA
5/9/2016	B	Classroom B4	Pipe Fitting Insulation	N/A	Encapsulated	<1 EA
5/9/2016	B	Women's Restroom across from Classroom B8	Pipe Fitting Insulation	N/A	Encapsulated	<1 EA
5/9/2016	B	Boy's Restroom across from Kitchen	Pipe Fitting Insulation	N/A	Encapsulated	1 EA
6/9/2016	B	Hallway outside Gym	Floor Tile VAT 9" x 9"	Tan	Removed	20 SF

## Section I – C.4

Information on the AHERA inspection that noted damage to various Building Materials at this location is contained in updates to the Management Plan. These updates are kept on file by the School District of Philadelphia and were reviewed for this project. Work orders are created for Corrective Action responses and tracked for completion. Updates to the Management Plan include the following:

### *Periodic (Six-Month) Surveillance (Damaged Materials)*

<i>Date</i>	<i>Element</i>	<i>Floor</i>	<i>On Site Room Name</i>	<i>Material</i>	<i>Amount of Material</i>	<i>Amount of Damage</i>
3/9/2016	1	GR	Gym	Pipe Fitting Insulation	135 EA	1 EA
3/9/2016	1	2	Library	Pipe Fitting Insulation	22 EA	1 EA
3/9/2016	1	2	Classroom 212	Pipe Fitting Insulation	8 EA	1 EA
3/9/2016	1	2	Classroom 207	Pipe Fitting Insulation	13 EA	1 EA
11/10/2016	1	GR	Classroom B8	Transite Closet	27 SF	1 SF
11/10/2016	1	GR	Women's Restroom across from Classroom B8	Pipe Fitting Insulation	7 EA	1 EA
11/10/2016	1	GR	Food Service Restroom and Storage	Pipe Fitting Insulation	6 EA	1 EA
11/10/2016	1	GR	Boy's Restroom across from Kitchen	Pipe Fitting Insulation	60 EA	2 EA
11/10/2016	1	1	Classroom 102	Transite Closet	54 SF	1 SF
11/10/2016	1	1	Classroom 104	Pipe Fitting Insulation	7 EA	2 EA
11/10/2016	1	1	Psychologist's Office 119	Pipe Fitting Insulation	18 EA	3 EA
11/10/2016	1	1	Classroom 106	Transite Closet	54 SF	1 SF
11/10/2016	1	1	Classroom 103	Transite Closet	54 SF	1 SF
11/10/2016	1	1	Classroom 110	Transite Closet	54 SF	1 SF
11/10/2016	1	1	Auditorium Stage	Pipe Fitting Insulation	28 EA	1 EA
11/10/2016	1	2	Classroom 205	Transite Closet	54 SF	1 SF
11/10/2016	1	2	Stairwell near Classrooms 207 and 218	Pipe Fitting Insulation	3 EA	1 EA
11/10/2016	1	3	Classroom 303	Transite Closet	54 SF	1 SF
11/10/2016	1	3	Stairwell near Classrooms 307 and 318	Pipe Fitting Insulation	4 EA	2 EA

## **Section II**

### **Re-Inspection Data**

#### **A. Introduction**

#### **B. Re-Inspection Key Definitions**

#### **C. Room by Room Location Log Report**

## **Section II - A**

### **Re-inspection Data**

#### Introduction

The following information documents the Three-Year Re-inspection IX of the subject school/facility. The Homogeneous Area Reports were produced using the building inspector's field data on the facility. The key to the Homogeneous Area Report is outlined in the following pages of this report.

**Section II - B**  
**(page 1 of 4)**

**SCHOOL DISTRICT OF PHILADELPHIA**  
**AHERA THREE YEAR RE-INSPECTION IX**

<b>ITEM</b>	<b>DEFINITION</b>
<b>ULCS#</b>	Individual identification number assigned to each school within the School District of Philadelphia.
<b>HOMOGENEOUS AREA ID#</b>	Identification number assigned to each homogeneous area in a school/facility. Each section of the homogeneous area ID is significant.  1010/01/01/01 <b>A B C D</b>  <b>A.</b> Is the ULCS# for the school. <b>B.</b> Designates the specific building/building area within the school. <b>C.</b> Designates the floor or level within the building/building area. <b>D.</b> Designates the homogeneous material within that floor or level. Note: Item D may be a number or a letter.
<b>SYSTEM AFFECTED</b>	Corresponds to the AHERA system for classifying materials.  <b>T</b> : Thermal System <b>S</b> : Surfacing System <b>M</b> : Miscellaneous
<b>ITEM AFFECTED</b>	Is a description of the homogeneous material.
<b>ORIGINAL INSPECTION DATA</b>	This section contains the information found in the original Management Plan (1988-1989).
<b>AMOUNT OF MATERIAL/ UNIT</b>	Quantity of material, and measuring unit. Units include: Square Feet (SF) Each (EA) Linear Feet (LF) Cubic Feet (CF).

**SCHOOL DISTRICT OF PHILADELPHIA  
AHERA THREE YEAR RE-INSPECTION IX**

**RE-INSPECTION FORM KEY**

<b>ITEM</b>	<b>DEFINITION</b>
<b>CND Condition</b>	Corresponds to AHERA condition rating for materials.  <b>0</b> : No Damage <b>1</b> : Damage <b>2</b> : Significant Damage
<b>DP Damage Potential</b>	Corresponds to the AHERA material assessment system.  <b>1</b> : Potential for Damage <b>2</b> : Potential for Significant Damage
<b>ASMD Assumed Asbestos</b>	This means that a material was not sampled for asbestos content during the original Management Plan inspection.
<b>RA Response Action</b>	This corresponds to the AHERA system of response action rating for materials.  <b>1</b> : Establish O&M Program <b>2</b> : Repair and Establish O&M Program <b>3</b> : Enclose <b>4</b> : Encapsulate <b>5</b> : Remove <b>6</b> : Partial Removal and Establish O&M Program
<b>CHANGES</b>	This section describes changes to the homogeneous material in the twenty-four years since the original AHERA inspection. The abbreviations are defined below.  <b>RMVD</b> : Removed <b>ENCL</b> : Enclosed <b>ENCP</b> : Encapsulated <b>DMGD</b> : Damaged <b>SMPLD</b> : Sampled <b>MTRL</b> : Material <b>RPRD</b> : Repaired <b>N/L</b> : None Located <b>RPLCD</b> : Replaced

**SCHOOL DISTRICT OF PHILADELPHIA  
AHERA THREE-YEAR RE-INSPECTION IX**

**RE-INSPECTION FORM KEY**

<b>ITEM</b>	<b>DEFINITION</b>												
<b>THREE YEAR RE-INSPECTION</b>	<p>This section contains the information obtained from the Three-Year Re-inspection IX. With three exceptions, the information categories are identical in format and meaning to those found in the original inspection data section. The three exceptions are defined below.</p>												
<b>DMGD AMT Amount Damaged</b>	<p>This section gives the quantity of damaged material in a homogeneous area. The quantity is shown in the same format as the amount of material/unit section.</p>												
<b>NF Newly Friable</b>	<p>This section identifies materials in the original Management Plan which have since become friable.</p>												
<b>RA Response Action</b>	<p>This rating is based on the AHERA regulations, and is comparable to the RA rating found in the "Original Inspection Data" section. The following table details the response actions.</p> <table><tr><td>1.</td><td>Establish O&amp;M Program</td></tr><tr><td>2.</td><td>Repair and Establish O&amp;M Program</td></tr><tr><td>3.</td><td>Enclose</td></tr><tr><td>4.</td><td>Encapsulate</td></tr><tr><td>5.</td><td>Remove</td></tr><tr><td>6.</td><td>Partial Removal and Establish O&amp;M Program</td></tr></table> <p>a.    <b>High Priority Response</b> The homogeneous material has been scheduled for abatement or other response action.</p> <p>b.    <b>Medium Priority Response</b> The homogeneous material will be scheduled for abatement or other response action as soon as the high priority responses have been addressed.</p> <p>c.    <b>Low Priority Response</b> The homogeneous material will be scheduled for abatement or other response action as soon as the medium priority responses have been addressed.</p> <p>d.    <b>On-Going Response/Operations and Maintenance</b> The homogeneous material does not require abatement or other response action at present, and should be included in the facility's on-going operations and maintenance program.</p>	1.	Establish O&M Program	2.	Repair and Establish O&M Program	3.	Enclose	4.	Encapsulate	5.	Remove	6.	Partial Removal and Establish O&M Program
1.	Establish O&M Program												
2.	Repair and Establish O&M Program												
3.	Enclose												
4.	Encapsulate												
5.	Remove												
6.	Partial Removal and Establish O&M Program												



**SCHOOL DISTRICT OF PHILADELPHIA  
AHERA THREE-YEAR RE-INSPECTION IX**

**RE-INSPECTION FORM KEY**

---

The information presented in the changes section has been compiled from a variety of sources, including the Re-inspection and the following:

- \* Quality Control/Quality Assurance Reports of asbestos abatement projects, prepared by consultants to the School District.
- \* Permit and Notification Forms for asbestos abatement projects.
- \* Periodic Surveillance Forms
- \* Operations and Maintenance activities performed by School District personnel.
- \* Verbal information from School District personnel.
- \* Reports of sampling and analysis of suspected materials by both School District personnel and outside consultants.

**ROOM BY  
ROOM  
LOCATION LOG  
REPORT**

This section gives information, including damage amount and location, for a specific homogeneous material on a room-by-room basis and follows the Re-inspection form.

*NOTE:* The disparate nature of the above sources of information prohibits the verification of much information within the scope of the AHERA Three-Year Re-inspection. Discrepancies and omissions may exist in this information, and therefore is included on an "as is" basis. The inspectors for the Three-Year Re-inspection IX evaluated homogeneous areas based on the materials current condition and location, as evidenced during the inspector's site visit.

## Section II - C

### Room by Room Location Log Report

These charts are to be used for a quick reference\* in order to avoid the unknowing disturbance of Asbestos Containing Materials during any and all Operations, Maintenance, Renovation, and/or Demolition activities at this location.

*NOTE:*

*Contact OEMS prior to the disturbance of any of the materials that are listed as **Confirmed and/or Assumed**.*

*The quantities listed for (NAD) non-asbestos containing materials and/or Non-Suspect Materials are only estimated and were not measured for the purpose of this report. Field verification of quantities for renovation purposes would be necessary.*

# 8390 Aloysius Fitzpatrick ES 2015 2016 AHERA Three-Year Report.xls

School District of Philadelphia			AHERA Three-Year Reinspection 2015-2016										Reinspection Date: 11/20/2015					
Aloysius L. Fitzpatrick Elementary School			Room by Room Location Log Report										Building Inspector: Paul Davis					
11061 Knights Road, Philadelphia, PA, 19154													Number: 050368					
ULCS# 8390													Management Planner: Megan Vala					
Year Built: 1960													Number: 740728					
Element	Floor	On Site Room Name	System Affected	Material Description	HID#	Confirmed/Assumed/NAD/Non Suspect ACM	Amount of Material	SF LF EA	Amount of Damage	SF LF EA	Color required for VAT	Comments/Description/Notes	Attic/Crawl Space Ranking	Damage Potential (DP)	Newly Friable (NF)	Response Action (RA)		
1	GR	Elevator	N/A	Metal Walls		Non Suspect ACM	306	SF	0	SF				N/A	N/A	N/A		
1	GR	Elevator	N/A	Metal Ceiling		Non Suspect ACM	72	SF	0	SF				N/A	N/A	N/A		
1	GR	Elevator	M	Floor Tile VAT 12" x 12"	8390/01/0G/RR	Assumed	72	SF	0	SF	Blue			1	No	1/D		
1	GR	Building Engineer's Office	T	Pipe Fitting Insulation	8390/01/0G/07	Confirmed	14	EA	0	EA				1	No	1/D		
1	GR	Building Engineer's Office	N/A	Fiberglass Pipe Insulation		Non Suspect ACM	40	LF	0	LF				N/A	N/A	N/A		
1	GR	Building Engineer's Office	N/A	Concrete Ceiling		Non Suspect ACM	450	SF	0	SF				N/A	N/A	N/A		
1	GR	Building Engineer's Office	N/A	Cement Floor		Non Suspect ACM	450	SF	0	SF				N/A	N/A	N/A		
1	GR	Building Engineer's Office	N/A	Concrete Block Wall		Non Suspect ACM	1800	SF	0	SF				N/A	N/A	N/A		
1	GR	Building Engineer's Office	M	Vibration Damper Cloth	8390/01/0G/EE	Assumed	5	SF	0	SF				1	No	1/D		
1	GR	Building Engineer's Office Restroom	T	Pipe Fitting Insulation	8390/01/0G/07	Confirmed	1	EA	0	EA				1	No	1/D		
1	GR	Building Engineer's Office Restroom	N/A	Fiberglass Pipe Insulation		Non Suspect ACM	5	LF	0	LF				N/A	N/A	N/A		
1	GR	Building Engineer's Office Restroom	N/A	Concrete Ceiling		Non Suspect ACM	18	SF	0	SF				N/A	N/A	N/A		
1	GR	Building Engineer's Office Restroom	N/A	Concrete Block Wall		Non Suspect ACM	360	SF	0	SF				N/A	N/A	N/A		
1	GR	Building Engineer's Office Restroom	M	Floor Tile VAT 9" x 9"	8390/01/0G/18	Confirmed	18	SF	0	SF	Brown			1	No	1/D		
1	GR	Building Engineer's Office Shower	N/A	Concrete Ceiling		Non Suspect ACM	11	SF	0	SF				N/A	N/A	N/A		
1	GR	Building Engineer's Office Shower	N/A	Concrete Block Wall		Non Suspect ACM	260	SF	0	SF				N/A	N/A	N/A		
1	GR	Building Engineer's Office Shower	N/A	Cement Floor		Non Suspect ACM	11	SF	0	SF				N/A	N/A	N/A		
1	GR	Boiler Room	N/A	Fiberglass Pipe Insulation		Non Suspect ACM	600	LF	0	LF				N/A	N/A	N/A		
1	GR	Boiler Room	N/A	Fiberglass Pipe Fitting Insulation		Non Suspect ACM	70	EA	0	EA				N/A	N/A	N/A		
1	GR	Boiler Room	N/A	Concrete Ceiling		Non Suspect ACM	2205	SF	0	SF				N/A	N/A	N/A		
1	GR	Boiler Room	N/A	Concrete Block Wall		Non Suspect ACM	3920	SF	0	SF				N/A	N/A	N/A		
1	GR	Boiler Room	N/A	Cement Floor		Non Suspect ACM	2205	SF	0	SF				N/A	N/A	N/A		
1	GR	Emergency Generator Room/Storage	N/A	Fiberglass Pipe Insulation		Non Suspect ACM	180	LF	0	LF				N/A	N/A	N/A		
1	GR	Emergency Generator Room/Storage	N/A	Concrete Ceiling		Non Suspect ACM	1320	SF	0	SF				N/A	N/A	N/A		
1	GR	Emergency Generator Room/Storage	N/A	Concrete Block Wall		Non Suspect ACM	2920	SF	0	SF				N/A	N/A	N/A		
1	GR	Emergency Generator Room/Storage	N/A	Cement Floor		Non Suspect ACM	1320	SF	0	SF				N/A	N/A	N/A		
1	GR	Emergency Generator Room/Storage	T	Emergency Generator Piping	8390/01/0G/KEM/PD/2604	Assumed	20	LF	0	LF				1	No	1/D		
1	GR	Emergency Generator Room/Storage	N/A	Sheetrock Wall		Non Suspect ACM	11	SF	0	SF				N/A	N/A	N/A		
1	GR	Fuel Oil Pump Room/Storage	N/A	Concrete Ceiling		Non Suspect ACM	330	SF	0	SF				N/A	N/A	N/A		
1	GR	Fuel Oil Pump Room/Storage	N/A	Concrete Block Wall		Non Suspect ACM	1480	SF	0	SF				N/A	N/A	N/A		
1	GR	Fuel Oil Pump Room/Storage	N/A	Cement Floor		Non Suspect ACM	330	SF	0	SF				N/A	N/A	N/A		
1	GR	Stairwell near Classroom B-2	T	Pipe Fitting Insulation	8390/01/0G/07	Confirmed	7	EA	0	EA				1	No	1/D		
1	GR	Stairwell near Classroom B-2	N/A	Fiberglass Pipe Insulation		Non Suspect ACM	30	LF	10	LF				N/A	N/A	N/A		
1	GR	Stairwell near Classroom B-2	N/A	Concrete Ceiling		Non Suspect ACM	180	SF	0	SF				N/A	N/A	N/A		
1	GR	Stairwell near Classroom B-2	N/A	CMU		Non Suspect ACM	1410	SF	0	SF				N/A	N/A	N/A		
1	GR	Stairwell near Classroom B-2	N/A	Cement Floor		Non Suspect ACM	370	SF	0	SF				N/A	N/A	N/A		
1	GR	Classroom B2	T	Pipe Fitting Insulation	8390/01/0G/07	Confirmed	65	EA	0	EA				1	No	1/D		
1	GR	Classroom B2	N/A	Fiberglass Pipe Insulation		Non Suspect ACM	300	LF	0	LF				N/A	N/A	N/A		
1	GR	Classroom B2	N/A	Concrete Ceiling		Non Suspect ACM	1215	SF	0	SF				N/A	N/A	N/A		
1	GR	Classroom B2	N/A	CMU		Non Suspect ACM	1440	SF	0	SF				N/A	N/A	N/A		
1	GR	Classroom B2	M	Floor Tile VAT 9" x 9"	8390/01/0G/18	Confirmed	642	SF	0	SF	Grey			1	No	1/D		
1	GR	Classroom B2	M	Floor Tile VAT 9" x 9"	8390/01/0G/18	Confirmed	34	SF	0	SF	Green			1	No	1/D		
1	GR	Classroom B2	M	Floor Tile VAT 12" x 12"	8390/01/0G/RR	Assumed	486	SF	0	SF	Grey			1	No	1/D		
1	GR	Classrooms B2 and B4 Restroom	T	Pipe Fitting Insulation	8390/01/0G/07	Confirmed	12	EA	0	EA				1	No	1/D		
1	GR	Classrooms B2 and B4 Restroom	N/A	Fiberglass Pipe Insulation		Non Suspect ACM	35	LF	0	LF				N/A	N/A	N/A		
1	GR	Classrooms B2 and B4 Restroom	N/A	Concrete Ceiling		Non Suspect ACM	80	SF	0	SF				N/A	N/A	N/A		
1	GR	Classrooms B2 and B4 Restroom	N/A	CMU		Non Suspect ACM	360	SF	0	SF				N/A	N/A	N/A		
1	GR	Classrooms B2 and B4 Restroom	M	Floor Tile VAT 12" x 12"	8390/01/0G/RR	Assumed	80	SF	0	SF	Grey			1	No	1/D		
1	GR	Classroom B2 Coatroom	T	Pipe Fitting Insulation	8390/01/0G/07	Confirmed	12	EA	0	EA				1	No	1/D		
1	GR	Classroom B2 Coatroom	N/A	Fiberglass Pipe Insulation		Non Suspect ACM	35	LF	0	LF				N/A	N/A	N/A		
1	GR	Classroom B2 Coatroom	N/A	Concrete Ceiling		Non Suspect ACM	120	SF	0	SF				N/A	N/A	N/A		
1	GR	Classroom B2 Coatroom	N/A	CMU		Non Suspect ACM	320	SF	0	SF				N/A	N/A	N/A		
1	GR	Classroom B2 Coatroom	M	Floor Tile VAT 9" x 9"	8390/01/0G/18	Confirmed	120	SF	0	SF	Grey			1	No	1/D		
1	GR	Classroom B2 Closet/Storage	T	Pipe Fitting Insulation	8390/01/0G/07	Confirmed	5	EA	0	EA				1	No	1/D		
1	GR	Classroom B2 Closet/Storage	N/A	Fiberglass Pipe Insulation		Non Suspect ACM	50	LF	0	LF				N/A	N/A	N/A		
1	GR	Classroom B2 Closet/Storage	N/A	Concrete Ceiling		Non Suspect ACM	50	SF	0	SF				N/A	N/A	N/A		
1	GR	Classroom B2 Closet/Storage	N/A	CMU		Non Suspect ACM	300	SF	0	SF				N/A	N/A	N/A		
1	GR	Classroom B2 Closet/Storage	N/A	Cement Floor		Non Suspect ACM	50	SF	0	SF				N/A	N/A	N/A		
1	GR	Classroom B1	T	Pipe Fitting Insulation	8390/01/0G/07	Confirmed	41	EA	0	EA				1	No	1/D		
1	GR	Classroom B1	N/A	Fiberglass Pipe Insulation		Non Suspect ACM	140	LF	0	LF				N/A	N/A	N/A		
1	GR	Classroom B1	N/A	Concrete Ceiling		Non Suspect ACM	1377	SF	0	SF				N/A	N/A	N/A		
1	GR	Classroom B1	N/A	CMU		Non Suspect ACM	1560	SF	0	SF				N/A	N/A	N/A		
1	GR	Classroom B1	M	Floor Tile VAT 9" x 9"	8390/01/0G/18	Confirmed	675	SF	0	SF	Tan			1	No	1/D		
1	GR	Classroom B1	M	Floor Tile VAT 12" x 12"	8390/01/0G/RR	Assumed	486	SF	0	SF	Grey			1	No	1/D		
1	GR	Classroom B1 Closet/Storage	T	Pipe Fitting Insulation	8390/01/0G/07	Confirmed	4	EA	0	EA				1	No	1/D		
1	GR	Classroom B1 Closet/Storage	N/A	Fiberglass Pipe Insulation		Non Suspect ACM	30	LF	0	LF				N/A	N/A	N/A		
1	GR	Classroom B1 Closet/Storage	N/A	Concrete Ceiling		Non Suspect ACM	60	SF	0	SF				N/A	N/A	N/A		
1	GR	Classroom B1 Closet/Storage	N/A	CMU		Non Suspect ACM	320	SF	0	SF				N/A	N/A	N/A		
1	GR	Classroom B1 Closet/Storage	M	Floor Tile VAT 9" x 9"	8390/01/0G/18	Confirmed	60	SF	0	SF	Tan			1	No	1/D		
1	GR	Classroom B1 Coatroom	T	Pipe Fitting Insulation	8390/01/0G/07	Confirmed	13	EA	0	EA				1	No	1/D		
1	GR	Classroom B1 Coatroom	N/A	Fiberglass Pipe Insulation		Non Suspect ACM	50	LF	0	LF				N/A	N/A	N/A		

# 8390 Aloysius Fitzpatrick ES 2015 2016 AHERA Three-Year Report.xls

School District of Philadelphia			AHERA Three-Year Reinspection 2015-2016										Reinspection Date: 11/20/2015					
Aloysius L. Fitzpatrick Elementary School			Room by Room Location Log Report										Building Inspector: Paul Davis					
11061 Knights Road, Philadelphia, PA, 19154													Number: 050368					
ULCS# 8390													Management Planner: Megan Vala					
Year Built: 1960													Number: 740728					
E l e m e n t	F l o o r	On Site Room Name	System Affected	Material Description	HID#	Confirmed/Assumed/NAD/ Non Suspect ACM	Amount of Material	SF LF EA	Amount of Damage	SF LF EA	Color required for VAT	Comments/Description/Notes	Attic/ Crawl/ Space Ranking	Damage Potential (DP)	Newly Friable (NF)	Response Action (RA)		
1	GR	Classroom B1 Coatroom	N/A	Concrete Ceiling		Non Suspect ACM	120	SF	0	SF				N/A	N/A	N/A		
1	GR	Classroom B1 Coatroom	N/A	CMU		Non Suspect ACM	320	SF	0	SF				N/A	N/A	N/A		
1	GR	Classroom B1 Coatroom	M	Floor Tile VAT 9" x 9"	8390/01/0G/18	Confirmed	114	SF	0	SF	Tan			1	No	1/D		
1	GR	Classroom B1 Coatroom	M	Floor Tile VAT 9" x 9"	8390/01/0G/18	Confirmed	6	SF	0	SF	Brown			1	No	1/D		
1	GR	Classroom B1 Restroom	T	Pipe Fitting Insulation	8390/01/0G/07	Confirmed	27	EA	0	EA				1	No	1/D		
1	GR	Classroom B1 Restroom	N/A	Fiberglass Pipe Insulation		Non Suspect ACM	60	LF	0	LF				N/A	N/A	N/A		
1	GR	Classroom B1 Restroom	N/A	Concrete Ceiling		Non Suspect ACM	96	SF	0	SF				N/A	N/A	N/A		
1	GR	Classroom B1 Restroom	N/A	CMU		Non Suspect ACM	400	SF	0	SF				N/A	N/A	N/A		
1	GR	Classroom B1 Restroom	M	Floor Tile VAT 12" x 12"	8390/01/0G/RR	Assumed	96	SF	0	SF	Grey			1	No	1/D		
1	GR	Classroom B1 Storage Area in Rear	T	Pipe Fitting Insulation	8390/01/0G/07	Confirmed	39	EA	0	EA				1	No	1/D		
1	GR	Classroom B1 Storage Area in Rear	N/A	Fiberglass Pipe Insulation		Non Suspect ACM	100	SF	0	SF				N/A	N/A	N/A		
1	GR	Classroom B1 Storage Area in Rear	N/A	Concrete Ceiling		Non Suspect ACM	162	SF	0	SF				N/A	N/A	N/A		
1	GR	Classroom B1 Storage Area in Rear	N/A	CMU		Non Suspect ACM	660	SF	0	SF				N/A	N/A	N/A		
1	GR	Classroom B1 Storage Area in Rear	N/A	Cement Floor		Non Suspect ACM	162	SF	0	SF				N/A	N/A	N/A		
1	GR	Classroom B4	T	Pipe Fitting Insulation	8390/01/0G/07	Confirmed	60	EA	1	EA		Small Gouge		1	Yes	5/A		
1	GR	Classroom B4	N/A	Fiberglass Pipe Insulation		Non Suspect ACM	250	LF	0	LF				N/A	N/A	N/A		
1	GR	Classroom B4	N/A	Concrete Ceiling		Non Suspect ACM	864	SF	0	SF				N/A	N/A	N/A		
1	GR	Classroom B4	N/A	CMU		Non Suspect ACM	1180	SF	0	SF				N/A	N/A	N/A		
1	GR	Classroom B4	M	Transite Closet	8390/01/0G/14	Confirmed	54	SF	0	SF				1	No	1/D		
1	GR	Classroom B4	M	Floor Tile VAT 9" x 9"	8390/01/0G/18	Confirmed	410	SF	0	SF	Grey			1	No	1/D		
1	GR	Classroom B4	M	Floor Tile VAT 9" x 9"	8390/01/0G/18	Confirmed	22	SF	0	SF	Green			1	No	1/D		
1	GR	Classroom B4	M	Floor Tile VAT 12" x 12"	8390/01/0G/RR	Assumed	432	SF	0	SF	Grey			1	No	1/D		
1	GR	Classroom B4	T	Sheetrock Wall		Non Suspect ACM	80	SF	0	SF				N/A	N/A	N/A		
1	GR	School Police Office	N/A	Pipe Fitting Insulation	8390/01/0G/07	Confirmed	23	EA	0	EA				1	No	1/D		
1	GR	School Police Office	N/A	Fiberglass Pipe Insulation		Non Suspect ACM	175	LF	0	LF				N/A	N/A	N/A		
1	GR	School Police Office	N/A	Concrete Ceiling		Non Suspect ACM	405	SF	0	SF				N/A	N/A	N/A		
1	GR	School Police Office	N/A	CMU		Non Suspect ACM	840	SF	0	SF				N/A	N/A	N/A		
1	GR	School Police Office	N/A	Cement Floor		Non Suspect ACM	405	SF	0	SF				N/A	N/A	N/A		
1	GR	School Police Office Restroom	T	Pipe Fitting Insulation	8390/01/0G/07	Confirmed	7	EA	1	EA		Gouges		1	Yes	5/A		
1	GR	School Police Office Restroom	N/A	Fiberglass Pipe Insulation		Non Suspect ACM	15	LF	0	LF				N/A	N/A	N/A		
1	GR	School Police Office Restroom	N/A	Concrete Ceiling		Non Suspect ACM	40	SF	0	SF				N/A	N/A	N/A		
1	GR	School Police Office Restroom	N/A	CMU		Non Suspect ACM	260	SF	0	SF				N/A	N/A	N/A		
1	GR	School Police Office Restroom	N/A	Cement Floor		Non Suspect ACM	40	SF	0	SF				N/A	N/A	N/A		
1	GR	Storage Room B6	T	Pipe Fitting Insulation	8390/01/0G/07	Confirmed	36	EA	0	EA				1	No	1/D		
1	GR	Storage Room B6	N/A	Fiberglass Pipe Insulation		Non Suspect ACM	160	LF	0	LF				N/A	N/A	N/A		
1	GR	Storage Room B6	N/A	Concrete Ceiling		Non Suspect ACM	972	SF	0	SF				N/A	N/A	N/A		
1	GR	Storage Room B6	N/A	CMU		Non Suspect ACM	1260	SF	0	SF				N/A	N/A	N/A		
1	GR	Storage Room B6	M	Floor Tile VAT 9" x 9"	8390/01/0G/18	Confirmed	972	SF	0	SF	Green			1	No	1/D		
1	GR	Water Meter Room located in Storage Room B6	T	Pipe Fitting Insulation	8390/01/0G/07	Confirmed	5	EA	0	EA				1	No	1/D		
1	GR	Water Meter Room located in Storage Room B6	N/A	Fiberglass Pipe Insulation		Non Suspect ACM	32	LF	0	LF				N/A	N/A	N/A		
1	GR	Water Meter Room located in Storage Room B6	N/A	Concrete Ceiling		Non Suspect ACM	84	SF	0	SF				N/A	N/A	N/A		
1	GR	Water Meter Room located in Storage Room B6	N/A	CMU		Non Suspect ACM	340	SF	0	SF				N/A	N/A	N/A		
1	GR	Water Meter Room located in Storage Room B6	M	Floor Tile VAT 9" x 9"	8390/01/0G/18	Confirmed	64	SF	0	SF	Green			1	No	1/D		
1	GR	Water Meter Room located in Storage Room B6	M	Floor Tile VAT 12" x 12"	8390/01/0G/RR	Assumed	20	SF	0	SF	Blue			1	No	1/D		
1	GR	Classroom B8	T	Pipe Fitting Insulation	8390/01/0G/07	Confirmed	22	EA	0	EA				1	No	1/D		
1	GR	Classroom B8	N/A	Fiberglass Pipe Insulation		Non Suspect ACM	70	LF	0	LF				N/A	N/A	N/A		
1	GR	Classroom B8	N/A	Concrete Ceiling		Non Suspect ACM	972	SF	0	SF				N/A	N/A	N/A		
1	GR	Classroom B8	N/A	CMU		Non Suspect ACM	1260	SF	0	SF				N/A	N/A	N/A		
1	GR	Classroom B8	M	Transite Closet	8390/01/0G/14	Confirmed	27	SF	1	SF		Less than 1 SF; Saw Cut Square in Material.		1	Yes	5/C		
1	GR	Classroom B8	M	Floor Tile VAT 9" x 9"	8390/01/0G/18	Confirmed	923	SF	0	SF	Grey			1	No	1/D		
1	GR	Classroom B8	M	Floor Tile VAT 9" x 9"	8390/01/0G/18	Confirmed	49	SF	0	SF	Green			1	No	1/D		
1	GR	Storage Room across from Classroom B6 (Telephone Mechanical Room)	T	Pipe Fitting Insulation	8390/01/0G/07	Confirmed	9	EA	0	EA				1	No	1/D		
1	GR	Storage Room across from Classroom B6 (Telephone Mechanical Room)	N/A	Fiberglass Pipe Insulation		Non Suspect ACM	32	LF	0	LF				N/A	N/A	N/A		
1	GR	Storage Room across from Classroom B6 (Telephone Mechanical Room)	N/A	Concrete Ceiling		Non Suspect ACM	189	SF	0	SF				N/A	N/A	N/A		
1	GR	Storage Room across from Classroom B6 (Telephone Mechanical Room)	N/A	CMU		Non Suspect ACM	680	SF	0	SF				N/A	N/A	N/A		
1	GR	Storage Room across from Classroom B6 (Telephone Mechanical Room)	N/A	Cement Floor		Non Suspect ACM	189	SF	0	SF				N/A	N/A	N/A		
1	GR	Women's Restroom across from Classroom B8	T	Pipe Fitting Insulation	8390/01/0G/07	Confirmed	7	EA	1	EA		Small Hole.		1	Yes	5/A		
1	GR	Women's Restroom across from Classroom B8	N/A	Fiberglass Pipe Insulation		Non Suspect ACM	30	LF	0	LF				N/A	N/A	N/A		
1	GR	Women's Restroom across from Classroom B8	N/A	Concrete Ceiling		Non Suspect ACM	49	SF	0	SF				N/A	N/A	N/A		
1	GR	Women's Restroom across from Classroom B8	N/A	CMU		Non Suspect ACM	280	SF	0	SF				N/A	N/A	N/A		
1	GR	Women's Restroom across from Classroom B8	N/A	Cement Floor		Non Suspect ACM	49	SF	0	SF				N/A	N/A	N/A		
1	GR	Kindergarden Only Restroom across from Classroom B8	T	Pipe Fitting Insulation	8390/01/0G/07	Confirmed	5	EA	0	EA				1	No	1/D		
1	GR	Kindergarden Only Restroom across from Classroom B8	N/A	Fiberglass Pipe Insulation		Non Suspect ACM	30	LF	0	LF				N/A	N/A	N/A		
1	GR	Kindergarden Only Restroom across from Classroom B8	N/A	Concrete Ceiling		Non Suspect ACM	56	SF	0	SF				N/A	N/A	N/A		
1	GR	Kindergarden Only Restroom across from Classroom B8	N/A	CMU		Non Suspect ACM	300	SF	0	SF				N/A	N/A	N/A		
1	GR	Kindergarden Only Restroom across from Classroom B8	N/A	Cement Floor		Non Suspect ACM	56	SF	0	SF				N/A	N/A	N/A		
1	GR	Hallway from Cafeteria to Classroom B2	T	Pipe Fitting Insulation	8390/01/0G/07	Confirmed	10	EA	0	EA				1	No	1/D		

# 8390 Aloysius Fitzpatrick ES 2015 2016 AHERA Three-Year Report.xls

School District of Philadelphia			AHERA Three-Year Reinspection 2015-2016										Reinspection Date: 11/20/2015					
Aloysius L. Fitzpatrick Elementary School			Room by Room Location Log Report										Building Inspector: Paul Davis					
11061 Knights Road, Philadelphia, PA, 19154													Number: 050368					
ULCS# 8390													Management Planner: Megan Vala					
Year Built: 1960													Number: 740728					
E l e m e n t	F i l o r	On Site Room Name	System Affected	Material Description	HID#	Confirmed/Assumed/NAD/ Non Suspect ACM	Amount of Material	SF LF EA	Amount of Damage	SF LF EA	Color required for VAT	Comments/Description/Notes	Attic/ Crawl Space Ranking	Damage Potential (DP)	Newly Friable (NF)	Response Action (RA)		
1	GR	Hallway from Cafeteria to Classroom B2	N/A	Fiberglass Pipe Insulation		Non Suspect ACM	200	LF	0	LF				N/A	N/A	N/A		
1	GR	Hallway from Cafeteria to Classroom B2	N/A	Concrete Ceiling		Non Suspect ACM	1179	SF	0	SF				N/A	N/A	N/A		
1	GR	Hallway from Cafeteria to Classroom B2	N/A	CMU		Non Suspect ACM	2710	SF	0	SF				N/A	N/A	N/A		
1	GR	Hallway from Cafeteria to Classroom B2	M	Floor Tile VAT 9" x 9"	8390/01/0G/18	Confirmed	36	SF	0	SF	Tan			1	No	1/D		
1	GR	Hallway from Cafeteria to Classroom B2	M	Floor Tile VAT 12" x 12"	8390/01/0G/RR	Assumed	871	SF	0	SF	Tan			1	No	1/D		
1	GR	Hallway from Cafeteria to Classroom B2	M	Floor Tile VAT 12" x 12"	8390/01/0G/RR	Assumed	218	SF	0	SF	Brown			1	No	1/D		
1	GR	Hallway from Cafeteria to Classroom B2	N/A	Cement Floor		Non Suspect ACM	54	SF	0	SF				N/A	N/A	N/A		
1	GR	Custodial Closet near Classrooms B6 and B8	T	Pipe Fitting Insulation	8390/01/0G/07	Confirmed	2	EA	0	EA				1	No	1/D		
1	GR	Custodial Closet near Classrooms B6 and B8	N/A	Fiberglass Pipe Insulation		Non Suspect ACM	20	LF	0	LF				N/A	N/A	N/A		
1	GR	Custodial Closet near Classrooms B6 and B8	N/A	Concrete Ceiling		Non Suspect ACM	35	SF	0	SF				N/A	N/A	N/A		
1	GR	Custodial Closet near Classrooms B6 and B8	N/A	CMU		Non Suspect ACM	240	SF	0	SF				N/A	N/A	N/A		
1	GR	Custodial Closet near Classrooms B6 and B8	N/A	Cement Floor		Non Suspect ACM	35	SF	0	SF				N/A	N/A	N/A		
1	GR	Cafeteria	T	Pipe Fitting Insulation	8390/01/0G/07	Confirmed	85	EA	0	EA				1	No	1/D		
1	GR	Cafeteria	N/A	Fiberglass Pipe Insulation		Non Suspect ACM	400	LF	0	LF				N/A	N/A	N/A		
1	GR	Cafeteria	N/A	Ceiling Tile 1' x 1'		NAD	3200	SF	0	SF				N/A	N/A	N/A		
1	GR	Cafeteria	M	Spline Ceiling Tile Glue Dots	8390/01/0G/KEM/PD/2603	Assumed	320	SF	0	SF				1	No	1/D		
1	GR	Cafeteria	N/A	CMU		Non Suspect ACM	3192	SF	0	SF				N/A	N/A	N/A		
1	GR	Cafeteria	M	Floor Tile VAT 12" x 12"	8390/01/0G/RR	Assumed	3200	SF	0	SF	Tan			1	No	1/D		
1	GR	Kitchen	T	Pipe Fitting Insulation	8390/01/0G/07	Confirmed	59	EA	0	EA				1	No	1/D		
1	GR	Kitchen	N/A	Fiberglass Pipe Insulation		Non Suspect ACM	300	LF	0	LF				N/A	N/A	N/A		
1	GR	Kitchen	N/A	Concrete Ceiling		Non Suspect ACM	810	SF	0	SF				N/A	N/A	N/A		
1	GR	Kitchen	N/A	CMU		Non Suspect ACM	1596	SF	0	SF				N/A	N/A	N/A		
1	GR	Kitchen	M	Floor Tile VAT 12" x 12"	8390/01/0G/RR	Assumed	810	SF	0	SF	Grey			1	No	1/D		
1	GR	Food Service Restroom and Storage	T	Pipe Fitting Insulation	8390/01/0G/07	Confirmed	6	EA	1	EA		Gouges. No Access (S2017)		1	Yes	5/A		
1	GR	Food Service Restroom and Storage	N/A	Fiberglass Pipe Insulation		Non Suspect ACM	30	LF	0	LF		No Access (S2017)		N/A	N/A	N/A		
1	GR	Food Service Restroom and Storage	N/A	Concrete Ceiling		Non Suspect ACM	78	SF	0	SF		No Access (S2017)		N/A	N/A	N/A		
1	GR	Food Service Restroom and Storage	N/A	CMU		Non Suspect ACM	532	SF	0	SF		No Access (S2017)		N/A	N/A	N/A		
1	GR	Food Service Restroom and Storage	N/A	Cement Floor		Non Suspect ACM	78	SF	0	SF		No Access (S2017)		N/A	N/A	N/A		
1	GR	Food Service Restroom and Storage	T	Duct Work	8390/01/0G/KEM/PD/1670	Assumed	144	SF	0	SF		Spoke to OEMS about this item/Assumed. No Access (S2017)		1	No	1/D		
1	GR	Storage Area in Cafeteria next to Food Service Restroom	T	Pipe Fitting Insulation	8390/01/0G/07	Confirmed	7	EA	0	EA		No Access (S2017)		1	No	1/D		
1	GR	Storage Area in Cafeteria next to Food Service Restroom	N/A	Fiberglass Pipe Insulation		Non Suspect ACM	40	LF	0	LF		No Access (S2017)		N/A	N/A	N/A		
1	GR	Storage Area in Cafeteria next to Food Service Restroom	N/A	Concrete Ceiling		Non Suspect ACM	63	SF	0	SF		No Access (S2017)		N/A	N/A	N/A		
1	GR	Storage Area in Cafeteria next to Food Service Restroom	N/A	CMU		Non Suspect ACM	518	SF	0	SF		No Access (S2017)		N/A	N/A	N/A		
1	GR	Storage Area in Cafeteria next to Food Service Restroom	N/A	Cement Floor		Non Suspect ACM	63	SF	0	SF		No Access (S2017)		N/A	N/A	N/A		
1	GR	Storage Area in Cafeteria next to Food Service Restroom	T	Duct Work	8390/01/0G/KEM/PD/1670	Assumed	72	SF	0	SF		Spoke to OEMS about this item/Assumed. No Access (S2017)		1	No	1/D		
1	GR	Kitchen Storage Area/Former Money Safe Room	T	Pipe Fitting Insulation	8390/01/0G/07	Confirmed	3	EA	0	EA		No Access (S2017)		1	No	1/D		
1	GR	Kitchen Storage Area/Former Money Safe Room	N/A	Fiberglass Pipe Insulation		Non Suspect ACM	30	LF	0	LF		No Access (S2017)		N/A	N/A	N/A		
1	GR	Kitchen Storage Area/Former Money Safe Room	N/A	Concrete Ceiling		Non Suspect ACM	48	SF	0	SF		No Access (S2017)		N/A	N/A	N/A		
1	GR	Kitchen Storage Area/Former Money Safe Room	N/A	CMU		Non Suspect ACM	308	SF	0	SF		No Access (S2017)		N/A	N/A	N/A		
1	GR	Kitchen Storage Area/Former Money Safe Room	N/A	Brick Wall		Non Suspect ACM	84	SF	0	SF		No Access (S2017)		N/A	N/A	N/A		
1	GR	Kitchen Storage Area/Former Money Safe Room	N/A	Cement Floor		Non Suspect ACM	48	SF	0	SF		No Access (S2017)		N/A	N/A	N/A		
1	GR	Women's Restroom across from Kitchen	T	Pipe Fitting Insulation	8390/01/0G/07	Confirmed	6	EA	0	EA				1	No	1/D		
1	GR	Women's Restroom across from Kitchen	N/A	Fiberglass Pipe Insulation		Non Suspect ACM	40	LF	0	LF				N/A	N/A	N/A		
1	GR	Women's Restroom across from Kitchen	N/A	Concrete Ceiling		Non Suspect ACM	72	SF	0	SF				N/A	N/A	N/A		
1	GR	Women's Restroom across from Kitchen	N/A	CMU		Non Suspect ACM	504	SF	0	SF				N/A	N/A	N/A		
1	GR	Women's Restroom across from Kitchen	N/A	Cement Floor		Non Suspect ACM	72	SF	0	SF				N/A	N/A	N/A		
1	GR	Classroom B10 (Music Room)	T	Pipe Fitting Insulation	8390/01/0G/07	Confirmed	16	EA	0	EA				1	No	1/D		
1	GR	Classroom B10 (Music Room)	N/A	Fiberglass Pipe Insulation		Non Suspect ACM	180	LF	0	LF				N/A	N/A	N/A		
1	GR	Classroom B10 (Music Room)	N/A	Ceiling Tile 1' x 1'		NAD	884	SF	0	SF				N/A	N/A	N/A		
1	GR	Classroom B10 (Music Room)	M	Spline Ceiling Tile Glue Dots	8390/01/0G/KEM/PD/2603	Assumed	88	SF	0	SF				1	No	1/D		
1	GR	Classroom B10 (Music Room)	N/A	CMU		Non Suspect ACM	1560	SF	0	SF				N/A	N/A	N/A		
1	GR	Classroom B10 (Music Room)	M	Floor Tile VAT 9" x 9"	8390/01/0G/18	Confirmed	730	SF	0	SF	Brown			1	No	1/D		
1	GR	Classroom B10 (Music Room)	M	Floor Tile VAT 9" x 9"	8390/01/0G/18	Confirmed	50	SF	0	SF	Green			1	No	1/D		
1	GR	Classroom B10 (Music Room)	M	Floor Tile VAT 9" x 9"	8390/01/0G/18	Confirmed	41	SF	0	SF	Black			1	No	1/D		
1	GR	Classroom B10 (Music Room)	M	Floor Tile VAT 12" x 12"	8390/01/0G/RR	Assumed	63	SF	0	SF	Brown			1	No	1/D		
1	GR	Boy's Restroom across from Kitchen	T	Pipe Fitting Insulation	8390/01/0G/07	Confirmed	60	EA	2	EA		Gouges.		1	Yes	5/A		
1	GR	Boy's Restroom across from Kitchen	N/A	Fiberglass Pipe Insulation		Non Suspect ACM	250	LF	0	LF				N/A	N/A	N/A		
1	GR	Boy's Restroom across from Kitchen	N/A	Concrete Ceiling		Non Suspect ACM	459	SF	0	SF				N/A	N/A	N/A		
1	GR	Boy's Restroom across from Kitchen	N/A	CMU		Non Suspect ACM	1056	SF	0	SF				N/A	N/A	N/A		
1	GR	Boy's Restroom across from Kitchen	N/A	Cement Floor		Non Suspect ACM	459	SF	0	SF				N/A	N/A	N/A		
1	GR	Stairwell near Classroom B10 to Schoolyard	N/A	Fiberglass Pipe Insulation		Non Suspect ACM	60	LF	0	LF				N/A	N/A	N/A		
1	GR	Stairwell near Classroom B10 to Schoolyard	N/A	Concrete Ceiling		Non Suspect ACM	90	SF	0	SF				N/A	N/A	N/A		
1	GR	Stairwell near Classroom B10 to Schoolyard	N/A	CMU		Non Suspect ACM	1110	SF	0	SF				N/A	N/A	N/A		
1	GR	Stairwell near Classroom B10 to Schoolyard	N/A	Cement Floor		Non Suspect ACM	270	SF	0	SF				N/A	N/A	N/A		
1	GR	Girl's Restroom across from Classroom B10	T	Pipe Fitting Insulation	8390/01/0G/07	Confirmed	32	EA	0	EA				1	No	1/D		
1	GR	Girl's Restroom across from Classroom B10	N/A	Fiberglass Pipe Insulation		Non Suspect ACM	160	LF	0	LF				N/A	N/A	N/A		
1	GR	Girl's Restroom across from Classroom B10	N/A	Concrete Ceiling		Non Suspect ACM	351	SF	0	SF				N/A	N/A	N/A		
1	GR	Girl's Restroom across from Classroom B10	N/A	CMU		Non Suspect ACM	960	SF	0	SF				N/A	N/A	N/A		
1	GR	Girl's Restroom across from Classroom B10	N/A	Cement Floor		Non Suspect ACM	351	SF	0	SF				N/A	N/A	N/A		
1	GR	Hallway from Cafeteria to Gymnasium	T	Pipe Fitting Insulation	8390/01/0G/07	Confirmed	14	EA	0	EA				1	No	1/D		

# 8390 Aloysius Fitzpatrick ES 2015 2016 AHERA Three-Year Report.xls

		School District of Philadelphia		AHERA Three-Year Reinspection 2015-2016										Reinspection Date: 11/20/2015					
		Aloysius L. Fitzpatrick Elementary School		Room by Room Location Log Report										Building Inspector: Paul Davis					
		11061 Knights Road, Philadelphia, PA, 19154												Number: 050368					
		ULCS# 8390												Management Planner: Megan Vala					
		Year Built: 1960												Number: 740728					
E l e m e n t	F l o o r	On Site Room Name		System Affected	Material Description	HID#	Confirmed/Assumed/NAD/ Non Suspect ACM	Amount of Material	SF LF EA	Amount of Damage	SF LF EA	Color required for VAT	Comments/Description/Notes	Attic/ Crawl Space Ranking	Damage Potential (DP)	Newly Friable (NF)	Response Action (RA)		
1	GR	Hallway from Cafeteria to Gymnasium	N/A		Fiberglass Pipe Insulation		Non Suspect ACM	110	LF	0	LF				N/A	N/A	N/A		
1	GR	Hallway from Cafeteria to Gymnasium	N/A		Concrete Ceiling		Non Suspect ACM	603	SF	0	SF				N/A	N/A	N/A		
1	GR	Hallway from Cafeteria to Gymnasium	N/A		CMU		Non Suspect ACM	2128	SF	0	SF				N/A	N/A	N/A		
1	GR	Hallway from Cafeteria to Gymnasium	M		Floor Tile VAT 9" x 9"	8390/01/0G/18	Confirmed	20	SF	0	SF	White			1	No	1/D		
1	GR	Hallway from Cafeteria to Gymnasium	M		Floor Tile VAT 9" x 9"	8390/01/0G/18	Confirmed	36	SF	0	SF	Brown			1	No	1/D		
1	GR	Hallway from Cafeteria to Gymnasium	M		Floor Tile VAT 9" x 9"	8390/01/0G/18	Confirmed	427	SF	0	SF	Tan			1	No	1/D		
1	GR	Hallway from Cafeteria to Gymnasium	M		Floor Tile VAT 9" x 9"	8390/01/0G/18	Confirmed	27	SF	0	SF	Green			1	No	1/D		
1	GR	Hallway from Cafeteria to Gymnasium	M		Floor Tile VAT 12" x 12"	8390/01/0G/RR	Assumed	93	SF	0	SF	Tan			1	No	1/D		
1	GR	Gym	T		Pipe Fitting Insulation	8390/01/0G/07	Confirmed	135	EA	0	EA				1	No	1/D		
1	GR	Gym	N/A		Fiberglass Pipe Insulation		Non Suspect ACM	800	LF	0	LF				N/A	N/A	N/A		
1	GR	Gym	N/A		Concrete Ceiling		Non Suspect ACM	4800	SF	0	SF				N/A	N/A	N/A		
1	GR	Gym	N/A		CMU		Non Suspect ACM	5600	SF	0	SF				N/A	N/A	N/A		
1	GR	Gym	M		Floor Tile VAT 9" x 9"	8390/01/0G/18	Confirmed	4474	SF	0	SF	Tan			1	No	1/D		
1	GR	Gym	M		Floor Tile VAT 9" x 9"	8390/01/0G/18	Confirmed	236	SF	0	SF	Brown			1	No	1/D		
1	GR	Gym	M		Floor Tile VAT 12" x 12"	8390/01/0G/RR	Assumed	90	SF	0	SF	Tan			1	No	1/D		
1	GR	Gym	M		Vibration Damper Cloth	8390/01/0G/EE	Assumed	20	SF	0	SF				1	No	1/D		
1	GR	Gym Storage Room adjacent to Gym Office	T		Pipe Fitting Insulation	8390/01/0G/07	Confirmed	7	EA	0	EA				1	No	1/D		
1	GR	Gym Storage Room adjacent to Gym Office	N/A		Fiberglass Pipe Insulation		Non Suspect ACM	70	LF	2	LF				N/A	N/A	N/A		
1	GR	Gym Storage Room adjacent to Gym Office	N/A		Concrete Ceiling		Non Suspect ACM	117	SF	0	SF				N/A	N/A	N/A		
1	GR	Gym Storage Room adjacent to Gym Office	N/A		CMU		Non Suspect ACM	880	SF	0	SF				N/A	N/A	N/A		
1	GR	Gym Storage Room adjacent to Gym Office	M		Floor Tile VAT 9" x 9"	8390/01/0G/18	Confirmed	117	SF	0	SF	Tan			1	No	1/D		
1	GR	Gym Office	T		Pipe Fitting Insulation	8390/01/0G/07	Confirmed	13	EA	0	EA				1	No	1/D		
1	GR	Gym Office	N/A		Fiberglass Pipe Insulation		Non Suspect ACM	110	LF	0	LF				N/A	N/A	N/A		
1	GR	Gym Office	N/A		Concrete Ceiling		Non Suspect ACM	108	SF	0	SF				N/A	N/A	N/A		
1	GR	Gym Office	N/A		CMU		Non Suspect ACM	840	SF	0	SF				N/A	N/A	N/A		
1	GR	Gym Office	M		Floor Tile VAT 9" x 9"	8390/01/0G/18	Confirmed	103	SF	0	SF	Tan			1	No	1/D		
1	GR	Gym Office	M		Floor Tile VAT 9" x 9"	8390/01/0G/18	Confirmed	5	SF	0	SF	Brown			1	No	1/D		
1	GR	Gym Office	M		Vibration Damper Cloth	8390/01/0G/EE	Assumed	16	SF	0	SF				1	No	1/D		
1	GR	Gym Storage Room	T		Pipe Fitting Insulation	8390/01/0G/07	Confirmed	23	EA	0	EA				1	No	1/D		
1	GR	Gym Storage Room	N/A		Fiberglass Pipe Insulation		Non Suspect ACM	80	LF	0	LF				N/A	N/A	N/A		
1	GR	Gym Storage Room	N/A		Concrete Ceiling		Non Suspect ACM	60	SF	0	SF				N/A	N/A	N/A		
1	GR	Gym Storage Room	N/A		CMU		Non Suspect ACM	680	SF	0	SF				N/A	N/A	N/A		
1	GR	Gym Storage Room	M		Floor Tile VAT 9" x 9"	8390/01/0G/18	Confirmed	60	SF	0	SF	Tan			1	No	1/D		
1	GR	Stairwell from Gym to Schoolyard	T		Pipe Fitting Insulation	8390/01/0G/07	Confirmed	6	EA	0	EA				1	No	1/D		
1	GR	Stairwell from Gym to Schoolyard	N/A		Fiberglass Pipe Insulation		Non Suspect ACM	5	LF	0	LF				N/A	N/A	N/A		
1	GR	Stairwell from Gym to Schoolyard	N/A		Steel Stair Deck		Non Suspect ACM	90	SF	0	SF				N/A	N/A	N/A		
1	GR	Stairwell from Gym to Schoolyard	N/A		CMU		Non Suspect ACM	1680	SF	0	SF				N/A	N/A	N/A		
1	GR	Stairwell from Gym to Schoolyard	N/A		Cement Floor		Non Suspect ACM	320	SF	0	SF				N/A	N/A	N/A		
1	1	Stairwell near Classroom 109	N/A		Fiberglass Pipe Insulation		Non Suspect ACM	1	LF	0	LF				N/A	N/A	N/A		
1	1	Stairwell near Classroom 109	N/A		Concrete Ceiling		Non Suspect ACM	90	SF	0	SF				N/A	N/A	N/A		
1	1	Stairwell near Classroom 109	N/A		CMU		Non Suspect ACM	1110	SF	0	SF				N/A	N/A	N/A		
1	1	Stairwell near Classroom 109	N/A		Cement Floor		Non Suspect ACM	180	SF	0	SF				N/A	N/A	N/A		
1	1	Classroom 109	T		Pipe Fitting Insulation	8390/01/01/06	Confirmed	11	EA	0	EA				1	No	1/D		
1	1	Classroom 109	N/A		Fiberglass Pipe Insulation		Non Suspect ACM	54	LF	0	LF				N/A	N/A	N/A		
1	1	Classroom 109	N/A		Ceiling Tile 1' x 1'		NAD	648	SF	0	SF				N/A	N/A	N/A		
1	1	Classroom 109	M		Spline Ceiling Tile Glue Dots	8390/01/01/KEM/DP/2603	Assumed	65	SF	0	SF				1	No	1/D		
1	1	Classroom 109	N/A		CMU		Non Suspect ACM	1020	SF	0	SF				N/A	N/A	N/A		
1	1	Classroom 109	M		Transite Closet	8390/01/01/15	Confirmed	36	SF	0	SF				1	No	1/D		
1	1	Classroom 109	T		Floor Tile VAT 9" x 9"	8390/01/01/19	Confirmed	648	SF	0	SF	Tan			1	No	1/D		
1	1	Book Closet across from Classroom 109	T		Pipe Fitting Insulation	8390/01/01/06	Confirmed	11	EA	0	EA				1	No	1/D		
1	1	Book Closet across from Classroom 109	N/A		Fiberglass Pipe Insulation		Non Suspect ACM	30	LF	0	LF				N/A	N/A	N/A		
1	1	Book Closet across from Classroom 109	N/A		Concrete Ceiling		Non Suspect ACM	216	SF	0	SF				N/A	N/A	N/A		
1	1	Book Closet across from Classroom 109	N/A		CMU		Non Suspect ACM	700	SF	0	SF				N/A	N/A	N/A		
1	1	Book Closet across from Classroom 109	M		Floor Tile VAT 9" x 9"	8390/01/01/19	Confirmed	205	SF	0	SF	Tan			1	No	1/D		
1	1	Book Closet across from Classroom 109	M		Floor Tile VAT 9" x 9"	8390/01/01/19	Confirmed	11	SF	0	SF	Brown			1	No	1/D		
1	1	Book Closet across from Classroom 109	T		Pipe Fitting Insulation	8390/01/01/06	Confirmed	6	EA	0	EA				1	No	1/D		
1	1	Classroom 101	N/A		Fiberglass Pipe Insulation		Non Suspect ACM	110	LF	0	LF				N/A	N/A	N/A		
1	1	Classroom 101	N/A		Concrete Ceiling		Non Suspect ACM	972	SF	0	SF				N/A	N/A	N/A		
1	1	Classroom 101	N/A		CMU		Non Suspect ACM	1260	SF	0	SF				N/A	N/A	N/A		
1	1	Classroom 101	N/A		Sheetrock Wall		Non Suspect ACM	54	SF	0	SF		Over Closet; Transite Removed.		N/A	N/A	N/A		
1	1	Classroom 101	M		Floor Tile VAT 9" x 9"	8390/01/01/19	Confirmed	918	SF	0	SF	Tan			1	No	1/D		
1	1	Classroom 101	M		Floor Tile VAT 9" x 9"	8390/01/01/19	Confirmed	48	SF	0	SF	Brown			1	No	1/D		
1	1	Classroom 101	M		Floor Tile VAT 12" x 12"	8390/01/01/SS	Assumed	6	SF	0	SF	Tan			1	No	1/D		
1	1	Nurse's Office	T		Pipe Fitting Insulation	8390/01/01/06	Confirmed	5	EA	0	EA				1	No	1/D		
1	1	Nurse's Office	N/A		Fiberglass Pipe Insulation		Non Suspect ACM	15	LF	0	LF				N/A	N/A	N/A		
1	1	Nurse's Office	N/A		Ceiling Tile 1' x 1'		NAD	300	SF	0	SF				N/A	N/A	N/A		
1	1	Nurse's Office	M		Spline Ceiling Tile Glue Dots	8390/01/01/KEM/DP/2603	Assumed	30	SF	0	SF				1	No	1/D		
1	1	Nurse's Office	N/A		CMU		Non Suspect ACM	700	SF	0	SF				N/A	N/A	N/A		
1	1	Nurse's Office	M		Floor Tile VAT 12" x 12"	8390/01/01/SS	Assumed	300	SF	0	SF	Tan			1	No	1/D		
1	1	Nurse's Office Restroom	N/A		Concrete Ceiling		Non Suspect ACM	49	SF	0	SF				N/A	N/A	N/A		
1	1	Nurse's Office Restroom	N/A		CMU		Non Suspect ACM	210	SF	0	SF				N/A	N/A	N/A		
1	1	Nurse's Office Restroom	N/A		Sheetrock Wall		Non Suspect ACM	70	SF	0	SF				N/A	N/A	N/A		

# 8390 Aloysius Fitzpatrick ES 2015 2016 AHERA Three-Year Report.xls

		School District of Philadelphia		AHERA Three-Year Reinspection 2015-2016										Reinspection Date: 11/20/2015					
		Aloysius L. Fitzpatrick Elementary School		Room by Room Location Log Report										Building Inspector: Paul Davis					
		11061 Knights Road, Philadelphia, PA, 19154												Number: 050368					
		ULCS# 8390												Management Planner: Megan Vala					
		Year Built: 1960												Number: 740728					
E l e m e n t	F l o o r	On Site Room Name	System Affected	Material Description	HID#	Confirmed/Assumed/NAD/ Non Suspect ACM	Amount of Material	SF LF EA	Amount of Damage	SF LF EA	Color required for VAT	Comments/Description/Notes	Attic/ Crawl Space Ranking	Damage Potential (DP)	Newly Friable (NF)	Response Action (RA)			
1	1	Nurse's Office Restroom	M	Floor Tile VAT 12" x 12"	8390/01/01/SS	Assumed	49	SF	0	SF	Tan			1	No	1/D			
1	1	Nurses' Office Closet	N/A	Concrete Ceiling		Non Suspect ACM	28	SF	0	SF				N/A	N/A	N/A			
1	1	Nurses' Office Closet	N/A	CMU		Non Suspect ACM	220	SF	0	SF				N/A	N/A	N/A			
1	1	Nurses' Office Closet	M	Floor Tile VAT 9" x 9"	8390/01/01/19	Confirmed	26	SF	0	SF	Tan			1	No	1/D			
1	1	Nurses' Office Closet	M	Floor Tile VAT 9" x 9"	8390/01/01/19	Confirmed	2	SF	0	SF	Brown			1	No	1/D			
1	1	Counselor's Office in Main Office	T	Pipe Fitting Insulation	8390/01/01/06	Confirmed	4	EA	0	EA				1	No	1/D			
1	1	Counselor's Office in Main Office	N/A	Fiberglass Pipe Insulation		Non Suspect ACM	4	LF	0	LF				N/A	N/A	N/A			
1	1	Counselor's Office in Main Office	N/A	Ceiling Tile 1' x 1'		NAD	150	SF	0	SF				N/A	N/A	N/A			
1	1	Counselor's Office in Main Office	M	Spline Ceiling Tile Glue Dots	8390/01/01/KEM/PD/2603	Assumed	15	SF	0	SF				1	No	1/D			
1	1	Counselor's Office in Main Office	N/A	CMU		Non Suspect ACM	500	SF	0	SF				N/A	N/A	N/A			
1	1	Counselor's Office in Main Office	M	Floor Tile VAT 12" x 12"	8390/01/01/SS	Assumed	150	SF	0	SF	Tan			1	No	1/D			
1	1	Main Office	T	Pipe Fitting Insulation	8390/01/01/06	Confirmed	9	EA	0	EA				1	No	1/D			
1	1	Main Office	N/A	Fiberglass Pipe Insulation		Non Suspect ACM	30	LF	0	LF				N/A	N/A	N/A			
1	1	Main Office	N/A	Ceiling Tile 1' x 1'		NAD	972	SF	0	SF				N/A	N/A	N/A			
1	1	Main Office	M	Spline Ceiling Tile Glue Dots	8390/01/01/KEM/PD/2603	Assumed	97	SF	0	SF				1	No	1/D			
1	1	Main Office	N/A	CMU		Non Suspect ACM	1260	SF	0	SF				N/A	N/A	N/A			
1	1	Main Office	M	Floor Tile VAT 12" x 12"	8390/01/01/SS	Assumed	972	SF	0	SF	Tan			1	No	1/D			
1	1	Main Office Storage Room	N/A	Concrete Ceiling		Non Suspect ACM	42	SF	0	SF				N/A	N/A	N/A			
1	1	Main Office Storage Room	N/A	CMU		Non Suspect ACM	260	SF	0	SF				N/A	N/A	N/A			
1	1	Main Office Storage Room	M	Floor Tile VAT 12" x 12"	8390/01/01/SS	Assumed	42	SF	0	SF	Tan			1	No	1/D			
1	1	Vice Principal's Office in Main Office	N/A	Fiberglass Pipe Insulation		Non Suspect ACM	10	LF	0	LF				N/A	N/A	N/A			
1	1	Vice Principal's Office in Main Office	N/A	Concrete Ceiling		Non Suspect ACM	96	SF	0	SF				N/A	N/A	N/A			
1	1	Vice Principal's Office in Main Office	N/A	CMU		Non Suspect ACM	400	SF	0	SF				N/A	N/A	N/A			
1	1	Vice Principal's Office in Main Office	M	Floor Tile VAT 12" x 12"	8390/01/01/SS	Assumed	96	SF	0	SF	Tan			1	No	1/D			
1	1	Principal's Office	T	Pipe Fitting Insulation	8390/01/01/06	Confirmed	7	EA	0	EA				1	No	1/D			
1	1	Principal's Office	N/A	Fiberglass Pipe Insulation		Non Suspect ACM	19	LF	0	LF				N/A	N/A	N/A			
1	1	Principal's Office	N/A	Ceiling Tile 1' x 1'		NAD	221	SF	0	SF				N/A	N/A	N/A			
1	1	Principal's Office	M	Spline Ceiling Tile Glue Dots	8390/01/01/KEM/PD/2603	Assumed	22	SF	0	SF				1	No	1/D			
1	1	Principal's Office	N/A	CMU		Non Suspect ACM	600	SF	0	SF				N/A	N/A	N/A			
1	1	Principal's Office	M	Floor Tile VAT 12" x 12"	8390/01/01/SS	Assumed	221	SF	0	SF	Grey			1	No	1/D			
1	1	Principal's Office Closet/Storage	N/A	Concrete Ceiling		Non Suspect ACM	12	SF	0	SF				N/A	N/A	N/A			
1	1	Principal's Office Closet/Storage	N/A	CMU		Non Suspect ACM	160	SF	0	SF				N/A	N/A	N/A			
1	1	Principal's Office Closet/Storage	M	Floor Tile VAT 12" x 12"	8390/01/01/SS	Assumed	12	SF	0	SF	Grey			1	No	1/D			
1	1	Principal's Office Restroom	N/A	Concrete Ceiling		Non Suspect ACM	30	SF	0	SF				N/A	N/A	N/A			
1	1	Principal's Office Restroom	N/A	CMU		Non Suspect ACM	220	SF	0	SF				N/A	N/A	N/A			
1	1	Principal's Office Restroom	M	Floor Tile VAT 12" x 12"	8390/01/01/SS	Assumed	30	SF	0	SF	Grey			1	No	1/D			
1	1	Closet across from Main Office next to Classroom 101	T	Pipe Fitting Insulation	8390/01/01/06	Confirmed	6	EA	0	EA				1	No	1/D			
1	1	Closet across from Main Office next to Classroom 101	N/A	Fiberglass Pipe Insulation		Non Suspect ACM	20	LF	0	LF				N/A	N/A	N/A			
1	1	Closet across from Main Office next to Classroom 101	N/A	Concrete Ceiling		Non Suspect ACM	20	SF	0	SF				N/A	N/A	N/A			
1	1	Closet across from Main Office next to Classroom 101	N/A	CMU		Non Suspect ACM	180	SF	0	SF				N/A	N/A	N/A			
1	1	Closet across from Main Office next to Classroom 101	N/A	Cement Floor		Non Suspect ACM	20	SF	0	SF				N/A	N/A	N/A			
1	1	Girl's Restroom across from Main Office	T	Pipe Fitting Insulation	8390/01/01/06	Confirmed	13	EA	0	EA				1	No	1/D			
1	1	Girl's Restroom across from Main Office	N/A	Fiberglass Pipe Insulation		Non Suspect ACM	50	LF	0	LF				N/A	N/A	N/A			
1	1	Girl's Restroom across from Main Office	N/A	Concrete Ceiling		Non Suspect ACM	378	SF	0	SF				N/A	N/A	N/A			
1	1	Girl's Restroom across from Main Office	N/A	CMU		Non Suspect ACM	820	SF	0	SF				N/A	N/A	N/A			
1	1	Girl's Restroom across from Main Office	N/A	Cement Floor		Non Suspect ACM	378	SF	0	SF				N/A	N/A	N/A			
1	1	Pipe Chace for Girl's Restroom on First Floor	X	X		X	X	X	X	X	No Access (S2017)			X	X	X			
1	1	Storage and Mechanical Room in Hall for Auditorium	N/A	Concrete Ceiling		Non Suspect ACM	120	SF	0	SF				N/A	N/A	N/A			
1	1	Storage and Mechanical Room in Hall for Auditorium	N/A	CMU		Non Suspect ACM	440	SF	0	SF				N/A	N/A	N/A			
1	1	Storage and Mechanical Room in Hall for Auditorium	N/A	Cement Floor		Non Suspect ACM	120	SF	0	SF				N/A	N/A	N/A			
1	1	Men's Restroom across from Principal's Office	N/A	Concrete Ceiling		Non Suspect ACM	63	SF	0	SF				N/A	N/A	N/A			
1	1	Men's Restroom across from Principal's Office	N/A	CMU		Non Suspect ACM	320	SF	0	SF				N/A	N/A	N/A			
1	1	Men's Restroom across from Principal's Office	N/A	Cement Floor		Non Suspect ACM	63	SF	0	SF				N/A	N/A	N/A			
1	1	Storage Room adjacent to Main Entrance Lobby	T	Pipe Fitting Insulation	8390/01/01/06	Confirmed	7	EA	0	EA				1	No	1/D			
1	1	Storage Room adjacent to Main Entrance Lobby	N/A	Fiberglass Pipe Insulation		Non Suspect ACM	25	LF	0	LF				N/A	N/A	N/A			
1	1	Storage Room adjacent to Main Entrance Lobby	N/A	Concrete Ceiling		Non Suspect ACM	304	SF	0	SF				N/A	N/A	N/A			
1	1	Storage Room adjacent to Main Entrance Lobby	N/A	CMU		Non Suspect ACM	540	SF	0	SF				N/A	N/A	N/A			
1	1	Storage Room adjacent to Main Entrance Lobby	N/A	Cement Floor		Non Suspect ACM	304	SF	0	SF				N/A	N/A	N/A			
1	1	Main Entrance Lobby	N/A	Concrete Ceiling		Non Suspect ACM	352	SF	0	SF				N/A	N/A	N/A			
1	1	Main Entrance Lobby	N/A	Brick Wall		Non Suspect ACM	648	SF	0	SF				N/A	N/A	N/A			
1	1	Main Entrance Lobby	M	Floor Tile VAT 9" x 9"	8390/01/01/19	Confirmed	176	SF	0	SF	Tan			1	No	1/D			
1	1	Main Entrance Lobby	N/A	Cement Floor		Non Suspect ACM	176	SF	0	SF				N/A	N/A	N/A			
1	1	Classroom 100	T	Pipe Fitting Insulation	8390/01/01/06	Confirmed	6	EA	0	EA				1	No	1/D			
1	1	Classroom 100	N/A	Fiberglass Pipe Insulation		Non Suspect ACM	21	LF	0	LF				N/A	N/A	N/A			
1	1	Classroom 100	N/A	Concrete Ceiling		Non Suspect ACM	972	SF	0	SF				N/A	N/A	N/A			
1	1	Classroom 100	N/A	CMU		Non Suspect ACM	990	SF	0	SF				N/A	N/A	N/A			
1	1	Classroom 100	N/A	Partition Room Dividers		Non Suspect ACM	270	SF	0	SF		Wood Divider.		N/A	N/A	N/A			
1	1	Classroom 100	M	Transite Closet	8390/01/01/15	Confirmed	54	SF	0	SF				1	No	1/D			
1	1	Classroom 100	M	Floor Tile VAT 9" x 9"	8390/01/01/19	Confirmed	919	SF	0	SF	Grey			1	No	1/D			
1	1	Classroom 100	M	Floor Tile VAT 9" x 9"	8390/01/01/19	Confirmed	48	SF	0	SF	Green			1	No	1/D			
1	1	Classroom 100	M	Floor Tile VAT 12" x 12"	8390/01/01/SS	Assumed	5	SF	0	SF	Tan			1	No	1/D			
1	1	Classroom 102	T	Pipe Fitting Insulation	8390/01/01/06	Confirmed	9	EA	0	EA				1	No	1/D			

# 8390 Aloysius Fitzpatrick ES 2015 2016 AHERA Three-Year Report.xls

School District of Philadelphia Aloysius L. Fitzpatrick Elementary School 11061 Knights Road, Philadelphia, PA, 19154 ULCS# 8390 Year Built: 1960			AHERA Three-Year Reinspection 2015-2016 Room by Room Location Log Report										Reinspection Date: 11/20/2015 Building Inspector: Paul Davis Number: 050368 Management Planner: Megan Vala Number: 740728					
E l e m e n t	F l o o r	On Site Room Name	System Affected	Material Description	HID#	Confirmed/Assumed/NAD/ Non Suspect ACM	Amount of Material	SF LF EA	Amount of Damage	SF LF EA	Color required for VAT	Comments/Description/Notes	Attic/ Crawl Space Ranking	Damage Potential (DP)	Newly Friable (NF)	Response Action (RA)		
1	1	Classroom 102	N/A	Fiberglass Pipe Insulation		Non Suspect ACM	22	LF	0	LF				N/A	N/A	N/A		
1	1	Classroom 102	N/A	Concrete Ceiling		Non Suspect ACM	972	SF	0	SF				N/A	N/A	N/A		
1	1	Classroom 102	N/A	CMU		Non Suspect ACM	990	SF	0	SF				N/A	N/A	N/A		
1	1	Classroom 102	N/A	Partition Room Dividers		Non Suspect ACM	270	SF	0	SF		Wood Divider.		N/A	N/A	N/A		
1	1	Classroom 102	M	Transite Closet	8390/01/01/15	Confirmed	54	SF	1	SF		Less than 1 SF; Chipped.		1	Yes	5/C		
1	1	Classroom 102	M	Floor Tile VAT 9" x 9"	8390/01/01/19	Confirmed	918	SF	0	SF	Grey			1	No	1/D		
1	1	Classroom 102	M	Floor Tile VAT 9" x 9"	8390/01/01/19	Confirmed	48	SF	0	SF	Green			1	No	1/D		
1	1	Classroom 102	M	Floor Tile VAT 12" x 12"	8390/01/01/SS	Assumed	6	SF	0	SF	Tan			1	No	1/D		
1	1	Classroom 104	T	Pipe Fitting Insulation	8390/01/01/06	Confirmed	7	EA	2	EA		(2) PFI Duct Taped.		1	Yes	5/A		
1	1	Classroom 104	N/A	Fiberglass Pipe Insulation		Non Suspect ACM	25	LF	0	LF				N/A	N/A	N/A		
1	1	Classroom 104	N/A	Concrete Ceiling		Non Suspect ACM	972	SF	0	SF				N/A	N/A	N/A		
1	1	Classroom 104	N/A	CMU		Non Suspect ACM	1260	SF	0	SF				N/A	N/A	N/A		
1	1	Classroom 104	M	Transite Closet	8390/01/01/15	Confirmed	54	SF	0	SF				1	No	1/D		
1	1	Classroom 104	M	Floor Tile VAT 9" x 9"	8390/01/01/19	Confirmed	883	SF	0	SF	Grey			1	No	1/D		
1	1	Classroom 104	M	Floor Tile VAT 9" x 9"	8390/01/01/19	Confirmed	47	SF	0	SF	Green			1	No	1/D		
1	1	Classroom 104	M	Floor Tile VAT 12" x 12"	8390/01/01/SS	Assumed	6	SF	0	SF	Tan			1	No	1/D		
1	1	Classroom 104	M	Floor Tile VAT 12" x 12"	8390/01/01/SS	Assumed	36	SF	0	SF	Grey			1	No	1/D		
1	1	Classroom 104 Storage	T	Pipe Fitting Insulation	8390/01/01/06	Confirmed	21	EA	0	EA		No Access (S2017)		1	No	1/D		
1	1	Classroom 104 Storage	N/A	Fiberglass Pipe Insulation		Non Suspect ACM	50	LF	0	LF		No Access (S2017)		N/A	N/A	N/A		
1	1	Classroom 104 Storage	N/A	Concrete Ceiling		Non Suspect ACM	112	SF	0	SF		No Access (S2017)		N/A	N/A	N/A		
1	1	Classroom 104 Storage	N/A	CMU		Non Suspect ACM	460	SF	0	SF		No Access (S2017)		N/A	N/A	N/A		
1	1	Classroom 104 Storage	M	Floor Tile VAT 9" x 9"	8390/01/01/19	Confirmed	112	SF	0	SF	Grey	No Access (S2017)		1	No	1/D		
1	1	Storage in Right Side of Auditorium Hall (Chimney extends through it)	T	Pipe Fitting Insulation	8390/01/01/06	Confirmed	10	EA	0	EA		No Access (S2017)		1	No	1/D		
1	1	Storage in Right Side of Auditorium Hall (Chimney extends through it)	N/A	Fiberglass Pipe Insulation		Non Suspect ACM	40	LF	0	LF		No Access (S2017)		N/A	N/A	N/A		
1	1	Storage in Right Side of Auditorium Hall (Chimney extends through it)	N/A	Concrete Ceiling		Non Suspect ACM	276	SF	0	SF		No Access (S2017)		N/A	N/A	N/A		
1	1	Storage in Right Side of Auditorium Hall (Chimney extends through it)	N/A	CMU		Non Suspect ACM	580	SF	0	SF		No Access (S2017)		N/A	N/A	N/A		
1	1	Storage in Right Side of Auditorium Hall (Chimney extends through it)	N/A	Cement Floor		Non Suspect ACM	276	SF	0	SF		No Access (S2017)		N/A	N/A	N/A		
1	1	Psychologist's Office 119	T	Pipe Fitting Insulation	8390/01/01/06	Confirmed	18	EA	3	EA		(3) PFI Duct Taped.		1	Yes	5/A		
1	1	Psychologist's Office 119	N/A	Fiberglass Pipe Insulation		Non Suspect ACM	30	LF	0	LF				N/A	N/A	N/A		
1	1	Psychologist's Office 119	N/A	Concrete Ceiling		Non Suspect ACM	140	SF	0	SF				N/A	N/A	N/A		
1	1	Psychologist's Office 119	N/A	CMU		Non Suspect ACM	480	SF	0	SF				N/A	N/A	N/A		
1	1	Psychologist's Office 119	M	Floor Tile VAT 9" x 9"	8390/01/01/19	Confirmed	140	SF	0	SF	Green			1	No	1/D		
1	1	Women's Restroom near Classroom 106	T	Pipe Fitting Insulation	8390/01/01/06	Confirmed	7	EA	0	EA				1	No	1/D		
1	1	Women's Restroom near Classroom 106	N/A	Fiberglass Pipe Insulation		Non Suspect ACM	25	LF	0	LF				N/A	N/A	N/A		
1	1	Women's Restroom near Classroom 106	N/A	Concrete Ceiling		Non Suspect ACM	99	SF	0	SF				N/A	N/A	N/A		
1	1	Women's Restroom near Classroom 106	N/A	CMU		Non Suspect ACM	400	SF	0	SF				N/A	N/A	N/A		
1	1	Women's Restroom near Classroom 106	N/A	Cement Floor		Non Suspect ACM	99	SF	0	SF				N/A	N/A	N/A		
1	1	Classroom 106	T	Pipe Fitting Insulation	8390/01/01/06	Confirmed	9	EA	0	EA				1	No	1/D		
1	1	Classroom 106	N/A	Fiberglass Pipe Insulation		Non Suspect ACM	36	LF	0	LF				N/A	N/A	N/A		
1	1	Classroom 106	N/A	Concrete Ceiling		Non Suspect ACM	972	SF	0	SF				N/A	N/A	N/A		
1	1	Classroom 106	N/A	CMU		Non Suspect ACM	1260	SF	0	SF				N/A	N/A	N/A		
1	1	Classroom 106	M	Transite Closet	8390/01/01/15	Confirmed	54	SF	1	SF		Less than 1 SF; Chipped.		1	Yes	5/C		
1	1	Classroom 106	M	Floor Tile VAT 9" x 9"	8390/01/01/19	Confirmed	919	SF	0	SF	Grey			1	No	1/D		
1	1	Classroom 106	M	Floor Tile VAT 9" x 9"	8390/01/01/19	Confirmed	48	SF	0	SF	Green			1	No	1/D		
1	1	Classroom 106	M	Floor Tile VAT 12" x 12"	8390/01/01/SS	Assumed	5	SF	0	SF	Tan			1	No	1/D		
1	1	Boy's Restroom across from Classroom 106	T	Pipe Fitting Insulation	8390/01/01/06	Confirmed	22	EA	0	EA				1	No	1/D		
1	1	Boy's Restroom across from Classroom 106	N/A	Fiberglass Pipe Insulation		Non Suspect ACM	25	LF	0	LF				N/A	N/A	N/A		
1	1	Boy's Restroom across from Classroom 106	N/A	Concrete Ceiling		Non Suspect ACM	297	SF	0	SF				N/A	N/A	N/A		
1	1	Boy's Restroom across from Classroom 106	N/A	CMU		Non Suspect ACM	760	SF	0	SF				N/A	N/A	N/A		
1	1	Boy's Restroom across from Classroom 106	N/A	Cement Floor		Non Suspect ACM	297	SF	0	SF				N/A	N/A	N/A		
1	1	Custodial Closet near Classroom 106	N/A	Concrete Ceiling		Non Suspect ACM	24	SF	0	SF				N/A	N/A	N/A		
1	1	Custodial Closet near Classroom 106	N/A	CMU		Non Suspect ACM	200	SF	0	SF				N/A	N/A	N/A		
1	1	Custodial Closet near Classroom 106	N/A	Cement Floor		Non Suspect ACM	24	SF	0	SF				N/A	N/A	N/A		
1	1	Pipe Chase in Custodial Closet near Classroom 106	T	Pipe Fitting Insulation	8390/01/01/06	Confirmed	30	EA	0	EA				1	No	1/D		
1	1	Pipe Chase in Custodial Closet near Classroom 106	N/A	Fiberglass Pipe Insulation		Non Suspect ACM	100	LF	0	LF				N/A	N/A	N/A		
1	1	Pipe Chase in Custodial Closet near Classroom 106	N/A	Concrete Ceiling		Non Suspect ACM	60	SF	0	SF				N/A	N/A	N/A		
1	1	Pipe Chase in Custodial Closet near Classroom 106	N/A	CMU		Non Suspect ACM	460	SF	0	SF				N/A	N/A	N/A		
1	1	Pipe Chase in Custodial Closet near Classroom 106	N/A	Cement Floor		Non Suspect ACM	60	SF	0	SF				N/A	N/A	N/A		
1	1	Stairwell near Classrooms 106 and 108	T	Pipe Fitting Insulation	8390/01/01/06	Confirmed	3	EA	0	EA				1	No	1/D		
1	1	Stairwell near Classrooms 106 and 108	N/A	Fiberglass Pipe Insulation		Non Suspect ACM	2	LF	0	LF				N/A	N/A	N/A		
1	1	Stairwell near Classrooms 106 and 108	N/A	Concrete Ceiling		Non Suspect ACM	90	SF	0	SF				N/A	N/A	N/A		
1	1	Stairwell near Classrooms 106 and 108	N/A	CMU		Non Suspect ACM	1110	SF	0	SF				N/A	N/A	N/A		
1	1	Stairwell near Classrooms 106 and 108	N/A	Cement Floor		Non Suspect ACM	180	SF	0	SF				N/A	N/A	N/A		
1	1	Classroom 108	T	Pipe Fitting Insulation	8390/01/01/06	Confirmed	6	EA	0	EA				1	No	1/D		
1	1	Classroom 108	N/A	Fiberglass Pipe Insulation		Non Suspect ACM	40	LF	0	LF				N/A	N/A	N/A		
1	1	Classroom 108	N/A	Concrete Ceiling		Non Suspect ACM	972	SF	0	SF				N/A	N/A	N/A		
1	1	Classroom 108	N/A	CMU		Non Suspect ACM	1260	SF	0	SF				N/A	N/A	N/A		



# 8390 Aloysius Fitzpatrick ES 2015 2016 AHERA Three-Year Report.xls

		School District of Philadelphia		AHERA Three-Year Reinspection 2015-2016										Reinspection Date: 11/20/2015						
		Aloysius L. Fitzpatrick Elementary School		Room by Room Location Log Report										Building Inspector: Paul Davis						
		11061 Knights Road, Philadelphia, PA, 19154												Number: 050368						
		ULCS# 8390												Management Planner: Megan Vala						
		Year Built: 1960												Number: 740728						
E l e m e n t	F l o o r																			
		On Site Room Name	System Affected	Material Description	HID#	Confirmed/Assumed/NAD/Non Suspect ACM	Amount of Material	SF	LF	EA	Amount of Damage	SF	LF	EA	Color required for VAT	Comments/Description/Notes	Attic/Crawl Space Ranking	Damage Potential (DP)	Newly Friable (NF)	Response Action (RA)
1	1	Classroom 108	M	Transite Closet	8390/01/01/15	Confirmed	54	SF	0	SF							1	No	1/D	
1	1	Classroom 108	M	Floor Tile VAT 9" x 9"	8390/01/01/19	Confirmed	895	SF	0	SF	Grey						1	No	1/D	
1	1	Classroom 108	M	Floor Tile VAT 9" x 9"	8390/01/01/19	Confirmed	47	SF	0	SF	Green						1	No	1/D	
1	1	Classroom 108	M	Floor Tile VAT 12" x 12"	8390/01/01/SS	Assumed	25	SF	0	SF	White						1	No	1/D	
1	1	Classroom 108	M	Floor Tile VAT 12" x 12"	8390/01/01/SS	Assumed	5	SF	0	SF	Tan						1	No	1/D	
1	1	Classroom 103	T	Pipe Fitting Insulation	8390/01/01/06	Confirmed	15	EA	0	EA							1	No	1/D	
1	1	Classroom 103	N/A	Fiberglass Pipe Insulation		Non Suspect ACM	40	LF	0	LF							N/A	N/A	N/A	
1	1	Classroom 103	N/A	Concrete Ceiling		Non Suspect ACM	972	SF	0	SF							N/A	N/A	N/A	
1	1	Classroom 103	N/A	CMU		Non Suspect ACM	1260	SF	0	SF							N/A	N/A	N/A	
1	1	Classroom 103	M	Transite Closet	8390/01/01/15	Confirmed	54	SF	1	SF				Less than 1 SF; Cracked.			1	Yes	5/C	
1	1	Classroom 103	M	Floor Tile VAT 9" x 9"	8390/01/01/19	Confirmed	903	SF	0	SF	Tan						1	No	1/D	
1	1	Classroom 103	M	Floor Tile VAT 9" x 9"	8390/01/01/19	Confirmed	48	SF	0	SF	Brown						1	No	1/D	
1	1	Classroom 103	M	Floor Tile VAT 12" x 12"	8390/01/01/SS	Assumed	16	SF	0	SF	Brown						1	No	1/D	
1	1	Classroom 103	M	Floor Tile VAT 12" x 12"	8390/01/01/SS	Assumed	5	SF	0	SF	Tan						1	No	1/D	
1	1	Classroom 110	T	Pipe Fitting Insulation	8390/01/01/06	Confirmed	9	EA	0	EA							1	No	1/D	
1	1	Classroom 110	N/A	Fiberglass Pipe Insulation		Non Suspect ACM	30	LF	0	LF							N/A	N/A	N/A	
1	1	Classroom 110	N/A	Concrete Ceiling		Non Suspect ACM	972	SF	0	SF							N/A	N/A	N/A	
1	1	Classroom 110	N/A	CMU		Non Suspect ACM	1260	SF	0	SF							N/A	N/A	N/A	
1	1	Classroom 110	M	Transite Closet	8390/01/01/15	Confirmed	54	SF	1	SF				Less than 1 SF; Chipped.			1	Yes	5/C	
1	1	Classroom 110	M	Floor Tile VAT 9" x 9"	8390/01/01/19	Confirmed	918	SF	0	SF	Grey						1	No	1/D	
1	1	Classroom 110	M	Floor Tile VAT 9" x 9"	8390/01/01/19	Confirmed	48	SF	0	SF	Green						1	No	1/D	
1	1	Classroom 110	M	Floor Tile VAT 12" x 12"	8390/01/01/SS	Assumed	6	SF	0	SF	Tan						1	No	1/D	
1	1	Classroom 105	T	Pipe Fitting Insulation	8390/01/01/06	Confirmed	7	EA	0	EA							1	No	1/D	
1	1	Classroom 105	N/A	Fiberglass Pipe Insulation		Non Suspect ACM	21	LF	0	LF							N/A	N/A	N/A	
1	1	Classroom 105	N/A	Concrete Ceiling		Non Suspect ACM	972	SF	0	SF							N/A	N/A	N/A	
1	1	Classroom 105	N/A	CMU		Non Suspect ACM	1260	SF	0	SF							N/A	N/A	N/A	
1	1	Classroom 105	M	Transite Closet	8390/01/01/15	Confirmed	54	SF	0	SF							1	No	1/D	
1	1	Classroom 105	M	Floor Tile VAT 9" x 9"	8390/01/01/19	Confirmed	898	SF	0	SF	Tan						1	No	1/D	
1	1	Classroom 105	M	Floor Tile VAT 9" x 9"	8390/01/01/19	Confirmed	47	SF	0	SF	Brown						1	No	1/D	
1	1	Classroom 105	M	Floor Tile VAT 12" x 12"	8390/01/01/SS	Assumed	27	SF	0	SF	Tan						1	No	1/D	
1	1	Classroom 112	T	Pipe Fitting Insulation	8390/01/01/06	Confirmed	12	EA	0	EA							1	No	1/D	
1	1	Classroom 112	N/A	Fiberglass Pipe Insulation		Non Suspect ACM	50	LF	0	LF							N/A	N/A	N/A	
1	1	Classroom 112	N/A	Concrete Ceiling		Non Suspect ACM	972	SF	0	SF							N/A	N/A	N/A	
1	1	Classroom 112	N/A	CMU		Non Suspect ACM	1260	SF	0	SF							N/A	N/A	N/A	
1	1	Classroom 112	M	Transite Closet	8390/01/01/15	Confirmed	54	SF	0	SF							1	No	1/D	
1	1	Classroom 112	M	Floor Tile VAT 9" x 9"	8390/01/01/19	Confirmed	919	SF	0	SF	Grey						1	No	1/D	
1	1	Classroom 112	M	Floor Tile VAT 9" x 9"	8390/01/01/19	Confirmed	48	SF	0	SF	Green						1	No	1/D	
1	1	Classroom 112	M	Floor Tile VAT 12" x 12"	8390/01/01/SS	Assumed	5	SF	0	SF	Tan						1	No	1/D	
1	1	Classroom 107	T	Pipe Fitting Insulation	8390/01/01/06	Confirmed	20	EA	0	EA							1	No	1/D	
1	1	Classroom 107	N/A	Fiberglass Pipe Insulation		Non Suspect ACM	50	LF	0	LF							N/A	N/A	N/A	
1	1	Classroom 107	N/A	Concrete Ceiling		Non Suspect ACM	576	SF	0	SF							N/A	N/A	N/A	
1	1	Classroom 107	N/A	CMU		Non Suspect ACM	960	SF	0	SF							N/A	N/A	N/A	
1	1	Classroom 107	M	Floor Tile VAT 9" x 9"	8390/01/01/19	Confirmed	523	SF	0	SF	Tan						1	No	1/D	
1	1	Classroom 107	M	Floor Tile VAT 9" x 9"	8390/01/01/19	Confirmed	28	SF	0	SF	Brown						1	No	1/D	
1	1	Classroom 107	M	Floor Tile VAT 9" x 9"	8390/01/01/19	Confirmed	20	SF	0	SF	Green						1	No	1/D	
1	1	Classroom 107	M	Floor Tile VAT 12" x 12"	8390/01/01/SS	Assumed	5	SF	0	SF	Tan						1	No	1/D	
1	1	Stairwell near Classrooms 107 and 112	T	Pipe Fitting Insulation	8390/01/01/06	Confirmed	1	EA	0	EA							1	No	1/D	
1	1	Stairwell near Classrooms 107 and 112	N/A	Fiberglass Pipe Insulation		Non Suspect ACM	2	LF	0	LF							N/A	N/A	N/A	
1	1	Stairwell near Classrooms 107 and 112	N/A	Concrete Ceiling		Non Suspect ACM	90	SF	0	SF							N/A	N/A	N/A	
1	1	Stairwell near Classrooms 107 and 112	N/A	CMU		Non Suspect ACM	1110	SF	0	SF							N/A	N/A	N/A	
1	1	Stairwell near Classrooms 107 and 112	N/A	Cement Floor		Non Suspect ACM	180	SF	0	SF							N/A	N/A	N/A	
1	1	Hallway from Classroom 104 to Classroom 112	T	Pipe Fitting Insulation	8390/01/01/06	Confirmed	18	EA	0	EA							1	No	1/D	
1	1	Hallway from Classroom 104 to Classroom 112	N/A	Fiberglass Pipe Insulation		Non Suspect ACM	30	LF	0	LF							N/A	N/A	N/A	
1	1	Hallway from Classroom 104 to Classroom 112	N/A	Concrete Ceiling		Non Suspect ACM	1665	SF	0	SF							N/A	N/A	N/A	
1	1	Hallway from Classroom 104 to Classroom 112	N/A	CMU		Non Suspect ACM	3790	SF	0	SF							N/A	N/A	N/A	
1	1	Hallway from Classroom 104 to Classroom 112	M	Floor Tile VAT 9" x 9"	8390/01/01/19	Confirmed	1905	SF	0	SF	Tan						1	No	1/D	
1	1	Hallway from Classroom 104 to Classroom 112	M	Floor Tile VAT 12" x 12"	8390/01/01/SS	Assumed	120	SF	0	SF	Tan						1	No	1/D	
1	1	Hallway from Principal's Office to Classroom 104	N/A	Concrete Ceiling		Non Suspect ACM	864	SF	0	SF							N/A	N/A	N/A	
1	1	Hallway from Principal's Office to Classroom 104	N/A	CMU		Non Suspect ACM	1140	SF	0	SF							N/A	N/A	N/A	
1	1	Hallway from Principal's Office to Classroom 104	M	Floor Tile VAT 9" x 9"	8390/01/01/19	Confirmed	864	SF	0	SF	Tan						1	No	1/D	
1	1	Hallway from Principal's Office to Classroom 104	M	Floor Tile VAT 12" x 12"	8390/01/01/SS	Assumed	48	SF	0	SF	Tan						1	No	1/D	
1	1	Hallway from Classroom 109 to Principal's Office	T	Pipe Fitting Insulation	8390/01/01/06	Confirmed	9	EA	0	EA							1	No	1/D	
1	1	Hallway from Classroom 109 to Principal's Office	N/A	Fiberglass Pipe Insulation		Non Suspect ACM	11	LF	0	LF							N/A	N/A	N/A	
1	1	Hallway from Classroom 109 to Principal's Office	N/A	Concrete Ceiling		Non Suspect ACM	819	SF	0	SF							N/A	N/A	N/A	
1	1	Hallway from Classroom 109 to Principal's Office	N/A	CMU		Non Suspect ACM	1910	SF	0	SF							N/A	N/A	N/A	
1	1	Hallway from Classroom 109 to Principal's Office	M	Floor Tile VAT 9" x 9"	8390/01/01/19	Confirmed	819	SF	0	SF	Tan						1	No	1/D	
1	1	Hallway from Classroom 109 to Principal's Office	M	Floor Tile VAT 12" x 12"	8390/01/01/SS	Assumed	15	SF	0	SF	Tan						1	No	1/D	
1	1	Classroom 102 Closet	T	Pipe Fitting Insulation	8390/01/01/06	Confirmed	8	EA	0	EA							1	No	1/D	
1	1	Classroom 102 Closet	N/A	Fiberglass Pipe Insulation		Non Suspect ACM	20	LF	0	LF							N/A	N/A	N/A	
1	1	Classroom 102 Closet	N/A	Concrete Ceiling		Non Suspect ACM	108	SF	0	SF							N/A	N/A	N/A	
1	1	Classroom 102 Closet	N/A	CMU		Non Suspect ACM	300	SF	0	SF							N/A	N/A	N/A	
1	1	Classroom 102 Closet	M	Floor Tile VAT 9" x 9"	8390/01/01/19	Confirmed	102	SF	0	SF	Grev						1	Nq	1/D	

# 8390 Aloysius Fitzpatrick ES 2015 2016 AHERA Three-Year Report.xls

School District of Philadelphia Aloysius L. Fitzpatrick Elementary School 11061 Knights Road, Philadelphia, PA, 19154 ULCS# 8390 Year Built: 1960			AHERA Three-Year Reinspection 2015-2016 Room by Room Location Log Report										Reinspection Date: 11/20/2015 Building Inspector: Paul Davis Number: 050368 Management Planner: Megan Vala Number: 740728							
E l e m e n t	F l o o r																Attic/ Crawl Space Ranking	Damage Potential (DP)	Newly Friable (NF)	Response Action (RA)
		On Site Room Name	System Affected	Material Description	HID#	Confirmed/Assumed/NAD/ Non Suspect ACM	Amount of Material	SF LF EA	Amount of Damage	SF LF EA	Color required for VAT	Comments/Description/Notes								
1	1	Classroom 102 Closet	M	Floor Tile VAT 9" x 9"	8390/01/01/19	Confirmed	6	SF	0	EA	Green				1	No	1/D			
1	1	Hallway along left side of Auditorium from across Main Office to Stage	T	Pipe Fitting Insulation	8390/01/01/06	Confirmed	9	EA	0	EA					1	No	1/D			
1	1	Hallway along left side of Auditorium from across Main Office to Stage	N/A	Fiberglass Pipe Insulation		Non Suspect ACM	20	LF	0	LF					N/A	N/A	N/A			
1	1	Hallway along left side of Auditorium from across Main Office to Stage	N/A	Concrete Ceiling		Non Suspect ACM	348	SF	0	SF					N/A	N/A	N/A			
1	1	Hallway along left side of Auditorium from across Main Office to Stage	N/A	CMU		Non Suspect ACM	1220	SF	0	SF					N/A	N/A	N/A			
1	1	Hallway along left side of Auditorium from across Main Office to Stage	M	Floor Tile VAT 9" x 9"	8390/01/01/19	Confirmed	150	SF	0	SF	Tan				1	No	1/D			
1	1	Hallway along left side of Auditorium from across Main Office to Stage	N/A	Cement Floor		Non Suspect ACM	198	SF	0	SF					N/A	N/A	N/A			
1	1	Stairwell from Hallway along left side of Auditorium near Stage to the Outdoors	N/A	Concrete Ceiling		Non Suspect ACM	189	SF	0	SF					N/A	N/A	N/A			
1	1	Stairwell from Hallway along left side of Auditorium near Stage to the Outdoors	N/A	CMU		Non Suspect ACM	1360	SF	0	SF					N/A	N/A	N/A			
1	1	Stairwell from Hallway along left side of Auditorium near Stage to the Outdoors	N/A	Cement Floor		Non Suspect ACM	189	SF	0	SF					N/A	N/A	N/A			
1	1	Auditorium Stage	T	Pipe Fitting Insulation	8390/01/01/06	Confirmed	28	EA	1	EA		Previous DDC for Stage Area was Repaired. This Damage is for a gouge on another Fiting on Left Side of Stage.			1	Yes	5/A			
1	1	Auditorium Stage	N/A	Fiberglass Pipe Insulation		Non Suspect ACM	60	LF	0	LF		Add 115 on the Map.			N/A	N/A	N/A			
1	1	Auditorium Stage	N/A	Concrete Ceiling		Non Suspect ACM	1040	SF	0	SF		Add 115 on the Map.			N/A	N/A	N/A			
1	1	Auditorium Stage	N/A	CMU		Non Suspect ACM	1288	SF	0	SF		Add 115 on the Map.			N/A	N/A	N/A			
1	1	Auditorium Stage	M	Floor Tile VAT 9" x 9"	8390/01/01/19	Confirmed	1040	SF	0	SF	Brown	Add 115 on the Map.			1	No	1/D			
1	1	Auditorium Stage	M	Vibration Damper Cloth	8390/01/01/JJ	Assumed	70	SF	0	SF		Add 115 on the Map.			1	No	1/D			
1	1	Auditorium	N/A	Ceiling Tile 1' x 1'		NAD	100	SF	20	SF		Sampled NAD October, 1993			N/A	N/A	N/A			
1	1	Auditorium	N/A	Ceiling Tile 2' x 2'		NAD	4450	SF	0	SF		Confirmed with OEMS.			N/A	N/A	N/A			
1	1	Auditorium	N/A	Wall Tile 1' x 1'		NAD	308	SF	0	SF		Same as Ceiling Tiles.			N/A	N/A	N/A			
1	1	Auditorium	M	Spline Ceiling/Wall Tile Glue Dots	8390/01/01/KEM/PD/2610	Assumed	486	SF	0	SF					1	No	1/D			
1	1	Auditorium	N/A	CMU		Non Suspect ACM	2870	SF	0	SF					N/A	N/A	N/A			
1	1	Auditorium	M	Floor Tile VAT 9" x 9"	8390/01/01/19	Confirmed	4305	SF	0	SF	Tan				1	No	1/D			
1	1	Auditorium	M	Floor Tile VAT 9" x 9"	8390/01/01/19	Confirmed	4305	SF	0	SF	Brown				1	No	1/D			
1	1	Auditorium	M	Floor Tile VAT 12" x 12"	8390/01/01/SS	Assumed	18	SF	0	SF	Tan				1	No	1/D			
1	1	Hallway along right side of Auditorium from across Classroom 104 to Stage	T	Pipe Fitting Insulation	8390/01/01/06	Confirmed	1	EA	0	EA					1	No	1/D			
1	1	Hallway along right side of Auditorium from across Classroom 104 to Stage	N/A	Fiberglass Pipe Insulation		Non Suspect ACM	2	LF	0	LF					N/A	N/A	N/A			
1	1	Hallway along right side of Auditorium from across Classroom 104 to Stage	N/A	Concrete Ceiling		Non Suspect ACM	235	SF	0	SF					N/A	N/A	N/A			
1	1	Hallway along right side of Auditorium from across Classroom 104 to Stage	N/A	CMU		Non Suspect ACM	990	SF	0	SF					N/A	N/A	N/A			
1	1	Hallway along right side of Auditorium from across Classroom 104 to Stage	M	Floor Tile VAT 9" x 9"	8390/01/01/19	Confirmed	125	SF	0	SF	Tan				1	No	1/D			
1	1	Hallway along right side of Auditorium from across Classroom 104 to Stage	N/A	Cement Floor		Non Suspect ACM	110	SF	0	SF					N/A	N/A	N/A			
1	2	Stairwell near Classroom 200	N/A	Fiberglass Pipe Insulation		Non Suspect ACM	1	LF	0	LF					N/A	N/A	N/A			
1	2	Stairwell near Classroom 200	N/A	Concrete Ceiling		Non Suspect ACM	90	SF	0	SF					N/A	N/A	N/A			
1	2	Stairwell near Classroom 200	N/A	CMU		Non Suspect ACM	1110	SF	0	SF					N/A	N/A	N/A			
1	2	Stairwell near Classroom 200	N/A	Cement Floor		Non Suspect ACM	180	SF	0	SF					N/A	N/A	N/A			
1	2	Classroom 200	T	Pipe Fitting Insulation	8390/01/02/08	Confirmed	8	EA	0	EA					1	No	1/D			
1	2	Classroom 200	N/A	Fiberglass Pipe Insulation		Non Suspect ACM	38	LF	0	LF					N/A	N/A	N/A			
1	2	Classroom 200	N/A	Concrete Ceiling		Non Suspect ACM	972	SF	0	SF					N/A	N/A	N/A			
1	2	Classroom 200	N/A	CMU		Non Suspect ACM	1260	SF	0	SF					N/A	N/A	N/A			
1	2	Classroom 200	M	Transite Closet	8390/01/02/16	Assumed	54	SF	0	SF					1	No	1/D			
1	2	Classroom 200	M	Floor Tile VAT 9" x 9"	8390/01/02/20	Confirmed	923	SF	0	SF	Grey				1	No	1/D			
1	2	Classroom 200	M	Floor Tile VAT 9" x 9"	8390/01/02/20	Confirmed	49	SF	0	SF	Green				1	No	1/D			
1	2	Book Closet across from Classroom 200	T	Pipe Fitting Insulation	8390/01/02/08	Confirmed	12	EA	0	EA					1	No	1/D			
1	2	Book Closet across from Classroom 200	N/A	Fiberglass Pipe Insulation		Non Suspect ACM	32	LF	0	LF					N/A	N/A	N/A			
1	2	Book Closet across from Classroom 200	N/A	Concrete Ceiling		Non Suspect ACM	189	SF	0	SF					N/A	N/A	N/A			
1	2	Book Closet across from Classroom 200	N/A	CMU		Non Suspect ACM	680	SF	0	SF					N/A	N/A	N/A			
1	2	Book Closet across from Classroom 200	N/A	Cement Floor		Non Suspect ACM	189	SF	0	SF					N/A	N/A	N/A			
1	2	Classroom 202	T	Pipe Fitting Insulation	8390/01/02/08	Confirmed	8	EA	0	EA					1	No	1/D			
1	2	Classroom 202	N/A	Fiberglass Pipe Insulation		Non Suspect ACM	38	LF	0	LF					N/A	N/A	N/A			
1	2	Classroom 202	N/A	Concrete Ceiling		Non Suspect ACM	972	SF	0	SF					N/A	N/A	N/A			
1	2	Classroom 202	N/A	CMU		Non Suspect ACM	1260	SF	0	SF					N/A	N/A	N/A			
1	2	Classroom 202	M	Transite Closet	8390/01/02/16	Assumed	54	SF	0	SF					1	No	1/D			
1	2	Classroom 202	M	Floor Tile VAT 9" x 9"	8390/01/02/20	Confirmed	923	SF	0	SF	Grey				1	No	1/D			
1	2	Classroom 202	M	Floor Tile VAT 9" x 9"	8390/01/02/20	Confirmed	49	SF	0	SF	Green				1	No	1/D			
1	2	Classroom 201	T	Pipe Fitting Insulation	8390/01/02/08	Confirmed	10	EA	0	EA					1	No	1/D			
1	2	Classroom 201	N/A	Fiberglass Pipe Insulation		Non Suspect ACM	30	LF	0	LF					N/A	N/A	N/A			
1	2	Classroom 201	N/A	Fiberglass Ceiling Tile 2' x 4'		Non Suspect ACM	720	SF	0	SF					N/A	N/A	N/A			
1	2	Classroom 201	N/A	Concrete Ceiling		Non Suspect ACM	252	SF	0	SF					N/A	N/A	N/A			

# 8390 Aloysius Fitzpatrick ES 2015 2016 AHERA Three-Year Report.xls

		School District of Philadelphia	AHERA Three-Year Reinspection 2015-2016										Reinspection Date: 11/20/2015					
		Aloysius L. Fitzpatrick Elementary School	Room by Room Location Log Report										Building Inspector: Paul Davis					
		11061 Knights Road, Philadelphia, PA, 19154											Number: 050368					
		ULCS# 8390											Management Planner: Megan Vala					
		Year Built: 1960											Number: 740728					
Element	Floor	On Site Room Name	System Affected	Material Description	HID#	Confirmed/Assumed/NAD/ Non Suspect ACM	Amount of Material	SF LF EA	Amount of Damage	SF LF EA	Color required for VAT	Comments/Description/Notes	Attic/ Crawl Space Ranking	Damage Potential (DP)	Newly Friable (NF)	Response Action (RA)		
1	2	Classroom 201	N/A	CMU		Non Suspect ACM	1260	SF	0	SF				N/A	N/A	N/A		
1	2	Classroom 201	M	Sink Undercoat Mastic	8390/01/02/KEM/PD/2602	Assumed	6	SF	0	SF				1	No	1/D		
1	2	Classroom 201	M	Floor Tile VAT 12" x 12"	8390/01/02/LL	Assumed	972	SF	0	SF	Multi			1	No	1/D		
1	2	Boy's Restroom next to Classroom 201	T	Pipe Fitting Insulation	8390/01/02/08	Confirmed	6	EA	0	EA				1	No	1/D		
1	2	Boy's Restroom next to Classroom 201	N/A	Fiberglass Pipe Insulation		Non Suspect ACM	18	LF	0	LF				N/A	N/A	N/A		
1	2	Boy's Restroom next to Classroom 201	N/A	Concrete Ceiling		Non Suspect ACM	216	SF	0	SF				N/A	N/A	N/A		
1	2	Boy's Restroom next to Classroom 201	N/A	CMU		Non Suspect ACM	700	SF	0	SF				N/A	N/A	N/A		
1	2	Boy's Restroom next to Classroom 201	N/A	Cement Floor		Non Suspect ACM	216	SF	0	SF				N/A	N/A	N/A		
1	2	Classroom 204	T	Pipe Fitting Insulation	8390/01/02/08	Confirmed	8	EA	0	EA				1	No	1/D		
1	2	Classroom 204	N/A	Fiberglass Pipe Insulation		Non Suspect ACM	30	LF	0	LF				N/A	N/A	N/A		
1	2	Classroom 204	N/A	Concrete Ceiling		Non Suspect ACM	972	SF	0	SF				N/A	N/A	N/A		
1	2	Classroom 204	N/A	CMU		Non Suspect ACM	1260	SF	0	SF				N/A	N/A	N/A		
1	2	Classroom 204	M	Transite Closet	8390/01/02/16	Assumed	54	SF	0	SF				1	No	1/D		
1	2	Classroom 204	M	Floor Tile VAT 9" x 9"	8390/01/02/20	Confirmed	890	SF	0	SF	Grey			1	No	1/D		
1	2	Classroom 204	M	Floor Tile VAT 9" x 9"	8390/01/02/20	Confirmed	47	SF	0	SF	Green			1	No	1/D		
1	2	Classroom 204	M	Floor Tile VAT 12" x 12"	8390/01/02/LL	Assumed	35	SF	0	SF	Blue			1	No	1/D		
1	2	Storage Room across from Classroom 204	T	Pipe Fitting Insulation	8390/01/02/08	Confirmed	10	EA	0	EA				1	No	1/D		
1	2	Storage Room across from Classroom 204	N/A	Fiberglass Pipe Insulation		Non Suspect ACM	8	LF	0	LF				N/A	N/A	N/A		
1	2	Storage Room across from Classroom 204	N/A	Concrete Ceiling		Non Suspect ACM	378	SF	0	SF				N/A	N/A	N/A		
1	2	Storage Room across from Classroom 204	N/A	CMU		Non Suspect ACM	820	SF	0	SF				N/A	N/A	N/A		
1	2	Storage Room across from Classroom 204	N/A	Cement Floor		Non Suspect ACM	378	SF	0	SF				N/A	N/A	N/A		
1	2	Room 204-A Speech Office	T	Pipe Fitting Insulation	8390/01/02/08	Confirmed	1	EA	0	EA				1	No	1/D		
1	2	Room 204-A Speech Office	N/A	Fiberglass Pipe Insulation		Non Suspect ACM	4	LF	0	LF				N/A	N/A	N/A		
1	2	Room 204-A Speech Office	N/A	Concrete Ceiling		Non Suspect ACM	99	SF	0	SF				N/A	N/A	N/A		
1	2	Room 204-A Speech Office	N/A	CMU		Non Suspect ACM	400	SF	0	SF				N/A	N/A	N/A		
1	2	Room 204-A Speech Office	N/A	Cement Floor		Non Suspect ACM	99	SF	0	SF				N/A	N/A	N/A		
1	2	Library	T	Pipe Fitting Insulation	8390/01/02/08	Confirmed	22	EA	0	EA				1	No	1/D		
1	2	Library	N/A	Fiberglass Pipe Insulation		Non Suspect ACM	72	LF	0	LF				N/A	N/A	N/A		
1	2	Library	N/A	Concrete Ceiling		Non Suspect ACM	2484	SF	0	SF				N/A	N/A	N/A		
1	2	Library	N/A	CMU		Non Suspect ACM	1116	SF	0	SF				N/A	N/A	N/A		
1	2	Library	N/A	Carpet		Non Suspect ACM	2484	SF	0	SF				N/A	N/A	N/A		
1	2	Library	N/A	Sheetrock Wall		Non Suspect ACM	360	SF	0	SF				N/A	N/A	N/A		
1	2	Library Storage Room	T	Pipe Fitting Insulation	8390/01/02/08	Confirmed	15	EA	0	EA				1	No	1/D		
1	2	Library Storage Room	N/A	Fiberglass Pipe Insulation		Non Suspect ACM	33	LF	0	LF				N/A	N/A	N/A		
1	2	Library Storage Room	N/A	Concrete Ceiling		Non Suspect ACM	180	SF	0	SF				N/A	N/A	N/A		
1	2	Library Storage Room	N/A	CMU		Non Suspect ACM	420	SF	0	SF				N/A	N/A	N/A		
1	2	Library Storage Room	M	Floor Tile VAT 12" x 12"	8390/01/02/LL	Assumed	180	SF	0	SF	Tan			1	No	1/D		
1	2	Classroom 210	T	Pipe Fitting Insulation	8390/01/02/08	Confirmed	6	EA	0	EA				1	No	1/D		
1	2	Classroom 210	N/A	Fiberglass Pipe Insulation		Non Suspect ACM	25	LF	0	LF				N/A	N/A	N/A		
1	2	Classroom 210	N/A	Concrete Ceiling		Non Suspect ACM	972	SF	0	SF				N/A	N/A	N/A		
1	2	Classroom 210	N/A	CMU		Non Suspect ACM	1260	SF	0	SF				N/A	N/A	N/A		
1	2	Classroom 210	M	Transite Closet	8390/01/02/16	Assumed	54	SF	0	SF				1	No	1/D		
1	2	Classroom 210	M	Floor Tile VAT 9" x 9"	8390/01/02/20	Confirmed	923	SF	0	SF	Grey			1	No	1/D		
1	2	Classroom 210	M	Floor Tile VAT 9" x 9"	8390/01/02/20	Confirmed	49	SF	0	SF	Green			1	No	1/D		
1	2	Book Storage across from Classroom 210	N/A	Concrete Ceiling		Non Suspect ACM	133	SF	0	SF				N/A	N/A	N/A		
1	2	Book Storage across from Classroom 210	N/A	CMU		Non Suspect ACM	520	SF	0	SF				N/A	N/A	N/A		
1	2	Book Storage across from Classroom 210	N/A	Cement Floor		Non Suspect ACM	133	SF	0	SF				N/A	N/A	N/A		
1	2	Men's Restroom across from Classroom 210	T	Pipe Fitting Insulation	8390/01/02/08	Confirmed	12	EA	0	EA				1	No	1/D		
1	2	Men's Restroom across from Classroom 210	N/A	Fiberglass Pipe Insulation		Non Suspect ACM	33	LF	0	LF				N/A	N/A	N/A		
1	2	Men's Restroom across from Classroom 210	N/A	Concrete Ceiling		Non Suspect ACM	77	SF	0	SF				N/A	N/A	N/A		
1	2	Men's Restroom across from Classroom 210	N/A	CMU		Non Suspect ACM	360	SF	0	SF				N/A	N/A	N/A		
1	2	Men's Restroom across from Classroom 210	N/A	Cement Floor		Non Suspect ACM	77	SF	0	SF				N/A	N/A	N/A		
1	2	Computer Server Room across from Classrooms 210 and 212	T	Pipe Fitting Insulation	8390/01/02/08	Confirmed	13	EA	0	EA		No Access (S2017)		1	No	1/D		
1	2	Computer Server Room across from Classrooms 210 and 212	N/A	Fiberglass Pipe Insulation		Non Suspect ACM	35	LF	0	LF		No Access (S2017)		N/A	N/A	N/A		
1	2	Computer Server Room across from Classrooms 210 and 212	N/A	Ceiling Tile 1' x 1'		NAD	475	SF	0	SF		No Access (S2017)		N/A	N/A	N/A		
1	2	Computer Server Room across from Classrooms 210 and 212	M	Spline Ceiling Tile Glue Dots	8390/01/02/KEM/PD/2603	Assumed	48	SF	0	SF		No Access (S2017)		1	No	1/D		
1	2	Computer Server Room across from Classrooms 210 and 212	N/A	CMU		Non Suspect ACM	880	SF	0	SF		No Access (S2017)		N/A	N/A	N/A		
1	2	Computer Server Room across from Classrooms 210 and 212	M	Floor Tile VAT 9" x 9"	8390/01/02/20	Confirmed	451	SF	0	SF	Tan	No Access (S2017)		1	No	1/D		
1	2	Computer Server Room across from Classrooms 210 and 212	M	Floor Tile VAT 9" x 9"	8390/01/02/20	Confirmed	24	SF	0	SF	Black	No Access (S2017)		1	No	1/D		
1	2	Women's Restroom across from Classroom 212	T	Pipe Fitting Insulation	8390/01/02/08	Confirmed	2	EA	0	EA				1	No	1/D		
1	2	Women's Restroom across from Classroom 212	N/A	Fiberglass Pipe Insulation		Non Suspect ACM	16	LF	0	LF				N/A	N/A	N/A		
1	2	Women's Restroom across from Classroom 212	N/A	Concrete Ceiling		Non Suspect ACM	100	SF	0	SF				N/A	N/A	N/A		
1	2	Women's Restroom across from Classroom 212	N/A	CMU		Non Suspect ACM	400	SF	0	SF				N/A	N/A	N/A		
1	2	Women's Restroom across from Classroom 212	N/A	Cement Floor		Non Suspect ACM	100	SF	0	SF				N/A	N/A	N/A		
1	2	Girl's Restroom across from Classroom 212	T	Pipe Fitting Insulation	8390/01/02/08	Confirmed	4	EA	0	EA				1	No	1/D		
1	2	Girl's Restroom across from Classroom 212	N/A	Fiberglass Pipe Insulation		Non Suspect ACM	13	LF	0	LF				N/A	N/A	N/A		

# 8390 Aloysius Fitzpatrick ES 2015 2016 AHERA Three-Year Report.xls

School District of Philadelphia			AHERA Three-Year Reinspection 2015-2016										Reinspection Date: 11/20/2015					
Aloysius L. Fitzpatrick Elementary School			Room by Room Location Log Report										Building Inspector: Paul Davis					
11061 Knights Road, Philadelphia, PA, 19154													Number: 050368					
ULCS# 8390													Management Planner: Megan Vala					
Year Built: 1960													Number: 740728					
E l e m e n t	F l o o r	On Site Room Name	System Affected	Material Description	HID#	Confirmed/Assumed/NAD/ Non Suspect ACM	Amount of Material	SF LF EA	Amount of Damage	SF LF EA	Color required for VAT	Comments/Description/Notes	Attic/ Crawl Space Ranking	Damage Potential (DP)	Newly Friable (NF)	Response Action (RA)		
1	2	Girl's Restroom across from Classroom 212	N/A	Concrete Ceiling		Non Suspect ACM	243	SF	0	SF				N/A	N/A	N/A		
1	2	Girl's Restroom across from Classroom 212	N/A	CMU		Non Suspect ACM	720	SF	0	SF				N/A	N/A	N/A		
1	2	Girl's Restroom across from Classroom 212	N/A	Cement Floor		Non Suspect ACM	243	SF	0	SF				N/A	N/A	N/A		
1	2	Custodial Closet across from Classroom 212	T	Pipe Fitting Insulation	8390/01/02/08	Confirmed	1	EA	0	EA				1	No	1/D		
1	2	Custodial Closet across from Classroom 212	N/A	Fiberglass Pipe Insulation		Non Suspect ACM	2	LF	0	LF				N/A	N/A	N/A		
1	2	Custodial Closet across from Classroom 212	N/A	Concrete Ceiling		Non Suspect ACM	49	SF	0	SF				N/A	N/A	N/A		
1	2	Custodial Closet across from Classroom 212	N/A	CMU		Non Suspect ACM	280	SF	0	SF				N/A	N/A	N/A		
1	2	Custodial Closet across from Classroom 212	N/A	Cement Floor		Non Suspect ACM	49	SF	0	SF				N/A	N/A	N/A		
1	2	Pipe Chase in Custodial Closet across from Classroom 212	T	Pipe Fitting Insulation	8390/01/02/08	Confirmed	25	EA	0	EA				1	No	1/D		
1	2	Pipe Chase in Custodial Closet across from Classroom 212	N/A	Fiberglass Pipe Insulation		Non Suspect ACM	100	LF	0	LF				N/A	N/A	N/A		
1	2	Pipe Chase in Custodial Closet across from Classroom 212	N/A	Concrete Ceiling		Non Suspect ACM	45	SF	0	SF				N/A	N/A	N/A		
1	2	Pipe Chase in Custodial Closet across from Classroom 212	N/A	CMU		Non Suspect ACM	360	SF	0	SF				N/A	N/A	N/A		
1	2	Pipe Chase in Custodial Closet across from Classroom 212	N/A	Cement Floor		Non Suspect ACM	45	SF	0	SF				N/A	N/A	N/A		
1	2	Classroom 212	T	Pipe Fitting Insulation	8390/01/02/08	Confirmed	8	EA	0	EA				1	No	1/D		
1	2	Classroom 212	N/A	Fiberglass Pipe Insulation		Non Suspect ACM	34	LF	1	LF				N/A	N/A	N/A		
1	2	Classroom 212	N/A	Concrete Ceiling		Non Suspect ACM	972	SF	0	SF				N/A	N/A	N/A		
1	2	Classroom 212	N/A	CMU		Non Suspect ACM	1260	SF	0	SF				N/A	N/A	N/A		
1	2	Classroom 212	M	Transite Closet	8390/01/02/16	Assumed	54	SF	0	SF				1	No	1/D		
1	2	Classroom 212	M	Floor Tile VAT 9" x 9"	8390/01/02/20	Confirmed	923	SF	0	SF	Grey			1	No	1/D		
1	2	Classroom 212	M	Floor Tile VAT 9" x 9"	8390/01/02/20	Confirmed	49	SF	0	SF	Green			1	No	1/D		
1	2	Stairwell near Classrooms 212 and 214	N/A	Fiberglass Pipe Insulation		Non Suspect ACM	1	LF	0	LF				N/A	N/A	N/A		
1	2	Stairwell near Classrooms 212 and 214	N/A	Concrete Ceiling		Non Suspect ACM	90	SF	0	SF				N/A	N/A	N/A		
1	2	Stairwell near Classrooms 212 and 214	N/A	CMU		Non Suspect ACM	1110	SF	0	SF				N/A	N/A	N/A		
1	2	Stairwell near Classrooms 212 and 214	N/A	Cement Floor		Non Suspect ACM	180	SF	0	SF				N/A	N/A	N/A		
1	2	Classroom 214	T	Pipe Fitting Insulation	8390/01/02/08	Confirmed	8	EA	0	EA				1	No	1/D		
1	2	Classroom 214	N/A	Fiberglass Pipe Insulation		Non Suspect ACM	36	LF	0	LF				N/A	N/A	N/A		
1	2	Classroom 214	N/A	Concrete Ceiling		Non Suspect ACM	972	SF	0	SF				N/A	N/A	N/A		
1	2	Classroom 214	N/A	CMU		Non Suspect ACM	1260	SF	0	SF				N/A	N/A	N/A		
1	2	Classroom 214	M	Transite Closet	8390/01/02/16	Assumed	54	SF	0	SF				1	No	1/D		
1	2	Classroom 214	M	Floor Tile VAT 9" x 9"	8390/01/02/20	Confirmed	912	SF	0	SF	Grey			1	No	1/D		
1	2	Classroom 214	M	Floor Tile VAT 9" x 9"	8390/01/02/20	Confirmed	48	SF	0	SF	Green			1	No	1/D		
1	2	Classroom 214	M	Floor Tile VAT 12" x 12"	8390/01/02/LL	Assumed	12	SF	0	SF	Grey			1	No	1/D		
1	2	Classroom 203	T	Pipe Fitting Insulation	8390/01/02/08	Confirmed	11	EA	0	EA				1	No	1/D		
1	2	Classroom 203	N/A	Fiberglass Pipe Insulation		Non Suspect ACM	40	LF	0	LF				N/A	N/A	N/A		
1	2	Classroom 203	N/A	Concrete Ceiling		Non Suspect ACM	972	SF	0	SF				N/A	N/A	N/A		
1	2	Classroom 203	N/A	CMU		Non Suspect ACM	1260	SF	0	SF				N/A	N/A	N/A		
1	2	Classroom 203	M	Transite Closet	8390/01/02/16	Assumed	54	SF	0	SF				1	No	1/D		
1	2	Classroom 203	M	Floor Tile VAT 9" x 9"	8390/01/02/20	Confirmed	923	SF	0	SF	Tan			1	No	1/D		
1	2	Classroom 203	M	Floor Tile VAT 9" x 9"	8390/01/02/20	Confirmed	49	SF	0	SF	Brown			1	No	1/D		
1	2	Classroom 216	T	Pipe Fitting Insulation	8390/01/02/08	Confirmed	8	EA	0	EA				1	No	1/D		
1	2	Classroom 216	N/A	Fiberglass Pipe Insulation		Non Suspect ACM	30	LF	0	LF				N/A	N/A	N/A		
1	2	Classroom 216	N/A	Concrete Ceiling		Non Suspect ACM	972	SF	0	SF				N/A	N/A	N/A		
1	2	Classroom 216	N/A	CMU		Non Suspect ACM	1260	SF	0	SF				N/A	N/A	N/A		
1	2	Classroom 216	M	Transite Closet	8390/01/02/16	Assumed	54	SF	0	SF				1	No	1/D		
1	2	Classroom 216	M	Floor Tile VAT 9" x 9"	8390/01/02/20	Confirmed	923	SF	0	SF	Grey			1	No	1/D		
1	2	Classroom 216	M	Floor Tile VAT 9" x 9"	8390/01/02/20	Confirmed	49	SF	0	SF	Green			1	No	1/D		
1	2	Classroom 205	T	Pipe Fitting Insulation	8390/01/02/08	Confirmed	6	EA	0	EA				1	No	1/D		
1	2	Classroom 205	N/A	Fiberglass Pipe Insulation		Non Suspect ACM	21	LF	0	LF				N/A	N/A	N/A		
1	2	Classroom 205	N/A	Concrete Ceiling		Non Suspect ACM	972	SF	0	SF				N/A	N/A	N/A		
1	2	Classroom 205	N/A	CMU		Non Suspect ACM	1260	SF	0	SF				N/A	N/A	N/A		
1	2	Classroom 205	M	Transite Closet	8390/01/02/16	Assumed	54	SF	1	SF		Less than 1 SF; Chipped.		1	Yes	5/C		
1	2	Classroom 205	M	Floor Tile VAT 9" x 9"	8390/01/02/20	Confirmed	923	SF	0	SF	Tan			1	No	1/D		
1	2	Classroom 205	M	Floor Tile VAT 9" x 9"	8390/01/02/20	Confirmed	49	SF	0	SF	Brown			1	No	1/D		
1	2	Classroom 218	T	Pipe Fitting Insulation	8390/01/02/08	Confirmed	10	EA	0	EA				1	No	1/D		
1	2	Classroom 218	N/A	Fiberglass Pipe Insulation		Non Suspect ACM	60	LF	0	LF				N/A	N/A	N/A		
1	2	Classroom 218	N/A	Concrete Ceiling		Non Suspect ACM	972	SF	0	SF				N/A	N/A	N/A		
1	2	Classroom 218	N/A	CMU		Non Suspect ACM	1260	SF	0	SF				N/A	N/A	N/A		
1	2	Classroom 218	M	Transite Closet	8390/01/02/16	Assumed	54	SF	0	SF				1	No	1/D		
1	2	Classroom 218	M	Floor Tile VAT 9" x 9"	8390/01/02/20	Confirmed	836	SF	0	SF	Grey			1	No	1/D		
1	2	Classroom 218	M	Floor Tile VAT 9" x 9"	8390/01/02/20	Confirmed	44	SF	0	SF	Green			1	No	1/D		
1	2	Classroom 218	M	Floor Tile VAT 12" x 12"	8390/01/02/LL	Assumed	48	SF	0	SF	Grey			1	No	1/D		
1	2	Classroom 218	M	Floor Tile VAT 12" x 12"	8390/01/02/LL	Assumed	44	SF	0	SF	Tan			1	No	1/D		
1	2	Classroom 207	T	Pipe Fitting Insulation	8390/01/02/08	Confirmed	13	EA	0	EA				1	No	1/D		
1	2	Classroom 207	N/A	Fiberglass Pipe Insulation		Non Suspect ACM	48	LF	0	LF				N/A	N/A	N/A		
1	2	Classroom 207	N/A	Concrete Ceiling		Non Suspect ACM	550	SF	0	SF				N/A	N/A	N/A		
1	2	Classroom 207	N/A	CMU		Non Suspect ACM	940	SF	0	SF				N/A	N/A	N/A		
1	2	Classroom 207	M	Floor Tile VAT 9" x 9"	8390/01/02/20	Confirmed	522	SF	0	SF	Tan			1	No	1/D		

# 8390 Aloysius Fitzpatrick ES 2015 2016 AHERA Three-Year Report.xls

School District of Philadelphia			AHERA Three-Year Reinspection 2015-2016										Reinspection Date: 11/20/2015							
Aloysius L. Fitzpatrick Elementary School			Room by Room Location Log Report										Building Inspector: Paul Davis							
11061 Knights Road, Philadelphia, PA, 19154													Number: 050368							
ULCS# 8390													Management Planner: Megan Vala							
Year Built: 1960													Number: 740728							
E l e m e n t	F l o o r	On Site Room Name	System Affected	Material Description	HID#	Confirmed/Assumed/NAD/ Non Suspect ACM	Amount of Material	SF	LF	EA	Amount of Damage	SF	LF	EA	Color required for VAT	Comments/Description/Notes	Attic/ Crawl Space Ranking	Damage Potential (DP)	Newly Friable (NF)	Response Action (RA)
1	2	Classroom 207	M	Floor Tile VAT 9" x 9"	8390/01/02/20	Confirmed	28	SF	0	SF					Brown			1	No	1/D
1	2	Stairwell near Classrooms 207 and 218	T	Pipe Fitting Insulation	8390/01/02/08	Confirmed	3	EA	1	EA						Seam		1	Yes	5/A
1	2	Stairwell near Classrooms 207 and 218	N/A	Fiberglass Pipe Insulation		Non Suspect ACM	2	LF	0	LF								N/A	N/A	N/A
1	2	Stairwell near Classrooms 207 and 218	N/A	Concrete Ceiling		Non Suspect ACM	90	SF	0	SF								N/A	N/A	N/A
1	2	Stairwell near Classrooms 207 and 218	N/A	CMU		Non Suspect ACM	1110	SF	0	SF								N/A	N/A	N/A
1	2	Stairwell near Classrooms 207 and 218	N/A	Cement Floor		Non Suspect ACM	180	SF	0	SF								N/A	N/A	N/A
1	2	Hallway from Classrooms 210 to 218	T	Pipe Fitting Insulation	8390/01/02/08	Confirmed	4	EA	0	EA								1	No	1/D
1	2	Hallway from Classrooms 210 to 218	N/A	Fiberglass Pipe Insulation		Non Suspect ACM	2	LF	0	LF								N/A	N/A	N/A
1	2	Hallway from Classrooms 210 to 218	N/A	Concrete Ceiling		Non Suspect ACM	1638	SF	0	SF								N/A	N/A	N/A
1	2	Hallway from Classrooms 210 to 218	N/A	CMU		Non Suspect ACM	3730	SF	0	SF								N/A	N/A	N/A
1	2	Hallway from Classrooms 210 to 218	M	Floor Tile VAT 9" x 9"	8390/01/02/20	Confirmed	1612	SF	0	SF					Tan			1	No	1/D
1	2	Hallway from Classrooms 210 to 218	M	Floor Tile VAT 9" x 9"	8390/01/02/LL	Confirmed	18	SF	0	SF					White			1	No	1/D
1	2	Hallway from Classrooms 210 to 218	M	Floor Tile VAT 12" x 12"	8390/01/02/LL	Assumed	8	SF	0	SF					Tan			1	No	1/D
1	2	Hallway outside IMC 206/208	T	Pipe Fitting Insulation	8390/01/02/08	Confirmed	8	EA	0	EA								1	No	1/D
1	2	Hallway outside IMC 206/208	N/A	Fiberglass Pipe Insulation		Non Suspect ACM	6	LF	0	LF								N/A	N/A	N/A
1	2	Hallway outside IMC 206/208	N/A	Concrete Ceiling		Non Suspect ACM	600	SF	0	SF								N/A	N/A	N/A
1	2	Hallway outside IMC 206/208	N/A	CMU		Non Suspect ACM	1000	SF	0	SF								N/A	N/A	N/A
1	2	Hallway outside IMC 206/208	M	Floor Tile VAT 9" x 9"	8390/01/02/20	Confirmed	570	SF	0	SF					Tan			1	No	1/D
1	2	Hallway outside IMC 206/208	M	Floor Tile VAT 12" x 12"	8390/01/02/LL	Assumed	30	SF	0	SF					Tan			1	No	1/D
1	2	Hallway from IMC to Classroom 200	T	Pipe Fitting Insulation	8390/01/02/08	Confirmed	4	EA	0	EA								1	No	1/D
1	2	Hallway from IMC to Classroom 200	N/A	Fiberglass Pipe Insulation		Non Suspect ACM	3	LF	0	LF								N/A	N/A	N/A
1	2	Hallway from IMC to Classroom 200	N/A	Concrete Ceiling		Non Suspect ACM	1044	SF	0	SF								N/A	N/A	N/A
1	2	Hallway from IMC to Classroom 200	N/A	CMU		Non Suspect ACM	2410	SF	0	SF								N/A	N/A	N/A
1	2	Hallway from IMC to Classroom 200	M	Floor Tile VAT 9" x 9"	8390/01/02/20	Confirmed	1029	SF	0	SF					Tan			1	No	1/D
1	2	Hallway from IMC to Classroom 200	M	Floor Tile VAT 12" x 12"	8390/01/02/LL	Assumed	15	SF	0	SF					Tan			1	No	1/D
1	3	Stairwell near Classroom 300	N/A	Concrete Ceiling		Non Suspect ACM	270	SF	0	SF								N/A	N/A	N/A
1	3	Stairwell near Classroom 300	N/A	CMU		Non Suspect ACM	1110	SF	0	SF								N/A	N/A	N/A
1	3	Stairwell near Classroom 300	N/A	Cement Floor		Non Suspect ACM	270	SF	0	SF								N/A	N/A	N/A
1	3	Classroom 300	N/A	Fiberglass Pipe Insulation		Non Suspect ACM	8	LF	0	LF								N/A	N/A	N/A
1	3	Classroom 300	N/A	Fiberglass Ceiling Tile 2' x 4'		Non Suspect ACM	972	SF	0	SF								N/A	N/A	N/A
1	3	Classroom 300	N/A	CMU		Non Suspect ACM	1260	SF	0	SF								N/A	N/A	N/A
1	3	Classroom 300	M	Transite Closet	8390/01/03/17	Assumed	36	SF	0	SF								1	No	1/D
1	3	Classroom 300	M	Floor Tile VAT 9" x 9"	8390/01/03/21	Confirmed	875	SF	0	SF					Grey			1	No	1/D
1	3	Classroom 300	M	Floor Tile VAT 9" x 9"	8390/01/03/21	Confirmed	97	SF	0	SF					Green			1	No	1/D
1	3	Book Closet across from Classroom 300	N/A	Concrete Ceiling		Non Suspect ACM	189	SF	0	SF								N/A	N/A	N/A
1	3	Book Closet across from Classroom 300	N/A	CMU		Non Suspect ACM	680	SF	0	SF								N/A	N/A	N/A
1	3	Book Closet across from Classroom 300	N/A	Cement Floor		Non Suspect ACM	189	SF	0	SF								N/A	N/A	N/A
1	3	Classroom 302	N/A	Fiberglass Ceiling Tile 2' x 4'		Non Suspect ACM	972	SF	0	SF								N/A	N/A	N/A
1	3	Classroom 302	N/A	CMU		Non Suspect ACM	1260	SF	0	SF								N/A	N/A	N/A
1	3	Classroom 302	M	Transite Closet	8390/01/03/17	Assumed	36	SF	0	SF								1	No	1/D
1	3	Classroom 302	M	Floor Tile VAT 9" x 9"	8390/01/03/21	Confirmed	807	SF	0	SF					Grey			1	No	1/D
1	3	Classroom 302	M	Floor Tile VAT 9" x 9"	8390/01/03/21	Confirmed	90	SF	0	SF					Green			1	No	1/D
1	3	Classroom 302	M	Floor Tile VAT 12" x 12"	8390/01/03/MM	Assumed	75	SF	0	SF					Grey			1	No	1/D
1	3	Classroom 302	N/A	Sheetrock Wall		Non Suspect ACM	70	SF	0	SF						Closet Walls.		N/A	N/A	N/A
1	3	Classroom 301	N/A	Fiberglass Ceiling Tile 2' x 4'		Non Suspect ACM	972	SF	0	SF								N/A	N/A	N/A
1	3	Classroom 301	N/A	CMU		Non Suspect ACM	1260	SF	0	SF								N/A	N/A	N/A
1	3	Classroom 301	M	Transite Closet	8390/01/03/17	Assumed	36	SF	0	SF								1	No	1/D
1	3	Classroom 301	M	Floor Tile VAT 9" x 9"	8390/01/03/21	Confirmed	875	SF	0	SF					Tan			1	No	1/D
1	3	Classroom 301	M	Floor Tile VAT 9" x 9"	8390/01/03/21	Confirmed	97	SF	0	SF					Brown			1	No	1/D
1	3	Classroom 301	N/A	Sheetrock Wall		Non Suspect ACM	56	SF	0	SF						Closet Walls.		N/A	N/A	N/A
1	3	Boy's Restroom next to Classroom 301	N/A	Fiberglass Pipe Insulation		Non Suspect ACM	3	LF	2	LF								N/A	N/A	N/A
1	3	Boy's Restroom next to Classroom 301	N/A	Fiberglass Pipe Fitting Insulation		Non Suspect ACM	1	EA	0	EA								N/A	N/A	N/A
1	3	Boy's Restroom next to Classroom 301	N/A	Concrete Ceiling		Non Suspect ACM	216	SF	0	SF								N/A	N/A	N/A
1	3	Boy's Restroom next to Classroom 301	N/A	CMU		Non Suspect ACM	700	SF	0	SF								N/A	N/A	N/A
1	3	Boy's Restroom next to Classroom 301	N/A	Cement Floor		Non Suspect ACM	216	SF	0	SF								N/A	N/A	N/A
1	3	Storage Room across from Classroom 304	N/A	Concrete Ceiling		Non Suspect ACM	324	SF	0	SF								N/A	N/A	N/A
1	3	Storage Room across from Classroom 304	N/A	CMU		Non Suspect ACM	780	SF	0	SF								N/A	N/A	N/A
1	3	Storage Room across from Classroom 304	N/A	Cement Floor		Non Suspect ACM	324	SF	0	SF								N/A	N/A	N/A
1	3	Classroom 304	N/A	Concrete Ceiling		Non Suspect ACM	972	SF	0	SF								N/A	N/A	N/A
1	3	Classroom 304	N/A	CMU		Non Suspect ACM	1260	SF	0	SF								N/A	N/A	N/A
1	3	Classroom 304	M	Transite Closet	8390/01/03/17	Assumed	54	SF	0	SF								1	No	1/D
1	3	Classroom 304	M	Floor Tile VAT 9" x 9"	8390/01/03/21	Confirmed	900	SF	0	SF					Grey			1	No	1/D
1	3	Classroom 304	M	Floor Tile VAT 9" x 9"	8390/01/03/21	Confirmed	48	SF	0	SF					Green			1	No	1/D
1	3	Classroom 304	M	Floor Tile VAT 12" x 12"	8390/01/03/MM	Assumed	24	SF	0	SF					Tan			1	No	1/D
1	3	Storage Room across from Classroom 304 next to Elevator	N/A	Concrete Ceiling		Non Suspect ACM	63	SF	0	SF								N/A	N/A	N/A
1	3	Storage Room across from Classroom 304 next to Elevator	N/A	CMU		Non Suspect ACM	320	SF	0	SF								N/A	N/A	N/A
1	3	Storage Room across from Classroom 304 next to Elevator	N/A	Cement Floor		Non Suspect ACM	63	SF	0	SF								N/A	N/A	N/A
1	3	Home and School Room 334	N/A	Fiberglass Pipe Insulation		Non Suspect ACM	9	LF	0	LF								N/A	N/A	N/A
1	3	Home and School Room 334	N/A	Concrete Ceiling		Non Suspect ACM	540	SF	0	SF								N/A	N/A	N/A

# 8390 Aloysius Fitzpatrick ES 2015 2016 AHERA Three-Year Report.xls

School District of Philadelphia			AHERA Three-Year Reinspection 2015-2016										Reinspection Date: 11/20/2015							
Aloysius L. Fitzpatrick Elementary School			Room by Room Location Log Report										Building Inspector: Paul Davis							
11061 Knights Road, Philadelphia, PA, 19154													Number: 050368							
ULCS# 8390													Management Planner: Megan Vala							
Year Built: 1960													Number: 740728							
E l e m e n t	F l o o r	On Site Room Name	System Affected	Material Description	HID#	Confirmed/Assumed/NAD/ Non Suspect ACM	Amount of Material	SF	LF	EA	Amount of Damage	SF	LF	EA	Color required for VAT	Comments/Description/Notes	Attic/ Crawl Space Ranking	Damage Potential (DP)	Newly Friable (NF)	Response Action (RA)
1	3	Home and School Room 334	N/A	CMU		Non Suspect ACM	940	SF	0	SF								N/A	N/A	N/A
1	3	Home and School Room 334	M	Floor Tile VAT 12" x 12"	8390/01/03/MM	Assumed	540	SF	0	SF	Tan							1	No	1/D
1	3	Hallway from Classroom 300 to Home and School Room 334	N/A	Concrete Ceiling		Non Suspect ACM	1053	SF	0	SF								N/A	N/A	N/A
1	3	Hallway from Classroom 300 to Home and School Room 334	N/A	CMU		Non Suspect ACM	2430	SF	0	SF								N/A	N/A	N/A
1	3	Hallway from Classroom 300 to Home and School Room 334	M	Floor Tile VAT 12" x 12"	8390/01/03/MM	Assumed	842	SF	0	SF	Tan							1	No	1/D
1	3	Hallway from Classroom 300 to Home and School Room 334	M	Floor Tile VAT 12" x 12"	8390/01/03/MM	Assumed	211	SF	0	SF	Brown							1	No	1/D
1	3	Computer Lab 306/308	N/A	Fiberglass Pipe Insulation		Non Suspect ACM	9	LF	0	LF								N/A	N/A	N/A
1	3	Computer Lab 306/308	N/A	Concrete Ceiling		Non Suspect ACM	1944	SF	0	SF								N/A	N/A	N/A
1	3	Computer Lab 306/308	N/A	CMU		Non Suspect ACM	1980	SF	0	SF								N/A	N/A	N/A
1	3	Computer Lab 306/308	M	Transite Closet	8390/01/03/17	Assumed	108	SF	0	SF								1	No	1/D
1	3	Computer Lab 306/308	M	Floor Tile VAT 9" x 9"	8390/01/03/21	Confirmed	1847	SF	0	SF	Grey							1	No	1/D
1	3	Computer Lab 306/308	M	Floor Tile VAT 9" x 9"	8390/01/03/21	Confirmed	97	SF	0	SF	Green							1	No	1/D
1	3	Computer Lab Storage Room	N/A	Concrete Ceiling		Non Suspect ACM	77	SF	0	SF								N/A	N/A	N/A
1	3	Computer Lab Storage Room	N/A	CMU		Non Suspect ACM	360	SF	0	SF								N/A	N/A	N/A
1	3	Computer Lab Storage Room	M	Floor Tile VAT 9" x 9"	8390/01/03/21	Confirmed	70	SF	0	SF	Grey							1	No	1/D
1	3	Computer Lab Storage Room	M	Floor Tile VAT 9" x 9"	8390/01/03/21	Confirmed	7	SF	0	SF	Green							1	No	1/D
1	3	Hallway outside Computer Lab	N/A	Concrete Ceiling		Non Suspect ACM	600	SF	0	SF								N/A	N/A	N/A
1	3	Hallway outside Computer Lab	N/A	CMU		Non Suspect ACM	1000	SF	0	SF								N/A	N/A	N/A
1	3	Hallway outside Computer Lab	M	Floor Tile VAT 12" x 12"	8390/01/03/MM	Assumed	480	SF	0	SF	Tan							1	No	1/D
1	3	Hallway outside Computer Lab	M	Floor Tile VAT 12" x 12"	8390/01/03/MM	Assumed	120	SF	0	SF	Brown							1	No	1/D
1	3	Classroom 310	N/A	Concrete Ceiling		Non Suspect ACM	972	SF	0	SF								N/A	N/A	N/A
1	3	Classroom 310	N/A	CMU		Non Suspect ACM	1260	SF	0	SF								N/A	N/A	N/A
1	3	Classroom 310	M	Transite Closet	8390/01/03/17	Assumed	54	SF	0	SF								1	No	1/D
1	3	Classroom 310	M	Floor Tile VAT 9" x 9"	8390/01/03/21	Confirmed	923	SF	0	SF	Grey							1	No	1/D
1	3	Classroom 310	M	Floor Tile VAT 9" x 9"	8390/01/03/21	Confirmed	49	SF	0	SF	Green							1	No	1/D
1	3	Classroom 310 Storage Room	N/A	Concrete Ceiling		Non Suspect ACM	105	SF	0	SF								N/A	N/A	N/A
1	3	Classroom 310 Storage Room	N/A	CMU		Non Suspect ACM	440	SF	0	SF								N/A	N/A	N/A
1	3	Classroom 310 Storage Room	M	Floor Tile VAT 9" x 9"	8390/01/03/21	Confirmed	95	SF	0	SF	Grey							1	No	1/D
1	3	Classroom 310 Storage Room	M	Floor Tile VAT 9" x 9"	8390/01/03/21	Confirmed	10	SF	0	SF	Green							1	No	1/D
1	3	Book Storage across from Classroom 310	T	Pipe Fitting Insulation	8390/01/03/09	Confirmed	3	EA	0	EA								1	No	1/D
1	3	Book Storage across from Classroom 310	N/A	Fiberglass Pipe Insulation		Non Suspect ACM	8	LF	0	LF								N/A	N/A	N/A
1	3	Book Storage across from Classroom 310	N/A	Concrete Ceiling		Non Suspect ACM	147	SF	0	SF								N/A	N/A	N/A
1	3	Book Storage across from Classroom 310	N/A	CMU		Non Suspect ACM	560	SF	0	SF								N/A	N/A	N/A
1	3	Book Storage across from Classroom 310	N/A	Cement Floor		Non Suspect ACM	147	SF	0	SF								N/A	N/A	N/A
1	3	Men's Restroom across from Classrooms 310	N/A	Concrete Ceiling		Non Suspect ACM	77	SF	0	SF								N/A	N/A	N/A
1	3	Men's Restroom across from Classrooms 310	N/A	CMU		Non Suspect ACM	360	SF	0	SF								N/A	N/A	N/A
1	3	Men's Restroom across from Classrooms 310	N/A	Cement Floor		Non Suspect ACM	77	SF	0	SF								N/A	N/A	N/A
1	3	Teacher's Lounge	N/A	Ceiling Tile 1' x 1'		NAD	475	SF	0	SF								N/A	N/A	N/A
1	3	Teacher's Lounge	M	Spine Ceiling Tile Glue Dots	8390/01/03/KEM/PD/2603	Assumed	48	SF	0	SF								1	No	1/D
1	3	Teacher's Lounge	N/A	CMU		Non Suspect ACM	880	SF	0	SF								N/A	N/A	N/A
1	3	Teacher's Lounge	M	Floor Tile VAT 9" x 9"	8390/01/03/21	Confirmed	428	SF	0	SF	Tan							1	No	1/D
1	3	Teacher's Lounge	M	Floor Tile VAT 9" x 9"	8390/01/03/21	Confirmed	23	SF	0	SF	Brown							1	No	1/D
1	3	Teacher's Lounge	M	Floor Tile VAT 12" x 12"	8390/01/03/MM	Assumed	24	SF	0	SF	Tan							1	No	1/D
1	3	Teacher's Lounge Crawl Space on Left	N/A	Concrete Ceiling		Non Suspect ACM	96	SF	0	SF								N/A	N/A	N/A
1	3	Teacher's Lounge Crawl Space on Left	N/A	CMU		Non Suspect ACM	280	SF	0	SF								N/A	N/A	N/A
1	3	Teacher's Lounge Crawl Space on Left	N/A	Brick Wall		Non Suspect ACM	280	SF	0	SF								N/A	N/A	N/A
1	3	Teacher's Lounge Crawl Space on Left	N/A	Cement Floor		Non Suspect ACM	96	SF	0	SF								N/A	N/A	N/A
1	3	Teacher's Lounge Crawl Space on Right	X	X		X	X	X	X	X	No Access (S2017)							X	X	X
1	3	Women's Restroom across from Classroom 312	N/A	Concrete Ceiling		Non Suspect ACM	100	SF	0	SF								N/A	N/A	N/A
1	3	Women's Restroom across from Classroom 312	N/A	CMU		Non Suspect ACM	400	SF	0	SF								N/A	N/A	N/A
1	3	Women's Restroom across from Classroom 312	N/A	Cement Floor		Non Suspect ACM	100	SF	0	SF								N/A	N/A	N/A
1	3	Girl's Restroom across from Classroom 312	N/A	Concrete Ceiling		Non Suspect ACM	243	SF	0	SF								N/A	N/A	N/A
1	3	Girl's Restroom across from Classroom 312	N/A	CMU		Non Suspect ACM	720	SF	0	SF								N/A	N/A	N/A
1	3	Girl's Restroom across from Classroom 312	N/A	Cement Floor		Non Suspect ACM	243	SF	0	SF								N/A	N/A	N/A
1	3	Custodial Closet across from Classroom 312	N/A	Concrete Ceiling		Non Suspect ACM	49	SF	0	SF								N/A	N/A	N/A
1	3	Custodial Closet across from Classroom 312	N/A	CMU		Non Suspect ACM	280	SF	0	SF								N/A	N/A	N/A
1	3	Custodial Closet across from Classroom 312	N/A	Cement Floor		Non Suspect ACM	49	SF	0	SF								N/A	N/A	N/A
1	3	Pipe Chase in Custodial Closet across from Classroom 312	X	X		X	X	X	X	X	No Access (S2017)							X	X	X
1	3	Classroom 312	N/A	Fiberglass Pipe Insulation		Non Suspect ACM	9	LF	0	LF								N/A	N/A	N/A
1	3	Classroom 312	N/A	Concrete Ceiling		Non Suspect ACM	972	SF	0	SF								N/A	N/A	N/A
1	3	Classroom 312	N/A	CMU		Non Suspect ACM	1260	SF	0	SF								N/A	N/A	N/A
1	3	Classroom 312	M	Transite Closet	8390/01/03/17	Assumed	54	SF	0	SF								1	No	1/D
1	3	Classroom 312	M	Floor Tile VAT 9" x 9"	8390/01/03/21	Confirmed	895	SF	0	SF	Grey							1	No	1/D
1	3	Classroom 312	M	Floor Tile VAT 9" x 9"	8390/01/03/21	Confirmed	47	SF	0	SF	Green							1	No	1/D
1	3	Classroom 312	M	Floor Tile VAT 12" x 12"	8390/01/03/MM	Assumed	30	SF	0	SF	Grey							1	No	1/D
1	3	Stairwell across from Classroom 314	T	Pipe Fitting Insulation	8390/01/03/09	Confirmed	3	EA	0	EA								1	No	1/D
1	3	Stairwell across from Classroom 314	N/A	Fiberglass Pipe Insulation		Non Suspect ACM	2	LF	1	LF								N/A	N/A	N/A

# 8390 Aloysius Fitzpatrick ES 2015 2016 AHERA Three-Year Report.xls

School District of Philadelphia Aloysius L. Fitzpatrick Elementary School 11061 Knights Road, Philadelphia, PA, 19154 ULCS# 8390 Year Built: 1960			AHERA Three-Year Reinspection 2015-2016 Room by Room Location Log Report										Reinspection Date: 11/20/2015 Building Inspector: Paul Davis Number: 050368 Management Planner: Megan Vala Number: 740728						
			Element	Floor	On Site Room Name	System Affected	Material Description	HID#	Confirmed/Assumed/NAD/ Non Suspect ACM	Amount of Material	SF LF EA	Amount of Damage	SF LF EA	Color required for VAT	Comments/Description/Notes	Attic/Crawl Space Ranking	Damage Potential (DP)	Newly Friable (NF)	Response Action (RA)

Element	Floor	On Site Room Name	System Affected	Material Description	HID#	Confirmed/Assumed/NAD/ Non Suspect ACM	Amount of Material	SF LF EA	Amount of Damage	SF LF EA	Color required for VAT	Comments/Description/Notes	Attic/Crawl Space Ranking	Damage Potential (DP)	Newly Friable (NF)	Response Action (RA)
1	3	Stairwell across from Classroom 314	N/A	Concrete Ceiling		Non Suspect ACM	270	SF	0	SF				N/A	N/A	N/A
1	3	Stairwell across from Classroom 314	N/A	CMU		Non Suspect ACM	1110	SF	0	SF				N/A	N/A	N/A
1	3	Stairwell across from Classroom 314	N/A	Cement Floor		Non Suspect ACM	270	SF	0	SF				N/A	N/A	N/A
1	3	Classroom 314	N/A	Fiberglass Pipe Insulation		Non Suspect ACM	9	LF	0	LF				N/A	N/A	N/A
1	3	Classroom 314	N/A	Concrete Ceiling		Non Suspect ACM	972	SF	0	SF				N/A	N/A	N/A
1	3	Classroom 314	N/A	CMU		Non Suspect ACM	1260	SF	0	SF				N/A	N/A	N/A
1	3	Classroom 314	M	Transite Closet	8390/01/03/17	Assumed	54	SF	0	SF				1	No	1/D
1	3	Classroom 314	M	Floor Tile VAT 9" x 9"	8390/01/03/21	Confirmed	885	SF	0	SF	Grey			1	No	1/D
1	3	Classroom 314	M	Floor Tile VAT 9" x 9"	8390/01/03/21	Confirmed	47	SF	0	SF	Green			1	No	1/D
1	3	Classroom 314	M	Floor Tile VAT 12" x 12"	8390/01/03/MM	Assumed	40	SF	0	SF	Tan			1	No	1/D
1	3	Classroom 303	N/A	Concrete Ceiling		Non Suspect ACM	972	SF	0	SF				N/A	N/A	N/A
1	3	Classroom 303	N/A	CMU		Non Suspect ACM	1260	SF	0	SF				N/A	N/A	N/A
1	3	Classroom 303	M	Transite Closet	8390/01/03/17	Assumed	54	SF	1	SF		Less than 1 SF: Cracked.		1	Yes	5/C
1	3	Classroom 303	M	Floor Tile VAT 9" x 9"	8390/01/03/21	Confirmed	923	SF	0	SF	Tan			1	No	1/D
1	3	Classroom 303	M	Floor Tile VAT 9" x 9"	8390/01/03/21	Confirmed	49	SF	0	SF	Brown			1	No	1/D
1	3	Classroom 316	N/A	Concrete Ceiling		Non Suspect ACM	972	SF	0	SF				N/A	N/A	N/A
1	3	Classroom 316	N/A	CMU		Non Suspect ACM	1260	SF	0	SF				N/A	N/A	N/A
1	3	Classroom 316	M	Transite Closet	8390/01/03/17	Assumed	54	SF	0	SF				1	No	1/D
1	3	Classroom 316	M	Floor Tile VAT 9" x 9"	8390/01/03/21	Confirmed	906	SF	0	SF	Grey			1	No	1/D
1	3	Classroom 316	M	Floor Tile VAT 9" x 9"	8390/01/03/21	Confirmed	48	SF	0	SF	Green			1	No	1/D
1	3	Classroom 316	M	Floor Tile VAT 12" x 12"	8390/01/03/MM	Assumed	18	SF	0	SF	Tan			1	No	1/D
1	3	Classroom 305	N/A	Concrete Ceiling		Non Suspect ACM	972	SF	0	SF				N/A	N/A	N/A
1	3	Classroom 305	N/A	CMU		Non Suspect ACM	1260	SF	0	SF				N/A	N/A	N/A
1	3	Classroom 305	M	Transite Closet	8390/01/03/17	Assumed	54	SF	0	SF				1	No	1/D
1	3	Classroom 305	M	Floor Tile VAT 9" x 9"	8390/01/03/21	Confirmed	923	SF	0	SF	Tan			1	No	1/D
1	3	Classroom 305	M	Floor Tile VAT 9" x 9"	8390/01/03/21	Confirmed	49	SF	0	SF	Brown			1	No	1/D
1	3	Classroom 318	N/A	Fiberglass Pipe Insulation		Non Suspect ACM	8	LF	1	LF				N/A	N/A	N/A
1	3	Classroom 318	N/A	Concrete Ceiling		Non Suspect ACM	972	SF	0	SF				N/A	N/A	N/A
1	3	Classroom 318	N/A	CMU		Non Suspect ACM	1260	SF	0	SF				N/A	N/A	N/A
1	3	Classroom 318	M	Transite Closet	8390/01/03/17	Assumed	54	SF	0	SF				1	No	1/D
1	3	Classroom 318	M	Floor Tile VAT 9" x 9"	8390/01/03/21	Confirmed	885	SF	0	SF	Grey			1	No	1/D
1	3	Classroom 318	M	Floor Tile VAT 9" x 9"	8390/01/03/21	Confirmed	47	SF	0	SF	Green			1	No	1/D
1	3	Classroom 318	M	Floor Tile VAT 12" x 12"	8390/01/03/MM	Assumed	40	SF	0	SF	Tan			1	No	1/D
1	3	Classroom 307 (Special Education)	N/A	Concrete Ceiling		Non Suspect ACM	600	SF	0	SF				N/A	N/A	N/A
1	3	Classroom 307 (Special Education)	N/A	CMU		Non Suspect ACM	980	SF	0	SF				N/A	N/A	N/A
1	3	Classroom 307 (Special Education)	M	Floor Tile VAT 9" x 9"	8390/01/03/21	Confirmed	570	SF	0	SF	Tan			1	No	1/D
1	3	Classroom 307 (Special Education)	M	Floor Tile VAT 9" x 9"	8390/01/03/21	Confirmed	30	SF	0	SF	Brown			1	No	1/D
1	3	Hallway from Classrooms 310 to 318	N/A	Concrete Ceiling		Non Suspect ACM	1638	SF	0	SF				N/A	N/A	N/A
1	3	Hallway from Classrooms 310 to 318	N/A	CMU		Non Suspect ACM	3730	SF	0	SF				N/A	N/A	N/A
1	3	Hallway from Classrooms 310 to 318	M	Floor Tile VAT 12" x 12"	8390/01/03/MM	Assumed	1310	SF	0	SF	Tan			1	No	1/D
1	3	Hallway from Classrooms 310 to 318	M	Floor Tile VAT 12" x 12"	8390/01/03/MM	Assumed	328	SF	0	SF	Brown			1	No	1/D
1	3	Stairwell near Classrooms 307 and 318	T	Pipe Fitting Insulation	8390/01/03/09	Confirmed	4	EA	2	EA		(2) PFI Duct Taped.		1	Yes	5/A
1	3	Stairwell near Classrooms 307 and 318	N/A	Concrete Ceiling		Non Suspect ACM	270	SF	0	SF				N/A	N/A	N/A
1	3	Stairwell near Classrooms 307 and 318	N/A	CMU		Non Suspect ACM	1110	SF	0	SF				N/A	N/A	N/A
1	3	Stairwell near Classrooms 307 and 318	N/A	Cement Floor		Non Suspect ACM	270	SF	0	SF				N/A	N/A	N/A
2	1	Classroom 11	N/A	Concrete Ceiling		Non Suspect ACM	1080	SF	0	SF				N/A	N/A	N/A
2	1	Classroom 11	N/A	Concrete Block Wall		Non Suspect ACM	960	SF	0	SF				N/A	N/A	N/A
2	1	Classroom 11	N/A	Sheetrock Wall		Non Suspect ACM	425	SF	0	SF				N/A	N/A	N/A
2	1	Classroom 11	M	Floor Tile VAT 12" x 12"	8390/02/01/TT	Assumed	1080	SF	0	SF	Grey			1	No	1/D
2	1	Classroom 11 Closet/Storage	N/A	Concrete Ceiling		Non Suspect ACM	32	SF	0	SF				N/A	N/A	N/A
2	1	Classroom 11 Closet/Storage	N/A	Concrete Block Wall		Non Suspect ACM	144	SF	0	SF				N/A	N/A	N/A
2	1	Classroom 11 Closet/Storage	N/A	Sheetrock Wall		Non Suspect ACM	100	SF	0	SF				N/A	N/A	N/A
2	1	Classroom 11 Closet/Storage	M	Floor Tile VAT 9" x 9"	8390/02/01/24	Confirmed	32	SF	0	SF	Tan			1	No	1/D
2	1	Classroom 11 Office Cubby	N/A	Concrete Ceiling		Non Suspect ACM	56	SF	0	SF				N/A	N/A	N/A
2	1	Classroom 11 Office Cubby	N/A	Concrete Block Wall		Non Suspect ACM	96	SF	0	SF				N/A	N/A	N/A
2	1	Classroom 11 Office Cubby	N/A	Sheetrock Wall		Non Suspect ACM	160	SF	0	SF				N/A	N/A	N/A
2	1	Classroom 11 Office Cubby	M	Floor Tile VAT 12" x 12"	8390/02/01/TT	Assumed	56	SF	0	SF	Grey			1	No	1/D
2	1	Classroom 11 Restroom	N/A	Concrete Ceiling		Non Suspect ACM	48	SF	0	SF				N/A	N/A	N/A
2	1	Classroom 11 Restroom	N/A	Concrete Block Wall		Non Suspect ACM	96	SF	0	SF				N/A	N/A	N/A
2	1	Classroom 11 Restroom	N/A	Sheetrock Wall		Non Suspect ACM	242	SF	0	SF				N/A	N/A	N/A
2	1	Classroom 11 Restroom	M	Floor Tile VAT 12" x 12"	8390/02/01/TT	Assumed	48	SF	0	SF	Tan			1	No	1/D
2	1	Kitchen	N/A	Concrete Ceiling		Non Suspect ACM	272	SF	0	SF		Renovated into a Kitchen in 2014 per Building Engineer		N/A	N/A	N/A
2	1	Kitchen	N/A	Concrete Block Wall		Non Suspect ACM	396	SF	0	SF		Renovated into a Kitchen in 2014 per Building Engineer		N/A	N/A	N/A
2	1	Kitchen	N/A	Sheetrock Wall		Non Suspect ACM	316	SF	0	SF		Renovated into a Kitchen in 2014 per Building Engineer		N/A	N/A	N/A
2	1	Kitchen	M	Floor Tile VAT 12" x 12"	8390/02/01/TT	Assumed	272	SF	0	SF	Tan	Renovated into a Kitchen in 2014 per Building Engineer		1	No	1/D
2	1	Lobby Entrance to Kitchen and Classroom 12A	N/A	Concrete Ceiling		Non Suspect ACM	88	SF	0	SF		Renovated into Lobby in 2014 per Building Engineer		N/A	N/A	N/A
2	1	Lobby Entrance to Kitchen and Classroom 12A	N/A	Concrete Block Wall		Non Suspect ACM	160	SF	0	SF		Renovated into Lobby in 2014 per Building Engineer		N/A	N/A	N/A
2	1	Lobby Entrance to Kitchen and Classroom 12A	N/A	Sheetrock Wall		Non Suspect ACM	134	SF	0	SF		Renovated into Lobby in 2014 per Building Engineer		N/A	N/A	N/A

# 8390 Aloysius Fitzpatrick ES 2015 2016 AHERA Three-Year Report.xls

School District of Philadelphia			AHERA Three-Year Reinspection 2015-2016										Reinspection Date: 11/20/2015							
Aloysius L. Fitzpatrick Elementary School			Room by Room Location Log Report										Building Inspector: Paul Davis							
11061 Knights Road, Philadelphia, PA, 19154													Number: 050368							
ULCS# 8390													Management Planner: Megan Vala							
Year Built: 1960													Number: 740728							
Element	Floor	On Site Room Name	System Affected	Material Description	HID#	Confirmed/Assumed/NAD/Non Suspect ACM	Amount of Material	SF	LF	EA	Amount of Damage	SF	LF	EA	Color required for VAT	Comments/Description/Notes	Attic/Crawl Space Ranking	Damage Potential (DP)	Newly Friable (NF)	Response Action (RA)
2	1	Lobby Entrance to Kitchen and Classroom 12A	M	Floor Tile VAT 12" x 12"	8390/02/01/TT	Assumed	88	SF	0	SF						Renovated into Lobby in 2014 per Building Engineer		1	No	1/D
2	1	Classroom 12A	N/A	Concrete Ceiling		Non Suspect ACM	1053	SF	0	SF						Renovated in 2014 per Building Engineer.		N/A	N/A	N/A
2	1	Classroom 12A	N/A	Concrete Block Wall		Non Suspect ACM	936	SF	0	SF						Renovated in 2014 per Building Engineer.		N/A	N/A	N/A
2	1	Classroom 12A	N/A	Sheetrock Wall		Non Suspect ACM	542	SF	0	SF						Renovated in 2014 per Building Engineer.		N/A	N/A	N/A
2	1	Classroom 12A	M	Floor Tile VAT 12" x 12"	8390/02/01/TT	Assumed	1053	SF	0	SF					Tan	Renovated in 2014 per Building Engineer.		1	No	1/D
2	1	Classroom 12A Restroom	N/A	Fiberglass Ceiling Tile 2' x 4'		Non Suspect ACM	40	SF	0	SF						Renovated in 2014 per Building Engineer.		N/A	N/A	N/A
2	1	Classroom 12A Restroom	N/A	Sheetrock Wall		Non Suspect ACM	208	SF	0	SF						Renovated in 2014 per Building Engineer.		N/A	N/A	N/A
2	1	Classroom 12A Restroom	M	Floor Tile VAT 12" x 12"	8390/02/01/TT	Assumed	40	SF	0	SF					Tan	Renovated in 2014 per Building Engineer.		1	No	1/D
2	1	Classroom 10	N/A	Concrete Ceiling		Non Suspect ACM	864	SF	0	SF								N/A	N/A	N/A
2	1	Classroom 10	N/A	Concrete Block Wall		Non Suspect ACM	768	SF	0	SF								N/A	N/A	N/A
2	1	Classroom 10	N/A	Sheetrock Wall		Non Suspect ACM	518	SF	0	SF								N/A	N/A	N/A
2	1	Classroom 10	M	Floor Tile VAT 12" x 12"	8390/02/01/TT	Assumed	864	SF	0	SF					Tan			1	No	1/D
2	1	Classroom 10 Closet/Storage	N/A	Concrete Ceiling		Non Suspect ACM	32	SF	0	SF								N/A	N/A	N/A
2	1	Classroom 10 Closet/Storage	N/A	Concrete Block Wall		Non Suspect ACM	96	SF	0	SF								N/A	N/A	N/A
2	1	Classroom 10 Closet/Storage	N/A	CMU		Non Suspect ACM	48	SF	0	SF								N/A	N/A	N/A
2	1	Classroom 10 Closet/Storage	N/A	Sheetrock Wall		Non Suspect ACM	108	SF	0	SF								N/A	N/A	N/A
2	1	Classroom 10 Closet/Storage	M	Floor Tile VAT 12" x 12"	8390/02/01/TT	Assumed	32	SF	0	SF					Tan			1	No	1/D
2	1	Classroom 10 Storage/Computer Server Room	N/A	Concrete Ceiling		Non Suspect ACM	56	SF	0	SF								N/A	N/A	N/A
2	1	Classroom 10 Storage/Computer Server Room	N/A	CMU		Non Suspect ACM	96	SF	0	SF								N/A	N/A	N/A
2	1	Classroom 10 Storage/Computer Server Room	N/A	Sheetrock Wall		Non Suspect ACM	252	SF	0	SF								N/A	N/A	N/A
2	1	Classroom 10 Storage/Computer Server Room	M	Floor Tile VAT 12" x 12"	8390/02/01/TT	Assumed	56	SF	0	SF					Tan			1	No	1/D
2	1	Classroom 10 Restroom	N/A	Concrete Ceiling		Non Suspect ACM	48	SF	0	SF								N/A	N/A	N/A
2	1	Classroom 10 Restroom	N/A	CMU		Non Suspect ACM	96	SF	0	SF								N/A	N/A	N/A
2	1	Classroom 10 Restroom	N/A	Sheetrock Wall		Non Suspect ACM	200	SF	0	SF								N/A	N/A	N/A
2	1	Classroom 10 Restroom	M	Floor Tile VAT 12" x 12"	8390/02/01/TT	Assumed	48	SF	0	SF					Tan			1	No	1/D
2	1	Classroom 9	N/A	Concrete Ceiling		Non Suspect ACM	1053	SF	0	SF								N/A	N/A	N/A
2	1	Classroom 9	N/A	CMU		Non Suspect ACM	936	SF	0	SF								N/A	N/A	N/A
2	1	Classroom 9	N/A	Sheetrock Wall		Non Suspect ACM	568	SF	0	SF								N/A	N/A	N/A
2	1	Classroom 9	M	Floor Tile VAT 12" x 12"	8390/02/01/TT	Assumed	1053	SF	0	SF					Tan			1	No	1/D
2	1	Classroom 9 Closet/Storage	N/A	Concrete Ceiling		Non Suspect ACM	32	SF	0	SF								N/A	N/A	N/A
2	1	Classroom 9 Closet/Storage	N/A	CMU		Non Suspect ACM	48	SF	0	SF								N/A	N/A	N/A
2	1	Classroom 9 Closet/Storage	N/A	Concrete Block Wall		Non Suspect ACM	96	SF	0	SF								N/A	N/A	N/A
2	1	Classroom 9 Closet/Storage	N/A	Sheetrock Wall		Non Suspect ACM	92	SF	0	SF								N/A	N/A	N/A
2	1	Classroom 9 Closet/Storage	M	Floor Tile VAT 12" x 12"	8390/02/01/TT	Assumed	32	SF	0	SF					Tan			1	No	1/D
2	1	Classroom 9 Storage	N/A	Concrete Ceiling		Non Suspect ACM	56	SF	0	SF								N/A	N/A	N/A
2	1	Classroom 9 Storage	N/A	CMU		Non Suspect ACM	84	SF	0	SF								N/A	N/A	N/A
2	1	Classroom 9 Storage	N/A	Sheetrock Wall		Non Suspect ACM	233	SF	0	SF								N/A	N/A	N/A
2	1	Classroom 9 Storage	M	Floor Tile VAT 12" x 12"	8390/02/01/TT	Assumed	56	SF	0	SF					Tan			1	No	1/D
2	1	Classroom 9 Restroom	N/A	Concrete Ceiling		Non Suspect ACM	48	SF	0	SF								N/A	N/A	N/A
2	1	Classroom 9 Restroom	N/A	CMU		Non Suspect ACM	72	SF	0	SF								N/A	N/A	N/A
2	1	Classroom 9 Restroom	N/A	Sheetrock Wall		Non Suspect ACM	237	SF	0	SF								N/A	N/A	N/A
2	1	Classroom 9 Restroom	M	Floor Tile VAT 12" x 12"	8390/02/01/TT	Assumed	48	SF	0	SF					Tan			1	No	1/D
2	1	Annex Hallway from Classrooms 9 to 11	N/A	Concrete Ceiling		Non Suspect ACM	1030	SF	0	SF								N/A	N/A	N/A
2	1	Annex Hallway from Classrooms 9 to 11	N/A	Concrete Block Wall		Non Suspect ACM	2472	SF	0	SF								N/A	N/A	N/A
2	1	Annex Hallway from Classrooms 9 to 11	N/A	Sheetrock Wall		Non Suspect ACM	137	SF	0	SF								N/A	N/A	N/A
2	1	Annex Hallway from Classrooms 9 to 11	M	Floor Tile VAT 9" x 9"	8390/02/01/24	Confirmed	310	SF	0	SF					Brown			1	No	1/D
2	1	Annex Hallway from Classrooms 9 to 11	M	Floor Tile VAT 12" x 12"	8390/02/01/TT	Assumed	720	SF	0	SF					Tan			1	No	1/D
2	1	Electrical Room and Water Supply Room	N/A	Concrete Ceiling		Non Suspect ACM	133	SF	0	SF								N/A	N/A	N/A
2	1	Electrical Room and Water Supply Room	N/A	CMU		Non Suspect ACM	540	SF	0	SF								N/A	N/A	N/A
2	1	Electrical Room and Water Supply Room	N/A	Sheetrock Wall		Non Suspect ACM	63	SF	0	SF								N/A	N/A	N/A
2	1	Electrical Room and Water Supply Room	N/A	Cement Floor		Non Suspect ACM	133	SF	0	SF								N/A	N/A	N/A
2	1	Annex Hallway from Electrical Room to Schoolyard	N/A	Fiberglass Ceiling Tile 2' x 4'		Non Suspect ACM	196	SF	0	SF								N/A	N/A	N/A
2	1	Annex Hallway from Electrical Room to Schoolyard	N/A	Concrete Block Wall		Non Suspect ACM	448	SF	0	SF								N/A	N/A	N/A
2	1	Annex Hallway from Electrical Room to Schoolyard	M	Floor Tile VAT 12" x 12"	8390/02/01/TT	Assumed	196	SF	0	SF					Tan			1	No	1/D
2	1	Conference Room	N/A	Fiberglass Ceiling Tile 2' x 4'		Non Suspect ACM	1053	SF	0	SF								N/A	N/A	N/A
2	1	Conference Room	N/A	Concrete Block Wall		Non Suspect ACM	700	SF	0	SF								N/A	N/A	N/A
2	1	Conference Room	N/A	Sheetrock Wall		Non Suspect ACM	454	SF	0	SF								N/A	N/A	N/A
2	1	Conference Room	M	Floor Tile VAT 12" x 12"	8390/02/01/TT	Assumed	432	SF	0	SF					Grey			1	No	1/D
2	1	Conference Room	N/A	Carpet		Non Suspect ACM	621	SF	0	SF								N/A	N/A	N/A
2	1	Conference Room Kitchenette	N/A	Fiberglass Ceiling Tile 2' x 4'		Non Suspect ACM	48	SF	0	SF								N/A	N/A	N/A
2	1	Conference Room Kitchenette	N/A	CMU		Non Suspect ACM	54	SF	0	SF								N/A	N/A	N/A
2	1	Conference Room Kitchenette	N/A	Sheetrock Wall		Non Suspect ACM	180	SF	0	SF								N/A	N/A	N/A
2	1	Conference Room Kitchenette	M	Floor Tile VAT 12" x 12"	8390/02/01/TT	Assumed	48	SF	0	SF					Grey			1	No	1/D
2	1	Conference Room Restroom	N/A	Fiberglass Ceiling Tile 2' x 4'		Non Suspect ACM	56	SF	0	SF								N/A	N/A	N/A
2	1	Conference Room Restroom	N/A	CMU		Non Suspect ACM	63	SF	0	SF								N/A	N/A	N/A
2	1	Conference Room Restroom	N/A	Sheetrock Wall		Non Suspect ACM	189	SF	0	SF								N/A	N/A	N/A
2	1	Conference Room Restroom	M	Floor Tile VAT 12" x 12"	8390/02/01/TT	Assumed	56	SF	0	SF					Pink			1	No	1/D
2	1	Conference Room Closet/Storage	N/A	Concrete Ceiling		Non Suspect ACM	32	SF	0	SF								N/A	N/A	N/A
2	1	Conference Room Closet/Storage	N/A	CMU		Non Suspect ACM	48	SF	0	SF								N/A	N/A	N/A
2	1	Conference Room Closet/Storage	N/A	Concrete Block Wall		Non Suspect ACM	48	SF	0	SF								N/A	N/A	N/A
2	1	Conference Room Closet/Storage	N/A	Sheetrock Wall		Non Suspect ACM	128	SF	0	SF								N/A	N/A	N/A
2	1	Conference Room Closet/Storage	M	Floor Tile VAT 12" x 12"	8390/02/01/TT	Assumed	12	SF	0	SF					Pink			1	No	1/D



# 8390 Aloysius Fitzpatrick ES 2015 2016 AHERA Three-Year Report.xls

School District of Philadelphia			AHERA Three-Year Reinspection 2015-2016										Reinspection Date: 11/20/2015							
Aloysius L. Fitzpatrick Elementary School			Room by Room Location Log Report										Building Inspector: Paul Davis							
11061 Knights Road, Philadelphia, PA, 19154													Number: 050368							
ULCS# 8390													Management Planner: Megan Vala							
Year Built: 1960													Number: 740728							
Element	Floor	On Site Room Name	System Affected	Material Description	HID#	Confirmed/Assumed/NAD/Non Suspect ACM	Amount of Material	SF	LF	EA	Amount of Damage	SF	LF	EA	Color required for VAT	Comments/Description/Notes	Attic/Crawl Space Ranking	Damage Potential (DP)	Newly Friable (NF)	Response Action (RA)
2	1	Conference Room Closet/Storage	N/A	Cement Floor		Non Suspect ACM	20	SF	0	SF								N/A	N/A	N/A
2	1	Parent Workshop Room	N/A	Fiberglass Ceiling Tile 2' x 4'		Non Suspect ACM	459	SF	0	SF								N/A	N/A	N/A
2	1	Parent Workshop Room	N/A	Concrete Block Wall		Non Suspect ACM	486	SF	0	SF								N/A	N/A	N/A
2	1	Parent Workshop Room	N/A	Sheetrock Wall		Non Suspect ACM	454	SF	0	SF								N/A	N/A	N/A
2	1	Parent Workshop Room	N/A	Carpet		Non Suspect ACM	459	SF	0	SF								N/A	N/A	N/A
2	1	Parent Workshop Room Closet/Storage	N/A	Concrete Ceiling		Non Suspect ACM	32	SF	0	SF								N/A	N/A	N/A
2	1	Parent Workshop Room Closet/Storage	N/A	CMU		Non Suspect ACM	48	SF	0	SF								N/A	N/A	N/A
2	1	Parent Workshop Room Closet/Storage	N/A	Concrete Block Wall		Non Suspect ACM	96	SF	0	SF								N/A	N/A	N/A
2	1	Parent Workshop Room Closet/Storage	N/A	Sheetrock Wall		Non Suspect ACM	112	SF	0	SF								N/A	N/A	N/A
2	1	Parent Workshop Room Closet/Storage	M	Floor Tile VAT 12" x 12"	8390/02/01/TT	Assumed	32	SF	0	SF					Pink			1	No	1/D
2	1	Parent Workshop Room Women's Restroom	N/A	Fiberglass Ceiling Tile 2' x 4'		Non Suspect ACM	56	SF	0	SF								N/A	N/A	N/A
2	1	Parent Workshop Room Women's Restroom	N/A	CMU		Non Suspect ACM	63	SF	0	SF								N/A	N/A	N/A
2	1	Parent Workshop Room Women's Restroom	N/A	Sheetrock Wall		Non Suspect ACM	185	SF	0	SF								N/A	N/A	N/A
2	1	Parent Workshop Room Women's Restroom	M	Floor Tile VAT 12" x 12"	8390/02/01/TT	Assumed	56	SF	0	SF					Pink			1	No	1/D
2	1	Parent Workshop Room Men's Restroom	N/A	Fiberglass Ceiling Tile 2' x 4'		Non Suspect ACM	48	SF	0	SF								N/A	N/A	N/A
2	1	Parent Workshop Room Men's Restroom	N/A	CMU		Non Suspect ACM	54	SF	0	SF								N/A	N/A	N/A
2	1	Parent Workshop Room Men's Restroom	N/A	Sheetrock Wall		Non Suspect ACM	177	SF	0	SF								N/A	N/A	N/A
2	1	Parent Workshop Room Men's Restroom	M	Floor Tile VAT 12" x 12"	8390/02/01/TT	Assumed	48	SF	0	SF					Pink			1	No	1/D
2	1	Assistant Superintendent's Office (Region 8)	N/A	Fiberglass Ceiling Tile 2' x 4'		Non Suspect ACM	648	SF	0	SF								N/A	N/A	N/A
2	1	Assistant Superintendent's Office (Region 8)	N/A	Concrete Block Wall		Non Suspect ACM	104	SF	0	SF								N/A	N/A	N/A
2	1	Assistant Superintendent's Office (Region 8)	N/A	Sheetrock Wall		Non Suspect ACM	660	SF	0	SF								N/A	N/A	N/A
2	1	Assistant Superintendent's Office (Region 8)	N/A	Carpet		Non Suspect ACM	648	SF	0	SF								N/A	N/A	N/A
2	1	Area 6 - General Office Space in Corner (Hallway Side)	N/A	Fiberglass Ceiling Tile 2' x 4'		Non Suspect ACM	208	SF	0	SF						Room (Area) 6 was modified with the addition of offices		N/A	N/A	N/A
2	1	Area 6 - General Office Space in Corner (Hallway Side)	N/A	Concrete Block Wall		Non Suspect ACM	144	SF	0	SF						Room (Area) 6 was modified with the addition of offices		N/A	N/A	N/A
2	1	Area 6 - General Office Space in Corner (Hallway Side)	N/A	Sheetrock Wall		Non Suspect ACM	378	SF	0	SF						Room (Area) 6 was modified with the addition of offices		N/A	N/A	N/A
2	1	Area 6 - General Office Space in Corner (Hallway Side)	N/A	Carpet		Non Suspect ACM	208	SF	0	SF						Room (Area) 6 was modified with the addition of offices		N/A	N/A	N/A
2	1	Area 6 - General Office Space next to Entrance	N/A	Fiberglass Ceiling Tile 2' x 4'		Non Suspect ACM	160	SF	0	SF						Room (Area) 6 was modified with the addition of offices		N/A	N/A	N/A
2	1	Area 6 - General Office Space next to Entrance	N/A	Concrete Block Wall		Non Suspect ACM	144	SF	0	SF						Room (Area) 6 was modified with the addition of offices		N/A	N/A	N/A
2	1	Area 6 - General Office Space next to Entrance	N/A	Sheetrock Wall		Non Suspect ACM	324	SF	0	SF						Room (Area) 6 was modified with the addition of offices		N/A	N/A	N/A
2	1	Area 6 - General Office Space next to Entrance	N/A	Carpet		Non Suspect ACM	160	SF	0	SF						Room (Area) 6 was modified with the addition of offices		N/A	N/A	N/A
2	1	Area 6 Restroom by Entrance	N/A	Fiberglass Ceiling Tile 2' x 4'		Non Suspect ACM	48	SF	0	SF						Room (Area) 6 was modified with the addition of offices		N/A	N/A	N/A
2	1	Area 6 Restroom by Entrance	N/A	Concrete Block Wall		Non Suspect ACM	54	SF	0	SF						Room (Area) 6 was modified with the addition of offices		N/A	N/A	N/A
2	1	Area 6 Restroom by Entrance	N/A	Sheetrock Wall		Non Suspect ACM	180	SF	0	SF						Room (Area) 6 was modified with the addition of offices		N/A	N/A	N/A
2	1	Area 6 Restroom by Entrance	M	Floor Tile VAT 12" x 12"	8390/02/01/TT	Assumed	48	SF	0	SF					Tan	Room (Area) 6 was modified with the addition of offices		1	No	1/D
2	1	Area 6 Restroom next to Storage	N/A	Fiberglass Ceiling Tile 2' x 4'		Non Suspect ACM	56	SF	0	SF						Room (Area) 6 was modified with the addition of offices		N/A	N/A	N/A
2	1	Area 6 Restroom next to Storage	N/A	Concrete Block Wall		Non Suspect ACM	63	SF	0	SF						Room (Area) 6 was modified with the addition of offices		N/A	N/A	N/A
2	1	Area 6 Restroom next to Storage	N/A	Sheetrock Wall		Non Suspect ACM	180	SF	0	SF						Room (Area) 6 was modified with the addition of offices		N/A	N/A	N/A
2	1	Area 6 Restroom next to Storage	M	Floor Tile VAT 12" x 12"	8390/02/01/TT	Assumed	56	SF	0	SF					Tan	Room (Area) 6 was modified with the addition of offices		1	No	1/D
2	1	Area 6 Storage	N/A	Concrete Ceiling		Non Suspect ACM	32	SF	0	SF						Room (Area) 6 was modified with the addition of offices		N/A	N/A	N/A
2	1	Area 6 Storage	N/A	Concrete Block Wall		Non Suspect ACM	144	SF	0	SF						Room (Area) 6 was modified with the addition of offices		N/A	N/A	N/A
2	1	Area 6 Storage	N/A	Sheetrock Wall		Non Suspect ACM	108	SF	0	SF						Room (Area) 6 was modified with the addition of offices		N/A	N/A	N/A
2	1	Area 6 Storage	M	Floor Tile VAT 12" x 12"	8390/02/01/TT	Assumed	32	SF	0	SF					Tan	Room (Area) 6 was modified with the addition of offices		1	No	1/D
2	1	Area 6 - General Office Space between Storage and Copy Area	N/A	Fiberglass Ceiling Tile 2' x 4'		Non Suspect ACM	150	SF	0	SF						Room (Area) 6 was modified with the addition of offices		N/A	N/A	N/A
2	1	Area 6 - General Office Space between Storage and Copy Area	N/A	Concrete Block Wall		Non Suspect ACM	36	SF	0	SF						Room (Area) 6 was modified with the addition of offices		N/A	N/A	N/A
2	1	Area 6 - General Office Space between Storage and Copy Area	N/A	Sheetrock Wall		Non Suspect ACM	279	SF	0	SF						Room (Area) 6 was modified with the addition of offices		N/A	N/A	N/A
2	1	Area 6 - General Office Space between Storage and Copy Area	N/A	Carpet		Non Suspect ACM	150	SF	0	SF						Room (Area) 6 was modified with the addition of offices		N/A	N/A	N/A
2	1	Area 6 - Copy/Fax Area	N/A	Fiberglass Ceiling Tile 2' x 4'		Non Suspect ACM	80	SF	0	SF						Room (Area) 6 was modified with the addition of offices		N/A	N/A	N/A
2	1	Area 6 - Copy/Fax Area	N/A	Concrete Block Wall		Non Suspect ACM	24	SF	0	SF						Room (Area) 6 was modified with the addition of offices		N/A	N/A	N/A
2	1	Area 6 - Copy/Fax Area	N/A	Sheetrock Wall		Non Suspect ACM	216	SF	0	SF						Room (Area) 6 was modified with the addition of offices		N/A	N/A	N/A

# 8390 Aloysius Fitzpatrick ES 2015 2016 AHERA Three-Year Report.xls

School District of Philadelphia Aloysius L. Fitzpatrick Elementary School 11061 Knights Road, Philadelphia, PA, 19154 ULCS# 8390 Year Built: 1960			AHERA Three-Year Reinspection 2015-2016 Room by Room Location Log Report										Reinspection Date: 11/20/2015 Building Inspector: Paul Davis Number: 050368 Management Planner: Megan Vala Number: 740728							
			Element	Floor																
On Site Room Name			System Affected	Material Description	HID#	Confirmed/Assumed/NAD/Non Suspect ACM	Amount of Material	SF LF EA	Amount of Damage	SF LF EA	Color required for VAT	Comments/Description/Notes	Attic/Crawl Space Ranking	Damage Potential (DP)	Newly Friable (NF)	Response Action (RA)				
2	1	Area 6 - Copy/Fax Area	M	Floor Tile VAT 12" x 12"	8390/02/01/TT	Assumed	80	SF	0	SF	Tan	Room (Area) 6 was modified with the addition of offices		1	No	1/D				
2	1	Area 6 - General Office Space in Corner (Window Side)	N/A	Fiberglass Ceiling Tile 2' x 4'		Non Suspect ACM	208	SF	0	SF		Room (Area) 6 was modified with the addition of offices		N/A	N/A	N/A				
2	1	Area 6 - General Office Space in Corner (Window Side)	N/A	Concrete Block Wall		Non Suspect ACM	95	SF	0	SF		Room (Area) 6 was modified with the addition of offices		N/A	N/A	N/A				
2	1	Area 6 - General Office Space in Corner (Window Side)	N/A	Sheetrock Wall		Non Suspect ACM	378	SF	0	SF		Room (Area) 6 was modified with the addition of offices		N/A	N/A	N/A				
2	1	Area 6 - General Office Space in Corner (Window Side)	N/A	Carpet		Non Suspect ACM	208	SF	0	SF		Room (Area) 6 was modified with the addition of offices		N/A	N/A	N/A				
2	1	Area 6 - Hallway	N/A	Fiberglass Ceiling Tile 2' x 4'		Non Suspect ACM	314	SF	0	SF		Room (Area) 6 was modified with the addition of offices		N/A	N/A	N/A				
2	1	Area 6 - Hallway	N/A	Concrete Block Wall		Non Suspect ACM	144	SF	0	SF		Room (Area) 6 was modified with the addition of offices		N/A	N/A	N/A				
2	1	Area 6 - Hallway	N/A	Sheetrock Wall		Non Suspect ACM	656	SF	0	SF		Room (Area) 6 was modified with the addition of offices		N/A	N/A	N/A				
2	1	Area 6 - Hallway	M	Floor Tile VAT 12" x 12"	8390/02/01/TT	Assumed	314	SF	0	SF	Tan	Room (Area) 6 was modified with the addition of offices		1	No	1/D				
2	1	Area 5 - General Office Space in Corner (Hallway Side)	N/A	Fiberglass Ceiling Tile 2' x 4'		Non Suspect ACM	144	SF	0	SF		Room (Area) 5 was modified with the addition of offices		N/A	N/A	N/A				
2	1	Area 5 - General Office Space in Corner (Hallway Side)	N/A	Concrete Block Wall		Non Suspect ACM	81	SF	0	SF		Room (Area) 5 was modified with the addition of offices		N/A	N/A	N/A				
2	1	Area 5 - General Office Space in Corner (Hallway Side)	N/A	Sheetrock Wall		Non Suspect ACM	324	SF	0	SF		Room (Area) 5 was modified with the addition of offices		N/A	N/A	N/A				
2	1	Area 5 - General Office Space in Corner (Hallway Side)	M	Floor Tile VAT 12" x 12"	8390/02/01/TT	Assumed	144	SF	0	SF	Tan	Room (Area) 5 was modified with the addition of offices		1	No	1/D				
2	1	Area 5 - General Office Space in Center (Hallway Side)	N/A	Fiberglass Ceiling Tile 2' x 4'		Non Suspect ACM	144	SF	0	SF		Room (Area) 5 was modified with the addition of offices		N/A	N/A	N/A				
2	1	Area 5 - General Office Space in Center (Hallway Side)	N/A	Concrete Block Wall		Non Suspect ACM	108	SF	0	SF		Room (Area) 5 was modified with the addition of offices		N/A	N/A	N/A				
2	1	Area 5 - General Office Space in Center (Hallway Side)	N/A	Sheetrock Wall		Non Suspect ACM	303	SF	0	SF		Room (Area) 5 was modified with the addition of offices		N/A	N/A	N/A				
2	1	Area 5 - General Office Space in Center (Hallway Side)	M	Floor Tile VAT 12" x 12"	8390/02/01/TT	Assumed	144	SF	0	SF	Tan	Room (Area) 5 was modified with the addition of offices		1	No	1/D				
2	1	Area 5 - General Office Space next to Entrance	N/A	Fiberglass Ceiling Tile 2' x 4'		Non Suspect ACM	144	SF	0	SF		Room (Area) 5 was modified with the addition of offices		N/A	N/A	N/A				
2	1	Area 5 - General Office Space next to Entrance	N/A	Concrete Block Wall		Non Suspect ACM	108	SF	0	SF		Room (Area) 5 was modified with the addition of offices		N/A	N/A	N/A				
2	1	Area 5 - General Office Space next to Entrance	N/A	Sheetrock Wall		Non Suspect ACM	303	SF	0	SF		Room (Area) 5 was modified with the addition of offices		N/A	N/A	N/A				
2	1	Area 5 - General Office Space next to Entrance	M	Floor Tile VAT 12" x 12"	8390/02/01/TT	Assumed	144	SF	0	SF	Tan	Room (Area) 5 was modified with the addition of offices		1	No	1/D				
2	1	Area 5 Restroom next to Entrance	N/A	Fiberglass Ceiling Tile 2' x 4'		Non Suspect ACM	48	SF	0	SF		Room (Area) 5 was modified with the addition of offices		N/A	N/A	N/A				
2	1	Area 5 Restroom next to Entrance	N/A	Concrete Block Wall		Non Suspect ACM	54	SF	0	SF		Room (Area) 5 was modified with the addition of offices		N/A	N/A	N/A				
2	1	Area 5 Restroom next to Entrance	N/A	Sheetrock Wall		Non Suspect ACM	180	SF	0	SF		Room (Area) 5 was modified with the addition of offices		N/A	N/A	N/A				
2	1	Area 5 Restroom next to Entrance	M	Floor Tile VAT 12" x 12"	8390/02/01/TT	Assumed	48	SF	0	SF	Tan	Room (Area) 5 was modified with the addition of offices		1	No	1/D				
2	1	Area 5 Restroom next to Storage	N/A	Fiberglass Ceiling Tile 2' x 4'		Non Suspect ACM	56	SF	0	SF		Room (Area) 5 was modified with the addition of offices		N/A	N/A	N/A				
2	1	Area 5 Restroom next to Storage	N/A	Concrete Block Wall		Non Suspect ACM	63	SF	0	SF		Room (Area) 5 was modified with the addition of offices		N/A	N/A	N/A				
2	1	Area 5 Restroom next to Storage	N/A	Sheetrock Wall		Non Suspect ACM	186	SF	0	SF		Room (Area) 5 was modified with the addition of offices		N/A	N/A	N/A				
2	1	Area 5 Restroom next to Storage	M	Floor Tile VAT 12" x 12"	8390/02/01/TT	Assumed	56	SF	0	SF	Tan	Room (Area) 5 was modified with the addition of offices		1	No	1/D				
2	1	Area 5 Storage	N/A	Concrete Ceiling		Non Suspect ACM	32	SF	0	SF		Room (Area) 5 was modified with the addition of offices		N/A	N/A	N/A				
2	1	Area 5 Storage	N/A	Concrete Block Wall		Non Suspect ACM	144	SF	0	SF		Room (Area) 5 was modified with the addition of offices		N/A	N/A	N/A				
2	1	Area 5 Storage	N/A	Sheetrock Wall		Non Suspect ACM	104	SF	0	SF		Room (Area) 5 was modified with the addition of offices		N/A	N/A	N/A				
2	1	Area 5 Storage	M	Floor Tile VAT 12" x 12"	8390/02/01/TT	Assumed	32	SF	0	SF	Tan	Room (Area) 5 was modified with the addition of offices		1	No	1/D				
2	1	Area 5 - General Office Space between Storage and Copy Area	N/A	Fiberglass Ceiling Tile 2' x 4'		Non Suspect ACM	150	SF	0	SF		Room (Area) 5 was modified with the addition of offices		N/A	N/A	N/A				
2	1	Area 5 - General Office Space between Storage and Copy Area	N/A	Concrete Block Wall		Non Suspect ACM	39	SF	0	SF		Room (Area) 5 was modified with the addition of offices		N/A	N/A	N/A				
2	1	Area 5 - General Office Space between Storage and Copy Area	N/A	Sheetrock Wall		Non Suspect ACM	245	SF	0	SF		Room (Area) 5 was modified with the addition of offices		N/A	N/A	N/A				
2	1	Area 5 - General Office Space between Storage and Copy Area	M	Floor Tile VAT 12" x 12"	8390/02/01/TT	Assumed	150	SF	0	SF	Tan	Room (Area) 5 was modified with the addition of offices		1	No	1/D				
2	1	Area 5 - Copy/Fax Area	N/A	Fiberglass Ceiling Tile 2' x 4'		Non Suspect ACM	80	SF	0	SF		Room (Area) 5 was modified with the addition of offices		N/A	N/A	N/A				
2	1	Area 5 - Copy/Fax Area	N/A	Concrete Block Wall		Non Suspect ACM	24	SF	0	SF		Room (Area) 5 was modified with the addition of offices		N/A	N/A	N/A				

# 8390 Aloysius Fitzpatrick ES 2015 2016 AHERA Three-Year Report.xls

		School District of Philadelphia Aloysius L. Fitzpatrick Elementary School 11061 Knights Road, Philadelphia, PA, 19154 ULCS# 8390 Year Built: 1960	AHERA Three-Year Reinspection 2015-2016 Room by Room Location Log Report										Reinspection Date: 11/20/2015 Building Inspector: Paul Davis Number: 050368 Management Planner: Megan Vala Number: 740728					
E l e m e n t	F l o o r	On Site Room Name	System Affected	Material Description	HID#	Confirmed/Assumed/NAD/ Non Suspect ACM	Amount of Material	SF	LF EA	Amount of Damage	SF	LF EA	Color required for VAT	Comments/Description/Notes	Attic/ Crawl Space Ranking	Damage Potential (DP)	Newly Friable (NF)	Response Action (RA)
2	1	Area 5 - Copy/Fax Area	N/A	Sheetrock Wall		Non Suspect ACM	216	SF		0		SF		Room (Area) 5 was modified with the addition of offices		N/A	N/A	N/A
2	1	Area 5 - Copy/Fax Area	M	Floor Tile VAT 12" x 12"	8390/02/01/TT	Assumed	80	SF		0		SF	Tan	Room (Area) 5 was modified with the addition of offices		1	No	1/D
2	1	Area 5 - General Office Space in Corner next to Copy Area	N/A	Fiberglass Ceiling Tile 2' x 4'		Non Suspect ACM	120	SF		0		SF		Room (Area) 5 was modified with the addition of offices		N/A	N/A	N/A
2	1	Area 5 - General Office Space in Corner next to Copy Area	N/A	Concrete Block Wall		Non Suspect ACM	66	SF		0		SF		Room (Area) 5 was modified with the addition of offices		N/A	N/A	N/A
2	1	Area 5 - General Office Space in Corner next to Copy Area	N/A	Sheetrock Wall		Non Suspect ACM	222	SF		0		SF		Room (Area) 5 was modified with the addition of offices		N/A	N/A	N/A
2	1	Area 5 - General Office Space in Corner next to Copy Area	M	Floor Tile VAT 12" x 12"	8390/02/01/TT	Assumed	120	SF		0		SF	Tan	Room (Area) 5 was modified with the addition of offices		1	No	1/D
2	1	Area 5 - Hallway	N/A	Fiberglass Ceiling Tile 2' x 4'		Non Suspect ACM	254	SF		0		SF		Room (Area) 5 was modified with the addition of offices		N/A	N/A	N/A
2	1	Area 5 - Hallway	N/A	Sheetrock Wall		Non Suspect ACM	712	SF		0		SF		Room (Area) 5 was modified with the addition of offices		N/A	N/A	N/A
2	1	Area 5 - Hallway	M	Floor Tile VAT 12" x 12"	8390/02/01/TT	Assumed	254	SF		0		SF	Tan	Room (Area) 5 was modified with the addition of offices		1	No	1/D
2	1	Annex Hallway from Office Suites to Conference Room	N/A	Concrete Ceiling		Non Suspect ACM	950	SF		0		SF				N/A	N/A	N/A
2	1	Annex Hallway from Office Suites to Conference Room	N/A	Concrete Block Wall		Non Suspect ACM	2280	SF		0		SF				N/A	N/A	N/A
2	1	Annex Hallway from Office Suites to Conference Room	N/A	Sheetrock Wall		Non Suspect ACM	46	SF		0		SF				N/A	N/A	N/A
2	1	Annex Hallway from Office Suites to Conference Room	M	Floor Tile VAT 12" x 12"	8390/02/01/TT	Assumed	950	SF		0		SF	Tan			1	No	1/D
1	AT	Attic-above Pump Room	X	X		X	X	X	X	X	X	X			B	X	X	X
1	CS	Crawlspace	X	X		X	X	X	X	X	X	X			A	X	X	X

### **Section III    Certificates**

#### **A. Management Planner/Building Inspector Certificates**

### Section III – A

#### Management Planner/Building Inspector Certificates

These charts indicate the Name, Course Date, Expiration Date and Corresponding Certificate Number of the Management Planner and Building Inspector of individuals that participated in the AHERA 3 Year Inspection and Management Plan process of 2015/2016.

Management Planner	Date Granted	Expiration Date	Certificate Number
Monique Causley	2/15/2015	2/16/2016	ACC-0215-8-010
Monique Causley	2/16/2016	2/17/2017	ACC-0216-8-001
Megan Vala	5/22/2015	6/22/2016	740728
Mary Anne Lerro	4/5/2016	4/5/2017	742327

Building Inspector	Date Granted	Expiration Date	Certificate Number
Scott Magee	8/15/2015	8/15/2016	70016699C
William Garrity	8/15/2015	8/15/2016	70016699A
Bernard Brunner	10/2/2015	8/2/2016	45397
Mary Anne Lerro	3/3/2015	3/3/2016	740092
Mary Anne Lerro	4/5/2016	4/5/2017	742322
James Madden	12/11/2014	12/11/2015	ACC-1214-6-010
James Madden	12/3/2015	12/3/2016	ACC-1215-6-018
Troy Ray	3/15/2015	3/19/2016	ACC-0355-6-011
Ananth Vinjamuri	9/29/2015	9/29/2016	374
Shelton Williams	9/29/2015	9/29/2016	375
Paul Davis	2/12/2015	2/12/2016	ACC-0215-6-015
Paul Davis	2/2/2016	2/2/2017	741836
Bernard Bryson	2/16/2015	2/16/2016	ACC-0125-6-031
Bernard Bryson	2/15/2016	2/15/2017	ACC-0216-6-005
Alexander Roman	9/18/2015	9/18/2016	EHSBIR-150619-008
Norm Harrison	9/2/2015	9/2/2016	ACC-0915-6-011
Kelly Mayberry	2/20/2015	2/20/2016	EHSBIR-150220-005
Kelly Mayberry	2/18/2016	2/18/2017	EHSBIR-160218-006
Andrew Hine	5/6/2015	5/6/2016	AI05042015-3
Maryellen Leotta	2/12/2015	2/12/2016	ACC-0215-6-024

# Certificate of Completion

*awarded to*

**Monique Causley**

*for successfully completing the prescribed course of study in*

## **Pennsylvania Asbestos Management Planner Refresher Course**

*under TSCA Title II*

*presented by*

**ACCESS TRAINING SERVICES, INC.**  
7921 River Road, Pennsauken, NJ 08110  
(856) 665-3449

**2/16/15**

*Course Date*

**N/A**

*Exam Date*

**2/16/16**

*Expiration Date*

**Not Provided**

*Social Security Number*

**ACC-0215-8-010**

*Certificate Number*

**Mark K. Schlager**  
*Training Director*

# Certificate of Completion

*awarded to*

**Monique Causley**

*for successfully completing the prescribed course of study in*

## **Pennsylvania Asbestos Management Planner Refresher Course**

**under TSCA Title II**

*presented by*

**ACCESS TRAINING SERVICES, INC.  
7921 River Road, Pennsauken, NJ 08110  
(856) 665-3449**

**2/15/16**

*Course Date*

**N/A**

*Exam Date*

**2/15/17**

*Expiration Date*

**Not Provided**

*Social Security Number*

**ACC-0216-8-001**

*Certificate Number*

**Mark K. Schlüger**  
*Training Director*

# *Certificate of Training*

CRITERION LABORATORIES, INC.

HEREBY CERTIFIES THAT

Megan Vala

HAS SUCCESSFULLY COMPLETED A 16 HOUR COURSE ENTITLED

Asbestos Management Planner Initial

INCLUDING CLASSROOM INSTRUCTION

05/21/2015 to 05/22/2015


Exam passed on this 22nd day of May 2015 - Score - 94

Approved for AHERA Accreditation Under TSCA Title II

3370 Progress Drive, Suite J  
Bensalem, PA 19020  
(215) 244-1300 - Phone  
(215) 244-4349 - Fax  
www.criterionlabs.com

*Course is conducted in English*

DIRECTOR:

  
James A. Welte, CIH, President



# *Certificate of Training*

**CRITERION LABORATORIES, INC.**

HEREBY CERTIFIES THAT

**Mary Anne Lerro**

HAS SUCCESSFULLY COMPLETED A 4 HOUR COURSE ENTITLED

**Asbestos Management Planner Refresher**

INCLUDING CLASSROOM INSTRUCTION

on this 5th day of April 2016

Approved for AHERA Accreditation Under TSCA Title II

3370 Progress Drive, Suite J  
Bensalem, PA 19020  
(215) 244-1300 - Phone  
(215) 244-4349 - Fax  
www.criterionlabs.com

*Course is conducted in English*

DIRECTOR:

*James A. Welts*

*James A. Welts, CIH, President*

# EMSL ANALYTICAL, INC.

Certifies that

Scott Magee

has successfully completed the course of study for the

## Asbestos Building Inspector Refresher Course

for Accreditation under TSCA Title II

EMSL Certificate No. 70016699C


### Approved by:

PA Dept. of Labor and Industry  
Accreditation # 137

Course Date: 8/15/2015  
Granted: 8/15/2015  
Expiration Date: 8/15/2016

### Sponsored by:

EMSL Analytical, Inc.  
200 Route 130 North  
Cinnaminson, NJ 08077  
Phone: (800) 220-3675  
Fax: (856) 786-5973  
[www.emsl.com](http://www.emsl.com)



*Michael P. Menz*

Michael P. Menz, CIH  
Training Director

Environmental, Mold, Bacteria, IAQ, Asbestos, Lead, Forensic and Materials Testing Since 1981

# EMSL ANALYTICAL, INC.

Certifies that

William Garrity

has successfully completed the course of study for the

## Asbestos Building Inspector Refresher Course

for Accreditation under TSCA Title II

EMSL Certificate No. 70016699A


Approved by:

PA Dept. of Labor and Industry  
Accreditation # 137

Course Date: 8/15/2015  
Granted: 8/15/2015  
Expiration Date: 8/15/2016

Sponsored by:

EMSL Analytical, Inc.  
200 Route 130 North  
Cinnaminson, NJ 08077  
Phone: (800) 220-3675  
Fax: (856) 786-5973  
[www.emsl.com](http://www.emsl.com)



*Michael P. Menz*  
\_\_\_\_\_  
Michael P. Menz, CIH  
Training Director

Environmental, Mold, Bacteria, IAQ, Asbestos, Lead, Forensic and Materials Testing Since 1981

45397

# *National Asbestos & Environmental Training Institute*

## CERTIFICATE OF COMPLETION

AHERA/EPA Accredited Per 40 CFR Part 763  
Asbestos Accreditation under TSCA Title II

*This is to certify that*


***Bernard Brunner, Jr.***

*Successfully completed the course entitled*

**1/2-Day New York State/EP A/AHERA Asbestos Building Inspector Annual Refresher on  
October 2, 2015**

*Examination Passed October 2, 2015*

*Expiration Date on October 2, 2016*

  
**Doris L. Adler**  
*President, NAEETI*

Per 10 NYCRR Part 73.2 (L) (1), DOH 2832 Certificate of Completion of Asbestos  
Safety Training is the only official record of training for N.Y.S. students.

Language: English

ABIH 1/2 CM POINT

3321 Doris Avenue, Building B, Ocean, NJ 07712

Phone (732) 531-5571

Fax (732) 531-5956

[www.naeti.com](http://www.naeti.com)

Number 740092

Expiration Date:  
03/03/2016

# *Certificate of Training*

CRITERION LABORATORIES, INC.

HEREBY CERTIFIES THAT

Mary Anne Lerro

HAS SUCCESSFULLY COMPLETED A 4 HOUR COURSE ENTITLED

Asbestos Building Inspector Refresher

on this 3rd day of March 2015

Exam passed on this 3rd day of March 2015 - Score - 84

Approved for AHERA Accreditation Under TSCA Title II

3370 Progress Drive, Suite J  
Bensalem, PA 19020  
(215) 244-1300 - Phone  
(215) 244-4349 - Fax  
[www.criterionlabs.com](http://www.criterionlabs.com)

*Course is conducted in English*

DIRECTOR:

*James A. Welts*

*James A. Welts, CIH, President*

# *Certificate of Training*

**CRITERION LABORATORIES, INC.**

**HEREBY CERTIFIES THAT**

**Mary Anne Lerro**

**HAS SUCCESSFULLY COMPLETED A 4 HOUR COURSE ENTITLED**

**Asbestos Building Inspector Refresher**

**INCLUDING CLASSROOM INSTRUCTION**

**on this 5th day of April 2016**

**Exam passed on this 5th day of April 2016 - Score - 88**

**Approved for AHERA Accreditation Under TSCA Title II**

3370 Progress Drive, Suite J  
Bensalem, PA 19020  
(215) 244-1300 - Phone  
(215) 244-4349 - Fax  
www.criterionlabs.com

*Course is conducted in English*

**DIRECTOR:**

*James A. Wells*

*James A. Wells, CIH, President*



# Certificate of Completion

**James Madden**

*for successfully completing the prescribed course of study in*

## **Pennsylvania Asbestos Building Inspector Refresher Course**

under TSCA Title II

*presented by*

**ACCESS TRAINING SERVICES, INC.**  
7921 River Road, Pennsauken, NJ 08110  
(856) 665-3449

12/11/14

*Course Date*

N/A

*Exam Date*

12/11/15

*Expiration Date*

Not Provided

*Social Security Number*

ACC-1214-6-010

*Certificate Number*

**Mark K. Schlager**  
*Training Director*

# Certificate of Completion

**James Madden**

*for successfully completing the prescribed course of study in*

## **Pennsylvania Asbestos Building Inspector Refresher Course**

under TSCA Title II

*presented by*

**ACCESS TRAINING SERVICES, INC.**  
7921 River Road, Pennsauken, NJ 08110  
(856) 665-3449

**12/3/15**

*Course Date*

**N/A**

*Exam Date*

**12/3/16**

*Expiration Date*

**Not Provided**

*Social Security Number*

**ACC-1215-6-018**

*Certificate Number*

*Mark K. Schlager*  
**Mark K. Schlager**  
Training Director



# Certificate of Completion

**Troy A. Ray**

*for successfully completing the prescribed course of study in*

## **Pennsylvania Asbestos Building Inspector Refresher Course**

under TSCA Title II

*presented by*

**ACCESS TRAINING SERVICES, INC.**  
7921 River Road, Pennsauken, NJ 08110  
(856) 665-3449

**3/19/15**

*Course Date*

**N/A**

*Exam Date*

**3/19/16**

*Expiration Date*

**Not Provided**

*Social Security Number*

**ACC-0355-6-011**

*Certificate Number*

**Mark K. Schlager**  
*Training Director*

# CERTIFICATE NO 374

G&C Environmental Services, Inc. (#294)

2 Street Road, Newtown Square, Pennsylvania 19073

Telephone: (610) 993-9202 Facsimile: (610) 993-9232

Email: Training@gcenviro.com

www.GCenviro.com

This document certifies that Ananth K. Vinjamuri has successfully completed this State of New York Department of Health Approved AHERA BUILDING INSPECTOR

REFRESHER COURSE, completed as required for asbestos accreditation under the Toxic

Substances Control Act, Title II. This course was held from 09/29/2015 to 09/29/2015.

The examination date was 09/29/2015. This certificate expires one year from the date of  
successful completion of the examination 09/29/2016.

*The official record of successful training completion is the New York State Department of Health certificate of asbestos safety training completion (DPH 2832).*

Gail M. Conner  
Training Director

Gail M. Conner

# CERTIFICATE NO 375

G&C Environmental Services, Inc. (#294)

2 Street Road, Newtown Square, Pennsylvania 19073

Telephone: (610) 993-9202 Facsimile: (610) 993-9232

Email: Training@gcenviro.com

www.GCenviro.com

This document certifies that Shelton Williams has successfully completed this

State of New York Department of Health Approved AHERA BUILDING INSPECTOR

REFRESHER COURSE, completed as required for asbestos accreditation under the Toxic

Substances Control Act, Title II. This course was held from 09/29/2015 to 09/29/2015.

MM DD YR MM DD YR

The examination date was 09/29/2015. This certificate expires one year from the date of

MM DD YR

MM DD YR

MM DD YR

*The official record of successful training completion is the New York State Department of Health certificate of asbestos safety training completion (DPH 2832).*

Gail M. Conner

Training Director

Gail M. Conner

# Certificate of Completion

**Paul M. Davis**

*for successfully completing the prescribed course of study in*

## **Pennsylvania Asbestos Building Inspector Refresher Course**

under TSCA Title II

*presented by*

**ACCESS TRAINING SERVICES, INC.**  
7921 River Road, Pennsauken, NJ 08110  
(856) 665-3449

**2/12/15**

*Course Date*

**N/A**

*Exam Date*

**2/12/16**

*Expiration Date*

**Not Provided**

*Social Security Number*

**ACC-0215-6-015**

*Certificate Number*

**Mark K. Schlager**  
*Training Director*

# Certificate of Training

CRITERION LABORATORIES, INC.

HEREBY CERTIFIES THAT

Paul M. Davis

HAS SUCCESSFULLY COMPLETED A 4 HOUR COURSE ENTITLED  
Asbestos Building Inspector Refresher

INCLUDING CLASSROOM INSTRUCTION

on this 2nd day of February 2016

Exam passed on this 2nd day of February 2016 - Score - 92

Approved for AHERA Accreditation Under ISCA Title II

3370 Progress Drive, Suite J  
Bensalem, PA 19020  
(215) 244-1300 - Phone  
(215) 244-4349 - Fax  
www.criterionlabs.com

Course is conducted in English

DIRECTOR:

*James A. Wells*

James A. Wells, CIH, President

# Certificate of Completion

**Bernard J. Bryson**

*for successfully completing the prescribed course of study in*

## **Pennsylvania Asbestos Building Inspector Refresher Course**

under TSCA Title II

*presented by*

**ACCESS TRAINING SERVICES, INC.**  
7921 River Road, Pennsauken, NJ 08110  
(856) 665-3449

**2/16/15**  
*Course Date*

**N/A**

*Exam Date*

**2/16/16**

*Expiration Date*

**Not Provided**

*Social Security Number*

**ACC-0125-6-031**

*Certificate Number*

**Mark K. Schlager**  
*Training Director*



# Certificate of Completion

**Bernard J. Bryson**

*for successfully completing the prescribed course of study in*

## **Pennsylvania Asbestos Building Inspector Refresher Course**

under TSCA Title II

*presented by*

**ACCESS TRAINING SERVICES, INC.**  
7921 River Road, Pennsauken, NJ 08110  
(856) 665-3449

**2/15/16**

*Course Date*

**N/A**

*Exam Date*

**2/15/17**

*Expiration Date*

**Not Provided**

*Social Security Number*

**ACC-0216-6-005**

*Certificate Number*

**Mark K. Schlager**  
*Training Director*

**EHS TRAINING INSTITUTE, INC.**

A Division of BATTI, Inc.

# **Certificate of Completion**

## **AHERA Building Inspector**

**(Refresher)**

**Awarded To:**

**Alexander Roman**

SS#:XXX-XX-1743

Who has completed this 4-hour course and examination,

EPA Approved under TSCA Title II

AHERA / ASHARA Rule

40 CFR Part 763.

**EHS TRAINING INSTITUTE, INC.**

A Division of BATTI, Inc.

**Delaware Industrial Park • 6 Garfield Way**


**Newark, DE 19713-5817**

**(302) 737-3376 • Fax (302) 737-5764**

**Course Date: September 18, 2015**

**Date of Expiration: September 18, 201**

**Certification Number : EHSBIR 150619-008**

  
**Todd K. Zeisloff, Instructor**

  
**Neeraj K. Batta, President**



# Certificate of Completion

**Norman Harrison**

*for successfully completing the prescribed course of study in*

## **Pennsylvania Asbestos Building Inspector Refresher Course**

under TSCA Title II

*presented by*

**ACCESS TRAINING SERVICES, INC.**  
7921 River Road, Pennsauken, NJ 08109  
(856) 665-3449

**9/2/15**

*Course Date*

**N/A**

*Exam Date*

**9/2/16**


*Expiration Date*

**Not Provided**

*Social Security Number*

**ACC-0915-6-011**

*Certificate Number*

  
**Mark A. Schlenger**  
*Training Director*

**EHS TRAINING INSTITUTE, INC.**  
A Division of BATTI, Inc.

# **Certificate of Completion**

## **AHERA Building Inspector**

**(Refresher)**

**Awarded To:**

**Kelly Mayberry**

SS#:XXX-XX-1551

Who has completed this 4-hour course and examination,  
EPA Approved under TSCA Title II  
AHERA / ASHARA Rule  
40 CFR Part 763.

**EHS TRAINING INSTITUTE, INC.**

A Division of BATTI, Inc.

*Delaware Industrial Park • 6 Garfield Way*

*Newark, DE 19713-5817*

*(302) 737-3376 • Fax (302) 737-5764*

**Course Date: February 20, 2015**

**Date of Expiration: February 20, 2016**

**Certification Number : EHSBIR 150220-005**

  
Todd K. Zeisloft, Instructor

  
Neeraj K. Batta, President

**EHS TRAINING INSTITUTE, INC.**  
A Division of BATTI, Inc.

# **Certificate of Completion**

## **AHERA Building Inspector**

**(Refresher)**

**Awarded To:**

**Kelly Mayberry**

SS#:XXX-XX-1551  
Who has completed this 4-hour course and examination,  
EPA Approved under TSCA Title II  
AHERA / ASHARA Rule  
40 CFR Part 763.

**EHS TRAINING INSTITUTE, INC.**

A Division of BATTI, Inc.

Delaware Industrial Park • 6 Garfield Way  
Newark, DE 19713-5817  
(302) 737-3376 • Fax (302) 737-5764

Course Date: February 18, 2016  
Date of Expiration: February 18, 2017  
Certification Number : EHSBIR 160218-006

  
Todd K. Zeisloft, Instructor

  
Neeraj K. Batta, President

# AEROSOL MONITORING & ANALYSIS, INC.

*This is to certify that*  
**ANDREW HINE**

*has met the attendance requirements and successfully completed  
the course entitled*

**3-DAY EPA AHERA INSPECTOR**  
*For Accreditation Under TSCA Title II*

05/04/2015 to 05/06/2015

**Course Date**

05/06/2015

**Exam Date**

5/6/2016

**Expiration Date**

STEVE SIERAGI

**Principal Instructor**

*Steve Sieragi*

A105042015-3

**Certification No.**

E. Rush Barnett

**Course Director**

*E. Rush Barnett*

1331 Ashton Road

P.O.Box 646

Hanover, MD 21076

P: 410-684-3327

F: 410-684-3724

[www.amatraining.com](http://www.amatraining.com)

# Certificate of Completion

**Maryellen Leotta**

*for successfully completing the prescribed course of study in*

## **Pennsylvania Asbestos Building Inspector Refresher Course**

under TSCA Title II

*presented by*

**ACCESS TRAINING SERVICES, INC.**  
7921 River Road, Pennsauken, NJ 08110  
(856) 665-3449

**2/12/15**

*Course Date*

**N/A**

*Exam Date*

**2/12/16**

*Expiration Date*

**Not Provided**

*Social Security Number*

**ACC-0215-6-024**

*Certificate Number*

**Mark K. Schlüger**  
*Training Director*

# Asbestos Hazard Emergency Response Act (AHERA) Environmental Compliance Audit Cross Reference Table

In response to the AHERA Environmental Compliance Audit a Cross Reference Table has been prepared for inclusion into the Environmental Management Plan. The purpose of this Cross Reference Table is to link the following documents to the AHERA Management Plan.

<b>Cross Reference Table</b>	
3 Year Reinspection Report follows this Cross Reference Table documentation.	
<b>Subject Matter</b>	<b>Location of Required Documents</b>
Designated Person	Pages 1 - 3
Annual Notification	Pages 4 - 5
6 Month Periodic Surveillance Outline of Events	Page 6
3 Year Re-inspections Outline of Events	Page 7
Asbestos Management Program (operations and maintenance)	Pages 8 - 19
Asbestos Investigation Report (AIR)	Attachment 1 Letter Dated August 4, 2006
Training (included in the Asbestos Management Program)	<p>The original records are centralized at the School District's Environmental Library. Copies are maintained on staff and are required to be maintained in the latest Reinspection Report.</p> <p>2 hour awareness training records for all Building Engineers, Custodian Assistants and maintenance personnel</p> <p>40 hour worker/supervisor training records for the OEMS A-Team and various AST tradesmen.</p>
Response Actions (monthly mailings if applicable)	<p>The original documents are on file at the School District's Environmental Library.</p> <p>Copies of the original are mailed to the Schools Main Office for retention with the Management Plan documentation. These documents are typically kept separate from the management plan in an update binder due to the potential volume of response action reports.</p>



## **SCHOOL DISTRICT OF PHILADELPHIA**

### **ASBESTOS DESIGNATED PERSON**

**Gerald F Junod**  
**Office of Capital Programs**  
**Environmental Management & Services**  
**440 N Broad Street, 3<sup>rd</sup> Floor**  
**Philadelphia, PA 19130**  
**Telephone: 215 400 6738**  
**Fax: 215 400 4751**

<b>Drexel University- Asbestos Building Inspector Course</b>	<b>January 9-11, 1989 24 Hours</b>
<b>Drexel University- Asbestos Management Planner Course</b>	<b>January 12-13, 1989 16 Hours</b>
<b>Criterion Laboratories, Inc. - Asbestos Management Planner Course</b>	<b>October 11-12, 2012 16 Hours</b>

<b><u>Annual Building Inspector Refreshers</u></b>	<b>1990 to Present</b>
<b>4 Hours</b>	
<b>Drexel University</b>	
<b>Criterion Laboratories, Inc</b>	
<b>Access Training Services, Inc.</b>	

<b><u>Annual Building Management Planner Refreshers</u></b>	<b>1990 to 1994</b>
<b>4 Hours</b>	
<b>Drexel University</b>	
<b>Criterion Laboratories, Inc</b>	<b>2013 to Present</b>
<b>4 Hours</b>	

#### **Environmental Manager, School District of Philadelphia**

**Manages the design and implementation of asbestos and lead projects for the Capital Improvement Program and other District Departments including Facilities & Operations and Information Technology. Ensures that asbestos abatement and lead remediation projects are expertly designed and executed in accordance with industry best management practice standards and regulations.**

#### **Manager, City of Philadelphia Asbestos Control Program**

**Served as the Asbestos Control Program Manager for the City of Philadelphia, Department of Public Health, Air Management Services, Asbestos Control Unit from August 1, 2003 through October 23, 2006.**

#### **Mid Atlantic Regional Environmental Consortium (MAREC)**

**Former member with attendance and participation commitments of all quarterly EPA Region III and yearly National Asbestos Regulatory Conferences sponsored by the EPA and the National Conference of State Legislators respectively as a representative for the City of Philadelphia Department of Public Health Air Management Services from 1994 through 2006.**

#### **Philadelphia Environmental Task Force**

**Former member of the Philadelphia Environmental Task force as a representative and point of contact for the City of Philadelphia Department of Public Health Air Management Services Asbestos Control Unit from 2002 through 2006.**

**Asbestos Instructor**

Worked as the primary instructor for the initial and annual Asbestos Project Inspector training and licensing program as mandated by City of Philadelphia Department of Public Health Asbestos Control Regulations from August 1994 through October 2006.

Worked as a lead instructor with an Environmental Consulting Firm and approved by the US EPA for the initial and annual refresher training courses for various asbestos occupational disciplines such as the Building Inspector, Management Planner and Worker/Supervisor from 1991 through 1994.

I certify that the general, local agency responsibilities as stipulated in Section 763.84 will be met.



Gerald F. Junod  
Asbestos Designated Person  
Environmental Manager  
Office of Environmental Management and Services



## **SCHOOL DISTRICT OF PHILADELPHIA**

### **Accreditation Information Statement**

**All persons who inspect for Asbestos Containing Building Materials (ACBM) and who will design or carry out response actions with respect to assumed and confirmed ACBM, will be accredited by an EPA approved course and/or a State Contractors Accreditation Program under Sections 206 (c) and 206 (b) of Title II of the ACT.**

A handwritten signature in black ink, appearing to read 'Gerald F. Junod', is written over the printed name and title.

**Gerald F. Junod  
Asbestos Designated Person  
Environmental Manager  
Office of Environmental Management and Services**

SCHOOL DISTRICT OF PHILADELPHIA  
OFFICE OF CAPITAL PROGRAMS  
440 NORTH BROAD STREET, SUITE 373  
PHILADELPHIA, PENNSYLVANIA 19130

OFFICE OF ENVIRONMENTAL MANAGEMENT AND SERVICES

PHONE (215)-400-4750

September 2015

TO: Principals  
Building Administrators/Occupants  
Parents/Guardians

FROM: Fran Burns  
Chief Operating Officer

Francine Locke, M.S., Director  
Office of Environmental Management and Services

SUBJECT: Annual EPA Notification Letter

Pursuant to the Federal Environmental Protection Agency (EPA) mandate, as required by 40 C.F.R. 763.84 (c)(d) of public access to environmental records, this letter is to acknowledge the availability of your facility's Asbestos Hazard Emergency Response Act (AHERA) Management Plan.

Each member of the school staff, parents/guardians, temporary workers and/or contractors, are required to receive a copy of the Notification Letter. At the direction of the Principal, a copy is to be posted on the bulletin boards and an appropriate amount of copies are to be generated for distribution.


Note: The AHERA Three-Year Reinspection reports, in colored binders; White with Pink, Tan, Black, Red, Dark Blue, Green, Yellow and White, are Federal EPA mandated inspection documents. The School District of Philadelphia is subject to severe monetary penalties if the reports and associated paperwork are not available to the EPA and the public upon request.

It is incumbent on designated school personnel to gather and retain this data as it is delivered, in one location for future review. Acceptable locations include the Principal's Office or Main Office for the primary data. The Building Engineer should maintain any secondary or duplicate copies.

If you have any questions, please call 215-400-4750. Thank you for your cooperation.



Fran Burns  
Chief Operating Officer



Francine Locke, M.S., Director  
Office of Environmental Management  
and Services

c: Danielle Floyd

AHERA-4  
8/21/15



**School District of Philadelphia**  
**OFFICIAL NOTICE**

**PLEASE POST**

September 2015

TO: Principals  
Building Administrators  
Building Engineers  
Building Occupants  
Parents/Guardians

FROM: Fran Burns  
Chief Operating Officer

Francine Locke, M.S., Director  
Office of Environmental Management and Services

SUBJECT: Annual Notification Letter: Asbestos Hazard Emergency Response Act

The Federal Register published on October 30, 1987, Subpart E, in Schools: Final Rule and Notice, 763.84 (c)(d) states that each local education agency shall ensure that workers and building occupants or guardians are to be informed at least once each school year about inspections, response actions and post-response action activities including re-inspections and periodic surveillance activities. The School District as the Local Education Agency (LEA), retains such reports that are available for public inspection in the Office of the Principal or Building Administrator.

The Principal or Building Administrator is required to do the following with this notification:

- 1) Post in a Public Place or Main Office
- 2) Inform Building Occupants
- 3) Send a copy of this notification to Parents or Guardians
- 4) Insert a copy into the latest AHERA Three-Year Reinspection report (white/pink binder) in your office or facility.

Handwritten signature of Fran Burns in black ink.

Fran Burns  
Chief Operating Officer

Handwritten signature of Francine Locke in black ink.

Francine Locke, M.S., Director  
Office of Environmental Management  
and Services

c: Danielle Floyd

AHERA-4a  
8/21/15

SCHOOL DISTRICT OF PHILADELPHIA  
Education Center  
440 North Broad Street  
Philadelphia, Pennsylvania 19130

Office of Environmental Management and Services

215-400-4750

AHERA  
Six Month Surveillance  
Outline of Events

- Pursuant to the Federal Environmental Protection Agency (EPA) mandate, as required by 40 CFR 763.92(b), the following procedure is to be implemented. At least once every six (6) months after a Management Plan is in effect, each Local Education Agency (LEA) shall conduct a periodic surveillance in each building that it owns or leases that contains Asbestos Containing Building Materials (ACBM) or is assumed to contain ACBM.
- The first Bi-Annual Inspection starts in the Spring (March, April, May) and again in the Fall (October, November, December) of each year. The Building Engineer/Assistant should assist the Building Inspector with appropriate access to all areas including (Crawlspaces/Attics) and rooms in the facility. There is no action required of the Principal.
- The Building Inspector shall visually inspect all areas that are identified in the Management Plan as ACBM or assumed ACBM. The date of the surveillance is recorded, the inspectors name and any changes in the conditions of the materials.
- The Building Inspector shall make a copy of the inspection document and insert into the front of the latest Management Plan (AHERA Three Year Reinspection report). The original document is returned to the LEA's Environmental Library and filed.

SCHOOL DISTRICT OF PHILADELPHIA  
Education Center  
440 North Broad Street  
Philadelphia, Pennsylvania 19130

Office of Environmental Management and Services

215-400-4750

AHERA  
Three Year Reinspection  
Outline of Events

- Pursuant to the Federal Environmental Protection Agency (EPA) mandate, as required by 40 CFR 763.85(b) the following procedure is to be implemented. At least once every three (3) years after a Management Plan is in effect, each Local Education Agency (LEA) shall conduct a reinspection of each building that it owns or leases that contains Asbestos Containing Building Material's (ACBM's) or is assumed to contain ACBM.
- Subsequent Three Year Re-inspections (2009, 2012, 2015, etc) shall start in the Fall (October, November, December, January). The Building Engineer/Assistant should assist the Building Inspector with appropriate access to all areas including (Crawlspaces/Attics) and rooms in the facility. There is no action required of the Principal.
- An accredited Building Inspector shall visually inspect and touch to determine friability, all areas that are identified in the Management Plan as ACBM or assumed ACBM. The date of the surveillance is recorded, the inspectors name and any changes in the conditions of the materials. The Building Inspectors state of accreditation and license number is required.
- After the inspection, the Building Inspector shall make a copy of the inspection documents and insert into the front of the latest Management Plan (AHERA Three Year Reinspection report). The original document is returned to the LEA's Environmental Library and filed.
- The Building Inspector shall return the reinspection data to the Management Planner to be assessed and determine appropriate response actions and a report issued (AHERA Three Year Reinspection report). One copy of the report is delivered to the schools Principal to be permanently retained with all previous environmental data. Another copy is retained in the LEA's Environmental Library.



**School District of Philadelphia**  
Office of Environmental Management & Services  
440 North Broad Street  
Philadelphia, PA 19130  
(215) 400-4750

**School District of Philadelphia  
Asbestos Management Program**

## TABLE OF CONTENTS

Definitions.....	Page 9
1. Introduction.....	Page 10
2. Summary of Asbestos Management Plan	
3. Asbestos Management Plan Execution.....	Page 11
a. General Execution	
4. Summary of Program Execution	
a. Asbestos Management Plan Execution	
5. Responsibilities	
a. OEMS	
b. Asbestos Worker/Supervisor "A-TEAM".....	Page 12
c. Asbestos Designated Person	
d. Supervisor or Project Manager (Capital, Maintenance & Facilities)	
e. Employee Capital.....	Page 13
f. Employee Maintenance	
g. Employee Facilities and Custodial	
6. Requirements.....	Page 14
a. Employee Exposure Monitoring	
b. Employee Notification	
c. Observation of Monitoring	
d. Training Program	
e. Access of Information	
f. Record Keeping	
7. AHERA O&M Plan.....	Page 15
a. Controls	
8. O&M Response Actions.....	Page 16
a. Facility Maintenance Isolation of Area	
b. Unlikely Contact with ACM/PACM	
c. Accidental Disturbance of ACM/PACM	
d. Planned Disturbance of ACM/PACM	
e. Miscellaneous ACM/PACM.....	Page 17
f. Vinyl Asbestos Floor Tile	
g. Mastic/Adhesives	
h. Woven Vibration Dampers	
i. Other Work Practices	
j. Fiber Release Episodes	
9. References and Resources.....	Page 18

## **DEFINITIONS / ACRONYMS**

<b>ACM/PACM:</b>	<b>Asbestos Containing Material/Potential Asbestos Containing Material</b>
<b>AHERA:</b>	<b>Asbestos Hazard Emergency Response Act</b>
<b>AIR FORM:</b>	<b>Asbestos Inspection Report Form</b>
<b>Amended Water:</b>	<b>Water to which a surfactant (soap) has been added</b>
<b>AMP:</b>	<b>Asbestos Management Program/Asbestos Management Plan</b>
<b>Asbestos Designate Person:</b>	<b>Individual assigned by the district to oversee asbestos related issues.</b>
<b>Asbestos Regulated Area:</b>	<b>Location that is posted as an asbestos work area in which only approved and accredited personnel are permitted to enter</b>
<b>AST:</b>	<b>Asbestos Support Team involving approved and accredited school district tradespersons personnel that are school district person</b>
<b>A-TEAM:</b>	<b>School District of Philadelphia asbestos workers</b>
<b>CIP:</b>	<b>Capital Improvement Program</b>
<b>Consultant:</b>	<b>Asbestos consulting firm hired by the District</b>
<b>Demolition Directive:</b>	<b>Memorandum – August 4, 2006 from Patrick Henwood</b>
<b>EPA:</b>	<b>Environmental Protection Agency</b>
<b>In House Personnel:</b>	<b>School District of Philadelphia asbestos workers</b>
<b>LEA:</b>	<b>Local Education Agency</b>
<b>O&amp;M:</b>	<b>Operations and Maintenance</b>
<b>OEMS:</b>	<b>Office of Environmental Management and Services</b>
<b>OSHA:</b>	<b>Occupational Safety and Health Administration</b>
<b>PEL:</b>	<b>Permissible Exposure Limit</b>
<b>PSD or SDP:</b>	<b>Philadelphia School District/School District of Philadelphia</b>
<b>PSIT:</b>	<b>Philadelphia School Improvement Team</b>
<b>STEL:</b>	<b>Short Term Exposure Limit</b>



## **1. Introduction**

The School District of Philadelphia, Asbestos Policy Statement:

“The School District of Philadelphia is dedicated to providing a safe and healthful work environment for its employees, students, faculty, contractors and visitors. In recognition of the potential health problems associated with asbestos, the School District of Philadelphia is committed to a comprehensive asbestos control program. This program is implemented and maintained through the School District of Philadelphia's Office of Environmental Management and Services (OEMS).”

OEMS has the responsibility of establishing procedures for asbestos abatement, asbestos inspection, air monitoring, renovation and demolition activities within all School District of Philadelphia owned or leased facilities.

These procedures are developed to ensure that:

- (1) People are not exposed to significant levels of asbestos fibers
- (2) Asbestos waste is handled and disposed of properly
- (3) Members of the School District of Philadelphia community have access to the Office of Environmental Management and Services for information, assistance, guidance, and interpretation regarding asbestos related matters.
- (4) Members of the School District of Philadelphia community have access to the Asbestos Management Plans as required and outlined in the US EPA AHERA regulations including annual written notification to all parents.
- (5) Compliance with all applicable Federal, State and Local Asbestos Regulations

Requirements outlined in this manual are mandatory in nature where the word “SHALL” is used and are advisory in nature where the word “SHOULD” is used.

## **2. Summary of Asbestos Management Program**

The School District of Philadelphia's Asbestos Management Program was established to meet the requirements of Federal, State, and Local Regulations.

These regulations include, but are not limited to:

- US Environmental Protection Agency Asbestos Hazard Emergency Response Act (US EPA AHERA) and National Emissions Standard for Hazardous Air Pollutants subpart M, Part 61 (NESHAP);
- US Department of Labor, Occupational Safety and Health Administration (OSHA) General Industry Standard (29 CFR 1910.1001) and the OSHA Asbestos Standard for the Construction Industry (29 CFR 1926.1101);
- The Commonwealth of Pennsylvania, Department of Labor and Industry, Asbestos Occupations, Accreditation and Certification Act;
- The City of Philadelphia, Department of Public Health, Asbestos Control Regulations.

### **3. Asbestos Management Program Execution**

#### **a) General Execution**

The Office of Environmental Management and Services (OEMS) develops, implements and manages safety and health programs for the School District of Philadelphia faculty, staff and students and assists with ensuring that all contractors comply with Federal, State and Local Environmental Regulations. The OEMS provides the oversight of School District of Philadelphia employees (Asbestos A-Team), environmental consultants, and asbestos abatement contractors for all projects within the School District of Philadelphia concerning Asbestos Containing Materials.

The control of safety and health hazards at the School District of Philadelphia is primarily through the implementation of engineering, work practice and administrative controls. Personal Protective Equipment (PPE) is used to supplement these controls or whenever the controls are not feasible or are in the process of being implemented. PPE is also recommended whenever exposures to chemical, physical or biological agents can be prevented or reduced by its use.

This written program establishes the procedures necessary to:

- 1) meet established standards and federal regulations for occupational exposure to asbestos fibers;
- 2) meet the requirements of the City of Philadelphia Asbestos Control Regulations which encompasses the disturbance and/or abatement of asbestos containing building materials;
- 3) provide the necessary health and safety protection to the School District of Philadelphia staff, faculty, students, contractors and visitors.

This program is strengthened by input and cooperation with the Philadelphia Federation of Teachers (PFT), Health and Welfare Fund.

### **4. Summary of Program Execution**

#### **a) Asbestos Management Program Execution**

The Asbestos Management Program is administered by the Office of Environmental Management and Services (OEMS). OEMS provides the following services primarily through professional consultants:

- (1) exposure monitoring services;
- (2) building inspection/surveys (bulk sampling) for the identification of asbestos containing materials;
- (3) asbestos project design services;
- (4) asbestos abatement project and air monitoring services;
- (5) emergency response to fiber release episodes;
- (6) education/information;
- (7) medical monitoring;
- (8) training for School District of Philadelphia personnel

### **5. Responsibilities**

#### **a) Office of Environmental Management and Services**

OEMS is responsible for performing the following functions:

- (1) Developing and administering of the Asbestos Management Program.
- (2) Providing asbestos-related services to all School District of Philadelphia departments.
- (3) Conducting required training of the Asbestos Management Program and working jointly with departments to schedule training.
- (4) Identifying and posting areas where labeling/signage are required.
- (5) Medical Monitoring of OEMS "A-TEAM" and other departments "AST" Asbestos Program staff.

- (6) Certification and training as required for OEMS "A-TEAM" and other departments "AST" Asbestos program staff.
- (7) Record keeping as outlined in Section 3.5 and all records as by required by US EPA AHERA regulations.

**b) Asbestos Worker/Supervisor - "A-TEAM"**

- (1) OEMS shall ensure that all "A-TEAM" workers/supervisors adhere to the following requirements:
  - a) Attend an initial Worker/Supervisor Asbestos Course;
  - b) Maintain the annual re-certification per EPA AHERA requirements and Commonwealth of Pennsylvania Asbestos Occupations, Accreditation and Certifications Act;
  - c) Undergo an annual Asbestos Medical Evaluation;
  - d) Undergo an annual Respirator Medical Clearance;
  - e) Undergo an annual Respirator Fit Testing.

**c) Asbestos Designated Person**

The Asbestos Designated Person is responsible for:

- (1) Assuring the health and safety of employees, students and visitors in the School District of Philadelphia facilities under his/her control.
- (2) Being kept informed of all areas under his or her jurisdiction where potential asbestos exposures exist and initiating protection programs that adhere to the Asbestos Management Program requirements of this manual.
- (3) Assuring that Asbestos Management Program requirements are adhered to by principal investigators, project managers, supervisors, or division heads, and School District of Philadelphia personnel under their supervision.
- (4) Ensuring that all employees within the Asbestos Management Program comply with (OSHA 1910.1001 (j) (7) (iv)) and the US EPA AHERA regulations by attending the required training.
- (5) Ensure the posting of:
  - a) Warning labels/signage
  - b) Commonwealth of Pennsylvania Asbestos Abatement and Demolition/Renovation Notification form
  - c) Asbestos Inspection Reports (AIR) form (where required)
  - d) Ensuring that Construction Projects follow the Demolition Directive procedures as outlined in the August 4, 2006 letter.

**d) Supervisor or Project Manager (Capital, Maintenance and Facilities)**

Each person in charge of a project, maintenance/repair, renovation/demolition, or other activity from the Departments of Capital, Maintenance, and/or Facilities, where asbestos containing material may be present is responsible for:

Identifying, with the assistance of OEMS, asbestos containing building materials prior to any disturbance of these materials. Various Federal (EPA and OSHA) and Local (City of Philadelphia Asbestos Control Regulations) require Asbestos Inspections prior to renovation/demolition activities. This shall be accomplished by always following the Asbestos Management Program Procedures as follows:

- (1) Ensure that the requirements of the Asbestos Management Program Procedures are followed by all personnel, trades, and contractors who are involved with the project;

- (2) Review of the required Asbestos Inspection Report (AIR) form (Attachment 1) and AHERA Management Plan documents prior to activities that may disturb any Asbestos Containing Materials;
- (3) Perform all project related duties as outlined in the Project Management Responsibilities;
- (4) Keep the department chairperson or director informed on any actions proposed or taken regarding the Asbestos Management Plan;
- (5) Ensuring that Construction Projects follow the Demolition Directive procedure outlined in the August 4, 2006 letter.

**e) Employee – Capital**

School District of Philadelphia Capital employees and/or consultants shall:

- (1) Ensure that no suspect or asbestos containing building materials are disturbed in the course of the projects they are performing or managing. This shall be accomplished by notifying their supervisor and OEMS by issuance of a work order permit (a.k.a PSIT Service Request Form) and verifying that the materials which may be disturbed are non-asbestos containing. If this information is not available or verification has not been made, these materials should not be disturbed.
- (2) Immediately notify OEMS and their supervisor in the event of a potential fiber release episode upon discovery of visible damage to asbestos containing materials.
- (3) Ensuring that Construction Projects follow the Demolition Directive procedures as outlined in the August 4, 2006 letter.

The types of projects represented as part of the Capital Improvement Program are as follows:

- (1) Complete Renovation of an existing building that addresses all facility component concerns and educational program needs;
- (2) Major Renovation of an existing building addressing significant facility component and educational improvements;
- (3) Addition to an existing building (either as an attachment or stand-alone structure) to accommodate needed program space;
- (4) Conversion of an existing facility to accommodate a change in educational program;
- (5) Facility Component Improvement of specific facility needs (i.e. electrical or HVAC system upgrades, ADA improvements, life safety improvements, exterior renovations, etc.)

**f) Employee – Maintenance**

School District of Philadelphia Maintenance employees shall:

- (1) Ensure that no suspect or asbestos containing building materials are disturbed in the course of their duties or work they are performing. This shall be accomplished by notifying their supervisor and OEMS by issuance of a work order permit and verifying that the materials which may be disturbed are non-asbestos containing. If this information is not available or verification has not been made, these materials should not be disturbed.
- (2) Immediately notify OEMS and their supervisor in the event of a potential fiber release episode or upon discovery of visible damage to asbestos containing materials.
- (3) All employees involved in maintenance activities shall attend required Asbestos Awareness training program within 60 days of employment.

**g) Employee – Facilities & Custodial**

School District of Philadelphia Facilities and Custodial employees shall:

- (1) Ensure that no suspect or asbestos containing building materials are disturbed in the course of their duties or work they are performing. This shall be accomplished by notifying their supervisor and OEMS by issuance of a work permit and verifying that the materials which may be disturbed are non-asbestos containing. If this information is not available or verification has not been made, these materials should not be disturbed;
- (2) Immediately notify OEMS and their supervisor in the event of a potential fiber release episode or upon discovery of visible damage to asbestos containing materials.
- (3) All employees involved in Facilities and Custodial activities shall attend require Asbestos Awareness training program within 60 days of employment.

## **6. Requirements**

### **a) Employee Exposure Monitoring**

When information indicates that an employee's exposure to asbestos fibers may equal or exceed an 8-hour time-weighted average of 0.1 f/cc \* (per OSHA 1910.1001 & 1926.1101), OEMS shall develop and implement an asbestos exposure monitoring program. The sampling strategy shall be designed to identify employees by work task (job classification) that is exposed to asbestos fibers that exceed an 8-hour time-weighted average of 0.1 f/cc.

### **b) Employee Notification**

OEMS shall notify in writing, each employee exposed to asbestos fibers at or above an 8-hour time weighted average of 0.1 f/cc.

### **c) Observation and Monitoring**

OEMS shall provide employees or their representatives with an opportunity to observe any exposure measurements conducted.

### **d) Training Program**

OEMS shall institute a training program which meets the requirements of AHERA for all employees who perform maintenance operations in a facility/school which contains asbestos containing materials or presumed asbestos containing materials and 1910.1001 (j), and the Commonwealth of Pennsylvania Department of Labor and Industry and the City of Philadelphia Asbestos Control Regulations. The affected departments shall ensure employee participation in this program. The OEMS "A-TEAM" and other departments "AST" Asbestos Program staff training shall be conducted annually for each employee as required by all Federal, State and Local for each asbestos discipline.

All Asbestos Awareness training as required by AHERA shall be performed within 60 days of employment and shall include:

- Health effects of asbestos
- Locations of ACM and PACM in the building/facility
- Recognition of CM and PACM damage and deterioration
- Requirements of the OSHA 1910.1001 standard relating to maintenance
- Proper response to fiber release episodes
- Procedure to be followed to isolate areas affected by fiber release

### **e) Access to Information**

OEMS shall make available to affected employees or their representative's copies of the Occupational Safety and Health Administration (OSHA) General Industry Standard Part 1910.1001 and the department shall post a copy in the workplace.

### **f) Record Keeping**

OEMS shall maintain an accurate record of all employee exposure measurements. OEMS and/or the School District of Philadelphia Human Resources Department shall maintain records of employee medical monitoring program. OEMS shall maintain all employee training records. All records shall be provided upon request to employees, former employees, representatives designated by the individual employee.



## **7. AHERA OPERATIONS AND MAINTENANCE PLAN**

### **a) CONTROLS**

#### **i. Work Order System**

Minimizing disruption of ACM/PACM during maintenance and renovation activities is the primary goal and task encountered by OEMS. Operations and maintenance employees and contractors should be warned to avoid conducting any maintenance work which may disturb ACM/PACM. Initiating a work order system, where all work orders or requests are channeled through the Office of Environmental Management and Services (OEMS), will be the method used to control and minimize disruption of ACM/PACM.

Any work performed by in-house personnel or contractors that could or will impact ACM/PACM shall be coordinated by OEMS. A completed Asbestos Inspection Report Form (Attachment 1) shall be issued to in-house personnel and/or all contractors whose work could impact ACM/PACM. This form should accompany each contract issued to an outside contractor and posted on the jobsite.

All work order requests for maintenance and renovation activities in areas where ACM/PACM is suspected or known to be present are to be submitted to OEMS prior to proceeding with work. OEMS is responsible for reviewing asbestos survey records for information about the presence of ACM/PACM in the area where the work is to be performed. OEMS should physically inspect the area to ensure existing records reflect actual conditions. If no asbestos is present, a work order is not necessary and the planned actions can proceed. If ACM/PACM is found to be present in the area, OEMS will sign the work order application and obtain an approved and accredited asbestos contractor or assign OEMS "A-TEAM" to abate the ACM/PACM.

#### **ii. Regulated Areas**

The owner will identify and regulate all areas where airborne concentrations of ACM/PACM exceed the Permissible Exposure Limit (PEL)\* (Per OSHA determined to be 0.1 f/cc) and/or short term exposure limit (STEL) (Per OSHA determined to be 0.1 f/cc), or there is reasonable possibility that the (PEL) and/or (STEL) may be exceeded. All ACM/PACM removal activities involving thermal system insulation ACM/PACM (Class I), surfacing ACM/PACM (Class I), and miscellaneous ACM/PACM such as floor tile, roofing, and siding mastic, etc. (Class II), and repair and maintenance operations where thermal system insulation and surfacing ACM/PACM is likely to be disturbed (Class III) will be performed in accordance with federal, state, and local regulations. All asbestos abatement work and activities will be designed and managed as asbestos regulated areas. These areas will be demarcated and labeled.

#### **iii. Warning Signs**

Warning signs shall be displayed at all approaches to each asbestos regulated area. The asbestos abatement contractor will provide OSHA warning signs in all regulated areas during removal, repair, and other maintenance activities. OEMS will provide AIRs to all contractors who must inform all employees and supervisors working in locations contiguous to asbestos regulated areas of the potential hazards and work practices required.

#### **iv. Warning Labels**

Warning labels and/or signage shall be affixed to all raw materials, mixtures, scrap, waste, debris, and other products containing asbestos fibers, or to their containers. Generally, the asbestos abatement contractor or OEMS A-Team personnel will provide all warning labels for ACM/PACM containment.

## **8. O & M RESPONSE ACTIONS**

The Asbestos Management Program general O&M procedures are outlined in this section. Additional requirements specific to asbestos abatement activities are included in the Project Design documents for all Asbestos Abatement Work. Regular cleaning, inspection, and reporting of ACM/PACM deterioration or other problems must be diligently practiced by all employees including custodial and maintenance personnel.

### **a) Facility Maintenance Isolation of Area Responsibilities**

Maintenance personnel are often required to work in areas where ACM/PACM may potentially be disturbed. Most maintenance activities are conducted by in-house staff, outside contractors, or a combination.

Emergency fiber release episodes, such as pipe fitting or valve breaks, emergency boiler work, or mechanical equipment repair will be responded to by OEMS A-Team personnel or asbestos abatement contractor personnel. The owner's maintenance staff will: (1) isolate the emergency fiber release area; (2) post warning signs to prevent unauthorized access, and (3) notify their supervisor and OEMS. OEMS will ensure that the fiber release area remains isolated and is properly cleaned by and approved and accredited abatement contractor or by OEMS A-TEAM personnel.

### **b) Unlikely Contact with ACM/PACM**

Maintenance activities or repairs which can be performed without contacting or disturbing the ACM/PACM require little more than normal care and good workmanship. For example, valves which are either uncovered or covered with non-asbestos insulation can be packed or repaired without disturbing asbestos insulation on nearby pipes. The major precaution is to ensure that maintenance and custodial personnel are familiar with procedures such as isolating the area, posting warning signs, and notifying OEMS in the event of any accidental ACM/PACM disturbance.

### **c) Accidental Disturbance of ACM/PACM**

Maintenance and facilities personnel shall notify OEMS any time a fiber release is suspected. If friable ACM/PACM becomes airborne in the building,

### **d) Planned Disturbance of ACM/PACM**

Maintenance activities that may impact ACM/PACM include access to a valve, flange, duct, or related system component.

Where asbestos-containing insulation must be removed to maintain or repair the thermal system, the ACM/PACM will imminently be disturbed. ACM/PACM removal work shall be conducted by OEMS A-Team personnel or an approved and accredited asbestos abatement contractor.

If friable ACM/PACM becomes airborne in the building, maintenance and facilities personnel shall secure the area and contact OEMS. OEMS shall respond accordingly.

**e) Miscellaneous ACM/PACM**

Miscellaneous types of ACM/PACM may include vinyl asbestos floor tiles, mastics/adhesives and woven vibration dampers. Disturbance of these materials should be avoided. Routine maintenance activities involving these materials should not pose a problem if handled properly. Questions on the proper removal and disposal of miscellaneous ACM/PACM should be directed to OEMS. OEMS will contact an approved and accredited asbestos abatement contractor or utilize OEMS A-TEAM personnel to assist with miscellaneous ACM/PACM clean-up activities.

**f) Vinyl Asbestos Floor Tile**

Asbestos-containing floor tiles in good condition are considered non-friable unless they are crushed, drilled, sawed, sanded or disturbed by any activity that breaks up the material. Routine maintenance of these materials should employ the use of non-abrasive buffers and wet cleaning technique. Broken or loose floor tiles should be removed and disposed of as asbestos waste by OEMS. Remaining debris should be vacuumed with a HEPA vacuum and the area wet mopped using amended water.

**g) Mastics/Adhesives**

Mastics and adhesives containing asbestos in good condition are considered non-friable and do not pose a potential health concern unless crushed, drilled, sawed, sanded, or otherwise abraded. Questions on the proper removal should be directed to OEMS.

**h) Woven Vibration Dampers**

Woven vibration dampers in good condition are considered non-friable and do not pose a potential health concern unless cut, crushed, drilled, sawed, sanded, or otherwise abraded. Questions on the proper removal should be directed to OEMS.

**i) Other Work Practices**

Any special work not included in this section should be addressed to OEMS for review prior to the initiation of work that may involve the disturbance of ACM/PACM.

**j) Fiber Release Episodes**

Facilities and maintenance staff should report to OEMS the presence of asbestos debris, water or physical damage to ACM/PACM, or any other evidence of possible fiber release. OEMS should have the OEMS A-Team personnel or an approved and accredited abatement contractor respond to the site to clean up debris and make repairs as soon as possible. OEMS will also contact a consultant to conduct air monitoring and prepare a report and submit at project completion to OEMS for each episode. OEMS will forward the reports for each site location AHERA Management Plan accordingly.



## 9. REFERENCES and RESOURCES

Applicable regulations for asbestos projects impacted by renovation, demolition, and maintenance activities.

- **Philadelphia Air Management Services – Asbestos Control Unit**  
<http://www.phila.gov/health/units/ams/Asbestos/asbestos.html>
- **Pennsylvania Asbestos Occupations, Accreditation and Certification Act**  
<http://www.dli.state.pa.us/landi/cwp/view.asp?a=185&q=56262&landiNav=>
- **United States Environmental Protection Agency Asbestos Home Page**  
<http://www.epa.gov/asbestos/>
- **Occupational Safety and Health Administration (OSHA) Asbestos Home**  
<http://www.osha.gov/SLTC/asbestos>