



**SCHOOL DISTRICT OF PHILADELPHIA  
BOARD OF EDUCATION  
Office of Capital Programs  
440 North Broad Street, 3<sup>rd</sup> Floor – Suite 371  
Philadelphia, PA 19130**

TELEPHONE: (215) 400-4730

**Addendum No. 3**

**Subject: Mayfair Addition B001C/002C/003C/004C of 2022-23**

**Location: 2901 Princeton Ave**

---

**This Addendum, dated November 30, 2021, shall modify and become part of the Contract Documents. Any items not mentioned herein, or affected by, shall remain strictly in accordance with the original document.**

---

**Time of Bid:**

Bids are due at 2pm on Thursday, 2<sup>nd</sup> December

**Questions & Answers:**

**Question 1:** The number of P-6 fixtures shown on addendum drawing P103 on the 1st floor still doesn't match the number of P-6 fixtures (and piping) shown on the addendum drawing P501 riser. Which is correct?

**Answer 1:** The total number P-6 fixtures shall be five (5) as shown on P103.

**Question 2:** Please confirm that the 1/8"=1' scale on Plumbing drawings P102, P103, and P104 are incorrect (and advise what the correct scale should be).

**Answer 2:** Correct Scale for P102, P103, P104, and M102 drawings shall be 1/4" = 1'

**Question 3:** Key Notes 4&6 associated with Detail 1 on Drawings E503 seem contradictory, Note 4 indicates that CCTV Cabling can be installed, plenum, on the J-Hooks while Note 6 calls for all cabling to be installed in 3/4" conduit. Which is correct?

**Answer 3:** CCTV cables in spaces with hung ceiling shall be supported on J-hooks. However, CCTV cables in open ceiling spaces (exposed) and vertical cable drops in walls and risers shall be run in conduits.

**Addendum No. 3 (cont'd)**

**Question 4:** There are multiple instances in the drawings that call for 10" Ivany block CMU but Ivany does not make a 10" mold, only 8" and 12". Please advise?

**Answer 4:** Where 10" Ivany is indicated, 10" High Strength Block ( $f'm = 2500$  psi) can be used.

**End of Addendum #3**