

			School District of Philadelphia								
			Name of Inspector: Michael Barth, Melissa Billingsley		Lead Safe Certification Assessment Report						
			Inspection Company: Criterion Labs., Inc.		Taylor Elementary School and Annex						
E l e m e n t	F l o o r	Space #	On-Site Room Name	Student/ Teacher Occupied (yes/no)	Component	Substrate Material	Color	Description of Damage	Damage Quantity (sf)	XRF Reading (mg/cm2)	XRF (positive/ negative)
1	3	310A	Classroom 300	yes	Door Frame (W1)	Wood	Blue	Chipping	1	1.4	Positive
1	3	310A	Classroom 300	yes	W1	Concrete	Blue	None	0	N/A	N/A
1	3	310A	Classroom 300	yes	Door Cage (W1)	Metal	Black	Chipping	1	0	Negative
1	3	310A	Classroom 300	yes	W2	Plaster	Blue	None	0	N/A	N/A
1	3	310A	Classroom 300	yes	W3	Plaster	Blue	Moisture Damage	10	5.3	Positive
1	3	310A	Classroom 300	yes	Radiator (W3)	Metal	Blue	None	0	N/A	N/A
1	3	310A	Classroom 300	yes	Window Stool (W3)	Wood	Blue	Chipping	1	2.3	Positive
1	3	310A	Classroom 300	yes	W4	Plaster	Blue	Flaking	1	10.1	Positive
1	3	310A	Classroom 300	yes	Floor	N/A	N/A	N/A	N/A	N/A	N/A
1	3	310A	Classroom 300	yes	Ceiling	N/A	N/A	N/A	N/A	N/A	N/A
1	3	NP2	Classroom 300 Staff Restroom	yes	Door Frame (W1)	Metal	White	Chipping	1	0.02	Negative
1	3	NP2	Classroom 300 Staff Restroom	yes	W1	Concrete	White	None	0	N/A	N/A
1	3	NP2	Classroom 300 Staff Restroom	yes	W2	Plaster	White	None	0	N/A	N/A
1	3	NP2	Classroom 300 Staff Restroom	yes	W3	Concrete	White	None	0	N/A	N/A
1	3	NP2	Classroom 300 Staff Restroom	yes	W4	Concrete	White	None	0	N/A	N/A
1	3	NP2	Classroom 300 Staff Restroom	yes	Floor	N/A	N/A	N/A	N/A	N/A	N/A
1	3	NP2	Classroom 300 Staff Restroom	yes	Ceiling	Plaster	White	None	0	N/A	N/A
1	3	301	Classroom 301	yes	W1	Plaster	Tan	None	0	N/A	N/A
1	3	301	Classroom 301	yes	Door (W1)	Wood	Tan	None	0	N/A	N/A
1	3	301	Classroom 301	yes	Cove Base (W1)	Concrete	Tan	Flaking	3	3.4	Positive
1	3	301	Classroom 301	yes	W1	Plaster	White	None	0	N/A	N/A

			School District of Philadelphia								
			Name of Inspector: Michael Barth, Melissa Billingsley		Lead Safe Certification Assessment Report						
			Inspection Company: Criterion Labs., Inc.		Taylor Elementary School and Annex						
E l e m e n t	F l o o r	Space #	On-Site Room Name	Student/ Teacher Occupied (yes/no)	Component	Substrate Material	Color	Description of Damage	Damage Quantity (sf)	XRF Reading (mg/cm2)	XRF (positive/ negative)
1	3	301	Classroom 301	yes	Chalkboard (W2)	Wood	Blue	None	0	N/A	N/A
1	3	301	Classroom 301	yes	Chalkboard (W2)	Wood	Tan	None	0	N/A	N/A
1	3	301	Classroom 301	yes	W2	Plaster	White	None	0	N/A	N/A
1	3	301	Classroom 301	yes	Cove Base (W2)	Concrete	Tan	Chipping	3	2.2	Positive
1	3	301	Classroom 301	yes	Radiator (W3)	Metal	Tan	Chipping	10	5.4	Positive
1	3	301	Classroom 301	yes	Window Stool (W3)	Wood	Tan	Cracking	5	10.2	Positive
1	3	301	Classroom 301	yes	W3	Plaster	White	None	0	N/A	N/A
1	3	301	Classroom 301	yes	W3	Plaster	Blue	None	0	N/A	N/A
1	3	301	Classroom 301	yes	W4	Plaster	Tan	Flaking	1	8.9	Positive
1	3	301	Classroom 301	yes	Chalkboard (W4)	Wood	Tan	Cracking	1	0.03	Negative
1	3	301	Classroom 301	yes	Floor	N/A	N/A	N/A	N/A	N/A	N/A
1	3	301	Classroom 301	yes	Ceiling	N/A	N/A	N/A	N/A	N/A	N/A
1	3	301A	Classroom 301 Storage	yes	W1	Plaster	Tan	None	0	N/A	N/A
1	3	301A	Classroom 301 Storage	yes	Door (W1)	Wood	Tan	Chipping	1	0.01	Negative
1	3	301A	Classroom 301 Storage	yes	W2	Plaster	Tan	Efflorescence	10	15.4	Positive
1	3	301A	Classroom 301 Storage	yes	Cove Base (W2)	Concrete	Tan	Chipping	3	0.03	Negative
1	3	301A	Classroom 301 Storage	yes	Radiator (W3)	Metal	Tan	None	0	N/A	N/A
1	3	301A	Classroom 301 Storage	yes	Window Stool (W3)	Wood	Tan	Cracking	1	0.01	Negative
1	3	301A	Classroom 301 Storage	yes	W3	Plaster	Tan	Chipping	1	0	Negative
1	3	301A	Classroom 301 Storage	yes	Cove Base (W3)	Concrete	Tan	Chipping	1	0.03	Negative

			School District of Philadelphia								
			Name of Inspector: Michael Barth, Melissa Billingsley		Lead Safe Certification Assessment Report						
			Inspection Company: Criterion Labs., Inc.		Taylor Elementary School and Annex						
E l e m e n t	F l o o r	Space #	On-Site Room Name	Student/ Teacher Occupied (yes/no)	Component	Substrate Material	Color	Description of Damage	Damage Quantity (sf)	XRF Reading (mg/cm2)	XRF (positive/ negative)
1	3	301A	Classroom 301 Storage	yes	W4	Plaster	Tan	None	0	N/A	N/A
1	3	301A	Classroom 301 Storage	yes	Cove Base (W4)	Concrete	Tan	Chipping	1	0	Negative
1	3	301A	Classroom 301 Storage	yes	Floor	N/A	N/A	N/A	N/A	N/A	N/A
1	3	301A	Classroom 301 Storage	yes	Ceiling	Plaster	White	None	0	N/A	N/A
1	3	302	Classroom 302	yes	W1	Plaster	White	None	0	N/A	N/A
1	3	302	Classroom 302	yes	W1	Plaster	Tan	None	0	N/A	N/A
1	3	302	Classroom 302	yes	Door Frame (W1)	Wood	White	None	0	N/A	N/A
1	3	302	Classroom 302	yes	Door (W1)	Wood	Tan	Chipping	3	0.03	Negative
1	3	302	Classroom 302	yes	Door Cage (W1)	Metal	Black	None	0	N/A	N/A
1	3	302	Classroom 302	yes	W2	Plaster	Tan	None	0	N/A	N/A
1	3	302	Classroom 302	yes	W2	Plaster	White	None	0	N/A	N/A
1	3	302	Classroom 302	yes	Chalkboard (W2)	Wood	Tan	Chipping	5	0	Negative
1	3	302	Classroom 302	yes	W3	Plaster	Tan	None	0	N/A	N/A
1	3	302	Classroom 302	yes	W3	Plaster	White	Moisture Damage	3	11.5	Positive
1	3	302	Classroom 302	yes	Window Stool (W3)	Wood	Tan	Chipping	1	0	Negative
1	3	302	Classroom 302	yes	Radiator (W3)	Metal	Tan	Chipping	1	0.02	Negative
1	3	302	Classroom 302	yes	W4	Plaster	Tan	None	0	N/A	N/A
1	3	302	Classroom 302	yes	W4	Plaster	White	None	0	N/A	N/A
1	3	302	Classroom 302	yes	Chalkboard (W4)	Wood	Tan	None	0	N/A	N/A
1	3	302	Classroom 302	yes	Floor	Wood	N/A	N/A	0	N/A	N/A
1	3	302	Classroom 302	yes	Ceiling	N/A	N/A	N/A	N/A	N/A	N/A
1	3	302A	Classroom 302 Storage	yes	W1	Plaster	White	None	0	N/A	N/A

			School District of Philadelphia								
			Name of Inspector: Michael Barth, Melissa Billingsley		Lead Safe Certification Assessment Report						
			Inspection Company: Criterion Labs., Inc.		Taylor Elementary School and Annex						
E l e m e n t	F l o o r	Space #	On-Site Room Name	Student/ Teacher Occupied (yes/no)	Component	Substrate Material	Color	Description of Damage	Damage Quantity (sf)	XRF Reading (mg/cm2)	XRF (positive/ negative)
1	3	302A	Classroom 302 Storage	yes	Door Frame (W1)	Wood	White	Chipping	1	0	Negative
1	3	302A	Classroom 302 Storage	yes	W2	Plaster	White	None	0	N/A	N/A
1	3	302A	Classroom 302 Storage	yes	Chalkboard (W2)	Wood	White	Cracking	1	0.01	Negative
1	3	302A	Classroom 302 Storage	yes	W3	Plaster	White	Moisture Damage	5	10.4	Positive
1	3	302A	Classroom 302 Storage	yes	Window Stool (W3)	Wood	White	None	0	N/A	N/A
1	3	302A	Classroom 302 Storage	yes	W4	Plaster	White	Cracking	5	9.1	Positive
1	3	302A	Classroom 302 Storage	yes	Chalkboard (W4)	Wood	White	None	0	N/A	N/A
1	3	302A	Classroom 302 Storage	yes	Floor	N/A	N/A	N/A	N/A	N/A	N/A
1	3	302A	Classroom 302 Storage	yes	Ceiling	N/A	N/A	N/A	N/A	N/A	N/A
1	3	S31	Stairwell next to Classroom 302	yes	W1	Plaster	Tan	Chipping	2	0	Negative
1	3	S31	Stairwell next to Classroom 302	yes	W1	Plaster	White	None	0	N/A	N/A
1	3	S31	Stairwell next to Classroom 302	yes	Stair Post (W1)	Wood	Grey	Chipping	1	0	Negative
1	3	S31	Stairwell next to Classroom 302	yes	W2	Plaster	Tan	Hole	2	0.01	Negative
1	3	S31	Stairwell next to Classroom 302	yes	W2	Plaster	White	None	0	N/A	N/A
1	3	S31	Stairwell next to Classroom 302	yes	Handrail (W2)	Wood	Brown	Friction	3	0	Negative

			School District of Philadelphia								
			Name of Inspector: Michael Barth, Melissa Billingsley		Lead Safe Certification Assessment Report						
			Inspection Company: Criterion Labs., Inc.		Taylor Elementary School and Annex						
E l e m e n t	F l o o r	Space #	On-Site Room Name	Student/ Teacher Occupied (yes/no)	Component	Substrate Material	Color	Description of Damage	Damage Quantity (sf)	XRF Reading (mg/cm2)	XRF (positive/ negative)
1	3	S31	Stairwell next to Classroom 302	yes	W3	Plaster	Tan	None	0	N/A	N/A
1	3	S31	Stairwell next to Classroom 302	yes	W3	Plaster	White	None	0	N/A	N/A
1	3	S31	Stairwell next to Classroom 302	yes	Door (W3)	Metal	Grey	None	0	N/A	N/A
1	3	S31	Stairwell next to Classroom 302	yes	W4	Plaster	Tan	None	0	N/A	N/A
1	3	S31	Stairwell next to Classroom 302	yes	W4	Plaster	White	None	0	N/A	N/A
1	3	S31	Stairwell next to Classroom 302	yes	Radiator (W4)	Metal	Grey	None	0	N/A	N/A
1	3	S31	Stairwell next to Classroom 302	yes	Floor	Concrete	Red	Friction	3	0.3	Negative
1	3	S31	Stairwell next to Classroom 302	yes	Floor	Concrete	Black	Friction	3	0	Negative
1	3	S31	Stairwell next to Classroom 302	yes	Ceiling	N/A	N/A	N/A	N/A	N/A	N/A
1	3	303	Classroom 303	yes	W1	Plaster	White	None	0	N/A	N/A
1	3	303	Classroom 303	yes	W1	Plaster	Purple	Chipping	2	1.6	Positive
1	3	303	Classroom 303	yes	W1	Plaster	Blue	None	0	N/A	N/A
1	3	303	Classroom 303	yes	Door (W1)	Wood	White	Chipping	1	0	Negative
1	3	303	Classroom 303	yes	W2	Plaster	White	None	0	N/A	N/A
1	3	303	Classroom 303	yes	W2	Plaster	Blue	None	0	N/A	N/A
1	3	303	Classroom 303	yes	Chalkboard (W2)	Wood	White	None	0	N/A	N/A
1	3	303	Classroom 303	yes	W3	Plaster	White	Moisture Damage	5	3.4	Positive
1	3	303	Classroom 303	yes	W3	Plaster	Blue	None	0	N/A	N/A
1	3	303	Classroom 303	yes	Radiator (W3)	Metal	Blue	Chipping	1	0.01	Negative
1	3	303	Classroom 303	yes	Radiator (W3)	Metal	Purple	Chipping	5	0	Negative

			School District of Philadelphia								
			Name of Inspector: Michael Barth, Melissa Billingsley		Lead Safe Certification Assessment Report						
			Inspection Company: Criterion Labs., Inc.		Taylor Elementary School and Annex						
E l e m e n t	F l o o r	Space #	On-Site Room Name	Student/ Teacher Occupied (yes/no)	Component	Substrate Material	Color	Description of Damage	Damage Quantity (sf)	XRF Reading (mg/cm2)	XRF (positive/ negative)
1	3	303	Classroom 303	yes	Window Stool (W3)	Wood	Purple	Cracking	1	1.7	Positive
1	3	303	Classroom 303	yes	W4	Plaster	White	None	0	N/A	N/A
1	3	303	Classroom 303	yes	W4	Plaster	Purple	None	0	N/A	N/A
1	3	303	Classroom 303	yes	W4	Plaster	Blue	None	0	N/A	N/A
1	3	303	Classroom 303	yes	Chalkboard (W4)	Wood	White	Chipping	1	0.03	Negative
1	3	303	Classroom 303	yes	Floor	Wood	N/A	N/A	0	N/A	N/A
1	3	303	Classroom 303	yes	Ceiling	N/A	N/A	N/A	N/A	N/A	N/A
1	3	303A	Classroom 303 Storage	yes	W1	Plaster	White	None	0	N/A	N/A
1	3	303A	Classroom 303 Storage	yes	Door (W1)	Wood	White	Cracking	2	0	Negative
1	3	303A	Classroom 303 Storage	yes	W2	Plaster	White	Cracking	2	4.3	Positive
1	3	303A	Classroom 303 Storage	yes	Cove Base (W2)	Wood	White	None	0	N/A	N/A
1	3	303A	Classroom 303 Storage	yes	W3	Plaster	White	None	0	N/A	N/A
1	3	303A	Classroom 303 Storage	yes	Cove Base (W3)	Wood	White	None	0	N/A	N/A
1	3	303A	Classroom 303 Storage	yes	Cove Base (W3)	Wood	Purple	None	0	N/A	N/A
1	3	303A	Classroom 303 Storage	yes	W4	Plaster	White	Chipping	1	5.4	Positive
1	3	303A	Classroom 303 Storage	yes	Cove Base (W4)	Wood	White	Chipping	1	1.1	Positive
1	3	303A	Classroom 303 Storage	yes	Floor	Wood	N/A	N/A	N/A	N/A	N/A
1	3	303A	Classroom 303 Storage	yes	Ceiling	N/A	N/A	N/A	N/A	N/A	N/A

			School District of Philadelphia								
			Name of Inspector: Michael Barth, Melissa Billingsley		Lead Safe Certification Assessment Report						
			Inspection Company: Criterion Labs., Inc.		Taylor Elementary School and Annex						
E l e m e n t	F l o o r	Space #	On-Site Room Name	Student/ Teacher Occupied (yes/no)	Component	Substrate Material	Color	Description of Damage	Damage Quantity (sf)	XRF Reading (mg/cm2)	XRF (positive/ negative)
1	3	304	Classroom 304	yes	W1	Plaster	Tan	Chipping	1	6.7	Positive
1	3	304	Classroom 304	yes	W1	Plaster	White	None	0	N/A	N/A
1	3	304	Classroom 304	yes	W1	Plaster	Blue	None	0	N/A	N/A
1	3	304	Classroom 304	yes	Door (W1)	Wood	Tan	Chipping	3	0.02	Negative
1	3	304	Classroom 304	yes	Door Frame (W1)	Wood	White	None	0	N/A	N/A
1	3	304	Classroom 304	yes	W2	Plaster	White	None	0	N/A	N/A
1	3	304	Classroom 304	yes	Chalkboard (W2)	Wood	White	Chipping	1	0	Negative
1	3	304	Classroom 304	yes	Chalkboard (W2)	Wood	Blue	None	0	N/A	N/A
1	3	304	Classroom 304	yes	W3	Plaster	White	None	0	N/A	N/A
1	3	304	Classroom 304	yes	W3	Plaster	Blue	None	0	N/A	N/A
1	3	304	Classroom 304	yes	Radiator (W3)	Metal	Blue	Chipping	1	0	Negative
1	3	304	Classroom 304	yes	Window Stool (W3)	Wood	White	Cracking	2	0	Negative
1	3	304	Classroom 304	yes	W4	Plaster	Tan	None	0	N/A	N/A
1	3	304	Classroom 304	yes	W4	Plaster	White	None	0	N/A	N/A
1	3	304	Classroom 304	yes	Chalkboard (W4)	Wood	Tan	None	0	N/A	N/A
1	3	304	Classroom 304	yes	Chalkboard (W4)	Wood	White	None	0	N/A	N/A
1	3	304	Classroom 304	yes	Floor	Wood	N/A	N/A	N/A	N/A	N/A
1	3	304	Classroom 304	yes	Ceiling	N/A	N/A	N/A	N/A	N/A	N/A
1	3	304A	Classroom 304 Storage	yes	W1	Plaster	Tan	None	0	N/A	N/A
1	3	304A	Classroom 304 Storage	yes	Cove Base (W1)	Wood	Tan	None	0	N/A	N/A
1	3	304A	Classroom 304 Storage	yes	W2	Plaster	Tan	Cracking	3	0.03	Negative
1	3	304A	Classroom 304 Storage	yes	Cove Base (W2)	Wood	Tan	None	0	N/A	N/A

			School District of Philadelphia								
			Name of Inspector: Michael Barth, Melissa Billingsley		Lead Safe Certification Assessment Report						
			Inspection Company: Criterion Labs., Inc.		Taylor Elementary School and Annex						
E l e m e n t	F l o o r	Space #	On-Site Room Name	Student/ Teacher Occupied (yes/no)	Component	Substrate Material	Color	Description of Damage	Damage Quantity (sf)	XRF Reading (mg/cm2)	XRF (positive/ negative)
1	3	304A	Classroom 304 Storage	yes	W3	Plaster	Tan	None	0	N/A	N/A
1	3	304A	Classroom 304 Storage	yes	Cove Base (W3)	Wood	Tan	None	0	N/A	N/A
1	3	304A	Classroom 304 Storage	yes	W4	Plaster	Tan	None	0	N/A	N/A
1	3	304A	Classroom 304 Storage	yes	Cove Base (W4)	Wood	Tan	Chipping	1	0	Negative
1	3	304A	Classroom 304 Storage	yes	Floor	Wood	N/A	N/A	0	N/A	N/A
1	3	304A	Classroom 304 Storage	yes	Ceiling	N/A	N/A	N/A	N/A	N/A	N/A
1	3	305	Classroom 305	yes	W1	Plaster	Green	None	0	N/A	N/A
1	3	305	Classroom 305	yes	Door (W1)	Wood	Green	None	0	N/A	N/A
1	3	305	Classroom 305	yes	Cove Base (W1)	Concrete	Green	Friction	3	0	Negative
1	3	305	Classroom 305	yes	W2	Plaster	Green	None	0	N/A	N/A
1	3	305	Classroom 305	yes	Chalkboard (W2)	Wood	Green	None	0	N/A	N/A
1	3	305	Classroom 305	yes	Cove Base (W2)	Concrete	Green	None	0	N/A	N/A
1	3	305	Classroom 305	yes	Radiator (W2)	Metal	Green	Chipping	1	0	Negative
1	3	305	Classroom 305	yes	W3	Plaster	Green	None	0	N/A	N/A
1	3	305	Classroom 305	yes	Window Stool (W3)	Wood	Green	Cracking	1	0	Negative
1	3	305	Classroom 305	yes	Radiator (W3)	Metal	Green	Chipping	3	0	Negative
1	3	305	Classroom 305	yes	W4	Plaster	Green	None	0	N/A	N/A
1	3	305	Classroom 305	yes	Chalkboard (W4)	Wood	Green	None	0	N/A	N/A
1	3	305	Classroom 305	yes	Floor	Wood	N/A	N/A	0	N/A	N/A
1	3	305	Classroom 305	yes	Ceiling	N/A	N/A	N/A	N/A	N/A	N/A
1	3	305A	Classroom 305 Storage	yes	W1	Plaster	White	None	0	N/A	N/A

			School District of Philadelphia								
			Name of Inspector: Michael Barth, Melissa Billingsley		Lead Safe Certification Assessment Report						
			Inspection Company: Criterion Labs., Inc.		Taylor Elementary School and Annex						
E l e m e n t	F l o o r	Space #	On-Site Room Name	Student/ Teacher Occupied (yes/no)	Component	Substrate Material	Color	Description of Damage	Damage Quantity (sf)	XRF Reading (mg/cm2)	XRF (positive/ negative)
1	3	305A	Classroom 305 Storage	yes	Cove Base (W1)	Concrete	Purple	None	0	N/A	N/A
1	3	305A	Classroom 305 Storage	yes	W2	Plaster	White	None	0	N/A	N/A
1	3	305A	Classroom 305 Storage	yes	Cove Base (W2)	Concrete	Purple	None	0	N/A	N/A
1	3	305A	Classroom 305 Storage	yes	W3	Plaster	White	None	0	N/A	N/A
1	3	305A	Classroom 305 Storage	yes	Cove Base (W3)	Concrete	Purple	None	0	N/A	N/A
1	3	305A	Classroom 305 Storage	yes	W4	Plaster	White	None	0	N/A	N/A
1	3	305A	Classroom 305 Storage	yes	Cove Base (W4)	Concrete	Purple	None	0	N/A	N/A
1	3	305A	Classroom 305 Storage	yes	Floor	N/A	N/A	N/A	N/A	N/A	N/A
1	3	305A	Classroom 305 Storage	yes	Ceiling	N/A	N/A	N/A	N/A	N/A	N/A
1	3	306	Classroom 306	yes	W1	Plaster	White	None	0	N/A	N/A
1	3	306	Classroom 306	yes	W1	Plaster	Blue	None	0	N/A	N/A
1	3	306	Classroom 306	yes	Door (W1)	Wood	White	Chipping	3	0	Negative
1	3	306	Classroom 306	yes	Chalkboard (W1)	Wood	Blue	Chipping	1	0	Negative
1	3	306	Classroom 306	yes	W2	Plaster	Blue	None	0	N/A	N/A
1	3	306	Classroom 306	yes	Chalkboard (W2)	Wood	Blue	None	0	N/A	N/A
1	3	306	Classroom 306	yes	W3	Plaster	Dark Blue	None	0	N/A	N/A
1	3	306	Classroom 306	yes	W3	Plaster	Light Blue	None	0	N/A	N/A
1	3	306	Classroom 306	yes	Radiator (W3)	Metal	Blue	Chipping	3	0	Negative
1	3	306	Classroom 306	yes	WIndow Stool (W3)	Wood	Blue	Chipping	3	0.03	Negative
1	3	306	Classroom 306	yes	W4	Plaster	Blue	Chipping	1	4.5	Positive

			School District of Philadelphia								
			Name of Inspector: Michael Barth, Melissa Billingsley		Lead Safe Certification Assessment Report						
			Inspection Company: Criterion Labs., Inc.		Taylor Elementary School and Annex						
E l e m e n t	F l o o r	Space #	On-Site Room Name	Student/ Teacher Occupied (yes/no)	Component	Substrate Material	Color	Description of Damage	Damage Quantity (sf)	XRF Reading (mg/cm2)	XRF (positive/ negative)
1	3	306	Classroom 306	yes	Chalkboard (W4)	Wood	Blue	None	0	N/A	N/A
1	3	306	Classroom 306	yes	Chalkboard (W4)	Wood	White	None	0	N/A	N/A
1	3	306	Classroom 306	yes	Small Closet Space (W4)	Metal	White	None	0	N/A	N/A
1	3	306	Classroom 306	yes	Small Closet Space Interior (W4)	Plaster	Tan	Chipping	1	3.3	Positive
1	3	306	Classroom 306	yes	Small Closet Space Interior Shelving (W4)	Wood	Tan	Cracking	1	0	Negative
1	3	306	Classroom 306	yes	Floor	Wood	N/A	N/A	0	N/A	N/A
1	3	306	Classroom 306	yes	Ceiling	N/A	N/A	N/A	N/A	N/A	N/A
1	3	306A	Classroom 306 Storage	yes	W1	Plaster	Tan	None	0	N/A	N/A
1	3	306A	Classroom 306 Storage	yes	Door Frame (W1)	Wood	Tan	Friction	1	0	Negative
1	3	306A	Classroom 306 Storage	yes	Cove Base (W1)	Concrete	Purple	None	0	N/A	N/A
1	3	306A	Classroom 306 Storage	yes	W2	Plaster	Tan	Chipping	2	0.2	Negative
1	3	306A	Classroom 306 Storage	yes	Shelving (W2)	Wood	Tan	None	0	N/A	N/A
1	3	306A	Classroom 306 Storage	yes	Cove Base (W2)	Concrete	Purple	Friction	2	0	Negative
1	3	306A	Classroom 306 Storage	yes	W3	Plaster	Tan	None	0	N/A	N/A
1	3	306A	Classroom 306 Storage	yes	Window Stool (W3)	Wood	Tan	None	0	N/A	N/A
1	3	306A	Classroom 306	yes	Cove Base (W3)	Concrete	Purple	Friction	1	0	Negative
1	3	306A	Classroom 306	yes	W4	Plaster	Tan	N/A	1	0	Negative

			School District of Philadelphia								
			Name of Inspector: Michael Barth, Melissa Billingsley		Lead Safe Certification Assessment Report						
			Inspection Company: Criterion Labs., Inc.		Taylor Elementary School and Annex						
E l e m e n t	F l o o r	Space #	On-Site Room Name	Student/ Teacher Occupied (yes/no)	Component	Substrate Material	Color	Description of Damage	Damage Quantity (sf)	XRF Reading (mg/cm2)	XRF (positive/ negative)
1	3	306A	Classroom 306 Storage	yes	Shelving (W4)	Wood	Tan	None	0	N/A	N/A
1	3	306A	Classroom 306 Storage	yes	Door Frame (W4)	Metal	Tan	Chipping	1	0	Negative
1	3	306A	Classroom 306 Storage	yes	Cove Base (W4)	Concrete	Purple	Friction	1	0.03	Negative
1	3	306A	Classroom 306 Storage	yes	Floor	Wood	N/A	N/A	0	N/A	N/A
1	3	306A	Classroom 306 Storage	yes	Ceiling	N/A	N/A	N/A	N/A	N/A	N/A
1	3	S32	Stairwell next to Classroom 306	yes	W1	Plaster	Tan	Chipping	2	3.4	Positive
1	3	S32	Stairwell next to Classroom 306	yes	W1	Plaster	White	None	0	N/A	N/A
1	3	S32	Stairwell next to Classroom 306	yes	Stairs (W1)	Concrete	Grey	None	0	N/A	N/A
1	3	S32	Stairwell next to Classroom 306	yes	W2	Plaster	Tan	None	0	N/A	N/A
1	3	S32	Stairwell next to Classroom 306	yes	W2	Plaster	White	None	0	N/A	N/A
1	3	S32	Stairwell next to Classroom 306	yes	Stair Riser (W2)	Concrete	Grey	None	0	N/A	N/A
1	3	S32	Stairwell next to Classroom 306	yes	Handrail (W2)	Wood	Brown	Friction	1	0	Negative
1	3	S32	Stairwell next to Classroom 306	yes	Stair Posts (W2)	Metal	Grey	None	0	N/A	N/A
1	3	S32	Stairwell next to Classroom 306	yes	W3	Plaster	Tan	None	0	N/A	N/A
1	3	S32	Stairwell next to Classroom 306	yes	W3	Plaster	White	None	0	N/A	N/A

			School District of Philadelphia								
			Name of Inspector: Michael Barth, Melissa Billingsley		Lead Safe Certification Assessment Report						
			Inspection Company: Criterion Labs., Inc.		Taylor Elementary School and Annex						
E l e m e n t	F l o o r	Space #	On-Site Room Name	Student/ Teacher Occupied (yes/no)	Component	Substrate Material	Color	Description of Damage	Damage Quantity (sf)	XRF Reading (mg/cm2)	XRF (positive/ negative)
1	3	S32	Stairwell next to Classroom 306	yes	Door (W3)	Metal	Grey	Friction	1	0	Negative
1	3	S32	Stairwell next to Classroom 306	yes	Stairs (W3)	Concrete	Grey	Friction	2	N/A	N/A
1	3	S32	Stairwell next to Classroom 306	yes	Handrail (W3)	Wood	Brown	Friction	2	0	Negative
1	3	S32	Stairwell next to Classroom 306	yes	W4	Plaster	Tan	Hole	1	N/A	N/A
1	3	S32	Stairwell next to Classroom 306	yes	W4	Plaster	White	None	0	N/A	N/A
1	3	S32	Stairwell next to Classroom 306	yes	Stiar Riser (W4)	Concrete	Grey	None	0	N/A	N/A
1	3	S32	Stairwell next to Classroom 306	yes	Floor	Concrete	Red	Friction	3	0.3	Negative
1	3	S32	Stairwell next to Classroom 306	yes	Floor	Concrete	Black	Friction	5	0.02	Negative
1	3	S32	Stairwell next to Classroom 306	yes	Ceiling	N/A	N/A	N/A	N/A	N/A	N/A
1	3	S33	3rd Floor Fire Tower	no	W1	Brick	White	None	0	N/A	N/A
1	3	S33	3rd Floor Fire Tower	no	W2	Brick	White	None	0	N/A	N/A
1	3	S33	3rd Floor Fire Tower	no	W3	Brick	White	None	0	N/A	N/A
1	3	S33	3rd Floor Fire Tower	no	W4	Brick	White	None	0	N/A	N/A
1	3	S33	3rd Floor Fire Tower	no	Floor	Concrete	N/A	None	0	N/A	N/A
1	3	S33	3rd Floor Fire Tower	no	Ceiling	Plaster	White	Moisture Damage	10	0.02	Negative
1	3	306B	Boy's Restroom next to Classroom 306	yes	W1	Plaster	White	None	0	N/A	N/A
1	3	306B	Boy's Restroom next to Classroom 306	yes	W2	Plaster	White	None	0	N/A	N/A

			School District of Philadelphia								
			Name of Inspector: Michael Barth, Melissa Billingsley		Lead Safe Certification Assessment Report						
			Inspection Company: Criterion Labs., Inc.		Taylor Elementary School and Annex						
E l e m e n t	F l o o r	Space #	On-Site Room Name	Student/ Teacher Occupied (yes/no)	Component	Substrate Material	Color	Description of Damage	Damage Quantity (sf)	XRF Reading (mg/cm2)	XRF (positive/ negative)
1	3	306B	Boy's Restroom next to Classroom 306	yes	W3	Plaster	White	None	0	N/A	N/A
1	3	306B	Boy's Restroom next to Classroom 306	yes	W4	Plaster	White	None	0	N/A	N/A
1	3	306B	Boy's Restroom next to Classroom 306	yes	Floor	N/A	N/A	None	0	N/A	N/A
1	3	306B	Boy's Restroom next to Classroom 306	yes	Ceiling	Plaster	White	Flaking	1	0	Negative
1	3	NP3	Custodial Closet next to Boy's Restroom	no	W1	Concrete	White	None	0	N/A	N/A
1	3	NP3	Custodial Closet next to Boy's Restroom	no	W2	Concrete	White	None	0	N/A	N/A
1	3	NP3	Custodial Closet next to Boy's Restroom	no	W3	Concrete	White	None	0	N/A	N/A
1	3	NP3	Custodial Closet next to Boy's Restroom	no	W4	Concrete	White	None	0	N/A	N/A
1	3	NP3	Custodial Closet next to Boy's Restroom	no	Floor	N/A	N/A	N/A	N/A	N/A	N/A
1	3	NP3	Custodial Closet next to Boy's Restroom	no	Ceiling	N/A	N/A	N/A	N/A	N/A	N/A
1	3	H37	3rd Floor Hallway	yes	W1	Plaster	Blue	Flaking	15	3.2	Positive
1	3	H37	3rd Floor Hallway	yes	Fire Extinguisher Box (W1)	Metal	Red	Chipping	1	0.02	Negative
1	3	H37	3rd Floor Hallway	yes	Door (W1)	Metal	Grey	None	0	N/A	N/A
1	3	H37	3rd Floor Hallway	yes	Door Frame (W1)	Wood	Tan	Chipping	5	0.01	Negative
1	3	H37	3rd Floor Hallway	yes	Molding (W1)	Wood	Blue	Cracking	2	0	Negative
1	3	H37	3rd Floor Hallway	yes	Cove Base (W1)	Concrete	Grey	Chipping	1	0.2	Negative
1	3	H37	3rd Floor Hallway	yes	W2	Plaster	Blue	None	0	N/A	N/A
1	3	H37	3rd Floor Hallway	yes	W2	Plaster	White	None	0	N/A	N/A

			School District of Philadelphia								
			Name of Inspector: Michael Barth, Melissa Billingsley		Lead Safe Certification Assessment Report						
			Inspection Company: Criterion Labs., Inc.		Taylor Elementary School and Annex						
E l e m e n t	F l o o r	Space #	On-Site Room Name	Student/ Teacher Occupied (yes/no)	Component	Substrate Material	Color	Description of Damage	Damage Quantity (sf)	XRF Reading (mg/cm2)	XRF (positive/ negative)
1	3	H37	3rd Floor Hallway	yes	Door Frame (W2)	Metal	Black	None	0	N/A	N/A
1	3	H37	3rd Floor Hallway	yes	W3	Plaster	Blue	Cracking	5	2.4	Positive
1	3	H37	3rd Floor Hallway	yes	W3	Plaster	White	None	0	N/A	N/A
1	3	H37	3rd Floor Hallway	yes	Window Stool (W3)	Wood	Blue	Chipping	3	0.01	Negative
1	3	H37	3rd Floor Hallway	yes	Radiator (W3)	Metal	Blue	Chipping	3	0	Negative
1	3	H37	3rd Floor Hallway	yes	Cove Base (W3)	Concrete	Grey	Chipping	3	0.2	Negative
1	3	H37	3rd Floor Hallway	yes	Molding (W3)	Wood	Red	Chipping	1	0.01	Negative
1	3	H37	3rd Floor Hallway	yes	Fire Extinguisher Panel (W3)	Wood	Red	None	0	N/A	N/A
1	3	H37	3rd Floor Hallway	yes	Fire Door (W3)	Metal	Red	None	0	N/A	N/A
1	3	H37	3rd Floor Hallway	yes	Wooden Storage Closet (W3)	Wood	Tan	Chipping	3	0.01	Negative
1	3	H37	3rd Floor Hallway	yes	W4	Plaster	Blue	Chipping	2	3.3	Positive
1	3	H37	3rd Floor Hallway	yes	W4	Plaster	White	None	0	N/A	N/A
1	3	H37	3rd Floor Hallway	yes	Cove Base (W4)	Concrete	Grey	Chipping	1	0.1	Negative
1	3	H37	3rd Floor Hallway	yes	Floor	N/A	N/A	N/A	N/A	N/A	N/A
1	3	H37	3rd Floor Hallway	yes	Ceiling	N/A	N/A	N/A	N/A	N/A	N/A
1	2	207	Girl's Restroom next to Classroom 206	yes	W1	Plaster	White	Chipping	1	0.01	Negative
1	2	207	Girl's Restroom next to Classroom 206	yes	W2	Plaster	White	None	0	N/A	N/A
1	2	207	Girl's Restroom next to Classroom 206	yes	W3	Plaster	White	None	0	N/A	N/A
1	2	207	Girl's Restroom next to Classroom 206	yes	W4	Plaster	White	None	0	N/A	N/A
1	2	207	Girl's Restroom next to Classroom 206	yes	Floor	N/A	N/A	None	0	N/A	N/A
1	2	207	Girl's Restroom next to Classroom 206	yes	Ceiling	Plaster	White	Flaking	2	0.01	Negative

			School District of Philadelphia								
			Name of Inspector: Michael Barth, Melissa Billingsley		Lead Safe Certification Assessment Report						
			Inspection Company: Criterion Labs., Inc.		Taylor Elementary School and Annex						
E l e m e n t	F l o o r	Space #	On-Site Room Name	Student/ Teacher Occupied (yes/no)	Component	Substrate Material	Color	Description of Damage	Damage Quantity (sf)	XRF Reading (mg/cm2)	XRF (positive/ negative)
1	2	NP-2	Custodial Closet next to Girl's Restroom	no	W1	Concrete	White	None	0	N/A	N/A
1	2	NP-2	Custodial Closet next to Girl's Restroom	no	W2	Concrete	White	None	0	N/A	N/A
1	2	NP-2	Custodial Closet next to Girl's Restroom	no	W3	Concrete	White	None	0	N/A	N/A
1	2	NP-2	Custodial Closet next to Girl's Restroom	no	W4	Concrete	White	None	0	N/A	N/A
1	2	NP-2	Custodial Closet next to Girl's Restroom	no	Floor	N/A	N/A	N/A	N/A	N/A	N/A
1	2	NP-2	Custodial Closet next to Girl's Restroom	no	Ceiling	N/A	N/A	N/A	N/A	N/A	N/A
1	2	206	Classroom 206	yes	W1	Plaster	Tan	Cracking	1	0.01	Negative
1	2	206	Classroom 206	yes	W1	Plaster	White	Cracking	1	0	Negative
1	2	206	Classroom 206	yes	Door Frame (W1)	Wood	Tan	Chipping	1	0.01	Negative
1	2	206	Classroom 206	yes	Door Frame (W1)	Wood	White	None	0	N/A	N/A
1	2	206	Classroom 206	yes	Chalkboard (W1)	Wood	Blue	Chipping	1	0	Negative
1	2	206	Classroom 206	yes	Cove Base (W1)	Concrete	Tan	Friction	1	0.03	Negative
1	2	206	Classroom 206	yes	W2	Plaster	Tan	Chipping	1	0.3	Negative
1	2	206	Classroom 206	yes	W2	Plaster	White	None	0	N/A	N/A
1	2	206	Classroom 206	yes	Chalkboard (W2)	Wood	Tan	None	0	N/A	N/A
1	2	206	Classroom 206	yes	Cove Base (W2)	Concrete	Tan	Friction	2	0.3	Negative
1	2	206	Classroom 206	yes	Small Closet Space Door (W2)	Metal	Tan	Chipping	1	0.01	Negative
1	2	206	Classroom 206	yes	Small Closet Space Shelving (W2)	Wood	Tan	Cracking	1	0	Negative
1	2	206	Classroom 206	yes	Small Closet Space Interior (W2)	Wood	Tan	None	0	N/A	N/A
1	2	206	Classroom 206	yes	W3	Plaster	Tan	Chipping	2	0.01	Negative

			School District of Philadelphia								
			Name of Inspector: Michael Barth, Melissa Billingsley		Lead Safe Certification Assessment Report						
			Inspection Company: Criterion Labs., Inc.		Taylor Elementary School and Annex						
E l e m e n t	F l o o r	Space #	On-Site Room Name	Student/ Teacher Occupied (yes/no)	Component	Substrate Material	Color	Description of Damage	Damage Quantity (sf)	XRF Reading (mg/cm2)	XRF (positive/ negative)
1	2	206	Classroom 206	yes	W3	Plaster	White	None	0	N/A	N/A
1	2	206	Classroom 206	yes	Window Stool (W3)	Wood	Blue	Chipping	1	0	Negative
1	2	206	Classroom 206	yes	Radiator (W3)	Metal	Blue	Cracking	1	0.01	Negative
1	2	206	Classroom 206	yes	Cove Base (W3)	Concrete	Tan	Friction	1	0.1	Negative
1	2	206	Classroom 206	yes	W4	Plaster	Purple	None	0	N/A	N/A
1	2	206	Classroom 206	yes	W4	Plaster	White	None	0	N/A	N/A
1	2	206	Classroom 206	yes	Chalkboard (W4)	Wood	Tan	Chipping	1	0.01	Negative
1	2	206	Classroom 206	yes	Floor	Wood	N/A	N/A	N/A	N/A	N/A
1	2	206	Classroom 206	yes	Ceiling	N/A	N/A	N/A	N/A	N/A	N/A
1	2	206A	Classroom 206 Storage	yes	W1	Plaster	Tan	None	0	N/A	N/A
1	2	206A	Classroom 206 Storage	yes	Cove Base (W1)	Wood	Tan	None	0	N/A	N/A
1	2	206A	Classroom 206 Storage	yes	W2	Plaster	Tan	Cracking	3	0.01	Negative
1	2	206A	Classroom 206 Storage	yes	Cove Base (W2)	Wood	Tan	None	0	N/A	N/A
1	2	206A	Classroom 206 Storage	yes	W3	Plaster	Tan	None	0	N/A	N/A
1	2	206A	Classroom 206 Storage	yes	Cove Base (W3)	Wood	Tan	Chipping	1	0.1	Negative
1	2	206A	Classroom 206 Storage	yes	W4	Plaster	Tan	None	0	N/A	N/A
1	2	206A	Classroom 206 Storage	yes	Cove Base (W4)	Wood	Tan	None	0	N/A	N/A
1	2	206A	Classroom 206 Storage	yes	Floor	Wood	N/A	N/A	N/A	N/A	N/A
1	2	206A	Classroom 206 Storage	yes	Ceiling	N/A	N/A	N/A	N/A	N/A	N/A

			School District of Philadelphia								
			Name of Inspector: Michael Barth, Melissa Billingsley		Lead Safe Certification Assessment Report						
			Inspection Company: Criterion Labs., Inc.		Taylor Elementary School and Annex						
E l e m e n t	F l o o r	Space #	On-Site Room Name	Student/ Teacher Occupied (yes/no)	Component	Substrate Material	Color	Description of Damage	Damage Quantity (sf)	XRF Reading (mg/cm2)	XRF (positive/ negative)
1	2	205	Classroom 205	yes	W1	Plaster	Yellow	None	0	N/A	N/A
1	2	205	Classroom 205	yes	Door Frame (W1)	Wood	Blue	Chipping	1	0.3	Negative
1	2	205	Classroom 205	yes	Cove Base (W1)	Concrete	Blue	None	0	N/A	N/A
1	2	205	Classroom 205	yes	Door (W1)	Wood	Yellow	None	0	N/A	N/A
1	2	205	Classroom 205	yes	Cove Base (W2)	Concrete	Yellow	None	0	N/A	N/A
1	2	205	Classroom 205	yes	Chalkboard (W2)	Wood	Blue	None	0	N/A	N/A
1	2	205	Classroom 205	yes	W3	Plaster	Yellow	Chipping	3	0.01	Negative
1	2	205	Classroom 205	yes	Window Stool (W3)	Wood	Blue	Chipping	5	0.1	Negative
1	2	205	Classroom 205	yes	Radiator (W3)	Metal	Blue	Chipping	5	0	Negative
1	2	205	Classroom 205	yes	Cove Base (W3)	Concrete	Blue	None	0	N/A	N/A
1	2	205	Classroom 205	yes	W4	Plaster	Yellow	None	0	N/A	N/A
1	2	205	Classroom 205	yes	Moulding (W4)	Wood	Blue	Chipping	2	0.01	Negative
1	2	205	Classroom 205	yes	Cove Base (W4)	Concrete	Blue	None	0	N/A	N/A
1	2	205	Classroom 205	yes	Vertical Pipe (W4)	Metal	Blue	Chipping	1	0.3	Negative
1	2	205	Classroom 205	yes	Small Closet Space Door(W4)	Metal	Yellow	Chipping	3	0.2	Negative
1	2	205	Classroom 205	yes	Small Closet Space Shelving (W4)	Wood	Tan	Cracking	1	0.01	Negative
1	2	205	Classroom 205	yes	Small Closet Space Interior (W4)	Wood	Tan	Chipping	1	0.1	Negative
1	2	205	Classroom 205	yes	Floor	Wood	N/A	N/A	N/A	N/A	N/A
1	2	205	Classroom 205	yes	Ceiling	N/A	N/A	N/A	N/A	N/A	N/A
1	2	205A	Classroom 205 Storage	yes	W1	Plaster	Tan	None	0	N/A	N/A
1	2	205A	Classroom 205 Storage	yes	Door Frame (W1)	Wood	Tan	None	0	N/A	N/A
1	2	205A	Classroom 205 Storage	yes	Cove Base (W1)	Concrete	Tan	None	0	N/A	N/A

			School District of Philadelphia								
			Name of Inspector: Michael Barth, Melissa Billingsley		Lead Safe Certification Assessment Report						
			Inspection Company: Criterion Labs., Inc.		Taylor Elementary School and Annex						
E l e m e n t	F l o o r	Space #	On-Site Room Name	Student/ Teacher Occupied (yes/no)	Component	Substrate Material	Color	Description of Damage	Damage Quantity (sf)	XRF Reading (mg/cm2)	XRF (positive/ negative)
1	2	205A	Classroom 205 Storage	yes	W2	Plaster	Tan	Chipping	1	0.01	Negative
1	2	205A	Classroom 205 Storage	yes	Shelving (W2)	Wood	Tan	None	0	N/A	N/A
1	2	205A	Classroom 205 Storage	yes	Cove Base (W2)	Concrete	Tan	None	0	N/A	N/A
1	2	205A	Classroom 205 Storage	yes	W3	Plaster	Tan	None	0	N/A	N/A
1	2	205A	Classroom 205 Storage	yes	Window Stool (W3)	Wood	Tan	None	0	N/A	N/A
1	2	205A	Classroom 205 Storage	yes	Cove Base (W3)	Concrete	Tan	None	0	N/A	N/A
1	2	205A	Classroom 205 Storage	yes	Vertical Pipe (W3)	Metal	Tan	Chipping	1	0.03	Negative
1	2	205A	Classroom 205 Storage	yes	W4	Plaster	Tan	None	0	N/A	N/A
1	2	205A	Classroom 205 Storage	yes	Shelving (W4)	Wood	Tan	None	0	N/A	N/A
1	2	205A	Classroom 205 Storage	yes	Cove Base (W4)	Concrete	Tan	Chipping	1	0.01	Negative
1	2	205A	Classroom 205 Storage	yes	Floor	Wood	N/A	N/A	N/A	N/A	N/A
1	2	205A	Classroom 205 Storage	yes	Ceiling	N/A	N/A	N/A	N/A	N/A	N/A
1	2	S22	Stairwell next to Classroom 206	yes	W1	Plaster	Tan	Chipping	2	0	Negative
1	2	S22	Stairwell next to Classroom 206	yes	W1	Plaster	White	None	0	N/A	N/A
1	2	S22	Stairwell next to Classroom 206	yes	Stairs (W1)	Concrete	Grey	None	0	N/A	N/A

			School District of Philadelphia								
			Name of Inspector: Michael Barth, Melissa Billingsley		Lead Safe Certification Assessment Report						
			Inspection Company: Criterion Labs., Inc.		Taylor Elementary School and Annex						
E l e m e n t	F l o o r	Space #	On-Site Room Name	Student/ Teacher Occupied (yes/no)	Component	Substrate Material	Color	Description of Damage	Damage Quantity (sf)	XRF Reading (mg/cm2)	XRF (positive/ negative)
1	2	S22	Stairwell next to Classroom 206	yes	W2	Plaster	Tan	Hole	2	0.02	Negative
1	2	S22	Stairwell next to Classroom 206	yes	W2	Plaster	White	None	0	N/A	N/A
1	2	S22	Stairwell next to Classroom 206	yes	Stair Riser (W2)	Concrete	Grey	None	0	N/A	N/A
1	2	S22	Stairwell next to Classroom 206	yes	Handrail (W2)	Wood	Brown	Friction	2	0	Negative
1	2	S22	Stairwell next to Classroom 206	yes	W3	Plaster	Tan	None	0	N/A	N/A
1	2	S22	Stairwell next to Classroom 206	yes	W3	Plaster	White	None	0	N/A	N/A
1	2	S22	Stairwell next to Classroom 206	yes	Stairs (W3)	Concrete	Grey	Friction	1	0.2	Negative
1	2	S22	Stairwell next to Classroom 206	yes	Handrail (W3)	Wood	Brown	Friction	2	0.1	Negative
1	2	S22	Stairwell next to Classroom 206	yes	Door (W3)	Metal	Grey	Chipping	1	0	Negative
1	2	S22	Stairwell next to Classroom 206	yes	W4	Plaster	Tan	None	0	N/A	N/A
1	2	S22	Stairwell next to Classroom 206	yes	W4	Plaster	White	None	0	N/A	N/A
1	2	S22	Stairwell next to Classroom 206	yes	Stair Riser (W4)	Concrete	Grey	None	0	N/A	N/A
1	2	S22	Stairwell next to Classroom 206	yes	Floor	Concrete	Red	Friction	2	0.4	Negative
1	2	S22	Stairwell next to Classroom 206	yes	Floor	Concrete	Black	Friction	2	0.1	Negative
1	2	S22	Stairwell next to Classroom 206	yes	Ceiling	N/A	N/A	N/A	N/A	N/A	N/A

			School District of Philadelphia								
			Name of Inspector: Michael Barth, Melissa Billingsley		Lead Safe Certification Assessment Report						
			Inspection Company: Criterion Labs., Inc.		Taylor Elementary School and Annex						
E l e m e n t	F l o o r	Space #	On-Site Room Name	Student/ Teacher Occupied (yes/no)	Component	Substrate Material	Color	Description of Damage	Damage Quantity (sf)	XRF Reading (mg/cm2)	XRF (positive/ negative)
1	2	204	Classroom 204	yes	W1	Plaster	Tan	Cracking	6	0.01	Negative
1	2	204	Classroom 204	yes	W1	Plaster	White	Chipping	2	0.2	Negative
1	2	204	Classroom 204	yes	W1	Plaster	Blue	Chipping	1	0.3	Negative
1	2	204	Classroom 204	yes	Door (W1)	Wood	Tan	Chipping	1	0	Negative
1	2	204	Classroom 204	yes	Chalkboard (W1)	Wood	Tan	None	N/A	N/A	N/A
1	2	204	Classroom 204	yes	W2	Sheetrock	Tan	Chipping	1	0.01	Negative
1	2	204	Classroom 204	yes	W2	Sheetrock	White	Chipping	1	0.01	Negative
1	2	204	Classroom 204	yes	Chalkboard (W2)	Wood	Tan	Chipping	1	0.2	Negative
1	2	204	Classroom 204	yes	Small Closet Space In Shelving Door (W2)	Metal	Tan	Chipping	5	3.6	Positive
1	2	204	Classroom 204	yes	Small Closet Space In Shelving Interior (W2)	Wood	Red	Cracking	1	3.4	Positive
1	2	204	Classroom 204	yes	Small Closet Space In Shelving Interior (W2)	Wood	Tan	Chipping	1	2.2	Positive
1	2	204	Classroom 204	yes	Small Closet Space In Shelving Interior (W2)	Wood	Brown	Chipping	1	0.1	Negative
1	2	204	Classroom 204	yes	Small Closet Space In Shelving Interior (W2)	Wood	Tan	None	N/A	N/A	N/A
1	2	204	Classroom 204	yes	Small Closet Space In Shelving Interior (W2)	Plaster	Tan	Cracking	5	0.01	Negative
1	2	204	Classroom 204	yes	Window Stool (W3)	Wood	Black	Chipping	2	0.1	Negative
1	2	204	Classroom 204	yes	Window Stool (W3)	Wood	Tan	Chipping	2	0	Negative
1	2	204	Classroom 204	yes	Radiator (W3)	Metal	Tan	None	N/A	N/A	N/A
1	2	204	Classroom 204	yes	Radiator (W3)	Metal	Blue	None	N/A	N/A	N/A
1	2	204	Classroom 204	yes	Radiator (W3)	Metal	Black	None	N/A	N/A	N/A
1	2	204	Classroom 204	yes	W3	Concrete	Black	Chipping	1	0.1	Negative
1	2	204	Classroom 204	yes	W4	Concrete	White	None	N/A	N/A	N/A
1	2	204	Classroom 204	yes	W4	Concrete	Tan	None	N/A	N/A	N/A

			School District of Philadelphia								
			Name of Inspector: Michael Barth, Melissa Billingsley		Lead Safe Certification Assessment Report						
			Inspection Company: Criterion Labs., Inc.		Taylor Elementary School and Annex						
E l e m e n t	F l o o r	Space #	On-Site Room Name	Student/ Teacher Occupied (yes/no)	Component	Substrate Material	Color	Description of Damage	Damage Quantity (sf)	XRF Reading (mg/cm2)	XRF (positive/ negative)
1	2	204	Classroom 204	yes	W4	Concrete	Blue	None	N/A	N/A	N/A
1	2	204	Classroom 204	yes	Chalkboard (W4)	Wood	Black	Chipping	1	0.1	Negative
1	2	204	Classroom 204	yes	Floor	N/A	N/A	N/A	N/A	N/A	N/A
1	2	204	Classroom 204	yes	Ceiling	N/A	N/A	N/A	N/A	N/A	N/A
1	2	204A	Classroom 204 Storage	yes	W1	Plaster	Tan	None	0	N/A	N/A
1	2	204A	Classroom 204 Storage	yes	Cove Base (W1)	Wood	Tan	Chipping	2	0	Negative
1	2	204A	Classroom 204 Storage	yes	Door Frame (W1)	Wood	Tan	Cracking	1	0	Negative
1	2	204A	Classroom 204 Storage	yes	W2	Plaster	Tan	Chipping	2	0.1	Negative
1	2	204A	Classroom 204 Storage	yes	Cove Base (W2)	Wood	Tan	Cracking	1	0.2	Negative
1	2	204A	Classroom 204 Storage	yes	W3	Plaster	Tan	Chipping	2	0	Negative
1	2	204A	Classroom 204 Storage	yes	Cove Base (W3)	Wood	Tan	Cracking	1	0.2	Negative
1	2	204A	Classroom 204 Storage	yes	W4	Plaster	Tan	Chipping	2	0	Negative
1	2	204A	Classroom 204 Storage	yes	Cove Base (W4)	Wood	Tan	Cracking	1	0.2	Negative
1	2	204A	Classroom 204 Storage	yes	Floor	N/A	N/A	N/A	N/A	N/A	N/A
1	2	204A	Classroom 204 Storage	yes	Ceiling	Plaster	Tan	None	0	N/A	N/A
1	2	203	Classroom 203	yes	W1	Plaster	Tan	Cracking	10	0.3	Negative
1	2	203	Classroom 203	yes	W1	Plaster	White	None	0	N/A	N/A
1	2	203	Classroom 203	yes	Door Frame (W1)	Wood	Tan	Friction	1	0.2	Negative

			School District of Philadelphia								
			Name of Inspector: Michael Barth, Melissa Billingsley		Lead Safe Certification Assessment Report						
			Inspection Company: Criterion Labs., Inc.		Taylor Elementary School and Annex						
E l e m e n t	F l o o r	Space #	On-Site Room Name	Student/ Teacher Occupied (yes/no)	Component	Substrate Material	Color	Description of Damage	Damage Quantity (sf)	XRF Reading (mg/cm2)	XRF (positive/ negative)
1	2	203	Classroom 203	yes	Cove Base (W1)	Concrete	Tan	Friction	1	0	Negative
1	2	203	Classroom 203	yes	W2	Plaster	Tan	Chipping	3	0.01	Negative
1	2	203	Classroom 203	yes	W2	Plaster	White	None	0	N/A	N/A
1	2	203	Classroom 203	yes	Chalkboard (W2)	Wood	Tan	Chipping	2	0.2	Negative
1	2	203	Classroom 203	yes	W3	Plaster	Tan	Cracking	5	0.1	Negative
1	2	203	Classroom 203	yes	Window Stool (W3)	Wood	Tan	Cracking	2	0.32	Negative
1	2	203	Classroom 203	yes	Radiator (W3)	Metal	Tan	Chipping	5	0.23	Negative
1	2	203	Classroom 203	yes	Cove Base (W3)	Concrete	Tan	Friction	5	0.2	Negative
1	2	203	Classroom 203	yes	W4	Plaster	Tan	Cracking	5	0.1	Negative
1	2	203	Classroom 203	yes	W4	Plaster	White	Chipping	1	0.34	Negative
1	2	203	Classroom 203	yes	W4	Concrete	Tan	Friction	3	0.2	Negative
1	2	203	Classroom 203	yes	Floor	Wood	N/A	N/A	N/A	N/A	N/A
1	2	203	Classroom 203	yes	Ceiling	N/A	N/A	N/A	N/A	N/A	N/A
1	2	203A	Classroom 203 Storage	yes	W1	Plaster	Tan	None	0	N/A	N/A
1	2	203A	Classroom 203 Storage	yes	Cove Base (W1)	Wood	Tan	Chipping	2	0.01	Negative
1	2	203A	Classroom 203 Storage	yes	W2	Plaster	Tan	Cracking	2	0.21	Negative
1	2	203A	Classroom 203 Storage	yes	Cove Base (W2)	Wood	Tan	Chipping	2	0.1	Negative
1	2	203A	Classroom 203 Storage	yes	W3	Plaster	Tan	None	0	N/A	N/A
1	2	203A	Classroom 203 Storage	yes	Cove Base (W3)	Wood	Tan	None	0	N/A	N/A
1	2	203A	Classroom 203 Storage	yes	W4	Plaster	Tan	Cracking	2	0.2	Negative
1	2	203A	Classroom 203 Storage	yes	Floor	Wood	N/A	N/A	N/A	N/A	N/A

			School District of Philadelphia								
			Name of Inspector: Michael Barth, Melissa Billingsley		Lead Safe Certification Assessment Report						
			Inspection Company: Criterion Labs., Inc.		Taylor Elementary School and Annex						
E l e m e n t	F l o o r	Space #	On-Site Room Name	Student/ Teacher Occupied (yes/no)	Component	Substrate Material	Color	Description of Damage	Damage Quantity (sf)	XRF Reading (mg/cm2)	XRF (positive/ negative)
1	2	203A	Classroom 203 Storage	yes	Ceiling	N/A	N/A	N/A	N/A	N/A	N/A
1	2	202	Classroom 202	yes	Door (W1)	Wood	Yellow	None	0	N/A	N/A
1	2	202	Classroom 202	yes	Door Frame (W1)	Wood	Tan	Cracking	1	0.2	Negative
1	2	202	Classroom 202	yes	Chalkboard (W1)	Wood	Tan	Cracking	2	0	Negative
1	2	202	Classroom 202	yes	W1	Plaster	Tan	Cracking	5	3.1	Positive
1	2	202	Classroom 202	yes	W1	Plaster	White	None	0	N/A	N/A
1	2	202	Classroom 202	yes	Cove Base (W1)	Concrete	Tan	Chipping	1	0.2	Negative
1	2	202	Classroom 202	yes	W2	Plaster	Tan	Cracking	3	2.3	Positive
1	2	202	Classroom 202	yes	W2	Plaster	White	None	0	N/A	N/A
1	2	202	Classroom 202	yes	Cove Base (W2)	Concrete	Tan	Chipping	1	0.1	Negative
1	2	202	Classroom 202	yes	W3	Plaster	Tan	Cracking	3	3.3	Positive
1	2	202	Classroom 202	yes	W3	Plaster	White	None	0	N/A	N/A
1	2	202	Classroom 202	yes	Cove Base (W3)	Concrete	Tan	Chipping	1	0.02	Negative
1	2	202	Classroom 202	yes	W4	Plaster	White	Cracking	2	1.3	Positive
1	2	202	Classroom 202	yes	Chalkboard (W4)	Wood	Tan	Chipping	1	0.01	Negative
1	2	202	Classroom 202	yes	Cove Base (W4)	Concrete	Tan	Chipping	1	0	Negative
1	2	202	Classroom 202	yes	Floor	Wood	N/A	N/A	N/A	N/A	N/A
1	2	202	Classroom 202	yes	Ceiling	N/A	N/A	N/A	N/A	N/A	N/A
1	2	202A	Classroom 202 Storage	yes	W1	Plaster	Tan	None	0	N/A	N/A
1	2	202A	Classroom 202 Storage	yes	Cove Base (W1)	Concrete	Tan	None	0	N/A	N/A
1	2	202A	Classroom 202 Storage	yes	Door Frame (W1)	Wood	Tan	None	0	N/A	N/A
1	2	202A	Classroom 202 Storage	yes	W2	Plaster	Tan	None	0	N/A	N/A

			School District of Philadelphia								
			Name of Inspector: Michael Barth, Melissa Billingsley		Lead Safe Certification Assessment Report						
			Inspection Company: Criterion Labs., Inc.		Taylor Elementary School and Annex						
E l e m e n t	F l o o r	Space #	On-Site Room Name	Student/ Teacher Occupied (yes/no)	Component	Substrate Material	Color	Description of Damage	Damage Quantity (sf)	XRF Reading (mg/cm2)	XRF (positive/ negative)
1	2	202A	Classroom 202 Storage	yes	Cove Base (W2)	Concrete	Tan	Chipping	2	0.2	Negative
1	2	202A	Classroom 202 Storage	yes	Shelving (W2)	Wood	Tan	None	0	N/A	N/A
1	2	202A	Classroom 202 Storage	yes	W3	Plaster	Tan	None	0	N/A	N/A
1	2	202A	Classroom 202 Storage	yes	Cove Base (W3)	Concrete	Tan	Chipping	2	0.2	Negative
1	2	202A	Classroom 202 Storage	yes	W4	Plaster	Tan	None	0	N/A	N/A
1	2	202A	Classroom 202 Storage	yes	Cove Base (W4)	Concrete	Tan	Chipping	2	0.01	Negative
1	2	202A	Classroom 202 Storage	yes	Shelving (W4)	Wood	Tan	None	0	N/A	N/A
1	2	202A	Classroom 202 Storage	yes	Floor	N/A	N/A	N/A	N/A	N/A	N/A
1	2	202A	Classroom 202 Storage	yes	Ceiling	Plaster	Tan	None	0	N/A	N/A
1	2	S21	Stairwell next to Classroom 202	yes	W1	Plaster	Tan	None	0	N/A	N/A
1	2	S21	Stairwell next to Classroom 202	yes	W1	Plaster	White	None	0	N/A	N/A
1	2	S21	Stairwell next to Classroom 202	yes	Moulding (W1)	Wood	Tan	None	0	N/A	N/A
1	2	S21	Stairwell next to Classroom 202	yes	Vertical Pipe (W1)	Metal	Tan	None	0	N/A	N/A
1	2	S21	Stairwell next to Classroom 202	yes	Vertical Pipe (W1)	Metal	White	None	0	N/A	N/A
1	2	S21	Stairwell next to Classroom 202	yes	Radiator (W1)	Metal	Grey	Chipping	1	0	Negative

			School District of Philadelphia								
			Name of Inspector: Michael Barth, Melissa Billingsley		Lead Safe Certification Assessment Report						
			Inspection Company: Criterion Labs., Inc.		Taylor Elementary School and Annex						
E l e m e n t	F l o o r	Space #	On-Site Room Name	Student/ Teacher Occupied (yes/no)	Component	Substrate Material	Color	Description of Damage	Damage Quantity (sf)	XRF Reading (mg/cm2)	XRF (positive/ negative)
1	2	S21	Stairwell next to Classroom 202	yes	W2	Plaster	White	None	0	N/A	N/A
1	2	S21	Stairwell next to Classroom 202	yes	W2	Plaster	Tan	None	0	N/A	N/A
1	2	S21	Stairwell next to Classroom 202	yes	Moulding (W2)	Wood	Tan	None	0	N/A	N/A
1	2	S21	Stairwell next to Classroom 202	yes	Handrail (W2)	Wood	Brown	Friction	3	0.2	Negative
1	2	S21	Stairwell next to Classroom 202	yes	Stair Riser (W2)	Concrete	Grey	None	0	N/A	N/A
1	2	S21	Stairwell next to Classroom 202	yes	Stairs (W3)	Concrete	Grey	Friction	3	0.1	Negative
1	2	S21	Stairwell next to Classroom 202	yes	Handrail (W3)	Wood	Brown	Friction	3	0	Negative
1	2	S21	Stairwell next to Classroom 202	yes	W4	Plaster	Tan	None	0	N/A	N/A
1	2	S21	Stairwell next to Classroom 202	yes	W4	Plaster	White	None	0	N/A	N/A
1	2	S21	Stairwell next to Classroom 202	yes	Handrail (W4)	Wood	Tan	None	0	N/A	N/A
1	2	S21	Stairwell next to Classroom 202	yes	Stair Riser (W4)	Concrete	Grey	None	0	N/A	N/A
1	2	S21	Stairwell next to Classroom 202	yes	Floor	Concrete	Grey	Friction	2	0.3	Negative
1	2	S21	Stairwell next to Classroom 202	yes	Floor	Concrete	Red	Friction	2	0.2	Negative
1	2	S21	Stairwell next to Classroom 202	yes	Ceiling	N/A	N/A	N/A	N/A	N/A	N/A
1	2	200	Counselor's Office 200	yes	Moulding (W1)	Wood	White	None	0	N/A	N/A
1	2	200	Counselor's Office 200	yes	Door Frame (W1)	Wood	Tan	Chipping	1	0.2	Negative

			School District of Philadelphia								
			Name of Inspector: Michael Barth, Melissa Billingsley		Lead Safe Certification Assessment Report						
			Inspection Company: Criterion Labs., Inc.		Taylor Elementary School and Annex						
E l e m e n t	F l o o r	Space #	On-Site Room Name	Student/ Teacher Occupied (yes/no)	Component	Substrate Material	Color	Description of Damage	Damage Quantity (sf)	XRF Reading (mg/cm2)	XRF (positive/ negative)
1	2	200	Counselor's Office 200	yes	W1	Concrete	White	None	0	N/A	N/A
1	2	200	Counselor's Office 200	yes	W1	Concrete	Tan	None	0	N/A	N/A
1	2	200	Counselor's Office 200	yes	W2	Plaster	White	None	0	N/A	N/A
1	2	200	Counselor's Office 200	yes	W2	Plaster	Tan	Flaking	3	3.4	Positive
1	2	200	Counselor's Office 200	yes	W2	Concrete	White	None	0	N/A	N/A
1	2	200	Counselor's Office 200	yes	W2	Concrete	Tan	None	0	N/A	N/A
1	2	200	Counselor's Office 200	yes	Moulding (W2)	Wood	Tan	Chipping	1	0	Negative
1	2	200	Counselor's Office 200	yes	Radiator (W2)	Metal	Tan	Chipping	1	0.2	Negative
1	2	200	Counselor's Office 200	yes	W3	Plaster	White	Moisture Damage	1	2.3	Positive
1	2	200	Counselor's Office 200	yes	W3	Plaster	Tan	None	0	N/A	N/A
1	2	200	Counselor's Office 200	yes	Window Stool (W3)	Wood	Tan	Chipping	1	0.2	Negative
1	2	200	Counselor's Office 200	yes	Radiator (W3)	Metal	Tan	Chipping	1	0	Negative
1	2	200	Counselor's Office 200	yes	W4	Plaster	White	None	0	N/A	N/A
1	2	200	Counselor's Office 200	yes	W4	Plaster	Tan	Flaking	5	1.7	Positive
1	2	200	Counselor's Office 200	yes	Floor	N/A	N/A	N/A	N/A	N/A	N/A
1	2	200	Counselor's Office 200	yes	Ceiling	N/A	N/A	N/A	N/A	N/A	N/A
1	2	200A	Counselor's Office 200 Restroom	yes	W1	Concrete	Tan	None	0	N/A	N/A
				yes	Door Frame (W1)	Metal	Tan	Chipping	1	0.2	Negative
1	2	200A	Counselor's Office 200 Restroom	yes	W2	Plaster	Tan	Flaking	1	5.4	Positive
1	2	200A	Counselor's Office 200 Restroom	yes	W3	Concrete	Tan	None	0	N/A	N/A
1	2	200A	Counselor's Office 200 Restroom	yes	W4	Concrete	Tan	None	0	N/A	N/A
1	2	200A	Counselor's Office 200 Restroom	yes	Floor	N/A	N/A	N/A	N/A	N/A	N/A

			School District of Philadelphia								
			Name of Inspector: Michael Barth, Melissa Billingsley		Lead Safe Certification Assessment Report						
			Inspection Company: Criterion Labs., Inc.		Taylor Elementary School and Annex						
E l e m e n t	F l o o r	Space #	On-Site Room Name	Student/ Teacher Occupied (yes/no)	Component	Substrate Material	Color	Description of Damage	Damage Quantity (sf)	XRF Reading (mg/cm2)	XRF (positive/ negative)
1	2	200A	Counselor's Office 200 Restroom	yes	Ceiling	Plaster	Tan	None	0	N/A	N/A
1	1	H13	1st Floor Hallway	yes	W1	Plaster	Tan	Chipping	4	0.2	Negative
1	1	H13	1st Floor Hallway	yes	W1	Plaster	Red	None	0	N/A	N/A
1	1	H13	1st Floor Hallway	yes	W1	Plaster	Blue	Chipping	1	0.12	Negative
1	1	H13	1st Floor Hallway	yes	Cove Base (W1)	Concrete	Grey	Chipping	5	0.2	Negative
1	1	H13	1st Floor Hallway	yes	Fire Extinguisher Container (W1)	Metal	Red	Chipping	1	0	Negative
1	1	H13	1st Floor Hallway	yes	Moulding (W1)	Wood	Tan	None	0	N/A	N/A
1	1	H13	1st Floor Hallway	yes	W2	Plaster	Tan	None	0	N/A	N/A
1	1	H13	1st Floor Hallway	yes	Door Frame (W2)	Metal	Black	Chipping	1	N/A	N/A
1	1	H13	1st Floor Hallway	yes	W3	Plaster	Tan	None	0	N/A	N/A
1	1	H13	1st Floor Hallway	yes	W3	Plaster	Blue	Chipping	1	0.2	Negative
1	1	H13	1st Floor Hallway	yes	Radiator (W3)	Metal	Blue	Chipping	5	0.01	Negative
1	1	H13	1st Floor Hallway	yes	Firedoors (W3)	Metal	Red	None	0	N/A	N/A
1	1	H13	1st Floor Hallway	yes	Window Stool (W3)	Wood	Blue	Chipping	5	0.2	Negative
1	1	H13	1st Floor Hallway	yes	W4	Plaster	Tan	None	0	N/A	N/A
1	1	H13	1st Floor Hallway	yes	Door (W4)	Wood	Yellow	None	0	N/A	N/A
1	1	H13	1st Floor Hallway	yes	Door Frame (W4)	Metal	Black	None	0	N/A	N/A
1	1	H13	1st Floor Hallway	yes	Floor	Concrete	Black	Friction	10	0.2	Negative
1	1	H13	1st Floor Hallway	yes	Ceiling	N/A	N/A	N/A	N/A	N/A	N/A
1	2	S23	2nd Floor Fire Tower	no	W1	Brick	White	None	0	N/A	N/A
1	2	S23	2nd Floor Fire Tower	no	W2	Brick	White	None	0	N/A	N/A
1	2	S23	2nd Floor Fire Tower	no	W3	Brick	White	None	0	N/A	N/A
1	2	S23	2nd Floor Fire Tower	no	W4	Brick	White	None	0	N/A	N/A
1	2	S23	2nd Floor Fire Tower	no	Floor	Concrete	N/A	None	0	N/A	N/A
1	2	S23	2nd Floor Fire Tower	no	Ceiling	Concrete	White	None	0	N/A	N/A
1	2	H26	2nd Floor Hallway	yes	W1	Plaster	White	None	0	N/A	N/A

			School District of Philadelphia								
			Name of Inspector: Michael Barth, Melissa Billingsley		Lead Safe Certification Assessment Report						
			Inspection Company: Criterion Labs., Inc.		Taylor Elementary School and Annex						
E l e m e n t	F l o o r	Space #	On-Site Room Name	Student/ Teacher Occupied (yes/no)	Component	Substrate Material	Color	Description of Damage	Damage Quantity (sf)	XRF Reading (mg/cm2)	XRF (positive/ negative)
1	2	H26	2nd Floor Hallway	yes	W1	Plaster	Purple	Chipping	3	0.2	Negative
1	2	H26	2nd Floor Hallway	yes	W1	Plaster	Pink	Chipping	3	0.1	Negative
1	2	H26	2nd Floor Hallway	yes	Moulding (W1)	Wood	Tan	None	0	N/A	N/A
1	2	H26	2nd Floor Hallway	yes	Fire Extinguisher Box (W1)	Metal	Red	Chipping	1	0.01	Negative
1	2	H26	2nd Floor Hallway	yes	Door Frame (W1)	Metal	Black	Friction	1	0.2	Negative
1	2	H26	2nd Floor Hallway	yes	Cove Base (W1)	Concrete	Grey	Chipping	5	0.23	Negative
1	2	H26	2nd Floor Hallway	yes	W2	Plaster	White	None	0	N/A	N/A
1	2	H26	2nd Floor Hallway	yes	W2	Plaster	Purple	None	0	N/A	N/A
1	2	H26	2nd Floor Hallway	yes	Cove Base (W2)	Concrete	Grey	None	0	N/A	N/A
1	2	H26	2nd Floor Hallway	yes	Door Frame (W2)	Metal	Black	None	0	N/A	N/A
1	2	H26	2nd Floor Hallway	yes	W3	Plaster	White	None	0	N/A	N/A
1	2	H26	2nd Floor Hallway	yes	W3	Plaster	Purple	Chipping	3	0.31	Negative
1	2	H26	2nd Floor Hallway	yes	W3	Plaster	Pink	None	0	N/A	N/A
1	2	H26	2nd Floor Hallway	yes	Moulding (W3)	Wood	Tan	None	0	N/A	N/A
1	2	H26	2nd Floor Hallway	yes	Fire Doors (W3)	Metal	Red	None	0	N/A	N/A
1	2	H26	2nd Floor Hallway	yes	Radiator (W3)	Metal	Purple	None	0	N/A	N/A
1	2	H26	2nd Floor Hallway	yes	Cove Base (W3)	Concrete	Grey	Friction	5	0.2	Negative
1	2	H26	2nd Floor Hallway	yes	W4	Plaster	White	None	0	N/A	N/A
1	2	H26	2nd Floor Hallway	yes	W4	Plaster	Purple	Chipping	1	0.4	Negative
1	2	H26	2nd Floor Hallway	yes	Cove Base (W4)	Concrete	Grey	Friction	2	0.1	Negative
1	2	H26	2nd Floor Hallway	yes	Floor	Concrete	Red	Friction	10	0.25	Negative
1	2	H26	2nd Floor Hallway	yes	Floor	Concrete	Grey	Friction	10	0.3	Negative
1	2	H26	2nd Floor Hallway	yes	Ceiling	N/A	N/A	N/A	N/A	N/A	N/A
1	1	100D	Main Office	yes	W1	Plaster	Tan	None	0	N/A	N/A
1	1	100D	Main Office	yes	Cove Base (W1)	Concrete	Blue	None	0	N/A	N/A
1	1	100D	Main Office	yes	Moulding (W1)	Wood	Tan	Chipping	1	0.2	Negative
1	1	100D	Main Office	yes	W2	Plaster	Tan	Cracking	2	0.3	Negative

			School District of Philadelphia								
			Name of Inspector: Michael Barth, Melissa Billingsley		Lead Safe Certification Assessment Report						
			Inspection Company: Criterion Labs., Inc.		Taylor Elementary School and Annex						
E l e m e n t	F l o o r	Space #	On-Site Room Name	Student/ Teacher Occupied (yes/no)	Component	Substrate Material	Color	Description of Damage	Damage Quantity (sf)	XRF Reading (mg/cm2)	XRF (positive/ negative)
1	1	100D	Main Office	yes	Cove Base (W2)	Concrete	Blue	Chipping	2	0.02	Negative
1	1	100D	Main Office	yes	Electrical Box (W2)	Metal	Tan	Chipping	3	0.2	Negative
1	1	100D	Main Office	yes	W3	Plaster	Tan	None	0	N/A	N/A
1	1	100D	Main Office	yes	Cove Base (W3)	Concrete	Blue	None	0	N/A	N/A
1	1	100D	Main Office	yes	Window Stool (W3)	Wood	Tan	Chipping	1	0.2	Negative
1	1	100D	Main Office	yes	Radiator (W3)	Metal	Tan	Chipping	1	0.2	Negative
1	1	100D	Main Office	yes	W4	Plaster	Tan	Cracking	1	0.21	Negative
1	1	100D	Main Office	yes	W4	Plaster	Blue	Chipping	1	0.32	Negative
1	1	100D	Main Office	yes	Cove Base (W4)	Concrete	Blue	Chipping	3	0.1	Negative
1	1	100D	Main Office	yes	Door Frame (W4)	Metal	Tan	None	0	N/A	N/A
1	1	100D	Main Office	yes	Moulding (W4)	Wood	Tan	Friction	1	0.01	Negative
1	1	100D	Main Office	yes	Floor	N/A	N/A	N/A	N/A	N/A	N/A
1	1	100D	Main Office	yes	Ceiling	N/A	N/A	N/A	N/A	N/A	N/A
1	1	102B	Storage Closet in Main Office next to Windows	no	W1	Plaster	Tan	None	0	N/A	N/A
1	1	102B	Storage Closet in Main Office next to Windows	no	Shelving (W1)	Wood	Black	None	0	N/A	N/A
1	1	102B	Storage Closet in Main Office next to Windows	no	W2	Plaster	Tan	None	0	N/A	N/A
1	1	102B	Storage Closet in Main Office next to Windows	no	Shelving (W2)	Wood	Black	Chipping	1	0.01	Negative
1	1	102B	Storage Closet in Main Office next to Windows	no	Electrical Conduit (W2)	Metal	Tan	Chipping	1	0.2	Negative
1	1	102B	Storage Closet in Main Office next to Windows	no	W3	Concrete	Tan	None	0	N/A	N/A
1	1	102B	Storage Closet in Main Office next to Windows	no	W4	Concrete	Tan	None	0	N/A	N/A
1	1	102B	Storage Closet in Main Office next to Windows	no	Floor	N/A	N/A	N/A	N/A	N/A	N/A

			School District of Philadelphia								
			Name of Inspector: Michael Barth, Melissa Billingsley		Lead Safe Certification Assessment Report						
			Inspection Company: Criterion Labs., Inc.		Taylor Elementary School and Annex						
E l e m e n t	F l o o r	Space #	On-Site Room Name	Student/ Teacher Occupied (yes/no)	Component	Substrate Material	Color	Description of Damage	Damage Quantity (sf)	XRF Reading (mg/cm2)	XRF (positive/ negative)
1	1	102B	Storage Closet in Main Office next to Windows	no	Ceiling	N/A	N/A	N/A	N/A	N/A	N/A
1	1	102A	Counselor's Office	yes	W1	Plaster	Tan	Chipping	1	0.1	Negative
1	1	102A	Counselor's Office	yes	Door Frame (W1)	Metal	Grey	Chipping	1	0.2	Negative
1	1	102A	Counselor's Office	yes	W2	Plaster	Tan	None	0	N/A	N/A
1	1	102A	Counselor's Office	yes	W3	Plaster	Tan	None	0	N/A	N/A
1	1	102A	Counselor's Office	yes	W4	Plaster	Tan	Chipping	1	0.41	Negative
1	1	102A	Counselor's Office	yes	Floor	N/A	N/A	N/A	N/A	N/A	N/A
1	1	102A	Counselor's Office	yes	Ceiling	N/A	N/A	N/A	N/A	N/A	N/A
1	1	102F	Nurse's Office	yes	W1	Plaster	Tan	None	0	N/A	N/A
1	1	102F	Nurse's Office	yes	Door Frame (W1)	Metal	Black	Friction	2	0	Negative
1	1	102F	Nurse's Office	yes	W2	Plaster	Tan	None	0	N/A	N/A
1	1	102F	Nurse's Office	yes	W3	Plaster	Tan	None	0	N/A	N/A
1	1	102F	Nurse's Office	yes	Radiator (W3)	Metal	Brown	Chipping	5	0.01	Negative
1	1	102F	Nurse's Office	yes	Window Stool (W3)	Wood	Brown	Cracking	5	0.1	Negative
1	1	102F	Nurse's Office	yes	W4	Plaster	Tan	None	0	N/A	N/A
1	1	102F	Nurse's Office	yes	Floor	N/A	N/A	N/A	N/A	N/A	N/A
1	1	102F	Nurse's Office	yes	Ceiling	N/A	N/A	N/A	N/A	N/A	N/A
1	1	102G	Nurse's Office Restroom	yes	W1	Plaster	Tan	None	0	N/A	N/A
1	1	102G	Nurse's Office Restroom	yes	Door Frame (W1)	Metal	Black	Friction	1	0.1	Negative
1	1	102G	Nurse's Office Restroom	yes	W2	Plaster	Tan	None	0	N/A	N/A
1	1	102G	Nurse's Office Restroom	yes	W3	Plaster	Tan	None	0	N/A	N/A
1	1	102G	Nurse's Office Restroom	yes	W4	Plaster	Tan	None	0	N/A	N/A

			School District of Philadelphia								
			Name of Inspector: Michael Barth, Melissa Billingsley		Lead Safe Certification Assessment Report						
			Inspection Company: Criterion Labs., Inc.		Taylor Elementary School and Annex						
E l e m e n t	F l o o r	Space #	On-Site Room Name	Student/ Teacher Occupied (yes/no)	Component	Substrate Material	Color	Description of Damage	Damage Quantity (sf)	XRF Reading (mg/cm2)	XRF (positive/ negative)
1	1	102G	Nurse's Office Restroom	yes	Floor	N/A	N/A	N/A	N/A	N/A	N/A
1	1	102G	Nurse's Office Restroom	yes	Ceiling	N/A	N/A	N/A	N/A	N/A	N/A
1	1	102C	Coat Closet next to Nurse's Office	yes	W1	Plaster	Tan	None	0	N/A	N/A
1	1	102C	Coat Closet next to Nurse's Office	yes	W2	Plaster	Tan	None	0	N/A	N/A
1	1	102C	Coat Closet next to Nurse's Office	yes	W3	Plaster	Tan	None	0	N/A	N/A
1	1	102C	Coat Closet next to Nurse's Office	yes	W4	Plaster	Tan	None	0	N/A	N/A
1	1	102C	Coat Closet next to Nurse's Office	yes	Floor	N/A	N/A	N/A	N/A	N/A	N/A
1	1	102C	Coat Closet next to Nurse's Office	yes	Ceiling	N/A	N/A	N/A	N/A	N/A	N/A
1	1	102D	Main Office Restroom	yes	W1	Plaster	Tan	None	0	N/A	N/A
1	1	102D	Main Office Restroom	yes	Door Frame (W1)	Metal	Black	None	0	N/A	N/A
1	1	102D	Main Office Restroom	yes	W2	Plaster	Tan	None	0	N/A	N/A
1	1	102D	Main Office Restroom	yes	W3	Plaster	Tan	None	0	N/A	N/A
1	1	102D	Main Office Restroom	yes	W4	Plaster	Tan	None	0	N/A	N/A
1	1	102D	Main Office Restroom	yes	Floor	N/A	N/A	N/A	N/A	N/A	N/A
1	1	102D	Main Office Restroom	yes	Ceiling	Plaster	Tan	None	0	N/A	N/A
1	1	100E	Teacher's Lounge Restroom	yes	W1	Plaster	Green	None	0	N/A	N/A
1	1	100E	Teacher's Lounge Restroom	yes	Door Frame (W1)	Metal	Black	None	0	N/A	N/A
1	1	100E	Teacher's Lounge Restroom	yes	W2	Plaster	Green	None	0	N/A	N/A

			School District of Philadelphia								
			Name of Inspector: Michael Barth, Melissa Billingsley		Lead Safe Certification Assessment Report						
			Inspection Company: Criterion Labs., Inc.		Taylor Elementary School and Annex						
E l e m e n t	F l o o r	Space #	On-Site Room Name	Student/ Teacher Occupied (yes/no)	Component	Substrate Material	Color	Description of Damage	Damage Quantity (sf)	XRF Reading (mg/cm2)	XRF (positive/ negative)
1	1	100E	Teacher's Lounge Restroom	yes	W3	Plaster	Green	None	0	N/A	N/A
1	1	100E	Teacher's Lounge Restroom	yes	W4	Plaster	Green	Chipping	1	0.2	Negative
1	1	100E	Teacher's Lounge Restroom	yes	Floor	N/A	N/A	N/A	N/A	N/A	N/A
1	1	100E	Teacher's Lounge Restroom	yes	Ceiling	Plaster	Green	None	0	N/A	N/A
1	1	100E	Teacher's Lounge Restroom	yes	HVAC Vent (Ceiling)	Metal	Green	None	0	N/A	N/A
1	1	100C	Teacher's Lounge	yes	W1	Plaster	Tan	Chipping	2	0.31	Negative
1	1	100C	Teacher's Lounge	yes	Door Frame (W1)	Metal	Grey	Friction	3	0.2	Negative
1	1	100C	Teacher's Lounge	yes	W2	Plaster	Tan	Chipping	1	0.11	Negative
1	1	100C	Teacher's Lounge	yes	Cove Base (W2)	Concrete	Grey	None	0	N/A	N/A
1	1	100C	Teacher's Lounge	yes	Radiator (W2)	Metal	Grey	Chipping	3	0.02	Negative
1	1	100C	Teacher's Lounge	yes	Window Stool (W2)	Wood	Black	Cracking	3	0.1	Negative
1	1	100C	Teacher's Lounge	yes	W3	Sheetrock	Tan	Chipping	1	0.01	Negative
1	1	100C	Teacher's Lounge	yes	Door (W3)	Metal	Black	None	0	N/A	N/A
1	1	100C	Teacher's Lounge	yes	W4	Plaster	Tan	Chipping	1	0.4	Negative
1	1	100C	Teacher's Lounge	yes	Cove Base (W4)	Concrete	Grey	Friction	3	0.1	Negative
1	1	100C	Teacher's Lounge	yes	Door Frame (W4)	Metal	Black	Friction	1	0.2	Negative
1	1	100C	Teacher's Lounge	yes	Floor	N/A	N/A	N/A	N/A	N/A	N/A
1	1	100C	Teacher's Lounge	yes	Ceiling	N/A	N/A	N/A	N/A	N/A	N/A
1	1	100F	Storage Closet in Teacher's Lounge	no	W1	Plaster	Tan	None	0	N/A	N/A
1	1	100F	Storage Closet in Teacher's Lounge	no	W2	Concrete	Tan	None	0	N/A	N/A
1	1	100F	Storage Closet in Teacher's Lounge	no	W3	Concrete	Tan	None	0	N/A	N/A

			School District of Philadelphia								
			Name of Inspector: Michael Barth, Melissa Billingsley		Lead Safe Certification Assessment Report						
			Inspection Company: Criterion Labs., Inc.		Taylor Elementary School and Annex						
E l e m e n t	F l o o r	Space #	On-Site Room Name	Student/ Teacher Occupied (yes/no)	Component	Substrate Material	Color	Description of Damage	Damage Quantity (sf)	XRF Reading (mg/cm2)	XRF (positive/ negative)
1	1	100F	Storage Closet in Teacher's Lounge	no	W4	Concrete	Tan	None	0	N/A	N/A
1	1	100F	Storage Closet in Teacher's Lounge	no	Floor	N/A	N/A	N/A	N/A	N/A	N/A
1	1	100F	Storage Closet in Teacher's Lounge	no	Ceiling	N/A	N/A	N/A	N/A	N/A	N/A
1	1	100A	Assistant Principal's/Dean's Office	yes	W1	Plaster	Tan	Chipping	1	0.2	Negative
1	1	100A	Assistant Principal's/Dean's Office	yes	Door Frame (W1)	Metal	Black	Chipping	1	0	Negative
1	1	100A	Assistant Principal's/Dean's Office	yes	W1	Concrete	White	None	0	N/A	N/A
1	1	100A	Assistant Principal's/Dean's Office	yes	W2	Plaster	Tan	Cracking	1	0.02	Negative
1	1	100A	Assistant Principal's/Dean's Office	yes	Cove Base (W2)	Concrete	Grey	None	0	N/A	N/A
1	1	100A	Assistant Principal's/Dean's Office	yes	W3	Plaster	Tan	None	0	N/A	N/A
1	1	100A	Assistant Principal's/Dean's Office	yes	Window Stool (W3)	Wood	Black	Chipping	1	0.01	Negative
1	1	100A	Assistant Principal's/Dean's Office	yes	Radiator (W3)	Metal	Black	Chipping	1	0	Negative

			School District of Philadelphia								
			Name of Inspector: Michael Barth, Melissa Billingsley		Lead Safe Certification Assessment Report						
			Inspection Company: Criterion Labs., Inc.		Taylor Elementary School and Annex						
E l e m e n t	F l o o r	Space #	On-Site Room Name	Student/ Teacher Occupied (yes/no)	Component	Substrate Material	Color	Description of Damage	Damage Quantity (sf)	XRF Reading (mg/cm2)	XRF (positive/ negative)
1	1	100A	Assistant Principal's/Dean's Office	yes	Cove Base (W3)	Concrete	Grey	None	0	N/A	N/A
1	1	100A	Assistant Principal's/Dean's Office	yes	W4	Plaster	Tan	Chipping	1	2.3	Positive
1	1	100A	Assistant Principal's/Dean's Office	yes	Floor	N/A	N/A	N/A	N/A	N/A	N/A
1	1	100A	Assistant Principal's/Dean's Office	yes	Ceiling	N/A	N/A	N/A	N/A	N/A	N/A
1	1	100B	Principal's Office	yes	W1	Plaster	Tan	Moisture Damage	3	0.01	Negative
1	1	100B	Principal's Office	yes	Moulding (W1)	Wood	Purple	Chipping	1	0.2	Negative
1	1	100B	Principal's Office	yes	W2	Plaster	Tan	None	0	N/A	N/A
1	1	100B	Principal's Office	yes	Moulding (W2)	Wood	Purple	Chipping	1	0.01	Negative
1	1	100B	Principal's Office	yes	W3	Plaster	Tan	None	0	N/A	N/A
1	1	100B	Principal's Office	yes	Window Stool (W3)	Wood	Tan	Cracking	2	0.1	Negative
1	1	100B	Principal's Office	yes	Radiator (W3)	Metal	Tan	None	0	N/A	N/A
1	1	100B	Principal's Office	yes	W4	Plaster	Tan	Moisture Damage	3	0.33	Negative
1	1	100B	Principal's Office	yes	Window Stool (W4)	Wood	Tan	Chipping	1	0.2	Negative
1	1	100B	Principal's Office	yes	Radiator (W4)	Metal	Tan	Chipping	1	0.01	Negative
1	1	100B	Principal's Office	yes	Floor	Concrete	Purple	None	0	N/A	N/A
1	1	100B	Principal's Office	yes	Ceiling	N/A	N/A	N/A	N/A	N/A	N/A
1	1	100G	Principal's Office Restroom	yes	W1	Plaster	Tan	None	0	N/A	N/A
1	1	100G	Principal's Office Restroom	yes	Door Frame (W1)	Wood	Purple	None	0	N/A	N/A

			School District of Philadelphia								
			Name of Inspector: Michael Barth, Melissa Billingsley		Lead Safe Certification Assessment Report						
			Inspection Company: Criterion Labs., Inc.		Taylor Elementary School and Annex						
E l e m e n t	F l o o r	Space #	On-Site Room Name	Student/ Teacher Occupied (yes/no)	Component	Substrate Material	Color	Description of Damage	Damage Quantity (sf)	XRF Reading (mg/cm2)	XRF (positive/ negative)
1	1	100G	Principal's Office Restroom	yes	W2	Plaster	Tan	Spalling	1	0.33	Negative
1	1	100G	Principal's Office Restroom	yes	Cove Base (W2)	Concrete	Purple	Friction	1	0.2	Negative
1	1	100G	Principal's Office Restroom	yes	W3	Plaster	Tan	Cracking	2	0.01	Negative
1	1	100G	Principal's Office Restroom	yes	Cove Base (W3)	Concrete	Purple	Friction	1	0	Negative
1	1	100G	Principal's Office Restroom	yes	Shelving (W3)	Wood	Tan	None	0	N/A	N/A
1	1	100G	Principal's Office Restroom	yes	W4	Plaster	Tan	None	0	N/A	N/A
1	1	100G	Principal's Office Restroom	yes	Floor	N/A	N/A	N/A	N/A	N/A	N/A
1	1	100G	Principal's Office Restroom	yes	Ceiling	N/A	N/A	N/A	N/A	N/A	N/A
1	1	100H	Principal's Office Storage Closet	yes	W1	Plaster	White	None	0	N/A	N/A
1	1	100H	Principal's Office Storage Closet	yes	Door Frame (W1)	Metal	Black	None	0	N/A	N/A
1	1	100H	Principal's Office Storage Closet	yes	W2	Plaster	White	None	0	N/A	N/A
1	1	100H	Principal's Office Storage Closet	yes	Moulding (W2)	Wood	White	None	0	N/A	N/A
1	1	100H	Principal's Office Storage Closet	yes	Electrical Conduit (W2)	Metal	White	None	0	N/A	N/A
1	1	100H	Principal's Office Storage Closet	yes	W3	Plaster	White	None	0	N/A	N/A
1	1	100H	Principal's Office Storage Closet	yes	Shelving (W3)	Wood	White	None	0	N/A	N/A

			School District of Philadelphia								
			Name of Inspector: Michael Barth, Melissa Billingsley		Lead Safe Certification Assessment Report						
			Inspection Company: Criterion Labs., Inc.		Taylor Elementary School and Annex						
E l e m e n t	F l o o r	Space #	On-Site Room Name	Student/ Teacher Occupied (yes/no)	Component	Substrate Material	Color	Description of Damage	Damage Quantity (sf)	XRF Reading (mg/cm2)	XRF (positive/ negative)
1	1	100H	Principal's Office Storage Closet	yes	Electrical Conduit (W3)	Metal	White	None	0	N/A	N/A
1	1	100H	Principal's Office Storage Closet	yes	W4	Plaster	White	None	0	N/A	N/A
1	1	100H	Principal's Office Storage Closet	yes	Moulding (W4)	Wood	White	None	0	N/A	N/A
1	1	100H	Principal's Office Storage Closet	yes	Floor	N/A	N/A	N/A	N/A	N/A	N/A
1	1	100H	Principal's Office Storage Closet	yes	Ceiling	N/A	N/A	N/A	N/A	N/A	N/A
1	1	ROOF	Roof access shaft next to Classroom 102 and Main Office	no	W1	Brick	White	None	0	N/A	N/A
1	1	ROOF	Roof access shaft next to Classroom 102 and Main Office	no	W2	Brick	White	None	0	N/A	N/A
1	1	ROOF	Roof access shaft next to Classroom 102 and Main Office	no	W3	Brick	White	None	0	N/A	N/A
1	1	ROOF	Roof access shaft next to Classroom 102 and Main Office	no	W4	Brick	White	None	0	N/A	N/A
1	1	ROOF	Roof access shaft next to Classroom 102 and Main Office	no	Floor	N/A	N/A	N/A	N/A	N/A	N/A
1	1	ROOF	Roof access shaft next to Classroom 102 and Main Office	no	Ceiling	N/A	N/A	N/A	N/A	N/A	N/A
1	1	S11	Main Stairwell and Foyer near Main Office	yes	W1	Plaster	Tan	Friction	1	0.31	Negative

			School District of Philadelphia								
			Name of Inspector: Michael Barth, Melissa Billingsley		Lead Safe Certification Assessment Report						
			Inspection Company: Criterion Labs., Inc.		Taylor Elementary School and Annex						
E l e m e n t	F l o o r	Space #	On-Site Room Name	Student/ Teacher Occupied (yes/no)	Component	Substrate Material	Color	Description of Damage	Damage Quantity (sf)	XRF Reading (mg/cm2)	XRF (positive/ negative)
1	1	S11	Main Stairwell and Foyer near Main Office	yes	W1	Plaster	White	Cracking	1	0.2	Negative
1	1	S11	Main Stairwell and Foyer near Main Office	yes	W1	Plaster	Grey	Cracking	1	0.1	Negative
1	1	S11	Main Stairwell and Foyer near Main Office	yes	Door (W1)	Metal	Brown	None	0	N/A	N/A
1	1	S11	Main Stairwell and Foyer near Main Office	yes	W2	Plaster	Tan	None	0	N/A	N/A
1	1	S11	Main Stairwell and Foyer near Main Office	yes	W2	Plaster	White	None	0	N/A	N/A
1	1	S11	Main Stairwell and Foyer near Main Office	yes	W2	Plaster	Grey	None	0	N/A	N/A
1	1	S11	Main Stairwell and Foyer near Main Office	yes	Handrail (W2)	Wood	Brown	Friction	3	0.01	Negative
1	1	S11	Main Stairwell and Foyer near Main Office	yes	W3	Plaster	Tan	None	0	N/A	N/A
1	1	S11	Main Stairwell and Foyer near Main Office	yes	W3	Plaster	White	None	0	N/A	N/A
1	1	S11	Main Stairwell and Foyer near Main Office	yes	W3	Plaster	Grey	None	0	N/A	N/A
1	1	S11	Main Stairwell and Foyer near Main Office	yes	W4	Plaster	Tan	None	0	N/A	N/A
1	1	S11	Main Stairwell and Foyer near Main Office	yes	W4	Plaster	White	None	0	N/A	N/A
1	1	S11	Main Stairwell and Foyer near Main Office	yes	W4	Plaster	Grey	None	0	N/A	N/A
1	1	S11	Main Stairwell and Foyer near Main Office	yes	Handrail (W4)	Wood	Brown	Friction	3	0.1	Negative
1	1	S11	Main Stairwell and Foyer near Main Office	yes	Floor	Concrete	Black	None	0	N/A	N/A

			School District of Philadelphia								
			Name of Inspector: Michael Barth, Melissa Billingsley		Lead Safe Certification Assessment Report						
			Inspection Company: Criterion Labs., Inc.		Taylor Elementary School and Annex						
E l e m e n t	F l o o r	Space #	On-Site Room Name	Student/ Teacher Occupied (yes/no)	Component	Substrate Material	Color	Description of Damage	Damage Quantity (sf)	XRF Reading (mg/cm2)	XRF (positive/ negative)
1	1	S11	Main Stairwell and Foyer near Main Office	yes	Floor	Concrete	Red	None	0	N/A	N/A
1	1	S11	Main Stairwell and Foyer near Main Office	yes	Ceiling	Plaster	White	None	0	N/A	N/A
1	1	101	Classroom 101	yes	W1	Plaster	White	None	0	N/A	N/A
1	1	101	Classroom 101	yes	W1	Plaster	Blue	None	0	N/A	N/A
1	1	101	Classroom 101	yes	W1	Plaster	Tan	None	0	N/A	N/A
1	1	101	Classroom 101	yes	Door Frame (W1)	Wood	White	None	0	N/A	N/A
1	1	101	Classroom 101	yes	Door Frame (W1)	Wood	Blue	None	0	N/A	N/A
1	1	101	Classroom 101	yes	Chalkboard (W1)	Wood	Tan	None	0	N/A	N/A
1	1	101	Classroom 101	yes	Cove Base (W1)	Concrete	White	Friction	3	0.2	Negative
1	1	101	Classroom 101	yes	W2	Plaster	Tan	None	0	N/A	N/A
1	1	101	Classroom 101	yes	W2	Plaster	White	None	0	N/A	N/A
1	1	101	Classroom 101	yes	Moulding (W2)	Wood	Tan	None	0	N/A	N/A
1	1	101	Classroom 101	yes	Cove Base (W2)	Concrete	White	Friction	5	0.32	Negative
1	1	101	Classroom 101	yes	Vertical Pipe in Corner (W2)	Metal	White	Chipping	1	0.01	Negative
1	1	101	Classroom 101	yes	W3	Plaster	Tan	None	0	N/A	N/A
1	1	101	Classroom 101	yes	W3	Plaster	White	None	0	N/A	N/A
1	1	101	Classroom 101	yes	Moulding (W3)	Wood	Tan	None	0	N/A	N/A
1	1	101	Classroom 101	yes	Window Stool (W3)	Wood	Tan	Cracking	1	0.03	Negative
1	1	101	Classroom 101	yes	Radiator (W3)	Metal	Tan	Chipping	3	0.1	Negative
1	1	101	Classroom 101	yes	W4	Plaster	White	None	0	N/A	N/A
1	1	101	Classroom 101	yes	W4	Plaster	Blue	None	0	N/A	N/A
1	1	101	Classroom 101	yes	Moulding (W4)	Wood	White	None	0	N/A	N/A
1	1	101	Classroom 101	yes	Moulding (W4)	Wood	Blue	Chipping	1	0	Negative
1	1	101	Classroom 101	yes	cove Base (W4)	Concrete	White	Friction	3	0.01	Negative

			School District of Philadelphia								
			Name of Inspector: Michael Barth, Melissa Billingsley		Lead Safe Certification Assessment Report						
			Inspection Company: Criterion Labs., Inc.		Taylor Elementary School and Annex						
E l e m e n t	F l o o r	Space #	On-Site Room Name	Student/ Teacher Occupied (yes/no)	Component	Substrate Material	Color	Description of Damage	Damage Quantity (sf)	XRF Reading (mg/cm2)	XRF (positive/ negative)
1	1	101	Classroom 101	yes	Small Closet Space Door (W4)	Metal	Tan	Chipping	1	0.21	Negative
1	1	101	Classroom 101	yes	Small Closet Space Interior (W4)	Wood	Tan	Cracking	1	0.34	Negative
1	1	101	Classroom 101	yes	Small Closet Space Shelving (W4)	Wood	Tan	Cracking	1	0.01	Negative
1	1	101	Classroom 101	yes	Floor	Wood	N/A	N/A	0	N/A	N/A
1	1	101	Classroom 101	yes	Ceiling	N/A	N/A	N/A	N/A	N/A	N/A
1	1	101A	Classroom 101 Storage	yes	W1	Plaster	Tan	None	0	N/A	N/A
1	1	101A	Classroom 101 Storage	yes	Door Frame (W1)	Wood	Tan	Cracking	2	0	Negative
1	1	101A	Classroom 101 Storage	yes	Cove Base (W1)	Concrete	Tan	None	0	N/A	N/A
1	1	101A	Classroom 101 Storage	yes	W2	Plaster	Tan	None	0	N/A	N/A
1	1	101A	Classroom 101 Storage	yes	Shelving (W2)	Wood	Tan	None	0	N/A	N/A
1	1	101A	Classroom 101 Storage	yes	Cove Base (W2)	Concrete	Tan	Friction	3	0.03	Negative
1	1	101A	Classroom 101 Storage	yes	W3	Plaster	Tan	Cracking	1	0.4	Negative
1	1	101A	Classroom 101 Storage	yes	Window Stool (W3)	Wood	Tan	Chipping	1	0.33	Negative
1	1	101A	Classroom 101 Storage	yes	Cove Base (W3)	Concrete	Tan	Friction	2	0.01	Negative
1	1	101A	Classroom 101 Storage	yes	W4	Plaster	Tan	None	0	N/A	N/A
1	1	101A	Classroom 101 Storage	yes	Shelving (W4)	Wood	Tan	None	0	N/A	N/A

			School District of Philadelphia								
			Name of Inspector: Michael Barth, Melissa Billingsley		Lead Safe Certification Assessment Report						
			Inspection Company: Criterion Labs., Inc.		Taylor Elementary School and Annex						
E l e m e n t	F l o o r	Space #	On-Site Room Name	Student/ Teacher Occupied (yes/no)	Component	Substrate Material	Color	Description of Damage	Damage Quantity (sf)	XRF Reading (mg/cm2)	XRF (positive/ negative)
1	1	101A	Classroom 101 Storage	yes	Cove Base (W4)	Concrete	Tan	Friction	1	0	Negative
1	1	101A	Classroom 101 Storage	yes	Floor	Wood	N/A	N/A	0	N/A	N/A
1	1	101A	Classroom 101 Storage	yes	Ceiling	N/A	N/A	N/A	N/A	N/A	N/A
1	1	102	Classroom 102	yes	W1	Plaster	White	None	0	N/A	N/A
1	1	102	Classroom 102	yes	W1	Plaster	Tan	None	0	N/A	N/A
1	1	102	Classroom 102	yes	Moulding (W1)	Wood	White	None	0	N/A	N/A
1	1	102	Classroom 102	yes	Door (W1)	Wood	Tan	Friction	1		
1	1	102	Classroom 102	yes	Cove Base (W1)	Concrete	Tan	None	0	N/A	N/A
1	1	102	Classroom 102	yes	W2	Plaster	White	None	0	N/A	N/A
1	1	102	Classroom 102	yes	W2	Plaster	Tan	None	0	N/A	N/A
1	1	102	Classroom 102	yes	Moulding (W2)	Wood	White	None	0	N/A	N/A
1	1	102	Classroom 102	yes	Moulding (W2)	Wood	Tan	Chipping	1	0	Negative
1	1	102	Classroom 102	yes	W3	Plaster	White	None	0	N/A	N/A
1	1	102	Classroom 102	yes	W3	Plaster	Tan	None	0	N/A	N/A
1	1	102	Classroom 102	yes	Window Stool (W3)	Wood	Tan	Cracking	2		
1	1	102	Classroom 102	yes	Radiator (W3)	Metal	Tan	Chipping	3	0	Negative
1	1	102	Classroom 102	yes	Cove Base (W3)	Concrete	Tan	None	0	N/A	N/A
1	1	102	Classroom 102	yes	W4	Plaster	White	None	0	N/A	N/A
1	1	102	Classroom 102	yes	W4	Plaster	Tan	Chipping	2		
1	1	102	Classroom 102	yes	Moulding (W4)	Wood	White	None	0	N/A	N/A
1	1	102	Classroom 102	yes	Moulding (W4)	Wood	Tan	None	0	N/A	N/A
1	1	102	Classroom 102	yes	Small Closet Space Door (W4)	Metal	Tan	None	0	N/A	N/A
1	1	102	Classroom 102	yes	Small Closet Space Shelving (W4)	Wood	Tan	Cracking	1		

			School District of Philadelphia								
			Name of Inspector: Michael Barth, Melissa Billingsley		Lead Safe Certification Assessment Report						
			Inspection Company: Criterion Labs., Inc.		Taylor Elementary School and Annex						
E l e m e n t	F l o o r	Space #	On-Site Room Name	Student/ Teacher Occupied (yes/no)	Component	Substrate Material	Color	Description of Damage	Damage Quantity (sf)	XRF Reading (mg/cm2)	XRF (positive/ negative)
1	1	102	Classroom 102	yes	Small Closet Space Interior (W4)	Wood	Tan	None	0	N/A	N/A
1	1	102	Classroom 102	yes	Floor	Wood	N/A	N/A	0	N/A	N/A
1	1	102	Classroom 102	yes	Ceiling	N/A	N/A	N/A	N/A	N/A	N/A
1	1	102A	Classroom 102 Storage	yes	W1	Plaster	Tan	None	0	N/A	N/A
1	1	102A	Classroom 102 Storage	yes	Door Frame (W1)	Wood	Tan	Cracking	1	0	Negative
1	1	102A	Classroom 102 Storage	yes	W2	Plaster	Tan	Chipping	1		
1	1	102A	Classroom 102 Storage	yes	Shelving (W2)	Wood	Tan	None	0	N/A	N/A
1	1	102A	Classroom 102 Storage	yes	Cove Base (W2)	Concrete	Tan	Friction	2	0	Negative
1	1	102A	Classroom 102 Storage	yes	W3	Plaster	Tan	None	0	N/A	N/A
1	1	102A	Classroom 102 Storage	yes	Cove Base (W3)	Concrete	Tan	None	0	N/A	N/A
1	1	102A	Classroom 102 Storage	yes	W4	Plaster	Tan	Cracking	1	0.23	Negative
1	1	102A	Classroom 102 Storage	yes	Shelving (W4)	Wood	Tan	None	0	N/A	N/A
1	1	102A	Classroom 102 Storage	yes	Cove Base (W4)	Concrete	Tan	Friction	2	0.3	Negative
1	1	102A	Classroom 102 Storage	yes	Floor	Wood	N/A	N/A	0	N/A	N/A
1	1	102A	Classroom 102 Storage	yes	Ceiling	N/A	N/A	N/A	N/A	N/A	N/A
1	1	103	Classroom 103	yes	W1	Plaster	Tan	Chipping	1	2.3	Positive
1	1	103	Classroom 103	yes	W1	Plaster	White	Chipping	1	1.4	Positive

			School District of Philadelphia								
			Name of Inspector: Michael Barth, Melissa Billingsley		Lead Safe Certification Assessment Report						
			Inspection Company: Criterion Labs., Inc.		Taylor Elementary School and Annex						
E l e m e n t	F l o o r	Space #	On-Site Room Name	Student/ Teacher Occupied (yes/no)	Component	Substrate Material	Color	Description of Damage	Damage Quantity (sf)	XRF Reading (mg/cm2)	XRF (positive/ negative)
1	1	103	Classroom 103	yes	Door Frame (W1)	Wood	Tan	Chipping	2	0	Negative
1	1	103	Classroom 103	yes	Cove Base (W1)	Concrete	Tan	Chipping	1	0.01	Negative
1	1	103	Classroom 103	yes	Moulding (W2)	Wood	Tan	Chipping	2	0.2	Negative
1	1	103	Classroom 103	yes	Cove Base (W2)	Wood	Tan	Chipping	2	0	Negative
1	1	103	Classroom 103	yes	Cove Base (W2)	Wood	White	Chipping	2	0.1	Negative
1	1	103	Classroom 103	yes	W2	Plaster	Tan	None	0	N/A	N/A
1	1	103	Classroom 103	yes	W2	Plaster	White	None	0	N/A	N/A
1	1	103	Classroom 103	yes	Radiator (W3)	Metal	Tan	Flaking	10	0.1	Negative
1	1	103	Classroom 103	yes	Window Stool (W3)	Wood	Tan	Flaking	5	0	Negative
1	1	103	Classroom 103	yes	W3	Plaster	White	None	N/A	N/A	N/A
1	1	103	Classroom 103	yes	W3	Plaster	Tan	None	N/A	N/A	N/A
1	1	103	Classroom 103	yes	W4	Plaster	Tan	Chipping	1	3.2	Positive
1	1	103	Classroom 103	yes	W4	Plaster	White	None	0	N/A	N/A
1	1	103	Classroom 103	yes	Floor	N/A	N/A	N/A	N/A	N/A	N/A
1	1	103	Classroom 103	yes	Ceiling	N/A	N/A	N/A	N/A	N/A	N/A
1	1	103A	Classroom 103 Storage	yes	W1	Plaster	Tan	None	0	N/A	N/A
1	1	103A	Classroom 103 Storage	yes	Door Frame (W1)	Wood	Tan	None	0	N/A	N/A
1	1	103A	Classroom 103 Storage	yes	W2	Plaster	Tan	None	0	N/A	N/A
1	1	103A	Classroom 103 Storage	yes	Shelving (W2)	Wood	Tan	None	0	N/A	N/A
1	1	103A	Classroom 103 Storage	yes	Cove Base (W2)	Concrete	Tan	Friction	1	0.01	Negative

			School District of Philadelphia								
			Name of Inspector: Michael Barth, Melissa Billingsley		Lead Safe Certification Assessment Report						
			Inspection Company: Criterion Labs., Inc.		Taylor Elementary School and Annex						
E l e m e n t	F l o o r	Space #	On-Site Room Name	Student/ Teacher Occupied (yes/no)	Component	Substrate Material	Color	Description of Damage	Damage Quantity (sf)	XRF Reading (mg/cm2)	XRF (positive/ negative)
1	1	103A	Classroom 103 Storage	yes	W3	Plaster	Tan	None	0	N/A	N/A
1	1	103A	Classroom 103 Storage	yes	Cove Base (W3)	Concrete	Tan	Friction	1	0.1	Negative
1	1	103A	Classroom 103 Storage	yes	W4	Plaster	Tan	None	0	N/A	N/A
1	1	103A	Classroom 103 Storage	yes	Shelving (W4)	Wood	Tan	None	0	N/A	N/A
1	1	103A	Classroom 103 Storage	yes	Cove Base (W4)	Concrete	Tan	Friction	1	0	Negative
1	1	103A	Classroom 103 Storage	yes	Floor	Wood	N/A	N/A	N/A	N/A	N/A
1	1	103A	Classroom 103 Storage	yes	Ceiling	N/A	N/A	N/A	N/A	N/A	N/A
1	1	S12	Stairwell and Foyer next to Classroom 103	yes	Stairs (W1)	Concrete	Grey	Friction	10	0.23	Negative
1	1	S12	Stairwell and Foyer next to Classroom 103	yes	Handrail (W1)	Wood	Brown	Friction	5	0.01	Negative
1	1	S12	Stairwell and Foyer next to Classroom 103	yes	W2	Plaster	Tan	None	0	N/A	N/A
1	1	S12	Stairwell and Foyer next to Classroom 103	yes	W2	Plaster	White	None	0	N/A	N/A
1	1	S12	Stairwell and Foyer next to Classroom 103	yes	Handrail (W2)	Wood	Brown	Friction	5	0.1	Negative
1	1	S12	Stairwell and Foyer next to Classroom 103	yes	Stair Riser (W2)	Concrete	Grey	None	0	N/A	N/A
1	1	S12	Stairwell and Foyer next to Classroom 103	yes	W3	Plaster	White	None	0	N/A	N/A
1	1	S12	Stairwell and Foyer next to Classroom 103	yes	W3	Plaster	Blue	None	0	N/A	N/A

			School District of Philadelphia								
			Name of Inspector: Michael Barth, Melissa Billingsley		Lead Safe Certification Assessment Report						
			Inspection Company: Criterion Labs., Inc.		Taylor Elementary School and Annex						
E l e m e n t	F l o o r	Space #	On-Site Room Name	Student/ Teacher Occupied (yes/no)	Component	Substrate Material	Color	Description of Damage	Damage Quantity (sf)	XRF Reading (mg/cm2)	XRF (positive/ negative)
1	1	S12	Stairwell and Foyer next to Classroom 103	yes	Stairs (W3)	Concrete	Grey	None	0	N/A	N/A
1	1	S12	Stairwell and Foyer next to Classroom 103	yes	Door Frame (W3)	Metal	Black	None	0	N/A	N/A
1	1	S12	Stairwell and Foyer next to Classroom 103	yes	Electrical Conduit (W3)	Metal	White	None	0	N/A	N/A
1	1	S12	Stairwell and Foyer next to Classroom 103	yes	Electrical Conduit (W3)	Metal	Blue	None	0	N/A	N/A
1	1	S12	Stairwell and Foyer next to Classroom 103	yes	W4	Plaster	Tan	None	0	N/A	N/A
1	1	S12	Stairwell and Foyer next to Classroom 103	yes	W4	Plaster	White	None	0	N/A	N/A
1	1	S12	Stairwell and Foyer next to Classroom 103	yes	Stairs (W4)	Concrete	Grey	None	0	N/A	N/A
1	1	S12	Stairwell and Foyer next to Classroom 103	yes	Handrail (W4)	Wood	Brown	Friction	5	0.01	Negative
1	1	S12	Stairwell and Foyer next to Classroom 103	yes	Floor	Concrete	Red	Friction	5	0.41	Negative
1	1	S12	Stairwell and Foyer next to Classroom 103	yes	Floor	Concrete	Grey	Friction	5	0.22	Negative
1	1	S12	Stairwell and Foyer next to Classroom 103	yes	Ceiling	N/A	N/A	N/A	N/A	N/A	N/A
1	1	104	Classroom 104	yes	W1	Plaster	White	None	0	N/A	N/A
1	1	104	Classroom 104	yes	W1	Plaster	Tan	Chipping	3	1.1	Positive
1	1	104	Classroom 104	yes	Door Frame (W2)	Wood	Tan	Chipping	1	0.02	Negative
1	1	104	Classroom 104	yes	Small Closet Space Door (W2)	Metal	Tan	Chipping	2	0.01	Negative
1	1	104	Classroom 104	yes	Small Closet Space Shelving (W2)	Wood	Tan	Chipping	2	0.01	Negative

			School District of Philadelphia								
			Name of Inspector: Michael Barth, Melissa Billingsley		Lead Safe Certification Assessment Report						
			Inspection Company: Criterion Labs., Inc.		Taylor Elementary School and Annex						
E l e m e n t	F l o o r	Space #	On-Site Room Name	Student/ Teacher Occupied (yes/no)	Component	Substrate Material	Color	Description of Damage	Damage Quantity (sf)	XRF Reading (mg/cm2)	XRF (positive/ negative)
1	1	104	Classroom 104	yes	Small Closet Space Interior (W2)	Wood	Tan	Chipping	2	0	Negative
1	1	104	Classroom 104	yes	W2	Plaster	Tan	Chipping	1	2.3	Positive
1	1	104	Classroom 104	yes	W2	Plaster	White	Chipping	1	0.41	Negative
1	1	104	Classroom 104	yes	Cove Base (W2)	Concrete	Grey	Chipping	1	0.11	Negative
1	1	104	Classroom 104	yes	Window Stool (W3)	Wood	Tan	None	0	N/A	N/A
1	1	104	Classroom 104	yes	Radiator (W3)	Metal	Tan	Chipping	10	0.01	Negative
1	1	104	Classroom 104	yes	W3	Plaster	Tan	Chipping	1	1.5	Positive
1	1	104	Classroom 104	yes	W3	Plaster	White	None	0	N/A	N/A
1	1	104	Classroom 104	yes	Cove Base (W3)	Concrete	Tan	Friction	5	0.01	Negative
1	1	104	Classroom 104	yes	W4	Plaster	Tan	Chipping	1	0.5	Negative
1	1	104	Classroom 104	yes	W4	Plaster	White	None	0	N/A	N/A
1	1	104	Classroom 104	yes	Cove Base (W4)	Concrete	Tan	Chipping	5	0.2	Negative
1	1	104	Classroom 104	yes	Floor	N/A	N/A	N/A	N/A	N/A	N/A
1	1	104	Classroom 104	yes	Ceiling	N/A	N/A	N/A	N/A	N/A	N/A
1	1	104A	Classroom 104 Storage	yes	W1	Plaster	White	None	0	N/A	N/A
1	1	104A	Classroom 104 Storage	yes	Door Frame (W1)	Metal	Brown	Chipping	2	0.01	Negative
1	1	104A	Classroom 104 Storage	yes	Cove Base (W1)	Concrete	Brown	Chipping	1	0	Negative
1	1	104A	Classroom 104 Storage	yes	W2	Plaster	White	Chipping	1	1.2	Positive
1	1	104A	Classroom 104 Storage	yes	Cove Base (W2)	Concrete	Brown	Chipping	1	0.01	Negative
1	1	104A	Classroom 104 Storage	yes	W3	Plaster	White	Chipping	1	4.1	Positive
1	1	104A	Classroom 104 Storage	yes	Cove Base (W3)	Concrete	Brown	Chipping	1	0	Negative

			School District of Philadelphia								
			Name of Inspector: Michael Barth, Melissa Billingsley		Lead Safe Certification Assessment Report						
			Inspection Company: Criterion Labs., Inc.		Taylor Elementary School and Annex						
E l e m e n t	F l o o r	Space #	On-Site Room Name	Student/ Teacher Occupied (yes/no)	Component	Substrate Material	Color	Description of Damage	Damage Quantity (sf)	XRF Reading (mg/cm2)	XRF (positive/ negative)
1	1	104A	Classroom 104 Storage	yes	W4	Plaster	White	Chipping	1	1.3	Positive
1	1	104A	Classroom 104 Storage	yes	Cove Base (W4)	Concrete	Brown	Chipping	1	0.1	Negative
1	1	104A	Classroom 104 Storage	yes	Floor	N/A	N/A	N/A	N/A	N/A	N/A
1	1	104A	Classroom 104 Storage	yes	Ceiling	N/A	N/A	N/A	N/A	N/A	N/A
1	1	107	Boy's Restroom next to Classroom 104	yes	W1	Concrete	Tan	None	0	N/A	N/A
1	1	107	Boy's Restroom next to Classroom 104	yes	W1	Plaster	Tan	None	0	N/A	N/A
1	1	107	Boy's Restroom next to Classroom 104	yes	W1	Metal	Tan	Chipping	1	0.01	Negative
1	1	107	Boy's Restroom next to Classroom 104	yes	Door Frame (W1)	Metal	Black	None	0	N/A	N/A
1	1	107	Boy's Restroom next to Classroom 104	yes	W2	Concrete	Tan	None	0	N/A	N/A
1	1	107	Boy's Restroom next to Classroom 104	yes	W3	Plaster	Tan	None	0	N/A	N/A
1	1	107	Boy's Restroom next to Classroom 104	yes	W4	Plaster	Tan	Cracking	1	0.2	Negative
1	1	107	Boy's Restroom next to Classroom 104	yes	Radiator (W4)	Metal	Blue	Chipping	3	5.7	Positive
1	1	107	Boy's Restroom next to Classroom 104	yes	Window Stool (W4)	Wood	Blue	Cracking	1	0.13	Negative
1	1	107	Boy's Restroom next to Classroom 104	yes	Floor	N/A	N/A	N/A	N/A	N/A	N/A
1	1	107	Boy's Restroom next to Classroom 104	yes	Ceiling	Plaster	White	Cracking	1	0.3	Negative

			School District of Philadelphia								
			Name of Inspector: Michael Barth, Melissa Billingsley		Lead Safe Certification Assessment Report						
			Inspection Company: Criterion Labs., Inc.		Taylor Elementary School and Annex						
E l e m e n t	F l o o r	Space #	On-Site Room Name	Student/ Teacher Occupied (yes/no)	Component	Substrate Material	Color	Description of Damage	Damage Quantity (sf)	XRF Reading (mg/cm2)	XRF (positive/ negative)
1	1	108	Girl's Restroom next to Classroom 104	yes	W1	Plaster	White	None	0	N/A	N/A
1	1	108	Girl's Restroom next to Classroom 104	yes	Door Frame (W1)	Metal	Black	Friction	1	0.01	Negative
1	1	108	Girl's Restroom next to Classroom 104	yes	W2	Concrete	White	None	0	N/A	N/A
1	1	108	Girl's Restroom next to Classroom 104	yes	W3	Plaster	White	None	0	N/A	N/A
1	1	108	Girl's Restroom next to Classroom 104	yes	W4	Plaster	White	None	0	N/A	N/A
1	1	108	Girl's Restroom next to Classroom 104	yes	Floor	N/A	N/A	N/A	N/A	N/A	N/A
1	1	108	Girl's Restroom next to Classroom 104	yes	Ceiling	Plaster	White	Chipping	2	0.1	Negative
1	1	S14	Stairwell next to Classroom 104	yes	W1	Plaster	Tan	None	N/A	N/A	N/A
1	1	S14	Stairwell next to Classroom 104	yes	W1	Plaster	White	None	N/A	N/A	N/A
1	1	S14	Stairwell next to Classroom 104	yes	Stairs (W1)	Concrete	Grey	None	N/A	N/A	N/A
1	1	S14	Stairwell next to Classroom 104	yes	Door (W1)	Metal	Grey	Chipping	1	0.01	Negative
1	1	S14	Stairwell next to Classroom 104	yes	W2	Plaster	Tan	None	N/A	N/A	N/A
1	1	S14	Stairwell next to Classroom 104	yes	W2	Plaster	White	None	N/A	N/A	N/A
1	1	S14	Stairwell next to Classroom 104	yes	Stair Riser (W2)	Concrete	Grey	None	N/A	N/A	N/A
1	1	S14	Stairwell next to Classroom 104	yes	W3	Plaster	Tan	None	N/A	N/A	N/A

			School District of Philadelphia								
			Name of Inspector: Michael Barth, Melissa Billingsley		Lead Safe Certification Assessment Report						
			Inspection Company: Criterion Labs., Inc.		Taylor Elementary School and Annex						
E l e m e n t	F l o o r	Space #	On-Site Room Name	Student/ Teacher Occupied (yes/no)	Component	Substrate Material	Color	Description of Damage	Damage Quantity (sf)	XRF Reading (mg/cm2)	XRF (positive/ negative)
1	1	S14	Stairwell next to Classroom 104	yes	W3	Plaster	White	None	N/A	N/A	N/A
1	1	S14	Stairwell next to Classroom 104	yes	Stair Riser (W3)	Concrete	Grey	Friction	2	0.1	Negative
1	1	S14	Stairwell next to Classroom 104	yes	Handrail (W3)	Wood	Brown	Friction	2	0.2	Negative
1	1	S14	Stairwell next to Classroom 104	yes	W4	Plaster	Tan	Hole	1	0.21	Negative
1	1	S14	Stairwell next to Classroom 104	yes	W4	Plaster	White	None	0	N/A	N/A
1	1	S14	Stairwell next to Classroom 104	yes	Stair Riser (W4)	Concrete	Grey	None	0	N/A	N/A
1	1	S14	Stairwell next to Classroom 104	yes	Floor	Concrete	Red	Friction	2	0	Negative
1	1	S14	Stairwell next to Classroom 104	yes	Floor	Concrete	Grey	Friction	2	0.3	Negative
1	1	S14	Stairwell next to Classroom 104	yes	Ceiling	N/A	N/A	N/A	N/A	N/A	N/A
1	1	109	Classroom 105	yes	W1	Plaster	Tan	Chipping	1	2.1	Positive
1	1	109	Classroom 105	yes	W2	Plaster	Tan	Cracking	6	3.2	Positive
1	1	109	Classroom 105	yes	W3	Plaster	Tan	Chipping	1	1.4	Positive
1	1	109	Classroom 105	yes	W4	Plaster	Tan	Chipping	1	0.9	Positive
1	1	109	Classroom 105	yes	Window Stool (W4)	Wood	Brown	Chipping	2	0.1	Negative
1	1	109	Classroom 105	yes	Floor	N/A	N/A	N/A	N/A	N/A	N/A
1	1	109	Classroom 105	yes	Ceiling	N/A	N/A	N/A	N/A	N/A	N/A
1	1	109	Classroom 105 Closet Space	yes	W1	Plaster	White	None	0	N/A	N/A
1	1	109	Classroom 105 Closet Space	yes	Door Frame (W1)	Wood	Black	Chipping	1	0.1	Negative

			School District of Philadelphia								
			Name of Inspector: Michael Barth, Melissa Billingsley		Lead Safe Certification Assessment Report						
			Inspection Company: Criterion Labs., Inc.		Taylor Elementary School and Annex						
E l e m e n t	F l o o r	Space #	On-Site Room Name	Student/ Teacher Occupied (yes/no)	Component	Substrate Material	Color	Description of Damage	Damage Quantity (sf)	XRF Reading (mg/cm2)	XRF (positive/ negative)
1	1	109	Classroom 105 Closet Space	yes	W2	Plaster	White	None	0	N/A	N/A
1	1	109	Classroom 105 Closet Space	yes	W3	Plaster	White	Cracking	4	1.1	Positive
1	1	109	Classroom 105 Closet Space	yes	W4	Plaster	White	None	0	N/A	N/A
1	1	109	Classroom 105 Closet Space	yes	Floor	N/A	N/A	N/A	N/A	N/A	N/A
1	1	109	Classroom 105 Closet Space	yes	Ceiling	N/A	N/A	N/A	N/A	N/A	N/A
1	1	110	Library IMC	yes	Door Cage (W1)	Metal	Black	Chipping	1	0.1	Negative
1	1	110	Library IMC	yes	Door Frame (W1)	Metal	Orange	None	0	N/A	N/A
1	1	110	Library IMC	yes	Door Frame (W1)	Metal	Green	None	0	N/A	N/A
1	1	110	Library IMC	yes	Door (W1)	Wood	Yellow	Chipping	1	0.1	Negative
1	1	110	Library IMC	yes	W1	Brick	N/A	None	0	N/A	N/A
1	1	110	Library IMC	yes	W2	Plaster	Orange	None	0	N/A	N/A
1	1	110	Library IMC	yes	Radiator (W2)	Metal	Green	Chipping	1	0.1	Negative
1	1	110	Library IMC	yes	W3	Plaster	Yellow	Partially Inaccessible	N/A	0.03	Negative
1	1	110	Library IMC	yes	W4	Plaster	Green	Partially Inaccessible	N/A	0.2	Negative
1	1	110	Library IMC	yes	Floor	N/A	N/A	N/A	N/A	N/A	N/A
1	1	110	Library IMC	yes	Ceiling	N/A	N/A	N/A	N/A	N/A	N/A
1	1	110A	Library Office	yes	Door (W1)	Wood	Black	Chipping	2	0.03	Negative
1	1	110A	Library Office	yes	Window Stool (W1)	Wood	Black	Chipping	2	0.1	Negative
1	1	110A	Library Office	yes	W2	Plaster	White	Chipping	1	0.34	Negative
1	1	110A	Library Office	yes	W3	Plaster	White	Chipping	1	0.2	Negative
1	1	110A	Library Office	yes	W4	Plaster	White	Cracking	1	0.4	Negative
1	1	110A	Library Office	yes	Radiator (W4)	Metal	Green	Chipping	1	0.01	Negative
1	1	110A	Library Office	yes	Floor	N/A	N/A	N/A	N/A	N/A	N/A

			School District of Philadelphia								
			Name of Inspector: Michael Barth, Melissa Billingsley		Lead Safe Certification Assessment Report						
			Inspection Company: Criterion Labs., Inc.		Taylor Elementary School and Annex						
E l e m e n t	F l o o r	Space #	On-Site Room Name	Student/ Teacher Occupied (yes/no)	Component	Substrate Material	Color	Description of Damage	Damage Quantity (sf)	XRF Reading (mg/cm2)	XRF (positive/ negative)
1	1	110A	Library Office	yes	Ceiling	N/A	N/A	N/A	N/A	N/A	N/A
1	G	0B1	Classroom B1	yes	W1	Brick	Blue	Flaking	3	1.3	Positive
1	G	0B1	Classroom B1	yes	Cove Base (W1)	Concrete	Grey	Cracking	6	0.1	Negative
1	G	0B1	Classroom B1	yes	W1	Brick	Brown	Cracking	N/A	N/A	N/A
1	G	0B1	Classroom B1	yes	Door Frame (W1)	Wood	Brown	Cracking	4	0.1	Negative
1	G	0B1	Classroom B1	yes	W2	Brick	Blue	Flaking	10	3.2	Positive
1	G	0B1	Classroom B1	yes	Cove Base (W2)	Concrete	Grey	Cracking	6	0.2	Negative
1	G	0B1	Classroom B1	yes	W2	Brick	Brown	Cracking	N/A	N/A	N/A
1	G	0B1	Classroom B1	yes	W3	Brick	Blue	Flaking	10	1.1	Positive
1	G	0B1	Classroom B1	yes	Cove Base (W3)	Concrete	Grey	Cracking	6	0.1	Negative
1	G	0B1	Classroom B1	yes	Radiator (W3)	Metal	Brown	Chipping	3	0.01	Negative
1	G	0B1	Classroom B1	yes	W4	Brick	Blue	Flaking	3	0.1	Negative
1	G	0B1	Classroom B1	yes	Cove Base (W4)	Concrete	Grey	Cracking	5	0.2	Negative
1	G	0B1	Classroom B1	yes	Floor	N/A	N/A	N/A	N/A	N/A	N/A
1	G	0B1	Classroom B1	yes	Ceiling	N/A	N/A	N/A	N/A	N/A	N/A
1	G	H01	Basement Hallways	yes	W1	Brick	White	Flaking	5	1.3	Positive
1	G	H01	Basement Hallways	yes	W1	Concrete	White	None	0	N/A	N/A
1	G	H01	Basement Hallways	yes	W1	Plaster	White	Flaking	5	5.4	Positive
1	G	H01	Basement Hallways	yes	Door (W1)	Metal	Brown	Flaking	1	0.1	Negative
1	G	H01	Basement Hallways	yes	Door Frame (W1)	Metal	Blue	Flaking	1	0.21	Negative
1	G	H01	Basement Hallways	yes	Electrical Conduit (W1)	Metal	Tan	Cracking	1	0.01	Negative
1	G	H01	Basement Hallways	yes	Fire Extinguisher Box (W1)	Metal	Red	Chipping	1	0.03	Negative
1	G	H01	Basement Hallways	yes	Cove Base (W1)	Concrete	Grey	Chipping	10	0.1	Negative
1	G	H01	Basement Hallways	yes	W1	Concrete	Blue	None	0	N/A	N/A
1	G	H01	Basement Hallways	yes	W2	Concrete	White	None	0	N/A	N/A
1	G	H01	Basement Hallways	yes	Door Frame (W2)	Metal	Black	None	0	N/A	N/A
1	G	H01	Basement Hallways	yes	W3	Concrete	White	None	0	N/A	N/A

			School District of Philadelphia								
			Name of Inspector: Michael Barth, Melissa Billingsley		Lead Safe Certification Assessment Report						
			Inspection Company: Criterion Labs., Inc.		Taylor Elementary School and Annex						
E l e m e n t	F l o o r	Space #	On-Site Room Name	Student/ Teacher Occupied (yes/no)	Component	Substrate Material	Color	Description of Damage	Damage Quantity (sf)	XRF Reading (mg/cm2)	XRF (positive/ negative)
1	G	H01	Basement Hallways	yes	W3	Brick	White	Cracking	3	2.5	Positive
1	G	H01	Basement Hallways	yes	W3	Brick	N/A	N/A	N/A	N/A	N/A
1	G	H01	Basement Hallways	yes	Cove Base (W3)	Concrete	Grey	Friction	4	0.1	Negative
1	G	H01	Basement Hallways	yes	Door Frame (W3)	Metal	Grey	Friction	3	0.3	Negative
1	G	H01	Basement Hallways	yes	W4	Sheetrock	White	None	0	N/A	N/A
1	G	H01	Basement Hallways	yes	Radiator (W4)	Metal	White	Chipping	2	0.1	Negative
1	G	H01	Basement Hallways	yes	W4	Brick	White	Chipping	2	0.9	Positive
1	G	H01	Basement Hallways	yes	W4	Brick	N/A	N/A	N/A	N/A	N/A
1	G	H01	Basement Hallways	yes	Floor	N/A	N/A	N/A	N/A	N/A	N/A
1	G	H01	Basement Hallways	yes	Ceiling	N/A	N/A	N/A	N/A	N/A	N/A
1	G	H01	Basement Hallways	yes	Ceiling	Plaster	White	Cracking	4	0.2	Negative
1	G	11B	Storage Closet in the Hallway across from Classroom B1	no	W1	Concrete	White	N/A	N/A	N/A	N/A
1	G	11B	Storage Closet in the Hallway across from Classroom B1	no	W2	Brick	White	Flaking	3	1.3	Positive
1	G	11B	Storage Closet in the Hallway across from Classroom B1	no	W3	Brick	White	Flaking	3	3.2	Positive
1	G	11B	Storage Closet in the Hallway across from Classroom B1	no	W4	Concrete	White	N/A	0	N/A	N/A
1	G	11B	Storage Closet in the Hallway across from Classroom B1	no	Floor	N/A	N/A	N/A	N/A	N/A	N/A
1	G	11B	Storage Closet in the Hallway across from Classroom B1	no	Ceiling	N/A	N/A	N/A	N/A	N/A	N/A

			School District of Philadelphia								
			Name of Inspector: Michael Barth, Melissa Billingsley		Lead Safe Certification Assessment Report						
			Inspection Company: Criterion Labs., Inc.		Taylor Elementary School and Annex						
E l e m e n t	F l o o r	Space #	On-Site Room Name	Student/ Teacher Occupied (yes/no)	Component	Substrate Material	Color	Description of Damage	Damage Quantity (sf)	XRF Reading (mg/cm2)	XRF (positive/ negative)
1	G	11A	Custodial Closet next to Classroom B1	no	W1	Sheetrock	N/A	N/A	N/A	N/A	N/A
1	G	11A	Custodial Closet next to Classroom B1	no	Door (W1)	Metal	Grey	Chipping	3	0.1	Negative
1	G	11A	Custodial Closet next to Classroom B1	no	W2	Brick	White	None	0	N/A	N/A
1	G	11A	Custodial Closet next to Classroom B1	no	Vertical Pipe (W2)	Metal	White	None	0	N/A	N/A
1	G	11A	Custodial Closet next to Classroom B1	no	W3	Brick	White	None	0	N/A	N/A
1	G	11A	Custodial Closet next to Classroom B1	no	W4	Brick	White	Cracking	1	1.4	Positive
1	G	11A	Custodial Closet next to Classroom B1	no	Door Frame (W4)	Metal	Black	Cracking	1	0.02	Negative
1	G	11A	Custodial Closet next to Classroom B1	no	Floor	N/A	N/A	N/A	N/A	N/A	N/A
1	G	11A	Custodial Closet next to Classroom B1	no	Ceiling	N/A	N/A	N/A	N/A	N/A	N/A
1	G	11A	Custodial Closet next to Classroom B1	no	W1	Brick	White	Flaking	10	5.4	Positive
1	G	11A	Custodial Closet next to Classroom B1	no	W2	Brick	White	Flaking	10	1.3	Positive
1	G	11A	Custodial Closet next to Classroom B1	no	W3	Brick	White	Flaking	10	3.1	Positive
1	G	11A	Custodial Closet next to Classroom B1	no	W4	Brick	White	Flaking	10	2.1	Positive
1	G	11A	Custodial Closet next to Classroom B1	no	Floor	Concrete	Black	N/A	N/A	N/A	N/A
1	G	11A	Custodial Closet next to Classroom B1	no	Ceiling	Plaster	White	Flaking	10	1.3	Positive

			School District of Philadelphia								
			Name of Inspector: Michael Barth, Melissa Billingsley		Lead Safe Certification Assessment Report						
			Inspection Company: Criterion Labs., Inc.		Taylor Elementary School and Annex						
E l e m e n t	F l o o r	Space #	On-Site Room Name	Student/ Teacher Occupied (yes/no)	Component	Substrate Material	Color	Description of Damage	Damage Quantity (sf)	XRF Reading (mg/cm2)	XRF (positive/ negative)
1	G	19	Classroom B5	yes	W1	Plaster	Tan	Chipping	6	0.3	Negative
1	G	19	Classroom B5	yes	Door Frame (W1)	Metal	Red	Friction	1	0.1	Negative
1	G	19	Classroom B5	yes	Cove Base (W1)	Concrete	White	None	N/A	N/A	N/A
1	G	19	Classroom B5	yes	Shelving (W2)	Wood	Red	Cracking	1	0.22	Negative
1	G	19	Classroom B5	yes	Closet Fixtures (W2)	Metal	Red	Chipping	1	0.01	Negative
1	G	19	Classroom B5	yes	W2	Concrete	White	None	N/A	N/A	N/A
1	G	19	Classroom B5	yes	W3	Concrete	White	None	0	N/A	N/A
1	G	19	Classroom B5	yes	W3	Concrete	Red	None	0	N/A	N/A
1	G	19	Classroom B5	yes	Door Frame (W3)	Metal	Red	None	0	N/A	N/A
1	G	19	Classroom B5	yes	Radiator (W3)	Metal	Grey	Chipping	1	0.02	Negative
1	G	19	Classroom B5	yes	Radiator (W3)	Metal	Red	Chipping	5	0.1	Negative
1	G	19	Classroom B5	yes	Window Stool (W3)	Wood	Green	Chipping	1	0	Negative
1	G	19	Classroom B5	yes	Window Stool (W3)	Wood	Yellow	Chipping	1	0.1	Negative
1	G	19	Classroom B5	yes	Window Stool (W3)	Wood	Blue	Chipping	1	0.2	Negative
1	G	19	Classroom B5	yes	W4	Plaster	Tan	None	0	N/A	N/A
1	G	19	Classroom B5	yes	W4	Concrete	Tan	Chipping	3	0.11	Negative
1	G	19	Classroom B5	yes	Floor	N/A	N/A	N/A	N/A	N/A	N/A
1	G	19	Classroom B5	yes	Ceiling	N/A	N/A	N/A	N/A	N/A	N/A
1	G	19	Classroom B5	yes	W1	Concrete	White	None	N/A	N/A	N/A
1	G	21	Classroom B5 Storage Closet	yes	W2	Concrete	White	None	N/A	N/A	N/A
1	G	21	Classroom B5 Storage Closet	yes	W3	Concrete	White	None	N/A	N/A	N/A
1	G	21	Classroom B5 Storage Closet	yes	W4	Concrete	White	None	N/A	N/A	N/A
1	G	21	Classroom B5 Storage Closet	yes	Floor	N/A	N/A	N/A	N/A	N/A	N/A

			School District of Philadelphia								
			Name of Inspector: Michael Barth, Melissa Billingsley		Lead Safe Certification Assessment Report						
			Inspection Company: Criterion Labs., Inc.		Taylor Elementary School and Annex						
E l e m e n t	F l o o r	Space #	On-Site Room Name	Student/ Teacher Occupied (yes/no)	Component	Substrate Material	Color	Description of Damage	Damage Quantity (sf)	XRF Reading (mg/cm2)	XRF (positive/ negative)
1	G	21	Classroom B5 Storage Closet	yes	Ceiling	N/A	N/A	N/A	N/A	N/A	N/A
1	G	22	Classroom B5 Student Restroom	yes	W1	Plaster	White	None	N/A	N/A	N/A
1	G	22	Classroom B5 Student Restroom	yes	W2	Plaster	White	None	N/A	N/A	N/A
1	G	22	Classroom B5 Student Restroom	yes	W3	Plaster	White	None	N/A	N/A	N/A
1	G	22	Classroom B5 Student Restroom	yes	W4	Plaster	White	None	N/A	N/A	N/A
1	G	22	Classroom B5 Student Restroom	yes	Floor	N/A	N/A	None	N/A	N/A	N/A
1	G	22	Classroom B5 Student Restroom	yes	Ceiling	Plaster	White	Flaking	1	0.2	Negative
1	G	B2	Classroom B2	yes	W1	Plaster	Tan	Chipping	1	0.45	Negative
1	G	B2	Classroom B2	yes	W2	Plaster	Tan	Efflorescence	5	0.1	Negative
1	G	B2	Classroom B2	yes	W3	Plaster	Tan	Efflorescence	5	0.3	Negative
1	G	B2	Classroom B2	yes	W4	Concrete	Tan	None	0	N/A	N/A
1	G	B2	Classroom B2	yes	Floor	N/A	N/A	N/A	N/A	N/A	N/A
1	G	B2	Classroom B2	yes	Ceiling	Plaster	Tan	None	0	N/A	N/A
1	G	B10	Text book Storage room next to Classroom B2	yes	W1	Concrete	White	None	0	N/A	N/A
1	G	B10	Text book Storage room next to Classroom B2	yes	Door Frame (W1)	Metal	Tan	Chipping	1	0.1	Negative
1	G	B10	Text book Storage room next to Classroom B2	yes	Door Cage (W1)	Metal	Black	None	0	N/A	N/A

			School District of Philadelphia								
			Name of Inspector: Michael Barth, Melissa Billingsley		Lead Safe Certification Assessment Report						
			Inspection Company: Criterion Labs., Inc.		Taylor Elementary School and Annex						
E l e m e n t	F l o o r	Space #	On-Site Room Name	Student/ Teacher Occupied (yes/no)	Component	Substrate Material	Color	Description of Damage	Damage Quantity (sf)	XRF Reading (mg/cm2)	XRF (positive/ negative)
1	G	B10	Text book Storage room next to Classroom B2	yes	W2	Concrete	Brown	None	0	N/A	N/A
1	G	B10	Text book Storage room next to Classroom B2	yes	W2	Concrete	White	None	0	N/A	N/A
1	G	B10	Text book Storage room next to Classroom B2	yes	W2	Brick	Brown	None	0	N/A	N/A
1	G	B10	Text book Storage room next to Classroom B2	yes	W2	Brick	White	None	0	N/A	N/A
1	G	B10	Text book Storage room next to Classroom B2	yes	W2	Concrete	Brown	None	0	N/A	N/A
1	G	B10	Text book Storage room next to Classroom B2	yes	W3	Concrete	Brown	None	0	N/A	N/A
1	G	B10	Text book Storage room next to Classroom B2	yes	W3	Concrete	White	None	0	N/A	N/A
1	G	B10	Text book Storage room next to Classroom B2	yes	W3	Brick	Brown	Chipping	1	1.3	Positive
1	G	B10	Text book Storage room next to Classroom B2	yes	W3	Brick	White	Chipping	1	1.5	Positive
1	G	B10	Text book Storage room next to Classroom B2	yes	W3	Concrete	Brown	None	0	N/A	N/A

			School District of Philadelphia								
			Name of Inspector: Michael Barth, Melissa Billingsley		Lead Safe Certification Assessment Report						
			Inspection Company: Criterion Labs., Inc.		Taylor Elementary School and Annex						
E l e m e n t	F l o o r	Space #	On-Site Room Name	Student/ Teacher Occupied (yes/no)	Component	Substrate Material	Color	Description of Damage	Damage Quantity (sf)	XRF Reading (mg/cm2)	XRF (positive/ negative)
1	G	B10	Text book Storage room next to Classroom B2	yes	W4	Concrete	White	None	0	N/A	N/A
1	G	B10	Text book Storage room next to Classroom B2	yes	Floor	N/A	N/A	N/A	N/A	N/A	N/A
1	G	B10	Text book Storage room next to Classroom B2	yes	Ceiling	Plaster	White	None	0	N/A	N/A
1	G	16	Building Engineer's Office	no	W1	Plaster	Tan	Moisture Damage	1	0.5	Negative
1	G	16	Building Engineer's Office	no	Door Frame (W1)	Metal	Brown	None	0	N/A	N/A
1	G	16	Building Engineer's Office	no	W2	Plaster	Tan	Flaking	1	0.4	Negative
1	G	16	Building Engineer's Office	no	W3	Plaster	Tan	Moisture Damage/Flaking	5	0.22	Negative
1	G	16	Building Engineer's Office	no	W4	Plaster	Tan	Flaking	5	0.1	Negative
1	G	16	Building Engineer's Office	no	Floor	N/A	N/A	N/A	N/A	N/A	N/A
1	G	16	Building Engineer's Office	no	Ceiling	Plaster	Tan	None	0	N/A	N/A
1	G	17	Building Engineer's Restroom	no	W1	Plaster	Tan	Moisture Damage	5	0.23	Negative
1	G	17	Building Engineer's Restroom	no	Door Frame (W1)	Metal	Brown	None	0	N/A	N/A
1	G	17	Building Engineer's Restroom	no	W2	Plaster	Tan	Flaking	1	0.2	Negative

			School District of Philadelphia								
			Name of Inspector: Michael Barth, Melissa Billingsley		Lead Safe Certification Assessment Report						
			Inspection Company: Criterion Labs., Inc.		Taylor Elementary School and Annex						
E l e m e n t	F l o o r	Space #	On-Site Room Name	Student/ Teacher Occupied (yes/no)	Component	Substrate Material	Color	Description of Damage	Damage Quantity (sf)	XRF Reading (mg/cm2)	XRF (positive/ negative)
1	G	17	Building Engineer's Restroom	no	W3	Plaster	White	Moisture Damage	5	0.5	Negative
1	G	17	Building Engineer's Restroom	no	W4	Plaster	White	Moisture Damage	5	0.44	Negative
1	G	17	Building Engineer's Restroom	no	W4	Plaster	Tan	Moisture Damage	5	0.3	Negative
1	G	17	Building Engineer's Restroom	no	Floor	N/A	N/A	N/A	N/A	N/A	N/A
1	G	17	Building Engineer's Restroom	no	Ceiling	Plaster	Tan	Cracking	2	0.2	Negative
1	G	15	Staff Lounge and Storage next to Building Engineer's Office	no	W1	Brick	White	Flaking	1	0.3	Negative
1	G	15	Staff Lounge and Storage next to Building Engineer's Office	no	Door Frame (W1)	Metal	White	Chipping	1	0.1	Negative
1	G	15	Staff Lounge and Storage next to Building Engineer's Office	no	W1	Concrete	White	None	0	N/A	N/A
1	G	15	Staff Lounge and Storage next to Building Engineer's Office	no	W2	Brick	White	Flaking	10	0.22	Negative
1	G	15	Staff Lounge and Storage next to Building Engineer's Office	no	W2	Concrete	White	None	0	N/A	N/A

			School District of Philadelphia								
			Name of Inspector: Michael Barth, Melissa Billingsley		Lead Safe Certification Assessment Report						
			Inspection Company: Criterion Labs., Inc.		Taylor Elementary School and Annex						
E l e m e n t	F l o o r	Space #	On-Site Room Name	Student/ Teacher Occupied (yes/no)	Component	Substrate Material	Color	Description of Damage	Damage Quantity (sf)	XRF Reading (mg/cm2)	XRF (positive/ negative)
1	G	15	Staff Lounge and Storage next to Building Engineer's Office	no	W2	Concrete	Tan	None	0	N/A	N/A
1	G	15	Staff Lounge and Storage next to Building Engineer's Office	no	Moulding (W2)	Wood	Brown	None	0	N/A	N/A
1	G	15	Staff Lounge and Storage next to Building Engineer's Office	no	Support Beam (W2)	Metal	Blue	Flaking	1	0.1	Negative
1	G	15	Staff Lounge and Storage next to Building Engineer's Office	no	Door Frame (W2)	Metal	Grey	None	0	N/A	N/A
1	G	15	Staff Lounge and Storage next to Building Engineer's Office	no	W3	Concrete	White	Flaking	60	0.5	Negative
1	G	15	Staff Lounge and Storage next to Building Engineer's Office	no	W3	Brick	White	Flaking	5	0.32	Negative
1	G	15	Staff Lounge and Storage next to Building Engineer's Office	no	W4	Brick	White	Flaking	5	0.1	Negative

			School District of Philadelphia								
			Name of Inspector: Michael Barth, Melissa Billingsley		Lead Safe Certification Assessment Report						
			Inspection Company: Criterion Labs., Inc.		Taylor Elementary School and Annex						
E l e m e n t	F l o o r	Space #	On-Site Room Name	Student/ Teacher Occupied (yes/no)	Component	Substrate Material	Color	Description of Damage	Damage Quantity (sf)	XRF Reading (mg/cm2)	XRF (positive/ negative)
1	G	15	Staff Lounge and Storage next to Building Engineer's Office	no	Door Frame (W4)	Metal	White	Chipping	1	0.1	Negative
1	G	15	Staff Lounge and Storage next to Building Engineer's Office	no	W4	Plaster	White	Chipping	1	0.3	Negative
1	G	15	Staff Lounge and Storage next to Building Engineer's Office	no	Pipe (W4)	Metal	Orange	Flaking	1	0.02	Negative
1	G	15	Staff Lounge and Storage next to Building Engineer's Office	no	Floor	Concrete	N/A	None	0	N/A	N/A
1	G	15	Staff Lounge and Storage next to Building Engineer's Office	no	Ceiling	Plaster	White	Flaking	5	0.44	Negative
1	G	18	Restroom near Staff Lounge in Boiler Room Area	no	W1	Plaster	White	Moisture Damage	10	0.3	Negative
1	G	18	Restroom near Staff Lounge in Boiler Room Area	no	W1	Plaster	Tan	Moisture Damage	10	0.25	Negative
1	G	18	Restroom near Staff Lounge in Boiler Room Area	no	W2	Plaster	Tan	Moisture Damage	10	0.5	Negative

			School District of Philadelphia								
			Name of Inspector: Michael Barth, Melissa Billingsley		Lead Safe Certification Assessment Report						
			Inspection Company: Criterion Labs., Inc.		Taylor Elementary School and Annex						
E l e m e n t	F l o o r	Space #	On-Site Room Name	Student/ Teacher Occupied (yes/no)	Component	Substrate Material	Color	Description of Damage	Damage Quantity (sf)	XRF Reading (mg/cm2)	XRF (positive/ negative)
1	G	18	Restroom near Staff Lounge in Boiler Room Area	no	W3	Plaster	Grey	Moisture Damage	10	0.34	Negative
1	G	18	Restroom near Staff Lounge in Boiler Room Area	no	W4	Plaster	Grey	Moisture Damage	10	0.4	Negative
1	G	18	Restroom near Staff Lounge in Boiler Room Area	no	Floor	N/A	N/A	N/A	N/A	N/A	N/A
1	G	18	Restroom near Staff Lounge in Boiler Room Area	no	Ceiling	Plaster	White	Moisture Damage	10	0.1	Negative
1	G	14	Large Boiler Room	no	W1	Brick	White	Cracking	5	0.3	Negative
1	G	14	Large Boiler Room	no	W2	Brick	White	Cracking	5	0.22	Negative
1	G	14	Large Boiler Room	no	W3	Brick	White	Flaking	10	0.5	Negative
1	G	14	Large Boiler Room	no	W4	Brick	White	Cracking	5	0.1	Negative
1	G	14	Large Boiler Room	no	Floor	Concrete	N/A	N/A	N/A	N/A	N/A
1	G	14	Large Boiler Room	no	Ceiling	Plaster	White	Flaking	15	0.9	Positive
1	G	13	Small Boiler Room	no	W1	Brick	White	Cracking	5	0.1	Negative
1	G	13	Small Boiler Room	no	W2	Brick	White	Cracking	5	0.3	Negative
1	G	13	Small Boiler Room	no	W2	Brick	Grey	None	0	N/A	N/A
1	G	13	Small Boiler Room	no	W3	Brick	White	None	0	N/A	N/A
1	G	13	Small Boiler Room	no	W3	Plaster	White	Cracking	5	0.44	Negative
1	G	13	Small Boiler Room	no	W4	Brick	White	None	0	N/A	N/A
1	G	13	Small Boiler Room	no	Floor	Concrete	N/A	N/A	0	N/A	N/A
1	G	13	Small Boiler Room	no	Ceiling	Plaster	White	Flaking	5	0.5	Negative
1	G	12	Mechanical room by the Small Boiler Room	no	W1	Brick	White	Cracking	1	0.22	Negative

			School District of Philadelphia								
			Name of Inspector: Michael Barth, Melissa Billingsley		Lead Safe Certification Assessment Report						
			Inspection Company: Criterion Labs., Inc.		Taylor Elementary School and Annex						
E l e m e n t	F l o o r	Space #	On-Site Room Name	Student/ Teacher Occupied (yes/no)	Component	Substrate Material	Color	Description of Damage	Damage Quantity (sf)	XRF Reading (mg/cm2)	XRF (positive/ negative)
1	G	12	Mechanical room by the Small Boiler Room	no	W2	Brick	White	None	0	N/A	N/A
1	G	12	Mechanical room by the Small Boiler Room	no	W3	Brick	White	None	0	N/A	N/A
1	G	12	Mechanical room by the Small Boiler Room	no	W4	Brick	White	None	0	N/A	N/A
1	G	12	Mechanical room by the Small Boiler Room	no	Vertical Pipe (W4)	Metal	White	None	0	N/A	N/A
1	G	12	Mechanical room by the Small Boiler Room	no	Floor	Concrete	N/A	None	0	N/A	N/A
1	G	12	Mechanical room by the Small Boiler Room	no	Ceiling	Plaster	White	Flaking	3	3.1	Positive
1	G	11	Mechanical room to the right of Small Boiler Room	no	W1	Brick	White	None	0	N/A	N/A
1	G	11	Mechanical room to the right of Small Boiler Room	no	W2	Brick	White	Flaking	3	0.3	Negative
1	G	11	Mechanical room to the right of Small Boiler Room	no	W3	Brick	White	None	0	N/A	N/A
1	G	11	Mechanical room to the right of Small Boiler Room	no	W4	Brick	White	None	0	N/A	N/A
1	G	11	Mechanical room to the right of Small Boiler Room	no	Floor	Concrete	N/A	N/A	0	N/A	N/A
1	G	11	Mechanical room to the right of Small Boiler Room	no	Ceiling	Plaster	White	Flaking	5	0.4	Negative

			School District of Philadelphia								
			Name of Inspector: Michael Barth, Melissa Billingsley		Lead Safe Certification Assessment Report						
			Inspection Company: Criterion Labs., Inc.		Taylor Elementary School and Annex						
E l e m e n t	F l o o r	Space #	On-Site Room Name	Student/ Teacher Occupied (yes/no)	Component	Substrate Material	Color	Description of Damage	Damage Quantity (sf)	XRF Reading (mg/cm2)	XRF (positive/ negative)
1	G	B2A	Classroom B2A	yes	W1	Plaster	Tan	Flaking	3	1.2	Positive
1	G	B2A	Classroom B2A	yes	Door Frame (W1)	Metal	Grey	Chipping	1	0.1	Negative
1	G	B2A	Classroom B2A	yes	W2	Concrete	Tan	N/A	N/A	N/A	N/A
1	G	B2A	Classroom B2A	yes	W3	Brick	Tan	Chipping	2	0.8	Positive
1	G	B2A	Classroom B2A	yes	Radiator (W3)	Metal	Tan	Chipping	2	0.1	Negative
1	G	B2A	Classroom B2A	yes	W4	Wood	Tan	Chipping	1	0.02	Negative
1	G	B2A	Classroom B2A	yes	W4	Concrete	Tan	None	N/A	N/A	N/A
1	G	B2A	Classroom B2A	yes	Floor	N/A	N/A	N/A	N/A	N/A	N/A
1	G	B2A	Classroom B2A	yes	Ceiling	N/A	N/A	N/A	N/A	N/A	N/A
1	G	B7	Classroom B7	yes	W1	Plaster	Tan	Chipping	1	0.12	Negative
1	G	B7	Classroom B7	yes	W2	Plaster	Tan	Efflorescence	5	0.4	Negative
1	G	B7	Classroom B7	yes	W3	Plaster	Tan	Efflorescence	5	0.32	Negative
1	G	B7	Classroom B7	yes	W4	Concrete	Tan	None	0	N/A	N/A
1	G	B7	Classroom B7	yes	Floor	N/A	N/A	N/A	N/A	N/A	N/A
1	G	B7	Classroom B7	yes	Ceiling	Plaster	Tan	None	0	N/A	N/A
1	G	22	Classroom B4 Student Restroom	yes	W1	Plaster	White	None	N/A	N/A	N/A
1	G	22	Classroom B4 Student Restroom	yes	W2	Plaster	White	None	N/A	N/A	N/A
1	G	22	Classroom B4 Student Restroom	yes	W3	Plaster	White	None	N/A	N/A	N/A
1	G	22	Classroom B4 Student Restroom	yes	W4	Plaster	White	None	N/A	N/A	N/A
1	G	22	Classroom B4 Student Restroom	yes	Floor	N/A	N/A	None	N/A	N/A	N/A
1	G	22	Classroom B4 Student Restroom	yes	Ceiling	Plaster	White	Flaking	1	0.22	Negative

			School District of Philadelphia								
			Name of Inspector: Michael Barth, Melissa Billingsley		Lead Safe Certification Assessment Report						
			Inspection Company: Criterion Labs., Inc.		Taylor Elementary School and Annex						
E l e m e n t	F l o o r	Space #	On-Site Room Name	Student/ Teacher Occupied (yes/no)	Component	Substrate Material	Color	Description of Damage	Damage Quantity (sf)	XRF Reading (mg/cm2)	XRF (positive/ negative)
1	G	20	Storage behind Classrooms B4 & B5 (accessed from outside)	no	W1	Concrete	White	None	0	N/A	N/A
1	G	20	Storage behind Classrooms B4 & B5 (accessed from outside)	no	W2	Concrete	White	None	0	N/A	N/A
1	G	20	Storage behind Classrooms B4 & B5 (accessed from outside)	no	W3	Concrete	White	None	0	N/A	N/A
1	G	20	Storage behind Classrooms B4 & B5 (accessed from outside)	no	W4	Concrete	White	None	0	N/A	N/A
1	G	20	Storage behind Classrooms B4 & B5 (accessed from outside)	no	Floor	N/A	N/A	N/A	N/A	N/A	N/A
1	G	20	Storage behind Classrooms B4 & B5 (accessed from outside)	no	Ceiling	Plaster	White	None	0	N/A	N/A
1	G	B2B	TTRR Classroom	yes	W1	Plaster	Blue	Chipping	2	0.4	Negative
1	G	B2B	TTRR Classroom	yes	Cove Base (W1)	Concrete	Blue	Chipping	1	0.2	Negative
1	G	B2B	TTRR Classroom	yes	Moulding (W1)	Wood	Blue	None	0	N/A	N/A
1	G	B2B	TTRR Classroom	yes	Moulding (W2)	Wood	Blue	Chipping	1	0.1	Negative
1	G	B2B	TTRR Classroom	yes	W3	Plaster	Blue	None	0	N/A	N/A
1	G	B2B	TTRR Classroom	yes	Radiator (W3)	Metal	Blue	None	0	N/A	N/A

			School District of Philadelphia								
			Name of Inspector: Michael Barth, Melissa Billingsley		Lead Safe Certification Assessment Report						
			Inspection Company: Criterion Labs., Inc.		Taylor Elementary School and Annex						
E l e m e n t	F l o o r	Space #	On-Site Room Name	Student/ Teacher Occupied (yes/no)	Component	Substrate Material	Color	Description of Damage	Damage Quantity (sf)	XRF Reading (mg/cm2)	XRF (positive/ negative)
1	G	B2B	TTRR Classroom	yes	W4	Concrete	Blue	Cracking	1	0.4	Negative
1	G	B2B	TTRR Classroom	yes	Cove Base (W4)	Concrete	Orange	None	0	N/A	N/A
1	G	B2B	TTRR Classroom	yes	Floor	N/A	N/A	N/A	N/A	N/A	N/A
1	G	B2B	TTRR Classroom	yes	Ceiling	N/A	N/A	N/A	N/A	N/A	N/A
1	G	B2BA	Storage Closet in TTRR Classroom	yes	W1	Brick	White	None	0	N/A	N/A
1	G	B2BA	Storage Closet in TTRR Classroom	yes	Door Frame (W1)	Metal	Black	Chipping	1	0.01	Negative
1	G	B2BA	Storage Closet in TTRR Classroom	yes	W2	Concrete	White	None	0	N/A	N/A
1	G	B2BA	Storage Closet in TTRR Classroom	yes	W3	Concrete	White	None	0	N/A	N/A
1	G	B2BA	Storage Closet in TTRR Classroom	yes	W4	Brick	White	None	0	N/A	N/A
1	G	B2BA	Storage Closet in TTRR Classroom	yes	W4	Concrete	White	None	0	N/A	N/A
1	G	B2BA	Storage Closet in TTRR Classroom	yes	Floor	Concrete	Black	None	0	N/A	N/A
1	G	B2BA	Storage Closet in TTRR Classroom	yes	Ceiling	Plaster	White	Flaking	10	0.44	Negative
1	G	S02	Stairwell next to Classroom B3	yes	W1	Plaster	Tan	None	0	N/A	N/A
1	G	S02	Stairwell next to Classroom B3	yes	W1	Plaster	White	None	0	N/A	N/A
1	G	S02	Stairwell next to Classroom B3	yes	Handrail (W1)	Wood	Brown	Friction	2	0.03	Negative
1	G	S02	Stairwell next to Classroom B3	yes	Door (W1)	Metal	Brown	Friction	1	0.01	Negative
1	G	S02	Stairwell next to Classroom B3	yes	Stairs (W1)	Concrete	Grey	None	0	N/A	N/A

			School District of Philadelphia								
			Name of Inspector: Michael Barth, Melissa Billingsley		Lead Safe Certification Assessment Report						
			Inspection Company: Criterion Labs., Inc.		Taylor Elementary School and Annex						
E l e m e n t	F l o o r	Space #	On-Site Room Name	Student/ Teacher Occupied (yes/no)	Component	Substrate Material	Color	Description of Damage	Damage Quantity (sf)	XRF Reading (mg/cm2)	XRF (positive/ negative)
1	G	S02	Stairwell next to Classroom B3	yes	Stair Post (W1)	Concrete	Grey	Friction	2	0.2	Negative
1	G	S02	Stairwell next to Classroom B3	yes	W2	Plaster	Tan	None	0	N/A	N/A
1	G	S02	Stairwell next to Classroom B3	yes	W2	Plaster	White	None	0	N/A	N/A
1	G	S02	Stairwell next to Classroom B3	yes	Handrail (W2)	Wood	Brown	Friction	1	0.2	Negative
1	G	S02	Stairwell next to Classroom B3	yes	Stair Riser (W2)	Concrete	Grey	None	0	N/A	N/A
1	G	S02	Stairwell next to Classroom B3	yes	W3	Plaster	Tan	None	0	N/A	N/A
1	G	S02	Stairwell next to Classroom B3	yes	W3	Plaster	White	None	0	N/A	N/A
1	G	S02	Stairwell next to Classroom B3	yes	Door (W3)	Metal	Brown	Friction	1	0.2	Negative
1	G	S02	Stairwell next to Classroom B3	yes	Stairs (W3)	Concrete	Grey	None	0	N/A	N/A
1	G	S02	Stairwell next to Classroom B3	yes	W4	Plaster	Tan	None	0	N/A	N/A
1	G	S02	Stairwell next to Classroom B3	yes	W4	Plaster	White	None	0	N/A	N/A
1	G	S02	Stairwell next to Classroom B3	yes	Electrical Conduit (W4)	Metal	Tan	None	0	N/A	N/A
1	G	S02	Stairwell next to Classroom B3	yes	Electrical Conduit (W4)	Metal	White	None	0	N/A	N/A
1	G	S02	Stairwell next to Classroom B3	yes	Stair Riser (W4)	Concrete	Grey	Chipping	2	0.01	Negative
1	G	S02	Stairwell next to Classroom B3	yes	Handrail (W4)	Wood	Brown	Friction	3	0.02	Negative

			School District of Philadelphia								
			Name of Inspector: Michael Barth, Melissa Billingsley		Lead Safe Certification Assessment Report						
			Inspection Company: Criterion Labs., Inc.		Taylor Elementary School and Annex						
E l e m e n t	F l o o r	Space #	On-Site Room Name	Student/ Teacher Occupied (yes/no)	Component	Substrate Material	Color	Description of Damage	Damage Quantity (sf)	XRF Reading (mg/cm2)	XRF (positive/ negative)
1	G	S02	Stairwell next to Classroom B3	yes	Floor	Concrete	Red	Friction	2	0.2	Negative
1	G	S02	Stairwell next to Classroom B3	yes	Floor	Concrete	Black	Friction	4	0.33	Negative
1	G	S02	Stairwell next to Classroom B3	yes	Ceiling	N/A	N/A	N/A	N/A	N/A	N/A
1	G	6	Girl's Restroom next to Classroom B3	yes	W1	Plaster	White	Chipping	1	0.33	Negative
1	G	6	Girl's Restroom next to Classroom B3	yes	W2	Plaster	White	Chipping	1	0.4	Negative
1	G	6	Girl's Restroom next to Classroom B3	yes	W3	Plaster	White	None	N/A	N/A	N/A
1	G	6	Girl's Restroom next to Classroom B3	yes	W4	Plaster	White	None	N/A	N/A	N/A
1	G	6	Girl's Restroom next to Classroom B3	yes	Floor	N/A	N/A	None	N/A	N/A	N/A
1	G	6	Girl's Restroom next to Classroom B3	yes	Ceiling	Plaster	White	Flaking	1	0.2	Negative
1	G	S01	Stairwell to Main Office	yes	W1	Plaster	White	None	0	N/A	N/A
1	G	S01	Stairwell to Main Office	yes	W1	Plaster	Blue	None	0	N/A	N/A
1	G	S01	Stairwell to Main Office	yes	Moulding (W1)	Wood	Tan	None	0	N/A	N/A
1	G	S01	Stairwell to Main Office	yes	Stairs (W1)	Concrete	Grey	Chipping	10	0.4	Negative
1	G	S01	Stairwell to Main Office	yes	Handrail (W1)	Wood	Brown	Friction	5	0.1	Negative
1	G	S01	Stairwell to Main Office	yes	Door (W1)	Metal	Brown	None	0	N/A	N/A
1	G	S01	Stairwell to Main Office	yes	W2	Plaster	Tan	Cracking	5	0.33	Negative
1	G	S01	Stairwell to Main Office	yes	W2	Brick	Tan	None	0	N/A	N/A
1	G	S01	Stairwell to Main Office	yes	W2	Brick	N/A	None	0	N/A	N/A
1	G	S01	Stairwell to Main Office	yes	W3	Plaster	White	None	0	N/A	N/A
1	G	S01	Stairwell to Main Office	yes	W3	Plaster	Tan	None	0	N/A	N/A

			School District of Philadelphia								
			Name of Inspector: Michael Barth, Melissa Billingsley		Lead Safe Certification Assessment Report						
			Inspection Company: Criterion Labs., Inc.		Taylor Elementary School and Annex						
E l e m e n t	F l o o r	Space #	On-Site Room Name	Student/ Teacher Occupied (yes/no)	Component	Substrate Material	Color	Description of Damage	Damage Quantity (sf)	XRF Reading (mg/cm2)	XRF (positive/ negative)
1	G	S01	Stairwell to Main Office	yes	Door (W3)	Metal	Brown	None	0	N/A	N/A
1	G	S01	Stairwell to Main Office	yes	W4	Plaster	Tan	None	0	N/A	N/A
1	G	S01	Stairwell to Main Office	yes	W4	Plaster	White	None	0	N/A	N/A
1	G	S01	Stairwell to Main Office	yes	W4	Plaster	Red	None	0	N/A	N/A
1	G	S01	Stairwell to Main Office	yes	Electical Conduit (W4)	Metal	Tan	None	0	N/A	N/A
1	G	S01	Stairwell to Main Office	yes	Electical Conduit (W4)	Metal	White	None	0	N/A	N/A
1	G	S01	Stairwell to Main Office	yes	Moulding (W4)	Wood	Tan	None	0	N/A	N/A
1	G	S01	Stairwell to Main Office	yes	Handrail (W4)	Wood	Brown	Friction	2	0.2	Negative
1	G	S01	Stairwell to Main Office	yes	Floor	Concrete	Black	Friction	10	0.33	Negative
1	G	S01	Stairwell to Main Office	yes	Ceiling	N/A	N/A	N/A	N/A	N/A	N/A
1	G	B3	Classroom B3	yes	W1	Plaster	White	Moisture Damage	5	4.1	Positive
1	G	B3	Classroom B3	yes	W2	Concrete	White	None	0	N/A	N/A
1	G	B3	Classroom B3	yes	W3	Brick	White	None	0	N/A	N/A
1	G	B3	Classroom B3	yes	W4	Concrete	White	None	0	N/A	N/A
1	G	B3	Classroom B3	yes	Floor	N/A	N/A	N/A	N/A	N/A	N/A
1	G	B3	Classroom B3	yes	Ceiling	N/A	N/A	N/A	N/A	N/A	N/A
1	G	5A	Music Storage next to Classroom B3	yes	Door (W1)	Metal	Green	Friction	1	0.2	Negative
1	G	5A	Music Storage next to Classroom B3	yes	Door Frame (W1)	Metal	Black	Friction	1	0.1	Negative
1	G	5A	Music Storage next to Classroom B3	yes	W1	Concrete	Tan	None	0	N/A	N/A
1	G	5A	Music Storage next to Classroom B3	yes	W2	Brick	Tan	Cracking	5	0.9	Positive
1	G	5A	Music Storage next to Classroom B3	yes	W3	Brick	Tan	Cracking	1	1.4	Positive
1	G	5A	Music Storage next to Classroom B3	yes	W4	Concrete	Tan	None	0	N/A	N/A

			School District of Philadelphia								
			Name of Inspector: Michael Barth, Melissa Billingsley		Lead Safe Certification Assessment Report						
			Inspection Company: Criterion Labs., Inc.		Taylor Elementary School and Annex						
E l e m e n t	F l o o r	Space #	On-Site Room Name	Student/ Teacher Occupied (yes/no)	Component	Substrate Material	Color	Description of Damage	Damage Quantity (sf)	XRF Reading (mg/cm2)	XRF (positive/ negative)
1	G	5A	Music Storage next to Classroom B3	yes	Floor	N/A	N/A	N/A	N/A	N/A	N/A
1	G	5A	Music Storage next to Classroom B3	yes	Ceiling	N/A	N/A	N/A	N/A	N/A	N/A
1	G	24	Classroom B4 Storage	no	W1	Concrete	White	None	0	N/A	N/A
1	G	24	Classroom B4 Storage	no	W2	Concrete	White	None	0	N/A	N/A
1	G	24	Classroom B4 Storage	no	W3	Concrete	White	None	0	N/A	N/A
1	G	24	Classroom B4 Storage	no	W4	Concrete	White	None	0	N/A	N/A
1	G	24	Classroom B4 Storage	no	Floor	N/A	N/A	N/A	N/A	N/A	N/A
1	G	24	Classroom B4 Storage	no	Ceiling	N/A	N/A	N/A	N/A	N/A	N/A
1	G	25	Classroom B4	yes	W1	Plaster	Tan	Chipping	2	0.6	Negative
1	G	25	Classroom B4	yes	Door (W1)	Wood	Blue	None	0	N/A	N/A
1	G	25	Classroom B4	yes	Door Frame (W1)	Wood	Black	Friction	1	0.1	Negative
1	G	25	Classroom B4	yes	W2	Concrete	White	Flaking	1	0.2	Negative
1	G	25	Classroom B4	yes	W3	Concrete	White	Chipping	1	0.33	Negative
1	G	25	Classroom B4	yes	Window Stool (W3)	Wood	Blue	None	0	N/A	N/A
1	G	25	Classroom B4	yes	Radiator (W3)	Metal	Blue	Chipping	1	0.2	Negative
1	G	25	Classroom B4	yes	Door (W)3	Metal	Brown	None	0	N/A	N/A
1	G	25	Classroom B4	yes	W4	Concrete	White	None	0	N/A	N/A
1	G	25	Classroom B4	yes	Moulding (W4)	Wood	Blue	Friction	3	0.3	Negative
1	G	25	Classroom B4	yes	Floor	N/A	N/A	N/A	N/A	N/A	N/A
1	G	25	Classroom B4	yes	Ceiling	N/A	N/A	N/A	N/A	N/A	N/A
1	G	4	Storage next to Stairwell/Entrance to Gym	no	W1	Concrete	White	None	0	N/A	N/A
1	G	4	Storage next to Stairwell/Entrance to Gym	no	W2	Concrete	White	None	0	N/A	N/A

			School District of Philadelphia								
			Name of Inspector: Michael Barth, Melissa Billingsley		Lead Safe Certification Assessment Report						
			Inspection Company: Criterion Labs., Inc.		Taylor Elementary School and Annex						
E l e m e n t	F l o o r	Space #	On-Site Room Name	Student/ Teacher Occupied (yes/no)	Component	Substrate Material	Color	Description of Damage	Damage Quantity (sf)	XRF Reading (mg/cm2)	XRF (positive/ negative)
1	G	4	Storage next to Stairwell/Entrance to Gym	no	W3	Concrete	White	None	0	N/A	N/A
1	G	4	Storage next to Stairwell/Entrance to Gym	no	W4	Concrete	White	None	0	N/A	N/A
1	G	4	Storage next to Stairwell/Entrance to Gym	no	Floor	N/A	N/A	N/A	N/A	N/A	N/A
1	G	4	Storage next to Stairwell/Entrance to Gym	no	Ceiling	Plaster	White	None	0	N/A	N/A
1	G	3	Women's Restroom outside Gym	yes	W1	Concrete	White	None	0	N/A	N/A
1	G	3	Women's Restroom outside Gym	yes	Door Frame (W1)	Metal	Brown	None	0	0.2	Negative
1	G	3	Women's Restroom outside Gym	yes	W2	Concrete	White	None	0	N/A	N/A
1	G	3	Women's Restroom outside Gym	yes	W3	Concrete	White	None	0	N/A	N/A
1	G	3	Women's Restroom outside Gym	yes	W4	Concrete	White	None	0	N/A	N/A
1	G	3	Women's Restroom outside Gym	yes	Floor	N/A	N/A	N/A	N/A	N/A	N/A
1	G	3	Women's Restroom outside Gym	yes	Ceiling	Plaster	White	None	0	N/A	N/A
1	G	2	Men's Restroom outside Gym	yes	W1	Concrete	White	None	0	N/A	N/A
1	G	2	Men's Restroom outside Gym	yes	Door Frame (W1)	Metal	Brown	None	0	N/A	N/A

			School District of Philadelphia								
			Name of Inspector: Michael Barth, Melissa Billingsley		Lead Safe Certification Assessment Report						
			Inspection Company: Criterion Labs., Inc.		Taylor Elementary School and Annex						
E l e m e n t	F l o o r	Space #	On-Site Room Name	Student/ Teacher Occupied (yes/no)	Component	Substrate Material	Color	Description of Damage	Damage Quantity (sf)	XRF Reading (mg/cm2)	XRF (positive/ negative)
1	G	2	Men's Restroom outside Gym	yes	W2	Concrete	White	None	0	N/A	N/A
1	G	2	Men's Restroom outside Gym	yes	W3	Concrete	White	None	0	N/A	N/A
1	G	2	Men's Restroom outside Gym	yes	W4	Concrete	White	None	0	N/A	N/A
1	G	2	Men's Restroom outside Gym	yes	Floor	N/A	N/A	N/A	N/A	N/A	N/A
1	G	2	Men's Restroom outside Gym	yes	Ceiling	Plaster	White	None	0	N/A	N/A
1	G	1	Boys Restroom outside Gym	yes	W1	Concrete	White	None	0	N/A	N/A
1	G	1	Boys Restroom outside Gym	yes	Door Frame (W1)	Metal	Brown	None	0	N/A	N/A
1	G	1	Boys Restroom outside Gym	yes	W2	Concrete	White	None	0	N/A	N/A
1	G	1	Boys Restroom outside Gym	yes	W3	Concrete	White	None	0	N/A	N/A
1	G	1	Boys Restroom outside Gym	yes	W4	Concrete	White	None	0	N/A	N/A
1	G	1	Boys Restroom outside Gym	yes	Floor	N/A	N/A	N/A	N/A	N/A	N/A
1	G	1	Boys Restroom outside Gym	yes	Ceiling	Plaster	White	Chipping	3	0.2	Negative
2	G	17/17A	Gymatorium	yes	W1	Brick	Tan	None	0	N/A	N/A
2	G	17/17A	Gymatorium	yes	W1	Brick	N/A	N/A	0	N/A	N/A
2	G	17/17A	Gymatorium	yes	Basketball Backboard (W1)	Wood	Tan	Chipping	1	0.1	Negative
2	G	17/17A	Gymatorium	yes	W2	Brick	Tan	None	0	N/A	N/A
2	G	17/17A	Gymatorium	yes	W2	Brick	N/A	N/A	0	N/A	N/A

			School District of Philadelphia								
			Name of Inspector: Michael Barth, Melissa Billingsley		Lead Safe Certification Assessment Report						
			Inspection Company: Criterion Labs., Inc.		Taylor Elementary School and Annex						
E l e m e n t	F l o o r	Space #	On-Site Room Name	Student/ Teacher Occupied (yes/no)	Component	Substrate Material	Color	Description of Damage	Damage Quantity (sf)	XRF Reading (mg/cm2)	XRF (positive/ negative)
2	G	17/17A	Gymatorium	yes	Basketball Backboard (W2)	Wood	Tan	Chipping	1	0.2	Negative
2	G	17/17A	Gymatorium	yes	W3	Brick	Tan	None	0	N/A	N/A
2	G	17/17A	Gymatorium	yes	W3	Brick	N/A	N/A	0	N/A	N/A
2	G	17/17A	Gymatorium	yes	W4	Brick	Tan	None	0	N/A	N/A
2	G	17/17A	Gymatorium	yes	W4	Brick	N/A	N/A	0	N/A	N/A
2	G	17/17A	Gymatorium	yes	Basketball Backboard (W4)	Wood	Tan	Chipping	1	0.2	Negative
2	G	17/17A	Gymatorium	yes	Table Storage (W4)	Metal	Black	Friction	3	0.01	Negative
2	G	17/17A	Gymatorium	yes	Floor	N/A	N/A	N/A	N/A	N/A	N/A
2	G	17/17A	Gymatorium	yes	Ceiling	N/A	N/A	N/A	N/A	N/A	N/A
2	G	3	Gymnasium Office	yes	W1	Concrete	Green	None	0	N/A	N/A
2	G	3	Gymnasium Office	yes	Door Frame (W1)	Metal	Black	Friction	1	0.01	Negative
2	G	3	Gymnasium Office	yes	W2	Concrete	Green	None	0	N/A	N/A
2	G	3	Gymnasium Office	yes	W3	Concrete	Green	None	0	N/A	N/A
2	G	3	Gymnasium Office	yes	W4	Concrete	Green	None	0	N/A	N/A
2	G	3	Gymnasium Office	yes	Door Frame (W4)	Metal	Black	Friction	1	0.2	Negative
2	G	3	Gymnasium Office	yes	Floor	N/A	N/A	N/A	N/A	N/A	N/A
2	G	3	Gymnasium Office	yes	Ceiling	N/A	N/A	N/A	N/A	N/A	N/A
2	G	3A	Gym Office Restroom	yes	W1	Concrete	White	None	0	N/A	N/A
2	G	3A	Gym Office Restroom	yes	Door Frame (W1)	Metal	Black	Friction	1	0.1	Negative
2	G	3A	Gym Office Restroom	yes	W2	Concrete	White	None	0	N/A	N/A
2	G	3A	Gym Office Restroom	yes	W3	Concrete	White	None	0	N/A	N/A
2	G	3A	Gym Office Restroom	yes	W4	Concrete	White	None	0	N/A	N/A
2	G	3A	Gym Office Restroom	yes	Floor	N/A	N/A	N/A	N/A	N/A	N/A
2	G	3A	Gym Office Restroom	yes	Ceiling	Plaster	Tan	Moisture Damage	2	0.2	Negative
2	G	5	Gym Storage Closet	yes	W1	Concrete	White	None	0	N/A	N/A
2	G	5	Gym Storage Closet	yes	Door Frame (W1)	Metal	Black	None	0	N/A	N/A

			School District of Philadelphia								
			Name of Inspector: Michael Barth, Melissa Billingsley		Lead Safe Certification Assessment Report						
			Inspection Company: Criterion Labs., Inc.		Taylor Elementary School and Annex						
E l e m e n t	F l o o r	Space #	On-Site Room Name	Student/ Teacher Occupied (yes/no)	Component	Substrate Material	Color	Description of Damage	Damage Quantity (sf)	XRF Reading (mg/cm2)	XRF (positive/ negative)
2	G	5	Gym Storage Closet	yes	W2	Concrete	White	None	0	N/A	N/A
2	G	5	Gym Storage Closet	yes	W3	Concrete	White	None	0	N/A	N/A
2	G	5	Gym Storage Closet	yes	W4	Concrete	White	None	0	N/A	N/A
2	G	5	Gym Storage Closet	yes	Floor	N/A	N/A	N/A	N/A	N/A	N/A
2	G	5	Gym Storage Closet	yes	Ceiling	N/A	N/A	N/A	N/A	N/A	N/A
2	G	H17	Hallway/Foyer next to Gym	yes	W1	Brick	N/A	N/A	N/A	N/A	N/A
2	G	H17	Hallway/Foyer next to Gym	yes	Door (W1)	Metal	Brown	Friction	1	0.2	Negative
2	G	H17	Hallway/Foyer next to Gym	yes	W2	Brick	N/A	N/A	N/A	N/A	N/A
2	G	H17	Hallway/Foyer next to Gym	yes	W2	Brick	Blue	None	N/A	N/A	N/A
2	G	H17	Hallway/Foyer next to Gym	yes	W2	Brick	Black	None	N/A	N/A	N/A
2	G	H17	Hallway/Foyer next to Gym	yes	W2	Brick	Green	None	N/A	N/A	N/A
2	G	H17	Hallway/Foyer next to Gym	yes	W2	Brick	Tan	None	N/A	N/A	N/A
2	G	H17	Hallway/Foyer next to Gym	yes	W2	Brick	Pink	None	N/A	N/A	N/A
2	G	H17	Hallway/Foyer next to Gym	yes	W2	Brick	Red	None	N/A	N/A	N/A
2	G	H17	Hallway/Foyer next to Gym	yes	W3	Brick	N/A	N/A	N/A	N/A	N/A
2	G	H17	Hallway/Foyer next to Gym	yes	Door (W3)	Metal	Brown	Friction	1	0.01	Negative
2	G	H17	Hallway/Foyer next to Gym	yes	W4	Brick	N/A	N/A	N/A	N/A	N/A

			School District of Philadelphia								
			Name of Inspector: Michael Barth, Melissa Billingsley		Lead Safe Certification Assessment Report						
			Inspection Company: Criterion Labs., Inc.		Taylor Elementary School and Annex						
E l e m e n t	F l o o r	Space #	On-Site Room Name	Student/ Teacher Occupied (yes/no)	Component	Substrate Material	Color	Description of Damage	Damage Quantity (sf)	XRF Reading (mg/cm2)	XRF (positive/ negative)
2	G	H17	Hallway/Foyer next to Gym	yes	W4	Brick	Blue	None	N/A	N/A	N/A
2	G	H17	Hallway/Foyer next to Gym	yes	W4	Brick	Yellow	None	N/A	N/A	N/A
2	G	H17	Hallway/Foyer next to Gym	yes	Door Frame (W4)	Metal	Brown	Friction	1	0.1	Negative
2	G	H17	Hallway/Foyer next to Gym	yes	Fire Extinguisher Box (W4)	Metal	Red	Chipping	1	0.3	Negative
2	G	H17	Hallway/Foyer next to Gym	yes	Floor	N/A	N/A	N/A	N/A	N/A	N/A
2	G	H17	Hallway/Foyer next to Gym	yes	Ceiling	N/A	N/A	N/A	N/A	N/A	N/A
2	G	17C	Storage to Left of Gymnasium Restrooms	no	W1	Concrete	White	None	0	N/A	N/A
2	G	17C	Storage to Left of Gymnasium Restrooms	no	Door Frame (W1)	Metal	Black	None	0	N/A	N/A
2	G	17C	Storage to Left of Gymnasium Restrooms	no	W2	Concrete	White	None	0	N/A	N/A
2	G	17C	Storage to Left of Gymnasium Restrooms	no	W3	Concrete	White	None	0	N/A	N/A
2	G	17C	Storage to Left of Gymnasium Restrooms	no	W4	Concrete	White	None	0	N/A	N/A
2	G	17C	Storage to Left of Gymnasium Restrooms	no	Floor	N/A	N/A	N/A	N/A	N/A	N/A

			School District of Philadelphia								
			Name of Inspector: Michael Barth, Melissa Billingsley		Lead Safe Certification Assessment Report						
			Inspection Company: Criterion Labs., Inc.		Taylor Elementary School and Annex						
E l e m e n t	F l o o r	Space #	On-Site Room Name	Student/ Teacher Occupied (yes/no)	Component	Substrate Material	Color	Description of Damage	Damage Quantity (sf)	XRF Reading (mg/cm2)	XRF (positive/ negative)
2	G	17C	Storage to Left of Gymnasium Restrooms	no	Ceiling	N/A	N/A	N/A	N/A	N/A	N/A
2	G	17D	Coat Room	yes	W1	Concrete	Green	None	0	N/A	N/A
2	G	17D	Coat Room	yes	W1	Concrete	White	None	0	N/A	N/A
2	G	17D	Coat Room	yes	Door Frame (W1)	Metal	Black	None	0	N/A	N/A
2	G	17D	Coat Room	yes	W2	Concrete	Green	None	0	N/A	N/A
2	G	17D	Coat Room	yes	W2	Concrete	White	None	0	N/A	N/A
2	G	17D	Coat Room	yes	Shelving (W2)	Wood	Tan	None	0	N/A	N/A
2	G	17D	Coat Room	yes	W3	Concrete	Green	None	0	N/A	N/A
2	G	17D	Coat Room	yes	W3	Concrete	White	None	0	N/A	N/A
2	G	17D	Coat Room	yes	Shelving (W3)	Wood	Tan	None	0	N/A	N/A
2	G	17D	Coat Room	yes	W4	Concrete	Green	None	0	N/A	N/A
2	G	17D	Coat Room	yes	W4	Concrete	White	None	0	N/A	N/A
2	G	17D	Coat Room	yes	Shelving (W4)	Wood	Tan	None	0	N/A	N/A
2	G	17D	Coat Room	yes	Floor	N/A	N/A	N/A	N/A	N/A	N/A
2	G	17D	Coat Room	yes	Ceiling	N/A	N/A	N/A	N/A	N/A	N/A
2	G	B6A	Kitchen Walk in Room and Storage Area	no	W1	Plaster	Tan	Chipping	1	0.3	Negative
2	G	B6A	Kitchen Walk in Room and Storage Area	no	Door Frame (W1)	Metal	Grey	Chipping	1	0.2	Negative
2	G	B6A	Kitchen Walk in Room and Storage Area	no	W2	Sheetrock	Tan	None	0	N/A	N/A
2	G	B6A	Kitchen Walk in Room and Storage Area	no	W3	Plaster	Tan	Chipping	1	0.33	Negative
2	G	B6A	Kitchen Walk in Room and Storage Area	no	Door Frame (W3)	Metal	Grey	Chipping	2	0.01	Negative
2	G	B6A	Kitchen Walk in Room and Storage Area	no	W4	Plaster	Tan	Flaking	5	0.4	Negative

			School District of Philadelphia								
			Name of Inspector: Michael Barth, Melissa Billingsley		Lead Safe Certification Assessment Report						
			Inspection Company: Criterion Labs., Inc.		Taylor Elementary School and Annex						
E l e m e n t	F l o o r	Space #	On-Site Room Name	Student/ Teacher Occupied (yes/no)	Component	Substrate Material	Color	Description of Damage	Damage Quantity (sf)	XRF Reading (mg/cm2)	XRF (positive/ negative)
2	G	B6A	Kitchen Walk in Room and Storage Area	no	Floor	N/A	N/A	N/A	N/A	N/A	N/A
2	G	B6A	Kitchen Walk in Room and Storage Area	no	Ceiling	N/A	N/A	N/A	N/A	N/A	N/A
2	G	B6	Kitchen	yes	W1	Brick	Tan	None	0	N/A	N/A
2	G	B6	Kitchen	yes	Door Frame (W1)	Metal	Black	Chipping	3	0.02	Negative
2	G	B6	Kitchen	yes	Door (W1)	Metal	Grey	Cracking	3	0.2	Negative
2	G	B6	Kitchen	yes	W2	Brick	Tan	None	0	N/A	N/A
2	G	B6	Kitchen	yes	Electrical Conduit (W2)	Metal	Black	Chipping	1	0.2	Negative
2	G	B6	Kitchen	yes	Electrical Conduit (W2)	Metal	Grey	Friction	1	0.1	Negative
2	G	B6	Kitchen	yes	W3	Brick	Tan	None	0	N/A	N/A
2	G	B6	Kitchen	yes	W4	Brick	Tan	None	0	N/A	N/A
2	G	B6	Kitchen	yes	Door Frame (W4)	Metal	Grey	Friction	5	0.01	Negative
2	G	B6	Kitchen	yes	Floor	N/A	N/A	N/A	N/A	N/A	N/A
2	G	B6	Kitchen	yes	Ceiling	N/A	N/A	N/A	N/A	N/A	N/A
2	G	20	Kitchen Office	no	W1	Brick	Tan	None	0	N/A	N/A
2	G	20	Kitchen Office	no	Vertical Pipe (W1)	Metal	Tan	Chipping	2	0.1	Negative
2	G	20	Kitchen Office	no	Door Frame (W1)	Metal	Grey	Chipping	1	0.3	Negative
2	G	20	Kitchen Office	no	W2	Brick	Tan	None	0	N/A	N/A
2	G	20	Kitchen Office	no	W3	Brick	Tan	None	0	N/A	N/A
2	G	20	Kitchen Office	no	W4	Brick	Tan	None	0	N/A	N/A
2	G	20	Kitchen Office	no	Floor	N/A	N/A	N/A	N/A	N/A	N/A
2	G	20	Kitchen Office	no	Ceiling	N/A	N/A	N/A	N/A	N/A	N/A
2	G	8	Staff Locker Room	no	W1	Brick	Blue	None	0	N/A	N/A
2	G	8	Staff Locker Room	no	W2	Brick	Blue	None	0	N/A	N/A
2	G	8	Staff Locker Room	no	W3	Brick	Blue	None	0	N/A	N/A
2	G	8	Staff Locker Room	no	W4	Brick	Blue	None	0	N/A	N/A
2	G	8	Staff Locker Room	no	Floor	N/A	N/A	N/A	N/A	N/A	N/A

			School District of Philadelphia								
			Name of Inspector: Michael Barth, Melissa Billingsley		Lead Safe Certification Assessment Report						
			Inspection Company: Criterion Labs., Inc.		Taylor Elementary School and Annex						
E l e m e n t	F l o o r	Space #	On-Site Room Name	Student/ Teacher Occupied (yes/no)	Component	Substrate Material	Color	Description of Damage	Damage Quantity (sf)	XRF Reading (mg/cm2)	XRF (positive/ negative)
2	G	8	Staff Locker Room	no	Ceiling	N/A	N/A	N/A	N/A	N/A	N/A
2	G	11	Custodial Closet in Kitchen	no	W1	Concrete	White	None	0	N/A	N/A
2	G	11	Custodial Closet in Kitchen	no	Door Frame (W1)	Metal	Grey	Chipping	1	0.01	Negative
2	G	11	Custodial Closet in Kitchen	no	W2	Concrete	White	None	0	N/A	N/A
2	G	11	Custodial Closet in Kitchen	no	W3	Concrete	White	None	0	N/A	N/A
2	G	11	Custodial Closet in Kitchen	no	W4	Concrete	White	None	0	N/A	N/A
2	G	11	Custodial Closet in Kitchen	no	Floor	N/A	N/A	N/A	N/A	N/A	N/A
2	G	11	Custodial Closet in Kitchen	no	Ceiling	Plaster	White	None	0	N/A	N/A
2	G	9A	Kitchen Restroom	no	W1	Concrete	Blue	None	0	N/A	N/A
2	G	9A	Kitchen Restroom	no	Door Frame (W1)	Metal	Grey	Friction	1	0.02	Negative
2	G	9A	Kitchen Restroom	no	W2	Concrete	Blue	None	0	N/A	N/A
2	G	9A	Kitchen Restroom	no	W3	Concrete	Blue	None	0	N/A	N/A
2	G	9A	Kitchen Restroom	no	W4	Concrete	Blue	None	0	N/A	N/A
2	G	9A	Kitchen Restroom	no	Floor	N/A	N/A	N/A	N/A	N/A	N/A
2	G	9A	Kitchen Restroom	no	Ceiling	Plaster	Tan	Flaking	2	0.2	Negative
2	G	13	Kitchen Storage Closet Near W2	no	W1	Brick	Tan	None	0	N/A	N/A
2	G	13	Kitchen Storage Closet Near W2	no	Door Frame (W1)	Metal	Grey	Chipping	1	0.01	Negative
2	G	13	Kitchen Storage Closet Near W2	no	W2	Concrete	Tan	None	0	N/A	N/A

			School District of Philadelphia								
			Name of Inspector: Michael Barth, Melissa Billingsley		Lead Safe Certification Assessment Report						
			Inspection Company: Criterion Labs., Inc.		Taylor Elementary School and Annex						
E l e m e n t	F l o o r	Space #	On-Site Room Name	Student/ Teacher Occupied (yes/no)	Component	Substrate Material	Color	Description of Damage	Damage Quantity (sf)	XRF Reading (mg/cm2)	XRF (positive/ negative)
2	G	13	Kitchen Storage Closet Near W2	no	W3	Concrete	Tan	None	0	N/A	N/A
2	G	13	Kitchen Storage Closet Near W2	no	W4	Concrete	Tan	None	0	N/A	N/A
2	G	13	Kitchen Storage Closet Near W2	no	Floor	Concrete	N/A	N/A	N/A	N/A	N/A
2	G	13	Kitchen Storage Closet Near W2	no	Ceiling	N/A	N/A	N/A	N/A	N/A	N/A
2	G	13	Kitchen Storage Closet Near W4	no	W1	Brick	Tan	None	0	N/A	N/A
2	G	13	Kitchen Storage Closet Near W4	no	Door Frame (W1)	Metal	Grey	Chipping	1	0.01	Negative
2	G	13	Kitchen Storage Closet Near W4	no	W2	Brick	Tan	None	0	N/A	N/A
2	G	13	Kitchen Storage Closet Near W4	no	W3	Brick	Tan	None	0	N/A	N/A
2	G	13	Kitchen Storage Closet Near W4	no	W4	Brick	Tan	None	0	N/A	N/A
2	G	13	Kitchen Storage Closet Near W4	no	Floor	N/A	N/A	N/A	N/A	N/A	N/A
2	G	13	Kitchen Storage Closet Near W4	no	Ceiling	Plaster	Tan	Moisture Damage	5	0.4	Negative
1	A	AT	Attic above 3rd Fl	no	W1	Plaster	Tan	Flaking	20	0.6	Negative
1	A	AT	Attic above 3rd Fl	no	W2	Plaster	Tan	Flaking	10	0.42	Negative
1	A	AT	Attic above 3rd Fl	no	W3	Plaster	Tan	Flaking	5	0.4	Negative
1	A	AT	Attic above 3rd Fl	no	W4	Plaster	Tan	Flaking	20	0.3	Negative
1	A	AT	Attic above 3rd Fl	no	Floor	Concrete	Grey	None	0	N/A	N/A
1	A	AT	Attic above 3rd Fl	no	Ceiling	Plaster	Tan	None	0	N/A	N/A

			School District of Philadelphia								
			Name of Inspector: Michael Barth, Melissa Billingsley		Lead Safe Certification Assessment Report						
			Inspection Company: Criterion Labs., Inc.		Taylor Elementary School and Annex						
E l e m e n t	F l o o r	Space #	On-Site Room Name	Student/ Teacher Occupied (yes/no)	Component	Substrate Material	Color	Description of Damage	Damage Quantity (sf)	XRF Reading (mg/cm2)	XRF (positive/ negative)
1	A	AT	Attic above Gymatorium	no	W1	Plaster	Tan	Flaking	20	0.5	Negative
1	A	AT	Attic above Gymatorium	no	W2	Plaster	Tan	Flaking	20	0.33	Negative
1	A	AT	Attic above Gymatorium	no	W3	Plaster	Tan	Flaking	5	0.1	Negative
1	A	AT	Attic above Gymatorium	no	W4	Plaster	Tan	Flaking	5	0.4	Negative
1	A	AT	Attic above Gymatorium	no	Floor	Concrete	Grey	None	0	N/A	N/A
1	A	AT	Attic above Gymatorium	no	Ceiling	Plaster	Tan	None	0	N/A	N/A
1	C	CS	Crawlspc	no	W1	Wood	N/A	N/A	N/A	N/A	N/A
1	C	CS	Crawlspc	no	W2	Wood	N/A	N/A	N/A	N/A	N/A
1	C	CS	Crawlspc	no	W3	Wood	N/A	N/A	N/A	N/A	N/A
1	C	CS	Crawlspc	no	W4	Wood	N/A	N/A	N/A	N/A	N/A
1	C	CS	Crawlspc	no	Floor	Concrete	N/A	N/A	N/A	N/A	N/A
1	C	CS	Crawlspc	no	Ceiling	Concrete	N/A	N/A	N/A	N/A	N/A
1	3	333	Classroom 33	yes	W1	Plaster	White	None	0	N/A	N/A
1	3	333	Classroom 33	yes	Door (W1)	Wood	Green	Chipping	6	0.04	Negative
1	3	333	Classroom 33	yes	W2	Plaster	White	None	0	N/A	N/A
1	3	333	Classroom 33	yes	W2	Plaster	Green	None	0	N/A	N/A
1	3	333	Classroom 33	yes	Vertical Pipe (W2)	Metal	White	None	0	N/A	N/A
1	3	333	Classroom 33	yes	W3	Plaster	White	None	0	N/A	N/A
1	3	333	Classroom 33	yes	W3	Plaster	Green	Cracking	2	0.1	Negative
1	3	333	Classroom 33	yes	Radiator (W3)	Metal	White	Chipping	1	0.03	Negative
1	3	333	Classroom 33	yes	W4	Plaster	White	None	0	N/A	N/A
1	3	333	Classroom 33	yes	W4	Plaster	Green	Chipping	1	0.07	Negative

			School District of Philadelphia								
			Name of Inspector: Michael Barth, Melissa Billingsley		Lead Safe Certification Assessment Report						
			Inspection Company: Criterion Labs., Inc.		Taylor Elementary School and Annex						
E l e m e n t	F l o o r	Space #	On-Site Room Name	Student/ Teacher Occupied (yes/no)	Component	Substrate Material	Color	Description of Damage	Damage Quantity (sf)	XRF Reading (mg/cm2)	XRF (positive/ negative)
1	3	333	Classroom 33	yes	Chalkboard (W4)	Wood	Green	Chipping	1	0.17	Negative
1	3	333	Classroom 33	yes	Floor	N/A	N/A	N/A	N/A	N/A	N/A
1	3	333	Classroom 33	yes	Ceiling	N/A	N/A	N/A	N/A	N/A	N/A
1	3	334	Classroom 34	yes	W1	Plaster	Yellow	None	0	N/A	N/A
1	3	334	Classroom 34	yes	Door Frame (W1)	Wood	Orange	None	0	N/A	N/A
1	3	334	Classroom 34	yes	Door (W1)	Wood	Yellow	None	0	N/A	N/A
1	3	334	Classroom 34	yes	W2	Plaster	Yellow	None	0	N/A	N/A
1	3	334	Classroom 34	yes	W3	Plaster	Yellow	Flaking	1	0.3	Negative
1	3	334	Classroom 34	yes	Radiator (W3)	Metal	Orange	Flaking	1	0.01	Negative
1	3	334	Classroom 34	yes	W4	Plaster	Yellow	None	0	N/A	N/A
1	3	334	Classroom 34	yes	Moulding (W4)	Wood	Orange	None	0	N/A	N/A
1	3	334	Classroom 34	yes	Moulding (W4)	Wood	Yellow	None	0	N/A	N/A
1	3	334	Classroom 34	yes	Floor	N/A	N/A	N/A	N/A	N/A	N/A
1	3	334	Classroom 34	yes	Ceiling	N/A	N/A	N/A	N/A	N/A	N/A
1	3	332	Classroom 32	yes	W1	Plaster	White	None	0	N/A	N/A
1	3	332	Classroom 32	yes	W1	Plaster	Tan	Chipping	1	0.2	Negative
1	3	332	Classroom 32	yes	Door (W1)	Wood	Tan	Chipping	2	0.1	Negative
1	3	332	Classroom 32	yes	Chalkboard (W1)	Wood	Tan	Chipping	2	0.02	Negative
1	3	332	Classroom 32	yes	W2	Plaster	White	None	0	N/A	N/A
1	3	332	Classroom 32	yes	W2	Plaster	Tan	Flaking	1	0.2	Negative
1	3	332	Classroom 32	yes	Moulding (W2)	Wood	Tan	Chipping	1	0.01	Negative
1	3	332	Classroom 32	yes	W3	Plaster	White	None	0	N/A	N/A
1	3	332	Classroom 32	yes	W3	Plaster	Tan	Flaking	5	0.5	Negative
1	3	332	Classroom 32	yes	W3	Plaster	Green	Flaking	1	0.4	Negative
1	3	332	Classroom 32	yes	Radiator (W3)	Metal	Green	None	0	N/A	N/A
1	3	332	Classroom 32	yes	W4	Plaster	White	None	0	N/A	N/A
1	3	332	Classroom 32	yes	W4	Plaster	Tan	Chipping	1	0.33	Negative

			School District of Philadelphia								
			Name of Inspector: Michael Barth, Melissa Billingsley		Lead Safe Certification Assessment Report						
			Inspection Company: Criterion Labs., Inc.		Taylor Elementary School and Annex						
E l e m e n t	F l o o r	Space #	On-Site Room Name	Student/ Teacher Occupied (yes/no)	Component	Substrate Material	Color	Description of Damage	Damage Quantity (sf)	XRF Reading (mg/cm2)	XRF (positive/ negative)
1	3	332	Classroom 32	yes	Moulding (W4)	Wood	Tan	Chipping	1	0.1	Negative
1	3	332	Classroom 32	yes	Floor	N/A	N/A	N/A	N/A	N/A	N/A
1	3	332	Classroom 32	yes	Ceiling	N/A	N/A	N/A	N/A	N/A	N/A
1	3	332A	Classroom 32 Closet	yes	Door Frame (W1)	Wood	Tan	Chipping	2	0.01	Negative
1	3	332A	Classroom 32 Closet	yes	W1	Plaster	White	None	0	N/A	N/A
1	3	332A	Classroom 32 Closet	yes	W2	Plaster	White	None	0	N/A	N/A
1	3	332A	Classroom 32 Closet	yes	W3	Plaster	White	None	0	N/A	N/A
1	3	332A	Classroom 32 Closet	yes	W4	Plaster	White	Cracking	1	0.32	Negative
1	3	332A	Classroom 32 Closet	yes	Floor	N/A	N/A	N/A	N/A	N/A	N/A
1	3	332A	Classroom 32 Closet	yes	Ceiling	Plaster	White	N/A	0	N/A	N/A
1	3	331	Classroom 31	yes	W1	Plaster	White	None	0	N/A	N/A
1	3	331	Classroom 31	yes	W1	Plaster	Blue	Flaking	1	1.3	Positive
1	3	331	Classroom 31	yes	Moulding (W1)	Wood	Blue	Cracking	1	0.01	Negative
1	3	331	Classroom 31	yes	Moulding (W1)	Wood	Green	None	0	N/A	N/A
1	3	331	Classroom 31	yes	Door (W1)	Wood	White	Friction	1	0.01	Negative
1	3	331	Classroom 31	yes	W2	Plaster	White	None	0	N/A	N/A
1	3	331	Classroom 31	yes	W2	Plaster	Blue	Chipping	1	1	Positive
1	3	331	Classroom 31	yes	Radiator (W2)	Metal	Blue	Cracking	1	0.01	Negative
1	3	331	Classroom 31	yes	W3	Plaster	White	Flaking	2	0.9	Positive
1	3	331	Classroom 31	yes	W3	Plaster	Blue	Flaking	1	2.2	Positive
1	3	331	Classroom 31	yes	Radiator (W3)	Metal	Blue	Cracking	2	0	Negative
1	3	331	Classroom 31	yes	W4	Plaster	Blue	Chipping	1	3.1	Positive
1	3	331	Classroom 31	yes	W4	Plaster	White	None	0	N/A	N/A
1	3	331	Classroom 31	yes	Moulding (W4)	Wood	Blue	None	0	N/A	N/A
1	3	331	Classroom 31	yes	Moulding (W4)	Wood	Green	None	0	N/A	N/A
1	3	331	Classroom 31	yes	Floor	N/A	N/A	N/A	N/A	N/A	N/A
1	3	331	Classroom 31	yes	Ceiling	N/A	N/A	N/A	N/A	N/A	N/A

			School District of Philadelphia								
			Name of Inspector: Michael Barth, Melissa Billingsley		Lead Safe Certification Assessment Report						
			Inspection Company: Criterion Labs., Inc.		Taylor Elementary School and Annex						
E l e m e n t	F l o o r	Space #	On-Site Room Name	Student/ Teacher Occupied (yes/no)	Component	Substrate Material	Color	Description of Damage	Damage Quantity (sf)	XRF Reading (mg/cm2)	XRF (positive/ negative)
1	3	336	Boy's Restroom next to Classroom 31	yes	W1	Plaster	Tan	None	0	N/A	N/A
1	3	336	Boy's Restroom next to Classroom 31	yes	W1	Plaster	Blue	None	0	N/A	N/A
1	3	336	Boy's Restroom next to Classroom 31	yes	Door Frame (W1)	Metal	Brown	None	0	N/A	N/A
1	3	336	Boy's Restroom next to Classroom 31	yes	W2	Plaster	Tan	Cracking	1	1.1	Positive
1	3	336	Boy's Restroom next to Classroom 31	yes	W2	Plaster	Blue	None	0	N/A	N/A
1	3	336	Boy's Restroom next to Classroom 31	yes	W3	Plaster	Blue	None	0	N/A	N/A
1	3	336	Boy's Restroom next to Classroom 31	yes	W3	Plaster	White	None	0	N/A	N/A
1	3	336	Boy's Restroom next to Classroom 31	yes	Window (W3)	Metal	Tan	Alligatoring	5	5.4	Positive
1	3	336	Boy's Restroom next to Classroom 31	yes	W4	Plaster	White	None	0	N/A	N/A
1	3	336	Boy's Restroom next to Classroom 31	yes	W4	Plaster	Blue	None	0	N/A	N/A
1	3	336	Boy's Restroom next to Classroom 31	yes	Sink (W4)	Metal	White	Flaking	5	0.01	Negative
1	3	336	Boy's Restroom next to Classroom 31	yes	Floor	N/A	N/A	N/A	N/A	N/A	N/A
1	3	336	Boy's Restroom next to Classroom 31	yes	Ceiling	Plaster	Tan	Cracking	1	1.3	Positive
1	3	H31	Hallway next to Classroom 32	yes	W1	Plaster	White	None	0	N/A	N/A
1	3	H31	Hallway next to Classroom 32	yes	W2	Plaster	White	None	0	N/A	N/A

			School District of Philadelphia								
			Name of Inspector: Michael Barth, Melissa Billingsley		Lead Safe Certification Assessment Report						
			Inspection Company: Criterion Labs., Inc.		Taylor Elementary School and Annex						
E l e m e n t	F l o o r	Space #	On-Site Room Name	Student/ Teacher Occupied (yes/no)	Component	Substrate Material	Color	Description of Damage	Damage Quantity (sf)	XRF Reading (mg/cm2)	XRF (positive/ negative)
1	3	H31	Hallway next to Classroom 32	yes	Radiator (W2)	Metal	Tan	Chipping	5	0.01	Negative
1	3	H31	Hallway next to Classroom 32	yes	W3	Plaster	White	Moisture Damage/Chipping	1	0.23	Negative
1	3	H31	Hallway next to Classroom 32	yes	Moulding (W3)	Wood	Tan	None	0	N/A	N/A
1	3	H31	Hallway next to Classroom 32	yes	W4	Plaster	White	Cracking	2	0.5	Negative
1	3	H31	Hallway next to Classroom 32	yes	Moulding (W4)	Wood	White	Chipping	1	0.1	Negative
1	3	H31	Hallway next to Classroom 32	yes	Moulding (W4)	Wood	Tan	Chipping	1	0.01	Negative
1	3	H31	Hallway next to Classroom 32	yes	Floor	N/A	N/A	N/A	N/A	N/A	N/A
1	3	H31	Hallway next to Classroom 32	yes	Ceiling	Plaster	White	Cracking	4	0.33	Negative
1	3	H32	Hallway next to Classroom 33	yes	W1	Plaster	White	None	0	N/A	N/A
1	3	H32	Hallway next to Classroom 33	yes	Moulding (W1)	Wood	White	Chipping	1	0.1	Negative
1	3	H32	Hallway next to Classroom 33	yes	W2	Plaster	White	None	0	N/A	N/A
1	3	H32	Hallway next to Classroom 33	yes	Moulding (W2)	Wood	White	Chipping	1	0.01	Negative
1	3	H32	Hallway next to Classroom 33	yes	W3	Plaster	White	None	0	N/A	N/A
1	3	H32	Hallway next to Classroom 33	yes	Moulding (W3)	Wood	White	Chipping	1	0.2	Negative
1	3	H32	Hallway next to Classroom 33	yes	W4	Plaster	White	None	0	N/A	N/A

			School District of Philadelphia								
			Name of Inspector: Michael Barth, Melissa Billingsley		Lead Safe Certification Assessment Report						
			Inspection Company: Criterion Labs., Inc.		Taylor Elementary School and Annex						
E l e m e n t	F l o o r	Space #	On-Site Room Name	Student/ Teacher Occupied (yes/no)	Component	Substrate Material	Color	Description of Damage	Damage Quantity (sf)	XRF Reading (mg/cm2)	XRF (positive/ negative)
1	3	H32	Hallway next to Classroom 33	yes	Moulding (W4)	Wood	White	Chipping	1	0.1	Negative
1	3	H32	Hallway next to Classroom 33	yes	Floor	N/A	N/A	N/A	N/A	N/A	N/A
1	3	H32	Hallway next to Classroom 33	yes	Ceiling	Plaster	White	None	0	N/A	N/A
1	3	335	Storage Room next to Classroom 31	no	W1	Plaster	White	None	0	N/A	N/A
1	3	335	Storage Room next to Classroom 31	no	W1	Plaster	Tan	Chipping	1	0.3	Negative
1	3	335	Storage Room next to Classroom 31	no	Door Frame (W1)	Wood	Tan	None	0	N/A	N/A
1	3	335	Storage Room next to Classroom 31	no	W2	Plaster	White	None	0	N/A	N/A
1	3	335	Storage Room next to Classroom 31	no	W2	Plaster	Tan	Chipping	1	0.1	Negative
1	3	335	Storage Room next to Classroom 31	no	W3	Plaster	White	Flaking	3	0.1	Negative
1	3	335	Storage Room next to Classroom 31	no	W3	Plaster	Tan	Chipping	1	0.5	Negative
1	3	335	Storage Room next to Classroom 31	no	W4	Plaster	White	None	0	N/A	N/A
1	3	335	Storage Room next to Classroom 31	no	W4	Plaster	Tan	Chipping	1	0.3	Negative
1	3	335	Storage Room next to Classroom 31	no	Floor	N/A	N/A	N/A	N/A	N/A	N/A
1	3	335	Storage Room next to Classroom 31	no	Ceiling	Plaster	White	None	0	N/A	N/A
1	2	222	Classroom 22	yes	W1	Plaster	Yellow	Flaking	3	1.5	Positive
1	2	222	Classroom 22	yes	Door Frame (W1)	Wood	Tan	Chipping	3	0.02	Negative

			School District of Philadelphia								
			Name of Inspector: Michael Barth, Melissa Billingsley		Lead Safe Certification Assessment Report						
			Inspection Company: Criterion Labs., Inc.		Taylor Elementary School and Annex						
E l e m e n t	F l o o r	Space #	On-Site Room Name	Student/ Teacher Occupied (yes/no)	Component	Substrate Material	Color	Description of Damage	Damage Quantity (sf)	XRF Reading (mg/cm2)	XRF (positive/ negative)
1	2	222	Classroom 22	yes	Mouding (W1)	Wood	Blue	Chipping	1	0.1	Negative
1	2	222	Classroom 22	yes	Moulding (W1)	Wood	Black	Chipping	3	0.1	Negative
1	2	222	Classroom 22	yes	W2	Plaster	Tan	Flaking	1	3.3	Positive
1	2	222	Classroom 22	yes	W2	Plaster	Yellow	Cracking	1	3.1	Positive
1	2	222	Classroom 22	yes	W2	Plaster	White	Flaking	1	1	Positive
1	2	222	Classroom 22	yes	W2	Plaster	Blue	Cracking	1	1.3	Positive
1	2	222	Classroom 22	yes	Moulding (W2)	Wood	Pink	Chipping	1	0.1	Negative
1	2	222	Classroom 22	yes	Cove Base (W2)	Concrete	Black	None	0	N/A	N/A
1	2	222	Classroom 22	yes	W3	Plaster	Yellow	Flaking	5	1.4	Positive
1	2	222	Classroom 22	yes	Radiator (W3)	Metal	Blue	Chipping	1	0.1	Negative
1	2	222	Classroom 22	yes	Cove Base (W3)	Concrete	Black	Friction	1	0.01	Negative
1	2	222	Classroom 22	yes	W4	Plaster	Yellow	Flaking	2	0.5	Negative
1	2	222	Classroom 22	yes	Moulding (W4)	Wood	Black	Cracking	5	0	Negative
1	2	222	Classroom 22	yes	Floor	N/A	N/A	N/A	N/A	N/A	N/A
1	2	222	Classroom 22	yes	Ceiling	N/A	N/A	N/A	N/A	N/A	N/A
1	2	223	Classroom 24	yes	W1	Plaster	Yellow	Chipping	2	0.4	Negative
1	2	223	Classroom 24	yes	Moulding (W1)	Wood	Green	Cracking	1	0.1	Negative
1	2	223	Classroom 24	yes	Cove Base (W1)	Concrete	Black	None	0	N/A	N/A
1	2	223	Classroom 24	yes	W2	Plaster	Yellow	Chipping	1	0.33	Negative
1	2	223	Classroom 24	yes	Moulding (W2)	Wood	Green	None	0	N/A	N/A
1	2	223	Classroom 24	yes	Cove Base (W2)	Concrete	Black	None	0	N/A	N/A
1	2	223	Classroom 24	yes	W3	Plaster	Yellow	Moisture Damage	10	0.5	Negative
1	2	223	Classroom 24	yes	Radiator (W3)	Metal	Green	Friction	1	0.1	Negative
1	2	223	Classroom 24	yes	Cove Base (W3)	Concrete	Black	None	0	N/A	N/A
1	2	223	Classroom 24	yes	W4	Plaster	Yellow	None	0	N/A	N/A
1	2	223	Classroom 24	yes	Moulding (W4)	Wood	Green	Chipping	1	0.1	Negative
1	2	223	Classroom 24	yes	Floor	N/A	N/A	N/A	N/A	N/A	N/A

			School District of Philadelphia								
			Name of Inspector: Michael Barth, Melissa Billingsley		Lead Safe Certification Assessment Report						
			Inspection Company: Criterion Labs., Inc.		Taylor Elementary School and Annex						
E l e m e n t	F l o o r	Space #	On-Site Room Name	Student/ Teacher Occupied (yes/no)	Component	Substrate Material	Color	Description of Damage	Damage Quantity (sf)	XRF Reading (mg/cm2)	XRF (positive/ negative)
1	2	223	Classroom 24	yes	Ceiling	N/A	N/A	N/A	N/A	N/A	N/A
1	2	222	Classroom 23	yes	W1	Plaster	White	Cracking	5	0.22	Negative
1	2	222	Classroom 23	yes	Door Frame (W1)	Wood	Tan	Chipping	3	0.1	Negative
1	2	222	Classroom 23	yes	W2	Plaster	White	None	0	N/A	N/A
1	2	222	Classroom 23	yes	W2	Plaster	Tan	None	0	N/A	N/A
1	2	222	Classroom 23	yes	Radiator (W2)	Metal	Orange	None	0	N/A	N/A
1	2	222	Classroom 23	yes	W3	Plaster	White	None	0	N/A	N/A
1	2	222	Classroom 23	yes	W3	Plaster	Tan	Moisture Damage	10	0.34	Negative
1	2	222	Classroom 23	yes	Radiator (W3)	Metal	Orange	None	0	N/A	N/A
1	2	222	Classroom 23	yes	W4	Plaster	White	None	0	N/A	N/A
1	2	222	Classroom 23	yes	W4	Plaster	Tan	None	0	N/A	N/A
1	2	222	Classroom 23	yes	Moulding (W4)	Wood	Tan	Chipping	3	0.1	Negative
1	2	222	Classroom 23	yes	Floor	N/A	N/A	N/A	N/A	N/A	N/A
1	2	222	Classroom 23	yes	Ceiling	N/A	N/A	N/A	N/A	N/A	N/A
1	2	222A	Closet next to Classroom 21	yes	W1	Plaster	Tan	Cracking	2	0.3	Negative
1	2	222A	Closet next to Classroom 21	yes	Door Frame (W1)	Wood	Tan	Cracking	5	0.1	Negative
1	2	222A	Closet next to Classroom 21	yes	W2	Plaster	Tan	Cracking	1	0.5	Negative
1	2	222A	Closet next to Classroom 21	yes	Shelving (W2)	Wood	Tan	Chipping	1	0	Negative
1	2	222A	Closet next to Classroom 21	yes	W3	Plaster	Tan	Chipping	1	0.23	Negative
1	2	222A	Closet next to Classroom 21	yes	W4	Plaster	Tan	Cracking	2	0.4	Negative
1	2	222A	Closet next to Classroom 21	yes	Shelving (W4)	Wood	Tan	Chipping	1	0.02	Negative

			School District of Philadelphia								
			Name of Inspector: Michael Barth, Melissa Billingsley		Lead Safe Certification Assessment Report						
			Inspection Company: Criterion Labs., Inc.		Taylor Elementary School and Annex						
E l e m e n t	F l o o r	Space #	On-Site Room Name	Student/ Teacher Occupied (yes/no)	Component	Substrate Material	Color	Description of Damage	Damage Quantity (sf)	XRF Reading (mg/cm2)	XRF (positive/ negative)
1	2	222A	Closet next to Classroom 21	yes	Floor	N/A	N/A	N/A	N/A	N/A	N/A
1	2	222A	Closet next to Classroom 21	yes	Ceiling	Plaster	White	Chipping	1	0.32	Negative
1	2	231	Classroom 21	yes	W1	Plaster	Blue	Chipping	1	2.2	Positive
1	2	231	Classroom 21	yes	Door Frame (W1)	Wood	Orange	Cracking	1	0.1	Negative
1	2	231	Classroom 21	yes	Moulding (W1)	Wood	Blue	Chipping	1	0.31	Negative
1	2	231	Classroom 21	yes	Moulding (W1)	Wood	White	Friction	1	0.22	Negative
1	2	231	Classroom 21	yes	Moulding (W1)	Wood	Black	Chipping	3	0.4	Negative
1	2	231	Classroom 21	yes	W2	Plaster	Blue	Chipping	1	1.3	Positive
1	2	231	Classroom 21	yes	Radiator (W2)	Metal	Blue	Chipping	1	0.1	Negative
1	2	231	Classroom 21	yes	Moulding (W2)	Wood	Black	None	0	N/A	N/A
1	2	231	Classroom 21	yes	W3	Plaster	Blue	Flaking	2	0.8	Positive
1	2	231	Classroom 21	yes	Radiator (W3)	Metal	Blue	Chipping	1	0.02	Negative
1	2	231	Classroom 21	yes	Window Stool (W3)	Wood	Black	None	0	N/A	N/A
1	2	231	Classroom 21	yes	W4	Plaster	Blue	None	0	N/A	N/A
1	2	231	Classroom 21	yes	Moulding (W4)	Wood	Orange	Cracking	1	0.1	Negative
1	2	231	Classroom 21	yes	Moulding (W4)	Wood	Black	Chipping	1	0.1	Negative
1	2	231	Classroom 21	yes	Floor	N/A	N/A	N/A	N/A	N/A	N/A
1	2	231	Classroom 21	yes	Ceiling	N/A	N/A	N/A	N/A	N/A	N/A
1	2	235	Office next to Classroom 21	yes	W1	Sheetrock	White	None	0	N/A	N/A
1	2	235	Office next to Classroom 21	yes	Door Frame (W1)	Wood	Tan	Chipping	1	0.1	Negative
1	2	235	Office next to Classroom 21	yes	Cove Base (W1)	Wood	Black	None	0	N/A	N/A
1	2	235	Office next to Classroom 21	yes	W2	Plaster	White	Moisture Damage	1	0.31	Negative

			School District of Philadelphia								
			Name of Inspector: Michael Barth, Melissa Billingsley		Lead Safe Certification Assessment Report						
			Inspection Company: Criterion Labs., Inc.		Taylor Elementary School and Annex						
E l e m e n t	F l o o r	Space #	On-Site Room Name	Student/ Teacher Occupied (yes/no)	Component	Substrate Material	Color	Description of Damage	Damage Quantity (sf)	XRF Reading (mg/cm2)	XRF (positive/ negative)
1	2	235	Office next to Classroom 21	yes	Cove Base (W2)	Wood	Black	None	0	N/A	N/A
1	2	235	Office next to Classroom 21	yes	W3	Plaster	White	None	0	N/A	N/A
1	2	235	Office next to Classroom 21	yes	Door Frame (W3)	Wood	Tan	None	0	N/A	N/A
1	2	235	Office next to Classroom 21	yes	Cove Base (W3)	Wood	Black	None	0	N/A	N/A
1	2	235	Office next to Classroom 21	yes	W4	Plaster	White	None	0	N/A	N/A
1	2	235	Office next to Classroom 21	yes	Cove Base (W4)	Wood	Black	None	0	N/A	N/A
1	2	235	Office next to Classroom 21	yes	Floor	N/A	N/A	N/A	N/A	N/A	N/A
1	2	235	Office next to Classroom 21	yes	Ceiling	N/A	N/A	N/A	N/A	N/A	N/A
1	2	235A	Office next to Classroom 21 Restroom	yes	W1	Plaster	Red	None	0	N/A	N/A
1	2	235A	Office next to Classroom 21 Restroom	yes	Door Frame (W1)	Wood	White	None	0	N/A	N/A
1	2	235A	Office next to Classroom 21 Restroom	yes	W2	Plaster	Red	Spalling	1	0.4	Negative
1	2	235A	Office next to Classroom 21 Restroom	yes	W3	Plaster	Red	None	0	N/A	N/A

			School District of Philadelphia								
			Name of Inspector: Michael Barth, Melissa Billingsley		Lead Safe Certification Assessment Report						
			Inspection Company: Criterion Labs., Inc.		Taylor Elementary School and Annex						
E l e m e n t	F l o o r	Space #	On-Site Room Name	Student/ Teacher Occupied (yes/no)	Component	Substrate Material	Color	Description of Damage	Damage Quantity (sf)	XRF Reading (mg/cm2)	XRF (positive/ negative)
1	2	235A	Office next to Classroom 21 Restroom	yes	W4	Plaster	Red	Cracking	1	0.41	Negative
1	2	235A	Office next to Classroom 21 Restroom	yes	W4	Plaster	White	Cracking	1	0.6	Negative
1	2	235A	Office next to Classroom 21 Restroom	yes	Floor	N/A	N/A	N/A	N/A	N/A	N/A
1	2	235A	Office next to Classroom 21 Restroom	yes	Ceiling	N/A	N/A	N/A	N/A	N/A	N/A
1	2	236	Girl's Restroom	yes	W1	Plaster	Tan	None	0	N/A	N/A
1	2	236	Girl's Restroom	yes	W2	Plaster	Blue	None	0	N/A	N/A
1	2	236	Girl's Restroom	yes	W2	Plaster	Tan	None	0	N/A	N/A
1	2	236	Girl's Restroom	yes	W3	Plaster	Blue	None	0	N/A	N/A
1	2	236	Girl's Restroom	yes	W3	Plaster	Tan	None	0	N/A	N/A
1	2	236	Girl's Restroom	yes	W4	Plaster	Grey	None	0	N/A	N/A
1	2	236	Girl's Restroom	yes	W4	Plaster	Blue	None	0	N/A	N/A
1	2	236	Girl's Restroom	yes	W4	Plaster	Tan	None	0	N/A	N/A
1	2	236	Girl's Restroom	yes	Floor	Concrete	Grey	None	0	N/A	N/A
1	2	236	Girl's Restroom	yes	Ceiling	N/A	N/A	N/A	N/A	N/A	N/A
1	2	H21	Hallway next to Classroom 22	yes	W1	Plaster	Tan	Chipping	2	0.4	Negative
1	2	H21	Hallway next to Classroom 22	yes	W1	Plaster	Pink	None	0	N/A	N/A
1	2	H21	Hallway next to Classroom 22	yes	Radiator (W1)	Metal	White	None	0	N/A	N/A

			School District of Philadelphia								
			Name of Inspector: Michael Barth, Melissa Billingsley		Lead Safe Certification Assessment Report						
			Inspection Company: Criterion Labs., Inc.		Taylor Elementary School and Annex						
E l e m e n t	F l o o r	Space #	On-Site Room Name	Student/ Teacher Occupied (yes/no)	Component	Substrate Material	Color	Description of Damage	Damage Quantity (sf)	XRF Reading (mg/cm2)	XRF (positive/ negative)
1	2	H21	Hallway next to Classroom 22	yes	Cove Base (W1)	Wood	Black	None	0	N/A	N/A
1	2	H21	Hallway next to Classroom 22	yes	W2	Plaster	Tan	Cracking/Chipping	1	0.33	Negative
1	2	H21	Hallway next to Classroom 22	yes	Door Frame (W2)	Wood	Tan	Chipping	2	0.02	Negative
1	2	H21	Hallway next to Classroom 22	yes	Cove Base (W2)	Wood	Black	Chipping	1	0.03	Negative
1	2	H21	Hallway next to Classroom 22	yes	W3	Plaster	Tan	Partially Inaccessible	0	0.23	Negative
1	2	H21	Hallway next to Classroom 22	yes	Door (W3)	Wood	Blue	Friction	1	0.1	Negative
1	2	H21	Hallway next to Classroom 22	yes	Moulding (W3)	Wood	Tan	Chipping	5	0.1	Negative
1	2	H21	Hallway next to Classroom 22	yes	Cove Base (W3)	Wood	Black	Chipping	1	0.1	Negative
1	2	H21	Hallway next to Classroom 22	yes	W4	Plaster	Tan	Chipping	1	0.24	Negative
1	2	H21	Hallway next to Classroom 22	yes	Cove Base (W4)	Wood	Black	Chipping	1	0.03	Negative
1	2	H21	Hallway next to Classroom 22	yes	Door (W4)	Wood	Green	None	0	N/A	N/A
1	2	H21	Hallway next to Classroom 22	yes	Door (W4)	Wood	Yellow	None	0	N/A	N/A
1	2	H21	Hallway next to Classroom 22	yes	Floor	N/A	N/A	N/A	N/A	N/A	N/A
1	2	H21	Hallway next to Classroom 22	yes	Ceiling	Plaster	White	None	0	N/A	N/A
1	2	H22	Hallway next to Classroom 23	yes	W1	Plaster	Tan	None	0	N/A	N/A

			School District of Philadelphia								
			Name of Inspector: Michael Barth, Melissa Billingsley		Lead Safe Certification Assessment Report						
			Inspection Company: Criterion Labs., Inc.		Taylor Elementary School and Annex						
E l e m e n t	F l o o r	Space #	On-Site Room Name	Student/ Teacher Occupied (yes/no)	Component	Substrate Material	Color	Description of Damage	Damage Quantity (sf)	XRF Reading (mg/cm2)	XRF (positive/ negative)
1	2	H22	Hallway next to Classroom 23	yes	Cove Base (W1)	Wood	Black	None	0	N/A	N/A
1	2	H22	Hallway next to Classroom 23	yes	Door (W1)	Wood	Green	None	0	N/A	N/A
1	2	H22	Hallway next to Classroom 23	yes	Door (W1)	Wood	Yellow	None	0	N/A	N/A
1	2	H22	Hallway next to Classroom 23	yes	W2	Plaster	Tan	None	0	N/A	N/A
1	2	H22	Hallway next to Classroom 23	yes	Moulding (W2)	Wood	Tan	Flaking	2	0.1	Negative
1	2	H22	Hallway next to Classroom 23	yes	Cove Base (W2)	Wood	Black	None	0	N/A	N/A
1	2	H22	Hallway next to Classroom 23	yes	W3	Plaster	Tan	Flaking	1	0.2	Negative
1	2	H22	Hallway next to Classroom 23	yes	Cove Base (W3)	Wood	Black	None	0	N/A	N/A
1	2	H22	Hallway next to Classroom 23	yes	W4	Plaster	Tan	None	0	N/A	N/A
1	2	H22	Hallway next to Classroom 23	yes	Moulding (W4)	Wood	Tan	Chipping	1	0.01	Negative
1	2	H22	Hallway next to Classroom 23	yes	Floor	N/A	N/A	N/A	N/A	N/A	N/A
1	2	H22	Hallway next to Classroom 23	yes	Ceiling	Plaster	Tan	None	0	N/A	N/A
1	2	H22	Hallway next to Classroom 23	yes	Ceiling	Plaster	White	None	0	N/A	N/A
1	1	001A	Small Kitchen in Rear of Auditorium	no	W1	Plaster	Green	Chipping	1	0.3	Negative
1	1	001A	Small Kitchen in Rear of Auditorium	no	Door FRame (W2)	Metal	Black	Friction	1	0.01	Negative

			School District of Philadelphia								
			Name of Inspector: Michael Barth, Melissa Billingsley		Lead Safe Certification Assessment Report						
			Inspection Company: Criterion Labs., Inc.		Taylor Elementary School and Annex						
E l e m e n t	F l o o r	Space #	On-Site Room Name	Student/ Teacher Occupied (yes/no)	Component	Substrate Material	Color	Description of Damage	Damage Quantity (sf)	XRF Reading (mg/cm2)	XRF (positive/ negative)
1	1	001A	Small Kitchen in Rear of Auditorium	no	W2	Plaster	Green	Chipping	2	0.21	Negative
1	1	001A	Small Kitchen in Rear of Auditorium	no	W2	Plaster	Orange	None	0	N/A	N/A
1	1	001A	Small Kitchen in Rear of Auditorium	no	Cabinets (W2)	Wood	Green	Friction	2	0.01	Negative
1	1	001A	Small Kitchen in Rear of Auditorium	no	W3	Plaster	Orange	None	0	N/A	N/A
1	1	001A	Small Kitchen in Rear of Auditorium	no	Cabinets (W3)	Wood	Green	None	0	N/A	N/A
1	1	001A	Small Kitchen in Rear of Auditorium	no	Cabinets (W3)	Wood	Tan	Chipping	1	0.01	Negative
1	1	001A	Small Kitchen in Rear of Auditorium	no	W4	Plaster	Orange	None	0	N/A	N/A
1	1	001A	Small Kitchen in Rear of Auditorium	no	W4	Plaster	Green	None	0	N/A	N/A
1	1	001A	Small Kitchen in Rear of Auditorium	no	Cabinets (W4)	Wood	Green	Chipping	1	0.01	Negative
1	1	001A	Small Kitchen in Rear of Auditorium	no	Floor	N/A	N/A	N/A	N/A	N/A	N/A
1	1	001A	Small Kitchen in Rear of Auditorium	no	Ceiling	Plaster	Green	None	0	N/A	N/A
1	1	001C	Room next to Kitchen in Rear of Auditorium	no	W1	Plaster	White	Chipping	1	0.2	Negative
1	1	001C	Room next to Kitchen in Rear of Auditorium	no	Radiator (W2)	Metal	White	Chipping	1	0.01	Negative
1	1	001C	Room next to Kitchen in Rear of Auditorium	no	W2	Plaster	White	Cracking	1	0.32	Negative
1	1	001C	Room next to Kitchen in Rear of Auditorium	no	W3	Plaster	White	Cracking	1	0.1	Negative

			School District of Philadelphia								
			Name of Inspector: Michael Barth, Melissa Billingsley		Lead Safe Certification Assessment Report						
			Inspection Company: Criterion Labs., Inc.		Taylor Elementary School and Annex						
E l e m e n t	F l o o r	Space #	On-Site Room Name	Student/ Teacher Occupied (yes/no)	Component	Substrate Material	Color	Description of Damage	Damage Quantity (sf)	XRF Reading (mg/cm2)	XRF (positive/ negative)
1	1	001C	Room next to Kitchen in Rear of Auditorium	no	W4	Plaster	White	Flaking	1	0.2	Negative
1	1	001C	Room next to Kitchen in Rear of Auditorium	no	Floor	N/A	N/A	N/A	N/A	N/A	N/A
1	1	001C	Room next to Kitchen in Rear of Auditorium	no	Ceiling	Brick	White	Flaking	5	0.01	Negative
1	1	001C	Storage Room next to Kitchen in Rear of Auditorium	no	W1	Brick	N/A	None	0	N/A	N/A
1	1	001C	Storage Room next to Kitchen in Rear of Auditorium	no	W2	Brick	N/A	None	0	N/A	N/A
1	1	001C	Storage Room next to Kitchen in Rear of Auditorium	no	W3	Brick	N/A	None	0	N/A	N/A
1	1	001C	Storage Room next to Kitchen in Rear of Auditorium	no	W4	Brick	N/A	None	0	N/A	N/A
1	1	001C	Storage Room next to Kitchen in Rear of Auditorium	no	Floor	Concrete	N/A	None	0	N/A	N/A
1	1	001C	Storage Room next to Kitchen in Rear of Auditorium	no	Ceiling	Plaster	N/A	None	0	N/A	N/A
1	1	1	Auditorium	yes	W1	Plaster	Yellow	Chipping	1	0.2	Negative
1	1	1	Auditorium	yes	W1	Plaster	Tan	Moisture Damage	1	0.36	Negative
1	1	1	Auditorium	yes	W2	Plaster	Red	Flaking	5	0.4	Negative
1	1	1	Auditorium	yes	Radiator (W2)	Metal	Red	Chipping	1	0.1	Negative
1	1	1	Auditorium	yes	W2	Plaster	Yellow	Chipping	1	0.2	Negative
1	1	1	Auditorium	yes	W2	Plaster	Orange	Chipping	1	0.33	Negative

			School District of Philadelphia								
			Name of Inspector: Michael Barth, Melissa Billingsley		Lead Safe Certification Assessment Report						
			Inspection Company: Criterion Labs., Inc.		Taylor Elementary School and Annex						
E l e m e n t	F l o o r	Space #	On-Site Room Name	Student/ Teacher Occupied (yes/no)	Component	Substrate Material	Color	Description of Damage	Damage Quantity (sf)	XRF Reading (mg/cm2)	XRF (positive/ negative)
1	1	1	Auditorium	yes	Radiator (W2)	Metal	Orange	Chipping	1	0.01	Negative
1	1	1	Auditorium	yes	W2	Plaster	Blue	Chipping	1	0.43	Negative
1	1	1	Auditorium	yes	W2	Plaster	Light Blue	Moisture Damage	2	0.4	Negative
1	1	1	Auditorium	yes	W2	Plaster	Tan	None	0	N/A	N/A
1	1	1	Auditorium	yes	W2	Plaster	Teal	None	0	N/A	N/A
1	1	1	Auditorium	yes	W3	Plaster	Green	None	0	N/A	N/A
1	1	1	Auditorium	yes	W3	Plaster	White	None	0	N/A	N/A
1	1	1	Auditorium	yes	W3	Plaster	Tan	None	0	N/A	N/A
1	1	1	Auditorium	yes	W3	Plaster	Blue	Chipping	1	0.4	Negative
1	1	1	Auditorium	yes	W4	Plaster	Orange	Chipping	1	0.33	Negative
1	1	1	Auditorium	yes	W4	Plaster	Blue	Chipping	1	0.2	Negative
1	1	1	Auditorium	yes	W4	Plaster	Yellow	Chipping	1	0.3	Negative
1	1	1	Auditorium	yes	W4	Plaster	Light Blue	Chipping	1	0.42	Negative
1	1	1	Auditorium	yes	W4	Plaster	Teal	Chipping	1	0.04	Negative
1	1	1	Auditorium	yes	Window Frame (W4)	Wood	Red	Chipping	1	0.01	Negative
1	1	1	Auditorium	yes	Floor	N/A	N/A	N/A	N/A	N/A	N/A
1	1	1	Auditorium	yes	Ceiling	N/A	N/A	N/A	N/A	N/A	N/A
1	1	3A	Auditorium side Foyer	yes	W1	Plaster	White	Chipping	1	0.31	Negative
1	1	3A	Auditorium side Foyer	yes	W1	Plaster	Orange	Cracking	1	0.22	Negative
1	1	3A	Auditorium side Foyer	yes	Radiator (W1)	Metal	Red	Friction	1	0	Negative
1	1	3A	Auditorium side Foyer	yes	W2	Plaster	White	None	0	N/A	N/A
1	1	3A	Auditorium side Foyer	yes	W2	Plaster	Red	None	0	N/A	N/A
1	1	3A	Auditorium side Foyer	yes	W2	Plaster	Yellow	None	0	N/A	N/A
1	1	3A	Auditorium side Foyer	yes	Door Frame (W2)	Metal	Black	Friction	1	0.01	Negative
1	1	3A	Auditorium side Foyer	yes	Moulding (W3)	Wood	Tan	Chipping	1	0	Negative
1	1	3A	Auditorium side Foyer	yes	W3	Plaster	White	None	0	N/A	N/A
1	1	3A	Auditorium side Foyer	yes	W4	Plaster	Orange	Cracking	1	0.24	Negative

			School District of Philadelphia								
			Name of Inspector: Michael Barth, Melissa Billingsley		Lead Safe Certification Assessment Report						
			Inspection Company: Criterion Labs., Inc.		Taylor Elementary School and Annex						
E l e m e n t	F l o o r	Space #	On-Site Room Name	Student/ Teacher Occupied (yes/no)	Component	Substrate Material	Color	Description of Damage	Damage Quantity (sf)	XRF Reading (mg/cm2)	XRF (positive/ negative)
1	1	3A	Auditorium side Foyer	yes	Door Frame (W4)	Metal	Black	Friction	1	0.01	Negative
1	1	3A	Auditorium side Foyer	yes	Floor	N/A	N/A	N/A	N/A	N/A	N/A
1	1	3A	Auditorium side Foyer	yes	Ceiling	Plaster	White	None	0	N/A	N/A
1	1	3B	Stage Storage Room	yes	W1	Plaster	Tan	N/A	0	N/A	N/A
1	1	3B	Stage Storage Room	yes	W1	Plaster	Yellow	Flaking	2	0.28	Negative
1	1	3B	Stage Storage Room	yes	W2	Plaster	Tan	Flaking	5	0.27	Negative
1	1	3B	Stage Storage Room	yes	Electrical Conduits (W2)	Metal	Tan	Flaking	1	0.06	Negative
1	1	3B	Stage Storage Room	yes	Stairs (W2)	Wood	Tan	Chipping	5	0.1	Negative
1	1	3B	Stage Storage Room	yes	Handrail (W2)	Wood	Blue	Friction	3	0.05	Negative
1	1	3B	Stage Storage Room	yes	Radiator Cover(W3)	Wood	Blue	Chipping	1	0.06	Negative
1	1	3B	Stage Storage Room	yes	Radiator Cover (W3)	Wood	Tan	Chipping	1	0.06	Negative
1	1	3B	Stage Storage Room	yes	W3	Wood	N/A	N/A	N/A	N/A	N/A
1	1	3B	Stage Storage Room	yes	W4	Plaster	Tan	None	0	N/A	N/A
1	1	3B	Stage Storage Room	yes	W4	Plaster	Green	None	0	N/A	N/A
1	1	3B	Stage Storage Room	yes	Floor	N/A	N/A	N/A	N/A	N/A	N/A
1	1	3B	Stage Storage Room	yes	Ceiling	N/A	N/A	N/A	N/A	N/A	N/A
1	1	3	Women's Restroom to Right of Stage	yes	W1	Plaster	White	Flaking	1	0.03	Negative
1	1	3	Women's Restroom to Right of Stage	yes	W1	Plaster	Red	Cracking	1	0.4	Negative
1	1	3	Women's Restroom to Right of Stage		W1	Plaster	Pink	Moisture Damage	5	0	Negative
1	1	3	Women's Restroom to Right of Stage	yes	Door (W1)	Wood	White	Chipping	2	0	Negative
1	1	3	Women's Restroom to Right of Stage	yes	Door Frame (W1)	Wood	Red	Cracking	1	0	Negative
1	1	3	Women's Restroom to Right of Stage	yes	W2	Plaster	White	Flaking	1	0	Negative

			School District of Philadelphia								
			Name of Inspector: Michael Barth, Melissa Billingsley		Lead Safe Certification Assessment Report						
			Inspection Company: Criterion Labs., Inc.		Taylor Elementary School and Annex						
E l e m e n t	F l o o r	Space #	On-Site Room Name	Student/ Teacher Occupied (yes/no)	Component	Substrate Material	Color	Description of Damage	Damage Quantity (sf)	XRF Reading (mg/cm2)	XRF (positive/ negative)
1	1	3	Women's Restroom to Right of Stage	yes	W2	Plaster	Grey	Moisture Damage	3	0	Negative
1	1	3	Women's Restroom to Right of Stage	yes	W3	Plaster	White	Flaking	1	0.02	Negative
1	1	3	Women's Restroom to Right of Stage	yes	W3	Plaster	Grey	Moisture Damage	1	0.01	Negative
1	1	3	Women's Restroom to Right of Stage	yes	W4	Plaster	Pink	None	0	N/A	N/A
1	1	3	Women's Restroom to Right of Stage	yes	Floor	Concrete	Pink	Chipping	1	0.3	Negative
1	1	3	Women's Restroom to Right of Stage	yes	Ceiling	Plaster	White	Chipping	1	0.1	Negative
1	1	4	Men's Restroom to Left of Stage	yes	Door Frame (W1)	Wood	White	Chipping	1	0.02	Negative
1	1	4	Men's Restroom to Left of Stage	yes	W1	Brick	Yellow	None	0	N/A	N/A
1	1	4	Men's Restroom to Left of Stage	yes	W1	Brick	Grey	Moisture Damage	2	0	Negative
1	1	4	Men's Restroom to Left of Stage	yes	W1	Brick	White	None	0	N/A	N/A
1	1	4	Men's Restroom to Left of Stage	yes	Door (W1)	Metal	Grey	Chipping	1	0	Negative
1	1	4	Men's Restroom to Left of Stage	yes	W2	Brick	Yellow	None	0	N/A	N/A
1	1	4	Men's Restroom to Left of Stage	yes	Window (W2)	Metal	Grey	Chipping	1	0	Negative
1	1	4	Men's Restroom to Left of Stage	yes	W3	Plaster	Yellow	Friction	1	0	Negative
1	1	4	Men's Restroom to Left of Stage	yes	W3	Plaster	Grey	Flaking	1	0.01	Negative

			School District of Philadelphia								
			Name of Inspector: Michael Barth, Melissa Billingsley		Lead Safe Certification Assessment Report						
			Inspection Company: Criterion Labs., Inc.		Taylor Elementary School and Annex						
E l e m e n t	F l o o r	Space #	On-Site Room Name	Student/ Teacher Occupied (yes/no)	Component	Substrate Material	Color	Description of Damage	Damage Quantity (sf)	XRF Reading (mg/cm2)	XRF (positive/ negative)
1	1	4	Men's Restroom to Left of Stage	yes	W3	Plaster	White	None	0	N/A	N/A
1	1	4	Men's Restroom to Left of Stage	yes	Pipe (W3)	Metal	Grey	Chipping	1	0.02	Negative
1	1	4	Men's Restroom to Left of Stage	yes	W4	Brick	White	Chipping	1	0	Negative
1	1	4	Men's Restroom to Left of Stage	yes	W4	Brick	Gray	Moisture Damage	1	0.01	Negative
1	1	4	Men's Restroom to Left of Stage	yes	W4	Brick	Green	Moisture Damage	1	0	Negative
1	1	4	Men's Restroom to Left of Stage	yes	Radiator (W4)	Metal	White	Cracking	1	0.3	Negative
1	1	4	Men's Restroom to Left of Stage	yes	Floor	Concrete	Blue	Friction	2	0.01	Negative
1	1	4	Men's Restroom to Left of Stage	yes	Ceiling	Plaster	White	Moisture Damage	1	0	Negative
1	1	H11	Main Entrance Hallway/Stair	yes	W1	Plaster	White	Flaking	1	0.01	Negative
1	1	H11	Main Entrance Hallway/Stair	yes	Door Frame (W1)	Metal	Black	Friction	1	0.3	Negative
1	1	H11	Main Entrance Hallway/Stair	yes	W2	Plaster	White	Cracking	1	0	Negative
1	1	H11	Main Entrance Hallway/Stair	yes	Handrail (W2)	Wood	Tan	Chipping	1	0.01	Negative
1	1	H11	Main Entrance Hallway/Stair	yes	Stairs (W2)	Concrete	Black	Friction	1	0.2	Negative
1	1	H11	Main Entrance Hallway/Stair	yes	W3	Plaster	White	Cracking	1	0.1	Negative
1	1	H11	Main Entrance Hallway/Stair	yes	Handrail (W3)	Wood	Tan	Chipping	1	0.01	Negative

			School District of Philadelphia								
			Name of Inspector: Michael Barth, Melissa Billingsley		Lead Safe Certification Assessment Report						
			Inspection Company: Criterion Labs., Inc.		Taylor Elementary School and Annex						
E l e m e n t	F l o o r	Space #	On-Site Room Name	Student/ Teacher Occupied (yes/no)	Component	Substrate Material	Color	Description of Damage	Damage Quantity (sf)	XRF Reading (mg/cm2)	XRF (positive/ negative)
1	1	H11	Main Entrance Hallway/Stair	yes	W3	Plaster	Yellow	None	0	N/A	N/A
1	1	H11	Main Entrance Hallway/Stair	yes	Sink (W3)	Metal	Red	Chipping	1	0.01	Negative
1	1	H11	Main Entrance Hallway/Stair	yes	Door (W3)	Metal	Black	Chipping	1	0	Negative
1	1	H11	Main Entrance Hallway/Stair	yes	W4	Plaster	White	Flaking	1	0.2	Negative
1	1	H11	Main Entrance Hallway/Stair	yes	W4	Plaster	Yellow	None	0	N/A	N/A
1	1	H11	Main Entrance Hallway/Stair	yes	W4	Plaster	Red	None	0	N/A	N/A
1	1	H11	Main Entrance Hallway/Stair	yes	Radiator (W4)	Metal	Yellow	None	0	N/A	N/A
1	1	H11	Main Entrance Hallway/Stair	yes	Radiator (W4)	Metal	Red	None	0	N/A	N/A
1	1	H11	Main Entrance Hallway/Stair	yes	Floor	N/A	N/A	N/A	N/A	N/A	N/A
1	1	H11	Main Entrance Hallway/Stair	yes	Ceiling	Plaster	White	Flaking	2	0.01	Negative
1	1	S11	Stairs near Auditorium Stage	yes	Door Frame (W1)	Metal	Black	Chipping	1	0	Negative
1	1	S11	Stairs near Auditorium Stage	yes	W1	Plaster	Tan	None	0	N/A	N/A
1	1	S11	Stairs near Auditorium Stage	yes	Stair Post (W1)	Wood	Black	None	0	N/A	N/A
1	1	S11	Stairs near Auditorium Stage	yes	W1	Plaster	Red	None	0	N/A	N/A
1	1	S11	Stairs near Auditorium Stage	yes	W2	Plaster	Tan	Chipping	1	0	Negative

			School District of Philadelphia								
			Name of Inspector: Michael Barth, Melissa Billingsley		Lead Safe Certification Assessment Report						
			Inspection Company: Criterion Labs., Inc.		Taylor Elementary School and Annex						
E l e m e n t	F l o o r	Space #	On-Site Room Name	Student/ Teacher Occupied (yes/no)	Component	Substrate Material	Color	Description of Damage	Damage Quantity (sf)	XRF Reading (mg/cm2)	XRF (positive/ negative)
1	1	S11	Stairs near Auditorium Stage	yes	W2	Plaster	Red	None	0	N/A	N/A
1	1	S11	Stairs near Auditorium Stage	yes	Handrail (W2)	Wood	Brown	Friction	6	0.01	Negative
1	1	S11	Stairs near Auditorium Stage	yes	W3	Plaster	Blue	None	0	N/A	N/A
1	1	S11	Stairs near Auditorium Stage	yes	W3	Plaster	Tan	None	0	N/A	N/A
1	1	S11	Stairs near Auditorium Stage	yes	W4	Plaster	Tan	None	0	N/A	N/A
1	1	S11	Stairs near Auditorium Stage	yes	W4	Plaster	Blue	Flaking	2	0	Negative
1	1	S11	Stairs near Auditorium Stage	yes	W4	Plaster	Red	None	0	N/A	N/A
1	1	S11	Stairs near Auditorium Stage	yes	W4	Plaster	Yellow	None	0	N/A	N/A
1	1	S11	Stairs near Auditorium Stage	yes	Floor	N/A	N/A	N/A	N/A	N/A	N/A
1	1	S11	Stairs near Auditorium Stage	yes	Ceiling	Plaster	White	None	0	N/A	N/A
1	2	S22	Stairs near Girl's Restroom	yes	Door Frame (W1)	Metal	Brown	Friction	2	0	Negative
1	2	S22	Stairs near Girl's Restroom	yes	W1	Plaster	White	None	0	N/A	N/A
1	2	S22	Stairs near Girl's Restroom	yes	W1	Plaster	Orange	Chipping	1	0	Negative
1	2	S22	Stairs near Girl's Restroom	yes	Handrail (W1)	Wood	Brown	Friction	1	0	Negative
1	2	S22	Stairs near Girl's Restroom	yes	W2	Plaster	White	None	0	N/A	N/A

			School District of Philadelphia								
			Name of Inspector: Michael Barth, Melissa Billingsley		Lead Safe Certification Assessment Report						
			Inspection Company: Criterion Labs., Inc.		Taylor Elementary School and Annex						
E l e m e n t	F l o o r	Space #	On-Site Room Name	Student/ Teacher Occupied (yes/no)	Component	Substrate Material	Color	Description of Damage	Damage Quantity (sf)	XRF Reading (mg/cm2)	XRF (positive/ negative)
1	2	S22	Stairs near Girl's Restroom	yes	W2	Plaster	Orange	None	0	N/A	N/A
1	2	S22	Stairs near Girl's Restroom	yes	W3	Plaster	White	None	0	N/A	N/A
1	2	S22	Stairs near Girl's Restroom	yes	W3	Plaster	Orange	Chipping	1	0	Negative
1	2	S22	Stairs near Girl's Restroom	yes	Radiator (W3)	Metal	Orange	None	0	N/A	N/A
1	2	S22	Stairs near Girl's Restroom	yes	W4	Plaster	White	Friction	1	0.03	Negative
1	2	S22	Stairs near Girl's Restroom	yes	W4	Plaster	Orange	None	0	N/A	N/A
1	2	S22	Stairs near Girl's Restroom	yes	Floor	N/A	N/A	N/A	N/A	N/A	N/A
1	2	S22	Stairs near Girl's Restroom	yes	Ceiling	Plaster	White	None	0	N/A	N/A
1	2	S21	Stairs near Classroom 23	yes	W1	Plaster	Tan	None	0	N/A	N/A
1	2	S21	Stairs near Classroom 23	yes	W1	Plaster	White	None	0	N/A	N/A
1	2	S21	Stairs near Classroom 23	yes	W2	Plaster	Tan	None	0	N/A	N/A
1	2	S21	Stairs near Classroom 23	yes	W2	Plaster	White	None	0	N/A	N/A
1	2	S21	Stairs near Classroom 23	yes	Handrail (W2)	Wood	Black	Chipping	5	0	Negative
1	2	S21	Stairs near Classroom 23	yes	W3	Plaster	Tan	None	0	N/A	N/A
1	2	S21	Stairs near Classroom 23	yes	Door Frame (W3)	Metal	Brown	Chipping	1	0.01	Negative

			School District of Philadelphia								
			Name of Inspector: Michael Barth, Melissa Billingsley		Lead Safe Certification Assessment Report						
			Inspection Company: Criterion Labs., Inc.		Taylor Elementary School and Annex						
E l e m e n t	F l o o r	Space #	On-Site Room Name	Student/ Teacher Occupied (yes/no)	Component	Substrate Material	Color	Description of Damage	Damage Quantity (sf)	XRF Reading (mg/cm2)	XRF (positive/ negative)
1	2	S21	Stairs near Classroom 23	yes	W4	Plaster	Tan	None	0	N/A	N/A
1	2	S21	Stairs near Classroom 23	yes	W4	Plaster	White	None	0	N/A	N/A
1	2	S21	Stairs near Classroom 23	yes	Door Frame (W4)	Metal	Brown	Chipping	2	0.2	Negative
1	2	S21	Stairs near Classroom 23	yes	Floor	N/A	N/A	N/A	N/A	N/A	N/A
1	2	S21	Stairs near Classroom 23	yes	Ceiling	Plaster	White	None	0	N/A	N/A
1	3	S32	Stairs near Boy's Restroom	yes	Handrail (W1)	Wood	Black	Friction	1	0	Negative
1	3	S32	Stairs near Boy's Restroom	yes	Moulding (W1)	Wood	Tan	Chipping	1	0	Negative
1	3	S32	Stairs near Boy's Restroom	yes	W2	Plaster	Tan	None	0	N/A	N/A
1	3	S32	Stairs near Boy's Restroom	yes	W2	Plaster	White	None	0	N/A	N/A
1	3	S32	Stairs near Boy's Restroom	yes	W3	Plaster	Tan	Chipping	1	0.3	Negative
1	3	S32	Stairs near Boy's Restroom	yes	W3	Plaster	White	None	0	N/A	N/A
1	3	S32	Stairs near Boy's Restroom	yes	Radiator (W3)	Metal	Orange	None	0	N/A	N/A
1	3	S32	Stairs near Boy's Restroom	yes	W4	Plaster	Tan	Chipping	3	0.4	Negative
1	3	S32	Stairs near Boy's Restroom	yes	Handrail (W4)	Wood	Black	Friction	3	0.2	Negative
1	3	S32	Stairs near Boy's Restroom	yes	Floor	N/A	N/A	N/A	N/A	N/A	N/A

			School District of Philadelphia								
			Name of Inspector: Michael Barth, Melissa Billingsley		Lead Safe Certification Assessment Report						
			Inspection Company: Criterion Labs., Inc.		Taylor Elementary School and Annex						
E l e m e n t	F l o o r	Space #	On-Site Room Name	Student/ Teacher Occupied (yes/no)	Component	Substrate Material	Color	Description of Damage	Damage Quantity (sf)	XRF Reading (mg/cm2)	XRF (positive/ negative)
1	3	S32	Stairs near Boy's Restroom	yes	Ceiling	Plaster	White	None	0	N/A	N/A
1	3	S31	Stairs near Classroom 34	yes	W1	Plaster	Tan	Spalling	1	0.32	Negative
1	3	S31	Stairs near Classroom 34	yes	W1	Plaster	White	None	0	N/A	N/A
1	3	S31	Stairs near Classroom 34	yes	Storage Unit (W2)	Wood	Tan	Chipping	1	0.1	Negative
1	3	S31	Stairs near Classroom 34	yes	W3	N/A	N/A	N/A	N/A	N/A	N/A
1	3	S31	Stairs near Classroom 34	yes	W4	Plaster	Tan	Chipping	3	0.6	Negative
1	3	S31	Stairs near Classroom 34	yes	W4	Plaster	White	None	0	0.4	Negative
1	3	S31	Stairs near Classroom 34	yes	Door Frame (W4)	Metal	Brown	Friction	1	0.1	Negative
1	3	S31	Stairs near Classroom 34	yes	Floor	N/A	N/A	N/A	N/A	N/A	N/A
1	3	S31	Stairs near Classroom 34	yes	Ceiling	Plaster	White	None	0	N/A	N/A
1	1	001B	Room in Rear of Auditorium next to Vestibule	yes	W1	Sheetrock	White	Chipping	3	0	Negative
1	1	001B	Room in Rear of Auditorium next to Vestibule	yes	W1	Plaster	White	Cracking	1	0.06	Negative
1	1	001B	Room in Rear of Auditorium next to Vestibule	yes	Vertical Pipe (W1)	Metal	White	None	0	N/A	N/A

			School District of Philadelphia								
			Name of Inspector: Michael Barth, Melissa Billingsley		Lead Safe Certification Assessment Report						
			Inspection Company: Criterion Labs., Inc.		Taylor Elementary School and Annex						
E l e m e n t	F l o o r	Space #	On-Site Room Name	Student/ Teacher Occupied (yes/no)	Component	Substrate Material	Color	Description of Damage	Damage Quantity (sf)	XRF Reading (mg/cm2)	XRF (positive/ negative)
1	1	001B	Room in Rear of Auditorium next to Vestibule	yes	Cove Base (W1)	Wood	White	Cracking	1	0.06	Negative
1	1	001B	Room in Rear of Auditorium next to Vestibule	yes	Door Frame (W1)	Wood	White	None	0	N/A	N/A
1	1	001B	Room in Rear of Auditorium next to Vestibule	yes	W2	Sheetrock	White	Chipping	2	0.01	Negative
1	1	001B	Room in Rear of Auditorium next to Vestibule	yes	Window Stool (W2)	Wood	White	Flaking	2	0.05	Negative
1	1	001B	Room in Rear of Auditorium next to Vestibule	yes	Cove Base (W2)	Wood	White	Cracking	1	0.01	Negative
1	1	001B	Room in Rear of Auditorium next to Vestibule	yes	Window (W2)	Metal	Blue	Flaking	5	5.4	Positive
1	1	001B	Room in Rear of Auditorium next to Vestibule	yes	W3	Sheetrock	White	Chipping	1	0	Negative
1	1	001B	Room in Rear of Auditorium next to Vestibule	yes	W4	Sheetrock	White	Chipping	1	0	Negative
1	1	001B	Room in Rear of Auditorium next to Vestibule	yes	W4	Plaster	White	Moisture Damage	5	0	Negative
1	1	001B	Room in Rear of Auditorium next to Vestibule	yes	Floor	N/A	N/A	N/A	N/A	N/A	N/A

			School District of Philadelphia								
			Name of Inspector: Michael Barth, Melissa Billingsley		Lead Safe Certification Assessment Report						
			Inspection Company: Criterion Labs., Inc.		Taylor Elementary School and Annex						
E l e m e n t	F l o o r	Space #	On-Site Room Name	Student/ Teacher Occupied (yes/no)	Component	Substrate Material	Color	Description of Damage	Damage Quantity (sf)	XRF Reading (mg/cm2)	XRF (positive/ negative)
1	1	001B	Room in Rear of Auditorium next to Vestibule	yes	Ceiling	N/A	N/A	N/A	N/A	N/A	N/A
1	2	S200	Fire Stair next near Girl's Restroom	no	W1	Brick	Green	Chipping	1	0.03	Negative
1	2	S200	Fire Stair next near Girl's Restroom	no	W1	Plaster	Green	Chipping	1	0.1	Negative
1	2	S200	Fire Stair next near Girl's Restroom	no	W2	Brick	Green	Chipping	5	0	Negative
1	2	S200	Fire Stair next near Girl's Restroom	no	W2	Plaster	Green	None	0	N/A	N/A
1	2	S200	Fire Stair next near Girl's Restroom	no	W3	Brick	Green	Chipping	1	0	Negative
1	2	S200	Fire Stair next near Girl's Restroom	no	Door Frame (W3)	Metal	Brown	Chipping	2	0.03	Negative
1	2	S200	Fire Stair next near Girl's Restroom	no	W4	Brick	Green	Chipping	1	0.1	Negative
1	2	S200	Fire Stair next near Girl's Restroom	no	Floor	Concrete	Blue	Chipping	5	0	Negative
1	2	S200	Fire Stair next near Girl's Restroom	no	Ceiling	Plaster	Green	None	0	N/A	N/A
1	3	S300	Fire Stair next to Boy's Restroom	no	W1	Brick	Green	Chipping	5	0	Negative
1	3	S300	Fire Stair next to Boy's Restroom	no	W1	Plaster	Green	Chipping	1	0	Negative
1	3	S300	Fire Stair next to Boy's Restroom	no	W2	Brick	Green	Chipping	5	0	Negative
1	3	S300	Fire Stair next to Boy's Restroom	no	W2	Plaster	Green	None	0	0.01	Negative

			School District of Philadelphia								
			Name of Inspector: Michael Barth, Melissa Billingsley		Lead Safe Certification Assessment Report						
			Inspection Company: Criterion Labs., Inc.		Taylor Elementary School and Annex						
E l e m e n t	F l o o r	Space #	On-Site Room Name	Student/ Teacher Occupied (yes/no)	Component	Substrate Material	Color	Description of Damage	Damage Quantity (sf)	XRF Reading (mg/cm2)	XRF (positive/ negative)
1	3	S300	Fire Stair next to Boy's Restroom	no	W3	Brick	Green	Chipping	1	0	Negative
1	3	S300	Fire Stair next to Boy's Restroom	no	Door Frame (W3)	Metal	Brown	Chipping	2	0.04	Negative
1	3	S300	Fire Stair next to Boy's Restroom	no	W4	Brick	Green	Chipping	1	0	Negative
1	3	S300	Fire Stair next to Boy's Restroom	no	Floor	Concrete	Blue	Chipping	5	0.03	Negative
1	3	S300	Fire Stair next to Boy's Restroom	no	Ceiling	Plaster	Green	None	0	N/A	N/A
1	1	1.5	Vice Principal Office on Landing of Stairs between 1st and 2nd Floor	yes	W1	Plaster	Green	None	0	N/A	N/A
1	1	1.5	Vice Principal Office on Landing of Stairs between 1st and 2nd Floor	yes	Cove Base (W1)	Wood	White	None	0	N/A	N/A
1	1	1.5	Vice Principal Office on Landing of Stairs between 1st and 2nd Floor	yes	Moulding (W1)	Wood	White	Cracking	1	0	Negative
1	1	1.5	Vice Principal Office on Landing of Stairs between 1st and 2nd Floor	yes	W2	Plaster	Green	None	0	N/A	N/A
1	1	1.5	Vice Principal Office on Landing of Stairs between 1st and 2nd Floor	yes	Moulding (W2)	Wood	White	Cracking	1	0	Negative

			School District of Philadelphia								
			Name of Inspector: Michael Barth, Melissa Billingsley		Lead Safe Certification Assessment Report						
			Inspection Company: Criterion Labs., Inc.		Taylor Elementary School and Annex						
E l e m e n t	F l o o r	Space #	On-Site Room Name	Student/ Teacher Occupied (yes/no)	Component	Substrate Material	Color	Description of Damage	Damage Quantity (sf)	XRF Reading (mg/cm2)	XRF (positive/ negative)
1	1	1.5	Vice Principal Office on Landing of Stairs between 1st and 2nd Floor	yes	W3	Plaster	Green	Moisture Damage	3	0.3	Negative
1	1	1.5	Vice Principal Office on Landing of Stairs between 1st and 2nd Floor	yes	Radiator (W3)	Metal	Green	None	0	N/A	N/A
1	1	1.5	Vice Principal Office on Landing of Stairs between 1st and 2nd Floor	yes	Moulding (W3)	Wood	White	Cracking	1	0.2	Negative
1	1	1.5	Vice Principal Office on Landing of Stairs between 1st and 2nd Floor	yes	W4	Plaster	Green	None	0	N/A	N/A
1	1	1.5	Vice Principal Office on Landing of Stairs between 1st and 2nd Floor	yes	Moulding (W4)	Wood	White	Cracking	1	0	Negative
1	1	1.5	Vice Principal Office on Landing of Stairs between 1st and 2nd Floor	yes	Floor	N/A	N/A	N/A	N/A	N/A	N/A
1	1	1.5	Vice Principal Office on Landing of Stairs between 1st and 2nd Floor	yes	Ceiling	Plaster	White	None	0	N/A	N/A

			School District of Philadelphia								
			Name of Inspector: Michael Barth, Melissa Billingsley		Lead Safe Certification Assessment Report						
			Inspection Company: Criterion Labs., Inc.		Taylor Elementary School and Annex						
E l e m e n t	F l o o r	Space #	On-Site Room Name	Student/ Teacher Occupied (yes/no)	Component	Substrate Material	Color	Description of Damage	Damage Quantity (sf)	XRF Reading (mg/cm2)	XRF (positive/ negative)
1	1	1.5A	Storage Closet in Vice Principal Office in Landing of Stairs between 1st and 2nd Floor	yes	W1	Plaster	Blue	None	0	N/A	N/A
1	1	1.5A	Storage Closet in Vice Principal Office in Landing of Stairs between 1st and 2nd Floor	yes	Moulding (W1)	Wood	White	None	0	N/A	N/A
1	1	1.5A	Storage Closet in Vice Principal Office in Landing of Stairs between 1st and 2nd Floor	yes	W2	Plaster	White	None	0	N/A	N/A
1	1	1.5A	Storage Closet in Vice Principal Office in Landing of Stairs between 1st and 2nd Floor	yes	Moulding (W2)	Wood	White	Chipping	1	0	Negative
1	1	1.5A	Storage Closet in Vice Principal Office in Landing of Stairs between 1st and 2nd Floor	yes	Cove Base (W2)	Wood	Brown	None	0	N/A	N/A
1	1	1.5A	Storage Closet in Vice Principal Office in Landing of Stairs between 1st and 2nd Floor	yes	Moulding (W2)	Wood	White	None	0	N/A	N/A

			School District of Philadelphia								
			Name of Inspector: Michael Barth, Melissa Billingsley		Lead Safe Certification Assessment Report						
			Inspection Company: Criterion Labs., Inc.		Taylor Elementary School and Annex						
E l e m e n t	F l o o r	Space #	On-Site Room Name	Student/ Teacher Occupied (yes/no)	Component	Substrate Material	Color	Description of Damage	Damage Quantity (sf)	XRF Reading (mg/cm2)	XRF (positive/ negative)
1	1	1.5A	Storage Closet in Vice Principal Office in Landing of Stairs between 1st and 2nd Floor	yes	Cove Base (W3)	Wood	Brown	None	0	N/A	N/A
1	1	1.5A	Storage Closet in Vice Principal Office in Landing of Stairs between 1st and 2nd Floor	yes	W3	Plaster	White	Chipping	2	0.44	Negative
1	1	1.5A	Storage Closet in Vice Principal Office in Landing of Stairs between 1st and 2nd Floor	yes	W4	Plaster	White	Flaking	5	0.24	Negative
1	1	1.5A	Storage Closet in Vice Principal Office in Landing of Stairs between 1st and 2nd Floor	yes	Floor	Wood	Grey	None	0	N/A	N/A
1	1	1.5A	Storage Closet in Vice Principal Office in Landing of Stairs between 1st and 2nd Floor	yes	Floor	Wood	Blue	None	0	N/A	N/A
1	1	1.5A	Storage Closet in Vice Principal Office in Landing of Stairs between 1st and 2nd Floor	yes	Ceiling	Plaster	White	Flaking	5	0	Negative
1	B	Basement	Boiler Room	no	W1	Concrete	White	Flaking	20	0.03	Negative

			School District of Philadelphia								
			Name of Inspector: Michael Barth, Melissa Billingsley		Lead Safe Certification Assessment Report						
			Inspection Company: Criterion Labs., Inc.		Taylor Elementary School and Annex						
E l e m e n t	F l o o r	Space #	On-Site Room Name	Student/ Teacher Occupied (yes/no)	Component	Substrate Material	Color	Description of Damage	Damage Quantity (sf)	XRF Reading (mg/cm2)	XRF (positive/ negative)
1	B	Basement	Boiler Room	no	Door Frame (W1)	Metal	White	Friction	2	6.4	Positive
1	B	Basement	Boiler Room	no	Door (W1)	Wood	White	Chipping	5	3.3	Positive
1	B	Basement	Boiler Room	no	Support Beam (W1)	Metal	Red	Chipping	1	0.01	Negative
1	B	Basement	Boiler Room	no	W2	Concrete	White	Flaking	90	0.02	Negative
1	B	Basement	Boiler Room	no	W3	Concrete	White	Flaking	60	0.01	Negative
1	B	Basement	Boiler Room	no	W4	Concrete	White	Flaking	90	0.01	Negative
1	B	Basement	Boiler Room	no	Panel Board (W4)	Wood	Red	None	0	N/A	N/A
1	B	Basement	Boiler Room	no	Panel Board (W4)	Wood	Yellow	None	0	N/A	N/A
1	B	Basement	Boiler Room	no	Floor	Concrete	N/A	N/A	N/A	N/A	N/A
1	B	Basement	Boiler Room	no	Ceiling	Plaster	White	Flaking	60	0.02	Negative
1	B	Basement	Building Engineer's Office	no	W1	Concrete	White	Flaking	15	0.01	Negative
1	B	Basement	Building Engineer's Office	no	W1	Concrete	Pink	None	0	0.01	Negative
1	B	Basement	Building Engineer's Office	no	Piping (W1)	Metal	White	Chipping	2	0	Negative
1	B	Basement	Building Engineer's Office	no	W2	Concrete	White	Cracking	1	0	Negative
1	B	Basement	Building Engineer's Office	no	Door (W2)	Wood	White	Chipping	3	5.8	Positive
1	B	Basement	Building Engineer's Office	no	W3	Concrete	White	Flaking	10	0.02	Negative
1	B	Basement	Building Engineer's Office	no	W3	Concrete	Pink	Flaking	10	0	Negative
1	B	Basement	Building Engineer's Office	no	W4	Concrete	White	Flaking	80	0	Negative
1	B	Basement	Building Engineer's Office	no	Pipe (W4)	Metal	White	Flaking	5	0.01	Negative

			School District of Philadelphia								
			Name of Inspector: Michael Barth, Melissa Billingsley		Lead Safe Certification Assessment Report						
			Inspection Company: Criterion Labs., Inc.		Taylor Elementary School and Annex						
E l e m e n t	F l o o r	Space #	On-Site Room Name	Student/ Teacher Occupied (yes/no)	Component	Substrate Material	Color	Description of Damage	Damage Quantity (sf)	XRF Reading (mg/cm2)	XRF (positive/ negative)
1	B	Basement	Building Engineer's Office	no	Stairs (W4)	Wood	Blue	Friction	5	0.03	Negative
1	B	Basement	Building Engineer's Office	no	Floor	Concrete	Red	Chipping	5	0.02	Negative
1	B	Basement	Building Engineer's Office	no	Ceiling	Plaster	White	None	0	N/A	N/A
1	B	Basement	Building Engineer's Office	no	Ceiling	Metal	White	Chipping	10	0.01	Negative
1	C	CS	Crawlspace below Auditorium Stage	no	W1	Wood	N/A	None	0	N/A	N/A
1	C	CS	Crawlspace below Auditorium Stage	no	W2	Wood	N/A	None	0	N/A	N/A
1	C	CS	Crawlspace below Auditorium Stage	no	W3	Wood	N/A	None	0	N/A	N/A
1	C	CS	Crawlspace below Auditorium Stage	no	W4	Wood	N/A	None	0	N/A	N/A
1	C	CS	Crawlspace below Auditorium Stage	no	Floor	Concrete	N/A	None	0	N/A	N/A
1	C	CS	Crawlspace below Auditorium Stage	no	Ceiling	Wood	N/A	None	0	N/A	N/A
1	A	AT	Attic	no	W1	No Access	N/A	No Access	No Access	No Access	No Access
1	A	AT	Attic	no	W2	No Access	N/A	No Access	No Access	No Access	No Access
1	A	AT	Attic	no	W3	No Access	N/A	No Access	No Access	No Access	No Access
1	A	AT	Attic	no	W4	No Access	N/A	No Access	No Access	No Access	No Access
1	A	AT	Attic	no	Floor	No Access	N/A	No Access	No Access	No Access	No Access
1	A	AT	Attic	no	Ceiling	No Access	N/A	No Access	No Access	No Access	No Access