

		Dates: 6/5 - 7/6/2023	Lead-Safe Certification Assessment Report						
		Inspector Name and Certificate Number: Tim Smith 057662	John Bartram High School						
		Inspection Company: BATA	2401 S 67th St, Philadelphia PA 19142						
Element	Floor	On-Site Room Name	Component	Substrate Material [1]	Paint Color	Description of Paint Damage	Damage Quantity (sf) [2]	XRF Reading (mg/cm ²)	XRF (positive/negative) [3]
1	1	Pipe Shaft in Women's Restroom	W1	Concrete	Not Painted	N/A	N/A	N/A	N/A
1	1	Pipe Shaft in Women's Restroom	Doorframe	Metal	Brown	Chipping	3	2	Positive
1	1	Pipe Shaft in Women's Restroom	W2	Concrete	Not Painted	N/A	N/A	N/A	N/A
1	1	Pipe Shaft in Women's Restroom	W3	Concrete	Not Painted	N/A	N/A	N/A	N/A
1	1	Pipe Shaft in Women's Restroom	W4	Concrete	Not Painted	N/A	N/A	N/A	N/A
1	1	Pipe Shaft in Women's Restroom	Ceiling	Concrete	Not Painted	N/A	N/A	N/A	N/A
1	1	Pipe Shaft in Women's Restroom	Floor	Concrete	Not Painted	N/A	N/A	N/A	N/A
1	1	Women's Restroom	W1	Plaster	White/Red	None	0	0.1	Negative
1	1	Women's Restroom	Pipe Cover	Metal	White/Red	None	0	4.4	Positive
1	1	Women's Restroom	Pipe Insulation	Asbestos	White	None	0	0.1	Negative
1	1	Women's Restroom	Conduit	Plastic	White	None	0	0.3	Negative
1	1	Women's Restroom	Door	Wood	Red	Chipping	2	4.5	Positive
1	1	Women's Restroom	Doorframe	Metal	Multi-Color	Friction	6	0.9	Positive
1	1	Women's Restroom	W2	Plaster	White/Red	None	0	0.1	Negative
1	1	Women's Restroom	W3	Plaster	White/Red	None	0	0.1	Negative
1	1	Women's Restroom	Radiator cover	Metal	brown	Chipping	6	0.5	Negative
1	1	Women's Restroom	W4	Plaster	White/Red	None	0	0.1	Negative
1	1	Women's Restroom	Ceiling	Plaster	White	None	0	0.3	Negative
1	1	Women's Restroom	Ceiling	2'x4' Ceiling Tile	Not Painted	N/A	N/A	N/A	N/A
1	1	Women's Restroom	Floor	Floor Tile	Not Painted	N/A	N/A	N/A	N/A
1	1	Storage Room next to Women's Restroom	W1	Plaster	White	None	0	0	Negative
1	1	Storage Room next to Women's Restroom	Door	Wood	Red	Friction	3	2.2	Positive
1	1	Storage Room next to Women's Restroom	Doorframe	Metal	Multi-Color	Friction	3	0.5	Negative
1	1	Storage Room next to Women's Restroom	W2	Plaster	White	None	0	0	Negative
1	1	Storage Room next to Women's Restroom	W3	Plaster	White	Cracking	20	0.5	Negative
1	1	Storage Room next to Women's Restroom	W4	Plaster	White	None	0	0	Negative

		Dates: 6/5 - 7/6/2023	Lead-Safe Certification Assessment Report							
		Inspector Name and Certificate Number: Tim Smith 057662	John Bartram High School							
		Inspection Company: BATA	2401 S 67th St, Philadelphia PA 19142							
E l e m e n t	F l o o r	On-Site Room Name	Component	Substrate Material [1]	Paint Color	Description of Paint Damage	Damage Quantity (sf) [2]	XRF Reading (mg/cm2)	XRF (positive/ negative) [3]	
1	1	Storage Room next to Women's Restroom	Covebase	Concrete	Grey	None	0	0.2	Negative	
1	1	Storage Room next to Women's Restroom	Ceiling	Plaster	White	None	0	0.3	Negative	
1	1	Storage Room next to Women's Restroom	Floor	Concrete	Not Painted	N/A	N/A	N/A	N/A	
1	1	Storage Room next to Office 121B	W1	Plaster	White/Pink	None	0	11.8	Positive	
1	1	Storage Room next to Office 121B	Door	Wood	Red	Friction	1	0.1	Negative	
1	1	Storage Room next to Office 121B	Doorframe	Metal	Multi-Color	Friction	2	0.6	Negative	
1	1	Storage Room next to Office 121B	W2	Plaster	White	None	0	10.6	Positive	
1	1	Storage Room next to Office 121B	W3	Plaster	White	None	0	0.3	Negative	
1	1	Storage Room next to Office 121B	Pipe	Metal	White	None	0	17.1	Positive	
1	1	Storage Room next to Office 121B	W4	Plaster	White	None	0	8.1	Positive	
1	1	Storage Room next to Office 121B	Covebase	Concrete	Grey	Chipping	2	2	Positive	
1	1	Storage Room next to Office 121B	Ceiling	Plaster	White	None	0	9.4	Positive	
1	1	Storage Room next to Office 121B	Floor	Floor Tile	Not Painted	N/A	N/A	N/A	N/A	
1	1	Closet inside Storage Room next to Office 121B	W1	Plaster	Green	None	0	0.3	Negative	
1	1	Closet inside Storage Room next to Office 121B	Door	Wood	Green	None	0	0	Negative	
1	1	Closet inside Storage Room next to Office 121B	Doorframe	Metal	Multi-Color	None	0	0.2	Negative	
1	1	Closet inside Storage Room next to Office 121B	W2	Plaster	Green	Chipping	6	0.3	Negative	
1	1	Closet inside Storage Room next to Office 121B	W3	Plaster	Green	None	0	0	Negative	
1	1	Closet inside Storage Room next to Office 121B	W4	Plaster	Green	None	0	0	Negative	
1	1	Closet inside Storage Room next to Office 121B	Ceiling	Plaster	White	Cracking	2	0.1	Negative	
1	1	Closet inside Storage Room next to Office 121B	Floor	Floor Tile	Not Painted	N/A	N/A	N/A	N/A	
1	1	Custodial Closet between 1st Floor Girl's and Woman's Bathroom	W1	Plaster	Green	Flaking	12	0	Negative	
1	1	Custodial Closet between 1st Floor Girl's and Woman's Bathroom	Door	Wood	Red	None	0	3.3	Positive	
1	1	Custodial Closet between 1st Floor Girl's and Woman's Bathroom	Doorframe	Metal	Multi-Color	Flaking	20	1.4	Positive	

		Dates: 6/5 - 7/6/2023	Lead-Safe Certification Assessment Report						
		Inspector Name and Certificate Number: Tim Smith 057662	John Bartram High School						
		Inspection Company: BATA	2401 S 67th St, Philadelphia PA 19142						
E l e m e n t	F l o o r	On-Site Room Name	Component	Substrate Material [1]	Paint Color	Description of Paint Damage	Damage Quantity (sf) [2]	XRF Reading (mg/cm2)	XRF (positive/ negative) [3]
1	1	Custodial Closet between 1st Floor Girl's and Woman's Bathroom	W2	Plaster	Green	Flaking	80	0.2	Negative
1	1	Custodial Closet between 1st Floor Girl's and Woman's Bathroom	W3	Plaster	Green	Flaking	30	0.3	Negative
1	1	Custodial Closet between 1st Floor Girl's and Woman's Bathroom	Shelf	Wood	White	Friction	6	0	Negative
1	1	Custodial Closet between 1st Floor Girl's and Woman's Bathroom	W4	Plaster	Green	Flaking	90	0.1	Negative
1	1	Custodial Closet between 1st Floor Girl's and Woman's Bathroom	Covebase	Concrete	Brown	Chipping	12	0.1	Negative
1	1	Custodial Closet between 1st Floor Girl's and Woman's Bathroom	Ceiling	Plaster	White	Cracking	12	0.4	Negative
1	1	Custodial Closet between 1st Floor Girl's and Woman's Bathroom	Floor	Concrete	Not Painted	N/A	N/A	N/A	N/A
1	1	Pipe Chase in Custodial Closet between 1st Floor Girl's and Woman's Bathroom	W1	Concrete	Not Painted	N/A	N/A	N/A	N/A
1	1	Pipe Chase in Custodial Closet between 1st Floor Girl's and Woman's Bathroom	Door	Wood	Grey	Cracking	6	0.1	Negative
1	1	Pipe Chase in Custodial Closet between 1st Floor Girl's and Woman's Bathroom	Doorframe	Metal	Grey	Chipping	4	0.9	Positive
1	1	Pipe Chase in Custodial Closet between 1st Floor Girl's and Woman's Bathroom	W2	Concrete	Not Painted	N/A	N/A	N/A	N/A
1	1	Pipe Chase in Custodial Closet between 1st Floor Girl's and Woman's Bathroom	W3	Concrete	Not Painted	N/A	N/A	N/A	N/A
1	1	Pipe Chase in Custodial Closet between 1st Floor Girl's and Woman's Bathroom	W4	Concrete	Not Painted	N/A	N/A	N/A	N/A
1	1	Pipe Chase in Custodial Closet between 1st Floor Girl's and Woman's Bathroom	Ceiling	Concrete	Not Painted	N/A	N/A	N/A	N/A
1	1	Pipe Chase in Custodial Closet between 1st Floor Girl's and Woman's Bathroom	Floor	Concrete	Not Painted	N/A	N/A	N/A	N/A
1	1	Men's Restroom	W1	Plaster	White/Red	None	0	0	Negative

		Dates: 6/5 - 7/6/2023	Lead-Safe Certification Assessment Report						
		Inspector Name and Certificate Number: Tim Smith 057662	John Bartram High School						
		Inspection Company: BATA	2401 S 67th St, Philadelphia PA 19142						
E l e m e n t	F l o o r	On-Site Room Name	Component	Substrate Material [1]	Paint Color	Description of Paint Damage	Damage Quantity (sf) [2]	XRF Reading (mg/cm2)	XRF (positive/ negative) [3]
1	1	Men's Restroom	Pipe Cover	Metal	White/Red	None	0	3	Positive
1	1	Men's Restroom	Pipe Insulation	Asbestos	White	None	0	0	Negative
1	1	Men's Restroom	Conduit	Plastic	White	None	0	0.3	Negative
1	1	Men's Restroom	Door	Wood	Red	Friction	4	4	Positive
1	1	Men's Restroom	Doorframe	Metal	Brown	Chipping	2	1	Positive
1	1	Men's Restroom	W2	Plaster	White/Red	None	0	0.1	Negative
1	1	Men's Restroom	W3	Plaster	White/Red	None	0	0.1	Negative
1	1	Men's Restroom	Windowsill	Wood	Brown	None	0	0.2	Negative
1	1	Men's Restroom	Radiator cover	Metal	brown	None	0	0	Negative
1	1	Men's Restroom	W4	Plaster	White/Red	None	0	0.5	Negative
1	1	Men's Restroom	Ceiling	Plaster	White	None	0	0.3	Negative
1	1	Men's Restroom	Ceiling	2'x4' Ceiling Tile	Not Painted	N/A	N/A	N/A	N/A
1	1	Men's Restroom	Floor	Floor Tile	Not Painted	N/A	N/A	N/A	N/A
1	1	Custodial Closet between Men's and Boy's restrooms	W1	Plaster	Green	Cracking	4	0.5	Negative
1	1	Custodial Closet between Men's and Boy's restrooms	Door	Wood	Red	Friction	2	2.6	Positive
1	1	Custodial Closet between Men's and Boy's restrooms	Doorframe	Metal	Multi-Color	Chipping	8	0.6	Negative
1	1	Custodial Closet between Men's and Boy's restrooms	W2	Plaster	Green	Cracking	30	0.3	Negative
1	1	Custodial Closet between Men's and Boy's restrooms	W3	Plaster	Green	Cracking	10	0.2	Negative
1	1	Custodial Closet between Men's and Boy's restrooms	Shelf	Wood	White	Friction	6	0.2	Negative
1	1	Custodial Closet between Men's and Boy's restrooms	W4	Plaster	Green	Cracking	30	0.2	Negative
1	1	Custodial Closet between Men's and Boy's restrooms	Covebase	Concrete	Brown	Flaking	10	0.2	Negative
1	1	Custodial Closet between Men's and Boy's restrooms	Ceiling	Concrete	White	None	0	0.1	Negative
1	1	Custodial Closet between Men's and Boy's restrooms	Floor	Concrete	Not Painted	N/A	N/A	N/A	N/A
1	1	Classroom 101	W1	Plaster	White	None	0	0.2	Negative
1	1	Classroom 101	Doorframe	Metal	Brown	None	0	0.9	Positive
1	1	Classroom 101	Conduit	Plastic	White	None	0	0.6	Negative

		Dates: 6/5 - 7/6/2023	Lead-Safe Certification Assessment Report						
		Inspector Name and Certificate Number: Tim Smith 057662	John Bartram High School						
		Inspection Company: BATA	2401 S 67th St, Philadelphia PA 19142						
E l e m e n t	F l o o r	On-Site Room Name	Component	Substrate Material [1]	Paint Color	Description of Paint Damage	Damage Quantity (sf) [2]	XRF Reading (mg/cm ²)	XRF (positive/ negative) [3]
1	1	Classroom 101	W2	Plaster	White	None	0	0.2	Negative
1	1	Classroom 101	W3	Plaster	White	None	0	0.1	Negative
1	1	Classroom 101	Conduit	Metal	White	None	0	0	Negative
1	1	Classroom 101	Radiator cover	Metal	Tan	Chipping	16	0.3	Negative
1	1	Classroom 101	W4	Plaster	White	None	0	0.1	Negative
1	1	Classroom 101	Ceiling	Plaster	White	Flaking	300	0.5	Negative
1	1	Classroom 101	Ceiling	2'x4' Ceiling Tile	Not Painted	N/A	N/A	N/A	N/A
1	1	Classroom 101	Floor	Wood	Not Painted	N/A	N/A	N/A	N/A
1	1	Classroom 102	W1	Plaster	White	None	0	0	Negative
1	1	Classroom 102	Doorframe	Metal	Brown	None	0	0.9	Positive
1	1	Classroom 102	Conduit	Metal	White	None	0	0.1	Negative
1	1	Classroom 102	W2	Plaster	White	Cracking	2	0.1	Negative
1	1	Classroom 102	W3	Plaster	White	Flaking	14	0	Negative
1	1	Classroom 102	Pipe Cover	Metal	White	None	0	2.9	Positive
1	1	Classroom 102	Pipe Insulation	Asbestos	White	None	0	0	Negative
1	1	Classroom 102	Radiator cover	Metal	Brown	Chipping	12	0.7	Positive
1	1	Classroom 102	W4	Plaster	White	Cracking	3	0	Negative
1	1	Classroom 102	Ceiling	Plaster	White	Flaking	200	0.1	Negative
1	1	Classroom 102	Ceiling	2'x4' Ceiling Tile	Not Painted	N/A	N/A	N/A	N/A
1	1	Classroom 102	Floor	Wood	Not Painted	N/A	N/A	N/A	N/A
1	1	Classroom 103	W1	Plaster	White	None	0	0.1	Negative
1	1	Classroom 103	Doorframe	Metal	Brown	None	0	0.9	Positive
1	1	Classroom 103	Conduit	Metal	White	None	0	0	Negative
1	1	Classroom 103	Conduit	Plastic	White	None	0	0.1	Negative
1	1	Classroom 103	Blackboard Frame	Wood	White	None	0	0.2	Negative
1	1	Classroom 103	W2	Wood	Green	None	0	0.1	Negative

		Dates: 6/5 - 7/6/2023	Lead-Safe Certification Assessment Report						
		Inspector Name and Certificate Number: Tim Smith 057662	John Bartram High School						
		Inspection Company: BATA	2401 S 67th St, Philadelphia PA 19142						
E l e m e n t	F l o o r	On-Site Room Name	Component	Substrate Material [1]	Paint Color	Description of Paint Damage	Damage Quantity (sf) [2]	XRF Reading (mg/cm2)	XRF (positive/ negative) [3]
1	1	Classroom 103	W3	Plaster	White	None	0	0.1	Negative
1	1	Classroom 103	Windowframe	Wood	White	None	0	0.3	Negative
1	1	Classroom 103	Radiator cover	Metal	Brown	Chipping	4	0.4	Negative
1	1	Classroom 103	Covebase	Concrete	Brown	None	0	0.2	Negative
1	1	Classroom 103	W4	Plaster	White	None	0	0	Negative
1	1	Classroom 103	Ceiling	Plaster	White	Flaking	40	0.3	Negative
1	1	Classroom 103	Ceiling	2'x4' Ceiling Tile	Not Painted	N/A	N/A	N/A	N/A
1	1	Classroom 103	Floor	Wood	Not Painted	N/A	N/A	N/A	N/A
1	1	Classroom 103 Office	W1	Drywall	White	None	0	0	Negative
1	1	Classroom 103 Office	Doorframe	Wood	White	None	0	0.1	Negative
1	1	Classroom 103 Office	W2	Drywall	White	None	0	0.3	Negative
1	1	Classroom 103 Office	Windowframe	Metal	White	None	0	0.1	Negative
1	1	Classroom 103 Office	W3	Drywall	White	None	0	0.2	Negative
1	1	Classroom 103 Office	W4	Plaster	White	None	0	0.5	Negative
1	1	Classroom 103 Office	Ceiling	Plaster	White	None	0	0.3	Negative
1	1	Classroom 103 Office	Ceiling	2'x4' Ceiling Tile	Not Painted	N/A	N/A	N/A	N/A
1	1	Classroom 103 Office	Floor	Wood	Not Painted	N/A	N/A	N/A	N/A
1	1	Classroom 104	W1	Plaster	White	None	0	0.1	Negative
1	1	Classroom 104	Doorframe	Metal	Brown	None	0	0.9	Positive
1	1	Classroom 104	Conduit	Metal	White	None	0	0.1	Negative
1	1	Classroom 104	W2	Plaster	White	None	0	0.2	Negative
1	1	Classroom 104	Conduit	Plastic	White	None	0	0.5	Negative
1	1	Classroom 104	W3	Plaster	White	None	0	0.5	Negative
1	1	Classroom 104	Pipe Cover	Metal	White	Chipping	3	2.2	Positive
1	1	Classroom 104	Pipe Insulation	Asbestos	White	None	0	0	Negative
1	1	Classroom 104	Radiator cover	Metal	Brown	Friction	5	0.2	Negative

		Dates: 6/5 - 7/6/2023	Lead-Safe Certification Assessment Report							
		Inspector Name and Certificate Number: Tim Smith 057662	John Bartram High School							
		Inspection Company: BATA	2401 S 67th St, Philadelphia PA 19142							
E l e m e n t	F l o o r	On-Site Room Name	Component	Substrate Material [1]	Paint Color	Description of Paint Damage	Damage Quantity (sf) [2]	XRF Reading (mg/cm2)	XRF (positive/ negative) [3]	
1	1	Classroom 104	W4	Plaster	White	None	0	0.2	Negative	
1	1	Classroom 104	Ceiling	Plaster	White	None	0	0.1	Negative	
1	1	Classroom 104	Ceiling	2'x4' Ceiling Tile	Not Painted	N/A	N/A	N/A	N/A	
1	1	Classroom 104	Floor	Wood	Not Painted	N/A	N/A	N/A	N/A	
1	1	Classroom 105	W1	Plaster	White	None	0	0	Negative	
1	1	Classroom 105	Doorframe	Metal	Brown	None	0	0.8	Positive	
1	1	Classroom 105	Conduit	Metal	White	None	0	0.1	Negative	
1	1	Classroom 105	Blackboard Frame	Wood	White	None	0	0.2	Negative	
1	1	Classroom 105	Covebase	Concrete	Brown	None	0	0.3	Negative	
1	1	Classroom 105	W2	Plaster	White	None	0	0	Negative	
1	1	Classroom 105	W3	Plaster	White	None	0	0.1	Negative	
1	1	Classroom 105	Windowsill	Wood	White	None	0	0.2	Negative	
1	1	Classroom 105	Radiator cover	Metal	Brown	None	0	0.4	Negative	
1	1	Classroom 105	W4	Wood	Green	None	0	0.1	Negative	
1	1	Classroom 105	Ceiling	Plaster	White	None	0	0.1	Negative	
1	1	Classroom 105	Ceiling	2'x4' Ceiling Tile	Not Painted	N/A	N/A	N/A	N/A	
1	1	Classroom 105	Floor	Wood	Not Painted	N/A	N/A	N/A	N/A	
1	1	Classroom 105 - Office	W1	Drywall	White	None	0	0.3	Negative	
1	1	Classroom 105 - Office	Doorframe	Wood	White	Friction	1	0.1	Negative	
1	1	Classroom 105 - Office	W2	Plaster	White	None	0	0	Negative	
1	1	Classroom 105 - Office	W3	Plaster	White	None	0	0.1	Negative	
1	1	Classroom 105 - Office	Windowframe	Metal	White	None	0	0.1	Negative	
1	1	Classroom 105 - Office	W4	Plaster	White	None	0	0.2	Negative	
1	1	Classroom 105 - Office	Ceiling	Plaster	White	None	0	0.1	Negative	
1	1	Classroom 105 - Office	Ceiling	2'x4' Ceiling Tile	Not Painted	N/A	N/A	N/A	N/A	
1	1	Classroom 105 - Office	Floor	Wood	Not Painted	N/A	N/A	N/A	N/A	

		Dates: 6/5 - 7/6/2023	Lead-Safe Certification Assessment Report						
		Inspector Name and Certificate Number: Tim Smith 057662	John Bartram High School						
		Inspection Company: BATA	2401 S 67th St, Philadelphia PA 19142						
E l e m e n t	F l o o r	On-Site Room Name	Component	Substrate Material [1]	Paint Color	Description of Paint Damage	Damage Quantity (sf) [2]	XRF Reading (mg/cm ²)	XRF (positive/ negative) [3]
1	1	Classroom 106	W1	Plaster	White	None	0	0.1	Negative
1	1	Classroom 106	Doorframe	Metal	Brown	Friction	2	0.5	Negative
1	1	Classroom 106	Conduit	Plastic	White	None	0	0.7	Positive
1	1	Classroom 106	W2	Plaster	White	None	0	0	Negative
1	1	Classroom 106	Wall Partition	Drywall	White	None	0	0	Negative
1	1	Classroom 106	Partition Doorframe	Metal	Brown	Chipping	6	0.1	Negative
1	1	Classroom 106	W3	Plaster	White	None	0	0.1	Negative
1	1	Classroom 106	Pipe Cover	Metal	White	Chipping	2	4.5	Positive
1	1	Classroom 106	Pipe Insulation	Asbestos	White	None	0	0.1	Negative
1	1	Classroom 106	Radiator cover	Metal	Tan	Chipping	6	0.6	Negative
1	1	Classroom 106	W4	Plaster	White	None	0	0.1	Negative
1	1	Classroom 106	Ceiling	Plaster	White	Flaking	230	0.1	Negative
1	1	Classroom 106	Ceiling	2'x4' Ceiling Tile	Not Painted	N/A	N/A	N/A	N/A
1	1	Classroom 106	Floor	Wood	Not Painted	N/A	N/A	N/A	N/A
1	1	Restroom inside Classroom 106	W1	Drywall	White	None	0	0.2	Negative
1	1	Restroom inside Classroom 106	Doorframe	Metal	Brown	Friction	2	0	Negative
1	1	Restroom inside Classroom 106	W2	Drywall	White	None	0	0.2	Negative
1	1	Restroom inside Classroom 106	W3	Plaster	White	None	0	0	Negative
1	1	Restroom inside Classroom 106	Pipe Cover	Metal	White	None	0	4	Positive
1	1	Restroom inside Classroom 106	Pipe Insulation	Asbestos	White	None	0	0.1	Negative
1	1	Restroom inside Classroom 106	W4	Plaster	White	None	0	0	Negative
1	1	Restroom inside Classroom 106	Ceiling	Plaster	White	None	0	0.1	Negative
1	1	Restroom inside Classroom 106	Floor	Wood	Not Painted	N/A	N/A	N/A	N/A
1	1	Classroom 107/109	W1	Plaster	White	None	0	0.5	Negative
1	1	Classroom 107/109	Doorframe	Metal	Brown	Friction	7	1.4	Positive
1	1	Classroom 107/109	Conduit	Metal	White	None	0	0.1	Negative

		Dates: 6/5 - 7/6/2023	Lead-Safe Certification Assessment Report						
		Inspector Name and Certificate Number: Tim Smith 057662	John Bartram High School						
		Inspection Company: BATA	2401 S 67th St, Philadelphia PA 19142						
E l e m e n t	F l o o r	On-Site Room Name	Component	Substrate Material [1]	Paint Color	Description of Paint Damage	Damage Quantity (sf) [2]	XRF Reading (mg/cm2)	XRF (positive/ negative) [3]
1	1	Classroom 107/109	W2	Plaster	White	None	0	0.2	Negative
1	1	Classroom 107/109	Windowsill	Wood	White	Chipping	5	0.2	Negative
1	1	Classroom 107/109	W3	Plaster	White	Cracking	16	0	Negative
1	1	Classroom 107/109	Radiator cover	Metal	Tan	Chipping	22	0.5	Negative
1	1	Classroom 107/109	W4	Plaster	White	None	0	0	Negative
1	1	Classroom 107/109	Ceiling	Plaster	White	None	0	0.3	Negative
1	1	Classroom 107/109	Ceiling	2'x4' Ceiling Tile	Not Painted	N/A	N/A	N/A	N/A
1	1	Classroom 107/109	Floor	Wood	Not Painted	N/A	N/A	N/A	N/A
1	1	Classroom 108	W1	Plaster	White	Chipping	6	0.6	Negative
1	1	Classroom 108	Doorframe	Metal	Brown	Friction	3	1	Positive
1	1	Classroom 108	W2	Plaster	White	None	0	0	Negative
1	1	Classroom 108	Conduit	Metal	White	None	0	0.5	Negative
1	1	Classroom 108	W3	Plaster	White	Chipping	2	0.1	Negative
1	1	Classroom 108	Pipe	Metal	White	Flaking	4	16.4	Positive
1	1	Classroom 108	Radiator cover	Metal	Tan	Chipping	10	0.8	Positive
1	1	Classroom 108	Conduit	Plastic	White	None	0	0.5	Negative
1	1	Classroom 108	W4	Plaster	White	None	0	0	Negative
1	1	Classroom 108	Ceiling	Plaster	White	Flaking	140	0.2	Negative
1	1	Classroom 108	Ceiling	2'x4' Ceiling Tile	Not Painted	N/A	N/A	N/A	N/A
1	1	Classroom 108	Floor	Wood	Not Painted	N/A	N/A	N/A	N/A
1	1	Girl's Restroom	W1	Ceramic	White	None	0	0	Negative
1	1	Girl's Restroom	Doorframe	Metal	Brown	Chipping	4	0.6	Negative
1	1	Girl's Restroom	Door	Wood	Red	None	0	0	Negative
1	1	Girl's Restroom	W2	Ceramic	White	None	0	0	Negative
1	1	Girl's Restroom	Pipe Cover	Metal	Brown	None	0	0.6	Negative
1	1	Girl's Restroom	Pipe Insulation	Asbestos	White	None	0	0	Negative

		Dates: 6/5 - 7/6/2023	Lead-Safe Certification Assessment Report						
		Inspector Name and Certificate Number: Tim Smith 057662	John Bartram High School						
		Inspection Company: BATA	2401 S 67th St, Philadelphia PA 19142						
E l e m e n t	F l o o r	On-Site Room Name	Component	Substrate Material [1]	Paint Color	Description of Paint Damage	Damage Quantity (sf) [2]	XRF Reading (mg/cm2)	XRF (positive/ negative) [3]
1	1	Girl's Restroom	W3	Ceramic	White	None	0	0	Negative
1	1	Girl's Restroom	Radiator cover	Metal	Brown	Chipping	12	0	Negative
1	1	Girl's Restroom	W4	Ceramic	White	None	0	0	Negative
1	1	Girl's Restroom	Stall	Metal	Green	Chipping	8	0.1	Negative
1	1	Girl's Restroom	Ceiling	Plaster	White	None	0	0.1	Negative
1	1	Girl's Restroom	Floor	Terrazzo	Not Painted	N/A	N/A	N/A	N/A
1	1	Custodial Closet next to Girl's Restroom	W1	Plaster	Blue	Cracking	20	0	Negative
1	1	Custodial Closet next to Girl's Restroom	Doorframe	Metal	Brown	Friction	3	0.5	Negative
1	1	Custodial Closet next to Girl's Restroom	Door	Wood	Red	None	0	4.3	Positive
1	1	Custodial Closet next to Girl's Restroom	W2	Plaster	Blue	Cracking	30	0	Negative
1	1	Custodial Closet next to Girl's Restroom	W3	Plaster	Blue	Cracking	40	0.1	Negative
1	1	Custodial Closet next to Girl's Restroom	W4	Plaster	Blue	Cracking	100	0	Negative
1	1	Custodial Closet next to Girl's Restroom	Covebase	Concrete	Grey	Flaking	10	0.1	Negative
1	1	Custodial Closet next to Girl's Restroom	Ceiling	Plaster	White	None	0	0.2	Negative
1	1	Custodial Closet next to Girl's Restroom	Floor	Concrete	Not Painted	N/A	N/A	N/A	N/A
1	1	Office 110	W1	Plaster	White	None	0	0	Negative
1	1	Office 110	Doorframe	Metal	Brown	Chipping	3	1.3	Positive
1	1	Office 110	W2	Plaster	White	None	0	0.1	Negative
1	1	Office 110	Conduit	Metal	White	None	0	0.2	Negative
1	1	Office 110	W3	Plaster	White	None	0	0.1	Negative
1	1	Office 110	Pipe Cover	Metal	White	None	0	2.6	Positive
1	1	Office 110	Pipe Insulation	Asbestos	White	None	0	0.1	Negative
1	1	Office 110	Radiator cover	Metal	Brown	Friction	2	2.6	Positive
1	1	Office 110	W4	Plaster	White	None	0	0.1	Negative
1	1	Office 110	Ceiling	Plaster	White	None	0	0.5	Negative
1	1	Office 110	Ceiling	2'x4' Ceiling Tile	Not Painted	N/A	N/A	N/A	N/A

		Dates: 6/5 - 7/6/2023	Lead-Safe Certification Assessment Report						
		Inspector Name and Certificate Number: Tim Smith 057662	John Bartram High School						
		Inspection Company: BATA	2401 S 67th St, Philadelphia PA 19142						
E l e m e n t	F l o o r	On-Site Room Name	Component	Substrate Material [1]	Paint Color	Description of Paint Damage	Damage Quantity (sf) [2]	XRF Reading (mg/cm ²)	XRF (positive/ negative) [3]
1	1	Office 110	Floor	Wood	Not Painted	N/A	N/A	N/A	N/A
1	1	Office 110 - Closet	W1	Plaster	Green	Cracking	6	0.5	Negative
1	1	Office 110 - Closet	Doorframe	Metal	Brown	None	0	0.8	Positive
1	1	Office 110 - Closet	W2	Plaster	Green	Cracking	3	0.1	Negative
1	1	Office 110 - Closet	W3	Plaster	Green	None	0	0	Negative
1	1	Office 110 - Closet	W4	Plaster	Green	None	0	0	Negative
1	1	Office 110 - Closet	Ceiling	Plaster	White	Cracking	2	0.1	Negative
1	1	Office 110 - Closet	Floor	Floor Tile	Not Painted	N/A	N/A	N/A	N/A
1	1	Classroom 111	W1	Plaster	White	None	0	0	Negative
1	1	Classroom 111	Doorframe	Metal	Brown	Friction	3	0.6	Negative
1	1	Classroom 111	W2	Plaster	White	None	0	0.1	Negative
1	1	Classroom 111	Conduit	Plastic	White	None	0	0.4	Negative
1	1	Classroom 111	W3	Plaster	White	None	0	0.1	Negative
1	1	Classroom 111	Pipe Cover	Metal	White	None	0	3.7	Positive
1	1	Classroom 111	Pipe Insulation	Asbestos	White	None	0	0.1	Negative
1	1	Classroom 111	Radiator cover	Metal	Brown	Friction	6	0.5	Negative
1	1	Classroom 111	W4	Plaster	White	None	0	0	Negative
1	1	Classroom 111	Ceiling	Plaster	White	None	0	0.1	Negative
1	1	Classroom 111	Ceiling	2'x4' Ceiling Tile	Not Painted	N/A	N/A	N/A	N/A
1	1	Classroom 111	Floor	Wood	Not Painted	N/A	N/A	N/A	N/A
1	1	Classroom 112	W1	Terracotta	Blue	None	0	0.1	Negative
1	1	Classroom 112	Doorframe	Metal	Blue	Chipping	1	0.5	Negative
1	1	Classroom 112	Door	Metal	Blue	Friction	4	0	Negative
1	1	Classroom 112	W2	Plaster	Blue	None	0	0.1	Negative
1	1	Classroom 112	Conduit	Metal	Blue	None	0	0	Negative
1	1	Classroom 112	W3	Plaster	Blue	Cracking	6	0	Negative

		Dates: 6/5 - 7/6/2023	Lead-Safe Certification Assessment Report							
		Inspector Name and Certificate Number: Tim Smith 057662	John Bartram High School							
		Inspection Company: BATA	2401 S 67th St, Philadelphia PA 19142							
E l e m e n t	F l o o r	On-Site Room Name	Component	Substrate Material [1]	Paint Color	Description of Paint Damage	Damage Quantity (sf) [2]	XRF Reading (mg/cm2)	XRF (positive/ negative) [3]	
1	1	Classroom 112	Pipe Cover	Metal	White	Chipping	12	4.8	Positive	
1	1	Classroom 112	Pipe Insulation	Asbestos	White	None	0	0.1	Negative	
1	1	Classroom 112	Radiator cover	Metal	Brown	Chipping	6	0.7	Positive	
1	1	Classroom 112	W4	Drywall	White	None	0	0.1	Negative	
1	1	Classroom 112	Mural Wall	Drywall	Multi-Color	None	0	0.1	Negative	
1	1	Classroom 112	Ceiling	Plaster	White	flaking	240	0.2	Negative	
1	1	Classroom 112	Ceiling	2'x4' Ceiling Tile	Not Painted	N/A	N/A	N/A	N/A	
1	1	Classroom 112	Floor	Floor Tile	Not Painted	N/A	N/A	N/A	N/A	
1	1	Classroom 112 - Closet	W1	No Access	No Access	No Access	No Access	No Access	No Access	
1	1	Classroom 112 - Closet	W2	No Access	No Access	No Access	No Access	No Access	No Access	
1	1	Classroom 112 - Closet	W3	No Access	No Access	No Access	No Access	No Access	No Access	
1	1	Classroom 112 - Closet	W4	No Access	No Access	No Access	No Access	No Access	No Access	
1	1	Classroom 112 - Closet	Ceiling	No Access	No Access	No Access	No Access	No Access	No Access	
1	1	Classroom 112 - Closet	Floor	No Access	No Access	No Access	No Access	No Access	No Access	
1	1	Classroom 113	W1	Plaster	White	Cracking	2	0.2	Negative	
1	1	Classroom 113	Doorframe	Metal	Brown	Friction	6	0.8	Positive	
1	1	Classroom 113	W2	Plaster	White	None	0	0.1	Negative	
1	1	Classroom 113	Conduit	Plastic	White	None	0	0.6	Negative	
1	1	Classroom 113	W3	Plaster	White	Flaking	46	0	Negative	
1	1	Classroom 113	Pipe Cover	Metal	White	Chipping	5	3.3	Positive	
1	1	Classroom 113	Pipe Insulation	Asbestos	White	None	0	0	Negative	
1	1	Classroom 113	Radiator cover	Metal	Brown	Friction	3	0.2	Negative	
1	1	Classroom 113	W4	Plaster	White	Chipping	8	0.5	Negative	
1	1	Classroom 113	Ceiling	Plaster	White	None	0	0.1	Negative	
1	1	Classroom 113	Ceiling	2'x4' Ceiling Tile	Not Painted	N/A	N/A	N/A	N/A	
1	1	Classroom 113	Floor	Wood	Not Painted	N/A	N/A	N/A	N/A	

		Dates: 6/5 - 7/6/2023	Lead-Safe Certification Assessment Report						
		Inspector Name and Certificate Number: Tim Smith 057662	John Bartram High School						
		Inspection Company: BATA	2401 S 67th St, Philadelphia PA 19142						
E l e m e n t	F l o o r	On-Site Room Name	Component	Substrate Material [1]	Paint Color	Description of Paint Damage	Damage Quantity (sf) [2]	XRF Reading (mg/cm2)	XRF (positive/ negative) [3]
1	1	Classroom 115	W1	Plaster	White/Pink	Cracking	2	0.1	Negative
1	1	Classroom 115	Doorframe	Metal	Brown	Flaking	4	0.5	Negative
1	1	Classroom 115	W2	Plaster	White/Pink	None	0	0.1	Negative
1	1	Classroom 115	W3	Plaster	White/Pink	Cracking	20	0.1	Negative
1	1	Classroom 115	Pipe Cover	Metal	White/Pink	Cracking	2	4.1	Positive
1	1	Classroom 115	Pipe Insulation	Asbestos	White	None	0	0	Negative
1	1	Classroom 115	Radiator cover	Metal	Brown	None	0	0.6	Negative
1	1	Classroom 115	W4	Plaster	White/Pink	None	0	0	Negative
1	1	Classroom 115	Ceiling	Plaster	White	Flaking	20	0.2	Negative
1	1	Classroom 115	Ceiling	2'x4' Ceiling Tile	Not Painted	N/A	N/A	N/A	N/A
1	1	Classroom 115	Floor	Wood	Not Painted	N/A	N/A	N/A	N/A
1	1	Weight Room	W1	Terracotta	White	Chipping	13	0.1	Negative
1	1	Weight Room	Door	Metal	Brown	Chipping	1	0.1	Negative
1	1	Weight Room	Doorframe	Metal	White	None	0	0.6	Negative
1	1	Weight Room	Pipe	Metal	White	None	0	9.3	Positive
1	1	Weight Room	W2	Plaster	White	None	0	0.1	Negative
1	1	Weight Room	Conduit	Metal	White	None	0	0.3	Negative
1	1	Weight Room	W3	Terracotta	White	Chipping	30	0.1	Negative
1	1	Weight Room	Pipe Cover	Metal	White	Chipping	2	0.4	Negative
1	1	Weight Room	Pipe Insulation	Asbestos	White	None	0	0.1	Negative
1	1	Weight Room	Radiator cover	Metal	Brown	Friction	8	0.6	Negative
1	1	Weight Room	W4	Terracotta	White	None	0	0.1	Negative
1	1	Weight Room	Ceiling	Plaster	White	Flaking	600	0.2	Negative
1	1	Weight Room	Ceiling	2'x4' Ceiling Tile	Not Painted	N/A	N/A	N/A	N/A
1	1	Weight Room	Floor	Floor Tile	Not Painted	N/A	N/A	N/A	N/A
1	1	Classroom 117	W1	Plaster	White	Cracking	4	0	Negative

		Dates: 6/5 - 7/6/2023	Lead-Safe Certification Assessment Report						
		Inspector Name and Certificate Number: Tim Smith 057662	John Bartram High School						
		Inspection Company: BATA	2401 S 67th St, Philadelphia PA 19142						
E l e m e n t	F l o o r	On-Site Room Name	Component	Substrate Material [1]	Paint Color	Description of Paint Damage	Damage Quantity (sf) [2]	XRF Reading (mg/cm2)	XRF (positive/ negative) [3]
1	1	Classroom 117	Doorframe	Metal	Brown	Friction	12	1.2	Positive
1	1	Classroom 117	W2	Plaster	White	None	0	0.1	Negative
1	1	Classroom 117	W3	Plaster	White	Chipping	3	0.1	Negative
1	1	Classroom 117	Pipe Cover	Metal	White	Chipping	2	3.4	Positive
1	1	Classroom 117	Pipe Insulation	Asbestos	White	None	0	0.1	Negative
1	1	Classroom 117	Radiator cover	Metal	Brown	Friction	4	0.9	Positive
1	1	Classroom 117	W4	Plaster	White	Chipping	6	0	Negative
1	1	Classroom 117	Ceiling	Plaster	White	None	0	0	Negative
1	1	Classroom 117	Ceiling	2'x4' Ceiling Tile	Not Painted	N/A	N/A	N/A	N/A
1	1	Classroom 117	Floor	Wood	Not Painted	N/A	N/A	N/A	N/A
1	1	Classroom 118	W1	Plaster	White	None	0	0.1	Negative
1	1	Classroom 118	Doorframe	Metal	Brown	Friction	4	1.1	Positive
1	1	Classroom 118	W2	Plaster	White	None	0	0.3	Negative
1	1	Classroom 118	Conduit	Metal	White	None	0	0	Negative
1	1	Classroom 118	W3	Plaster	White	Cracking	30	0.6	Negative
1	1	Classroom 118	Pipe Cover	Metal	White	Chipping	5	4.1	Positive
1	1	Classroom 118	Pipe Insulation	Asbestos	White	None	0	0	Negative
1	1	Classroom 118	Radiator cover	Metal	Brown	Friction	4	0.5	Negative
1	1	Classroom 118	W4	Plaster	White	Chipping	16	0.1	Negative
1	1	Classroom 118	Ceiling	Plaster	White	Flaking	300	0.1	Negative
1	1	Classroom 118	Ceiling	2'x4' Ceiling Tile	Not Painted	N/A	N/A	N/A	N/A
1	1	Classroom 118	Floor	Wood	Not Painted	N/A	N/A	N/A	N/A
1	1	Classroom 119	W1	Plaster	White	None	0	0	Negative
1	1	Classroom 119	Doorframe	Metal	Brown	Friction	6	1	Positive
1	1	Classroom 119	W2	Plaster	White	None	0	0.1	Negative
1	1	Classroom 119	Conduit	Plastic	White	None	0	0.8	Positive

		Dates: 6/5 - 7/6/2023	Lead-Safe Certification Assessment Report						
		Inspector Name and Certificate Number: Tim Smith 057662	John Bartram High School						
		Inspection Company: BATA	2401 S 67th St, Philadelphia PA 19142						
E l e m e n t	F l o o r	On-Site Room Name	Component	Substrate Material [1]	Paint Color	Description of Paint Damage	Damage Quantity (sf) [2]	XRF Reading (mg/cm2)	XRF (positive/ negative) [3]
1	1	Classroom 119	W3	Plaster	White	Flaking	1	0	Negative
1	1	Classroom 119	Pipe Cover	Metal	White	Chipping	1	3.5	Positive
1	1	Classroom 119	Pipe Insulation	Asbestos	White	None	0	0.1	Negative
1	1	Classroom 119	Radiator cover	Metal	Brown	Chipping	3	0.8	Positive
1	1	Classroom 119	W4	Plaster	White	None	0	0.1	Negative
1	1	Classroom 119	Ceiling	Plaster	White	Flaking	20	0.2	Negative
1	1	Classroom 119	Ceiling	2'x4' Ceiling Tile	Not Painted	N/A	N/A	N/A	N/A
1	1	Classroom 119	Floor	Wood	Not Painted	N/A	N/A	N/A	N/A
1	1	Classroom 120	W1	Plaster	White/Pink	Cracking	4	0.6	Negative
1	1	Classroom 120	Doorframe	Metal	Brown	Chipping	6	1.1	Positive
1	1	Classroom 120	W2	Plaster	White/Pink	Chipping	2	0	Negative
1	1	Classroom 120	W3	Plaster	White/Pink	Cracking	10	0	Negative
1	1	Classroom 120	Pipe Cover	Metal	White/Pink	Chipping	5	4	Positive
1	1	Classroom 120	Pipe Insulation	Asbestos	White	None	0	0	Negative
1	1	Classroom 120	Radiator cover	Metal	Brown	Friction	2	0.9	Positive
1	1	Classroom 120	W4	Plaster	White/Pink	None	0	0	Negative
1	1	Classroom 119	Ceiling	Plaster	White	Flaking	140	0.2	Negative
1	1	Classroom 119	Ceiling	2'x4' Ceiling Tile	Not Painted	N/A	N/A	N/A	N/A
1	1	Classroom 120	Floor	Wood	Not Painted	N/A	N/A	N/A	N/A
1	1	Office 121B	W1	Plaster	Green	Chipping	1	0.5	Negative
1	1	Office 121B	Doorframe	Metal	Brown	Friction	2	0.9	Positive
1	1	Office 121B	W2	Plaster	Green	None	0	0.4	Negative
1	1	Office 121B	W3	Plaster	Green	None	0	0.1	Negative
1	1	Office 121B	Pipe Cover	Metal	Green	None	0	2.1	Positive
1	1	Office 121B	Pipe Insulation	Asbestos	White	None	0	0	Negative
1	1	Office 121B	Radiator cover	Metal	Brown	Chipping	8	0.9	Positive

		Dates: 6/5 - 7/6/2023	Lead-Safe Certification Assessment Report							
		Inspector Name and Certificate Number: Tim Smith 057662	John Bartram High School							
		Inspection Company: BATA	2401 S 67th St, Philadelphia PA 19142							
E l e m e n t	F l o o r	On-Site Room Name	Component	Substrate Material [1]	Paint Color	Description of Paint Damage	Damage Quantity (sf) [2]	XRF Reading (mg/cm2)	XRF (positive/ negative) [3]	
1	1	Office 121B	W4	Plaster	Green	None	0	0.1	Negative	
1	1	Office 121B	Chair Rail	Wood	Green	None	0	0.2	Negative	
1	1	Office 121B	Ceiling	Plaster	White	None	0	0.2	Negative	
1	1	Office 121B	Ceiling	2'x4' Ceiling Tile	Not Painted	N/A	N/A	N/A	N/A	
1	1	Office 121B	Floor	Wood	Not Painted	N/A	N/A	N/A	N/A	
1	1	Counselor's Office Suite 123	W1	Plaster	White	None	0	0	Negative	
1	1	Counselor's Office Suite 123	Doorframe	Metal	Brown	Friction	1	1.1	Positive	
1	1	Counselor's Office Suite 123	Covebase	Wood	Tan	Friction	16	0.1	Negative	
1	1	Counselor's Office Suite 123	W2	Plaster	White	Cracking	1	0	Negative	
1	1	Counselor's Office Suite 123	W3	Plaster	White	None	0	0	Negative	
1	1	Counselor's Office Suite 123	Pipe Cover	Metal	White	None	0	2.2	Positive	
1	1	Counselor's Office Suite 123	Pipe Insulation	Asbestos	White	None	0	0.1	Negative	
1	1	Counselor's Office Suite 123	Radiator cover	Metal	Brown	None	0	0	Negative	
1	1	Counselor's Office Suite 123	W4	Plaster	White	None	0	0	Negative	
1	1	Counselor's Office Suite 123	Conduit	Metal	White	None	0	0.7	Positive	
1	1	Counselor's Office Suite 123	Ceiling	Plaster	White	None	0	0.5	Negative	
1	1	Counselor's Office Suite 123	Ceiling	2'x4' Ceiling Tile	Not Painted	N/A	N/A	N/A	N/A	
1	1	Counselor's Office Suite 123	Floor	Wood	Not Painted	N/A	N/A	N/A	N/A	
1	1	Office in Health Suite	W1	Plaster	White	None	0	6.9	Positive	
1	1	Office in Health Suite	Doorframe	Metal	White	Friction	3	4.2	Positive	
1	1	Office in Health Suite	Door	Wood	White	Chipping	5	3.6	Positive	
1	1	Office in Health Suite	Chair Rail	Wood	Brown	None	0	4.5	Positive	
1	1	Office in Health Suite	W2	Plaster	White	None	0	8.3	Positive	
1	1	Office in Health Suite	W3	Plaster	White	None	0	5.3	Positive	
1	1	Office in Health Suite	Windowsill	Wood	White	Flaking	6	6.1	Positive	
1	1	Office in Health Suite	Pipe Cover	Metal	White	None	0	1.8	Positive	

		Dates: 6/5 - 7/6/2023	Lead-Safe Certification Assessment Report						
		Inspector Name and Certificate Number: Tim Smith 057662	John Bartram High School						
		Inspection Company: BATA	2401 S 67th St, Philadelphia PA 19142						
E l e m e n t	F l o o r	On-Site Room Name	Component	Substrate Material [1]	Paint Color	Description of Paint Damage	Damage Quantity (sf) [2]	XRF Reading (mg/cm2)	XRF (positive/ negative) [3]
1	1	Office in Health Suite	Pipe Insulation	Asbestos	White	None	0	9.7	Positive
1	1	Office in Health Suite	Radiator cover	Metal	Pink	Chipping	4	0.1	Negative
1	1	Office in Health Suite	W4	Plaster	White	Cracking	2	7.9	Positive
1	1	Office in Health Suite	Covebase	Wood	Brown	Friction	16	11.6	Positive
1	1	Office in Health Suite	Ceiling	Plaster	White	Cracking	30	12.1	Positive
1	1	Office in Health Suite	Ceiling	2'x4' Ceiling Tile	Not Painted	N/A	N/A	N/A	N/A
1	1	Office in Health Suite	Floor	Wood	Not Painted	N/A	N/A	N/A	N/A
1	1	Health Suite	W1	Plaster	White	None	0	8.4	Positive
1	1	Health Suite	Door	Wood	White	Chipping	2	4	Positive
1	1	Health Suite	Doorframe	Metal	White	Friction	1	3.8	Positive
1	1	Health Suite	Covebase	Wood	White	Friction	6	7.7	Positive
1	1	Health Suite	W2	Plaster	White	Cracking	3	8.2	Positive
1	1	Health Suite	W3	Plaster	White	None	0	8.2	Positive
1	1	Health Suite	Windowframe	Metal	White	Chipping	4	10.8	Positive
1	1	Health Suite	Radiator cover	Metal	Tan	Chipping	3	0	Negative
1	1	Health Suite	W4	Plaster	White	Cracking	1	0	Negative
1	1	Health Suite	Ceiling	Plaster	White	Flaking	60	8.1	Positive
1	1	Health Suite	Ceiling	2'x4' Ceiling Tile	Not Painted	N/A	N/A	N/A	N/A
1	1	Health Suite	Floor	Floor Tile	Not Painted	N/A	N/A	N/A	N/A
1	1	Office 124A, bathroom and Closet	W1	Plaster	White	Cracking	12	0	Negative
1	1	Office 124A, bathroom and Closet	Door	Wood	Tan	None	0	3.7	Positive
1	1	Office 124A, bathroom and Closet	Doorframe	Metal	Tan	Chipping	3	4.5	Positive
1	1	Office 124A, bathroom and Closet	W2	Plaster	White	Cracking	20	0.1	Negative
1	1	Office 124A, bathroom and Closet	Shelf	Wood	Tan	Chipping	2	4.2	Positive
1	1	Office 124A, bathroom and Closet	Windowframe	Metal	White	None	0	8.4	Positive
1	1	Office 124A, bathroom and Closet	W3	Plaster	White	None	0	0	Negative

		Dates: 6/5 - 7/6/2023	Lead-Safe Certification Assessment Report							
		Inspector Name and Certificate Number: Tim Smith 057662	John Bartram High School							
		Inspection Company: BATA	2401 S 67th St, Philadelphia PA 19142							
E l e m e n t	F l o o r	On-Site Room Name	Component	Substrate Material [1]	Paint Color	Description of Paint Damage	Damage Quantity (sf) [2]	XRF Reading (mg/cm2)	XRF (positive/ negative) [3]	
1	1	Office 124A, bathroom and Closet	W4	Plaster	White	Cracking	6	0.1	Negative	
1	1	Office 124A, bathroom and Closet	Ceiling	Plaster	White	Cracking	3	2.9	Positive	
1	1	Office 124A, bathroom and Closet	Floor	Floor Tile	Not Painted	N/A	N/A	N/A	N/A	
1	1	Closet in Health Suite	W1	No Access	No Access	No Access	No Access	No Access	No Access	
1	1	Closet in Health Suite	W2	No Access	No Access	No Access	No Access	No Access	No Access	
1	1	Closet in Health Suite	W3	No Access	No Access	No Access	No Access	No Access	No Access	
1	1	Closet in Health Suite	W4	No Access	No Access	No Access	No Access	No Access	No Access	
1	1	Closet in Health Suite	Ceiling	No Access	No Access	No Access	No Access	No Access	No Access	
1	1	Closet in Health Suite	Floor	No Access	No Access	No Access	No Access	No Access	No Access	
1	1	Office Bathroom in Health Suite	W1	No Access	No Access	No Access	No Access	No Access	No Access	
1	1	Office Bathroom in Health Suite	W2	No Access	No Access	No Access	No Access	No Access	No Access	
1	1	Office Bathroom in Health Suite	W3	No Access	No Access	No Access	No Access	No Access	No Access	
1	1	Office Bathroom in Health Suite	W4	No Access	No Access	No Access	No Access	No Access	No Access	
1	1	Office Bathroom in Health Suite	Ceiling	No Access	No Access	No Access	No Access	No Access	No Access	
1	1	Office Bathroom in Health Suite	Floor	No Access	No Access	No Access	No Access	No Access	No Access	
1	1	Office 125	W1	Plaster	White	None	0	0.2	Negative	
1	1	Office 125	Doorframe	Metal	Brown	None	0	0.1	Negative	
1	1	Office 125	W2	Plaster	White	None	0	0.5	Negative	
1	1	Office 125	Conduit	Plastic	White	None	0	0.5	Negative	
1	1	Office 125	W3	Plaster	White	None	0	0.1	Negative	
1	1	Office 125	Pipe Cover	Metal	White	None	0	1.4	Positive	
1	1	Office 125	Pipe Insulation	Asbestos	White	None	0	0.1	Negative	
1	1	Office 125	W4	Plaster	White	Cracking	2	0.2	Negative	
1	1	Office 125	Radiator cover	Metal	Brown	None	0	0.4	Negative	
1	1	Office 125	Ceiling	Plaster	White	None	0	0	Negative	
1	1	Office 125	Ceiling	2'x4' Ceiling Tile	Not Painted	N/A	N/A	N/A	N/A	

		Dates: 6/5 - 7/6/2023	Lead-Safe Certification Assessment Report							
		Inspector Name and Certificate Number: Tim Smith 057662	John Bartram High School							
		Inspection Company: BATA	2401 S 67th St, Philadelphia PA 19142							
E l e m e n t	F l o o r	On-Site Room Name	Component	Substrate Material [1]	Paint Color	Description of Paint Damage	Damage Quantity (sf) [2]	XRF Reading (mg/cm2)	XRF (positive/ negative) [3]	
1	1	Office 125	Floor	Floor Tile	Not Painted	N/A	N/A	N/A	N/A	
1	1	Mail Office 126	W1	Plaster	White/Pink	Cracking	6	11.4	Positive	
1	1	Mail Office 126	Doorframe	Metal	Brown	Friction	4	0.9	Positive	
1	1	Mail Office 126	W2	Plaster	White/Pink	Cracking	20	0.4	Negative	
1	1	Mail Office 126	Conduit	Plastic	White/Pink	None	0	0.2	Negative	
1	1	Mail Office 126	W3	Plaster	White/Pink	Cracking	6	11.9	Positive	
1	1	Mail Office 126	Radiator cover	Metal	Brown	Chipping	2	0.3	Negative	
1	1	Mail Office 126	W4	Plaster	White/Pink	Flaking	10	0	Negative	
1	1	Mail Office 126	Ceiling	Plaster	White	None	0	8.6	Positive	
1	1	Mail Office 126	Ceiling	2'x4' Ceiling Tile	Not Painted	N/A	N/A	N/A	N/A	
1	1	Mail Office 126	Floor	Floor Tile	Not Painted	N/A	N/A	N/A	N/A	
1	1	Office inside/adjacent to Mail Room	W1	Plaster	White	None	0	0.5	Negative	
1	1	Office inside/adjacent to Mail Room	Conduit	Plastic	White	None	0	0.2	Negative	
1	1	Office inside/adjacent to Mail Room	Doorframe	Metal	Brown	Friction	3	0.5	Negative	
1	1	Office inside/adjacent to Mail Room	W2	Plaster	White	Cracking	6	0.1	Negative	
1	1	Office inside/adjacent to Mail Room	W3	Plaster	White	Flaking	30	0.1	Negative	
1	1	Office inside/adjacent to Mail Room	W4	Plaster	White	None	0	0.1	Negative	
1	1	Office inside/adjacent to Mail Room	Pipe	Metal	White	None	0	23.8	Positive	
1	1	Office inside/adjacent to Mail Room	Pipe Cover	Metal	White	None	0	5.3	Positive	
1	1	Office inside/adjacent to Mail Room	Pipe Insulation	Asbestos	White	None	0	11.4	Positive	
1	1	Office inside/adjacent to Mail Room	Windowframe	Wood	White	None	0	5.9	Positive	
1	1	Office inside/adjacent to Mail Room	Covebase	Wood	Pink	None	0	0	Negative	
1	1	Office inside/adjacent to Mail Room	Radiator cover	Metal	Brown	None	0	0.1	Negative	
1	1	Office inside/adjacent to Mail Room	Ceiling	Plaster	White	Flaking	60	5.8	Positive	
1	1	Office inside/adjacent to Mail Room	Ceiling	2'x4' Ceiling Tile	Not Painted	N/A	N/A	N/A	N/A	
1	1	Office inside/adjacent to Mail Room	Floor	Floor Tile	Not Painted	N/A	N/A	N/A	N/A	

		Dates: 6/5 - 7/6/2023	Lead-Safe Certification Assessment Report						
		Inspector Name and Certificate Number: Tim Smith 057662	John Bartram High School						
		Inspection Company: BATA	2401 S 67th St, Philadelphia PA 19142						
Element	Floor	On-Site Room Name	Component	Substrate Material [1]	Paint Color	Description of Paint Damage	Damage Quantity (sf) [2]	XRF Reading (mg/cm2)	XRF (positive/negative) [3]
1	1	127 Conference Room	W1	Plaster	White	Cracking	8	0	Negative
1	1	127 Conference Room	Conduit	Metal	White	None	0	0.2	Negative
1	1	127 Conference Room	Doorframe	Metal	Brown	Friction	3	0.7	Positive
1	1	127 Conference Room	W2	Plaster	White	None	0	0	Negative
1	1	127 Conference Room	Radiator cover	Metal	Brown	None	0	0.6	Negative
1	1	127 Conference Room	Pipe	Metal	White	None	0	0.4	Negative
1	1	127 Conference Room	Pipe Cover	Metal	White	None	0	1.6	Positive
1	1	127 Conference Room	Pipe Insulation	Asbestos	White	None	0	0	Negative
1	1	127 Conference Room	W3	Plaster	White	None	0	0	Negative
1	1	127 Conference Room	W4	Plaster	White	None	0	0.1	Negative
1	1	127 Conference Room	Ceiling	Plaster	White	None	0	0.2	Negative
1	1	127 Conference Room	Ceiling	2'x4' Ceiling Tile	Not Painted	N/A	N/A	N/A	N/A
1	1	127 Conference Room	Floor	Floor Tile	Not Painted	N/A	N/A	N/A	N/A
1	1	127 Conference Room - Restroom	W1	Drywall	White	None	0	0.1	Negative
1	1	127 Conference Room - Restroom	Doorframe	Metal	Brown	None	0	0.1	Negative
1	1	127 Conference Room - Restroom	W2	Plaster	White	None	0	0	Negative
1	1	127 Conference Room - Restroom	Pipe	Metal	White	None	0	0.6	Negative
1	1	127 Conference Room - Restroom	W3	Drywall	White	None	0	0.1	Negative
1	1	127 Conference Room - Restroom	W4	Drywall	White	None	0	0.1	Negative
1	1	127 Conference Room - Restroom	Ceiling	Plaster	White	Flaking	10	0.1	Negative
1	1	127 Conference Room - Restroom	Floor	Floor Tile	Not Painted	N/A	N/A	N/A	N/A
1	1	Office 127B	W1	Plaster	Blue	None	0	0	Negative
1	1	Office 127B	Doorframe	Metal	Brown	Friction	3	0.9	Positive
1	1	Office 127B	W2	Drywall	Blue	None	0	0.1	Negative
1	1	Office 127B	W3	Plaster	Blue	None	0	0.3	Negative
1	1	Office 127B	Pipe Cover	Metal	Blue	None	0	1.5	Positive

		Dates: 6/5 - 7/6/2023	Lead-Safe Certification Assessment Report						
		Inspector Name and Certificate Number: Tim Smith 057662	John Bartram High School						
		Inspection Company: BATA	2401 S 67th St, Philadelphia PA 19142						
E l e m e n t	F l o o r	On-Site Room Name	Component	Substrate Material [1]	Paint Color	Description of Paint Damage	Damage Quantity (sf) [2]	XRF Reading (mg/cm2)	XRF (positive/ negative) [3]
1	1	Office 127B	Pipe Insulation	Asbestos	Blue	None	0	0.1	Negative
1	1	Office 127B	Chair Rail	Wood	Brown	Chipping	1	0.5	Negative
1	1	Office 127B	Radiator cover	Metal	Brown	None	0	0.5	Negative
1	1	Office 127B	Pipe	Metal	Blue	None	0	0.4	Negative
1	1	Office 127B	W4	Plaster	Blue	None	0	0.5	Negative
1	1	Office 127B	Ceiling	Plaster	White	None	0	0.3	Negative
1	1	Office 127B	Ceiling	2'x4' Ceiling Tile	Not Painted	N/A	N/A	N/A	N/A
1	1	Office 127B	Floor	Floor Tile	Not Painted	N/A	N/A	N/A	N/A
1	1	Kitchen in Office 127B	W1	Plaster	White	None	0	0	Negative
1	1	Kitchen in Office 127B	Doorframe	Metal	Brown	Friction	2	0.9	Positive
1	1	Kitchen in Office 127B	W2	Plaster	White	None	0	0	Negative
1	1	Kitchen in Office 127B	Covebase	Ceramic	Brown	Friction	6	0.2	Negative
1	1	Kitchen in Office 127B	Radiator	Metal	Brown	None	0	0.1	Negative
1	1	Kitchen in Office 127B	W3	Plaster	White	None	0	0	Negative
1	1	Kitchen in Office 127B	W4	Plaster	White	None	0	0.4	Negative
1	1	Kitchen in Office 127B	Ceiling	Plaster	White	None	0	0.2	Negative
1	1	Kitchen in Office 127B	Ceiling	2'x4' Ceiling Tile	Not Painted	N/A	N/A	N/A	N/A
1	1	Kitchen in Office 127B	Floor	Floor Tile	Not Painted	N/A	N/A	N/A	N/A
1	1	Foyer to Office 128	W1	Plaster	White	None	0	0.3	Negative
1	1	Foyer to Office 128	Doorframe	Metal	Brown	Friction	2	0.5	Negative
1	1	Foyer to Office 128	W2	Plaster	White	None	0	5.7	Positive
1	1	Foyer to Office 128	Conduit	Plastic	White	None	0	0.3	Negative
1	1	Foyer to Office 128	W3	Plaster	White	Flaking	14	0	Negative
1	1	Foyer to Office 128	W4	Plaster	White	Cracking	2	0.5	Negative
1	1	Foyer to Office 128	Covebase	Wood	Brown	Friction	8	0.2	Negative
1	1	Foyer to Office 128	Ceiling	Plaster	White	None	0	6.6	Positive

		Dates: 6/5 - 7/6/2023	Lead-Safe Certification Assessment Report						
		Inspector Name and Certificate Number: Tim Smith 057662	John Bartram High School						
		Inspection Company: BATA	2401 S 67th St, Philadelphia PA 19142						
E l e m e n t	F l o o r	On-Site Room Name	Component	Substrate Material [1]	Paint Color	Description of Paint Damage	Damage Quantity (sf) [2]	XRF Reading (mg/cm2)	XRF (positive/ negative) [3]
1	1	Foyer to Office 128	Ceiling	2'x4' Ceiling Tile	Not Painted	N/A	N/A	N/A	N/A
1	1	Foyer to Office 128	Floor	Floor Tile	Not Painted	N/A	N/A	N/A	N/A
1	1	Office 128	W1	Plaster	White	Flaking	8	0	Negative
1	1	Office 128	Doorframe	Metal	Brown	Friction	6	0.4	Negative
1	1	Office 128	Conduit	Plastic	White	None	0	0.3	Negative
1	1	Office 128	Covebase	Wood	Brown	Chipping	6	0.3	Negative
1	1	Office 128	W2	Plaster	White	Chipping	1	0	Negative
1	1	Office 128	W3	Plaster	White	None	0	13.2	Positive
1	1	Office 128	Radiator cover	Metal	Brown	None	0	0.2	Negative
1	1	Office 128	Pipe Cover	Metal	White	None	0	6.9	Positive
1	1	Office 128	Pipe Insulation	Asbestos	White	None	0	6.2	Positive
1	1	Office 128	W4	Plaster	White	Flaking	2	0	Negative
1	1	Office 128	Ceiling	Plaster	White	None	0	5.4	Positive
1	1	Office 128	Ceiling	2'x4' Ceiling Tile	Not Painted	N/A	N/A	N/A	N/A
1	1	Office 128	Floor	Floor Tile	Not Painted	N/A	N/A	N/A	N/A
1	1	Principal's Office	W1	Plaster	White	None	0	0.1	Negative
1	1	Principal's Office	Doorframe	Metal	Blue	Chipping	3	0.3	Negative
1	1	Principal's Office	Door	Wood	Blue	Chipping	1	2.7	Positive
1	1	Principal's Office	W2	Plaster	White	None	0	0.1	Negative
1	1	Principal's Office	W3	Plaster	White	None	0	0.1	Negative
1	1	Principal's Office	Windowframe	Wood	Blue	None	0	2	Positive
1	1	Principal's Office	Covebase	Wood	Blue	Chipping	4	4.6	Positive
1	1	Principal's Office	W4	Plaster	White	None	0	0.2	Negative
1	1	Principal's Office	Ceiling	Plaster	White	None	0	0.2	Negative
1	1	Principal's Office	Ceiling	2'x4' Ceiling Tile	Not Painted	N/A	N/A	N/A	N/A
1	1	Principal's Office	Crown Molding	Wood	Blue	None	0	3.8	Positive

		Dates: 6/5 - 7/6/2023	Lead-Safe Certification Assessment Report						
		Inspector Name and Certificate Number: Tim Smith 057662	John Bartram High School						
		Inspection Company: BATA	2401 S 67th St, Philadelphia PA 19142						
Element	Floor	On-Site Room Name	Component	Substrate Material [1]	Paint Color	Description of Paint Damage	Damage Quantity (sf) [2]	XRF Reading (mg/cm ²)	XRF (positive/negative) [3]
1	1	Principal's Office	Floor	Floor Tile	Not Painted	N/A	N/A	N/A	N/A
1	1	130A Storage Room next to Main Office	W1	Plaster	White	None	0	6.8	Positive
1	1	130A Storage Room next to Main Office	Doorframe	Metal	Brown	Friction	1	0.9	Positive
1	1	130A Storage Room next to Main Office	W2	Plaster	White	None	0	8.5	Positive
1	1	130A Storage Room next to Main Office	W3	Plaster	White	None	0	7.4	Positive
1	1	130A Storage Room next to Main Office	Conduit	Plastic	White	None	0	0.3	Negative
1	1	130A Storage Room next to Main Office	Pipe Cover	Metal	White	None	0	3.6	Positive
1	1	130A Storage Room next to Main Office	Pipe Insulation	Asbestos	White	None	0	10.4	Positive
1	1	130A Storage Room next to Main Office	Radiator cover	Metal	Tan	Chipping	6	0.4	Negative
1	1	130A Storage Room next to Main Office	Covebase	Wood	Brown	None	0	0.2	Negative
1	1	130A Storage Room next to Main Office	W4	Plaster	White	None	0	12.1	Positive
1	1	130A Storage Room next to Main Office	Ceiling	Plaster	White	None	0	4.9	Positive
1	1	130A Storage Room next to Main Office	Ceiling	2'x4' Ceiling Tile	Not Painted	N/A	N/A	N/A	N/A
1	1	130A Storage Room next to Main Office	Floor	Floor Tile	Not Painted	N/A	N/A	N/A	N/A
1	1	Bathroom in 130A Storage Room next to Main Office	W1	Plaster	White	None	0	2.5	Positive
1	1	Bathroom in 130A Storage Room next to Main Office	Doorframe	Metal	Brown	Friction	2	1.1	Positive
1	1	Bathroom in 130A Storage Room next to Main Office	W2	Plaster	White	Cracking	3	7.3	Positive
1	1	Bathroom in 130A Storage Room next to Main Office	W3	Plaster	White	Cracking	4	7.1	Positive
1	1	Bathroom in 130A Storage Room next to Main Office	W4	Plaster	White	Cracking	6	3.2	Positive
1	1	Bathroom in 130A Storage Room next to Main Office	Ceiling	Plaster	White	Cracking	2	8.7	Positive
1	1	Bathroom in 130A Storage Room next to Main Office	Floor	Floor Tile	Not Painted	N/A	N/A	N/A	N/A
1	1	Foyer to Office 130	W1	Plaster	Pink	None	0	12.2	Positive
1	1	Foyer to Office 130	Doorframe	Metal	Brown	None	0	0.8	Positive
1	1	Foyer to Office 130	Conduit	Plaster	Pink	None	0	1	Positive
1	1	Foyer to Office 130	Covebase	Wood	Brown	Chipping	24	0.2	Negative
1	1	Foyer to Office 130	W2	Plaster	Pink	None	0	0.5	Negative

		Dates: 6/5 - 7/6/2023	Lead-Safe Certification Assessment Report							
		Inspector Name and Certificate Number: Tim Smith 057662	John Bartram High School							
		Inspection Company: BATA	2401 S 67th St, Philadelphia PA 19142							
E l e m e n t	F l o o r	On-Site Room Name	Component	Substrate Material [1]	Paint Color	Description of Paint Damage	Damage Quantity (sf) [2]	XRF Reading (mg/cm2)	XRF (positive/ negative) [3]	
1	1	Foyer to Office 130	W3	Plaster	Pink	None	0	0.1	Negative	
1	1	Foyer to Office 130	W4	Plaster	Pink	None	0	0.1	Negative	
1	1	Foyer to Office 130	Ceiling	Plaster	White	None	0	5.4	Positive	
1	1	Foyer to Office 130	Ceiling	2'x4' Ceiling Tile	Not Painted	N/A	N/A	N/A	N/A	
1	1	Foyer to Office 130	Floor	Floor Tile	Not Painted	N/A	N/A	N/A	N/A	
1	1	Office 130	W1	Plaster	White	None	0	0	Negative	
1	1	Office 130	Conduit	Plastic	White	None	0	0.1	Negative	
1	1	Office 130	Doorframe	Metal	Brown	Friction	3	0.1	Negative	
1	1	Office 130	W2	Plaster	White	None	0	0	Negative	
1	1	Office 130	W3	Plaster	White	None	0	7.9	Positive	
1	1	Office 130	Conduit	Metal	White	None	0	0.6	Negative	
1	1	Office 130	Pipe Cover	Metal	White	None	0	6	Positive	
1	1	Office 130	Pipe Insulation	Asbestos	White	None	0	5.8	Positive	
1	1	Office 130	Radiator cover	Metal	Brown	Chipping	1	0.4	Negative	
1	1	Office 130	W4	Plaster	White	None	0	0.1	Negative	
1	1	Office 130	Ceiling	Plaster	White	None	0	5.4	Positive	
1	1	Office 130	Ceiling	2'x4' Ceiling Tile	Not Painted	N/A	N/A	N/A	N/A	
1	1	Office 130	Floor	Floor Tile	Not Painted	N/A	N/A	N/A	N/A	
1	1	Office 131	W1	Plaster	White	None	0	0.1	Negative	
1	1	Office 131	Conduit	Plastic	White	None	0	0.5	Negative	
1	1	Office 131	Doorframe	Metal	Brown	Chipping	2	0.8	Positive	
1	1	Office 131	W2	Plaster	White	None	0	0.5	Negative	
1	1	Office 131	W3	Plaster	White	None	0	0	Negative	
1	1	Office 131	Pipe Cover	Metal	White	Chipping	1	3.4	Positive	
1	1	Office 131	Pipe Insulation	Asbestos	White	None	0	0.2	Negative	
1	1	Office 131	Radiator cover	Metal	Brown	Chipping	3	1.2	Positive	

		Dates: 6/5 - 7/6/2023	Lead-Safe Certification Assessment Report							
		Inspector Name and Certificate Number: Tim Smith 057662	John Bartram High School							
		Inspection Company: BATA	2401 S 67th St, Philadelphia PA 19142							
E l e m e n t	F l o o r	On-Site Room Name	Component	Substrate Material [1]	Paint Color	Description of Paint Damage	Damage Quantity (sf) [2]	XRF Reading (mg/cm2)	XRF (positive/ negative) [3]	
1	1	Office 131	W4	Plaster	White	None	0	0	Negative	
1	1	Office 131	Ceiling	Plaster	White	None	0	0.5	Negative	
1	1	Office 131	Ceiling	2'x4' Ceiling Tile	Not Painted	N/A	N/A	N/A	N/A	
1	1	Office 131	Floor	Floor Tile	Not Painted	N/A	N/A	N/A	N/A	
1	1	Storage closet next to Office 131	W1	Plaster	White	None	0	0	Negative	
1	1	Storage closet next to Office 131	Doorframe	Metal	Brown	Friction	2	0.8	Positive	
1	1	Storage closet next to Office 131	W2	Plaster	White	None	0	0.6	Negative	
1	1	Storage closet next to Office 131	W3	Plaster	White	Cracking	20	0	Negative	
1	1	Storage closet next to Office 131	W4	Plaster	White	Cracking	30	0.2	Negative	
1	1	Storage closet next to Office 131	Ceiling	Plaster	White	Cracking	3	0.1	Negative	
1	1	Storage closet next to Office 131	Floor	Concrete	Not Painted	N/A	N/A	N/A	N/A	
1	1	Office 133	W1	Plaster	White	None	0	0	Negative	
1	1	Office 133	Door	Wood	Red	Friction	3	0	Negative	
1	1	Office 133	Doorframe	Metal	Brown	Friction	6	1	Positive	
1	1	Office 133	W2	Plaster	White	Flaking	2	0.1	Negative	
1	1	Office 133	Pipe Cover	Metal	White	None	0	0.3	Negative	
1	1	Office 133	Pipe Insulation	Asbestos	White	None	0	0.1	Negative	
1	1	Office 133	W3	Plaster	White	None	0	0.1	Negative	
1	1	Office 133	Conduit	Plastic	White	None	0	0.1	Negative	
1	1	Office 133	Radiator cover	Metal	Brown	Chipping	6	0.9	Positive	
1	1	Office 133	W4	Plaster	White	Cracking	8	0.1	Negative	
1	1	Office 133	Ceiling	Plaster	White	None	0	0.4	Negative	
1	1	Office 133	Ceiling	2'x4' Ceiling Tile	Not Painted	N/A	N/A	N/A	N/A	
1	1	Office 133	Floor	Wood	Black	Friction	60	0.1	Negative	
1	1	Boy's Restroom	W1	Ceramic	White	None	0	0	Negative	
1	1	Boy's Restroom	Doorframe	Metal	Brown	Chipping	4	0.6	Negative	

		Dates: 6/5 - 7/6/2023	Lead-Safe Certification Assessment Report							
		Inspector Name and Certificate Number: Tim Smith 057662	John Bartram High School							
		Inspection Company: BATA	2401 S 67th St, Philadelphia PA 19142							
E l e m e n t	F l o o r	On-Site Room Name	Component	Substrate Material [1]	Paint Color	Description of Paint Damage	Damage Quantity (sf) [2]	XRF Reading (mg/cm2)	XRF (positive/ negative) [3]	
1	1	Boy's Restroom	Door	Wood	Red	None	0	0	Negative	
1	1	Boy's Restroom	W2	Ceramic	White	None	0	0	Negative	
1	1	Boy's Restroom	Pipe Cover	Metal	Brown	None	0	0.6	Negative	
1	1	Boy's Restroom	Pipe Insulation	Asbestos	White	None	0	0	Negative	
1	1	Boy's Restroom	W3	Ceramic	White	None	0	0	Negative	
1	1	Boy's Restroom	Radiator cover	Metal	Brown	Chipping	12	0	Negative	
1	1	Boy's Restroom	W4	Ceramic	White	None	0	0	Negative	
1	1	Boy's Restroom	Stall	Metal	Green	Chipping	8	0.1	Negative	
1	1	Boy's Restroom	Ceiling	Plaster	White	None	0	0.1	Negative	
1	1	Boy's Restroom	Floor	Terrazzo	Not Painted	N/A	N/A	N/A	N/A	
1	1	Main Office	W1	Plaster	White	None	0	7.5	Positive	
1	1	Main Office	Covebase	Wood	Brown	Friction	30	0.1	Negative	
1	1	Main Office	Doorframe	Metal	Brown	None	0	0.6	Negative	
1	1	Main Office	W2	Plaster	White	None	0	0	Negative	
1	1	Main Office	W3	Plaster	White	None	0	3.8	Positive	
1	1	Main Office	Pipe Cover	Metal	White	None	0	5.5	Positive	
1	1	Main Office	Pipe Insulation	Asbestos	White	None	0	9.1	Positive	
1	1	Main Office	Conduit	Plastic	White	None	0	0.5	Negative	
1	1	Main Office	Cabinet	Metal	Purple	Friction	20	0.2	Negative	
1	1	Main Office	Windowsill	Wood	Brown	Cracking	24	0.2	Negative	
1	1	Main Office	Radiator cover	Metal	Brown	Chipping	4	0.5	Negative	
1	1	Main Office	W4	Plaster	White	None	0	0.1	Negative	
1	1	Main Office	Conduit	Metal	White	None	0	0.1	Negative	
1	1	Main Office	Ceiling	Plaster	White	None	0	6	Positive	
1	1	Main Office	Ceiling	2'x4' Ceiling Tile	Not Painted	N/A	N/A	N/A	N/A	
1	1	Main Office	Floor	Floor Tile	Not Painted	N/A	N/A	N/A	N/A	

		Dates: 6/5 - 7/6/2023	Lead-Safe Certification Assessment Report						
		Inspector Name and Certificate Number: Tim Smith 057662	John Bartram High School						
		Inspection Company: BATA	2401 S 67th St, Philadelphia PA 19142						
Element	Floor	On-Site Room Name	Component	Substrate Material [1]	Paint Color	Description of Paint Damage	Damage Quantity (sf) [2]	XRF Reading (mg/cm2)	XRF (positive/negative) [3]
1	1	Room labeled Assistant to Principal Office/Small mail room	W1	Plaster	White	Flaking	6	0	Negative
1	1	Room labeled Assistant to Principal Office/Small mail room	Conduit	Plastic	White	None	0	0.5	Negative
1	1	Room labeled Assistant to Principal Office/Small mail room	Door	Wood	Brown	Chipping	6	3.9	Positive
1	1	Room labeled Assistant to Principal Office/Small mail room	Doorframe	Metal	Brown	None	0	0.4	Negative
1	1	Room labeled Assistant to Principal Office/Small mail room	Chair Rail	Wood	Brown	None	0	0.1	Negative
1	1	Room labeled Assistant to Principal Office/Small mail room	W2	Plaster	White	None	0	0	Negative
1	1	Room labeled Assistant to Principal Office/Small mail room	Covebase	Wood	Brown	None	0	0.2	Negative
1	1	Room labeled Assistant to Principal Office/Small mail room	W3	Plaster	White	None	0	5.4	Positive
1	1	Room labeled Assistant to Principal Office/Small mail room	W4	Plaster	White	None	0	4.8	Positive
1	1	Room labeled Assistant to Principal Office/Small mail room	Pipe Cover	Metal	White	None	0	3.9	Positive
1	1	Room labeled Assistant to Principal Office/Small mail room	Pipe Insulation	Asbestos	White	Chipping	1	4	Positive
1	1	Room labeled Assistant to Principal Office/Small mail room	Ceiling	Concrete	Not Painted	N/A	N/A	N/A	N/A
1	1	Room labeled Assistant to Principal Office/Small mail room	Ceiling	2'x4' Ceiling Tile	Not Painted	N/A	N/A	N/A	N/A
1	1	Room labeled Assistant to Principal Office/Small mail room	Floor	Floor Tile	Not Painted	N/A	N/A	N/A	N/A
1	1	Copy Room in Main Office	W1	Plaster	White	None	0	0	Negative
1	1	Copy Room in Main Office	Doorframe	Metal	Brown	Friction	2	0.5	Negative

		Dates: 6/5 - 7/6/2023	Lead-Safe Certification Assessment Report							
		Inspector Name and Certificate Number: Tim Smith 057662	John Bartram High School							
		Inspection Company: BATA	2401 S 67th St, Philadelphia PA 19142							
E l e m e n t	F l o o r	On-Site Room Name	Component	Substrate Material [1]	Paint Color	Description of Paint Damage	Damage Quantity (sf) [2]	XRF Reading (mg/cm2)	XRF (positive/ negative) [3]	
1	1	Copy Room in Main Office	Conduit	Metal	White	None	0	7.3	Positive	
1	1	Copy Room in Main Office	W2	Plaster	White	Flaking	1	4.4	Positive	
1	1	Copy Room in Main Office	W3	Plaster	White	No Access	No Access	No Access	No Access	
1	1	Copy Room in Main Office	W4	Plaster	White	None	0	0.1	Negative	
1	1	Copy Room in Main Office	Ceiling	No Access	No Access	No Access	No Access	No Access	No Access	
1	1	Copy Room in Main Office	Floor	Floor Tile	Not Painted	N/A	N/A	N/A	N/A	
1	1	Main Office Restroom	W1	Plaster	Green	None	0	1.8	Positive	
1	1	Main Office Restroom	Doorframe	Metal	Brown	Friction	4	1	Positive	
1	1	Main Office Restroom	W2	Plaster	Green	None	0	6.7	Positive	
1	1	Main Office Restroom	W3	Plaster	Green	None	0	3.7	Positive	
1	1	Main Office Restroom	W4	Plaster	Green	None	0	5.7	Positive	
1	1	Main Office Restroom	Ceiling	Plaster	White	None	0	2.4	Positive	
1	1	Main Office Restroom	Floor	Terrazzo	Not Painted	N/A	N/A	N/A	N/A	
1	1	Closet adjacent to Main Office Powder Room	W1	No Access	No Access	No Access	No Access	No Access	No Access	
1	1	Closet adjacent to Main Office Powder Room	W2	No Access	No Access	No Access	No Access	No Access	No Access	
1	1	Closet adjacent to Main Office Powder Room	W3	No Access	No Access	No Access	No Access	No Access	No Access	
1	1	Closet adjacent to Main Office Powder Room	W4	No Access	No Access	No Access	No Access	No Access	No Access	
1	1	Closet adjacent to Main Office Powder Room	Ceiling	No Access	No Access	No Access	No Access	No Access	No Access	
1	1	Closet adjacent to Main Office Powder Room	Floor	No Access	No Access	No Access	No Access	No Access	No Access	
1	1	Main Office MDF Room	W1	No Access	No Access	No Access	No Access	No Access	No Access	
1	1	Main Office MDF Room	W2	No Access	No Access	No Access	No Access	No Access	No Access	
1	1	Main Office MDF Room	W3	No Access	No Access	No Access	No Access	No Access	No Access	
1	1	Main Office MDF Room	W4	No Access	No Access	No Access	No Access	No Access	No Access	
1	1	Main Office MDF Room	Ceiling	No Access	No Access	No Access	No Access	No Access	No Access	
1	1	Main Office MDF Room	Floor	No Access	No Access	No Access	No Access	No Access	No Access	
1	1	Main Office Lounge adjacent to MDF	W1	Plaster	White	None	0	0	Negative	

		Dates: 6/5 - 7/6/2023	Lead-Safe Certification Assessment Report							
		Inspector Name and Certificate Number: Tim Smith 057662	John Bartram High School							
		Inspection Company: BATA	2401 S 67th St, Philadelphia PA 19142							
E l e m e n t	F l o o r	On-Site Room Name	Component	Substrate Material [1]	Paint Color	Description of Paint Damage	Damage Quantity (sf) [2]	XRF Reading (mg/cm2)	XRF (positive/ negative) [3]	
1	1	Main Office Lounge adjacent to MDF	Doorframe	Metal	Brown	Friction	2	0.5	Negative	
1	1	Main Office Lounge adjacent to MDF	W2	Plaster	White	None	0	12.6	Positive	
1	1	Main Office Lounge adjacent to MDF	Conduit	Plastic	White	None	0	0.1	Negative	
1	1	Main Office Lounge adjacent to MDF	W3	Plaster	White	None	0	15	Positive	
1	1	Main Office Lounge adjacent to MDF	Pipe Cover	Metal	White	None	0	6.1	Positive	
1	1	Main Office Lounge adjacent to MDF	Pipe Insulation	Asbestos	White	None	0	10.5	Positive	
1	1	Main Office Lounge adjacent to MDF	Radiator cover	Metal	Brown	Chipping	2	0.6	Negative	
1	1	Main Office Lounge adjacent to MDF	W4	Plaster	White	None	0	15.1	Positive	
1	1	Main Office Lounge adjacent to MDF	Ceiling	Plaster	White	None	0	8.8	Positive	
1	1	Main Office Lounge adjacent to MDF	Ceiling	2'x4' Ceiling Tile	Not Painted	N/A	N/A	N/A	N/A	
1	1	Main Office Lounge adjacent to MDF	Floor	Concrete	blue	None	0	5.6	Positive	
1	1	Boy's Gymnasium	W1	Brick	Not Painted	N/A	N/A	N/A	N/A	
1	1	Boy's Gymnasium	Door	Wood	Red	Friction	10	0	Negative	
1	1	Boy's Gymnasium	Doorframe	Metal	Red	Friction	18	0.9	Positive	
1	1	Boy's Gymnasium	W2	Brick	Not Painted	N/A	N/A	N/A	N/A	
1	1	Boy's Gymnasium	W3	Brick	Not Painted	N/A	N/A	N/A	N/A	
1	1	Boy's Gymnasium	Radiator cover	Metal	White	Chipping	2	1.7	Positive	
1	1	Boy's Gymnasium	W4	Brick	Not Painted	N/A	N/A	N/A	N/A	
1	1	Boy's Gymnasium	Ceiling	Plaster	White	No Access	No Access	No Access	No Access	
1	1	Boy's Gymnasium	Floor	Wood	Not Painted	N/A	N/A	N/A	N/A	
1	1	Caged Storage Room inside the Boy's Gymnasium - Corner of Building	W1	Brick	Not Painted	N/A	N/A	N/A	N/A	
1	1	Caged Storage Room inside the Boy's Gymnasium - Corner of Building	W2	Brick	Not Painted	N/A	N/A	N/A	N/A	
1	1	Caged Storage Room inside the Boy's Gymnasium - Corner of Building	Pipe Insulation	Asbestos	Pink	None	0	0.2	Negative	

		Dates: 6/5 - 7/6/2023	Lead-Safe Certification Assessment Report							
		Inspector Name and Certificate Number: Tim Smith 057662	John Bartram High School							
		Inspection Company: BATA	2401 S 67th St, Philadelphia PA 19142							
E l e m e n t	F l o o r	On-Site Room Name	Component	Substrate Material [1]	Paint Color	Description of Paint Damage	Damage Quantity (sf) [2]	XRF Reading (mg/cm ²)	XRF (positive/ negative) [3]	
1	1	Caged Storage Room inside the Boy's Gymnasium - Corner of Building	W3	Brick	Not Painted	N/A	N/A	N/A	N/A	
1	1	Caged Storage Room inside the Boy's Gymnasium - Corner of Building	W4	Brick	Not Painted	N/A	N/A	N/A	N/A	
1	1	Caged Storage Room inside the Boy's Gymnasium - Corner of Building	Ceiling	Plaster	White	None	0	0.6	Negative	
1	1	Caged Storage Room inside the Boy's Gymnasium - Corner of Building	Floor	Wood	Not Painted	N/A	N/A	N/A	N/A	
1	1	Office inside Boy's Gymnasium	W1	No Access	No Access	No Access	No Access	No Access	No Access	
1	1	Office inside Boy's Gymnasium	W2	No Access	No Access	No Access	No Access	No Access	No Access	
1	1	Office inside Boy's Gymnasium	W3	No Access	No Access	No Access	No Access	No Access	No Access	
1	1	Office inside Boy's Gymnasium	W4	No Access	No Access	No Access	No Access	No Access	No Access	
1	1	Office inside Boy's Gymnasium	Ceiling	No Access	No Access	No Access	No Access	No Access	No Access	
1	1	Office inside Boy's Gymnasium	Floor	No Access	No Access	No Access	No Access	No Access	No Access	
1	1	Stairs next to Caged Storage Room inside the Boy's Gymnasium (to Bsmt Boys Locker Room)	W1	Plaster	White	None	0	0.1	Negative	
1	1	Stairs next to Caged Storage Room inside the Boy's Gymnasium (to Bsmt Boys Locker Room)	Doorframe	Metal	Brown	Friction	4	0.7	Positive	
1	1	Stairs next to Caged Storage Room inside the Boy's Gymnasium (to Bsmt Boys Locker Room)	Pipe Insulation	Asbestos	White	None	0	0.1	Negative	
1	1	Stairs next to Caged Storage Room inside the Boy's Gymnasium (to Bsmt Boys Locker Room)	W2	Plaster	White	Cracking	6	0.4	Negative	
1	1	Stairs next to Caged Storage Room inside the Boy's Gymnasium (to Bsmt Boys Locker Room)	W3	Plaster	White	None	0	0	Negative	
1	1	Stairs next to Caged Storage Room inside the Boy's Gymnasium (to Bsmt Boys Locker Room)	W4	Plaster	White	Cracking	3	0.1	Negative	
1	1	Stairs next to Caged Storage Room inside the Boy's Gymnasium (to Bsmt Boys Locker Room)	Covebase	Concrete	Brown	None	0	0	Negative	
1	1	Stairs next to Caged Storage Room inside the Boy's Gymnasium (to Bsmt Boys Locker Room)	Ceiling	Concrete	White	None	0	0	Negative	

		Dates: 6/5 - 7/6/2023	Lead-Safe Certification Assessment Report						
		Inspector Name and Certificate Number: Tim Smith 057662	John Bartram High School						
		Inspection Company: BATA	2401 S 67th St, Philadelphia PA 19142						
E l e m e n t	F l o o r	On-Site Room Name	Component	Substrate Material [1]	Paint Color	Description of Paint Damage	Damage Quantity (sf) [2]	XRF Reading (mg/cm2)	XRF (positive/ negative) [3]
1	1	Stairs next to Caged Storage Room inside the Boy's Gymnasium (to Bsmt Boys Locker Room)	Floor	Concrete	Not Painted	N/A	N/A	N/A	N/A
1	1	Caged Storage Room inside the Boy's Gymnasium - Between Stairwell and Office	W1	Brick	Not Painted	N/A	N/A	N/A	N/A
1	1	Caged Storage Room inside the Boy's Gymnasium - Between Stairwell and Office	Fence Door	Metal	Brown	None	0	0	Negative
1	1	Caged Storage Room inside the Boy's Gymnasium - Between Stairwell and Office	W2	Brick	Not Painted	N/A	N/A	N/A	N/A
1	1	Caged Storage Room inside the Boy's Gymnasium - Between Stairwell and Office	W3	Brick	Not Painted	N/A	N/A	N/A	N/A
1	1	Caged Storage Room inside the Boy's Gymnasium - Between Stairwell and Office	W4	Brick	Not Painted	N/A	N/A	N/A	N/A
1	1	Caged Storage Room inside the Boy's Gymnasium - Between Stairwell and Office	Pipe	Metal	White	None	0	16	Positive
1	1	Caged Storage Room inside the Boy's Gymnasium - Between Stairwell and Office	Pipe Insulation	Asbestos	White	None	0	0.3	Negative
1	1	Caged Storage Room inside the Boy's Gymnasium - Between Stairwell and Office	Ceiling	Plaster	White	None	0	0.4	Negative
1	1	Caged Storage Room inside the Boy's Gymnasium - Between Stairwell and Office	Floor	Wood	Not Painted	N/A	N/A	N/A	N/A
1	1	Storage Room inside Boy's Gymnasium - between Caged Storage Room and Stairwell to 2nd Floor	W1	No Access	No Access	No Access	No Access	No Access	No Access
1	1	Storage Room inside Boy's Gymnasium - between Caged Storage Room and Stairwell to 2nd Floor	W2	No Access	No Access	No Access	No Access	No Access	No Access
1	1	Storage Room inside Boy's Gymnasium - between Caged Storage Room and Stairwell to 2nd Floor	W3	No Access	No Access	No Access	No Access	No Access	No Access
1	1	Storage Room inside Boy's Gymnasium - between Caged Storage Room and Stairwell to 2nd Floor	W4	No Access	No Access	No Access	No Access	No Access	No Access
1	1	Storage Room inside Boy's Gymnasium - between Caged Storage Room and Stairwell to 2nd Floor	Ceiling	No Access	No Access	No Access	No Access	No Access	No Access

		Dates: 6/5 - 7/6/2023	Lead-Safe Certification Assessment Report						
		Inspector Name and Certificate Number: Tim Smith 057662	John Bartram High School						
		Inspection Company: BATA	2401 S 67th St, Philadelphia PA 19142						
Element	Floor	On-Site Room Name	Component	Substrate Material [1]	Paint Color	Description of Paint Damage	Damage Quantity (sf) [2]	XRF Reading (mg/cm ²)	XRF (positive/negative) [3]
1	1	Storage Room inside Boy's Gymnasium - between Caged Storage Room and Stairwell to 2nd Floor	Floor	No Access	No Access	No Access	No Access	No Access	No Access
1	1	Auditorium	W1	Plaster	White	Cracking	4	0.1	Negative
1	1	Auditorium	Trim	Wood	Red	None	0	7.1	Positive
1	1	Auditorium	Doorframe	Metal	Red	Chipping	30	5.4	Positive
1	1	Auditorium	Door	Wood	Red	Chipping	20	4.1	Positive
1	1	Auditorium	W2	Plaster	White	Cracking	80	0.1	Negative
1	1	Auditorium	Door Trim	Wood	Grey	Chipping	10	8.2	Positive
1	1	Auditorium	W3	Plaster	White	None	0	0.1	Negative
1	1	Auditorium	W4	Plaster	White	Cracking	280	0.6	Negative
1	1	Auditorium	Radiator cover	Metal	Red	Chipping	40	6	Positive
1	1	Auditorium	Windowframe	Metal	White	Flaking	120	1.9	Positive
1	1	Auditorium	Ceiling	Plaster	White	None	0	0.3	Negative
1	1	Auditorium	Floor	Floor Tile	Not Painted	N/A	N/A	N/A	N/A
1	1	Auditorium Stage	W1	CMU	White	None	0	0	Negative
1	1	Auditorium Stage	W1	Plaster	White	None	0	0.9	Positive
1	1	Auditorium Stage	Door	Wood	Brown	Chipping	20	3.8	Positive
1	1	Auditorium Stage	Doorframe	Metal	Multi-Color	Chipping	12	2.2	Positive
1	1	Auditorium Stage	W2	Plaster	White	Cracking	60	4.4	Positive
1	1	Auditorium Stage	Stage Face	Wood	White	Chipping	30	5.4	Positive
1	1	Auditorium Stage	Conduit	Metal	White	Chipping	12	0.1	Negative
1	1	Auditorium Stage	Covebase	Wood	Grey	Friction	40	1.1	Positive
1	1	Auditorium Stage	Column	Plaster	White	None	0	0.5	Negative
1	1	Auditorium Stage	W3	Plaster	White	Cracking	30	4.5	Positive
1	1	Auditorium Stage	W4	Plaster	White	Cracking	80	7.5	Positive
1	1	Auditorium Stage	Ceiling	Concrete	White	No Access	No Access	No Access	No Access

		Dates: 6/5 - 7/6/2023	Lead-Safe Certification Assessment Report						
		Inspector Name and Certificate Number: Tim Smith 057662	John Bartram High School						
		Inspection Company: BATA	2401 S 67th St, Philadelphia PA 19142						
E l e m e n t	F l o o r	On-Site Room Name	Component	Substrate Material [1]	Paint Color	Description of Paint Damage	Damage Quantity (sf) [2]	XRF Reading (mg/cm2)	XRF (positive/ negative) [3]
1	1	Auditorium Stage	Floor	Wood	Not Painted	N/A	N/A	N/A	N/A
1	1	Right Side Auditorium Storage	W1	Drywall	White	None	0	0.1	Negative
1	1	Right Side Auditorium Storage	Doorframe	Metal	Brown	Chipping	1	0	Negative
1	1	Right Side Auditorium Storage	W2	Drywall	White	None	0	0.1	Negative
1	1	Right Side Auditorium Storage	W3	Plaster	White	None	0	2.9	Positive
1	1	Right Side Auditorium Storage	W4	Plaster	White	None	0	3.3	Positive
1	1	Right Side Auditorium Storage	Ceiling	Drywall	White	None	0	0	Negative
1	1	Right Side Auditorium Storage	Floor	Wood	Not Painted	N/A	N/A	N/A	N/A
1	1	Left Side Auditorium Storage	W1	Drywall	White	None	0	0	Negative
1	1	Left Side Auditorium Storage	Doorframe	Metal	Brown	None	0	0.1	Negative
1	1	Left Side Auditorium Storage	W2	Drywall	White	None	0	0	Negative
1	1	Left Side Auditorium Storage	W3	Plaster	White	Chipping	2	0.2	Negative
1	1	Left Side Auditorium Storage	W4	Drywall	White	None	0	0.2	Negative
1	1	Left Side Auditorium Storage	Ceiling	Drywall	White	None	0	0	Negative
1	1	Left Side Auditorium Storage	Floor	Wood	Not Painted	N/A	N/A	N/A	N/A
1	1	Girl's Gymnasium	W1	Brick	Not Painted	N/A	N/A	N/A	N/A
1	1	Girl's Gymnasium	Doorframe	Metal	Red	Friction	20	0.6	Negative
1	1	Girl's Gymnasium	Door	Wood	Red	Friction	10	0	Negative
1	1	Girl's Gymnasium	W2	Brick	Not Painted	N/A	N/A	N/A	N/A
1	1	Girl's Gymnasium	Radiator cover	Metal	White	Chipping	9	0.9	Positive
1	1	Girl's Gymnasium	W3	Brick	Not Painted	N/A	N/A	N/A	N/A
1	1	Girl's Gymnasium	W4	Brick	Not Painted	N/A	N/A	N/A	N/A
1	1	Girl's Gymnasium	Conduit	Metal	Brown	None	0	0.1	Negative
1	1	Girl's Gymnasium	Ceiling	Plaster	White	No Access	No Access	No Access	No Access
1	1	Girl's Gymnasium	Floor	Wood	Not Painted	N/A	N/A	N/A	N/A

		Dates: 6/5 - 7/6/2023	Lead-Safe Certification Assessment Report						
		Inspector Name and Certificate Number: Tim Smith 057662	John Bartram High School						
		Inspection Company: BATA	2401 S 67th St, Philadelphia PA 19142						
E l e m e n t	F l o o r	On-Site Room Name	Component	Substrate Material [1]	Paint Color	Description of Paint Damage	Damage Quantity (sf) [2]	XRF Reading (mg/cm2)	XRF (positive/ negative) [3]
1	1	Caged Storage Room inside the Girl's Gymnasium - Corner of Building	W1	No Access	No Access	No Access	No Access	No Access	No Access
1	1	Caged Storage Room inside the Girl's Gymnasium - Corner of Building	W2	No Access	No Access	No Access	No Access	No Access	No Access
1	1	Caged Storage Room inside the Girl's Gymnasium - Corner of Building	W3	No Access	No Access	No Access	No Access	No Access	No Access
1	1	Caged Storage Room inside the Girl's Gymnasium - Corner of Building	W4	No Access	No Access	No Access	No Access	No Access	No Access
1	1	Caged Storage Room inside the Girl's Gymnasium - Corner of Building	Ceiling	No Access	No Access	No Access	No Access	No Access	No Access
1	1	Caged Storage Room inside the Girl's Gymnasium - Corner of Building	Floor	No Access	No Access	No Access	No Access	No Access	No Access
1	1	Stairs next to Caged Storage Room inside the Girl's Gymnasium - Corner of Building (to Bsmt Girls Locker Room)	W1	Plaster	White	Cracking	24	0	Negative
1	1	Stairs next to Caged Storage Room inside the Girl's Gymnasium - Corner of Building (to Bsmt Girls Locker Room)	Doorframe	Metal	Brown	None	0	0.7	Positive
1	1	Stairs next to Caged Storage Room inside the Girl's Gymnasium - Corner of Building (to Bsmt Girls Locker Room)	Pipe Insulation	Asbestos	White	None	0	0.1	Negative
1	1	Stairs next to Caged Storage Room inside the Girl's Gymnasium - Corner of Building (to Bsmt Girls Locker Room)	W2	Plaster	White	Cracking	6	0	Negative
1	1	Stairs next to Caged Storage Room inside the Girl's Gymnasium - Corner of Building (to Bsmt Girls Locker Room)	Covebase	Concrete	Brown	Friction	20	0.4	Negative
1	1	Stairs next to Caged Storage Room inside the Girl's Gymnasium - Corner of Building (to Bsmt Girls Locker Room)	W3	Plaster	White	None	0	0.1	Negative

		Dates: 6/5 - 7/6/2023	Lead-Safe Certification Assessment Report						
		Inspector Name and Certificate Number: Tim Smith 057662	John Bartram High School						
		Inspection Company: BATA	2401 S 67th St, Philadelphia PA 19142						
E l e m e n t	F l o o r	On-Site Room Name	Component	Substrate Material [1]	Paint Color	Description of Paint Damage	Damage Quantity (sf) [2]	XRF Reading (mg/cm2)	XRF (positive/ negative) [3]
1	1	Stairs next to Caged Storage Room inside the Girl's Gymnasium - Corner of Building (to Bsmt Girls Locker Room)	W4	Plaster	White	Cracking	14	0	Negative
1	1	Stairs next to Caged Storage Room inside the Girl's Gymnasium - Corner of Building (to Bsmt Girls Locker Room)	Ceiling	Plaster	White	None	0	0.2	Negative
1	1	Stairs next to Caged Storage Room inside the Girl's Gymnasium - Corner of Building (to Bsmt Girls Locker Room)	Floor	Concrete	Not Painted	N/A	N/A	N/A	N/A
1	1	Caged Storage Room inside the Girl's Gymnasium - Between Stairwell and Office	W1	No Access	No Access	No Access	No Access	No Access	No Access
1	1	Caged Storage Room inside the Girl's Gymnasium - Between Stairwell and Office	W2	No Access	No Access	No Access	No Access	No Access	No Access
1	1	Caged Storage Room inside the Girl's Gymnasium - Between Stairwell and Office	W3	No Access	No Access	No Access	No Access	No Access	No Access
1	1	Caged Storage Room inside the Girl's Gymnasium - Between Stairwell and Office	W4	No Access	No Access	No Access	No Access	No Access	No Access
1	1	Caged Storage Room inside the Girl's Gymnasium - Between Stairwell and Office	Ceiling	No Access	No Access	No Access	No Access	No Access	No Access
1	1	Caged Storage Room inside the Girl's Gymnasium - Between Stairwell and Office	Floor	No Access	No Access	No Access	No Access	No Access	No Access
1	1	Office inside Girl's Gymnasium	W1	No Access	No Access	No Access	No Access	No Access	No Access
1	1	Office inside Girl's Gymnasium	W2	No Access	No Access	No Access	No Access	No Access	No Access
1	1	Office inside Girl's Gymnasium	W3	No Access	No Access	No Access	No Access	No Access	No Access
1	1	Office inside Girl's Gymnasium	W4	No Access	No Access	No Access	No Access	No Access	No Access
1	1	Office inside Girl's Gymnasium	Ceiling	No Access	No Access	No Access	No Access	No Access	No Access
1	1	Office inside Girl's Gymnasium	Floor	No Access	No Access	No Access	No Access	No Access	No Access
1	1	Storage Closet 1J outside of Weight Room	W1	No Access	No Access	No Access	No Access	No Access	No Access
1	1	Storage Closet 1J outside of Weight Room	W2	No Access	No Access	No Access	No Access	No Access	No Access
1	1	Storage Closet 1J outside of Weight Room	W3	No Access	No Access	No Access	No Access	No Access	No Access

		Dates: 6/5 - 7/6/2023	Lead-Safe Certification Assessment Report							
		Inspector Name and Certificate Number: Tim Smith 057662	John Bartram High School							
		Inspection Company: BATA	2401 S 67th St, Philadelphia PA 19142							
E l e m e n t	F l o o r	On-Site Room Name	Component	Substrate Material [1]	Paint Color	Description of Paint Damage	Damage Quantity (sf) [2]	XRF Reading (mg/cm2)	XRF (positive/ negative) [3]	
1	1	Storage Closet 1J outside of Weight Room	W4	No Access	No Access	No Access	No Access	No Access	No Access	
1	1	Storage Closet 1J outside of Weight Room	Ceiling	No Access	No Access	No Access	No Access	No Access	No Access	
1	1	Storage Closet 1J outside of Weight Room	Floor	No Access	No Access	No Access	No Access	No Access	No Access	
1	1	A-Wing Hallway 123-134	W1	Plaster	White	Cracking	2	0.5	Negative	
1	1	A-Wing Hallway 123-134	Door	Metal	Red	Chipping	3	0.1	Negative	
1	1	A-Wing Hallway 123-134	Doorframe	Metal	Red	Chipping	6	0	Negative	
1	1	A-Wing Hallway 123-134	W2	Plaster	White	None	0	0.1	Negative	
1	1	A-Wing Hallway 123-134	Locker	Metal	Red	Chipping	65	0.1	Negative	
1	1	A-Wing Hallway 123-134	Covebase	Concrete	Red	None	0	0.4	Negative	
1	1	A-Wing Hallway 123-134	W3	Plaster	White	None	0	0.5	Negative	
1	1	A-Wing Hallway 123-134	W4	Plaster	White	Cracking	2	0	Negative	
1	1	A-Wing Hallway 123-134	Pipe Cover	Metal	Tan	Chipping	6	2.4	Positive	
1	1	A-Wing Hallway 123-134	Radiator cover	Metal	Tan	Chipping	3	0.1	Negative	
1	1	A-Wing Hallway 123-134	Pipe Insulation	Asbestos	White	None	0	0.1	Negative	
1	1	A-Wing Hallway 123-134	Ceiling	Plaster	White	None	0	0.1	Negative	
1	1	A-Wing Hallway 123-134	Ceiling	2'x4' Ceiling Tile	Not Painted	N/A	N/A	N/A	N/A	
1	1	A-Wing Hallway 123-134	Floor	Concrete	Not Painted	N/A	N/A	N/A	N/A	
1	1	B-Wing Hallway 111-121	W1	Plaster	White	None	0	3.1	Positive	
1	1	B-Wing Hallway 111-121	Door	Metal	Red	Chipping	8	0	Negative	
1	1	B-Wing Hallway 111-121	Doorframe	Metal	Red	Chipping	4	0	Negative	
1	1	B-Wing Hallway 111-121	W2	Plaster	White	Chipping	5	0.2	Negative	
1	1	B-Wing Hallway 111-121	Locker	Metal	Red	Chipping	60	0.3	Negative	
1	1	B-Wing Hallway 111-121	Pipe Cover	Metal	Tan	Chipping	8	2	Positive	
1	1	B-Wing Hallway 111-121	Pipe Insulation	Asbestos	White	None	0	0.2	Negative	
1	1	B-Wing Hallway 111-121	Radiator cover	Metal	Tan	Chipping	8	0	Negative	
1	1	B-Wing Hallway 111-121	Covebase	Concrete	Grey	None	0	0.2	Negative	

		Dates: 6/5 - 7/6/2023	Lead-Safe Certification Assessment Report							
		Inspector Name and Certificate Number: Tim Smith 057662	John Bartram High School							
		Inspection Company: BATA	2401 S 67th St, Philadelphia PA 19142							
E l e m e n t	F l o o r	On-Site Room Name	Component	Substrate Material [1]	Paint Color	Description of Paint Damage	Damage Quantity (sf) [2]	XRF Reading (mg/cm2)	XRF (positive/ negative) [3]	
1	1	B-Wing Hallway 111-121	W3	Plaster	White	None	0	0.2	Negative	
1	1	B-Wing Hallway 111-121	W4	Plaster	White	Flaking	3	0.2	Negative	
1	1	B-Wing Hallway 111-121	Ceiling	1'x1' Ceiling Tile	White	None	0	0.2	Negative	
1	1	B-Wing Hallway 111-121	Floor	Concrete	Not Painted	N/A	N/A	N/A	N/A	
1	1	Hallway 101-110	W1	Plaster	White	None	0	0.6	Negative	
1	1	Hallway 101-110	Door	Metal	Red	Friction	1	0	Negative	
1	1	Hallway 101-110	Doorframe	Metal	Red	Friction	1	0	Negative	
1	1	Hallway 101-110	W2	Plaster	White	Cracking	4	0.1	Negative	
1	1	Hallway 101-110	Locker	Metal	Red	Chipping	68	0.1	Negative	
1	1	Hallway 101-110	Pipe Cover	Metal	Tan	Chipping	5	3.1	Positive	
1	1	Hallway 101-110	Pipe Insulation	Asbestos	White	None	0	0.1	Negative	
1	1	Hallway 101-110	Radiator cover	Metal	Tan	Chipping	6	0	Negative	
1	1	Hallway 101-110	Covebase	Concrete	Grey	None	0	0.2	Negative	
1	1	Hallway 101-110	W3	Plaster	White	None	0	0.6	Negative	
1	1	Hallway 101-110	W4	Plaster	White	Flaking	2	0.1	Negative	
1	1	Hallway 101-110	Ceiling	1'x1' Ceiling Tile	White	None	0	0.1	Negative	
1	1	Hallway 101-110	Floor	Concrete	Not Painted	N/A	N/A	N/A	N/A	
1	1	Main Hallway 135-137	W1	Plaster	White	None	0	0.1	Negative	
1	1	Main Hallway 135-137	Door	Metal	Brown	Chipping	16	0.2	Negative	
1	1	Main Hallway 135-137	Doorframe	Metal	Brown	Chipping	4	0.1	Negative	
1	1	Main Hallway 135-137	W2	Plaster	White	None	0	0.2	Negative	
1	1	Main Hallway 135-137	Mural Wall	Plaster	Multi-Color	None	0	0.5	Negative	
1	1	Main Hallway 135-137	Conduit	Plastic	Multi-Color	None	0	0.4	Negative	
1	1	Main Hallway 135-137	W3	Plaster	White	None	0	0	Negative	
1	1	Main Hallway 135-137	W4	Plaster	White	None	0	0	Negative	
1	1	Main Hallway 135-137	Crown Molding	Plaster	White	None	0	0.4	Negative	

		Dates: 6/5 - 7/6/2023	Lead-Safe Certification Assessment Report							
		Inspector Name and Certificate Number: Tim Smith 057662	John Bartram High School							
		Inspection Company: BATA	2401 S 67th St, Philadelphia PA 19142							
E l e m e n t	F l o o r	On-Site Room Name	Component	Substrate Material [1]	Paint Color	Description of Paint Damage	Damage Quantity (sf) [2]	XRF Reading (mg/cm2)	XRF (positive/ negative) [3]	
1	1	Main Hallway 135-137	Ceiling	Plaster	White	None	0	0.5	Negative	
1	1	Main Hallway 135-137	Ceiling	2'x4' Ceiling Tile	Not Painted	N/A	N/A	N/A	N/A	
1	1	Main Hallway 135-137	Floor	Terrazzo	Not Painted	N/A	N/A	N/A	N/A	
1	1	Boy's Gym Hallway	W1	Plaster	White	None	0	0	Negative	
1	1	Boy's Gym Hallway	W2	Plaster	White	None	0	0	Negative	
1	1	Boy's Gym Hallway	W3	Plaster	White	None	0	0.2	Negative	
1	1	Boy's Gym Hallway	W4	Plaster	White	Chipping	4	0.2	Negative	
1	1	Boy's Gym Hallway	Conduit	Plastic	White	None	0	0.4	Negative	
1	1	Boy's Gym Hallway	Crown Molding	Plaster	White	None	0	0.3	Negative	
1	1	Boy's Gym Hallway	Ceiling	Plaster	White	None	0	0	Negative	
1	1	Boy's Gym Hallway	Floor	Terrazzo	Not Painted	N/A	N/A	N/A	N/A	
1	1	Girl's Gym Hallway	W1	Plaster	White	None	0	0	Negative	
1	1	Girl's Gym Hallway	W2	Plaster	White	None	0	0.1	Negative	
1	1	Girl's Gym Hallway	W3	Plaster	White	None	0	0.2	Negative	
1	1	Girl's Gym Hallway	W4	Plaster	White	None	0	0.1	Negative	
1	1	Girl's Gym Hallway	Conduit	Plastic	White	None	0	0.4	Negative	
1	1	Girl's Gym Hallway	Crown Molding	Plaster	White	None	0	0.1	Negative	
1	1	Girl's Gym Hallway	Ceiling	Plaster	White	None	0	0	Negative	
1	1	Girl's Gym Hallway	Floor	Terrazzo	Not Painted	N/A	N/A	N/A	N/A	
1	1	Foyer at Girl's Gym Hallway	W1	Marble	Not Painted	N/A	N/A	N/A	N/A	
1	1	Foyer at Girl's Gym Hallway	Door	Metal	Brown	None	0	0.1	Negative	
1	1	Foyer at Girl's Gym Hallway	Doorframe	Metal	Brown	None	0	0.1	Negative	
1	1	Foyer at Girl's Gym Hallway	W2	Marble	Not Painted	N/A	N/A	N/A	N/A	
1	1	Foyer at Girl's Gym Hallway	W3	Marble	Not Painted	N/A	N/A	N/A	N/A	
1	1	Foyer at Girl's Gym Hallway	W4	Marble	Not Painted	N/A	N/A	N/A	N/A	
1	1	Foyer at Girl's Gym Hallway	Crown Molding	Plaster	White	None	0	0.2	Negative	

		Dates: 6/5 - 7/6/2023	Lead-Safe Certification Assessment Report						
		Inspector Name and Certificate Number: Tim Smith 057662	John Bartram High School						
		Inspection Company: BATA	2401 S 67th St, Philadelphia PA 19142						
E l e m e n t	F l o o r	On-Site Room Name	Component	Substrate Material [1]	Paint Color	Description of Paint Damage	Damage Quantity (sf) [2]	XRF Reading (mg/cm2)	XRF (positive/ negative) [3]
1	1	Foyer at Girl's Gym Hallway	Ceiling	Plaster	White	None	0	0.5	Negative
1	1	Foyer at Girl's Gym Hallway	Floor	Terrazzo	Not Painted	N/A	N/A	N/A	N/A
1	1	Stairs to 2nd Floor inside Boy's Gymnasium	W1	Plaster	White	None	0	0.1	Negative
1	1	Stairs to 2nd Floor inside Boy's Gymnasium	Doorframe	Metal	Brown	Friction	2	1	Positive
1	1	Stairs to 2nd Floor inside Boy's Gymnasium	W2	Plaster	White	Cracking	3	0.1	Negative
1	1	Stairs to 2nd Floor inside Boy's Gymnasium	Post	Metal	Brown	None	0	11.5	Positive
1	1	Stairs to 2nd Floor inside Boy's Gymnasium	Riser	Concrete	Brown	Chipping	14	0.5	Negative
1	1	Stairs to 2nd Floor inside Boy's Gymnasium	Baluster	Metal	Brown	None	0	5.6	Positive
1	1	Stairs to 2nd Floor inside Boy's Gymnasium	Stringer	Concrete	Brown	None	0	0.8	Positive
1	1	Stairs to 2nd Floor inside Boy's Gymnasium	W3	Plaster	White	Flaking	6	0.1	Negative
1	1	Stairs to 2nd Floor inside Boy's Gymnasium	W4	Plaster	White	Cracking	6	0.1	Negative
1	1	Stairs to 2nd Floor inside Boy's Gymnasium	Ceiling	Plaster	White	None	0	0.3	Negative
1	1	Stairs to 2nd Floor inside Boy's Gymnasium	Floor	Concrete	Not Painted	N/A	N/A	N/A	N/A
1	1	Stairwell adjacent to Room 123	W1	Plaster	White	None	0	0.5	Negative
1	1	Stairwell adjacent to Room 123	Door	Metal	Red	None	0	0.1	Negative
1	1	Stairwell adjacent to Room 123	Doorframe	Metal	Red	None	0	0.2	Negative
1	1	Stairwell adjacent to Room 123	W2	Plaster	White	Flaking	20	0.3	Negative
1	1	Stairwell adjacent to Room 123	Pipe Cover	Metal	Tan	None	0	2.8	Positive
1	1	Stairwell adjacent to Room 123	Pipe Insulation	Asbestos	White	None	0	0.1	Negative
1	1	Stairwell adjacent to Room 123	Post	Metal	Brown	None	0	11.2	Positive
1	1	Stairwell adjacent to Room 123	Stringer	Concrete	Brown	None	0	0.5	Negative
1	1	Stairwell adjacent to Room 123	Baluster	Metal	Brown	None	0	9.6	Positive
1	1	Stairwell adjacent to Room 123	Riser	Concrete	Brown	Chipping	20	0.5	Negative
1	1	Stairwell adjacent to Room 123	Conduit	Metal	White	None	0	0	Negative
1	1	Stairwell adjacent to Room 123	W3	Plaster	White	Flaking	4	0.2	Negative
1	1	Stairwell adjacent to Room 123	Windowframe	Metal	White	Chipping	1	10.3	Positive

		Dates: 6/5 - 7/6/2023	Lead-Safe Certification Assessment Report							
		Inspector Name and Certificate Number: Tim Smith 057662	John Bartram High School							
		Inspection Company: BATA	2401 S 67th St, Philadelphia PA 19142							
E l e m e n t	F l o o r	On-Site Room Name	Component	Substrate Material [1]	Paint Color	Description of Paint Damage	Damage Quantity (sf) [2]	XRF Reading (mg/cm ²)	XRF (positive/ negative) [3]	
1	1	Stairwell adjacent to Room 123	Radiator cover	Metal	Brown	None	0	0	Negative	
1	1	Stairwell adjacent to Room 123	W4	Plaster	White	None	0	0	Negative	
1	1	Stairwell adjacent to Room 123	Ceiling	Plaster	White	None	0	0.3	Negative	
1	1	Stairwell adjacent to Room 123	Floor	Concrete	Not Painted	N/A	N/A	N/A	N/A	
1	1	Stairwell A adjacent to Room 131	W1	Plaster	White	None	0	0.6	Negative	
1	1	Stairwell A adjacent to Room 131	Door	Metal	Red	Chipping	1	0.1	Negative	
1	1	Stairwell A adjacent to Room 131	Doorframe	Metal	Red	None	0	0	Negative	
1	1	Stairwell A adjacent to Room 131	W2	Plaster	White	Flaking	3	0.2	Negative	
1	1	Stairwell A adjacent to Room 131	Pipe Cover	Metal	Tan	Chipping	7	3	Positive	
1	1	Stairwell A adjacent to Room 131	Pipe Insulation	Asbestos	White	None	0	0.1	Negative	
1	1	Stairwell A adjacent to Room 131	Post	Metal	Brown	Chipping	6	15.6	Positive	
1	1	Stairwell A adjacent to Room 131	Stringer	Concrete	Brown	Chipping	12	0.6	Negative	
1	1	Stairwell A adjacent to Room 131	Baluster	Metal	Brown	Flaking	4	7	Positive	
1	1	Stairwell A adjacent to Room 131	Riser	Concrete	Brown	Friction	50	0.3	Negative	
1	1	Stairwell A adjacent to Room 131	W3	Plaster	White	Flaking	8	0.6	Negative	
1	1	Stairwell A adjacent to Room 131	Windowframe	Metal	White	Cracking	2	13.6	Positive	
1	1	Stairwell A adjacent to Room 131	Radiator cover	Metal	Brown	Flaking	9	0	Negative	
1	1	Stairwell A adjacent to Room 131	W4	Plaster	White	Cracking	15	0.2	Negative	
1	1	Stairwell A adjacent to Room 131	Ceiling	Plaster	White	None	0	0.2	Negative	
1	1	Stairwell A adjacent to Room 131	Floor	Concrete	Not Painted	N/A	N/A	N/A	N/A	
1	1	Stairwell C next to Classroom 108	W1	Plaster	White	None	0	0.1	Negative	
1	1	Stairwell C next to Classroom 108	Door	Metal	Red	None	0	0	Negative	
1	1	Stairwell C next to Classroom 108	Doorframe	Metal	Red	Chipping	2	0.1	Negative	
1	1	Stairwell C next to Classroom 108	W2	Plaster	White	Flaking	4	0.2	Negative	
1	1	Stairwell C next to Classroom 108	Covebase	Concrete	Brown	None	0	0.7	Positive	
1	1	Stairwell C next to Classroom 108	Post	Metal	Brown	Chipping	8	15.1	Positive	

		Dates: 6/5 - 7/6/2023	Lead-Safe Certification Assessment Report							
		Inspector Name and Certificate Number: Tim Smith 057662	John Bartram High School							
		Inspection Company: BATA	2401 S 67th St, Philadelphia PA 19142							
E l e m e n t	F l o o r	On-Site Room Name	Component	Substrate Material [1]	Paint Color	Description of Paint Damage	Damage Quantity (sf) [2]	XRF Reading (mg/cm2)	XRF (positive/ negative) [3]	
1	1	Stairwell C next to Classroom 108	Riser	Concrete	Brown	Friction	12	0.5	Negative	
1	1	Stairwell C next to Classroom 108	Baluster	Metal	Brown	None	0	7	Positive	
1	1	Stairwell C next to Classroom 108	Stringer	Concrete	Brown	None	0	0.9	Positive	
1	1	Stairwell C next to Classroom 108	Radiator cover	Metal	Brown	Chipping	6	0.1	Negative	
1	1	Stairwell C next to Classroom 108	Pipe Cover	Metal	Tan	Chipping	5	2.5	Positive	
1	1	Stairwell C next to Classroom 108	Pipe Insulation	Asbestos	White	Alligatoring	8	0.2	Negative	
1	1	Stairwell C next to Classroom 108	W3	Plaster	White	Flaking	4	0.2	Negative	
1	1	Stairwell C next to Classroom 108	Windowframe	Metal	Tan	Chipping	6	12.7	Positive	
1	1	Stairwell C next to Classroom 108	W4	Plaster	White	None	0	0.1	Negative	
1	1	Stairwell C next to Classroom 108	Ceiling	Plaster	White	None	0	0.3	Negative	
1	1	Stairwell C next to Classroom 108	Floor	Concrete	Not Painted	N/A	N/A	N/A	N/A	
1	1	Stairwell B adjacent to Room 120	W1	Plaster	White	None	0	0	Negative	
1	1	Stairwell B adjacent to Room 120	Door	Metal	Red	Chipping	4	0.2	Negative	
1	1	Stairwell B adjacent to Room 120	Doorframe	Metal	Red	Friction	2	0	Negative	
1	1	Stairwell B adjacent to Room 120	W2	Plaster	White	None	0	0.1	Negative	
1	1	Stairwell B adjacent to Room 120	Covebase	Concrete	Brown	Chipping	14	0.5	Negative	
1	1	Stairwell B adjacent to Room 120	Post	Metal	Brown	Chipping	8	14.3	Positive	
1	1	Stairwell B adjacent to Room 120	Riser	Concrete	Brown	Friction	20	0.4	Negative	
1	1	Stairwell B adjacent to Room 120	Baluster	Metal	Brown	Chipping	15	9	Positive	
1	1	Stairwell B adjacent to Room 120	Stringer	Concrete	Brown	None	0	0.6	Negative	
1	1	Stairwell B adjacent to Room 120	Radiator cover	Metal	Brown	None	0	0.1	Negative	
1	1	Stairwell B adjacent to Room 120	Pipe Cover	Metal	Tan	Chipping	6	1.9	Positive	
1	1	Stairwell B adjacent to Room 120	Pipe Insulation	Asbestos	White	Alligatoring	30	0.2	Negative	
1	1	Stairwell B adjacent to Room 120	W3	Plaster	White	Flaking	4	0.3	Negative	
1	1	Stairwell B adjacent to Room 120	Windowframe	Metal	Tan	Flaking	10	14.3	Positive	
1	1	Stairwell B adjacent to Room 120	W4	Plaster	White	Flaking	3	0.1	Negative	

		Dates: 6/5 - 7/6/2023	Lead-Safe Certification Assessment Report						
		Inspector Name and Certificate Number: Tim Smith 057662	John Bartram High School						
		Inspection Company: BATA	2401 S 67th St, Philadelphia PA 19142						
E l e m e n t	F l o o r	On-Site Room Name	Component	Substrate Material [1]	Paint Color	Description of Paint Damage	Damage Quantity (sf) [2]	XRF Reading (mg/cm2)	XRF (positive/ negative) [3]
1	1	Stairwell B adjacent to Room 120	Ceiling	Plaster	White	None	0	0.6	Negative
1	1	Stairwell B adjacent to Room 120	Floor	Concrete	Not Painted	N/A	N/A	N/A	N/A
1	1	Girl's Gym Stairs	W1	Plaster	White	None	0	0.3	Negative
1	1	Girl's Gym Stairs	Doorframe	Metal	Brown	Friction	4	0.8	Positive
1	1	Girl's Gym Stairs	W2	Plaster	White	None	0	0	Negative
1	1	Girl's Gym Stairs	Covebase	Concrete	Brown	Friction	6	0.7	Positive
1	1	Girl's Gym Stairs	Post	Metal	Brown	None	0	9	Positive
1	1	Girl's Gym Stairs	Riser	Concrete	Brown	None	0	0.8	Positive
1	1	Girl's Gym Stairs	Baluster	Metal	Brown	None	0	5.4	Positive
1	1	Girl's Gym Stairs	Stringer	Concrete	Brown	None	0	1.6	Positive
1	1	Girl's Gym Stairs	W3	Plaster	White	None	0	0.2	Negative
1	1	Girl's Gym Stairs	W4	Plaster	White	None	0	0.4	Negative
1	1	Girl's Gym Stairs	Ceiling	Plaster	White	None	0	0.2	Negative
1	1	Girl's Gym Stairs	Floor	Concrete	Not Painted	N/A	N/A	N/A	N/A
1	1	Auditorium Stairs	W1	Plaster	White	None	0	0.1	Negative
1	1	Auditorium Stairs	W2	Plaster	White	Chipping	6	0.2	Negative
1	1	Auditorium Stairs	W3	Plaster	White	Cracking	12	0.1	Negative
1	1	Auditorium Stairs	W4	Plaster	White	None	0	0	Negative
1	1	Auditorium Stairs	Ceiling	Plaster	White	None	0	0.5	Negative
1	1	Auditorium Stairs	Floor	Marble	Not Painted	N/A	N/A	N/A	N/A
1	1	Stairwell adjacent to Room 101	W1	Plaster	White	None	0	0.4	Negative
1	1	Stairwell adjacent to Room 101	Door	Metal	Red	None	0	0.1	Negative
1	1	Stairwell adjacent to Room 101	Doorframe	Metal	Red	None	0	0.1	Negative
1	1	Stairwell adjacent to Room 101	W2	Plaster	White	None	0	0.1	Negative
1	1	Stairwell adjacent to Room 101	Covebase	Concrete	Brown	cracking	12	0.5	Negative
1	1	Stairwell adjacent to Room 101	Post	Metal	Brown	None	0	12.6	Positive

		Dates: 6/5 - 7/6/2023	Lead-Safe Certification Assessment Report						
		Inspector Name and Certificate Number: Tim Smith 057662	John Bartram High School						
		Inspection Company: BATA	2401 S 67th St, Philadelphia PA 19142						
E l e m e n t	F l o o r	On-Site Room Name	Component	Substrate Material [1]	Paint Color	Description of Paint Damage	Damage Quantity (sf) [2]	XRF Reading (mg/cm2)	XRF (positive/ negative) [3]
1	1	Stairwell adjacent to Room 101	Riser	Concrete	Brown	Chipping	16	0.5	Negative
1	1	Stairwell adjacent to Room 101	Baluster	Metal	Brown	Chipping	2	8.6	Positive
1	1	Stairwell adjacent to Room 101	Stringer	Concrete	Brown	None	0	0.2	Negative
1	1	Stairwell adjacent to Room 101	Radiator cover	Metal	Brown	None	0	0	Negative
1	1	Stairwell adjacent to Room 101	Pipe Cover	Metal	Tan	Chipping	5	2.8	Positive
1	1	Stairwell adjacent to Room 101	Pipe Insulation	Asbestos	White	None	0	0.1	Negative
1	1	Stairwell adjacent to Room 101	W3	Plaster	White	Efflorescence	16	0	Negative
1	1	Stairwell adjacent to Room 101	Windowframe	Metal	Tan	Chipping	12	6.4	Positive
1	1	Stairwell adjacent to Room 101	Conduit	Metal	White	None	0	0.2	Negative
1	1	Stairwell adjacent to Room 101	W4	Plaster	White	Efflorescence	12	0	Negative
1	1	Stairwell adjacent to Room 101	Ceiling	Plaster	White	None	0	0.3	Negative
1	1	Stairwell adjacent to Room 101	Floor	Concrete	Not Painted	N/A	N/A	N/A	N/A
1	1	Stairwell adjacent to 111	W1	Plaster	White	Flaking	60	0.4	Negative
1	1	Stairwell adjacent to 111	Door	Metal	Red	None	0	0.2	Negative
1	1	Stairwell adjacent to 111	Doorframe	Metal	Red	None	0	0.1	Negative
1	1	Stairwell adjacent to 111	W2	Plaster	White	Flaking	600	0.1	Negative
1	1	Stairwell adjacent to 111	Post	Metal	Brown	Chipping	10	14.8	Positive
1	1	Stairwell adjacent to 111	Riser	Concrete	Brown	Friction	16	0.3	Negative
1	1	Stairwell adjacent to 111	Baluster	Metal	Brown	Flaking	28	6.3	Positive
1	1	Stairwell adjacent to 111	Stringer	Concrete	Brown	Flaking	14	0.9	Positive
1	1	Stairwell adjacent to 111	Radiator cover	Metal	Brown	Flaking	4	0.1	Negative
1	1	Stairwell adjacent to 111	Pipe Cover	Metal	Tan	Flaking	12	2.9	Positive
1	1	Stairwell adjacent to 111	Pipe Insulation	Asbestos	White	Alligatoring	20	0.1	Negative
1	1	Stairwell adjacent to 111	W3	Plaster	White	Flaking	30	0.1	Negative
1	1	Stairwell adjacent to 111	Railing	Metal	Tan	Flaking	12	4.2	Positive
1	1	Stairwell adjacent to 111	Windowframe	Metal	Tan	Flaking	30	12.3	Positive

		Dates: 6/5 - 7/6/2023	Lead-Safe Certification Assessment Report							
		Inspector Name and Certificate Number: Tim Smith 057662	John Bartram High School							
		Inspection Company: BATA	2401 S 67th St, Philadelphia PA 19142							
E l e m e n t	F l o o r	On-Site Room Name	Component	Substrate Material [1]	Paint Color	Description of Paint Damage	Damage Quantity (sf) [2]	XRF Reading (mg/cm2)	XRF (positive/ negative) [3]	
1	1	Stairwell adjacent to 111	W4	Plaster	White	Flaking	500	0.5	Negative	
1	1	Stairwell adjacent to 111	Conduit	Metal	Tan	Cracking	1	0.1	Negative	
1	1	Stairwell adjacent to 111	Ceiling	Plaster	White	Flaking	600	0.3	Negative	
1	1	Stairwell adjacent to 111	Floor	Concrete	Not Painted	N/A	N/A	N/A	N/A	
1	1	Pipe Chase in Stairwell adjacent to 111	W1	No Access	No Access	No Access	No Access	No Access	No Access	
1	1	Pipe Chase in Stairwell adjacent to 111	W2	No Access	No Access	No Access	No Access	No Access	No Access	
1	1	Pipe Chase in Stairwell adjacent to 111	W3	No Access	No Access	No Access	No Access	No Access	No Access	
1	1	Pipe Chase in Stairwell adjacent to 111	W4	No Access	No Access	No Access	No Access	No Access	No Access	
1	1	Pipe Chase in Stairwell adjacent to 111	Ceiling	No Access	No Access	No Access	No Access	No Access	No Access	
1	1	Pipe Chase in Stairwell adjacent to 111	Floor	No Access	No Access	No Access	No Access	No Access	No Access	
1	2	Classroom 201	W1	Plaster	White/Pink	Cracking	8	0	Negative	
1	2	Classroom 201	Doorframe	Metal	Brown	Chipping	3	1.1	Positive	
1	2	Classroom 201	Conduit	Metal	White	None	0	0	Negative	
1	2	Classroom 201	Blackboard Frame	Wood	Purple	None	0	0.3	Negative	
1	2	Classroom 201	W2	Plaster	White	None	0	0.1	Negative	
1	2	Classroom 201	Cabinet	Wood	White	Chipping	30	0.2	Negative	
1	2	Classroom 201	Blackboard Frame	Wood	Pink	Cracking	30	2.4	Positive	
1	2	Classroom 201	Shelf	Wood	Yellow	None	0	0.1	Negative	
1	2	Classroom 201	W3	Plaster	White	Friction	120	0.2	Negative	
1	2	Classroom 201	Windowsill	Wood	Brown	Chipping	8	0.2	Negative	
1	2	Classroom 201	Pipe Cover	Metal	White	None	0	3.9	Positive	
1	2	Classroom 201	Pipe Insulation	Asbestos	White	None	0	0.1	Negative	
1	2	Classroom 201	Radiator cover	Metal	Brown	Chipping	12	0.8	Positive	
1	2	Classroom 201	W4	Plaster	White	Flaking	8	0.3	Negative	
1	2	Classroom 201	Ceiling	Plaster	White	None	0	0.3	Negative	
1	2	Classroom 201	Ceiling	2'x4' Ceiling Tile	Not Painted	N/A	N/A	N/A	N/A	

		Dates: 6/5 - 7/6/2023	Lead-Safe Certification Assessment Report						
		Inspector Name and Certificate Number: Tim Smith 057662	John Bartram High School						
		Inspection Company: BATA	2401 S 67th St, Philadelphia PA 19142						
E l e m e n t	F l o o r	On-Site Room Name	Component	Substrate Material [1]	Paint Color	Description of Paint Damage	Damage Quantity (sf) [2]	XRF Reading (mg/cm2)	XRF (positive/ negative) [3]
1	2	Classroom 201	Floor	Floor Tile	Not Painted	N/A	N/A	N/A	N/A
1	2	Classroom 202	W1	Plaster	White/Pink	Cracking	24	0	Negative
1	2	Classroom 202	Doorframe	Metal	Brown	Chipping	8	0.8	Positive
1	2	Classroom 202	W2	Plaster	White/Pink	Cracking	40	0.1	Negative
1	2	Classroom 202	Whiteboard Frame	Wood	Tan	Chipping	30	0.1	Negative
1	2	Classroom 202	W3	Plaster	White/Pink	Cracking	90	0	Negative
1	2	Classroom 202	Pipe Cover	Metal	White/Pink	Flaking	12	2.8	Positive
1	2	Classroom 202	Pipe Insulation	Asbestos	White/Pink	Cracking	2	0.1	Negative
1	2	Classroom 202	Radiator cover	Metal	Brown	Chipping	6	0.9	Positive
1	2	Classroom 202	W4	Plaster	White/Pink	Cracking	20	0.1	Negative
1	2	Classroom 202	Ceiling	Concrete	Not Painted	N/A	N/A	N/A	N/A
1	2	Classroom 202	Ceiling	2'x4' Ceiling Tile	Not Painted	N/A	N/A	N/A	N/A
1	2	Classroom 202	Floor	Floor Tile	Not Painted	N/A	N/A	N/A	N/A
1	2	Classroom 203	W1	Plaster	White/Pink	Flaking	40	0	Negative
1	2	Classroom 203	Doorframe	Metal	Brown	Chipping	4	1.1	Positive
1	2	Classroom 203	W2	Plaster	White/Pink	Chipping	40	0.1	Negative
1	2	Classroom 203	W3	Plaster	White/Pink	Flaking	180	0.1	Negative
1	2	Classroom 203	Pipe Cover	Metal	White/Pink	Flaking	16	2.6	Positive
1	2	Classroom 203	Pipe Insulation	Asbestos	White/Pink	None	0	0.1	Negative
1	2	Classroom 203	Radiator cover	Metal	Brown	Chipping	8	0.9	Positive
1	2	Classroom 203	W4	Plaster	White/Pink	Cracking	4	0	Negative
1	2	Classroom 203	Ceiling	Plaster	White	Flaking	440	0.2	Negative
1	2	Classroom 203	Ceiling	2'x4' Ceiling Tile	Not Painted	N/A	N/A	N/A	N/A
1	2	Classroom 203	Floor	Floor Tile	Not Painted	N/A	N/A	N/A	N/A
1	2	Classroom 204	W1	Plaster	White	Cracking	4	0	Negative
1	2	Classroom 204	Doorframe	Metal	Brown	Friction	6	1	Positive

		Dates: 6/5 - 7/6/2023	Lead-Safe Certification Assessment Report						
		Inspector Name and Certificate Number: Tim Smith 057662	John Bartram High School						
		Inspection Company: BATA	2401 S 67th St, Philadelphia PA 19142						
E l e m e n t	F l o o r	On-Site Room Name	Component	Substrate Material [1]	Paint Color	Description of Paint Damage	Damage Quantity (sf) [2]	XRF Reading (mg/cm2)	XRF (positive/ negative) [3]
1	2	Classroom 204	Conduit	Plastic	White	None	0	0.4	Negative
1	2	Classroom 204	W2	Plaster	White	None	0	0.1	Negative
1	2	Classroom 204	W3	Plaster	White	None	0	0.1	Negative
1	2	Classroom 204	Pipe Cover	Metal	White	Flaking	10	2.8	Positive
1	2	Classroom 204	Pipe Insulation	Asbestos	White	None	0	0.1	Negative
1	2	Classroom 204	Radiator cover	Metal	Brown	Chipping	2	0.8	Positive
1	2	Classroom 204	W4	Plaster	White	None	0	0.1	Negative
1	2	Classroom 204	Ceiling	Plaster	White	None	0	0	Negative
1	2	Classroom 204	Ceiling	2'x4' Ceiling Tile	Not Painted	N/A	N/A	N/A	N/A
1	2	Classroom 204	Floor	Floor Tile	Not Painted	N/A	N/A	N/A	N/A
1	2	Classroom 205	W1	Plaster	White/Pink	Cracking	56	0.1	Negative
1	2	Classroom 205	Doorframe	Metal	Brown	Friction	10	0.8	Positive
1	2	Classroom 205	Blackboard Ledge	Wood	Not Painted	N/A	N/A	N/A	N/A
1	2	Classroom 205	Pipe	Metal	Pink	None	0	16.7	Positive
1	2	Classroom 205	W2	Plaster	White/Pink	Cracking	18	0.3	Negative
1	2	Classroom 205	W3	Plaster	White/Pink	Flaking	100	0.1	Negative
1	2	Classroom 205	Pipe Cover	Metal	White/Pink	Flaking	16	2	Positive
1	2	Classroom 205	Pipe Insulation	Asbestos	White/Pink	None	0	0.1	Negative
1	2	Classroom 205	Radiator cover	Metal	Brown	Chipping	8	0.5	Negative
1	2	Classroom 205	W4	Plaster	White/Pink	Flaking	20	0	Negative
1	2	Classroom 205	Ceiling	Plaster	White	None	0	0	Negative
1	2	Classroom 205	Ceiling	2'x4' Ceiling Tile	Not Painted	N/A	N/A	N/A	N/A
1	2	Classroom 205	Floor	Floor Tile	Not Painted	N/A	N/A	N/A	N/A
1	2	Classroom 206	W1	Plaster	Tan	None	0	0	Negative
1	2	Classroom 206	Doorframe	Metal	Brown	Friction	12	1.3	Positive
1	2	Classroom 206	W2	Plaster	Tan	None	0	0.1	Negative

		Dates: 6/5 - 7/6/2023	Lead-Safe Certification Assessment Report							
		Inspector Name and Certificate Number: Tim Smith 057662	John Bartram High School							
		Inspection Company: BATA	2401 S 67th St, Philadelphia PA 19142							
E l e m e n t	F l o o r	On-Site Room Name	Component	Substrate Material [1]	Paint Color	Description of Paint Damage	Damage Quantity (sf) [2]	XRF Reading (mg/cm2)	XRF (positive/ negative) [3]	
1	2	Classroom 206	W3	Plaster	Tan	Flaking	12	0	Negative	
1	2	Classroom 206	Pipe Cover	Metal	Tan	Chipping	1	3.1	Positive	
1	2	Classroom 206	Conduit	Plastic	Tan	None	0	0.1	Negative	
1	2	Classroom 206	Pipe Insulation	Asbestos	Tan	None	0	0.1	Negative	
1	2	Classroom 206	Radiator cover	Metal	Brown	Chipping	3	0.4	Negative	
1	2	Classroom 206	W4	Plaster	Tan	Cracking	12	0.1	Negative	
1	2	Classroom 206	Ceiling	Plaster	White	None	0	0.1	Negative	
1	2	Classroom 206	Ceiling	2'x4' Ceiling Tile	Not Painted	N/A	N/A	N/A	N/A	
1	2	Classroom 206	Floor	Floor Tile	Not Painted	N/A	N/A	N/A	N/A	
1	2	Classroom 207	W1	Plaster	White/Pink	Cracking	30	0.1	Negative	
1	2	Classroom 207	Doorframe	Metal	Brown	Friction	3	0.7	Positive	
1	2	Classroom 207	W2	Plaster	White/Pink	Cracking	60	0.1	Negative	
1	2	Classroom 207	W3	Plaster	White/Pink	Flaking	60	0.2	Negative	
1	2	Classroom 207	Pipe Cover	Metal	White/Pink	Flaking	15	4	Positive	
1	2	Classroom 207	Pipe Insulation	Asbestos	White/Pink	None	0	0.2	Negative	
1	2	Classroom 207	Radiator cover	Metal	Brown	Chipping	6	0.6	Negative	
1	2	Classroom 207	W4	Plaster	White/Pink	Flaking	20	0.5	Negative	
1	2	Classroom 207	Ceiling	Plaster	White	Cracking	20	0.1	Negative	
1	2	Classroom 207	Ceiling	2'x4' Ceiling Tile	Not Painted	N/A	N/A	N/A	N/A	
1	2	Classroom 207	Floor	Floor Tile	Not Painted	N/A	N/A	N/A	N/A	
1	2	Classroom 208	W1	Plaster	White/Pink	Cracking	18	0	Negative	
1	2	Classroom 208	Doorframe	Metal	Brown	Friction	8	0.9	Positive	
1	2	Classroom 208	W2	Plaster	White/Pink	Flaking	20	0	Negative	
1	2	Classroom 208	W3	Plaster	White/Pink	Flaking	36	0	Negative	
1	2	Classroom 208	Pipe Cover	Metal	White/Pink	Flaking	10	2.9	Positive	
1	2	Classroom 208	Pipe Insulation	Asbestos	White/Pink	None	0	0.1	Negative	

		Dates: 6/5 - 7/6/2023	Lead-Safe Certification Assessment Report							
		Inspector Name and Certificate Number: Tim Smith 057662	John Bartram High School							
		Inspection Company: BATA	2401 S 67th St, Philadelphia PA 19142							
E l e m e n t	F l o o r	On-Site Room Name	Component	Substrate Material [1]	Paint Color	Description of Paint Damage	Damage Quantity (sf) [2]	XRF Reading (mg/cm2)	XRF (positive/ negative) [3]	
1	2	Classroom 208	Radiator cover	Metal	Brown	Chipping	6	0.5	Negative	
1	2	Classroom 208	W4	Plaster	White/Pink	None	0	0	Negative	
1	2	Classroom 208	Ceiling	Plaster	White	Flaking	200	0.1	Negative	
1	2	Classroom 208	Ceiling	2'x4' Ceiling Tile	Not Painted	N/A	N/A	N/A	N/A	
1	2	Classroom 208	Floor	Floor Tile	Not Painted	N/A	N/A	N/A	N/A	
1	2	Office 209	W1	Plaster	White/Blue	None	0	0	Negative	
1	2	Office 209	Doorframe	Metal	Brown	Friction	4	0.7	Positive	
1	2	Office 209	Conduit	Metal	White	None	0	1.2	Positive	
1	2	Office 209	W2	Plaster	White/Blue	None	0	0	Negative	
1	2	Office 209	W3	Plaster	White/Blue	None	0	0.1	Negative	
1	2	Office 209	Pipe Cover	Metal	White/Pink	Flaking	1	2.5	Positive	
1	2	Office 209	Pipe Insulation	Asbestos	White/Pink	None	0	0.1	Negative	
1	2	Office 209	Radiator cover	Metal	Brown	Chipping	4	0.8	Positive	
1	2	Office 209	W4	Plaster	White/Blue	None	0	0	Negative	
1	2	Office 209	Conduit	Plastic	Blue	None	0	0.2	Negative	
1	2	Office 209	Ceiling	Plaster	White	None	0	0.1	Negative	
1	2	Office 209	Ceiling	2'x4' Ceiling Tile	Not Painted	N/A	N/A	N/A	N/A	
1	2	Office 209	Floor	Linoleum	Not Painted	N/A	N/A	N/A	N/A	
1	2	Office 209 Closet	W1	Plaster	White	Cracking	40	0	Negative	
1	2	Office 209 Closet	Doorframe	Metal	Brown	Flaking	1	0.5	Negative	
1	2	Office 209 Closet	W2	Plaster	White	Cracking	40	0	Negative	
1	2	Office 209 Closet	Windowframe	Metal	Brown	None	0	0.7	Positive	
1	2	Office 209 Closet	W3	Plaster	White	Cracking	40	0	Negative	
1	2	Office 209 Closet	W4	Plaster	White	Cracking	30	0	Negative	
1	2	Office 209 Closet	Ceiling	Plaster	White	Cracking	15	0	Negative	
1	2	Office 209 Closet	Floor	Floor Covering	Not Painted	N/A	N/A	N/A	N/A	

		Dates: 6/5 - 7/6/2023	Lead-Safe Certification Assessment Report						
		Inspector Name and Certificate Number: Tim Smith 057662	John Bartram High School						
		Inspection Company: BATA	2401 S 67th St, Philadelphia PA 19142						
Element	Floor	On-Site Room Name	Component	Substrate Material [1]	Paint Color	Description of Paint Damage	Damage Quantity (sf) [2]	XRF Reading (mg/cm2)	XRF (positive/negative) [3]
1	2	Classroom 210	W1	Plaster	White/Pink	Cracking	10	0.5	Negative
1	2	Classroom 210	Doorframe	Metal	Brown	Chipping	6	0.9	Positive
1	2	Classroom 210	W2	Plaster	White/Pink	Flaking	10	0	Negative
1	2	Classroom 210	W3	Plaster	White/Pink	Flaking	10	0	Negative
1	2	Classroom 210	Pipe Cover	Metal	White/Pink	Cracking	6	3.1	Positive
1	2	Classroom 210	Pipe	Metal	White/Pink	Cracking	7	14.8	Positive
1	2	Classroom 210	Pipe Insulation	Asbestos	White/Pink	None	0	0.1	Negative
1	2	Classroom 210	Radiator cover	Metal	Brown	Chipping	2	0.5	Negative
1	2	Classroom 210	W4	Plaster	White/Pink	Flaking	8	0.5	Negative
1	2	Classroom 210	Conduit	Plastic	Pink	None	0	0.6	Negative
1	2	Classroom 210	Ceiling	Plaster	White	None	0	0.2	Negative
1	2	Classroom 210	Ceiling	2'x4' Ceiling Tile	Not Painted	N/A	N/A	N/A	N/A
1	2	Classroom 210	Floor	Wood	Not Painted	N/A	N/A	N/A	N/A
1	2	Office 210A	W1	Plaster	White/Pink	Cracking	6	0.5	Negative
1	2	Office 210A	Doorframe	Metal	Brown	Friction	4	1	Positive
1	2	Office 210A	W2	Plaster	White/Pink	None	0	0	Negative
1	2	Office 210A	W3	Plaster	White/Pink	None	0	0.1	Negative
1	2	Office 210A	Pipe Cover	Metal	White/Pink	None	0	3.7	Positive
1	2	Office 210A	Pipe Insulation	Asbestos	White/Pink	None	0	0	Negative
1	2	Office 210A	Radiator cover	Metal	Brown	Chipping	2	0.6	Negative
1	2	Office 210A	W4	Plaster	White/Pink	Efflorescence	16	0.1	Negative
1	2	Office 210A	Ceiling	Plaster	White	Efflorescence	12	0.3	Negative
1	2	Office 210A	Ceiling	2'x4' Ceiling Tile	Not Painted	N/A	N/A	N/A	N/A
1	2	Office 210A	Floor	Floor Tile	Not Painted	N/A	N/A	N/A	N/A
1	2	Office 210A Closet	W1	No Access	No Access	No Access	No Access	No Access	No Access
1	2	Office 210A Closet	W2	No Access	No Access	No Access	No Access	No Access	No Access

		Dates: 6/5 - 7/6/2023	Lead-Safe Certification Assessment Report							
		Inspector Name and Certificate Number: Tim Smith 057662	John Bartram High School							
		Inspection Company: BATA	2401 S 67th St, Philadelphia PA 19142							
E l e m e n t	F l o o r	On-Site Room Name	Component	Substrate Material [1]	Paint Color	Description of Paint Damage	Damage Quantity (sf) [2]	XRF Reading (mg/cm2)	XRF (positive/ negative) [3]	
1	2	Office 210A Closet	Doorframe	Metal	Brown	Friction	1	0.9	Positive	
1	2	Office 210A Closet	W3	No Access	No Access	No Access	No Access	No Access	No Access	
1	2	Office 210A Closet	W4	No Access	No Access	No Access	No Access	No Access	No Access	
1	2	Office 210A Closet	Ceiling	No Access	No Access	No Access	No Access	No Access	No Access	
1	2	Office 210A Closet	Floor	Wood	Not Painted	N/A	N/A	N/A	N/A	
1	2	Office 211	W1	Plaster	White/Pink	Cracking	30	0	Negative	
1	2	Office 211	Doorframe	Metal	Brown	Chipping	6	0.8	Positive	
1	2	Office 211	W2	Plaster	White/Pink	Cracking	60	0	Negative	
1	2	Office 211	W3	Plaster	White/Pink	Cracking	6	0.1	Negative	
1	2	Office 211	Pipe Cover	Metal	White/Pink	Flaking	6	2.9	Positive	
1	2	Office 211	Pipe Insulation	Asbestos	White/Pink	None	0	0	Negative	
1	2	Office 211	Radiator cover	Metal	Brown	Flaking	6	0	Negative	
1	2	Office 211	W4	Plaster	White/Pink	Cracking	40	0.1	Negative	
1	2	Office 211	Ceiling	Plaster	White	Flaking	20	0	Negative	
1	2	Office 211	Ceiling	2'x4' Ceiling Tile	Not Painted	N/A	N/A	N/A	N/A	
1	2	Office 211	Floor	Floor Covering	Not Painted	N/A	N/A	N/A	N/A	
1	2	Gym Office 211	W1	Plaster	White/Pink	Cracking	12	0.1	Negative	
1	2	Gym Office 211	Doorframe	Metal	Brown	Friction	3	0.6	Negative	
1	2	Gym Office 211	W2	Plaster	White/Pink	Cracking	12	0.1	Negative	
1	2	Gym Office 211	W3	Plaster	White/Pink	Cracking	20	0	Negative	
1	2	Gym Office 211	Pipe Cover	Metal	White/Pink	Chipping	1	4.1	Positive	
1	2	Gym Office 211	Pipe Insulation	Asbestos	White/Pink	None	0	0.1	Negative	
1	2	Gym Office 211	Radiator	Metal	Brown	None	0	0.4	Negative	
1	2	Gym Office 211	W4	Plaster	White/Pink	Cracking	4	0	Negative	
1	2	Gym Office 211	Ceiling	1'x1' Ceiling Tile	White	None	0	0.2	Negative	
1	2	Gym Office 211	Floor	Floor Covering	Not Painted	N/A	N/A	N/A	N/A	

		Dates: 6/5 - 7/6/2023	Lead-Safe Certification Assessment Report							
		Inspector Name and Certificate Number: Tim Smith 057662	John Bartram High School							
		Inspection Company: BATA	2401 S 67th St, Philadelphia PA 19142							
E l e m e n t	F l o o r	On-Site Room Name	Component	Substrate Material [1]	Paint Color	Description of Paint Damage	Damage Quantity (sf) [2]	XRF Reading (mg/cm2)	XRF (positive/ negative) [3]	
1	2	Gym Office 211 Restroom	W1	Plaster	White/Pink	Cracking	3	0	Negative	
1	2	Gym Office 211 Restroom	Doorframe	Metal	Brown	Friction	2	0.9	Positive	
1	2	Gym Office 211 Restroom	W2	Plaster	White/Pink	Cracking	12	0	Negative	
1	2	Gym Office 211 Restroom	W3	Plaster	White/Pink	Flaking	14	0	Negative	
1	2	Gym Office 211 Restroom	W4	Plaster	White/Pink	Cracking	20	0	Negative	
1	2	Gym Office 211 Restroom	Pipe Cover	Metal	White/Pink	None	0	3	Positive	
1	2	Gym Office 211 Restroom	Pipe Insulation	Asbestos	White/Pink	None	0	0.1	Negative	
1	2	Gym Office 211 Restroom	Radiator	Metal	Brown	None	0	0.2	Negative	
1	2	Gym Office 211 Restroom	Ceiling	1'x1' Ceiling Tile	White	None	0	0.1	Negative	
1	2	Gym Office 211 Restroom	Floor	Terrazzo	Not Painted	N/A	N/A	N/A	N/A	
1	2	Office 211B/212	W1	Plaster	White/Pink	Flaking	6	0	Negative	
1	2	Office 211B/212	Doorframe	Metal	Brown	Friction	3	0.7	Positive	
1	2	Office 211B/212	W2	Plaster	White/Pink	Cracking	16	0	Negative	
1	2	Office 211B/212	W3	Plaster	White/Pink	None	0	0.1	Negative	
1	2	Office 211B/212	Pipe Cover	Metal	White/Pink	None	0	4.1	Positive	
1	2	Office 211B/212	Pipe Insulation	Asbestos	White/Pink	None	0	0.1	Negative	
1	2	Office 211B/212	Radiator cover	Metal	Brown	None	0	0.2	Negative	
1	2	Office 211B/212	W4	Plaster	White/Pink	None	0	0.1	Negative	
1	2	Office 211B/212	Ceiling	1'x1' Ceiling Tile	White	None	0	0.1	Negative	
1	2	Office 211B/212	Floor	Floor Covering	Not Painted	N/A	N/A	N/A	N/A	
1	2	Gym Office 211 Closet	W1	Plaster	White	None	0	0.5	Negative	
1	2	Gym Office 211 Closet	Doorframe	Metal	Brown	Chipping	8	0.9	Positive	
1	2	Gym Office 211 Closet	W2	Plaster	White	Cracking	80	0	Negative	
1	2	Gym Office 211 Closet	W3	Plaster	White	Cracking	6	0.1	Negative	
1	2	Gym Office 211 Closet	Ladder	Metal	Brown	Friction	30	9.6	Positive	
1	2	Gym Office 211 Closet	Radiator	Metal	Brown	None	0	0.2	Negative	

		Dates: 6/5 - 7/6/2023	Lead-Safe Certification Assessment Report						
		Inspector Name and Certificate Number: Tim Smith 057662	John Bartram High School						
		Inspection Company: BATA	2401 S 67th St, Philadelphia PA 19142						
E l e m e n t	F l o o r	On-Site Room Name	Component	Substrate Material [1]	Paint Color	Description of Paint Damage	Damage Quantity (sf) [2]	XRF Reading (mg/cm2)	XRF (positive/ negative) [3]
1	2	Gym Office 211 Closet	Pipe Cover	Metal	White	None	0	4.5	Positive
1	2	Gym Office 211 Closet	Pipe Insulation	Asbestos	White	None	0	0.1	Negative
1	2	Gym Office 211 Closet	W4	Plaster	White	Cracking	80	0.4	Negative
1	2	Gym Office 211 Closet	Pipe	Metal	Tan	Flaking	10	14.5	Positive
1	2	Gym Office 211 Closet	Ceiling	Plaster	White	None	0	0.1	Negative
1	2	Gym Office 211 Closet	Floor	Floor Covering	Not Painted	N/A	N/A	N/A	N/A
1	2	Library	W1	Plaster	Blue	None	0	0.1	Negative
1	2	Library	Doorframe	Metal	Brown	Friction	3	0.4	Negative
1	2	Library	W2	Plaster	Blue	None	0	0.2	Negative
1	2	Library	Pipe Cover	Metal	Blue	None	0	4.5	Positive
1	2	Library	Conduit	Metal	Blue	None	0	0	Negative
1	2	Library	Pipe Insulation	Asbestos	Blue	None	0	0.1	Negative
1	2	Library	Radiator cover	Metal	Brown	Chipping	4	0.3	Negative
1	2	Library	W3	Plaster	Blue	None	0	0	Negative
1	2	Library	Column	Plaster	Blue	None	0	0.4	Negative
1	2	Library	W4	Plaster	Blue	None	0	0.1	Negative
1	2	Library	Pipe	Metal	Blue	None	0	23.3	Positive
1	2	Library	Ceiling	Plaster	Green	None	0	0.2	Negative
1	2	Library	Ceiling	2'x4' Ceiling Tile	Not Painted	N/A	N/A	N/A	N/A
1	2	Library	Floor	Carpet	Not Painted	N/A	N/A	N/A	N/A
1	2	Library Office	W1	Plaster	White/Pink	None	0	0	Negative
1	2	Library Office	Doorframe	Metal	Brown	Friction	6	0.9	Positive
1	2	Library Office	W2	Plaster	White/Pink	None	0	0.1	Negative
1	2	Library Office	W3	Plaster	White/Pink	None	0	0	Negative
1	2	Library Office	Pipe Cover	Metal	White/Pink	None	0	0.3	Negative
1	2	Library Office	Pipe	Metal	White/Pink	None	0	20.1	Positive

		Dates: 6/5 - 7/6/2023	Lead-Safe Certification Assessment Report							
		Inspector Name and Certificate Number: Tim Smith 057662	John Bartram High School							
		Inspection Company: BATA	2401 S 67th St, Philadelphia PA 19142							
E l e m e n t	F l o o r	On-Site Room Name	Component	Substrate Material [1]	Paint Color	Description of Paint Damage	Damage Quantity (sf) [2]	XRF Reading (mg/cm2)	XRF (positive/ negative) [3]	
1	2	Library Office	Pipe Insulation	Asbestos	White/Pink	None	0	0.1	Negative	
1	2	Library Office	Radiator cover	Metal	Brown	Chipping	2	0.8	Positive	
1	2	Library Office	W4	Plaster	White/Pink	Flaking	4	0	Negative	
1	2	Library Office	Ceiling	No Access	No Access	No Access	No Access	No Access	No Access	
1	2	Library Office	Floor	Floor Tile	Not Painted	N/A	N/A	N/A	N/A	
1	2	Classroom 214	W1	Plaster	White	None	0	0	Negative	
1	2	Classroom 214	Doorframe	Metal	Brown	Friction	6	0.9	Positive	
1	2	Classroom 214	W2	Plaster	White	Cracking	50	0.5	Negative	
1	2	Classroom 214	W3	Plaster	White	Flaking	2	0.5	Negative	
1	2	Classroom 214	Radiator cover	Metal	Brown	Friction	4	0.6	Negative	
1	2	Classroom 214	W4	Plaster	White	None	0	2.2	Positive	
1	2	Classroom 214	Ceiling	Concrete	Not Painted	N/A	N/A	N/A	N/A	
1	2	Classroom 214	Ceiling	2'x4' Ceiling Tile	Not Painted	N/A	N/A	N/A	N/A	
1	2	Classroom 214	Floor	Wood	Not Painted	N/A	N/A	N/A	N/A	
1	2	Classroom 215	W1	Plaster	Multi-Color	Cracking	4	0.1	Negative	
1	2	Classroom 215	Doorframe	Metal	Brown	Chipping	6	1	Positive	
1	2	Classroom 215	W2	Plaster	Multi-Color	Cracking	1	0.1	Negative	
1	2	Classroom 215	Conduit	Plastic	Blue	None	0	0.2	Negative	
1	2	Classroom 215	W3	Plaster	Multi-Color	Chipping	40	0.1	Negative	
1	2	Classroom 215	Radiator cover	Metal	Brown	Chipping	2	0.5	Negative	
1	2	Classroom 215	W4	Plaster	Multi-Color	None	0	0.1	Negative	
1	2	Classroom 215	Ceiling	Concrete	Not Painted	N/A	N/A	N/A	N/A	
1	2	Classroom 215	Ceiling	2'x4' Ceiling Tile	Not Painted	N/A	N/A	N/A	N/A	
1	2	Classroom 215	Floor	Wood	Not Painted	N/A	N/A	N/A	N/A	
1	2	Classroom 216	W1	Plaster	Green	Cracking	5	0.1	Negative	
1	2	Classroom 216	Doorframe	Metal	Brown	Chipping	3	0.6	Negative	

		Dates: 6/5 - 7/6/2023	Lead-Safe Certification Assessment Report						
		Inspector Name and Certificate Number: Tim Smith 057662	John Bartram High School						
		Inspection Company: BATA	2401 S 67th St, Philadelphia PA 19142						
E l e m e n t	F l o o r	On-Site Room Name	Component	Substrate Material [1]	Paint Color	Description of Paint Damage	Damage Quantity (sf) [2]	XRF Reading (mg/cm2)	XRF (positive/ negative) [3]
1	2	Classroom 216	Conduit	Plastic	Green	None	0	0.7	Positive
1	2	Classroom 216	W2	Plaster	Purple	Chipping	4	0	Negative
1	2	Classroom 216	W3	Plaster	Green	Chipping	12	0.2	Negative
1	2	Classroom 216	Pipe Insulation	Fiberglass	Black	None	0	0.1	Negative
1	2	Classroom 216	Radiator cover	Metal	Brown	Chipping	6	0.8	Positive
1	2	Classroom 216	W4	Plaster	Green	Chipping	20	0.1	Negative
1	2	Classroom 216	Ceiling	Concrete	Not Painted	N/A	N/A	N/A	N/A
1	2	Classroom 216	Ceiling	2'x4' Ceiling Tile	Not Painted	N/A	N/A	N/A	N/A
1	2	Classroom 216	Floor	Wood	Not Painted	N/A	N/A	N/A	N/A
1	2	Classroom 217	W1	Plaster	White/Pink	Cracking	24	0	Negative
1	2	Classroom 217	Doorframe	Metal	Brown	Chipping	4	0.8	Positive
1	2	Classroom 217	W2	Plaster	White/Pink	None	0	0.1	Negative
1	2	Classroom 217	W3	Plaster	White/Pink	Flaking	12	0	Negative
1	2	Classroom 217	Radiator cover	Metal	Brown	Chipping	2	0.6	Negative
1	2	Classroom 217	W4	Plaster	White/Pink	Cracking	6	0	Negative
1	2	Classroom 217	Conduit	Plastic	White/Pink	None	0	0.5	Negative
1	2	Classroom 217	Ceiling	Concrete	Not Painted	N/A	N/A	N/A	N/A
1	2	Classroom 217	Ceiling	2'x4' Ceiling Tile	Not Painted	N/A	N/A	N/A	N/A
1	2	Classroom 217	Floor	Wood	Not Painted	N/A	N/A	N/A	N/A
1	2	Pipe Shaft in Women's Restroom adjacent to 209	W1	No Access	No Access	No Access	No Access	No Access	No Access
1	2	Pipe Shaft in Women's Restroom adjacent to 209	Doorframe	Metal	Brown	Chipping	2	0.8	Positive
1	2	Pipe Shaft in Women's Restroom adjacent to 209	W2	No Access	No Access	No Access	No Access	No Access	No Access
1	2	Pipe Shaft in Women's Restroom adjacent to 209	W3	No Access	No Access	No Access	No Access	No Access	No Access
1	2	Pipe Shaft in Women's Restroom adjacent to 209	W4	No Access	No Access	No Access	No Access	No Access	No Access
1	2	Pipe Shaft in Women's Restroom adjacent to 209	Ceiling	No Access	No Access	No Access	No Access	No Access	No Access
1	2	Pipe Shaft in Women's Restroom adjacent to 209	Floor	No Access	No Access	No Access	No Access	No Access	No Access

		Dates: 6/5 - 7/6/2023	Lead-Safe Certification Assessment Report							
		Inspector Name and Certificate Number: Tim Smith 057662	John Bartram High School							
		Inspection Company: BATA	2401 S 67th St, Philadelphia PA 19142							
E l e m e n t	F l o o r	On-Site Room Name	Component	Substrate Material [1]	Paint Color	Description of Paint Damage	Damage Quantity (sf) [2]	XRF Reading (mg/cm2)	XRF (positive/ negative) [3]	
1	2	Women's Restroom adjacent to 209	W1	Plaster	White/Red	Cracking	12	0	Negative	
1	2	Women's Restroom adjacent to 209	Doorframe	Metal	Brown	Friction	6	0.8	Positive	
1	2	Women's Restroom adjacent to 209	Conduit	Plastic	White	None	0	0.3	Negative	
1	2	Women's Restroom adjacent to 209	W2	Plaster	White/Red	Flaking	14	0	Negative	
1	2	Women's Restroom adjacent to 209	W3	Plaster	White/Red	Cracking	10	0.1	Negative	
1	2	Women's Restroom adjacent to 209	Pipe Cover	Metal	White/Red	None	0	2.6	Positive	
1	2	Women's Restroom adjacent to 209	Pipe Insulation	Asbestos	White/Red	None	0	0.1	Negative	
1	2	Women's Restroom adjacent to 209	Radiator cover	Metal	Brown	Chipping	4	0.2	Negative	
1	2	Women's Restroom adjacent to 209	W4	Plaster	White/Red	Cracking	26	0.2	Negative	
1	2	Women's Restroom adjacent to 209	Ceiling	Plaster	White	Spalling	30	0.1	Negative	
1	2	Women's Restroom adjacent to 209	Floor	Floor Tile	Not Painted	N/A	N/A	N/A	N/A	
1	2	Men's Restroom next to storage room 2K	W1	Plaster	White/Red	Flaking	2	0.2	Negative	
1	2	Men's Restroom next to storage room 2K	Doorframe	Metal	Brown	Friction	4	1	Positive	
1	2	Men's Restroom next to storage room 2K	W2	Plaster	White/Red	Cracking	6	0.1	Negative	
1	2	Men's Restroom next to storage room 2K	W3	Plaster	White/Red	None	0	0	Negative	
1	2	Men's Restroom next to storage room 2K	Radiator cover	Metal	Brown	Chipping	8	0.8	Positive	
1	2	Men's Restroom next to storage room 2K	W4	Plaster	White/Red	None	0	0.1	Negative	
1	2	Men's Restroom next to storage room 2K	Conduit	Plastic	White	None	0	0.6	Negative	
1	2	Men's Restroom next to storage room 2K	Ceiling	Plaster	White	Flaking	170	0.4	Negative	
1	2	Men's Restroom next to storage room 2K	Floor	Floor Tile	Not Painted	N/A	N/A	N/A	N/A	
1	2	Classroom 218	W1	Plaster	White/Pink	Flaking	24	0.1	Negative	
1	2	Classroom 218	Doorframe	Metal	Brown	Chipping	3	0.8	Positive	
1	2	Classroom 218	W2	Plaster	White/Pink	Flaking	8	0.1	Negative	
1	2	Classroom 218	W3	Plaster	White/Pink	Chipping	30	0	Negative	
1	2	Classroom 218	Radiator cover	Metal	Brown	Chipping	6	0.1	Negative	
1	2	Classroom 218	W4	Plaster	White/Pink	None	0	0	Negative	

		Dates: 6/5 - 7/6/2023	Lead-Safe Certification Assessment Report							
		Inspector Name and Certificate Number: Tim Smith 057662	John Bartram High School							
		Inspection Company: BATTA	2401 S 67th St, Philadelphia PA 19142							
E l e m e n t	F l o o r	On-Site Room Name	Component	Substrate Material [1]	Paint Color	Description of Paint Damage	Damage Quantity (sf) [2]	XRF Reading (mg/cm2)	XRF (positive/ negative) [3]	
1	2	Classroom 218	Conduit	Plastic	Pink	None	0	0.4	Negative	
1	2	Classroom 218	Ceiling	Concrete	Not Painted	N/A	N/A	N/A	N/A	
1	2	Classroom 218	Ceiling	2'x4' Ceiling Tile	Not Painted	N/A	N/A	N/A	N/A	
1	2	Classroom 218	Floor	Wood	Not Painted	N/A	N/A	N/A	N/A	
1	2	Office 219	W1	Plaster	Purple/Blue	None	0	0	Negative	
1	2	Office 219	Doorframe	Metal	Brown	Chipping	1	0.9	Positive	
1	2	Office 219	W2	Plaster	Purple/Blue	Chipping	8	0.2	Negative	
1	2	Office 219	Conduit	Plastic	Purple	None	0	0.6	Negative	
1	2	Office 219	Conduit	Metal	Purple	None	0	0.3	Negative	
1	2	Office 219	W3	Plaster	Purple/Blue	None	0	0.2	Negative	
1	2	Office 219	Pipe Cover	Metal	Purple/Blue	None	0	2.9	Positive	
1	2	Office 219	Pipe Insulation	Asbestos	Purple/Blue	None	0	0.1	Negative	
1	2	Office 219	Radiator cover	Metal	Brown	Chipping	2	0.6	Negative	
1	2	Office 219	W4	Plaster	Purple/Blue	None	0	0.1	Negative	
1	2	Office 219	Ceiling	Plaster	White	None	0	0.3	Negative	
1	2	Office 219	Ceiling	2'x4' Ceiling Tile	Not Painted	N/A	N/A	N/A	N/A	
1	2	Office 219	Floor	Floor Tile	Not Painted	N/A	N/A	N/A	N/A	
1	2	Storage Closet in Office 219	W1	Plaster	White	Chipping	20	0.1	Negative	
1	2	Storage Closet in Office 219	Doorframe	Metal	Brown	None	0	0.9	Positive	
1	2	Storage Closet in Office 219	W2	Plaster	White	Cracking	30	0	Negative	
1	2	Storage Closet in Office 219	W3	Plaster	White	Cracking	30	0	Negative	
1	2	Storage Closet in Office 219	W4	Plaster	White	Cracking	20	0	Negative	
1	2	Storage Closet in Office 219	Windowframe	Metal	Brown	None	0	0.5	Negative	
1	2	Storage Closet in Office 219	Ceiling	Plaster	White	Cracking	5	0.2	Negative	
1	2	Storage Closet in Office 219	Floor	Wood	Not Painted	N/A	N/A	N/A	N/A	
1	2	Office 200A	W1	Plaster	Pink	None	0	0	Negative	

		Dates: 6/5 - 7/6/2023	Lead-Safe Certification Assessment Report							
		Inspector Name and Certificate Number: Tim Smith 057662	John Bartram High School							
		Inspection Company: BATA	2401 S 67th St, Philadelphia PA 19142							
E l e m e n t	F l o o r	On-Site Room Name	Component	Substrate Material [1]	Paint Color	Description of Paint Damage	Damage Quantity (sf) [2]	XRF Reading (mg/cm2)	XRF (positive/ negative) [3]	
1	2	Office 200A	Doorframe	Metal	Brown	Friction	8	0.9	Positive	
1	2	Office 200A	W2	Plaster	Pink	Flaking	8	0	Negative	
1	2	Office 200A	W3	Plaster	Pink	None	0	0.1	Negative	
1	2	Office 200A	Conduit	Plastic	Pink	None	0	0.1	Negative	
1	2	Office 200A	Conduit	Metal	Pink	None	0	1.1	Positive	
1	2	Office 200A	Pipe Cover	Metal	Pink	Flaking	1	3.1	Positive	
1	2	Office 200A	Pipe Insulation	Asbestos	Pink	None	0	0.1	Negative	
1	2	Office 200A	Radiator cover	Metal	Brown	Chipping	4	0.1	Negative	
1	2	Office 200A	W4	Plaster	Pink	None	0	0.1	Negative	
1	2	Office 200A	Ceiling	Plaster	White	Cracking	20	0.1	Negative	
1	2	Office 200A	Ceiling	2'x4' Ceiling Tile	Not Painted	N/A	N/A	N/A	N/A	
1	2	Office 200A	Floor	Floor Tile	Not Painted	N/A	N/A	N/A	N/A	
1	2	Weight room	W1	Ceramic	White	None	0	0.1	Negative	
1	2	Weight room	Doorframe	Metal	Brown	Friction	6	0.6	Negative	
1	2	Weight room	W2	Ceramic	White	None	0	0	Negative	
1	2	Weight room	Conduit	Plastic	White	None	0	0.4	Negative	
1	2	Weight room	W3	Ceramic	White	Flaking	20	0	Negative	
1	2	Weight room	Radiator	Metal	Brown	Chipping	6	0.1	Negative	
1	2	Weight room	W4	Ceramic	White	None	0	0	Negative	
1	2	Weight room	W4	CMU	White	Flaking	30	0.2	Negative	
1	2	Weight room	Ceiling	1'x1' Ceiling Tile	White	None	0	0.1	Negative	
1	2	Weight room	Fan Exhaust	Metal	White	Chipping	12	0.3	Negative	
1	2	Weight room	Floor	Wood	Not Painted	N/A	N/A	N/A	N/A	
1	2	Auditorium Balcony	W1	Plaster	White	None	0	0.5	Negative	
1	2	Auditorium Balcony	Doorframe	Wood	White	Chipping	8	6.3	Positive	
1	2	Auditorium Balcony	Door	Wood	White	Cracking	80	4.9	Positive	

		Dates: 6/5 - 7/6/2023	Lead-Safe Certification Assessment Report						
		Inspector Name and Certificate Number: Tim Smith 057662	John Bartram High School						
		Inspection Company: BATA	2401 S 67th St, Philadelphia PA 19142						
E l e m e n t	F l o o r	On-Site Room Name	Component	Substrate Material [1]	Paint Color	Description of Paint Damage	Damage Quantity (sf) [2]	XRF Reading (mg/cm2)	XRF (positive/ negative) [3]
1	2	Auditorium Balcony	Projector Door	Metal	White	None	0	0.4	Negative
1	2	Auditorium Balcony	W2	Plaster	White	None	0	0.1	Negative
1	2	Auditorium Balcony	Vent Under Seats	Metal	Brown	None	0	13.6	Positive
1	2	Auditorium Balcony	W3	Wood	White	Chipping	20	7.3	Positive
1	2	Auditorium Balcony	W4	Plaster	White	None	0	0	Negative
1	2	Auditorium Balcony	Ceiling	Plaster	White	Efflorescence	85	0	Negative
1	2	Auditorium Balcony	Floor	Wood	Not Painted	N/A	N/A	N/A	N/A
1	2	Classroom 221	W1	Plaster	Blue	None	0	0	Negative
1	2	Classroom 221	Blackboard Frame	Wood	Brown	None	0	0.2	Negative
1	2	Classroom 221	Doorframe	Metal	Brown	Friction	4	0.6	Negative
1	2	Classroom 221	W2	Plaster	Purple	None	0	0.5	Negative
1	2	Classroom 221	Conduit	Plastic	Purple	None	0	0.1	Negative
1	2	Classroom 221	W3	Plaster	Purple	None	0	0.4	Negative
1	2	Classroom 221	Pipe Cover	Metal	Purple	Chipping	1	2.8	Positive
1	2	Classroom 221	Pipe Insulation	Asbestos	Purple	None	0	0.1	Negative
1	2	Classroom 221	Radiator cover	Metal	Brown	Chipping	6	0.2	Negative
1	2	Classroom 221	W4	Plaster	Blue	None	0	0	Negative
1	2	Classroom 221	Ceiling	Plaster	White	None	0	0.3	Negative
1	2	Classroom 221	Ceiling	2'x4' Ceiling Tile	Not Painted	N/A	N/A	N/A	N/A
1	2	Classroom 221	Floor	Wood	Not Painted	N/A	N/A	N/A	N/A
1	2	Classroom 222	W1	Plaster	White	Flaking	8	0.1	Negative
1	2	Classroom 222	Doorframe	Metal	Brown	Friction	6	0.6	Negative
1	2	Classroom 222	Conduit	Plastic	White	None	0	0.3	Negative
1	2	Classroom 222	W2	Plaster	White	Flaking	6	0	Negative
1	2	Classroom 222	W3	Plaster	White	Flaking	30	0	Negative
1	2	Classroom 222	Pipe Cover	Metal	White	Flaking	3	3.7	Positive

		Dates: 6/5 - 7/6/2023	Lead-Safe Certification Assessment Report							
		Inspector Name and Certificate Number: Tim Smith 057662	John Bartram High School							
		Inspection Company: BATA	2401 S 67th St, Philadelphia PA 19142							
E l e m e n t	F l o o r	On-Site Room Name	Component	Substrate Material [1]	Paint Color	Description of Paint Damage	Damage Quantity (sf) [2]	XRF Reading (mg/cm2)	XRF (positive/ negative) [3]	
1	2	Classroom 222	Pipe Insulation	Asbestos	White	None	0	0.2	Negative	
1	2	Classroom 222	Radiator cover	Metal	Brown	Chipping	2	0.3	Negative	
1	2	Classroom 222	W4	Plaster	White	None	0	0.1	Negative	
1	2	Classroom 222	Ceiling	Plaster	White	Flaking	400	0.3	Negative	
1	2	Classroom 222	Ceiling	2'x4' Ceiling Tile	Not Painted	N/A	N/A	N/A	N/A	
1	2	Classroom 222	Floor	Wood	Not Painted	N/A	N/A	N/A	N/A	
1	2	Classroom 223	W1	Plaster	White/Pink	Cracking	30	2.7	Positive	
1	2	Classroom 223	Doorframe	Metal	Brown	Friction	6	0.6	Negative	
1	2	Classroom 223	W2	Plaster	White/Pink	Cracking	16	0.5	Negative	
1	2	Classroom 223	W3	Plaster	White/Pink	Cracking	60	0.1	Negative	
1	2	Classroom 223	Pipe Cover	Metal	White/Pink	Flaking	6	3	Positive	
1	2	Classroom 223	Pipe Insulation	Asbestos	White/Pink	None	0	0.1	Negative	
1	2	Classroom 223	Radiator cover	Metal	Brown	Chipping	6	0.8	Positive	
1	2	Classroom 223	W4	Plaster	White/Pink	Cracking	8	0.1	Negative	
1	2	Classroom 223	Conduit	Plastic	White/Pink	None	0	0.4	Negative	
1	2	Classroom 223	Ceiling	Plaster	White	None	0	0.2	Negative	
1	2	Classroom 223	Ceiling	2'x4' Ceiling Tile	Not Painted	N/A	N/A	N/A	N/A	
1	2	Classroom 223	Floor	Wood	Not Painted	N/A	N/A	N/A	N/A	
1	2	Classroom 224	W1	Plaster	Purple	Chipping	14	0	Negative	
1	2	Classroom 224	Doorframe	Metal	Brown	Chipping	3	0.7	Positive	
1	2	Classroom 224	W2	Plaster	Tan	Flaking	6	0	Negative	
1	2	Classroom 224	W3	Plaster	Purple	Flaking	30	0.4	Negative	
1	2	Classroom 224	Pipe	Metal	Purple	Chipping	5	5.2	Positive	
1	2	Classroom 224	Radiator cover	Metal	Brown	Chipping	4	0.6	Negative	
1	2	Classroom 224	W4	Plaster	Purple	None	0	0	Negative	
1	2	Classroom 224	Ceiling	Plaster	White	Flaking	320	0.2	Negative	

		Dates: 6/5 - 7/6/2023	Lead-Safe Certification Assessment Report							
		Inspector Name and Certificate Number: Tim Smith 057662	John Bartram High School							
		Inspection Company: BATA	2401 S 67th St, Philadelphia PA 19142							
E l e m e n t	F l o o r	On-Site Room Name	Component	Substrate Material [1]	Paint Color	Description of Paint Damage	Damage Quantity (sf) [2]	XRF Reading (mg/cm2)	XRF (positive/ negative) [3]	
1	2	Classroom 224	Ceiling	2'x4' Ceiling Tile	Not Painted	N/A	N/A	N/A	N/A	
1	2	Classroom 224	Floor	Wood	Not Painted	N/A	N/A	N/A	N/A	
1	2	Classroom 225	W1	Plaster	White/Pink	Cracking	8	0.1	Negative	
1	2	Classroom 225	Doorframe	Metal	Brown	Friction	4	0.6	Negative	
1	2	Classroom 225	W2	Plaster	White/Pink	None	0	0	Negative	
1	2	Classroom 225	W3	Plaster	White/Pink	Flaking	20	0	Negative	
1	2	Classroom 225	Pipe	Metal	White/Pink	Chipping	6	19	Positive	
1	2	Classroom 225	Pipe Cover	Metal	White/Pink	Chipping	5	2.6	Positive	
1	2	Classroom 225	Pipe Insulation	Asbestos	White/Pink	None	0	0.1	Negative	
1	2	Classroom 225	Radiator cover	Metal	Brown	Chipping	6	0.6	Negative	
1	2	Classroom 225	W4	Plaster	White/Pink	Chipping	16	0.1	Negative	
1	2	Classroom 225	Ceiling	Plaster	White	None	0	0.4	Negative	
1	2	Classroom 225	Ceiling	2'x4' Ceiling Tile	Not Painted	N/A	N/A	N/A	N/A	
1	2	Classroom 225	Floor	Wood	Not Painted	N/A	N/A	N/A	N/A	
1	2	Classroom 226	W1	Plaster	White	Cracking	10	0.1	Negative	
1	2	Classroom 226	Doorframe	Metal	Brown	Friction	6	1	Positive	
1	2	Classroom 226	W2	Plaster	White	Cracking	6	0	Negative	
1	2	Classroom 226	Conduit	Plastic	White	None	0	0.2	Negative	
1	2	Classroom 226	W3	Plaster	White	Flaking	20	0.1	Negative	
1	2	Classroom 226	Pipe Cover	Metal	White	None	0	2.2	Positive	
1	2	Classroom 226	Pipe Insulation	Asbestos	White	None	0	0.1	Negative	
1	2	Classroom 226	Radiator cover	Metal	Brown	Chipping	6	0.5	Negative	
1	2	Classroom 226	W4	Plaster	White	None	0	0.5	Negative	
1	2	Classroom 226	Ceiling	Plaster	White	None	0	0.1	Negative	
1	2	Classroom 226	Ceiling	2'x4' Ceiling Tile	Not Painted	N/A	N/A	N/A	N/A	
1	2	Classroom 226	Floor	Wood	Not Painted	N/A	N/A	N/A	N/A	

		Dates: 6/5 - 7/6/2023	Lead-Safe Certification Assessment Report						
		Inspector Name and Certificate Number: Tim Smith 057662	John Bartram High School						
		Inspection Company: BATA	2401 S 67th St, Philadelphia PA 19142						
E l e m e n t	F l o o r	On-Site Room Name	Component	Substrate Material [1]	Paint Color	Description of Paint Damage	Damage Quantity (sf) [2]	XRF Reading (mg/cm2)	XRF (positive/ negative) [3]
1	2	Classroom 227	W1	Plaster	White/Pink	Cracking	12	0.1	Negative
1	2	Classroom 227	Doorframe	Metal	Brown	Friction	4	0.5	Negative
1	2	Classroom 227	W2	Plaster	White/Pink	Cracking	30	0.1	Negative
1	2	Classroom 227	W3	Plaster	White/Pink	Cracking	60	0.1	Negative
1	2	Classroom 227	Pipe	Metal	White/Pink	Chipping	8	16.5	Positive
1	2	Classroom 227	Pipe Cover	Metal	White/Pink	Chipping	4	2.9	Positive
1	2	Classroom 227	Pipe Insulation	Asbestos	White/Pink	None	0	0.1	Negative
1	2	Classroom 227	Radiator cover	Metal	Brown	Chipping	6	0.8	Positive
1	2	Classroom 227	W4	Plaster	White/Pink	Cracking	14	0.2	Negative
1	2	Classroom 227	Ceiling	Plaster	White	None	0	0.2	Negative
1	2	Classroom 227	Ceiling	2'x4' Ceiling Tile	Not Painted	N/A	N/A	N/A	N/A
1	2	Classroom 227	Floor	Wood	Not Painted	N/A	N/A	N/A	N/A
1	2	Classroom 228	W1	Plaster	White/Pink	Flaking	26	0.4	Negative
1	2	Classroom 228	Doorframe	Metal	Brown	Friction	4	0.6	Negative
1	2	Classroom 228	W2	Plaster	White/Pink	Flaking	1	0.4	Negative
1	2	Classroom 228	W3	Plaster	White/Pink	Flaking	56	0	Negative
1	2	Classroom 228	Pipe	Metal	White/Pink	None	0	0.1	Negative
1	2	Classroom 228	Pipe Cover	Metal	White/Pink	Chipping	4	2.7	Positive
1	2	Classroom 228	Pipe Insulation	Asbestos	White/Pink	None	0	0	Negative
1	2	Classroom 228	Radiator cover	Metal	Brown	Chipping	6	0.4	Negative
1	2	Classroom 228	W4	Plaster	White/Pink	Cracking	3	0.4	Negative
1	2	Classroom 228	Ceiling	Plaster	White	Flaking	360	0.2	Negative
1	2	Classroom 228	Ceiling	2'x4' Ceiling Tile	Not Painted	N/A	N/A	N/A	N/A
1	2	Classroom 228	Floor	Wood	Not Painted	N/A	N/A	N/A	N/A
1	2	Classroom 229	W1	Plaster	White/Pink	Cracking	26	0.1	Negative
1	2	Classroom 229	Doorframe	Metal	Brown	Chipping	10	1	Positive

		Dates: 6/5 - 7/6/2023	Lead-Safe Certification Assessment Report						
		Inspector Name and Certificate Number: Tim Smith 057662	John Bartram High School						
		Inspection Company: BATA	2401 S 67th St, Philadelphia PA 19142						
E l e m e n t	F l o o r	On-Site Room Name	Component	Substrate Material [1]	Paint Color	Description of Paint Damage	Damage Quantity (sf) [2]	XRF Reading (mg/cm2)	XRF (positive/ negative) [3]
1	2	Classroom 229	W2	Plaster	White/Pink	None	0	0	Negative
1	2	Classroom 229	W3	Plaster	White/Pink	Cracking	30	0.4	Negative
1	2	Classroom 229	Pipe Cover	Metal	White/Pink	Chipping	6	3.7	Positive
1	2	Classroom 229	Pipe Insulation	Asbestos	White/Pink	None	0	0	Negative
1	2	Classroom 229	Radiator cover	Metal	Brown	Chipping	3	0.4	Negative
1	2	Classroom 229	W4	Plaster	White/Pink	Cracking	40	0.1	Negative
1	2	Classroom 229	Ceiling	Plaster	White	Flaking	200	0.3	Negative
1	2	Classroom 229	Ceiling	2'x4' Ceiling Tile	Not Painted	N/A	N/A	N/A	N/A
1	2	Classroom 229	Floor	Wood	Not Painted	N/A	N/A	N/A	N/A
1	2	Classroom 230	W1	Plaster	Blue	Flaking	20	0	Negative
1	2	Classroom 230	Doorframe	Metal	Brown	Chipping	3	0.6	Negative
1	2	Classroom 230	W2	Plaster	White/Pink	None	0	0.5	Negative
1	2	Classroom 230	W3	Plaster	blue	Cracking	6	0.4	Negative
1	2	Classroom 230	Pipe Cover	Metal	White/Pink	Chipping	15	2.5	Positive
1	2	Classroom 230	Pipe Insulation	Asbestos	White/Pink	None	0	0.1	Negative
1	2	Classroom 230	Radiator cover	Metal	Brown	Chipping	6	0.3	Negative
1	2	Classroom 230	W4	Plaster	Blue	None	0	0.1	Negative
1	2	Classroom 230	Conduit	Plastic	Blue	None	0	0.4	Negative
1	2	Classroom 230	Blackboard Ledge	Wood	Not Painted	N/A	N/A	N/A	N/A
1	2	Classroom 230	Ceiling	Plaster	White	Flaking	600	0.3	Negative
1	2	Classroom 230	Ceiling	2'x4' Ceiling Tile	Not Painted	N/A	N/A	N/A	N/A
1	2	Classroom 230	Floor	Wood	Not Painted	N/A	N/A	N/A	N/A
1	2	Office 231	W1	Plaster	Tan	None	0	0	Negative
1	2	Office 231	Doorframe	Metal	Brown	Friction	5	0.9	Positive
1	2	Office 231	W2	Plaster	Tan	None	0	0.1	Negative
1	2	Office 231	W3	Plaster	Tan	None	0	0.1	Negative

		Dates: 6/5 - 7/6/2023	Lead-Safe Certification Assessment Report						
		Inspector Name and Certificate Number: Tim Smith 057662	John Bartram High School						
		Inspection Company: BATA	2401 S 67th St, Philadelphia PA 19142						
E l e m e n t	F l o o r	On-Site Room Name	Component	Substrate Material [1]	Paint Color	Description of Paint Damage	Damage Quantity (sf) [2]	XRF Reading (mg/cm ²)	XRF (positive/ negative) [3]
1	2	Office 231	Pipe Cover	Metal	Tan	None	0	3.7	Positive
1	2	Office 231	Pipe Insulation	Asbestos	Tan	None	0	0	Negative
1	2	Office 231	Radiator cover	Metal	Brown	Chipping	2	0.5	Negative
1	2	Office 231	W4	Plaster	Tan	None	0	0	Negative
1	2	Office 231	Conduit	Plastic	Tan	None	0	0.3	Negative
1	2	Office 231	Ceiling	Plaster	White	None	0	0.3	Negative
1	2	Office 231	Ceiling	2'x4' Ceiling Tile	Not Painted	N/A	N/A	N/A	N/A
1	2	Office 231	Floor	Wood	Not Painted	N/A	N/A	N/A	N/A
1	2	Classroom 232	W1	Plaster	White	Flaking	20	0	Negative
1	2	Classroom 232	Doorframe	Metal	Brown	Friction	6	0.5	Negative
1	2	Classroom 232	W2	Plaster	White	Flaking	8	0.3	Negative
1	2	Classroom 232	W3	Plaster	White	Flaking	52	0.1	Negative
1	2	Classroom 232	Pipe	Metal	White	Chipping	5	14.6	Positive
1	2	Classroom 232	Pipe Cover	Metal	White	Chipping	4	2.8	Positive
1	2	Classroom 232	Pipe Insulation	Asbestos	White	None	0	0.1	Negative
1	2	Classroom 232	Radiator cover	Metal	Brown	Chipping	6	0.8	Positive
1	2	Classroom 232	W4	Plaster	White	Flaking	20	0.2	Negative
1	2	Classroom 232	Ceiling	Plaster	White	Flaking	400	0.2	Negative
1	2	Classroom 232	Ceiling	2'x4' Ceiling Tile	Not Painted	N/A	N/A	N/A	N/A
1	2	Classroom 232	Floor	Wood	Not Painted	N/A	N/A	N/A	N/A
1	2	Office 234	W1	Plaster	Green	None	0	0.5	Negative
1	2	Office 234	Doorframe	Metal	Brown	Friction	6	0.5	Negative
1	2	Office 234	W2	Plaster	Green	None	0	0	Negative
1	2	Office 234	Conduit	Plastic	Green	None	0	0.4	Negative
1	2	Office 234	W3	Plaster	Green	None	0	0	Negative
1	2	Office 234	Pipe Cover	Metal	Green	None	0	4.5	Positive

		Dates: 6/5 - 7/6/2023	Lead-Safe Certification Assessment Report							
		Inspector Name and Certificate Number: Tim Smith 057662	John Bartram High School							
		Inspection Company: BATA	2401 S 67th St, Philadelphia PA 19142							
E l e m e n t	F l o o r	On-Site Room Name	Component	Substrate Material [1]	Paint Color	Description of Paint Damage	Damage Quantity (sf) [2]	XRF Reading (mg/cm ²)	XRF (positive/ negative) [3]	
1	2	Office 234	Pipe Insulation	Asbestos	Green	None	0	0	Negative	
1	2	Office 234	Radiator cover	Metal	Brown	Chipping	8	0.5	Negative	
1	2	Office 234	W4	Plaster	Green	None	0	0.1	Negative	
1	2	Office 234	Ceiling	Plaster	White	None	0	0.4	Negative	
1	2	Office 234	Ceiling	2'x4' Ceiling Tile	Not Painted	N/A	N/A	N/A	N/A	
1	2	Office 234	Floor	Wood	Not Painted	N/A	N/A	N/A	N/A	
1	2	Office 234 - Closet	W1	Plaster	White	Cracking	30	0	Negative	
1	2	Office 234 - Closet	Doorframe	Metal	Brown	Chipping	1	0.8	Positive	
1	2	Office 234 - Closet	W2	Plaster	White	Cracking	20	0	Negative	
1	2	Office 234 - Closet	Windowframe	Metal	Brown	None	0	0.5	Negative	
1	2	Office 234 - Closet	W3	Plaster	White	Cracking	40	0	Negative	
1	2	Office 234 - Closet	W4	Plaster	White	Cracking	20	0.4	Negative	
1	2	Office 234 - Closet	Ceiling	Plaster	White	Cracking	4	0.4	Negative	
1	2	Office 234 - Closet	Floor	Wood	Not Painted	N/A	N/A	N/A	N/A	
1	2	Boys Gym Office 236	W1	Plaster	Orange	Chipping	3	0.1	Negative	
1	2	Boys Gym Office 236	Chair Rail	Wood	Orange	None	0	0.1	Negative	
1	2	Boys Gym Office 236	Conduit	Plastic	Orange	None	0	0.3	Negative	
1	2	Boys Gym Office 236	Doorframe	Metal	Brown	Chipping	1	0.2	Negative	
1	2	Boys Gym Office 236	W2	Plaster	Orange	None	0	0	Negative	
1	2	Boys Gym Office 236	Covebase	Wood	Brown	None	0	0.2	Negative	
1	2	Boys Gym Office 236	W3	Plaster	Orange	None	0	0.1	Negative	
1	2	Boys Gym Office 236	Pipe Cover	Metal	Orange	None	0	2	Positive	
1	2	Boys Gym Office 236	Pipe Insulation	Asbestos	Orange	None	0	0.1	Negative	
1	2	Boys Gym Office 236	Radiator cover	Metal	Brown	Friction	2	0.3	Negative	
1	2	Boys Gym Office 236	Windowsill	Wood	Brown	Friction	4	0.2	Negative	
1	2	Boys Gym Office 236	W4	Plaster	Orange	None	0	0.2	Negative	

		Dates: 6/5 - 7/6/2023	Lead-Safe Certification Assessment Report							
		Inspector Name and Certificate Number: Tim Smith 057662	John Bartram High School							
		Inspection Company: BATA	2401 S 67th St, Philadelphia PA 19142							
E l e m e n t	F l o o r	On-Site Room Name	Component	Substrate Material [1]	Paint Color	Description of Paint Damage	Damage Quantity (sf) [2]	XRF Reading (mg/cm2)	XRF (positive/ negative) [3]	
1	2	Boys Gym Office 236	Blackboard Ledge	Wood	Brown	None	0	0.1	Negative	
1	2	Boys Gym Office 236	Ceiling	Plaster	White	None	0	0.2	Negative	
1	2	Boys Gym Office 236	Ceiling	2'x4' Ceiling Tile	Not Painted	N/A	N/A	N/A	N/A	
1	2	Boys Gym Office 236	Floor	Floor Tile	Not Painted	N/A	N/A	N/A	N/A	
1	2	Closet inside the Boys Gym Office overlooking Gymnasium	W1	Plaster	White	None	0	0	Negative	
1	2	Closet inside the Boys Gym Office overlooking Gymnasium	Conduit	Plastic	White	None	0	0.1	Negative	
1	2	Closet inside the Boys Gym Office overlooking Gymnasium	Doorframe	Metal	Brown	None	0	0.8	Positive	
1	2	Closet inside the Boys Gym Office overlooking Gymnasium	W2	Plaster	White	Chipping	4	0	Negative	
1	2	Closet inside the Boys Gym Office overlooking Gymnasium	W3	Plaster	White	None	0	0	Negative	
1	2	Closet inside the Boys Gym Office overlooking Gymnasium	W4	Plaster	White	None	0	0	Negative	
1	2	Closet inside the Boys Gym Office overlooking Gymnasium	Ceiling	Plaster	White	None	0	0.1	Negative	
1	2	Closet inside the Boys Gym Office overlooking Gymnasium	Floor	Floor Covering	Not Painted	N/A	N/A	N/A	N/A	
1	2	Restroom inside Boys Gym Office overlooking Gymnasium	W1	Plaster	White	Cracking	8	0	Negative	
1	2	Restroom inside Boys Gym Office overlooking Gymnasium	Doorframe	Metal	Brown	Chipping	1	0.9	Positive	
1	2	Restroom inside Boys Gym Office overlooking Gymnasium	W2	Plaster	White	None	0	0.1	Negative	
1	2	Restroom inside Boys Gym Office overlooking Gymnasium	Pipe Cover	Metal	White	None	0	3.7	Positive	
1	2	Restroom inside Boys Gym Office overlooking Gymnasium	Pipe Insulation	Asbestos	White	None	0	0	Negative	

		Dates: 6/5 - 7/6/2023	Lead-Safe Certification Assessment Report						
		Inspector Name and Certificate Number: Tim Smith 057662	John Bartram High School						
		Inspection Company: BATA	2401 S 67th St, Philadelphia PA 19142						
E l e m e n t	F l o o r	On-Site Room Name	Component	Substrate Material [1]	Paint Color	Description of Paint Damage	Damage Quantity (sf) [2]	XRF Reading (mg/cm2)	XRF (positive/ negative) [3]
1	2	Restroom inside Boys Gym Office overlooking Gymnasium	Cabinet	Wood	White	None	0	0.1	Negative
1	2	Restroom inside Boys Gym Office overlooking Gymnasium	W3	Plaster	White	Cracking	6	0	Negative
1	2	Restroom inside Boys Gym Office overlooking Gymnasium	Radiator cover	Metal	Brown	None	0	0.1	Negative
1	2	Restroom inside Boys Gym Office overlooking Gymnasium	W4	Plaster	White	Cracking	12	0	Negative
1	2	Restroom inside Boys Gym Office overlooking Gymnasium	Ceiling	1'x1' Ceiling Tile	White	None	0	0	Negative
1	2	Restroom inside Boys Gym Office overlooking Gymnasium	Floor	Terrazzo	Not Painted	N/A	N/A	N/A	N/A
1	2	Boys Gym Office overlooking Gymnasium - next to Stairwell to Gym	W1	Plaster	White/Pink	Cracking	4	0.1	Negative
1	2	Boys Gym Office overlooking Gymnasium - next to Stairwell to Gym	Doorframe	Metal	Brown	Friction	2	0.5	Negative
1	2	Boys Gym Office overlooking Gymnasium - next to Stairwell to Gym	W2	Plaster	White/Pink	Cracking	10	0	Negative
1	2	Boys Gym Office overlooking Gymnasium - next to Stairwell to Gym	W3	Plaster	Black/Pink	None	0	0.1	Negative
1	2	Boys Gym Office overlooking Gymnasium - next to Stairwell to Gym	W4	Plaster	White/Pink	None	0	0	Negative
1	2	Boys Gym Office overlooking Gymnasium - next to Stairwell to Gym	Pipe Cover	Metal	White/Pink	Chipping	1	3.1	Positive
1	2	Boys Gym Office overlooking Gymnasium - next to Stairwell to Gym	Pipe Insulation	Asbestos	White/Pink	None	0	0.1	Negative
1	2	Boys Gym Office overlooking Gymnasium - next to Stairwell to Gym	Radiator cover	Metal	Brown	None	0	0.3	Negative
1	2	Boys Gym Office overlooking Gymnasium - next to Stairwell to Gym	Ceiling	1'x1' Ceiling Tile	White	None	0	0.1	Negative

		Dates: 6/5 - 7/6/2023	Lead-Safe Certification Assessment Report						
		Inspector Name and Certificate Number: Tim Smith 057662	John Bartram High School						
		Inspection Company: BATA	2401 S 67th St, Philadelphia PA 19142						
E l e m e n t	F l o o r	On-Site Room Name	Component	Substrate Material [1]	Paint Color	Description of Paint Damage	Damage Quantity (sf) [2]	XRF Reading (mg/cm2)	XRF (positive/ negative) [3]
1	2	Boys Gym Office overlooking Gymnasium - next to Stairwell to Gym	Floor	Floor Covering	Not Painted	N/A	N/A	N/A	N/A
1	2	Stairs to Gym next to Boys Gym Office overlooking Gymnasium	W1	Plaster	White	Chipping	12	0.2	Negative
1	2	Stairs to Gym next to Boys Gym Office overlooking Gymnasium	Doorframe	Metal	Brown	Friction	4	0.8	Positive
1	2	Stairs to Gym next to Boys Gym Office overlooking Gymnasium	W2	Plaster	White	None	0	0.1	Negative
1	2	Stairs to Gym next to Boys Gym Office overlooking Gymnasium	W3	Plaster	White	Cracking	30	0.2	Negative
1	2	Stairs to Gym next to Boys Gym Office overlooking Gymnasium	Riser	Concrete	Brown	Friction	12	0.5	Negative
1	2	Stairs to Gym next to Boys Gym Office overlooking Gymnasium	Post	Metal	Brown	Chipping	1	9.4	Positive
1	2	Stairs to Gym next to Boys Gym Office overlooking Gymnasium	Stringer	Concrete	Brown	None	0	0.5	Negative
1	2	Stairs to Gym next to Boys Gym Office overlooking Gymnasium	Baluster	Metal	Brown	None	0	8.3	Positive
1	2	Stairs to Gym next to Boys Gym Office overlooking Gymnasium	W4	Plaster	White	Cracking	20	0.1	Negative
1	2	Stairs to Gym next to Boys Gym Office overlooking Gymnasium	Covebase	Concrete	Brown	Friction	12	0.3	Negative
1	2	Stairs to Gym next to Boys Gym Office overlooking Gymnasium	Ceiling	Plaster	White	None	0	0.3	Negative
1	2	Stairs to Gym next to Boys Gym Office overlooking Gymnasium	Floor	Concrete	Not Painted	N/A	N/A	N/A	N/A
1	2	Conference Room 212 Adjacent to Projector Room 2C	W1	No Access	No Access	No Access	No Access	No Access	No Access
1	2	Conference Room 212 Adjacent to Projector Room 2C	W2	No Access	No Access	No Access	No Access	No Access	No Access

		Dates: 6/5 - 7/6/2023	Lead-Safe Certification Assessment Report						
		Inspector Name and Certificate Number: Tim Smith 057662	John Bartram High School						
		Inspection Company: BATA	2401 S 67th St, Philadelphia PA 19142						
E l e m e n t	F l o o r	On-Site Room Name	Component	Substrate Material [1]	Paint Color	Description of Paint Damage	Damage Quantity (sf) [2]	XRF Reading (mg/cm2)	XRF (positive/ negative) [3]
1	2	Conference Room 212 Adjacent to Projector Room 2C	W3	No Access	No Access	No Access	No Access	No Access	No Access
1	2	Conference Room 212 Adjacent to Projector Room 2C	W4	No Access	No Access	No Access	No Access	No Access	No Access
1	2	Conference Room 212 Adjacent to Projector Room 2C	Ceiling	No Access	No Access	No Access	No Access	No Access	No Access
1	2	Conference Room 212 Adjacent to Projector Room 2C	Floor	No Access	No Access	No Access	No Access	No Access	No Access
1	2	Storage Closet next to Girl's Restroom	W1	Plaster	Blue	Cracking	10	0	Negative
1	2	Storage Closet next to Girl's Restroom	Doorframe	Metal	Brown	Friction	12	0.8	Positive
1	2	Storage Closet next to Girl's Restroom	W2	Plaster	Blue	Cracking	80	0.1	Negative
1	2	Storage Closet next to Girl's Restroom	Covebase	Concrete	Grey	Cracking	20	0.1	Negative
1	2	Storage Closet next to Girl's Restroom	W3	Plaster	Blue	Cracking	40	0.1	Negative
1	2	Storage Closet next to Girl's Restroom	W4	Plaster	Blue	Cracking	80	0.1	Negative
1	2	Storage Closet next to Girl's Restroom	Ceiling	Plaster	White	Cracking	16	0.1	Negative
1	2	Storage Closet next to Girl's Restroom	Floor	Concrete	Grey	Friction	50	0.1	Negative
1	2	Boy's Restroom next to 220A	W1	Ceramic	White	None	0	0	Negative
1	2	Boy's Restroom next to 220A	Doorframe	Metal	Brown	Friction	3	0.5	Negative
1	2	Boy's Restroom next to 220A	Door	Wood	Brown	Chipping	1	0.1	Negative
1	2	Boy's Restroom next to 220A	Stall	Polymer	White	None	0	0.3	Negative
1	2	Boy's Restroom next to 220A	W2	Ceramic	White	None	0	0.1	Negative
1	2	Boy's Restroom next to 220A	Pipe Cover	Metal	Brown	None	0	4	Positive
1	2	Boy's Restroom next to 220A	Pipe Insulation	Asbestos	White	None	0	0.2	Negative
1	2	Boy's Restroom next to 220A	Radiator cover	Metal	Brown	Chipping	6	0	Negative
1	2	Boy's Restroom next to 220A	W3	Ceramic	White	None	0	0	Negative
1	2	Boy's Restroom next to 220A	W4	Ceramic	White	None	0	0.1	Negative
1	2	Boy's Restroom next to 220A	Pipe	Metal	White	None	0	14.2	Positive

		Dates: 6/5 - 7/6/2023	Lead-Safe Certification Assessment Report							
		Inspector Name and Certificate Number: Tim Smith 057662	John Bartram High School							
		Inspection Company: BATA	2401 S 67th St, Philadelphia PA 19142							
E l e m e n t	F l o o r	On-Site Room Name	Component	Substrate Material [1]	Paint Color	Description of Paint Damage	Damage Quantity (sf) [2]	XRF Reading (mg/cm2)	XRF (positive/ negative) [3]	
1	2	Boy's Restroom next to 220A	Ceiling	Plaster	White	Flaking	140	0	Negative	
1	2	Boy's Restroom next to 220A	Floor	Terrazzo	Not Painted	N/A	N/A	N/A	N/A	
1	2	Projector Room #1	W1	Plaster	White	Cracking	10	0.4	Negative	
1	2	Projector Room #1	Door	Metal	Brown	Chipping	2	0.4	Negative	
1	2	Projector Room #1	Doorframe	Metal	Brown	Chipping	6	0.7	Positive	
1	2	Projector Room #1	Conduit	Plastic	White	None	0	0.2	Negative	
1	2	Projector Room #1	W2	Plaster	White	Cracking	12	0.2	Negative	
1	2	Projector Room #1	Riser	Concrete	Brown	None	0	0.5	Negative	
1	2	Projector Room #1	Tread	Concrete	Black	None	0	0	Negative	
1	2	Projector Room #1	Railing	Metal	Brown	Chipping	8	0.7	Positive	
1	2	Projector Room #1	Stringer	Concrete	Brown	None	0	0.3	Negative	
1	2	Projector Room #1	W3	Plaster	White	Cracking	30	0	Negative	
1	2	Projector Room #1	Covebase	Concrete	Brown	None	0	0.2	Negative	
1	2	Projector Room #1	W4	Plaster	White	Cracking	14	0	Negative	
1	2	Projector Room #1	Ceiling	Concrete	White	None	0	0.3	Negative	
1	2	Projector Room #1	Floor	Concrete	Grey	Friction	60	0.2	Negative	
1	2	Projector Room #2	W1	Plaster	White	Flaking	3	0	Negative	
1	2	Projector Room #2	Door	Metal	Brown	None	0	0.3	Negative	
1	2	Projector Room #2	Doorframe	Metal	Brown	Friction	4	0.7	Positive	
1	2	Projector Room #2	Conduit	Plastic	White	None	0	0.3	Negative	
1	2	Projector Room #2	W2	Plaster	White	Flaking	10	0	Negative	
1	2	Projector Room #2	Conduit	Metal	White	Flaking	2	0.3	Negative	
1	2	Projector Room #2	Riser	Concrete	Brown	None	0	0.5	Negative	
1	2	Projector Room #2	Tread	Concrete	Black	None	0	0	Negative	
1	2	Projector Room #2	Railing	Metal	Brown	Chipping	4	2.2	Positive	
1	2	Projector Room #2	Stringer	Concrete	Brown	None	0	0.3	Negative	

		Dates: 6/5 - 7/6/2023	Lead-Safe Certification Assessment Report						
		Inspector Name and Certificate Number: Tim Smith 057662	John Bartram High School						
		Inspection Company: BATA	2401 S 67th St, Philadelphia PA 19142						
E l e m e n t	F l o o r	On-Site Room Name	Component	Substrate Material [1]	Paint Color	Description of Paint Damage	Damage Quantity (sf) [2]	XRF Reading (mg/cm ²)	XRF (positive/ negative) [3]
1	2	Projector Room #2	W3	Plaster	White	Cracking	3	0.1	Negative
1	2	Projector Room #2	Covebase	Concrete	Brown	None	0	0	Negative
1	2	Projector Room #2	W4	Plaster	White	Cracking	6	0	Negative
1	2	Projector Room #2	Ceiling	Concrete	White	None	0	0.2	Negative
1	2	Projector Room #2	Floor	Concrete	Grey	None	0	0.2	Negative
1	2	Main Hallway Service Closet 2-E	W1	Plaster	White/Grey	Cracking	3	0.1	Negative
1	2	Main Hallway Service Closet 2-E	Doorframe	Metal	Brown	Friction	4	0.8	Positive
1	2	Main Hallway Service Closet 2-E	W2	Plaster	White/Grey	Flaking	10	0.2	Negative
1	2	Main Hallway Service Closet 2-E	Shelf	Wood	White	Chipping	2	0	Negative
1	2	Main Hallway Service Closet 2-E	Covebase	Concrete	Grey	Chipping	10	0.2	Negative
1	2	Main Hallway Service Closet 2-E	W3	Plaster	White/Grey	Flaking	14	0.1	Negative
1	2	Main Hallway Service Closet 2-E	Sink	Ceramic	Grey	Chipping	2	1.1	Positive
1	2	Main Hallway Service Closet 2-E	W4	Plaster	White/Grey	None	0	0	Negative
1	2	Main Hallway Service Closet 2-E	Ceiling	Plaster	White	Cracking	4	0.3	Negative
1	2	Main Hallway Service Closet 2-E	Floor	Concrete	Grey	Friction	12	0.2	Negative
1	2	Pipe Chase in Service Closet 2-E	W1	Concrete	Not Painted	N/A	N/A	N/A	N/A
1	2	Pipe Chase in Service Closet 2-E	Door	Wood	Grey	Cracking	6	0	Negative
1	2	Pipe Chase in Service Closet 2-E	Doorframe	Metal	Grey	Friction	6	1	Positive
1	2	Pipe Chase in Service Closet 2-E	W2	Concrete	Not Painted	N/A	N/A	N/A	N/A
1	2	Pipe Chase in Service Closet 2-E	W3	Concrete	Not Painted	N/A	N/A	N/A	N/A
1	2	Pipe Chase in Service Closet 2-E	W4	Concrete	Not Painted	N/A	N/A	N/A	N/A
1	2	Pipe Chase in Service Closet 2-E	Ceiling	Concrete	Not Painted	N/A	N/A	N/A	N/A
1	2	Pipe Chase in Service Closet 2-E	Floor	Concrete	Not Painted	N/A	N/A	N/A	N/A
1	2	Main Hallway Book Storage Room 2-G	W1	Plaster	White	Cracking	30	0.5	Negative
1	2	Main Hallway Book Storage Room 2-G	Doorframe	Metal	Brown	Friction	6	0.9	Positive
1	2	Main Hallway Book Storage Room 2-G	W2	Plaster	White	None	0	0	Negative

		Dates: 6/5 - 7/6/2023	Lead-Safe Certification Assessment Report							
		Inspector Name and Certificate Number: Tim Smith 057662	John Bartram High School							
		Inspection Company: BATA	2401 S 67th St, Philadelphia PA 19142							
E l e m e n t	F l o o r	On-Site Room Name	Component	Substrate Material [1]	Paint Color	Description of Paint Damage	Damage Quantity (sf) [2]	XRF Reading (mg/cm2)	XRF (positive/ negative) [3]	
1	2	Main Hallway Book Storage Room 2-G	Covebase	Concrete	Grey	None	0	0	Negative	
1	2	Main Hallway Book Storage Room 2-G	W3	Plaster	White	Cracking	100	0.1	Negative	
1	2	Main Hallway Book Storage Room 2-G	W4	Plaster	White	Cracking	100	0	Negative	
1	2	Main Hallway Book Storage Room 2-G	Ceiling	Plaster	White	Cracking	60	0	Negative	
1	2	Main Hallway Book Storage Room 2-G	Floor	Concrete	Not Painted	N/A	N/A	N/A	N/A	
1	2	Girl's Restroom	W1	Ceramic	White	None	0	0	Negative	
1	2	Girl's Restroom	Doorframe	Metal	Brown	Chipping	2	0.8	Positive	
1	2	Girl's Restroom	Stall	Polymer	White	Chipping	1	0.1	Negative	
1	2	Girl's Restroom	W2	Ceramic	White	None	0	0.2	Negative	
1	2	Girl's Restroom	Pipe Cover	Metal	Brown	None	0	0.3	Negative	
1	2	Girl's Restroom	Pipe Insulation	Asbestos	White	None	0	0.1	Negative	
1	2	Girl's Restroom	Mirror Frame	Wood	Brown	Chipping	2	0.1	Negative	
1	2	Girl's Restroom	W3	Ceramic	White	None	0	0	Negative	
1	2	Girl's Restroom	Radiator cover	Metal	Brown	Chipping	10	0	Negative	
1	2	Girl's Restroom	W4	Ceramic	White	None	0	0	Negative	
1	2	Girl's Restroom	Ceiling	Plaster	White	Flaking	6	0.1	Negative	
1	2	Girl's Restroom	Floor	Terrazzo	Not Painted	N/A	N/A	N/A	N/A	
1	2	Main Hallway Book Storage Room 2-H	W1	Plaster	Grey	Cracking	8	0.2	Negative	
1	2	Main Hallway Book Storage Room 2-H	Doorframe	Metal	Brown	Friction	12	0.4	Negative	
1	2	Main Hallway Book Storage Room 2-H	W2	Plaster	Blue	Cracking	60	0.1	Negative	
1	2	Main Hallway Book Storage Room 2-H	Covebase	Concrete	Grey	Friction	6	0	Negative	
1	2	Main Hallway Book Storage Room 2-H	W3	Plaster	Blue	Cracking	100	0	Negative	
1	2	Main Hallway Book Storage Room 2-H	Pipe	Metal	White	Chipping	1	15.7	Positive	
1	2	Main Hallway Book Storage Room 2-H	W4	Plaster	Blue	Cracking	60	0	Negative	
1	2	Main Hallway Book Storage Room 2-H	Ceiling	Plaster	White	Cracking	20	0	Negative	
1	2	Main Hallway Book Storage Room 2-H	Floor	Concrete	Not Painted	N/A	N/A	N/A	N/A	

		Dates: 6/5 - 7/6/2023	Lead-Safe Certification Assessment Report						
		Inspector Name and Certificate Number: Tim Smith 057662	John Bartram High School						
		Inspection Company: BATA	2401 S 67th St, Philadelphia PA 19142						
E l e m e n t	F l o o r	On-Site Room Name	Component	Substrate Material [1]	Paint Color	Description of Paint Damage	Damage Quantity (sf) [2]	XRF Reading (mg/cm ²)	XRF (positive/ negative) [3]
1	2	Main Hallway Book Storage Room 2-K	W1	Plaster	White	Cracking	60	0	Negative
1	2	Main Hallway Book Storage Room 2-K	Doorframe	Metal	Brown	Friction	6	0.8	Positive
1	2	Main Hallway Book Storage Room 2-K	W2	Plaster	White	Cracking	80	0.1	Negative
1	2	Main Hallway Book Storage Room 2-K	Covebase	Concrete	Grey	Friction	12	0	Negative
1	2	Main Hallway Book Storage Room 2-K	W3	Plaster	White	None	0	0	Negative
1	2	Main Hallway Book Storage Room 2-K	W4	Plaster	White	Cracking	40	0	Negative
1	2	Main Hallway Book Storage Room 2-K	Ceiling	Plaster	White	None	0	0.1	Negative
1	2	Main Hallway Book Storage Room 2-K	Floor	Concrete	Not Painted	N/A	N/A	N/A	N/A
1	2	Custodial Closet next to boys restroom 2BRR	W1	Plaster	White/Grey	Chipping	4	0	Negative
1	2	Custodial Closet next to boys restroom 2BRR	Doorframe	Metal	Brown	Chipping	8	0.1	Negative
1	2	Custodial Closet next to boys restroom 2BRR	W2	Plaster	White/Grey	Cracking	30	0.1	Negative
1	2	Custodial Closet next to boys restroom 2BRR	Shelf	Wood	White	Chipping	6	0	Negative
1	2	Custodial Closet next to boys restroom 2BRR	Covebase	Concrete	Grey	Chipping	8	0	Negative
1	2	Custodial Closet next to boys restroom 2BRR	W3	Plaster	White/Grey	Flaking	20	0.1	Negative
1	2	Custodial Closet next to boys restroom 2BRR	Sink	Ceramic	Grey	Flaking	4	9.8	Positive
1	2	Custodial Closet next to boys restroom 2BRR	W4	Plaster	White/Grey	Flaking	30	0.3	Negative
1	2	Custodial Closet next to boys restroom 2BRR	Ceiling	Plaster	White	Cracking	6	0	Negative
1	2	Custodial Closet next to boys restroom 2BRR	Floor	Concrete	Grey	Friction	12	0	Negative
1	2	Pipe Chase in Custodial Closet next to boys restroom 2BRR	W1	Concrete	Not Painted	N/A	N/A	N/A	N/A
1	2	Pipe Chase in Custodial Closet next to boys restroom 2BRR	Door	Wood	Grey	Chipping	2	0.1	Negative
1	2	Pipe Chase in Custodial Closet next to boys restroom 2BRR	Doorframe	Metal	Grey	None	0	0.5	Negative
1	2	Pipe Chase in Custodial Closet next to boys restroom 2BRR	W2	Concrete	Not Painted	N/A	N/A	N/A	N/A

		Dates: 6/5 - 7/6/2023	Lead-Safe Certification Assessment Report						
		Inspector Name and Certificate Number: Tim Smith 057662	John Bartram High School						
		Inspection Company: BATA	2401 S 67th St, Philadelphia PA 19142						
Element	Floor	On-Site Room Name	Component	Substrate Material [1]	Paint Color	Description of Paint Damage	Damage Quantity (sf) [2]	XRF Reading (mg/cm2)	XRF (positive/negative) [3]
1	2	Pipe Chase in Custodial Closet next to boys restroom 2BRR	W3	Concrete	Not Painted	N/A	N/A	N/A	N/A
1	2	Pipe Chase in Custodial Closet next to boys restroom 2BRR	W4	Concrete	Not Painted	N/A	N/A	N/A	N/A
1	2	Pipe Chase in Custodial Closet next to boys restroom 2BRR	Ceiling	Concrete	Not Painted	N/A	N/A	N/A	N/A
1	2	Pipe Chase in Custodial Closet next to boys restroom 2BRR	Floor	Concrete	Not Painted	N/A	N/A	N/A	N/A
1	2	Attic above Boy's Gym- Closet in Rm 236	W1	No Access	No Access	No Access	No Access	No Access	No Access
1	2	Attic above Boy's Gym- Closet in Rm 236	W2	No Access	No Access	No Access	No Access	No Access	No Access
1	2	Attic above Boy's Gym- Closet in Rm 236	W3	No Access	No Access	No Access	No Access	No Access	No Access
1	2	Attic above Boy's Gym- Closet in Rm 236	W4	No Access	No Access	No Access	No Access	No Access	No Access
1	2	Attic above Boy's Gym- Closet in Rm 236	Ceiling	No Access	No Access	No Access	No Access	No Access	No Access
1	2	Attic above Boy's Gym- Closet in Rm 236	Floor	No Access	No Access	No Access	No Access	No Access	No Access
1	2	Attic above Girl's Gym- Closet in Rm 211	W1	No Access	No Access	No Access	No Access	No Access	No Access
1	2	Attic above Girl's Gym- Closet in Rm 211	W2	No Access	No Access	No Access	No Access	No Access	No Access
1	2	Attic above Girl's Gym- Closet in Rm 211	W3	No Access	No Access	No Access	No Access	No Access	No Access
1	2	Attic above Girl's Gym- Closet in Rm 211	W4	No Access	No Access	No Access	No Access	No Access	No Access
1	2	Attic above Girl's Gym- Closet in Rm 211	Ceiling	No Access	No Access	No Access	No Access	No Access	No Access
1	2	Attic above Girl's Gym- Closet in Rm 211	Floor	No Access	No Access	No Access	No Access	No Access	No Access
1	2	Crawl Space above 2nd Floor	W1	No Access	No Access	No Access	No Access	No Access	No Access
1	2	Crawl Space above 2nd Floor	W2	No Access	No Access	No Access	No Access	No Access	No Access
1	2	Crawl Space above 2nd Floor	W3	No Access	No Access	No Access	No Access	No Access	No Access
1	2	Crawl Space above 2nd Floor	W4	No Access	No Access	No Access	No Access	No Access	No Access
1	2	Crawl Space above 2nd Floor	Ceiling	No Access	No Access	No Access	No Access	No Access	No Access
1	2	Crawl Space above 2nd Floor	Floor	No Access	No Access	No Access	No Access	No Access	No Access
1	2	A-Wing Hallway	W1	Plaster	White	None	0	0.1	Negative

		Dates: 6/5 - 7/6/2023	Lead-Safe Certification Assessment Report						
		Inspector Name and Certificate Number: Tim Smith 057662	John Bartram High School						
		Inspection Company: BATA	2401 S 67th St, Philadelphia PA 19142						
E l e m e n t	F l o o r	On-Site Room Name	Component	Substrate Material [1]	Paint Color	Description of Paint Damage	Damage Quantity (sf) [2]	XRF Reading (mg/cm2)	XRF (positive/ negative) [3]
1	2	A-Wing Hallway	W2	Plaster	White	Flaking	6	0.1	Negative
1	2	A-Wing Hallway	Covebase	Concrete	Brown	None	0	0.1	Negative
1	2	A-Wing Hallway	Pipe Cover	Metal	Tan	Chipping	10	3.2	Positive
1	2	A-Wing Hallway	Pipe Insulation	Asbestos	White	None	0	0.1	Negative
1	2	A-Wing Hallway	Locker	Metal	Yellow	Chipping	30	0	Negative
1	2	A-Wing Hallway	Radiator cover	Metal	Tan	Chipping	12	0	Negative
1	2	A-Wing Hallway	W3	Plaster	White	None	0	0.5	Negative
1	2	A-Wing Hallway	Door	Metal	Red	Chipping	6	0.1	Negative
1	2	A-Wing Hallway	Doorframe	Metal	Red	Chipping	12	0.2	Negative
1	2	A-Wing Hallway	W4	Plaster	White	Flaking	3	0.2	Negative
1	2	A-Wing Hallway	Ceiling	1'x1' Ceiling Tile	White	None	0	0.1	Negative
1	2	A-Wing Hallway	Floor	Concrete	Black	None	0	0	Negative
1	2	B-Wing Hallway	W1	Plaster	White	None	0	0.5	Negative
1	2	B-Wing Hallway	Door	Metal	Red	Chipping	3	0.1	Negative
1	2	B-Wing Hallway	Doorframe	Metal	Red	Chipping	6	0.1	Negative
1	2	B-Wing Hallway	W2	Plaster	White	None	0	0	Negative
1	2	B-Wing Hallway	Covebase	Concrete	Brown	None	0	0	Negative
1	2	B-Wing Hallway	Conduit	Metal	White	Chipping	6	0.2	Negative
1	2	B-Wing Hallway	Locker	Metal	Yellow	Chipping	60	0.1	Negative
1	2	B-Wing Hallway	Radiator cover	Metal	Tan	Chipping	6	0.2	Negative
1	2	B-Wing Hallway	W3	Plaster	White	None	0	0.5	Negative
1	2	B-Wing Hallway	W4	Plaster	White	None	0	0.1	Negative
1	2	B-Wing Hallway	Ceiling	2'x4' Ceiling Tile	Not Painted	N/A	N/A	N/A	N/A
1	2	B-Wing Hallway	Floor	Concrete	Black	None	0	0.2	Negative
1	2	Hallway 201-210A	W1	Plaster	White	None	0	0	Negative
1	2	Hallway 201-210A	Door	Metal	Red	Chipping	6	0.2	Negative

		Dates: 6/5 - 7/6/2023	Lead-Safe Certification Assessment Report						
		Inspector Name and Certificate Number: Tim Smith 057662	John Bartram High School						
		Inspection Company: BATA	2401 S 67th St, Philadelphia PA 19142						
E l e m e n t	F l o o r	On-Site Room Name	Component	Substrate Material [1]	Paint Color	Description of Paint Damage	Damage Quantity (sf) [2]	XRF Reading (mg/cm2)	XRF (positive/ negative) [3]
1	2	Hallway 201-210A	Doorframe	Metal	Red	Chipping	2	0.1	Negative
1	2	Hallway 201-210A	W2	Plaster	White	None	0	0.1	Negative
1	2	Hallway 201-210A	Covebase	Concrete	Brown	None	0	0.1	Negative
1	2	Hallway 201-210A	Conduit	Metal	White	Chipping	5	0.2	Negative
1	2	Hallway 201-210A	Locker	Metal	Yellow	Chipping	40	0.1	Negative
1	2	Hallway 201-210A	Radiator cover	Metal	Tan	Friction	2	0.1	Negative
1	2	Hallway 201-210A	Pipe Cover	Metal	White	Chipping	5	4.5	Positive
1	2	Hallway 201-210A	Pipe Insulation	Asbestos	Tan	None	0	0.2	Negative
1	2	Hallway 201-210A	W3	Plaster	White	None	0	0.1	Negative
1	2	Hallway 201-210A	W4	Plaster	White	None	0	0.1	Negative
1	2	Hallway 201-210A	Ceiling	1'x1' Ceiling Tile	White	Flaking	6	0	Negative
1	2	Hallway 201-210A	Floor	Concrete	Black	None	0	0.3	Negative
1	2	Hallway 211-236	W1	Plaster	White	Flaking	30	0.1	Negative
1	2	Hallway 211-236	Conduit	Plastic	White	Chipping	8	0.3	Negative
1	2	Hallway 211-236	Covebase	Concrete	Brown	None	0	0.3	Negative
1	2	Hallway 211-236	Locker	Metal	Yellow	Chipping	300	0.2	Negative
1	2	Hallway 211-236	W2	Plaster	White	None	0	0	Negative
1	2	Hallway 211-236	W3	Plaster	White	None	0	0.1	Negative
1	2	Hallway 211-236	Pipe Cover	Metal	Tan	Chipping	24	2.4	Positive
1	2	Hallway 211-236	Pipe Insulation	Asbestos	White	None	0	0.2	Negative
1	2	Hallway 211-236	Radiator cover	Metal	Tan	Friction	16	0.1	Negative
1	2	Hallway 211-236	W4	Plaster	White	Flaking	10	0.1	Negative
1	2	Hallway 211-236	Ceiling	1'x1' Ceiling Tile	White	None	0	0.2	Negative
1	2	Hallway 211-236	Floor	Concrete	Black	None	0	0.4	Negative
1	2	Hallway adjacent to 211B	W1	Drywall	White	None	0	0	Negative
1	2	Hallway adjacent to 211B	W2	Plaster	White	None	0	0	Negative

		Dates: 6/5 - 7/6/2023	Lead-Safe Certification Assessment Report						
		Inspector Name and Certificate Number: Tim Smith 057662	John Bartram High School						
		Inspection Company: BATA	2401 S 67th St, Philadelphia PA 19142						
E l e m e n t	F l o o r	On-Site Room Name	Component	Substrate Material [1]	Paint Color	Description of Paint Damage	Damage Quantity (sf) [2]	XRF Reading (mg/cm2)	XRF (positive/ negative) [3]
1	2	Hallway adjacent to 211B	Conduit	Plastic	White	None	0	1.7	Positive
1	2	Hallway adjacent to 211B	Conduit	Metal	White	None	0	0.1	Negative
1	2	Hallway adjacent to 211B	W3	Plaster	White	None	0	0.4	Negative
1	2	Hallway adjacent to 211B	W4	Plaster	White	None	0	0	Negative
1	2	Hallway adjacent to 211B	Ramp	Wood	Black	Friction	40	0	Negative
1	2	Hallway adjacent to 211B	Ramp Wall	Wood	White	None	0	0.1	Negative
1	2	Hallway adjacent to 211B	Window Trophy Case	Wood	Tan	Chipping	6	3.5	Positive
1	2	Hallway adjacent to 211B	Ceiling	Plaster	White	Efflorescence	22	0.2	Negative
1	2	Hallway adjacent to 211B	Ceiling	2'x4' Ceiling Tile	Not Painted	N/A	N/A	N/A	N/A
1	2	Hallway adjacent to 211B	Floor	Terrazzo	Not Painted	N/A	N/A	N/A	N/A
1	2	Stairwell adjacent to Room 222	W1	Plaster	White	None	0	0.1	Negative
1	2	Stairwell adjacent to Room 222	Door	Metal	Red	Chipping	2	0.1	Negative
1	2	Stairwell adjacent to Room 222	Doorframe	Metal	Red	None	0	0.1	Negative
1	2	Stairwell adjacent to Room 222	W2	Plaster	White	Chipping	12	0.2	Negative
1	2	Stairwell adjacent to Room 222	Covebase	Concrete	Brown	None	0	0.2	Negative
1	2	Stairwell adjacent to Room 222	W3	Plaster	White	Flaking	6	0.1	Negative
1	2	Stairwell adjacent to Room 222	Riser	Concrete	Brown	Friction	4	13.7	Positive
1	2	Stairwell adjacent to Room 222	Stringer	Concrete	Brown	None	0	17.9	Positive
1	2	Stairwell adjacent to Room 222	Post	Metal	Brown	Chipping	1	10.4	Positive
1	2	Stairwell adjacent to Room 222	Baluster	Metal	Brown	Cracking	10	14.7	Positive
1	2	Stairwell adjacent to Room 222	Windowframe	Metal	White	None	0	12	Positive
1	2	Stairwell adjacent to Room 222	Radiator cover	Metal	Brown	None	0	0	Negative
1	2	Stairwell adjacent to Room 222	W4	Plaster	White	Flaking	10	0	Negative
1	2	Stairwell adjacent to Room 222	Pipe Cover	Metal	Tan	None	0	3	Positive
1	2	Stairwell adjacent to Room 222	Pipe Insulation	Asbestos	White	None	0	0.1	Negative
1	2	Stairwell adjacent to Room 222	Ceiling	Plaster	White	None	0	0.4	Negative

		Dates: 6/5 - 7/6/2023	Lead-Safe Certification Assessment Report						
		Inspector Name and Certificate Number: Tim Smith 057662	John Bartram High School						
		Inspection Company: BATA	2401 S 67th St, Philadelphia PA 19142						
E l e m e n t	F l o o r	On-Site Room Name	Component	Substrate Material [1]	Paint Color	Description of Paint Damage	Damage Quantity (sf) [2]	XRF Reading (mg/cm2)	XRF (positive/ negative) [3]
1	2	Stairwell adjacent to Room 222	Floor	Concrete	Not Painted	N/A	N/A	N/A	N/A
1	2	Stairwell A across from Room 232	W1	Plaster	White	None	0	0.2	Negative
1	2	Stairwell A across from Room 232	Door	Metal	Red	Friction	8	0.1	Negative
1	2	Stairwell A across from Room 232	Doorframe	Metal	Red	None	0	0.1	Negative
1	2	Stairwell A across from Room 232	W2	Plaster	White	Chipping	16	0.1	Negative
1	2	Stairwell A across from Room 232	Covebase	Concrete	Brown	None	0	0.1	Negative
1	2	Stairwell A across from Room 232	W3	Plaster	White	Cracking	12	0.1	Negative
1	2	Stairwell A across from Room 232	Riser	Concrete	Brown	None	0	0.4	Negative
1	2	Stairwell A across from Room 232	Stringer	Concrete	Brown	Chipping	8	1.6	Positive
1	2	Stairwell A across from Room 232	Post	Metal	Brown	Chipping	2	15.5	Positive
1	2	Stairwell A across from Room 232	Baluster	Metal	Brown	Chipping	14	8.5	Positive
1	2	Stairwell A across from Room 232	Windowframe	Metal	White	None	0	13.7	Positive
1	2	Stairwell A across from Room 232	Radiator cover	Metal	Brown	Chipping	2	0.1	Negative
1	2	Stairwell A across from Room 232	Pipe Cover	Metal	Tan	Chipping	5	3.5	Positive
1	2	Stairwell A across from Room 232	Pipe Insulation	Asbestos	White	Alligatoring	3	0.1	Negative
1	2	Stairwell A across from Room 232	W4	Plaster	White	Cracking	70	0	Negative
1	2	Stairwell A across from Room 232	Ceiling	Plaster	White	None	0	0.2	Negative
1	2	Stairwell A across from Room 232	Floor	Concrete	Not Painted	N/A	N/A	N/A	N/A
1	2	Stairwell C adjacent to Elevator	W1	Plaster	White	None	0	0	Negative
1	2	Stairwell C adjacent to Elevator	Door	Metal	Red	None	0	0.1	Negative
1	2	Stairwell C adjacent to Elevator	Doorframe	Metal	Red	None	0	0.2	Negative
1	2	Stairwell C adjacent to Elevator	W2	Plaster	White	Flaking	30	0	Negative
1	2	Stairwell C adjacent to Elevator	Covebase	Concrete	Brown	Chipping	10	0.1	Negative
1	2	Stairwell C adjacent to Elevator	W3	Plaster	White	Cracking	20	0.3	Negative
1	2	Stairwell C adjacent to Elevator	Riser	Concrete	Brown	None	0	0.5	Negative
1	2	Stairwell C adjacent to Elevator	Stringer	Concrete	Brown	None	0	1	Positive

		Dates: 6/5 - 7/6/2023	Lead-Safe Certification Assessment Report						
		Inspector Name and Certificate Number: Tim Smith 057662	John Bartram High School						
		Inspection Company: BATA	2401 S 67th St, Philadelphia PA 19142						
E l e m e n t	F l o o r	On-Site Room Name	Component	Substrate Material [1]	Paint Color	Description of Paint Damage	Damage Quantity (sf) [2]	XRF Reading (mg/cm2)	XRF (positive/ negative) [3]
1	2	Stairwell C adjacent to Elevator	Post	Metal	Brown	Chipping	2	31	Positive
1	2	Stairwell C adjacent to Elevator	Baluster	Metal	Brown	Chipping	8	11	Positive
1	2	Stairwell C adjacent to Elevator	Windowframe	Metal	White	Cracking	6	12.8	Positive
1	2	Stairwell C adjacent to Elevator	Radiator cover	Metal	Brown	Chipping	6	0.1	Negative
1	2	Stairwell C adjacent to Elevator	Pipe Cover	Metal	Tan	Chipping	5	3.6	Positive
1	2	Stairwell C adjacent to Elevator	Pipe Insulation	Asbestos	White	Alligatoring	10	0.1	Negative
1	2	Stairwell C adjacent to Elevator	W4	Plaster	White	Flaking	3	0	Negative
1	2	Stairwell C adjacent to Elevator	Ceiling	Concrete	White	None	0	0.3	Negative
1	2	Stairwell C adjacent to Elevator	Floor	Concrete	Not Painted	N/A	N/A	N/A	N/A
1	2	Stairwell B adjacent to Room 218	W1	Plaster	White	None	0	0.6	Negative
1	2	Stairwell B adjacent to Room 218	Door	Metal	Red	Chipping	2	0	Negative
1	2	Stairwell B adjacent to Room 218	Doorframe	Metal	Red	Chipping	1	0	Negative
1	2	Stairwell B adjacent to Room 218	W2	Plaster	White	Cracking	4	0.2	Negative
1	2	Stairwell B adjacent to Room 218	Covebase	Concrete	Brown	Flaking	6	0.2	Negative
1	2	Stairwell B adjacent to Room 218	W3	Plaster	White	Cracking	16	0.3	Negative
1	2	Stairwell B adjacent to Room 218	Riser	Concrete	Brown	Friction	30	0.4	Negative
1	2	Stairwell B adjacent to Room 218	Stringer	Concrete	Brown	None	0	0.7	Positive
1	2	Stairwell B adjacent to Room 218	Post	Metal	Brown	Chipping	4	14	Positive
1	2	Stairwell B adjacent to Room 218	Baluster	Metal	Brown	Chipping	10	11.5	Positive
1	2	Stairwell B adjacent to Room 218	Windowframe	Metal	White	Cracking	5	12.6	Positive
1	2	Stairwell B adjacent to Room 218	Radiator cover	Metal	Brown	Chipping	6	0	Negative
1	2	Stairwell B adjacent to Room 218	Pipe Cover	Metal	Tan	Chipping	6	3.2	Positive
1	2	Stairwell B adjacent to Room 218	Pipe Insulation	Asbestos	White	Alligatoring	24	0.3	Negative
1	2	Stairwell B adjacent to Room 218	W4	Plaster	White	Cracking	20	0.2	Negative
1	2	Stairwell B adjacent to Room 218	Ceiling	Concrete	White	None	0	0.5	Negative
1	2	Stairwell B adjacent to Room 218	Floor	Concrete	Not Painted	N/A	N/A	N/A	N/A

		Dates: 6/5 - 7/6/2023	Lead-Safe Certification Assessment Report						
		Inspector Name and Certificate Number: Tim Smith 057662	John Bartram High School						
		Inspection Company: BATA	2401 S 67th St, Philadelphia PA 19142						
E l e m e n t	F l o o r	On-Site Room Name	Component	Substrate Material [1]	Paint Color	Description of Paint Damage	Damage Quantity (sf) [2]	XRF Reading (mg/cm2)	XRF (positive/ negative) [3]
1	2	Stairwell adjacent to 211B	W1	Plaster	White	None	0	0.1	Negative
1	2	Stairwell adjacent to 211B	Doorframe	Metal	Brown	None	0	1	Positive
1	2	Stairwell adjacent to 211B	W2	Plaster	White	None	0	0.2	Negative
1	2	Stairwell adjacent to 211B	Covebase	Concrete	Brown	Friction	12	0.2	Negative
1	2	Stairwell adjacent to 211B	W3	Plaster	White	Cracking	4	0.3	Negative
1	2	Stairwell adjacent to 211B	Riser	Concrete	Brown	None	0	0.7	Positive
1	2	Stairwell adjacent to 211B	Stringer	Concrete	Brown	None	0	2.8	Positive
1	2	Stairwell adjacent to 211B	Post	Metal	Brown	Chipping	1	10.3	Positive
1	2	Stairwell adjacent to 211B	Baluster	Metal	Brown	Chipping	8	6.1	Positive
1	2	Stairwell adjacent to 211B	W4	Plaster	White	None	0	0.2	Negative
1	2	Stairwell adjacent to 211B	Ceiling	Plaster	White	None	0	0.3	Negative
1	2	Stairwell adjacent to 211B	Floor	Concrete	Not Painted	N/A	N/A	N/A	N/A
1	2	Stairwell adjacent to 202	W1	Plaster	White	Cracking	8	0.5	Negative
1	2	Stairwell adjacent to 202	Door	Metal	Red	Chipping	6	0.1	Negative
1	2	Stairwell adjacent to 202	Doorframe	Metal	Red	Friction	2	0	Negative
1	2	Stairwell adjacent to 202	W2	Plaster	White	None	0	0.1	Negative
1	2	Stairwell adjacent to 202	Covebase	Concrete	Brown	Friction	20	0.1	Negative
1	2	Stairwell adjacent to 202	W3	Plaster	White	Efflorescence	20	0	Negative
1	2	Stairwell adjacent to 202	Riser	Concrete	Brown	None	0	0.4	Negative
1	2	Stairwell adjacent to 202	Stringer	Concrete	Brown	None	0	0.5	Negative
1	2	Stairwell adjacent to 202	Post	Metal	Brown	Chipping	2	10.9	Positive
1	2	Stairwell adjacent to 202	Baluster	Metal	Brown	Cracking	10	11.7	Positive
1	2	Stairwell adjacent to 202	Windowframe	Metal	White	Cracking	10	11.1	Positive
1	2	Stairwell adjacent to 202	Radiator cover	Metal	Brown	Chipping	4	0.1	Negative
1	2	Stairwell adjacent to 202	Pipe Cover	Metal	Tan	Flaking	6	2.9	Positive
1	2	Stairwell adjacent to 202	Pipe Insulation	Asbestos	White	None	0	0.2	Negative

		Dates: 6/5 - 7/6/2023	Lead-Safe Certification Assessment Report							
		Inspector Name and Certificate Number: Tim Smith 057662	John Bartram High School							
		Inspection Company: BATA	2401 S 67th St, Philadelphia PA 19142							
E l e m e n t	F l o o r	On-Site Room Name	Component	Substrate Material [1]	Paint Color	Description of Paint Damage	Damage Quantity (sf) [2]	XRF Reading (mg/cm ²)	XRF (positive/ negative) [3]	
1	2	Stairwell adjacent to 202	W4	Plaster	White	Efflorescence	30	0.1	Negative	
1	2	Stairwell adjacent to 202	Ceiling	Concrete	White	None	0	0.3	Negative	
1	2	Stairwell adjacent to 202	Floor	Concrete	Not Painted	N/A	N/A	N/A	N/A	
1	2	Stairwell behind Library	W1	Plaster	White	Flaking	30	0.4	Negative	
1	2	Stairwell behind Library	Door	Metal	Blue	None	0	0.2	Negative	
1	2	Stairwell behind Library	Doorframe	Metal	Blue	None	0	0.2	Negative	
1	2	Stairwell behind Library	W2	Plaster	White	Flaking	400	0.1	Negative	
1	2	Stairwell behind Library	Covebase	Concrete	Brown	Chipping	30	0	Negative	
1	2	Stairwell behind Library	W3	Plaster	White	Flaking	60	0.1	Negative	
1	2	Stairwell behind Library	Riser	Concrete	Brown	None	0	0.4	Negative	
1	2	Stairwell behind Library	Stringer	Concrete	Brown	Flaking	10	1.2	Positive	
1	2	Stairwell behind Library	Post	Metal	Brown	Chipping	4	13.5	Positive	
1	2	Stairwell behind Library	Baluster	Metal	Brown	Chipping	10	1.3	Positive	
1	2	Stairwell behind Library	Windowframe	Metal	White	Flaking	30	11.5	Positive	
1	2	Stairwell behind Library	Radiator cover	Metal	Brown	Cracking	10	0	Negative	
1	2	Stairwell behind Library	Pipe Cover	Metal	Tan	Flaking	6	0.5	Negative	
1	2	Stairwell behind Library	Pipe Insulation	Asbestos	White	Alligatoring	12	0.2	Negative	
1	2	Stairwell behind Library	W4	Plaster	White	Flaking	600	0.6	Negative	
1	2	Stairwell behind Library	Ceiling	Concrete	White	Flaking	400	0.3	Negative	
1	2	Stairwell behind Library	Floor	Concrete	Not Painted	N/A	N/A	N/A	N/A	
1	3	Classroom 301	W1	Drywall	White	Chipping	4	0.2	Negative	
1	3	Classroom 301	W1	Plaster	White	None	0	0.3	Negative	
1	3	Classroom 301	Doorframe	Metal	Tan	Friction	2	0.3	Negative	
1	3	Classroom 301	W2	Drywall	White	None	0	0.2	Negative	
1	3	Classroom 301	W3	Plaster	White	None	0	0.3	Negative	
1	3	Classroom 301	Radiator cover	Metal	Tan	Chipping	20	0	Negative	

		Dates: 6/5 - 7/6/2023	Lead-Safe Certification Assessment Report							
		Inspector Name and Certificate Number: Tim Smith 057662	John Bartram High School							
		Inspection Company: BATA	2401 S 67th St, Philadelphia PA 19142							
E l e m e n t	F l o o r	On-Site Room Name	Component	Substrate Material [1]	Paint Color	Description of Paint Damage	Damage Quantity (sf) [2]	XRF Reading (mg/cm ²)	XRF (positive/ negative) [3]	
1	3	Classroom 301	W4	Plaster	White	None	0	0.2	Negative	
1	3	Classroom 301	Covebase	Concrete	Brown	None	0	0.1	Negative	
1	3	Classroom 301	Ceiling	2'x4' Ceiling Tile	Not Painted	N/A	N/A	N/A	N/A	
1	3	Classroom 301	Ceiling	Plaster	White	Efflorescence	5	0.1	Negative	
1	3	Classroom 301	Floor	Concrete	Not Painted	N/A	N/A	N/A	N/A	
1	3	Classroom 302	W1	Drywall	White	None	0	0.2	Negative	
1	3	Classroom 302	W1	Plaster	White	None	0	0	Negative	
1	3	Classroom 302	Conduit	Metal	White	None	0	0	Negative	
1	3	Classroom 302	Doorframe	Metal	Tan	Friction	4	0.1	Negative	
1	3	Classroom 302	W2	Plaster	White	Cracking	8	0.1	Negative	
1	3	Classroom 302	Covebase	Concrete	Brown	None	0	0.2	Negative	
1	3	Classroom 302	W3	Plaster	White	None	0	0	Negative	
1	3	Classroom 302	Radiator cover	Metal	Tan	Cracking	2	0.1	Negative	
1	3	Classroom 302	W4	Drywall	White	None	0	0.1	Negative	
1	3	Classroom 302	Ceiling	2'x4' Ceiling Tile	Not Painted	N/A	N/A	N/A	N/A	
1	3	Classroom 302	Ceiling	Plaster	White	Flaking	120	0.1	Negative	
1	3	Classroom 302	Floor	Concrete	Not Painted	N/A	N/A	N/A	N/A	
1	3	Classroom 303	W1	Drywall	White	Chipping	20	0.5	Negative	
1	3	Classroom 303	Column	Plaster	White	None	0	0.3	Negative	
1	3	Classroom 303	Doorframe	Metal	Tan	Friction	2	0.1	Negative	
1	3	Classroom 303	W2	Drywall	White	Chipping	3	0.2	Negative	
1	3	Classroom 303	Conduit	Metal	White	None	0	0.1	Negative	
1	3	Classroom 303	W3	Plaster	White	None	0	0	Negative	
1	3	Classroom 303	Covebase	Concrete	Brown	None	0	0.2	Negative	
1	3	Classroom 303	Radiator cover	Metal	Tan	Chipping	6	0	Negative	
1	3	Classroom 303	W4	Drywall	White	None	0	0.1	Negative	

		Dates: 6/5 - 7/6/2023	Lead-Safe Certification Assessment Report						
		Inspector Name and Certificate Number: Tim Smith 057662	John Bartram High School						
		Inspection Company: BATA	2401 S 67th St, Philadelphia PA 19142						
E l e m e n t	F l o o r	On-Site Room Name	Component	Substrate Material [1]	Paint Color	Description of Paint Damage	Damage Quantity (sf) [2]	XRF Reading (mg/cm2)	XRF (positive/ negative) [3]
1	3	Classroom 303	Ceiling	2'x4' Ceiling Tile	Not Painted	N/A	N/A	N/A	N/A
1	3	Classroom 303	Ceiling	Plaster	White	None	0	0.1	Negative
1	3	Classroom 303	Floor	Concrete	Not Painted	N/A	N/A	N/A	N/A
1	3	Storage Room inside Classroom 303	W1	Drywall	White	None	0	0.1	Negative
1	3	Storage Room inside Classroom 303	Doorframe	Metal	Tan	None	0	0.1	Negative
1	3	Storage Room inside Classroom 303	W2	Drywall	White	None	0	0.1	Negative
1	3	Storage Room inside Classroom 303	W3	Drywall	White	None	0	0.2	Negative
1	3	Storage Room inside Classroom 303	W3	Plaster	White	None	0	0.2	Negative
1	3	Storage Room inside Classroom 303	W4	Drywall	White	None	0	0.2	Negative
1	3	Storage Room inside Classroom 303	Ceiling	Plaster	White	None	0	0	Negative
1	3	Storage Room inside Classroom 303	Ceiling	2'x4' Ceiling Tile	Not Painted	N/A	N/A	N/A	N/A
1	3	Storage Room inside Classroom 303	Floor	Concrete	Not Painted	N/A	N/A	N/A	N/A
1	3	Classroom 304	W1	Drywall	White	Chipping	10	0.2	Negative
1	3	Classroom 304	Column	Plaster	White	None	0	0.1	Negative
1	3	Classroom 304	Doorframe	Metal	Tan	None	0	0.1	Negative
1	3	Classroom 304	W2	Drywall	White	None	0	0.1	Negative
1	3	Classroom 304	W3	Plaster	White	None	0	0.1	Negative
1	3	Classroom 304	Covebase	Concrete	Brown	None	0	0.1	Negative
1	3	Classroom 304	Radiator cover	Metal	Tan	Chipping	6	0	Negative
1	3	Classroom 304	W4	Drywall	White	Chipping	2	0.1	Negative
1	3	Classroom 304	W4	Plaster	White	None	0	0	Negative
1	3	Classroom 304	Ceiling	Plaster	White	Flaking	4	0.2	Negative
1	3	Classroom 304	Ceiling	2'x4' Ceiling Tile	Not Painted	N/A	N/A	N/A	N/A
1	3	Classroom 304	Floor	Concrete	Not Painted	N/A	N/A	N/A	N/A
1	3	Storage Room inside Classroom 304	W1	Drywall	White	None	0	0.2	Negative
1	3	Storage Room inside Classroom 304	Doorframe	Metal	Tan	None	0	0.1	Negative

		Dates: 6/5 - 7/6/2023	Lead-Safe Certification Assessment Report						
		Inspector Name and Certificate Number: Tim Smith 057662	John Bartram High School						
		Inspection Company: BATA	2401 S 67th St, Philadelphia PA 19142						
Element	Floor	On-Site Room Name	Component	Substrate Material [1]	Paint Color	Description of Paint Damage	Damage Quantity (sf) [2]	XRF Reading (mg/cm2)	XRF (positive/negative) [3]
1	3	Storage Room inside Classroom 304	W2	Drywall	White	None	0	0.2	Negative
1	3	Storage Room inside Classroom 304	W3	Drywall	White	None	0	0.3	Negative
1	3	Storage Room inside Classroom 304	W3	Plaster	White	Flaking	1	0.2	Negative
1	3	Storage Room inside Classroom 304	W4	Drywall	White	None	0	0.1	Negative
1	3	Storage Room inside Classroom 304	Ceiling	Plaster	White	None	0	0.1	Negative
1	3	Storage Room inside Classroom 304	Ceiling	2'x4' Ceiling Tile	Not Painted	N/A	N/A	N/A	N/A
1	3	Storage Room inside Classroom 304	Floor	Concrete	Not Painted	N/A	N/A	N/A	N/A
1	3	Classroom 305	W1	Drywall	White	Chipping	8	0.3	Negative
1	3	Classroom 305	Column	Plaster	White	None	0	0.2	Negative
1	3	Classroom 305	Doorframe	Metal	Tan	Friction	3	0	Negative
1	3	Classroom 305	Trim	Wood	White	None	0	0.4	Negative
1	3	Classroom 305	W2	Drywall	White	Chipping	1	0.1	Negative
1	3	Classroom 305	W3	Plaster	White	None	0	0.6	Negative
1	3	Classroom 305	Conduit	Metal	Tan	None	0	0.4	Negative
1	3	Classroom 305	Covebase	Concrete	Brown	None	0	0.2	Negative
1	3	Classroom 305	Radiator cover	Metal	Tan	Chipping	2	0.1	Negative
1	3	Classroom 305	W4	Drywall	White	None	0	0.1	Negative
1	3	Classroom 305	Ceiling	Plaster	White	None	0	0.2	Negative
1	3	Classroom 305	Ceiling	2'x4' Ceiling Tile	Not Painted	N/A	N/A	N/A	N/A
1	3	Classroom 305	Floor	Concrete	Not Painted	N/A	N/A	N/A	N/A
1	3	Storage Room inside Classroom 305	W1	Drywall	White	None	0	0.2	Negative
1	3	Storage Room inside Classroom 305	Doorframe	Metal	Tan	None	0	0.1	Negative
1	3	Storage Room inside Classroom 305	W2	Drywall	White	None	0	0.1	Negative
1	3	Storage Room inside Classroom 305	W3	Drywall	White	None	0	0.2	Negative
1	3	Storage Room inside Classroom 305	W3	Plaster	White	None	0	0.2	Negative
1	3	Storage Room inside Classroom 305	W4	Drywall	White	None	0	0.2	Negative

		Dates: 6/5 - 7/6/2023	Lead-Safe Certification Assessment Report							
		Inspector Name and Certificate Number: Tim Smith 057662	John Bartram High School							
		Inspection Company: BATA	2401 S 67th St, Philadelphia PA 19142							
E l e m e n t	F l o o r	On-Site Room Name	Component	Substrate Material [1]	Paint Color	Description of Paint Damage	Damage Quantity (sf) [2]	XRF Reading (mg/cm2)	XRF (positive/ negative) [3]	
1	3	Storage Room inside Classroom 305	Ceiling	Plaster	White	None	0	0.1	Negative	
1	3	Storage Room inside Classroom 305	Ceiling	2'x4' Ceiling Tile	Not Painted	N/A	N/A	N/A	N/A	
1	3	Storage Room inside Classroom 305	Floor	Concrete	Not Painted	N/A	N/A	N/A	N/A	
1	3	ROTC Storage next to Classroom 308	W1	No Access	No Access	No Access	No Access	No Access	No Access	
1	3	ROTC Storage next to Classroom 308	Doorframe	Metal	White	Friction	6	0.2	Negative	
1	3	ROTC Storage next to Classroom 308	Door	Metal	White	Friction	2	0.2	Negative	
1	3	ROTC Storage next to Classroom 308	W2	No Access	No Access	No Access	No Access	No Access	No Access	
1	3	ROTC Storage next to Classroom 308	W3	No Access	No Access	No Access	No Access	No Access	No Access	
1	3	ROTC Storage next to Classroom 308	W4	No Access	No Access	No Access	No Access	No Access	No Access	
1	3	ROTC Storage next to Classroom 308	Ceiling	No Access	No Access	No Access	No Access	No Access	No Access	
1	3	ROTC Storage next to Classroom 308	Floor	No Access	No Access	No Access	No Access	No Access	No Access	
1	3	Copy Room 307	W1	Drywall	Blue	Chipping	2	0.1	Negative	
1	3	Copy Room 307	W1	Plaster	Blue	Flaking	8	0.1	Negative	
1	3	Copy Room 307	Doorframe	Metal	Tan	Friction	3	0.2	Negative	
1	3	Copy Room 307	W2	Drywall	Blue	Chipping	6	0.3	Negative	
1	3	Copy Room 307	Conduit	Metal	Tan	None	0	0.1	Negative	
1	3	Copy Room 307	Blackboard Frame	Metal	Blue	Chipping	4	0.2	Negative	
1	3	Copy Room 307	W3	Plaster	Blue	Chipping	2	0.1	Negative	
1	3	Copy Room 307	Covebase	Concrete	Brown	None	0	0.1	Negative	
1	3	Copy Room 307	Radiator cover	Metal	Brown	Chipping	20	0	Negative	
1	3	Copy Room 307	Pipe Cover	Metal	Blue	Flaking	5	5.8	Positive	
1	3	Copy Room 307	Pipe Insulation	Asbestos	Blue	None	0	0.1	Negative	
1	3	Copy Room 307	W4	Drywall	Blue	Chipping	2	0.4	Negative	
1	3	Copy Room 307	Ceiling	Plaster	White	Flaking	60	0.1	Negative	
1	3	Copy Room 307	Ceiling	2'x4' Ceiling Tile	Not Painted	N/A	N/A	N/A	N/A	
1	3	Copy Room 307	Floor	Concrete	Not Painted	N/A	N/A	N/A	N/A	

		Dates: 6/5 - 7/6/2023	Lead-Safe Certification Assessment Report							
		Inspector Name and Certificate Number: Tim Smith 057662	John Bartram High School							
		Inspection Company: BATA	2401 S 67th St, Philadelphia PA 19142							
Element	Floor	On-Site Room Name	Component	Substrate Material [1]	Paint Color	Description of Paint Damage	Damage Quantity (sf) [2]	XRF Reading (mg/cm2)	XRF (positive/negative) [3]	
1	3	Classroom 308	W1	Metal	Blue	Chipping	60	0.2	Negative	
1	3	Classroom 308	W1	Ceramic	Blue	None	0	0	Negative	
1	3	Classroom 308	Doorframe	Metal	Tan	Friction	4	0.1	Negative	
1	3	Classroom 308	W2	Ceramic	Grey	None	0	0.1	Negative	
1	3	Classroom 308	W3	Ceramic	Blue	None	0	0.1	Negative	
1	3	Classroom 308	Radiator cover	Metal	Brown	Flaking	18	0.1	Negative	
1	3	Classroom 308	Conduit	Plaster	Blue	None	0	0.8	Positive	
1	3	Classroom 308	W4	Drywall	Grey	Chipping	4	0.1	Negative	
1	3	Classroom 308	Ceiling	Plaster	White	Partially Inaccess	Partially Inacce	0.4	Negative	
1	3	Classroom 308	Ceiling	2'x4' Ceiling Tile	Not Painted	N/A	N/A	N/A	N/A	
1	3	Classroom 308	Floor	Quarry Tile	Not Painted	N/A	N/A	N/A	N/A	
1	3	ROTC Office next to Classroom 308	W1	Metal	White	None	0	0	Negative	
1	3	ROTC Office next to Classroom 308	Door	Metal	White	Chipping	3	0.3	Negative	
1	3	ROTC Office next to Classroom 308	Doorframe	Metal	White	Friction	1	0.2	Negative	
1	3	ROTC Office next to Classroom 308	W2	Metal	White	None	0	0.2	Negative	
1	3	ROTC Office next to Classroom 308	Windowframe	Metal	White	None	0	0.1	Negative	
1	3	ROTC Office next to Classroom 308	W3	Plaster	White	None	0	0.5	Negative	
1	3	ROTC Office next to Classroom 308	Radiator cover	Metal	Brown	Flaking	4	0.1	Negative	
1	3	ROTC Office next to Classroom 308	W4	Terracotta	White	None	0	0	Negative	
1	3	ROTC Office next to Classroom 308	W4	Plaster	White	None	0	0.1	Negative	
1	3	ROTC Office next to Classroom 308	Ceiling	Plaster	White	Flaking	20	0.4	Negative	
1	3	ROTC Office next to Classroom 308	Ceiling	2'x4' Ceiling Tile	Not Painted	N/A	N/A	N/A	N/A	
1	3	ROTC Office next to Classroom 308	Floor	Floor Tile	Not Painted	N/A	N/A	N/A	N/A	
1	3	Restroom inside ROTC Office next to Classroom 308	W1	Metal	White	None	0	0.3	Negative	
1	3	Restroom inside ROTC Office next to Classroom 308	Door	Metal	White	Flaking	3	0.2	Negative	
1	3	Restroom inside ROTC Office next to Classroom 308	Doorframe	Metal	White	Chipping	1	3.1	Positive	

		Dates: 6/5 - 7/6/2023	Lead-Safe Certification Assessment Report						
		Inspector Name and Certificate Number: Tim Smith 057662	John Bartram High School						
		Inspection Company: BATA	2401 S 67th St, Philadelphia PA 19142						
Element	Floor	On-Site Room Name	Component	Substrate Material [1]	Paint Color	Description of Paint Damage	Damage Quantity (sf) [2]	XRF Reading (mg/cm ²)	XRF (positive/negative) [3]
1	3	Restroom inside ROTC Office next to Classroom 308	W2	Metal	White	None	0	0.3	Negative
1	3	Restroom inside ROTC Office next to Classroom 308	W3	Plaster	White	None	0	0.4	Negative
1	3	Restroom inside ROTC Office next to Classroom 308	Pipe Cover	Metal	White	Flaking	6	4.7	Positive
1	3	Restroom inside ROTC Office next to Classroom 308	Pipe Insulation	Asbestos	White	None	0	0.2	Negative
1	3	Restroom inside ROTC Office next to Classroom 308	Radiator cover	Metal	Brown	None	0	0	Negative
1	3	Restroom inside ROTC Office next to Classroom 308	W4	Plaster	White	None	0	0	Negative
1	3	Restroom inside ROTC Office next to Classroom 308	Ceiling	Plaster	White	None	0	0.4	Negative
1	3	Restroom inside ROTC Office next to Classroom 308	Ceiling	2'x4' Ceiling Tile	Not Painted	N/A	N/A	N/A	N/A
1	3	Restroom inside ROTC Office next to Classroom 308	Floor	Floor Tile	Not Painted	N/A	N/A	N/A	N/A
1	3	Office 310	W1	Plaster	White/Red	Cracking	16	0.3	Negative
1	3	Office 310	Doorframe	Metal	Brown	Friction	6	0.1	Negative
1	3	Office 310	Conduit	Metal	White/Red	None	0	0.4	Negative
1	3	Office 310	W2	Plaster	White/Red	None	0	0.1	Negative
1	3	Office 310	W3	Plaster	White/Red	None	0	0.1	Negative
1	3	Office 310	Pipe Cover	Metal	Red	Flaking	1	5.9	Positive
1	3	Office 310	Pipe Insulation	Asbestos	White	None	0	0.3	Negative
1	3	Office 310	Radiator cover	Metal	Red	None	0	0	Negative
1	3	Office 310	Conduit	Plastic	Multi-Color	None	0	0.3	Negative
1	3	Office 310	W4	Drywall	White/Red	None	0	0.2	Negative
1	3	Office 310	Ceiling	Plaster	White	Spalling	20	0	Negative
1	3	Office 310	Ceiling	2'x4' Ceiling Tile	Not Painted	N/A	N/A	N/A	N/A
1	3	Office 310	Floor	Concrete	Not Painted	N/A	N/A	N/A	N/A
1	3	Office 309	W1	Drywall	White/Pink	Chipping	1	0.3	Negative
1	3	Office 309	Doorframe	Metal	Brown	None	0	0.1	Negative
1	3	Office 309	Conduit	Plastic	White/Pink	None	0	0.2	Negative
1	3	Office 309	W2	Drywall	White/Pink	None	0	0.2	Negative

		Dates: 6/5 - 7/6/2023	Lead-Safe Certification Assessment Report							
		Inspector Name and Certificate Number: Tim Smith 057662	John Bartram High School							
		Inspection Company: BATA	2401 S 67th St, Philadelphia PA 19142							
E l e m e n t	F l o o r	On-Site Room Name	Component	Substrate Material [1]	Paint Color	Description of Paint Damage	Damage Quantity (sf) [2]	XRF Reading (mg/cm ²)	XRF (positive/ negative) [3]	
1	3	Office 309	W3	Plaster	White/Pink	Chipping	4	0	Negative	
1	3	Office 309	Pipe Cover	Metal	Brown	None	0	5.3	Positive	
1	3	Office 309	Pipe Insulation	Asbestos	White	None	0	0.2	Negative	
1	3	Office 309	Radiator cover	Metal	Red	Flaking	5	0.1	Negative	
1	3	Office 309	W4	Drywall	White/Pink	Chipping	16	0.1	Negative	
1	3	Office 309	Ceiling	Plaster	White	Flaking	16	0.2	Negative	
1	3	Office 309	Ceiling	2'x4' Ceiling Tile	Not Painted	N/A	N/A	N/A	N/A	
1	3	Office 309	Floor	Concrete	Not Painted	N/A	N/A	N/A	N/A	
1	3	Classroom 312	W1	Ceramic	White	None	0	0	Negative	
1	3	Classroom 312	Doorframe	Metal	Brown	Friction	4	0.7	Positive	
1	3	Classroom 312	W2	Ceramic	White	None	0	0	Negative	
1	3	Classroom 312	Conduit	Plastic	White	None	0	0.4	Negative	
1	3	Classroom 312	W3	Ceramic	White	None	0	0	Negative	
1	3	Classroom 312	Pipe Cover	Metal	White	Chipping	2	3.1	Positive	
1	3	Classroom 312	Pipe Insulation	Asbestos	White	None	0	0.2	Negative	
1	3	Classroom 312	Radiator cover	Metal	Brown	Chipping	8	0	Negative	
1	3	Classroom 312	W4	Ceramic	White	None	0	0	Negative	
1	3	Classroom 312	Ceiling	Plaster	White	Flaking	40	0.2	Negative	
1	3	Classroom 312	Ceiling	2'x4' Ceiling Tile	Not Painted	N/A	N/A	N/A	N/A	
1	3	Classroom 312	Floor	Quarry Tile	Not Painted	N/A	N/A	N/A	N/A	
1	3	Classroom 313	W1	Plaster	Blue	Cracking	40	6.2	Positive	
1	3	Classroom 313	Doorframe	Metal	Brown	Friction	6	1.1	Positive	
1	3	Classroom 313	W2	Plaster	Blue	None	0	4.9	Positive	
1	3	Classroom 313	W3	Plaster	Blue	Cracking	30	5.9	Positive	
1	3	Classroom 313	Conduit	Plastic	Blue	None	0	0.4	Negative	
1	3	Classroom 313	Radiator cover	Metal	Brown	Friction	2	0.8	Positive	

		Dates: 6/5 - 7/6/2023	Lead-Safe Certification Assessment Report							
		Inspector Name and Certificate Number: Tim Smith 057662	John Bartram High School							
		Inspection Company: BATA	2401 S 67th St, Philadelphia PA 19142							
E l e m e n t	F l o o r	On-Site Room Name	Component	Substrate Material [1]	Paint Color	Description of Paint Damage	Damage Quantity (sf) [2]	XRF Reading (mg/cm2)	XRF (positive/ negative) [3]	
1	3	Classroom 313	W4	Plaster	Blue	Chipping	6	6.2	Positive	
1	3	Classroom 313	Ceiling	Plaster	White	None	0	4.4	Positive	
1	3	Classroom 313	Ceiling	2'x4' Ceiling Tile	Not Painted	N/A	N/A	N/A	N/A	
1	3	Classroom 313	Floor	Floor Tile	Not Painted	N/A	N/A	N/A	N/A	
1	3	Girl's Restroom	W1	Ceramic	White	None	0	0.1	Negative	
1	3	Girl's Restroom	Door	Wood	Brown	Chipping	1	0	Negative	
1	3	Girl's Restroom	Doorframe	Metal	Brown	Friction	6	1	Positive	
1	3	Girl's Restroom	Stall	Polymer	White	None	0	0.1	Negative	
1	3	Girl's Restroom	W2	Ceramic	White	None	0	0.1	Negative	
1	3	Girl's Restroom	W3	Ceramic	White	None	0	0	Negative	
1	3	Girl's Restroom	W4	Ceramic	White	None	0	0	Negative	
1	3	Girl's Restroom	Pipe	Metal	White	Chipping	4	13.2	Positive	
1	3	Girl's Restroom	Radiator cover	Metal	Brown	Flaking	2	0	Negative	
1	3	Girl's Restroom	Ceiling	Plaster	White	None	0	0.4	Negative	
1	3	Girl's Restroom	Floor	Terrazzo	Not Painted	N/A	N/A	N/A	N/A	
1	3	Office 314	W1	No Access	No Access	No Access	No Access	No Access	No Access	
1	3	Office 314	W2	No Access	No Access	No Access	No Access	No Access	No Access	
1	3	Office 314	W3	No Access	No Access	No Access	No Access	No Access	No Access	
1	3	Office 314	W4	No Access	No Access	No Access	No Access	No Access	No Access	
1	3	Office 314	Ceiling	No Access	No Access	No Access	No Access	No Access	No Access	
1	3	Office 314	Floor	No Access	No Access	No Access	No Access	No Access	No Access	
1	3	Office 314A	W1	Plaster	White	Cracking	30	0	Negative	
1	3	Office 314A	Doorframe	Metal	Brown	Friction	2	1.3	Positive	
1	3	Office 314A	Conduit	Plastic	White	None	0	0.6	Negative	
1	3	Office 314A	Conduit	Metal	White	None	0	0.1	Negative	
1	3	Office 314A	W2	Plaster	White	Cracking	40	0	Negative	

		Dates: 6/5 - 7/6/2023	Lead-Safe Certification Assessment Report							
		Inspector Name and Certificate Number: Tim Smith 057662	John Bartram High School							
		Inspection Company: BATA	2401 S 67th St, Philadelphia PA 19142							
E l e m e n t	F l o o r	On-Site Room Name	Component	Substrate Material [1]	Paint Color	Description of Paint Damage	Damage Quantity (sf) [2]	XRF Reading (mg/cm ²)	XRF (positive/ negative) [3]	
1	3	Office 314A	Covebase	Concrete	Red	Chipping	30	0.1	Negative	
1	3	Office 314A	W3	Plaster	White	Cracking	20	0	Negative	
1	3	Office 314A	Radiator	Metal	Brown	Chipping	6	0	Negative	
1	3	Office 314A	W4	Plaster	White	Flaking	12	0	Negative	
1	3	Office 314A	Ceiling	Plaster	White	Flaking	2	0	Negative	
1	3	Office 314A	Floor	Concrete	Not Painted	N/A	N/A	N/A	N/A	
1	3	Book Storage (315)	W1	Plaster	White	Cracking	50	0	Negative	
1	3	Book Storage (315)	Doorframe	Metal	Brown	Friction	2	0.5	Negative	
1	3	Book Storage (315)	W2	Plaster	White	None	0	0	Negative	
1	3	Book Storage (315)	W3	Plaster	White	Cracking	40	0.6	Negative	
1	3	Book Storage (315)	W4	Plaster	White	Cracking	100	0	Negative	
1	3	Book Storage (315)	Covebase	Concrete	Grey	None	0	0	Negative	
1	3	Book Storage (315)	Ceiling	Plaster	White	Cracking	60	0	Negative	
1	3	Book Storage (315)	Floor	Concrete	Grey	None	0	0.1	Negative	
1	3	Auditorium Exhaust Fan Room	W1	Terracotta	Green	None	0	0.2	Negative	
1	3	Auditorium Exhaust Fan Room	Doorframe	Metal	Brown	Friction	4	0.7	Positive	
1	3	Auditorium Exhaust Fan Room	Door	Metal	Brown	Chipping	1	0.3	Negative	
1	3	Auditorium Exhaust Fan Room	W2	Terracotta	Green	None	0	0.2	Negative	
1	3	Auditorium Exhaust Fan Room	Windowframe	Metal	Brown	None	0	0.6	Negative	
1	3	Auditorium Exhaust Fan Room	Railing	Metal	Grey	Chipping	16	9.3	Positive	
1	3	Auditorium Exhaust Fan Room	Louver	Metal	White	Flaking	80	0.2	Negative	
1	3	Auditorium Exhaust Fan Room	Exterior Fan Unit	Metal	White	Spalling	400	11.7	Positive	
1	3	Auditorium Exhaust Fan Room	Fan Unit Pad	Concrete	White	Chipping	5	0.2	Negative	
1	3	Auditorium Exhaust Fan Room	W3	Terracotta	Green	Flaking	2	0	Negative	
1	3	Auditorium Exhaust Fan Room	W4	Terracotta	Green	None	0	0.3	Negative	
1	3	Auditorium Exhaust Fan Room	Conduit	Metal	Green	None	0	0.2	Negative	

		Dates: 6/5 - 7/6/2023	Lead-Safe Certification Assessment Report						
		Inspector Name and Certificate Number: Tim Smith 057662	John Bartram High School						
		Inspection Company: BATA	2401 S 67th St, Philadelphia PA 19142						
Element	Floor	On-Site Room Name	Component	Substrate Material [1]	Paint Color	Description of Paint Damage	Damage Quantity (sf) [2]	XRF Reading (mg/cm ²)	XRF (positive/negative) [3]
1	3	Auditorium Exhaust Fan Room	Ceiling	Concrete	White	None	0	0.2	Negative
1	3	Auditorium Exhaust Fan Room	Floor	Concrete	Not Painted	N/A	N/A	N/A	N/A
1	3	General Storage Area (315)	W1	Wood	White	None	0	0.2	Negative
1	3	General Storage Area (315)	Doorframe	Metal	Brown	Friction	4	0.4	Negative
1	3	General Storage Area (315)	Conduit	Plastic	White	None	0	0.3	Negative
1	3	General Storage Area (315)	W2	Wood	White	None	0	0.4	Negative
1	3	General Storage Area (315)	Covebase	Concrete	Brown	None	0	0.1	Negative
1	3	General Storage Area (315)	W3	Wood	White	None	0	0.3	Negative
1	3	General Storage Area (315)	W3	Plaster	Tan	Cracking	48	0.5	Negative
1	3	General Storage Area (315)	W4	Wood	White	None	0	0.1	Negative
1	3	General Storage Area (315)	Windowframe	Metal	Brown	None	0	0.2	Negative
1	3	General Storage Area (315)	Ceiling	Plaster	Tan	Flaking	40	0.2	Negative
1	3	General Storage Area (315)	Ceiling	2'x4' Ceiling Tile	Not Painted	N/A	N/A	N/A	N/A
1	3	General Storage Area (315)	Floor	Floor Tile	Not Painted	N/A	N/A	N/A	N/A
1	3	Girl's Gym Exhaust Fan Room	W1	Terracotta	Green	None	0	0.2	Negative
1	3	Girl's Gym Exhaust Fan Room	Door	Metal	Brown	None	0	0.4	Negative
1	3	Girl's Gym Exhaust Fan Room	Doorframe	Metal	Brown	Friction	1	0.9	Positive
1	3	Girl's Gym Exhaust Fan Room	W2	Terracotta	Green	None	0	0.1	Negative
1	3	Girl's Gym Exhaust Fan Room	Railing	Metal	Grey	Chipping	20	9.1	Positive
1	3	Girl's Gym Exhaust Fan Room	Exterior Fan Unit	Metal	Grey	Flaking	400	10.3	Positive
1	3	Girl's Gym Exhaust Fan Room	Exterior Fan Unit	Metal	Grey	Flaking	200	13.7	Positive
1	3	Girl's Gym Exhaust Fan Room	Conduit	Metal	Green	None	0	0	Negative
1	3	Girl's Gym Exhaust Fan Room	W3	Terracotta	Green	None	0	0.1	Negative
1	3	Girl's Gym Exhaust Fan Room	Fan Unit Pad	Concrete	Grey	Flaking	30	0.6	Negative
1	3	Girl's Gym Exhaust Fan Room	W4	Terracotta	Green	Flaking	8	0	Negative
1	3	Girl's Gym Exhaust Fan Room	Ceiling	Concrete	White	None	0	0.2	Negative

		Dates: 6/5 - 7/6/2023	Lead-Safe Certification Assessment Report						
		Inspector Name and Certificate Number: Tim Smith 057662	John Bartram High School						
		Inspection Company: BATA	2401 S 67th St, Philadelphia PA 19142						
E l e m e n t	F l o o r	On-Site Room Name	Component	Substrate Material [1]	Paint Color	Description of Paint Damage	Damage Quantity (sf) [2]	XRF Reading (mg/cm2)	XRF (positive/ negative) [3]
1	3	Girl's Gym Exhaust Fan Room	Floor	Concrete	Not Painted	N/A	N/A	N/A	N/A
1	3	Hallway to Fan Rooms and Book Storage (near Girl's Restroom)	W1	Plaster	White	Cracking	20	0.2	Negative
1	3	Hallway to Fan Rooms and Book Storage (near Girl's Restroom)	Doorframe	Metal	Brown	Friction	8	0.8	Positive
1	3	Hallway to Fan Rooms and Book Storage (near Girl's Restroom)	W2	Plaster	White	Cracking	420	0	Negative
1	3	Hallway to Fan Rooms and Book Storage (near Girl's Restroom)	Covebase	Concrete	Grey	Chipping	80	0	Negative
1	3	Hallway to Fan Rooms and Book Storage (near Girl's Restroom)	Railing	Metal	Brown	Chipping	8	0	Negative
1	3	Hallway to Fan Rooms and Book Storage (near Girl's Restroom)	W3	Plaster	White	Cracking	24	0.1	Negative
1	3	Hallway to Fan Rooms and Book Storage (near Girl's Restroom)	W4	Plaster	White	Cracking	300	0.2	Negative
1	3	Hallway to Fan Rooms and Book Storage (near Girl's Restroom)	Ceiling	1'x1' Ceiling Tile	White	Cracking	36	0	Negative
1	3	Hallway to Fan Rooms and Book Storage (near Girl's Restroom)	Floor	Concrete	Not Painted	N/A	N/A	N/A	N/A
1	3	Book Storage (near Fan Rooms)	W1	Terracotta	Green	None	0	0	Negative
1	3	Book Storage (near Fan Rooms)	Doorframe	Metal	Brown	Friction	4	0.4	Negative
1	3	Book Storage (near Fan Rooms)	Door	Metal	Brown	Friction	6	0.3	Negative
1	3	Book Storage (near Fan Rooms)	W2	Terracotta	Green	None	0	0	Negative
1	3	Book Storage (near Fan Rooms)	W3	Terracotta	Green	None	0	0.2	Negative
1	3	Book Storage (near Fan Rooms)	W4	Terracotta	Green	None	0	0.1	Negative
1	3	Book Storage (near Fan Rooms)	Ceiling	1'x1' Ceiling Tile	Not Painted	N/A	N/A	N/A	N/A
1	3	Book Storage (near Fan Rooms)	Floor	Concrete	Not Painted	N/A	N/A	N/A	N/A
1	3	Classroom 316	W1	Drywall	White/Pink	Cracking	12	0.1	Negative
1	3	Classroom 316	Doorframe	Metal	Brown	Friction	4	0.1	Negative

		Dates: 6/5 - 7/6/2023	Lead-Safe Certification Assessment Report							
		Inspector Name and Certificate Number: Tim Smith 057662	John Bartram High School							
		Inspection Company: BATA	2401 S 67th St, Philadelphia PA 19142							
E l e m e n t	F l o o r	On-Site Room Name	Component	Substrate Material [1]	Paint Color	Description of Paint Damage	Damage Quantity (sf) [2]	XRF Reading (mg/cm ²)	XRF (positive/ negative) [3]	
1	3	Classroom 316	Covebase	Wood	Brown	None	0	0.1	Negative	
1	3	Classroom 316	W2	Terracotta	Not Painted	N/A	N/A	N/A	N/A	
1	3	Classroom 316	W3	Terracotta	Not Painted	N/A	N/A	N/A	N/A	
1	3	Classroom 316	Radiator cover	Metal	Brown	Chipping	2	1.1	Positive	
1	3	Classroom 316	W4	Drywall	White/Pink	Cracking	16	0.1	Negative	
1	3	Classroom 316	Ceiling	Plaster	Not Painted	N/A	N/A	N/A	N/A	
1	3	Classroom 316	Floor	Wood	Not Painted	N/A	N/A	N/A	N/A	
1	3	Storage Room along exterior wall of Classroom 316	W1	Terracotta	Not Painted	N/A	N/A	N/A	N/A	
1	3	Storage Room along exterior wall of Classroom 316	Doorframe	Metal	Brown	Chipping	8	1.1	Positive	
1	3	Storage Room along exterior wall of Classroom 316	W2	Terracotta	Not Painted	N/A	N/A	N/A	N/A	
1	3	Storage Room along exterior wall of Classroom 316	W3	Terracotta	Not Painted	N/A	N/A	N/A	N/A	
1	3	Storage Room along exterior wall of Classroom 316	W4	Terracotta	Not Painted	N/A	N/A	N/A	N/A	
1	3	Storage Room along exterior wall of Classroom 316	Ceiling	Concrete	Not Painted	N/A	N/A	N/A	N/A	
1	3	Storage Room along exterior wall of Classroom 316	Floor	Wood	Not Painted	N/A	N/A	N/A	N/A	
1	3	Book Storage Room along hallway wall of Classroom 316	W1	Plaster	White	Chipping	60	0.1	Negative	
1	3	Book Storage Room along hallway wall of Classroom 316	Doorframe	Metal	Brown	Friction	4	1.1	Positive	
1	3	Book Storage Room along hallway wall of Classroom 316	W2	Plaster	White	Cracking	180	0	Negative	
1	3	Book Storage Room along hallway wall of Classroom 316	W3	Plaster	White	Cracking	150	0	Negative	
1	3	Book Storage Room along hallway wall of Classroom 316	Pipe Cover	Metal	Tan	Chipping	1	0.4	Negative	
1	3	Book Storage Room along hallway wall of Classroom 316	Pipe Insulation	Asbestos	White	None	0	0	Negative	
1	3	Book Storage Room along hallway wall of Classroom 316	Radiator cover	Metal	Brown	Chipping	4	0.6	Negative	

		Dates: 6/5 - 7/6/2023	Lead-Safe Certification Assessment Report						
		Inspector Name and Certificate Number: Tim Smith 057662	John Bartram High School						
		Inspection Company: BATA	2401 S 67th St, Philadelphia PA 19142						
E l e m e n t	F l o o r	On-Site Room Name	Component	Substrate Material [1]	Paint Color	Description of Paint Damage	Damage Quantity (sf) [2]	XRF Reading (mg/cm2)	XRF (positive/ negative) [3]
1	3	Book Storage Room along hallway wall of Classroom 316	W4	Plaster	White	Cracking	180	0	Negative
1	3	Book Storage Room along hallway wall of Classroom 316	Ceiling	Plaster	White	Cracking	40	0.1	Negative
1	3	Book Storage Room along hallway wall of Classroom 316	Floor	Wood	Not Painted	N/A	N/A	N/A	N/A
1	3	Classroom 317	W1	Drywall	White/Blue	Chipping	30	0.1	Negative
1	3	Classroom 317	Doorframe	Metal	Brown	Friction	2	0	Negative
1	3	Classroom 317	Covebase	Wood	Brown	Chipping	20	0.1	Negative
1	3	Classroom 317	W2	Drywall	White/Blue	Chipping	30	0	Negative
1	3	Classroom 317	W3	Terracotta	Not Painted	N/A	N/A	N/A	N/A
1	3	Classroom 317	Radiator cover	Metal	Brown	Chipping	2	0.7	Positive
1	3	Classroom 317	W4	Terracotta	Not Painted	N/A	N/A	N/A	N/A
1	3	Classroom 317	Ceiling	Plaster	Not Painted	N/A	N/A	N/A	N/A
1	3	Classroom 317	Floor	Wood	Not Painted	N/A	N/A	N/A	N/A
1	3	Classroom 318	W1	Drywall	White	None	0	0	Negative
1	3	Classroom 318	Doorframe	Metal	Brown	Friction	4	0.2	Negative
1	3	Classroom 318	Covebase	Wood	Brown	Chipping	30	0.1	Negative
1	3	Classroom 318	W2	Drywall	White	Cracking	3	0.1	Negative
1	3	Classroom 318	W3	Terracotta	Not Painted	N/A	N/A	N/A	N/A
1	3	Classroom 318	Radiator cover	Metal	Brown	Chipping	2	0.5	Negative
1	3	Classroom 318	W4	Terracotta	Not Painted	N/A	N/A	N/A	N/A
1	3	Classroom 318	Ceiling	Plaster	Not Painted	N/A	N/A	N/A	N/A
1	3	Classroom 318	Floor	Wood	Not Painted	N/A	N/A	N/A	N/A
1	3	Classroom 319	W1	Drywall	White/Pink	Cracking	12	0.1	Negative
1	3	Classroom 319	Doorframe	Metal	Brown	Friction	2	0.1	Negative
1	3	Classroom 319	Covebase	Wood	Brown	None	0	0.1	Negative

		Dates: 6/5 - 7/6/2023	Lead-Safe Certification Assessment Report						
		Inspector Name and Certificate Number: Tim Smith 057662	John Bartram High School						
		Inspection Company: BATA	2401 S 67th St, Philadelphia PA 19142						
E l e m e n t	F l o o r	On-Site Room Name	Component	Substrate Material [1]	Paint Color	Description of Paint Damage	Damage Quantity (sf) [2]	XRF Reading (mg/cm2)	XRF (positive/ negative) [3]
1	3	Classroom 319	W2	Terracotta	Not Painted	N/A	N/A	N/A	N/A
1	3	Classroom 319	W3	Terracotta	Not Painted	N/A	N/A	N/A	N/A
1	3	Classroom 319	Radiator cover	Metal	Brown	Chipping	2	0.7	Positive
1	3	Classroom 319	W4	Drywall	White/Pink	Cracking	4	0.1	Negative
1	3	Classroom 319	Ceiling	Plaster	Not Painted	N/A	N/A	N/A	N/A
1	3	Classroom 319	Floor	Wood	Not Painted	N/A	N/A	N/A	N/A
1	3	Classroom 320	W1	Plaster	White	Cracking	60	0	Negative
1	3	Classroom 320	Doorframe	Metal	Brown	Friction	2	1.1	Positive
1	3	Classroom 320	Conduit	Metal	White	None	0	0.2	Negative
1	3	Classroom 320	Pipe	Metal	White	None	0	14.4	Positive
1	3	Classroom 320	W2	Plaster	White	Chipping	3	0.1	Negative
1	3	Classroom 320	W3	Plaster	White	Cracking	80	0	Negative
1	3	Classroom 320	Radiator cover	Metal	Brown	Chipping	4	0.1	Negative
1	3	Classroom 320	W4	Plaster	White	None	0	0.4	Negative
1	3	Classroom 320	Ceiling	Drywall	White	None	0	0.1	Negative
1	3	Classroom 320	Ceiling	2'x4' Ceiling Tile	Not Painted	N/A	N/A	N/A	N/A
1	3	Classroom 320	Floor	Floor Covering	Not Painted	N/A	N/A	N/A	N/A
1	3	Classroom 321	W1	Plaster	White	Chipping	8	0	Negative
1	3	Classroom 321	Doorframe	Metal	Brown	Friction	1	0.6	Negative
1	3	Classroom 321	Pipe	Metal	White	None	0	18	Positive
1	3	Classroom 321	Pipe Insulation	Asbestos	White	None	0	0.3	Negative
1	3	Classroom 321	W2	Plaster	White	Flaking	2	0.1	Negative
1	3	Classroom 321	W3	Plaster	White	Cracking	60	0	Negative
1	3	Classroom 321	Conduit	Metal	White	None	0	0.2	Negative
1	3	Classroom 321	Radiator cover	Metal	Brown	Chipping	12	0.1	Negative
1	3	Classroom 321	W4	Plaster	White	None	0	0.4	Negative

		Dates: 6/5 - 7/6/2023	Lead-Safe Certification Assessment Report							
		Inspector Name and Certificate Number: Tim Smith 057662	John Bartram High School							
		Inspection Company: BATA	2401 S 67th St, Philadelphia PA 19142							
E l e m e n t	F l o o r	On-Site Room Name	Component	Substrate Material [1]	Paint Color	Description of Paint Damage	Damage Quantity (sf) [2]	XRF Reading (mg/cm2)	XRF (positive/ negative) [3]	
1	3	Classroom 321	Ceiling	Drywall	White	None	0	0	Negative	
1	3	Classroom 321	Ceiling	2'x4' Ceiling Tile	Not Painted	N/A	N/A	N/A	N/A	
1	3	Classroom 321	Floor	Floor Tile	Not Painted	N/A	N/A	N/A	N/A	
1	3	Prep Room 322	W1	Plaster	White	Cracking	6	0.1	Negative	
1	3	Prep Room 322	Doorframe	Metal	Brown	None	0	0.9	Positive	
1	3	Prep Room 322	Conduit	Plastic	White	None	0	0.1	Negative	
1	3	Prep Room 322	Windowframe	Metal	Brown	None	0	0.4	Negative	
1	3	Prep Room 322	Window Sash	Wood	Brown	None	0	0.1	Negative	
1	3	Prep Room 322	Door Trim	Wood	Brown	None	0	0.4	Negative	
1	3	Prep Room 322	W2	Plaster	White	None	0	0	Negative	
1	3	Prep Room 322	Door	Wood	Brown	None	0	0.1	Negative	
1	3	Prep Room 322	Pipe	Metal	White	None	0	0.2	Negative	
1	3	Prep Room 322	Conduit	Metal	White	None	0	0.1	Negative	
1	3	Prep Room 322	W3	Plaster	White	Cracking	12	0.5	Negative	
1	3	Prep Room 322	Radiator cover	Metal	Brown	Flaking	2	0.6	Negative	
1	3	Prep Room 322	Windowframe	Wood	Brown	None	0	0.2	Negative	
1	3	Prep Room 322	W4	Plaster	White	Cracking	30	0	Negative	
1	3	Prep Room 322	Covebase	Wood	Brown	None	0	0.2	Negative	
1	3	Prep Room 322	Ceiling	Drywall	White	None	0	0.3	Negative	
1	3	Prep Room 322	Ceiling	2'x4' Ceiling Tile	Not Painted	N/A	N/A	N/A	N/A	
1	3	Prep Room 322	Floor	Floor Tile	Not Painted	N/A	N/A	N/A	N/A	
1	3	Prep Room 322-Compressor Room	W1	Plaster	White	Flaking	3	0	Negative	
1	3	Prep Room 322-Compressor Room	Door	Wood	Brown	None	0	0.2	Negative	
1	3	Prep Room 322-Compressor Room	Doorframe	Metal	Brown	None	0	0.3	Negative	
1	3	Prep Room 322-Compressor Room	Door Trim	Wood	Brown	None	0	0.4	Negative	
1	3	Prep Room 322-Compressor Room	W2	Plaster	White	None	0	0	Negative	

		Dates: 6/5 - 7/6/2023	Lead-Safe Certification Assessment Report						
		Inspector Name and Certificate Number: Tim Smith 057662	John Bartram High School						
		Inspection Company: BATA	2401 S 67th St, Philadelphia PA 19142						
Element	Floor	On-Site Room Name	Component	Substrate Material [1]	Paint Color	Description of Paint Damage	Damage Quantity (sf) [2]	XRF Reading (mg/cm2)	XRF (positive/negative) [3]
1	3	Prep Room 322-Compressor Room	W3	Plaster	White	None	0	0.2	Negative
1	3	Prep Room 322-Compressor Room	Conduit	Metal	White	None	0	0.1	Negative
1	3	Prep Room 322-Compressor Room	W4	Plaster	White	None	0	0	Negative
1	3	Prep Room 322-Compressor Room	Covebase	Wood	Brown	None	0	0.1	Negative
1	3	Prep Room 322-Compressor Room	Ceiling	Plaster	White	None	0	No Access	No Access
1	3	Prep Room 322-Compressor Room	Floor	Floor Tile	Not Painted	N/A	N/A	N/A	N/A
1	3	Prep Room 322 Closet	W1	Plaster	White	Cracking	2	0	Negative
1	3	Prep Room 322 Closet	Door	Wood	Brown	None	0	0	Negative
1	3	Prep Room 322 Closet	Doorframe	Metal	Brown	None	0	0.4	Negative
1	3	Prep Room 322 Closet	Door Trim	Wood	Brown	None	0	0.3	Negative
1	3	Prep Room 322 Closet	W2	Plaster	White	None	0	0	Negative
1	3	Prep Room 322 Closet	Window Trim	Metal	Brown	None	0	0.3	Negative
1	3	Prep Room 322 Closet	W3	Plaster	White	None	0	0	Negative
1	3	Prep Room 322 Closet	W4	Plaster	White	None	0	0	Negative
1	3	Prep Room 322 Closet	Ceiling	Plaster	White	Cracking	4	0.1	Negative
1	3	Prep Room 322 Closet	Floor	Floor Tile	Not Painted	N/A	N/A	N/A	N/A
1	3	Prep Room 323	W1	Plaster	White	None	0	0.1	Negative
1	3	Prep Room 323	Doorframe	Metal	Brown	None	0	0.8	Positive
1	3	Prep Room 323	Conduit	Plastic	White	None	0	0.2	Negative
1	3	Prep Room 323	Windowframe	Metal	Brown	None	0	0.2	Negative
1	3	Prep Room 323	W2	Plaster	White	Cracking	6	0	Negative
1	3	Prep Room 323	Conduit	Metal	White	None	0	0.1	Negative
1	3	Prep Room 323	W3	Plaster	White	Cracking	4	0.6	Negative
1	3	Prep Room 323	Pipe Cover	Metal	White	None	0	3.2	Positive
1	3	Prep Room 323	Pipe Insulation	Asbestos	White	None	0	0.2	Negative
1	3	Prep Room 323	Pipe	Metal	White	None	0	15.8	Positive

		Dates: 6/5 - 7/6/2023	Lead-Safe Certification Assessment Report						
		Inspector Name and Certificate Number: Tim Smith 057662	John Bartram High School						
		Inspection Company: BATA	2401 S 67th St, Philadelphia PA 19142						
E l e m e n t	F l o o r	On-Site Room Name	Component	Substrate Material [1]	Paint Color	Description of Paint Damage	Damage Quantity (sf) [2]	XRF Reading (mg/cm2)	XRF (positive/ negative) [3]
1	3	Prep Room 323	Radiator cover	Metal	Brown	Flaking	2	0.4	Negative
1	3	Prep Room 323	W4	Plaster	White	None	0	0.2	Negative
1	3	Prep Room 323	Covebase	Wood	Brown	None	0	0.1	Negative
1	3	Prep Room 323	Wall Trim	Wood	Brown	None	0	0.1	Negative
1	3	Prep Room 323	Ceiling	Drywall	White	None	0	0.1	Negative
1	3	Prep Room 323	Ceiling	2'x4' Ceiling Tile	Not Painted	N/A	N/A	N/A	N/A
1	3	Prep Room 323	Floor	Floor Tile	Not Painted	N/A	N/A	N/A	N/A
1	3	Prep Room 323-Closet 1	W1	No Access	No Access	No Access	No Access	No Access	No Access
1	3	Prep Room 323-Closet 1	W2	No Access	No Access	No Access	No Access	No Access	No Access
1	3	Prep Room 323-Closet 1	W3	No Access	No Access	No Access	No Access	No Access	No Access
1	3	Prep Room 323-Closet 1	W4	No Access	No Access	No Access	No Access	No Access	No Access
1	3	Prep Room 323-Closet 1	Ceiling	No Access	No Access	No Access	No Access	No Access	No Access
1	3	Prep Room 323-Closet 1	Floor	No Access	No Access	No Access	No Access	No Access	No Access
1	3	Prep Room 323-Closet 2	W1	No Access	No Access	No Access	No Access	No Access	No Access
1	3	Prep Room 323-Closet 2	W2	No Access	No Access	No Access	No Access	No Access	No Access
1	3	Prep Room 323-Closet 2	W3	No Access	No Access	No Access	No Access	No Access	No Access
1	3	Prep Room 323-Closet 2	W4	No Access	No Access	No Access	No Access	No Access	No Access
1	3	Prep Room 323-Closet 2	Ceiling	No Access	No Access	No Access	No Access	No Access	No Access
1	3	Prep Room 323-Closet 2	Floor	No Access	No Access	No Access	No Access	No Access	No Access
1	3	Classroom 324	W1	Plaster	White	Flaking	10	0.1	Negative
1	3	Classroom 324	Doorframe	Metal	Brown	None	0	0.8	Positive
1	3	Classroom 324	Conduit	Plastic	White	None	0	0.4	Negative
1	3	Classroom 324	Pipe	Metal	White	None	0	14.4	Positive
1	3	Classroom 324	W2	Plaster	White	Cracking	30	0.1	Negative
1	3	Classroom 324	W3	Plaster	White	Cracking	60	0	Negative
1	3	Classroom 324	Conduit	Metal	White	None	0	0.3	Negative

		Dates: 6/5 - 7/6/2023	Lead-Safe Certification Assessment Report						
		Inspector Name and Certificate Number: Tim Smith 057662	John Bartram High School						
		Inspection Company: BATA	2401 S 67th St, Philadelphia PA 19142						
E l e m e n t	F l o o r	On-Site Room Name	Component	Substrate Material [1]	Paint Color	Description of Paint Damage	Damage Quantity (sf) [2]	XRF Reading (mg/cm2)	XRF (positive/ negative) [3]
1	3	Classroom 324	Radiator cover	Metal	Brown	Cracking	5	0.2	Negative
1	3	Classroom 324	W4	Plaster	White	None	0	0.4	Negative
1	3	Classroom 324	Wall Trim	Wood	Brown	None	0	0.1	Negative
1	3	Classroom 324	Ceiling	Drywall	White	None	0	0	Negative
1	3	Classroom 324	Ceiling	2'x4' Ceiling Tile	Not Painted	N/A	N/A	N/A	N/A
1	3	Classroom 324	Floor	Floor Tile	Not Painted	N/A	N/A	N/A	N/A
1	3	Classroom 325	W1	Plaster	White	Flaking	16	0	Negative
1	3	Classroom 325	Doorframe	Metal	Brown	Friction	2	0.8	Positive
1	3	Classroom 325	Conduit	Plastic	White	None	0	0.3	Negative
1	3	Classroom 325	Pipe	Metal	White	Chipping	2	0	Negative
1	3	Classroom 325	W2	Plaster	White	None	0	0.5	Negative
1	3	Classroom 325	W3	Plaster	White	Flaking	20	0.6	Negative
1	3	Classroom 325	Conduit	Metal	White	None	0	0	Negative
1	3	Classroom 325	Radiator cover	Metal	Brown	Chipping	4	0.5	Negative
1	3	Classroom 325	W4	Plaster	White	Chipping	12	0.6	Negative
1	3	Classroom 325	Wall Trim	Wood	Brown	None	0	0.1	Negative
1	3	Classroom 325	Ceiling	Drywall	White	None	0	0.1	Negative
1	3	Classroom 325	Ceiling	2'x4' Ceiling Tile	Not Painted	N/A	N/A	N/A	N/A
1	3	Classroom 325	Floor	Floor Tile	Not Painted	N/A	N/A	N/A	N/A
1	3	Narrow Hallway across from Boys Restroom connecting Storage Rooms 326A, 326B, 326C to Fan Room 326D	W1	Plaster	White	Cracking	12	0.1	Negative
1	3	Narrow Hallway across from Boys Restroom connecting Storage Rooms 326A, 326B, 326C to Fan Room 326D	Doorframe	Metal	Brown	Friction	10	0.8	Positive
1	3	Narrow Hallway across from Boys Restroom connecting Storage Rooms 326A, 326B, 326C to Fan Room 326D	W2	Plaster	White	Cracking	180	0.1	Negative

		Dates: 6/5 - 7/6/2023	Lead-Safe Certification Assessment Report						
		Inspector Name and Certificate Number: Tim Smith 057662	John Bartram High School						
		Inspection Company: BATA	2401 S 67th St, Philadelphia PA 19142						
E l e m e n t	F l o o r	On-Site Room Name	Component	Substrate Material [1]	Paint Color	Description of Paint Damage	Damage Quantity (sf) [2]	XRF Reading (mg/cm2)	XRF (positive/ negative) [3]
1	3	Narrow Hallway across from Boys Restroom connecting Storage Rooms 326A, 326B, 326C to Fan Room 326D	Conduit	Plastic	White	None	0	0.3	Negative
1	3	Narrow Hallway across from Boys Restroom connecting Storage Rooms 326A, 326B, 326C to Fan Room 326D	W3	Plaster	White	Cracking	20	0	Negative
1	3	Narrow Hallway across from Boys Restroom connecting Storage Rooms 326A, 326B, 326C to Fan Room 326D	W4	Plaster	White	Flaking	85	0	Negative
1	3	Narrow Hallway across from Boys Restroom connecting Storage Rooms 326A, 326B, 326C to Fan Room 326D	Covebase	Concrete	Grey	None	0	0.2	Negative
1	3	Narrow Hallway across from Boys Restroom connecting Storage Rooms 326A, 326B, 326C to Fan Room 326D	Ceiling	1'x1' Ceiling Tile	Not Painted	N/A	N/A	N/A	N/A
1	3	Narrow Hallway across from Boys Restroom connecting Storage Rooms 326A, 326B, 326C to Fan Room 326D	Floor	Concrete	Grey	None	0	0.1	Negative
1	3	Storage Room 326A	W1	Plaster	White	Cracking	24	0	Negative
1	3	Storage Room 326A	Doorframe	Metal	Brown	Friction	4	0.5	Negative
1	3	Storage Room 326A	Covebase	Concrete	Grey	None	0	0.1	Negative
1	3	Storage Room 326A	W2	Plaster	White	Cracking	300	0	Negative
1	3	Storage Room 326A	W3	Plaster	White	Cracking	60	0	Negative
1	3	Storage Room 326A	W4	Plaster	White	Cracking	220	0	Negative
1	3	Storage Room 326A	Radiator	Metal	Brown	None	0	0.1	Negative
1	3	Storage Room 326A	Windowframe	Metal	Brown	None	0	0.5	Negative
1	3	Storage Room 326A	Ceiling	Plaster	White	Flaking	30	0.1	Negative
1	3	Storage Room 326A	Floor	Concrete	Grey	None	0	0.2	Negative
1	3	Storage Room 326B	W1	Plaster	White/Pink	Cracking	12	0	Negative

		Dates: 6/5 - 7/6/2023	Lead-Safe Certification Assessment Report						
		Inspector Name and Certificate Number: Tim Smith 057662	John Bartram High School						
		Inspection Company: BATA	2401 S 67th St, Philadelphia PA 19142						
E l e m e n t	F l o o r	On-Site Room Name	Component	Substrate Material [1]	Paint Color	Description of Paint Damage	Damage Quantity (sf) [2]	XRF Reading (mg/cm ²)	XRF (positive/ negative) [3]
1	3	Storage Room 326B	Doorframe	Metal	Brown	Friction	8	1	Positive
1	3	Storage Room 326B	Conduit	Plastic	White	None	0	0.1	Negative
1	3	Storage Room 326B	W2	Plaster	White/Pink	None	0	0.2	Negative
1	3	Storage Room 326B	W3	Plaster	White/Pink	Cracking	30	0	Negative
1	3	Storage Room 326B	Covebase	Concrete	Brown	None	0	0.2	Negative
1	3	Storage Room 326B	Radiator	Metal	Brown	None	0	0.1	Negative
1	3	Storage Room 326B	W4	Plaster	White/Pink	Flaking	6	0	Negative
1	3	Storage Room 326B	Ceiling	Plaster	White	None	0	0.1	Negative
1	3	Storage Room 326B	Ceiling	2'x4' Ceiling Tile	Not Painted	N/A	N/A	N/A	N/A
1	3	Storage Room 326B	Floor	Concrete	Not Painted	N/A	N/A	N/A	N/A
1	3	Storage Room 326C	W1	Plaster	White	Cracking	80	0	Negative
1	3	Storage Room 326C	Doorframe	Metal	Brown	Friction	8	0.1	Negative
1	3	Storage Room 326C	W2	Plaster	White	Cracking	110	0	Negative
1	3	Storage Room 326C	Covebase	Concrete	Grey	None	0	0.1	Negative
1	3	Storage Room 326C	W3	Plaster	White	Cracking	40	0	Negative
1	3	Storage Room 326C	Radiator	Metal	Brown	None	0	0.1	Negative
1	3	Storage Room 326C	W4	Plaster	White	Cracking	240	0	Negative
1	3	Storage Room 326C	Ceiling	Plaster	White	Spalling	4	0.3	Negative
1	3	Storage Room 326C	Ceiling	2'x4' Ceiling Tile	Not Painted	N/A	N/A	N/A	N/A
1	3	Storage Room 326C	Floor	Concrete	Not Painted	N/A	N/A	N/A	N/A
1	3	Boy's Gym Exhaust Fan Room	W1	Terracotta	Green	None	0	0	Negative
1	3	Boy's Gym Exhaust Fan Room	Door	Metal	Brown	Chipping	9	0.2	Negative
1	3	Boy's Gym Exhaust Fan Room	Doorframe	Metal	Brown	Friction	7	1	Positive
1	3	Boy's Gym Exhaust Fan Room	Conduit	Metal	Green	Chipping	4	0	Negative
1	3	Boy's Gym Exhaust Fan Room	W2	Terracotta	Green	Flaking	24	0.1	Negative
1	3	Boy's Gym Exhaust Fan Room	Railing	Metal	Grey	Chipping	24	7	Positive

		Dates: 6/5 - 7/6/2023	Lead-Safe Certification Assessment Report						
		Inspector Name and Certificate Number: Tim Smith 057662	John Bartram High School						
		Inspection Company: BATA	2401 S 67th St, Philadelphia PA 19142						
E l e m e n t	F l o o r	On-Site Room Name	Component	Substrate Material [1]	Paint Color	Description of Paint Damage	Damage Quantity (sf) [2]	XRF Reading (mg/cm2)	XRF (positive/ negative) [3]
1	3	Boy's Gym Exhaust Fan Room	Fan Unit Pad	Concrete	Grey	Flaking	3	0.2	Negative
1	3	Boy's Gym Exhaust Fan Room	Exterior Fan Unit	Metal	White	Flaking	70	15.8	Positive
1	3	Boy's Gym Exhaust Fan Room	Exterior Fan Unit	Metal	White	Flaking	160	12.1	Positive
1	3	Boy's Gym Exhaust Fan Room	W3	Terracotta	Green	Chipping	6	0.5	Negative
1	3	Boy's Gym Exhaust Fan Room	W4	Terracotta	Green	Flaking	7	0.1	Negative
1	3	Boy's Gym Exhaust Fan Room	Ceiling	Concrete	White	Efflorescence	12	0.4	Negative
1	3	Boy's Gym Exhaust Fan Room	Floor	Concrete	Grey	None	0	0.1	Negative
1	3	Storage Closet inside Fan Room 326D	W1	Terracotta	White	Flaking	10	0.2	Negative
1	3	Storage Closet inside Fan Room 326D	Doorframe	Metal	Brown	Friction	1	0.6	Negative
1	3	Storage Closet inside Fan Room 326D	W2	Terracotta	White	Flaking	3	0.1	Negative
1	3	Storage Closet inside Fan Room 326D	W3	Terracotta	White	None	0	0.6	Negative
1	3	Storage Closet inside Fan Room 326D	W4	Terracotta	White	None	0	0	Negative
1	3	Storage Closet inside Fan Room 326D	Ceiling	Plaster	White	Spalling	100	0.2	Negative
1	3	Storage Closet inside Fan Room 326D	Pipe	Metal	White	Flaking	12	11	Positive
1	3	Storage Closet inside Fan Room 326D	Floor	Concrete	Grey	None	0	0	Negative
1	3	Office 327	W1	Plaster	White/Pink	Flaking	2	0	Negative
1	3	Office 327	Doorframe	Metal	Brown	Friction	2	0.8	Positive
1	3	Office 327	Door	Wood	Brown	None	0	0	Negative
1	3	Office 327	Windowframe	Metal	Brown	None	0	0.5	Negative
1	3	Office 327	W2	Plaster	White/Pink	None	0	0	Negative
1	3	Office 327	Conduit	Plastic	White	None	0	0.1	Negative
1	3	Office 327	W3	Plaster	White/Pink	None	0	0.1	Negative
1	3	Office 327	Pipe Cover	Metal	White	None	0	4.9	Positive
1	3	Office 327	Pipe Insulation	Asbestos	White	None	0	0.1	Negative
1	3	Office 327	Radiator cover	Metal	Brown	Chipping	2	1	Positive
1	3	Office 327	W4	Plaster	White/Pink	Cracking	2	0	Negative

		Dates: 6/5 - 7/6/2023	Lead-Safe Certification Assessment Report							
		Inspector Name and Certificate Number: Tim Smith 057662	John Bartram High School							
		Inspection Company: BATA	2401 S 67th St, Philadelphia PA 19142							
E l e m e n t	F l o o r	On-Site Room Name	Component	Substrate Material [1]	Paint Color	Description of Paint Damage	Damage Quantity (sf) [2]	XRF Reading (mg/cm2)	XRF (positive/ negative) [3]	
1	3	Office 327	Ceiling	Plaster	White	Flaking	220	0.1	Negative	
1	3	Office 327	Ceiling	2'x4' Ceiling Tile	Not Painted	N/A	N/A	N/A	N/A	
1	3	Office 327	Floor	Floor Covering	Not Painted	N/A	N/A	N/A	N/A	
1	3	Office 327 - Closet	W1	Plaster	White	Cracking	20	0	Negative	
1	3	Office 327 - Closet	Doorframe	Metal	Brown	Friction	2	0.5	Negative	
1	3	Office 327 - Closet	W2	Plaster	White	Cracking	30	0.1	Negative	
1	3	Office 327 - Closet	W3	Plaster	White	Cracking	40	0	Negative	
1	3	Office 327 - Closet	W4	Plaster	White	Cracking	40	0	Negative	
1	3	Office 327 - Closet	Ceiling	Plaster	White	Cracking	20	0.2	Negative	
1	3	Office 327 - Closet	Floor	Floor Covering	Not Painted	N/A	N/A	N/A	N/A	
1	3	Office 328	W1	Plaster	White/Pink	Chipping	18	0	Negative	
1	3	Office 328	Doorframe	Metal	Brown	Friction	3	1.2	Positive	
1	3	Office 328	W2	Plaster	White/Pink	Cracking	12	0.1	Negative	
1	3	Office 328	W3	Plaster	White/Pink	None	0	0	Negative	
1	3	Office 328	Conduit	Metal	White	None	0	1.2	Positive	
1	3	Office 328	Pipe Cover	Metal	White	None	0	4.5	Positive	
1	3	Office 328	Pipe Insulation	Asbestos	White	None	0	0.1	Negative	
1	3	Office 328	Radiator cover	Metal	Brown	Chipping	6	0.6	Negative	
1	3	Office 328	W4	Plaster	White/Pink	Cracking	6	0.2	Negative	
1	3	Office 328	Ceiling	Plaster	White	Cracking	30	0	Negative	
1	3	Office 328	Ceiling	2'x4' Ceiling Tile	Not Painted	N/A	N/A	N/A	N/A	
1	3	Office 328	Floor	Floor Covering	Not Painted	N/A	N/A	N/A	N/A	
1	3	Boy's Restroom	W1	Ceramic	White	None	0	0.1	Negative	
1	3	Boy's Restroom	Door	Wood	Brown	Chipping	1	0	Negative	
1	3	Boy's Restroom	Doorframe	Metal	Brown	Friction	6	1	Positive	
1	3	Boy's Restroom	Stall	Polymer	White	None	0	0.1	Negative	

		Dates: 6/5 - 7/6/2023	Lead-Safe Certification Assessment Report						
		Inspector Name and Certificate Number: Tim Smith 057662	John Bartram High School						
		Inspection Company: BATA	2401 S 67th St, Philadelphia PA 19142						
E l e m e n t	F l o o r	On-Site Room Name	Component	Substrate Material [1]	Paint Color	Description of Paint Damage	Damage Quantity (sf) [2]	XRF Reading (mg/cm2)	XRF (positive/ negative) [3]
1	3	Boy's Restroom	W2	Ceramic	White	None	0	0.1	Negative
1	3	Boy's Restroom	W3	Ceramic	White	None	0	0	Negative
1	3	Boy's Restroom	W4	Ceramic	White	None	0	0	Negative
1	3	Boy's Restroom	Pipe	Metal	White	Chipping	4	13.2	Positive
1	3	Boy's Restroom	Radiator cover	Metal	Brown	Flaking	2	0	Negative
1	3	Boy's Restroom	Ceiling	Plaster	White	None	0	0.4	Negative
1	3	Boy's Restroom	Floor	Terrazzo	Not Painted	N/A	N/A	N/A	N/A
1	3	Boy's Restroom - Pipe Shaft	W1	Terracotta	Not Painted	N/A	N/A	N/A	N/A
1	3	Boy's Restroom - Pipe Shaft	Door	Metal	Brown	Chipping	1	0	Negative
1	3	Boy's Restroom - Pipe Shaft	Doorframe	Metal	Brown	Chipping	1	0.9	Positive
1	3	Boy's Restroom - Pipe Shaft	W2	Terracotta	Not Painted	N/A	N/A	N/A	N/A
1	3	Boy's Restroom - Pipe Shaft	W3	Terracotta	Not Painted	N/A	N/A	N/A	N/A
1	3	Boy's Restroom - Pipe Shaft	W4	Terracotta	Not Painted	N/A	N/A	N/A	N/A
1	3	Boy's Restroom - Pipe Shaft	Ceiling	Concrete	Not Painted	N/A	N/A	N/A	N/A
1	3	Boy's Restroom - Pipe Shaft	Floor	Concrete	Not Painted	N/A	N/A	N/A	N/A
1	3	Office 329	W1	Plaster	Tan/Red	None	0	0	Negative
1	3	Office 329	Doorframe	Metal	Brown	Friction	9	0.7	Positive
1	3	Office 329	W2	Plaster	Tan/Red	Cracking	16	0.1	Negative
1	3	Office 329	W3	Plaster	Tan/Red	Chipping	6	0	Negative
1	3	Office 329	Conduit	Metal	Red	None	0	0.1	Negative
1	3	Office 329	Radiator cover	Metal	Brown	Chipping	6	0.1	Negative
1	3	Office 329	W4	Plaster	Tan/Red	None	0	0.1	Negative
1	3	Office 329	Ceiling	Plaster	White	Cracking	4	0.3	Negative
1	3	Office 329	Ceiling	2'x4' Ceiling Tile	Not Painted	N/A	N/A	N/A	N/A
1	3	Office 329	Floor	Floor Covering	Not Painted	N/A	N/A	N/A	N/A
1	3	Office 330	W1	Plaster	White	Cracking	26	0	Negative

		Dates: 6/5 - 7/6/2023	Lead-Safe Certification Assessment Report						
		Inspector Name and Certificate Number: Tim Smith 057662	John Bartram High School						
		Inspection Company: BATA	2401 S 67th St, Philadelphia PA 19142						
E l e m e n t	F l o o r	On-Site Room Name	Component	Substrate Material [1]	Paint Color	Description of Paint Damage	Damage Quantity (sf) [2]	XRF Reading (mg/cm2)	XRF (positive/ negative) [3]
1	3	Office 330	Doorframe	Metal	Brown	Friction	5	1	Positive
1	3	Office 330	Conduit	Plastic	White	None	0	0.7	Positive
1	3	Office 330	W2	Plaster	White	Cracking	70	0	Negative
1	3	Office 330	W3	Plaster	White	Flaking	20	0	Negative
1	3	Office 330	Radiator cover	Metal	Brown	Chipping	6	0.1	Negative
1	3	Office 330	Pipe Cover	Metal	White	Chipping	2	2.5	Positive
1	3	Office 330	Pipe Insulation	Asbestos	White	None	0	0.2	Negative
1	3	Office 330	W4	Plaster	White	Cracking	16	0	Negative
1	3	Office 330	Chair Rail	Wood	White	None	0	0.2	Negative
1	3	Office 330	Ceiling	Plaster	White	Flaking	40	0.1	Negative
1	3	Office 330	Ceiling	2'x4' Ceiling Tile	Not Painted	N/A	N/A	N/A	N/A
1	3	Office 330	Floor	Floor Covering	Not Painted	N/A	N/A	N/A	N/A
1	3	Classroom 331	W1	Plaster	White	Cracking	20	0.2	Negative
1	3	Classroom 331	Doorframe	Metal	Brown	Friction	8	0.8	Positive
1	3	Classroom 331	Conduit	Plastic	White	None	0	0.3	Negative
1	3	Classroom 331	W2	Plaster	White	None	0	0.1	Negative
1	3	Classroom 331	W3	Plaster	White	Flaking	4	0.5	Negative
1	3	Classroom 331	Radiator cover	Metal	Brown	Chipping	6	0.5	Negative
1	3	Classroom 331	Pipe Cover	Metal	White	Chipping	1	4.2	Positive
1	3	Classroom 331	Pipe Insulation	Asbestos	White	None	0	0.2	Negative
1	3	Classroom 331	W4	Plaster	White	Cracking	6	0	Negative
1	3	Classroom 331	Pipe	Metal	White	None	0	0.1	Negative
1	3	Classroom 331	Ceiling	Plaster	White	Cracking	30	0.2	Negative
1	3	Classroom 331	Ceiling	2'x4' Ceiling Tile	Not Painted	N/A	N/A	N/A	N/A
1	3	Classroom 331	Floor	Wood	Not Painted	N/A	N/A	N/A	N/A
1	3	Classroom 331 - Closet	W1	Plaster	White	None	0	0.1	Negative

		Dates: 6/5 - 7/6/2023	Lead-Safe Certification Assessment Report						
		Inspector Name and Certificate Number: Tim Smith 057662	John Bartram High School						
		Inspection Company: BATA	2401 S 67th St, Philadelphia PA 19142						
E l e m e n t	F l o o r	On-Site Room Name	Component	Substrate Material [1]	Paint Color	Description of Paint Damage	Damage Quantity (sf) [2]	XRF Reading (mg/cm2)	XRF (positive/ negative) [3]
1	3	Classroom 331 - Closet	Doorframe	Metal	Brown	Chipping	4	0	Negative
1	3	Classroom 331 - Closet	Conduit	Plastic	White	None	0	0.1	Negative
1	3	Classroom 331 - Closet	W2	Plaster	White	None	0	0.2	Negative
1	3	Classroom 331 - Closet	W3	Plaster	White	Cracking	20	0.4	Negative
1	3	Classroom 331 - Closet	Shelf	Wood	White	Friction	2	0	Negative
1	3	Classroom 331 - Closet	W4	Plaster	White	None	0	0	Negative
1	3	Classroom 331 - Closet	Ceiling	Plaster	White	Cracking	4	No Access	No Access
1	3	Classroom 331 - Closet	Floor	Wood	Not Painted	N/A	N/A	N/A	N/A
1	3	Classroom 332	W1	Plaster	Green	None	0	0.1	Negative
1	3	Classroom 332	Doorframe	Metal	Brown	Friction	3	0.9	Positive
1	3	Classroom 332	W2	Plaster	Green	Cracking	4	0.1	Negative
1	3	Classroom 332	W3	Plaster	Green	Chipping	12	0.1	Negative
1	3	Classroom 332	Conduit	Plastic	White	None	0	0.3	Negative
1	3	Classroom 332	Radiator cover	Metal	Brown	Chipping	10	0.1	Negative
1	3	Classroom 332	Pipe Cover	Metal	White	Chipping	5	3.2	Positive
1	3	Classroom 332	Pipe Insulation	Asbestos	White	None	0	0	Negative
1	3	Classroom 332	W4	Plaster	Green	Cracking	2	0	Negative
1	3	Classroom 332	Pipe	Metal	White	Chipping	3	15.3	Positive
1	3	Classroom 332	Ceiling	Plaster	White	Flaking	260	0.2	Negative
1	3	Classroom 332	Ceiling	2'x4' Ceiling Tile	Not Painted	N/A	N/A	N/A	N/A
1	3	Classroom 332	Floor	Wood	Not Painted	N/A	N/A	N/A	N/A
1	3	Classroom 332 - Closet	W1	Plaster	White	Cracking	1	0.3	Negative
1	3	Classroom 332 - Closet	Doorframe	Metal	Green	Chipping	1	0.3	Negative
1	3	Classroom 332 - Closet	W2	Plaster	White	Cracking	6	0.2	Negative
1	3	Classroom 332 - Closet	W3	Plaster	White	Cracking	4	0.4	Negative
1	3	Classroom 332 - Closet	Shelf	Wood	White	None	0	0.1	Negative

		Dates: 6/5 - 7/6/2023	Lead-Safe Certification Assessment Report							
		Inspector Name and Certificate Number: Tim Smith 057662	John Bartram High School							
		Inspection Company: BATA	2401 S 67th St, Philadelphia PA 19142							
E l e m e n t	F l o o r	On-Site Room Name	Component	Substrate Material [1]	Paint Color	Description of Paint Damage	Damage Quantity (sf) [2]	XRF Reading (mg/cm2)	XRF (positive/ negative) [3]	
1	3	Classroom 332 - Closet	W4	Plaster	White	Cracking	6	0.2	Negative	
1	3	Classroom 332 - Closet	Conduit	Plastic	White	None	0	0.1	Negative	
1	3	Classroom 332 - Closet	Ceiling	Plaster	White	None	0	No Access	No Access	
1	3	Classroom 332 - Closet	Floor	Wood	Not Painted	N/A	N/A	N/A	N/A	
1	3	Classroom 333	W1	Plaster	White/Pink	Flaking	20	0	Negative	
1	3	Classroom 333	Doorframe	Metal	Brown	Friction	8	0.5	Negative	
1	3	Classroom 333	W2	Plaster	Green	None	0	0.2	Negative	
1	3	Classroom 333	W3	Plaster	White/Pink	Cracking	56	0	Negative	
1	3	Classroom 333	Conduit	Plastic	White	None	0	0.8	Positive	
1	3	Classroom 333	Radiator cover	Metal	Brown	Chipping	12	0.3	Negative	
1	3	Classroom 333	Pipe Cover	Metal	White	Chipping	4	4.6	Positive	
1	3	Classroom 333	Pipe Insulation	Asbestos	White	None	0	0.1	Negative	
1	3	Classroom 333	W4	Plaster	Green	Chipping	6	0.1	Negative	
1	3	Classroom 333	Ceiling	Plaster	White	Flaking	30	0	Negative	
1	3	Classroom 333	Ceiling	2'x4' Ceiling Tile	Not Painted	N/A	N/A	N/A	N/A	
1	3	Classroom 333	Floor	Wood	Not Painted	N/A	N/A	N/A	N/A	
1	3	Classroom 334	W1	Plaster	Blue	Chipping	4	0.1	Negative	
1	3	Classroom 334	Doorframe	Metal	Brown	Friction	8	0.9	Positive	
1	3	Classroom 334	Pipe	Metal	Blue	None	0	16	Positive	
1	3	Classroom 334	W2	Plaster	Blue	None	0	0	Negative	
1	3	Classroom 334	W3	Plaster	Blue	None	0	0.1	Negative	
1	3	Classroom 334	Radiator cover	Metal	Brown	Chipping	10	0.7	Positive	
1	3	Classroom 334	Pipe Cover	Metal	Blue	Chipping	4	3.5	Positive	
1	3	Classroom 334	Pipe Insulation	Asbestos	Blue	None	0	0.1	Negative	
1	3	Classroom 334	W4	Plaster	Blue	None	0	0	Negative	
1	3	Classroom 334	Whiteboard Ledge	Wood	Not Painted	N/A	N/A	N/A	N/A	

		Dates: 6/5 - 7/6/2023	Lead-Safe Certification Assessment Report							
		Inspector Name and Certificate Number: Tim Smith 057662	John Bartram High School							
		Inspection Company: BATA	2401 S 67th St, Philadelphia PA 19142							
E l e m e n t	F l o o r	On-Site Room Name	Component	Substrate Material [1]	Paint Color	Description of Paint Damage	Damage Quantity (sf) [2]	XRF Reading (mg/cm2)	XRF (positive/ negative) [3]	
1	3	Classroom 334	Conduit	Plastic	Blue	None	0	0.9	Positive	
1	3	Classroom 334	Ceiling	Plaster	White	Flaking	30	0.1	Negative	
1	3	Classroom 334	Ceiling	2'x4' Ceiling Tile	Not Painted	N/A	N/A	N/A	N/A	
1	3	Classroom 334	Floor	Wood	Not Painted	N/A	N/A	N/A	N/A	
1	3	Classroom 335	W1	Plaster	White/Pink	Chipping	6	0.1	Negative	
1	3	Classroom 335	Doorframe	Metal	Brown	Friction	5	0.5	Negative	
1	3	Classroom 335	W2	Plaster	White/Pink	Flaking	6	0.1	Negative	
1	3	Classroom 335	W3	Plaster	White/Pink	Cracking	60	0.1	Negative	
1	3	Classroom 335	Pipe	Metal	White	Chipping	6	16.7	Positive	
1	3	Classroom 335	Pipe Cover	Metal	White	Chipping	4	2.6	Positive	
1	3	Classroom 335	Pipe Insulation	Asbestos	White	None	0	0.1	Negative	
1	3	Classroom 335	Radiator cover	Metal	Brown	Chipping	6	0.6	Negative	
1	3	Classroom 335	W4	Plaster	White/Pink	None	0	0.1	Negative	
1	3	Classroom 335	Ceiling	Plaster	White	Flaking	12	0.1	Negative	
1	3	Classroom 335	Ceiling	2'x4' Ceiling Tile	Not Painted	N/A	N/A	N/A	N/A	
1	3	Classroom 335	Floor	Wood	Not Painted	N/A	N/A	N/A	N/A	
1	3	Classroom 336	W1	Plaster	Green	Cracking	8	0	Negative	
1	3	Classroom 336	Doorframe	Metal	Brown	Friction	8	0.5	Negative	
1	3	Classroom 336	W2	Plaster	Green	Cracking	12	0	Negative	
1	3	Classroom 336	W3	Plaster	Green	Cracking	48	0.1	Negative	
1	3	Classroom 336	Pipe	Metal	White/Pink	Chipping	1	0.1	Negative	
1	3	Classroom 336	Pipe Cover	Metal	White/Pink	Chipping	5	4.5	Positive	
1	3	Classroom 336	Pipe Insulation	Asbestos	White	None	0	0.1	Negative	
1	3	Classroom 336	Radiator cover	Metal	Brown	Chipping	6	0.1	Negative	
1	3	Classroom 336	W4	Plaster	Green	Flaking	6	0.1	Negative	
1	3	Classroom 336	Ceiling	Plaster	White	Flaking	160	0.3	Negative	

		Dates: 6/5 - 7/6/2023	Lead-Safe Certification Assessment Report							
		Inspector Name and Certificate Number: Tim Smith 057662	John Bartram High School							
		Inspection Company: BATA	2401 S 67th St, Philadelphia PA 19142							
E l e m e n t	F l o o r	On-Site Room Name	Component	Substrate Material [1]	Paint Color	Description of Paint Damage	Damage Quantity (sf) [2]	XRF Reading (mg/cm2)	XRF (positive/ negative) [3]	
1	3	Classroom 336	Ceiling	2'x4' Ceiling Tile	Not Painted	N/A	N/A	N/A	N/A	
1	3	Classroom 336	Floor	Wood	Not Painted	N/A	N/A	N/A	N/A	
1	3	Classroom 337	W1	Plaster	Green	Cracking	10	0	Negative	
1	3	Classroom 337	Doorframe	Metal	Brown	Friction	8	0.5	Negative	
1	3	Classroom 337	W2	Plaster	Green	None	0	0	Negative	
1	3	Classroom 337	W3	Plaster	Green	Flaking	3	0	Negative	
1	3	Classroom 337	Pipe	Metal	White	Chipping	6	15.2	Positive	
1	3	Classroom 337	Pipe Cover	Metal	White	Chipping	1	3.8	Positive	
1	3	Classroom 337	Pipe Insulation	Asbestos	White	None	0	0.1	Negative	
1	3	Classroom 337	Radiator cover	Metal	Brown	Chipping	10	0.9	Positive	
1	3	Classroom 337	W4	Plaster	Green	None	0	0.2	Negative	
1	3	Classroom 337	Ceiling	Plaster	White	None	0	0.2	Negative	
1	3	Classroom 337	Ceiling	2'x4' Ceiling Tile	Not Painted	N/A	N/A	N/A	N/A	
1	3	Classroom 337	Floor	Wood	Not Painted	N/A	N/A	N/A	N/A	
1	3	Classroom 338	W1	Plaster	Blue	None	0	0	Negative	
1	3	Classroom 338	Doorframe	Metal	Brown	Friction	7	1	Positive	
1	3	Classroom 338	Conduit	Plastic	Blue	None	0	1.2	Positive	
1	3	Classroom 338	W2	Plaster	Blue	Cracking	10	0.1	Negative	
1	3	Classroom 338	W3	Plaster	Blue	Cracking	14	0.5	Negative	
1	3	Classroom 338	Pipe Cover	Metal	Blue	Chipping	4	3.4	Positive	
1	3	Classroom 338	Pipe Insulation	Asbestos	Blue	None	0	0.1	Negative	
1	3	Classroom 338	Radiator cover	Metal	Brown	Chipping	6	0.8	Positive	
1	3	Classroom 338	W4	Plaster	Blue	Cracking	10	0	Negative	
1	3	Classroom 338	Whiteboard Ledge	Wood	Not Painted	N/A	N/A	N/A	N/A	
1	3	Classroom 338	Ceiling	Plaster	White	None	0	0.2	Negative	
1	3	Classroom 338	Ceiling	2'x4' Ceiling Tile	Not Painted	N/A	N/A	N/A	N/A	

		Dates: 6/5 - 7/6/2023	Lead-Safe Certification Assessment Report						
		Inspector Name and Certificate Number: Tim Smith 057662	John Bartram High School						
		Inspection Company: BATA	2401 S 67th St, Philadelphia PA 19142						
E l e m e n t	F l o o r	On-Site Room Name	Component	Substrate Material [1]	Paint Color	Description of Paint Damage	Damage Quantity (sf) [2]	XRF Reading (mg/cm2)	XRF (positive/ negative) [3]
1	3	Classroom 338	Floor	Wood	Not Painted	N/A	N/A	N/A	N/A
1	3	Classroom 339	W1	Plaster	Grey/Purple	Chipping	2	0.1	Negative
1	3	Classroom 339	Doorframe	Metal	Brown	Friction	4	0.7	Positive
1	3	Classroom 339	W2	Plaster	Grey/Purple	None	0	0	Negative
1	3	Classroom 339	W3	Plaster	Grey/Purple	Chipping	4	0.1	Negative
1	3	Classroom 339	Pipe Cover	Metal	Grey/Purple	Chipping	3	3.6	Positive
1	3	Classroom 339	Pipe Insulation	Asbestos	Grey	None	0	0.1	Negative
1	3	Classroom 339	Radiator cover	Metal	Brown	Chipping	2	0.8	Positive
1	3	Classroom 339	W4	Plaster	Grey/Purple	None	0	0.1	Negative
1	3	Classroom 339	Conduit	Plastic	Grey/Purple	None	0	0.9	Positive
1	3	Classroom 339	Ceiling	Plaster	White	None	0	0.2	Negative
1	3	Classroom 339	Ceiling	2'x4' Ceiling Tile	Not Painted	N/A	N/A	N/A	N/A
1	3	Classroom 339	Floor	Wood	Not Painted	N/A	N/A	N/A	N/A
1	3	Classroom 340	W1	Plaster	White	None	0	0	Negative
1	3	Classroom 340	Doorframe	Metal	Brown	Friction	4	1.1	Positive
1	3	Classroom 340	W2	Plaster	White	None	0	0	Negative
1	3	Classroom 340	W3	Plaster	White	None	0	0	Negative
1	3	Classroom 340	Windowsill	Wood	Brown	None	0	0.1	Negative
1	3	Classroom 340	Conduit	Plastic	White	None	0	0.1	Negative
1	3	Classroom 340	Pipe Cover	Metal	White	None	0	3.8	Positive
1	3	Classroom 340	Pipe Insulation	Asbestos	White	None	0	0.1	Negative
1	3	Classroom 340	Radiator cover	Metal	Brown	Chipping	6	0.2	Negative
1	3	Classroom 340	W4	Plaster	White	None	0	0	Negative
1	3	Classroom 340	Whiteboard Ledge	Wood	Brown	None	0	0	Negative
1	3	Classroom 340	Ceiling	Plaster	White	Cracking	40	0.3	Negative
1	3	Classroom 340	Ceiling	2'x4' Ceiling Tile	Not Painted	N/A	N/A	N/A	N/A

		Dates: 6/5 - 7/6/2023	Lead-Safe Certification Assessment Report						
		Inspector Name and Certificate Number: Tim Smith 057662	John Bartram High School						
		Inspection Company: BATA	2401 S 67th St, Philadelphia PA 19142						
E l e m e n t	F l o o r	On-Site Room Name	Component	Substrate Material [1]	Paint Color	Description of Paint Damage	Damage Quantity (sf) [2]	XRF Reading (mg/cm2)	XRF (positive/ negative) [3]
1	3	Classroom 340	Floor	Wood	Not Painted	N/A	N/A	N/A	N/A
1	3	Classroom 341	W1	Plaster	Green	Flaking	9	0	Negative
1	3	Classroom 341	Doorframe	Metal	Brown	Friction	5	0.5	Negative
1	3	Classroom 341	Chalkboard	Chalkboard	White	None	0	0.1	Negative
1	3	Classroom 341	W2	Plaster	Blue	Chipping	8	0.2	Negative
1	3	Classroom 341	W3	Plaster	Green/Blue	None	0	0.1	Negative
1	3	Classroom 341	Pipe Cover	Metal	Blue	None	0	3.7	Positive
1	3	Classroom 341	Pipe Insulation	Asbestos	White	None	0	0.1	Negative
1	3	Classroom 341	Radiator cover	Metal	Brown	Chipping	2	0.6	Negative
1	3	Classroom 341	W4	Plaster	Green	None	0	0.1	Negative
1	3	Classroom 341	Conduit	Plastic	Green	None	0	0.8	Positive
1	3	Classroom 341	Whiteboard Ledge	Wood	Not Painted	N/A	N/A	N/A	N/A
1	3	Classroom 341	Ceiling	Plaster	White	Flaking	40	0.1	Negative
1	3	Classroom 341	Ceiling	2'x4' Ceiling Tile	Not Painted	N/A	N/A	N/A	N/A
1	3	Classroom 341	Floor	Wood	Not Painted	N/A	N/A	N/A	N/A
1	3	Classroom 342	W1	Plaster	White/Pink	Flaking	20	0.1	Negative
1	3	Classroom 342	Doorframe	Metal	Brown	Friction	3	1	Positive
1	3	Classroom 342	W2	Plaster	White/Pink	Cracking	24	0.1	Negative
1	3	Classroom 342	W3	Plaster	White/Pink	Cracking	40	0.6	Negative
1	3	Classroom 342	Pipe	Metal	White	Chipping	6	16.6	Positive
1	3	Classroom 342	Pipe Cover	Metal	White	Chipping	2	3	Positive
1	3	Classroom 342	Pipe Insulation	Asbestos	White	None	0	0.1	Negative
1	3	Classroom 342	Radiator cover	Metal	Brown	Chipping	4	0.1	Negative
1	3	Classroom 342	W4	Plaster	White/Pink	Cracking	14	0.1	Negative
1	3	Classroom 342	Ceiling	Plaster	White	Cracking	80	0.1	Negative
1	3	Classroom 342	Ceiling	2'x4' Ceiling Tile	Not Painted	N/A	N/A	N/A	N/A

		Dates: 6/5 - 7/6/2023	Lead-Safe Certification Assessment Report						
		Inspector Name and Certificate Number: Tim Smith 057662	John Bartram High School						
		Inspection Company: BATA	2401 S 67th St, Philadelphia PA 19142						
E l e m e n t	F l o o r	On-Site Room Name	Component	Substrate Material [1]	Paint Color	Description of Paint Damage	Damage Quantity (sf) [2]	XRF Reading (mg/cm2)	XRF (positive/ negative) [3]
1	3	Classroom 342	Floor	Wood	Not Painted	N/A	N/A	N/A	N/A
1	3	Office 344	W1	Plaster	Green	None	0	0.2	Negative
1	3	Office 344	Doorframe	Metal	Brown	Friction	3	0.7	Positive
1	3	Office 344	W2	Plaster	Green	Flaking	1	0.1	Negative
1	3	Office 344	W3	Plaster	Green	Flaking	1	0	Negative
1	3	Office 344	Conduit	Metal	White	None	0	0.2	Negative
1	3	Office 344	Pipe Cover	Metal	White	None	0	3.7	Positive
1	3	Office 344	Pipe Insulation	Asbestos	White	None	0	0.1	Negative
1	3	Office 344	Radiator cover	Metal	Brown	Chipping	4	0.5	Negative
1	3	Office 344	W4	Plaster	Green	None	0	0.1	Negative
1	3	Office 344	Ceiling	Plaster	White	Flaking	30	0.3	Negative
1	3	Office 344	Ceiling	2'x4' Ceiling Tile	Not Painted	N/A	N/A	N/A	N/A
1	3	Office 344	Floor	Wood	Not Painted	N/A	N/A	N/A	N/A
1	3	Closet in Office 344	W1	Plaster	White	Cracking	30	0	Negative
1	3	Closet in Office 344	Doorframe	Wood	Brown	Friction	1	0.4	Negative
1	3	Closet in Office 344	W2	Plaster	White	Cracking	26	0	Negative
1	3	Closet in Office 344	W3	Plaster	White	Cracking	30	0	Negative
1	3	Closet in Office 344	W4	Plaster	White	Cracking	40	0	Negative
1	3	Closet in Office 344	Ceiling	Plaster	White	Cracking	10	No Access	No Access
1	3	Closet in Office 344	Floor	Wood	Not Painted	N/A	N/A	N/A	N/A
1	3	Classroom 346	W1	Plaster	White/Pink	Flaking	40	0.3	Negative
1	3	Classroom 346	Doorframe	Metal	Brown	Friction	4	0.7	Positive
1	3	Classroom 346	W2	Plaster	Yellow	None	0	0.1	Negative
1	3	Classroom 346	Conduit	Plastic	Yellow	None	0	0.3	Negative
1	3	Classroom 346	W3	Plaster	White/Pink	Flaking	60	0.7	Positive
1	3	Classroom 346	Radiator cover	Metal	Brown	Chipping	4	0.8	Positive

		Dates: 6/5 - 7/6/2023	Lead-Safe Certification Assessment Report							
		Inspector Name and Certificate Number: Tim Smith 057662	John Bartram High School							
		Inspection Company: BATA	2401 S 67th St, Philadelphia PA 19142							
E l e m e n t	F l o o r	On-Site Room Name	Component	Substrate Material [1]	Paint Color	Description of Paint Damage	Damage Quantity (sf) [2]	XRF Reading (mg/cm2)	XRF (positive/ negative) [3]	
1	3	Classroom 346	W4	Plaster	White/Pink	Flaking	30	0.1	Negative	
1	3	Classroom 346	Ceiling	Plaster	White	None	0	0.2	Negative	
1	3	Classroom 346	Ceiling	2'x4' Ceiling Tile	Not Painted	N/A	N/A	N/A	N/A	
1	3	Classroom 346	Floor	Floor Tile	Not Painted	N/A	N/A	N/A	N/A	
1	3	Storage Closet next to Women's Restroom	W1	Plaster	White	Chipping	12	0	Negative	
1	3	Storage Closet next to Women's Restroom	Doorframe	Metal	Brown	Friction	8	1.1	Positive	
1	3	Storage Closet next to Women's Restroom	W2	Plaster	White	Cracking	20	0	Negative	
1	3	Storage Closet next to Women's Restroom	Covebase	Concrete	Grey	None	0	0.1	Negative	
1	3	Storage Closet next to Women's Restroom	W3	Plaster	White	Flaking	8	0.1	Negative	
1	3	Storage Closet next to Women's Restroom	W4	Plaster	White	Chipping	30	0	Negative	
1	3	Storage Closet next to Women's Restroom	Ceiling	Plaster	White	Cracking	6	0.1	Negative	
1	3	Storage Closet next to Women's Restroom	Floor	Concrete	Not Painted	N/A	N/A	N/A	N/A	
1	3	Women's Staff Restroom	W1	Plaster	White/Red	Cracking	16	0.1	Negative	
1	3	Women's Staff Restroom	Doorframe	Metal	Brown	Friction	3	0.6	Negative	
1	3	Women's Staff Restroom	W2	Plaster	White/Red	Cracking	20	0	Negative	
1	3	Women's Staff Restroom	W3	Plaster	White/Red	Cracking	40	0	Negative	
1	3	Women's Staff Restroom	Radiator cover	Metal	Brown	Chipping	4	0.4	Negative	
1	3	Women's Staff Restroom	W4	Plaster	White/Red	Cracking	20	0	Negative	
1	3	Women's Staff Restroom	Ceiling	Plaster	White	Cracking	60	0	Negative	
1	3	Women's Staff Restroom	Floor	Terrazzo	Not Painted	N/A	N/A	N/A	N/A	
1	3	Custodial Closet outside of Women's Staff Restroom	W1	Plaster	White/Grey	None	0	0.1	Negative	
1	3	Custodial Closet outside of Women's Staff Restroom	Doorframe	Metal	Brown	Friction	10	0.9	Positive	
1	3	Custodial Closet outside of Women's Staff Restroom	W2	Plaster	White/Grey	Flaking	20	0	Negative	
1	3	Custodial Closet outside of Women's Staff Restroom	Conduit	Metal	Grey	Flaking	3	0.1	Negative	
1	3	Custodial Closet outside of Women's Staff Restroom	W3	Plaster	White/Grey	Flaking	12	0.3	Negative	
1	3	Custodial Closet outside of Women's Staff Restroom	Shelf	Wood	Grey	Chipping	2	0.1	Negative	

		Dates: 6/5 - 7/6/2023	Lead-Safe Certification Assessment Report						
		Inspector Name and Certificate Number: Tim Smith 057662	John Bartram High School						
		Inspection Company: BATA	2401 S 67th St, Philadelphia PA 19142						
E l e m e n t	F l o o r	On-Site Room Name	Component	Substrate Material [1]	Paint Color	Description of Paint Damage	Damage Quantity (sf) [2]	XRF Reading (mg/cm2)	XRF (positive/ negative) [3]
1	3	Custodial Closet outside of Women's Staff Restroom	Sink	Ceramic	Grey	Flaking	1	14.1	Positive
1	3	Custodial Closet outside of Women's Staff Restroom	W4	Plaster	White/Grey	Cracking	30	0.6	Negative
1	3	Custodial Closet outside of Women's Staff Restroom	Covebase	Concrete	Grey	Chipping	12	0.4	Negative
1	3	Custodial Closet outside of Women's Staff Restroom	Ceiling	Plaster	White	Cracking	4	0.1	Negative
1	3	Custodial Closet outside of Women's Staff Restroom	Floor	Concrete	Grey	Friction	12	0.1	Negative
1	3	Janitors Closet outside of Women's Staff Restroom Pipe Chase	W1	Concrete	Not Painted	N/A	N/A	N/A	N/A
1	3	Janitors Closet outside of Women's Staff Restroom Pipe Chase	Door	Wood	Grey	Chipping	3	0	Negative
1	3	Janitors Closet outside of Women's Staff Restroom Pipe Chase	Doorframe	Metal	Grey	Chipping	5	1.3	Positive
1	3	Janitors Closet outside of Women's Staff Restroom Pipe Chase	W2	Concrete	Not Painted	N/A	N/A	N/A	N/A
1	3	Janitors Closet outside of Women's Staff Restroom Pipe Chase	W3	Concrete	Not Painted	N/A	N/A	N/A	N/A
1	3	Janitors Closet outside of Women's Staff Restroom Pipe Chase	W4	Concrete	Not Painted	N/A	N/A	N/A	N/A
1	3	Janitors Closet outside of Women's Staff Restroom Pipe Chase	Ceiling	Concrete	Not Painted	N/A	N/A	N/A	N/A
1	3	Janitors Closet outside of Women's Staff Restroom Pipe Chase	Floor	Concrete	Not Painted	N/A	N/A	N/A	N/A
1	3	Women's Staff Restroom Pipe Shaft	W1	Terracotta	Not Painted	N/A	N/A	N/A	N/A
1	3	Women's Staff Restroom Pipe Shaft	Doorframe	Metal	Brown	None	0	0.9	Positive
1	3	Women's Staff Restroom Pipe Shaft	W2	Terracotta	Not Painted	N/A	N/A	N/A	N/A
1	3	Women's Staff Restroom Pipe Shaft	W3	Terracotta	Not Painted	N/A	N/A	N/A	N/A
1	3	Women's Staff Restroom Pipe Shaft	W4	Terracotta	Not Painted	N/A	N/A	N/A	N/A
1	3	Women's Staff Restroom Pipe Shaft	Ceiling	Concrete	Not Painted	N/A	N/A	N/A	N/A
1	3	Women's Staff Restroom Pipe Shaft	Floor	Concrete	Not Painted	N/A	N/A	N/A	N/A

		Dates: 6/5 - 7/6/2023	Lead-Safe Certification Assessment Report						
		Inspector Name and Certificate Number: Tim Smith 057662	John Bartram High School						
		Inspection Company: BATA	2401 S 67th St, Philadelphia PA 19142						
Element	Floor	On-Site Room Name	Component	Substrate Material [1]	Paint Color	Description of Paint Damage	Damage Quantity (sf) [2]	XRF Reading (mg/cm2)	XRF (positive/negative) [3]
1	3	Lounge outside of Women's Staff Restroom	W1	Plaster	White/Red	None	0	0	Negative
1	3	Lounge outside of Women's Staff Restroom	Doorframe	Metal	Brown	Friction	1	0.7	Positive
1	3	Lounge outside of Women's Staff Restroom	Conduit	Plastic	White	None	0	0.3	Negative
1	3	Lounge outside of Women's Staff Restroom	W2	Plaster	White/Red	None	0	0.1	Negative
1	3	Lounge outside of Women's Staff Restroom	Covebase	Wood	Brown	None	0	0.3	Negative
1	3	Lounge outside of Women's Staff Restroom	W3	Plaster	White/Red	None	0	0	Negative
1	3	Lounge outside of Women's Staff Restroom	Radiator cover	Metal	Brown	Chipping	2	0.2	Negative
1	3	Lounge outside of Women's Staff Restroom	Pipe Cover	Metal	White/Red	None	0	4.3	Positive
1	3	Lounge outside of Women's Staff Restroom	Pipe Insulation	Asbestos	White	None	0	0.1	Negative
1	3	Lounge outside of Women's Staff Restroom	W4	Plaster	White/Red	Cracking	6	0	Negative
1	3	Lounge outside of Women's Staff Restroom	Ceiling	Plaster	White	Cracking	10	0.1	Negative
1	3	Lounge outside of Women's Staff Restroom	Ceiling	2'x4' Ceiling Tile	Not Painted	N/A	N/A	N/A	N/A
1	3	Lounge outside of Women's Staff Restroom	Floor	Floor Tile	Not Painted	N/A	N/A	N/A	N/A
1	3	Storage 3E	W1	Plaster	Green	Cracking	16	0	Negative
1	3	Storage 3E	Doorframe	Metal	Brown	Friction	8	0.5	Negative
1	3	Storage 3E	W2	Plaster	Green	None	0	0.1	Negative
1	3	Storage 3E	W3	Plaster	Green	None	0	0.6	Negative
1	3	Storage 3E	Shelf	Wood	Brown	None	0	0.1	Negative
1	3	Storage 3E	Covebase	Concrete	Grey	None	0	0.2	Negative
1	3	Storage 3E	W4	Plaster	Green	None	0	0	Negative
1	3	Storage 3E	Pipe	Metal	Multi-Color	None	0	16.1	Positive
1	3	Storage 3E	Ceiling	Plaster	Green	Cracking	12	0	Negative
1	3	Storage 3E	Floor	Concrete	Not Painted	N/A	N/A	N/A	N/A
1	3	Storage Room labeled 3-L across from Office 329	W1	No Access	No Access	No Access	No Access	No Access	No Access
1	3	Storage Room labeled 3-L across from Office 329	W2	No Access	No Access	No Access	No Access	No Access	No Access
1	3	Storage Room labeled 3-L across from Office 329	W3	No Access	No Access	No Access	No Access	No Access	No Access

		Dates: 6/5 - 7/6/2023	Lead-Safe Certification Assessment Report						
		Inspector Name and Certificate Number: Tim Smith 057662	John Bartram High School						
		Inspection Company: BATA	2401 S 67th St, Philadelphia PA 19142						
Element	Floor	On-Site Room Name	Component	Substrate Material [1]	Paint Color	Description of Paint Damage	Damage Quantity (sf) [2]	XRF Reading (mg/cm2)	XRF (positive/negative) [3]
1	3	Storage Room labeled 3-L across from Office 329	W4	No Access	No Access	No Access	No Access	No Access	No Access
1	3	Storage Room labeled 3-L across from Office 329	Ceiling	No Access	No Access	No Access	No Access	No Access	No Access
1	3	Storage Room labeled 3-L across from Office 329	Floor	No Access	No Access	No Access	No Access	No Access	No Access
1	3	Lounge outside of Mens Staff Restroom	W1	Plaster	White/Red	None	0	0	Negative
1	3	Lounge outside of Mens Staff Restroom	Doorframe	Metal	Brown	Friction	3	0.9	Positive
1	3	Lounge outside of Mens Staff Restroom	Conduit	Plastic	White	None	0	0.3	Negative
1	3	Lounge outside of Mens Staff Restroom	W2	Plaster	White/Red	None	0	0	Negative
1	3	Lounge outside of Mens Staff Restroom	Covebase	Wood	Brown	None	0	0.1	Negative
1	3	Lounge outside of Mens Staff Restroom	W3	Plaster	White/Red	None	0	0	Negative
1	3	Lounge outside of Mens Staff Restroom	Radiator cover	Metal	Brown	Chipping	3	0.8	Positive
1	3	Lounge outside of Mens Staff Restroom	W4	Plaster	White/Red	None	0	0	Negative
1	3	Lounge outside of Mens Staff Restroom	Ceiling	Plaster	White	Cracking	20	0	Negative
1	3	Lounge outside of Mens Staff Restroom	Ceiling	2'x4' Ceiling Tile	Not Painted	N/A	N/A	N/A	N/A
1	3	Lounge outside of Mens Staff Restroom	Floor	Floor Tile	Not Painted	N/A	N/A	N/A	N/A
1	3	Mens Staff Restroom	W1	Plaster	White/Red	None	0	0	Negative
1	3	Mens Staff Restroom	Doorframe	Metal	Brown	Friction	4	0.7	Positive
1	3	Mens Staff Restroom	W2	Plaster	White/Red	None	0	0.4	Negative
1	3	Mens Staff Restroom	Radiator cover	Metal	Brown	Chipping	4	0.1	Negative
1	3	Mens Staff Restroom	W3	Plaster	White/Red	Cracking	30	0	Negative
1	3	Mens Staff Restroom	W4	Plaster	White/Red	Cracking	30	0	Negative
1	3	Mens Staff Restroom	Ceiling	Plaster	White	Cracking	60	0.1	Negative
1	3	Mens Staff Restroom	Floor	Terrazzo	Not Painted	N/A	N/A	N/A	N/A
1	3	Science Lab Storage Room next to Mens Staff Restroom	W1	Plaster	White	Cracking	24	0	Negative
1	3	Science Lab Storage Room next to Mens Staff Restroom	Doorframe	Metal	Brown	Friction	4	0.6	Negative

		Dates: 6/5 - 7/6/2023	Lead-Safe Certification Assessment Report						
		Inspector Name and Certificate Number: Tim Smith 057662	John Bartram High School						
		Inspection Company: BATA	2401 S 67th St, Philadelphia PA 19142						
E l e m e n t	F l o o r	On-Site Room Name	Component	Substrate Material [1]	Paint Color	Description of Paint Damage	Damage Quantity (sf) [2]	XRF Reading (mg/cm2)	XRF (positive/ negative) [3]
1	3	Science Lab Storage Room next to Mens Staff Restroom	W2	Plaster	White	Cracking	100	0	Negative
1	3	Science Lab Storage Room next to Mens Staff Restroom	W3	Plaster	White	Cracking	100	0	Negative
1	3	Science Lab Storage Room next to Mens Staff Restroom	Covebase	Concrete	Grey	None	0	0.2	Negative
1	3	Science Lab Storage Room next to Mens Staff Restroom	W4	Plaster	White	Cracking	100	0	Negative
1	3	Science Lab Storage Room next to Mens Staff Restroom	Ceiling	Plaster	Green	Cracking	30	0.2	Negative
1	3	Science Lab Storage Room next to Mens Staff Restroom	Floor	Concrete	Not Painted	N/A	N/A	N/A	N/A
1	3	Storage Closet labeled 3-J across from the Boys Restroom	W1	Plaster	White	Cracking	60	0.1	Negative
1	3	Storage Closet labeled 3-J across from the Boys Restroom	Doorframe	Metal	Brown	Friction	6	0.8	Positive
1	3	Storage Closet labeled 3-J across from the Boys Restroom	W2	Plaster	White	Cracking	4	0.2	Negative
1	3	Storage Closet labeled 3-J across from the Boys Restroom	Covebase	Concrete	Grey	None	0	0	Negative
1	3	Storage Closet labeled 3-J across from the Boys Restroom	W3	Plaster	White	Cracking	60	0.1	Negative
1	3	Storage Closet labeled 3-J across from the Boys Restroom	W4	Plaster	White	Cracking	40	0	Negative
1	3	Storage Closet labeled 3-J across from the Boys Restroom	Ceiling	Plaster	White	Cracking	30	0.3	Negative
1	3	Storage Closet labeled 3-J across from the Boys Restroom	Floor	Concrete	Not Painted	N/A	N/A	N/A	N/A
1	3	Custodial Closet next to Boys Restroom	W1	Plaster	White/Grey	Cracking	6	0.1	Negative
1	3	Custodial Closet next to Boys Restroom	Doorframe	Metal	Brown	Friction	5	0.8	Positive

		Dates: 6/5 - 7/6/2023	Lead-Safe Certification Assessment Report							
		Inspector Name and Certificate Number: Tim Smith 057662	John Bartram High School							
		Inspection Company: BATA	2401 S 67th St, Philadelphia PA 19142							
E l e m e n t	F l o o r	On-Site Room Name	Component	Substrate Material [1]	Paint Color	Description of Paint Damage	Damage Quantity (sf) [2]	XRF Reading (mg/cm2)	XRF (positive/ negative) [3]	
1	3	Custodial Closet next to Boys Restroom	Door	Wood	Brown	Chipping	3	0.1	Negative	
1	3	Custodial Closet next to Boys Restroom	W2	Plaster	White/Grey	Cracking	34	0	Negative	
1	3	Custodial Closet next to Boys Restroom	Conduit	Metal	White/Grey	Chipping	3	2.9	Positive	
1	3	Custodial Closet next to Boys Restroom	W3	Plaster	White/Grey	Cracking	30	0	Negative	
1	3	Custodial Closet next to Boys Restroom	Shelf	Wood	Grey	Chipping	6	0.1	Negative	
1	3	Custodial Closet next to Boys Restroom	Sink	Ceramic	White	Flaking	3	8.7	Positive	
1	3	Custodial Closet next to Boys Restroom	W4	Plaster	White/Grey	Cracking	80	0.1	Negative	
1	3	Custodial Closet next to Boys Restroom	Covebase	Concrete	Brown	Chipping	12	0.1	Negative	
1	3	Custodial Closet next to Boys Restroom	Ceiling	Plaster	White	Flaking	3	0.1	Negative	
1	3	Custodial Closet next to Boys Restroom	Floor	Concrete	Brown	Friction	12	0.1	Negative	
1	3	Pipe Chase Custodial Closet next to Boys Restroom	W1	Concrete	Not Painted	N/A	N/A	N/A	N/A	
1	3	Pipe Chase Custodial Closet next to Boys Restroom	Door	Wood	Grey	Cracking	4	0	Negative	
1	3	Pipe Chase Custodial Closet next to Boys Restroom	Doorframe	Metal	Grey	Chipping	4	0.7	Positive	
1	3	Pipe Chase Custodial Closet next to Boys Restroom	W2	Concrete	Not Painted	N/A	N/A	N/A	N/A	
1	3	Pipe Chase Custodial Closet next to Boys Restroom	W3	Concrete	Not Painted	N/A	N/A	N/A	N/A	
1	3	Pipe Chase Custodial Closet next to Boys Restroom	W4	Concrete	Not Painted	N/A	N/A	N/A	N/A	
1	3	Pipe Chase Custodial Closet next to Boys Restroom	Ceiling	Concrete	Not Painted	N/A	N/A	N/A	N/A	
1	3	Pipe Chase Custodial Closet next to Boys Restroom	Floor	Concrete	Not Painted	N/A	N/A	N/A	N/A	
1	3	Auditorium Attic	W1	Terracotta	Not Painted	N/A	N/A	N/A	N/A	
1	3	Auditorium Attic	Door	Metal	Brown	None	0	0.3	Negative	
1	3	Auditorium Attic	Doorframe	Metal	Brown	None	0	0.6	Negative	
1	3	Auditorium Attic	W2	Brick	Not Painted	N/A	N/A	N/A	N/A	
1	3	Auditorium Attic	W3	Terracotta	Not Painted	N/A	N/A	N/A	N/A	
1	3	Auditorium Attic	W4	Terracotta	Not Painted	N/A	N/A	N/A	N/A	
1	3	Auditorium Attic	Ceiling	Concrete	Not Painted	N/A	N/A	N/A	N/A	
1	3	Auditorium Attic	Floor	Plaster	Not Painted	N/A	N/A	N/A	N/A	

		Dates: 6/5 - 7/6/2023	Lead-Safe Certification Assessment Report						
		Inspector Name and Certificate Number: Tim Smith 057662	John Bartram High School						
		Inspection Company: BATA	2401 S 67th St, Philadelphia PA 19142						
E l e m e n t	F l o o r	On-Site Room Name	Component	Substrate Material [1]	Paint Color	Description of Paint Damage	Damage Quantity (sf) [2]	XRF Reading (mg/cm2)	XRF (positive/ negative) [3]
1	3	Hallway 313-346	W1	Plaster	White	None	0	0.1	Negative
1	3	Hallway 313-346	Locker	Metal	Green	Chipping	260	0.3	Negative
1	3	Hallway 313-346	Covebase	Concrete	Brown	None	0	0.2	Negative
1	3	Hallway 313-346	Pipe Cover	Metal	Tan	Chipping	15	4.4	Positive
1	3	Hallway 313-346	Pipe Insulation	Asbestos	White	None	0	0.2	Negative
1	3	Hallway 313-346	Radiator cover	Metal	Tan	Chipping	4	0.1	Negative
1	3	Hallway 313-346	W2	Plaster	White	None	0	0.1	Negative
1	3	Hallway 313-346	W3	Plaster	White	Flaking	4	0.2	Negative
1	3	Hallway 313-346	W4	Plaster	White	None	0	0.2	Negative
1	3	Hallway 313-346	Ceiling	1'x1' Ceiling Tile	White	None	0	0.1	Negative
1	3	Hallway 313-346	Floor	Concrete	Black	Chipping	30	0.1	Negative
1	3	Hallway 309-301	W1	Plaster	White	None	0	0.5	Negative
1	3	Hallway 309-301	W2	Drywall	White	None	0	0.1	Negative
1	3	Hallway 309-301	W2	Plaster	White	None	0	0.4	Negative
1	3	Hallway 309-301	Locker	Metal	Red	Chipping	60	0.1	Negative
1	3	Hallway 309-301	Windowframe	Wood	White	None	0	0	Negative
1	3	Hallway 309-301	Chair Rail	Wood	Brown	None	0	0.1	Negative
1	3	Hallway 309-301	W3	Plaster	White	None	0	0.1	Negative
1	3	Hallway 309-301	W4	Drywall	White	None	0	0.1	Negative
1	3	Hallway 309-301	Ceiling	Plaster	White	None	0	0.3	Negative
1	3	Hallway 309-301	Floor	Concrete	Black	None	0	0	Negative
1	3	B-Wing Hallway 327-316	W1	Plaster	White	None	0	0	Negative
1	3	B-Wing Hallway 327-316	W2	Plaster	White	None	0	0.1	Negative
1	3	B-Wing Hallway 327-316	Locker	Metal	Green	Chipping	50	0.1	Negative
1	3	B-Wing Hallway 327-316	Covebase	Concrete	Brown	None	0	0.1	Negative
1	3	B-Wing Hallway 327-316	Pipe Cover	Metal	Brown	Chipping	6	3.8	Positive

		Dates: 6/5 - 7/6/2023	Lead-Safe Certification Assessment Report						
		Inspector Name and Certificate Number: Tim Smith 057662	John Bartram High School						
		Inspection Company: BATA	2401 S 67th St, Philadelphia PA 19142						
E l e m e n t	F l o o r	On-Site Room Name	Component	Substrate Material [1]	Paint Color	Description of Paint Damage	Damage Quantity (sf) [2]	XRF Reading (mg/cm2)	XRF (positive/ negative) [3]
1	3	B-Wing Hallway 327-316	Pipe Insulation	Asbestos	White	None	0	0.1	Negative
1	3	B-Wing Hallway 327-316	Radiator cover	Metal	Tan	Chipping	4	0	Negative
1	3	B-Wing Hallway 327-316	Pipe	Metal	White	Chipping	10	0	Negative
1	3	B-Wing Hallway 327-316	W3	Plaster	White	None	0	0.5	Negative
1	3	B-Wing Hallway 327-316	W4	Plaster	White	Cracking	6	0.2	Negative
1	3	B-Wing Hallway 327-316	Ceiling	Plaster	White	None	0	0	Negative
1	3	B-Wing Hallway 327-316	Floor	Concrete	Black	None	0	0.1	Negative
1	3	Hallway 331-340	W1	Plaster	White	None	0	0.1	Negative
1	3	Hallway 331-340	W2	Plaster	White	None	0	0	Negative
1	3	Hallway 331-340	Locker	Metal	Green	Chipping	80	0.2	Negative
1	3	Hallway 331-340	Covebase	Concrete	Brown	Chipping	20	0.3	Negative
1	3	Hallway 331-340	Pipe Cover	Metal	Tan	Chipping	10	3.8	Positive
1	3	Hallway 331-340	Pipe Insulation	Asbestos	White	None	0	0.2	Negative
1	3	Hallway 331-340	Radiator cover	Metal	Tan	Chipping	12	0	Negative
1	3	Hallway 331-340	W3	Drywall	White	None	0	0	Negative
1	3	Hallway 331-340	W4	Plaster	White	None	0	0.1	Negative
1	3	Hallway 331-340	Conduit	Metal	White	Chipping	5	0.4	Negative
1	3	Hallway 331-340	Ceiling	1'x1' Ceiling Tile	White	None	0	0.1	Negative
1	3	Hallway 331-340	Floor	Concrete	Black	None	0	0.1	Negative
1	3	Hallway between Rooms 316 and 319	W1	Terracotta	Not Painted	N/A	N/A	N/A	N/A
1	3	Hallway between Rooms 316 and 319	Door	Metal	Red	Friction	5	0.1	Negative
1	3	Hallway between Rooms 316 and 319	Doorframe	Metal	Red	Chipping	6	0.3	Negative
1	3	Hallway between Rooms 316 and 319	W2	Drywall	White	Cracking	8	0.2	Negative
1	3	Hallway between Rooms 316 and 319	Covebase	Wood	Brown	Cracking	12	0.2	Negative
1	3	Hallway between Rooms 316 and 319	W3	Terracotta	Not Painted	N/A	N/A	N/A	N/A
1	3	Hallway between Rooms 316 and 319	W4	Drywall	White	Chipping	40	0.2	Negative

		Dates: 6/5 - 7/6/2023	Lead-Safe Certification Assessment Report							
		Inspector Name and Certificate Number: Tim Smith 057662	John Bartram High School							
		Inspection Company: BATA	2401 S 67th St, Philadelphia PA 19142							
E l e m e n t	F l o o r	On-Site Room Name	Component	Substrate Material [1]	Paint Color	Description of Paint Damage	Damage Quantity (sf) [2]	XRF Reading (mg/cm2)	XRF (positive/ negative) [3]	
1	3	Hallway between Rooms 316 and 319	Ceiling	Concrete	Not Painted	N/A	N/A	N/A	N/A	
1	3	Hallway between Rooms 316 and 319	Floor	Wood	Not Painted	N/A	N/A	N/A	N/A	
1	3	Lobby adjacent to Room 319	W1	Plaster	White	Flaking	16	0.1	Negative	
1	3	Lobby adjacent to Room 319	Door	Metal	Red	Chipping	2	0.1	Negative	
1	3	Lobby adjacent to Room 319	Doorframe	Metal	Red	Chipping	2	0.3	Negative	
1	3	Lobby adjacent to Room 319	W2	Plaster	White	Flaking	8	0.1	Negative	
1	3	Lobby adjacent to Room 319	W3	Plaster	White	Flaking	24	0	Negative	
1	3	Lobby adjacent to Room 319	W4	Plaster	White	Flaking	12	0.1	Negative	
1	3	Lobby adjacent to Room 319	Ceiling	Plaster	White	Flaking	60	0.4	Negative	
1	3	Lobby adjacent to Room 319	Floor	Concrete	Not Painted	N/A	N/A	N/A	N/A	
1	3	Stairwell adjacent to Room 301	W1	Plaster	White	None	0	0.5	Negative	
1	3	Stairwell adjacent to Room 301	Door	Metal	Red	Chipping	2	0	Negative	
1	3	Stairwell adjacent to Room 301	Doorframe	Metal	Red	Chipping	2	0.1	Negative	
1	3	Stairwell adjacent to Room 301	W2	Plaster	White	Flaking	100	0.5	Negative	
1	3	Stairwell adjacent to Room 301	Covebase	Concrete	Brown	Chipping	3	0.1	Negative	
1	3	Stairwell adjacent to Room 301	Post	Metal	Brown	None	0	10.5	Positive	
1	3	Stairwell adjacent to Room 301	Riser	Concrete	Brown	None	0	0.6	Negative	
1	3	Stairwell adjacent to Room 301	Baluster	Metal	Brown	Chipping	10	8.8	Positive	
1	3	Stairwell adjacent to Room 301	Stringer	Concrete	Brown	None	0	4.4	Positive	
1	3	Stairwell adjacent to Room 301	W3	Plaster	White	Cracking	6	0.1	Negative	
1	3	Stairwell adjacent to Room 301	Radiator cover	Metal	Brown	Chipping	2	0	Negative	
1	3	Stairwell adjacent to Room 301	Pipe Cover	Metal	Tan	Flaking	1	3.4	Positive	
1	3	Stairwell adjacent to Room 301	Pipe Insulation	Asbestos	White	None	0	0.2	Negative	
1	3	Stairwell adjacent to Room 301	Windowframe	Metal	White	Flaking	12	11.1	Positive	
1	3	Stairwell adjacent to Room 301	W4	Plaster	White	None	0	0.4	Negative	
1	3	Stairwell adjacent to Room 301	Ceiling	Plaster	White	None	0	0.3	Negative	

		Dates: 6/5 - 7/6/2023	Lead-Safe Certification Assessment Report						
		Inspector Name and Certificate Number: Tim Smith 057662	John Bartram High School						
		Inspection Company: BATA	2401 S 67th St, Philadelphia PA 19142						
E l e m e n t	F l o o r	On-Site Room Name	Component	Substrate Material [1]	Paint Color	Description of Paint Damage	Damage Quantity (sf) [2]	XRF Reading (mg/cm ²)	XRF (positive/ negative) [3]
1	3	Stairwell adjacent to Room 301	Floor	Concrete	Not Painted	N/A	N/A	N/A	N/A
1	3	Stairwell B adjacent to Room 324	W1	Plaster	White	None	0	0.1	Negative
1	3	Stairwell B adjacent to Room 324	Door	Metal	Red	Chipping	16	0.1	Negative
1	3	Stairwell B adjacent to Room 324	Doorframe	Metal	Red	Chipping	4	0.1	Negative
1	3	Stairwell B adjacent to Room 324	W2	Plaster	White	Cracking	80	0.3	Negative
1	3	Stairwell B adjacent to Room 324	Covebase	Concrete	Brown	None	0	0.1	Negative
1	3	Stairwell B adjacent to Room 324	Post	Metal	Brown	Chipping	2	10.8	Positive
1	3	Stairwell B adjacent to Room 324	Riser	Concrete	Brown	None	0	0.5	Negative
1	3	Stairwell B adjacent to Room 324	Baluster	Metal	Brown	Chipping	20	9.1	Positive
1	3	Stairwell B adjacent to Room 324	Stringer	Concrete	Brown	None	0	0.5	Negative
1	3	Stairwell B adjacent to Room 324	W3	Plaster	White	Cracking	12	0.1	Negative
1	3	Stairwell B adjacent to Room 324	Radiator cover	Metal	Brown	None	0	0.2	Negative
1	3	Stairwell B adjacent to Room 324	Pipe Cover	Metal	Tan	Cracking	2	3	Positive
1	3	Stairwell B adjacent to Room 324	Pipe Insulation	Asbestos	White	Alligatoring	20	0.1	Negative
1	3	Stairwell B adjacent to Room 324	Windowframe	Metal	White	Cracking	4	15.2	Positive
1	3	Stairwell B adjacent to Room 324	W4	Plaster	White	Flaking	24	0	Negative
1	3	Stairwell B adjacent to Room 324	Ceiling	Plaster	White	None	0	0.5	Negative
1	3	Stairwell B adjacent to Room 324	Floor	Concrete	Not Painted	N/A	N/A	N/A	N/A
1	3	Stairwell adjacent to Room 319	W1	Plaster	White	Flaking	30	0	Negative
1	3	Stairwell adjacent to Room 319	Door	Metal	Red	None	0	0	Negative
1	3	Stairwell adjacent to Room 319	Doorframe	Metal	Red	None	0	0.2	Negative
1	3	Stairwell adjacent to Room 319	W2	Plaster	White	Flaking	14	0	Negative
1	3	Stairwell adjacent to Room 319	Covebase	Concrete	Brown	Chipping	20	0.1	Negative
1	3	Stairwell adjacent to Room 319	Post	Metal	Brown	Chipping	6	8.9	Positive
1	3	Stairwell adjacent to Room 319	Riser	Concrete	Brown	None	0	0.6	Negative
1	3	Stairwell adjacent to Room 319	Baluster	Metal	Brown	Cracking	12	12.8	Positive

		Dates: 6/5 - 7/6/2023	Lead-Safe Certification Assessment Report						
		Inspector Name and Certificate Number: Tim Smith 057662	John Bartram High School						
		Inspection Company: BATA	2401 S 67th St, Philadelphia PA 19142						
E l e m e n t	F l o o r	On-Site Room Name	Component	Substrate Material [1]	Paint Color	Description of Paint Damage	Damage Quantity (sf) [2]	XRF Reading (mg/cm ²)	XRF (positive/ negative) [3]
1	3	Stairwell adjacent to Room 319	Stringer	Concrete	Brown	Chipping	9	1.4	Positive
1	3	Stairwell adjacent to Room 319	Radiator cover	Metal	Brown	Chipping	4	0.2	Negative
1	3	Stairwell adjacent to Room 319	Pipe Cover	Metal	Tan	Flaking	2	0.5	Negative
1	3	Stairwell adjacent to Room 319	Pipe Insulation	Asbestos	White	Alligatoring	12	0.2	Negative
1	3	Stairwell adjacent to Room 319	W3	Plaster	White	Flaking	24	0.1	Negative
1	3	Stairwell adjacent to Room 319	Windowframe	Metal	White	Flaking	20	10.2	Positive
1	3	Stairwell adjacent to Room 319	W4	Plaster	White	Flaking	120	0	Negative
1	3	Stairwell adjacent to Room 319	Ceiling	Plaster	White	Flaking	80	0.3	Negative
1	3	Stairwell adjacent to Room 319	Floor	Concrete	Not Painted	N/A	N/A	N/A	N/A
1	3	Stairwell adjacent to Room 331	W1	Plaster	White	Flaking	20	0.6	Negative
1	3	Stairwell adjacent to Room 331	Door	Metal	Grey	Chipping	1	0.1	Negative
1	3	Stairwell adjacent to Room 331	Doorframe	Metal	Red	Chipping	1	0.1	Negative
1	3	Stairwell adjacent to Room 331	W2	Plaster	White	None	0	0.1	Negative
1	3	Stairwell adjacent to Room 331	Covebase	Concrete	Brown	None	0	0.1	Negative
1	3	Stairwell adjacent to Room 331	Post	Metal	Brown	None	0	13.3	Positive
1	3	Stairwell adjacent to Room 331	Riser	Concrete	Brown	None	0	0.3	Negative
1	3	Stairwell adjacent to Room 331	Baluster	Metal	Brown	None	0	6.5	Positive
1	3	Stairwell adjacent to Room 331	Stringer	Concrete	Brown	None	0	0.6	Negative
1	3	Stairwell adjacent to Room 331	Radiator cover	Metal	Brown	None	0	0.1	Negative
1	3	Stairwell adjacent to Room 331	Pipe Cover	Metal	Tan	Flaking	2	7.3	Positive
1	3	Stairwell adjacent to Room 331	Pipe Insulation	Asbestos	White	None	0	0.1	Negative
1	3	Stairwell adjacent to Room 331	W3	Plaster	White	None	0	0	Negative
1	3	Stairwell adjacent to Room 331	Windowframe	Wood	Tan	None	0	8.5	Positive
1	3	Stairwell adjacent to Room 331	W4	Plaster	White	None	0	0	Negative
1	3	Stairwell adjacent to Room 331	Ceiling	Plaster	White	Flaking	40	0.1	Negative
1	3	Stairwell adjacent to Room 331	Floor	Concrete	Not Painted	N/A	N/A	N/A	N/A

		Dates: 6/5 - 7/6/2023	Lead-Safe Certification Assessment Report						
		Inspector Name and Certificate Number: Tim Smith 057662	John Bartram High School						
		Inspection Company: BATA	2401 S 67th St, Philadelphia PA 19142						
E l e m e n t	F l o o r	On-Site Room Name	Component	Substrate Material [1]	Paint Color	Description of Paint Damage	Damage Quantity (sf) [2]	XRF Reading (mg/cm2)	XRF (positive/ negative) [3]
1	3	Stairwell A adjacent to Room 341	W1	Plaster	White	None	0	0.6	Negative
1	3	Stairwell A adjacent to Room 341	Door	Metal	Brown	Chipping	6	0.1	Negative
1	3	Stairwell A adjacent to Room 341	Doorframe	Metal	Brown	Chipping	2	0.1	Negative
1	3	Stairwell A adjacent to Room 341	W2	Plaster	White	Cracking	20	0.2	Negative
1	3	Stairwell A adjacent to Room 341	Covebase	Concrete	Brown	None	0	0.2	Negative
1	3	Stairwell A adjacent to Room 341	Post	Metal	Brown	Chipping	4	14.4	Positive
1	3	Stairwell A adjacent to Room 341	Riser	Concrete	Brown	None	0	0.5	Negative
1	3	Stairwell A adjacent to Room 341	Baluster	Metal	Brown	Chipping	2	6.9	Positive
1	3	Stairwell A adjacent to Room 341	Stringer	Concrete	Brown	Cracking	3	0.5	Negative
1	3	Stairwell A adjacent to Room 341	W3	Plaster	White	None	0	0.1	Negative
1	3	Stairwell A adjacent to Room 341	Radiator cover	Metal	Brown	None	0	0.1	Negative
1	3	Stairwell A adjacent to Room 341	Pipe Cover	Metal	Tan	None	0	3.2	Positive
1	3	Stairwell A adjacent to Room 341	Pipe Insulation	Asbestos	White	Alligatoring	6	0.1	Negative
1	3	Stairwell A adjacent to Room 341	Windowframe	Wood	Tan	None	0	14.8	Positive
1	3	Stairwell A adjacent to Room 341	W4	Plaster	White	Chipping	12	0.1	Negative
1	3	Stairwell A adjacent to Room 341	Ceiling	Plaster	White	Cracking	12	0.5	Negative
1	3	Stairwell A adjacent to Room 341	Floor	Concrete	Not Painted	N/A	N/A	N/A	N/A
1	3	Stairwell C adjacent to Classroom 310 and ROTC Office	W1	Plaster	White	None	0	0.6	Negative
1	3	Stairwell C adjacent to Classroom 310 and ROTC Office	Door	Metal	Red	None	0	0.1	Negative
1	3	Stairwell C adjacent to Classroom 310 and ROTC Office	Doorframe	Metal	Red	None	0	0	Negative
1	3	Stairwell C adjacent to Classroom 310 and ROTC Office	W2	Plaster	White	Flaking	30	0.2	Negative
1	3	Stairwell C adjacent to Classroom 310 and ROTC Office	Covebase	Concrete	Brown	None	0	0.1	Negative

		Dates: 6/5 - 7/6/2023	Lead-Safe Certification Assessment Report						
		Inspector Name and Certificate Number: Tim Smith 057662	John Bartram High School						
		Inspection Company: BATA	2401 S 67th St, Philadelphia PA 19142						
E l e m e n t	F l o o r	On-Site Room Name	Component	Substrate Material [1]	Paint Color	Description of Paint Damage	Damage Quantity (sf) [2]	XRF Reading (mg/cm2)	XRF (positive/ negative) [3]
1	3	Stairwell C adjacent to Classroom 310 and ROTC Office	Post	Metal	Brown	Chipping	1	13.2	Positive
1	3	Stairwell C adjacent to Classroom 310 and ROTC Office	Riser	Concrete	Brown	None	0	0.5	Negative
1	3	Stairwell C adjacent to Classroom 310 and ROTC Office	Baluster	Metal	Brown	Chipping	3	11	Positive
1	3	Stairwell C adjacent to Classroom 310 and ROTC Office	Stringer	Concrete	Brown	None	0	2.6	Positive
1	3	Stairwell C adjacent to Classroom 310 and ROTC Office	W3	Plaster	White	Cracking	4	0.1	Negative
1	3	Stairwell C adjacent to Classroom 310 and ROTC Office	Radiator cover	Metal	Brown	None	0	0	Negative
1	3	Stairwell C adjacent to Classroom 310 and ROTC Office	Pipe Cover	Metal	Tan	Chipping	8	0.8	Positive
1	3	Stairwell C adjacent to Classroom 310 and ROTC Office	Pipe Insulation	Asbestos	White	Alligatoring	6	0.2	Negative
1	3	Stairwell C adjacent to Classroom 310 and ROTC Office	Fence Gate	Metal	Brown	Chipping	8	6.1	Positive
1	3	Stairwell C adjacent to Classroom 310 and ROTC Office	Windowframe	Metal	Tan	Chipping	6	11.8	Positive
1	3	Stairwell C adjacent to Classroom 310 and ROTC Office	W4	Plaster	White	None	0	0	Negative
1	3	Stairwell C adjacent to Classroom 310 and ROTC Office	Ceiling	Plaster	White	None	0	0.5	Negative
1	3	Stairwell C adjacent to Classroom 310 and ROTC Office	Floor	Concrete	Not Painted	N/A	N/A	N/A	N/A
1	4	Music/Choir Room	W1	Plaster	White	None	0	0	Negative
1	4	Music/Choir Room	Door	Metal	Brown	None	0	0	Negative
1	4	Music/Choir Room	Doorframe	Metal	Brown	None	0	0.1	Negative
1	4	Music/Choir Room	W2	Plaster	White	Flaking	12	0	Negative

		Dates: 6/5 - 7/6/2023	Lead-Safe Certification Assessment Report						
		Inspector Name and Certificate Number: Tim Smith 057662	John Bartram High School						
		Inspection Company: BATA	2401 S 67th St, Philadelphia PA 19142						
E l e m e n t	F l o o r	On-Site Room Name	Component	Substrate Material [1]	Paint Color	Description of Paint Damage	Damage Quantity (sf) [2]	XRF Reading (mg/cm2)	XRF (positive/ negative) [3]
1	4	Music/Choir Room	Windowframe	Wood	Brown	None	0	5.9	Positive
1	4	Music/Choir Room	Windowsill	Wood	Brown	None	0	0.2	Negative
1	4	Music/Choir Room	Radiator cover	Metal	Brown	Chipping	4	1.1	Positive
1	4	Music/Choir Room	Pipe Cover	Metal	White	None	0	2.6	Positive
1	4	Music/Choir Room	Pipe Insulation	Asbestos	White	None	0	0.1	Negative
1	4	Music/Choir Room	Pipe	Metal	White	None	0	17.2	Positive
1	4	Music/Choir Room	Conduit	Metal	White	None	0	0.2	Negative
1	4	Music/Choir Room	W3	Plaster	White	Cracking	10	0.5	Negative
1	4	Music/Choir Room	W4	Plaster	White	Flaking	7	0.4	Negative
1	4	Music/Choir Room	Stage	Wood	Black	Friction	20	0	Negative
1	4	Music/Choir Room	Covebase	Wood	Brown	None	0	0	Negative
1	4	Music/Choir Room	Wall Trim	Wood	Brown	None	0	0	Negative
1	4	Music/Choir Room	Ceiling	Plaster	White	None	0	0.2	Negative
1	4	Music/Choir Room	Floor	Floor Tile	Not Painted	N/A	N/A	N/A	N/A
1	4	Cooling Tower	W1	Concrete	Not Painted	N/A	N/A	N/A	N/A
1	4	Cooling Tower	Door	Metal	Brown	Chipping	6	0.3	Negative
1	4	Cooling Tower	Doorframe	Metal	Brown	Friction	8	0.7	Positive
1	4	Cooling Tower	W2	Concrete	Not Painted	N/A	N/A	N/A	N/A
1	4	Cooling Tower	Railing	Metal	Grey	Chipping	8	3.1	Positive
1	4	Cooling Tower	W3	Concrete	Not Painted	N/A	N/A	N/A	N/A
1	4	Cooling Tower	W4	Concrete	Not Painted	N/A	N/A	N/A	N/A
1	4	Cooling Tower	Ceiling	Concrete	Not Painted	N/A	N/A	N/A	N/A
1	4	Cooling Tower	Floor	Concrete	Not Painted	N/A	N/A	N/A	N/A
1	4	Computer IT Closet in the Music/Choir Room	W1	Plaster	White	None	0	0	Negative
1	4	Computer IT Closet in the Music/Choir Room	Doorframe	Metal	Brown	None	0	0.6	Negative
1	4	Computer IT Closet in the Music/Choir Room	Covebase	Wood	Brown	None	0	0.1	Negative

		Dates: 6/5 - 7/6/2023	Lead-Safe Certification Assessment Report						
		Inspector Name and Certificate Number: Tim Smith 057662	John Bartram High School						
		Inspection Company: BATA	2401 S 67th St, Philadelphia PA 19142						
E l e m e n t	F l o o r	On-Site Room Name	Component	Substrate Material [1]	Paint Color	Description of Paint Damage	Damage Quantity (sf) [2]	XRF Reading (mg/cm2)	XRF (positive/ negative) [3]
1	4	Computer IT Closet in the Music/Choir Room	W2	Plaster	White	None	0	0	Negative
1	4	Computer IT Closet in the Music/Choir Room	W3	Plaster	White	None	0	0	Negative
1	4	Computer IT Closet in the Music/Choir Room	W4	Plaster	White	None	0	0	Negative
1	4	Computer IT Closet in the Music/Choir Room	Conduit	Metal	White	None	0	0.1	Negative
1	4	Computer IT Closet in the Music/Choir Room	Ceiling	Plaster	Not Painted	N/A	N/A	N/A	N/A
1	4	Computer IT Closet in the Music/Choir Room	Floor	Floor Tile	Not Painted	N/A	N/A	N/A	N/A
1	4	Storage Closet in the Music/Choir Room	W1	Plaster	White	Cracking	8	0.6	Negative
1	4	Storage Closet in the Music/Choir Room	Doorframe	Metal	Brown	None	0	0.6	Negative
1	4	Storage Closet in the Music/Choir Room	Covebase	Wood	Brown	None	0	0	Negative
1	4	Storage Closet in the Music/Choir Room	W2	Plaster	White	None	0	0.2	Negative
1	4	Storage Closet in the Music/Choir Room	W3	Plaster	White	None	0	0.1	Negative
1	4	Storage Closet in the Music/Choir Room	W4	Plaster	White	Cracking	20	0	Negative
1	4	Storage Closet in the Music/Choir Room	Radiator	Metal	Brown	None	0	0.3	Negative
1	4	Storage Closet in the Music/Choir Room	Ceiling	Plaster	Not Painted	N/A	N/A	N/A	N/A
1	4	Storage Closet in the Music/Choir Room	Floor	Floor Tile	Not Painted	N/A	N/A	N/A	N/A
1	4	Lobby 401 (C-Wing)	W1	Ceramic	White	None	0	0.1	Negative
1	4	Lobby 401 (C-Wing)	Conduit	Plastic	White	None	0	0.2	Negative
1	4	Lobby 401 (C-Wing)	W2	Ceramic	White	Flaking	17	0.5	Negative
1	4	Lobby 401 (C-Wing)	W3	Ceramic	White	None	0	0	Negative
1	4	Lobby 401 (C-Wing)	Windowframe	Metal	White	None	0	10.7	Positive
1	4	Lobby 401 (C-Wing)	Radiator cover	Metal	Tan	Chipping	24	0.1	Negative
1	4	Lobby 401 (C-Wing)	W4	Ceramic	White	None	0	0.2	Negative
1	4	Lobby 401 (C-Wing)	W4	Wood	White	Cracking	40	0	Negative
1	4	Lobby 401 (C-Wing)	Covebase	Concrete	Grey	None	0	0.1	Negative
1	4	Lobby 401 (C-Wing)	Ceiling	1'x1' Ceiling Tile	Not Painted	N/A	N/A	N/A	N/A
1	4	Lobby 401 (C-Wing)	Floor	Concrete	Not Painted	N/A	N/A	N/A	N/A

		Dates: 6/5 - 7/6/2023	Lead-Safe Certification Assessment Report						
		Inspector Name and Certificate Number: Tim Smith 057662	John Bartram High School						
		Inspection Company: BATA	2401 S 67th St, Philadelphia PA 19142						
E l e m e n t	F l o o r	On-Site Room Name	Component	Substrate Material [1]	Paint Color	Description of Paint Damage	Damage Quantity (sf) [2]	XRF Reading (mg/cm2)	XRF (positive/ negative) [3]
1	4	Lobby 401 Office	W1	Plaster	White	None	0	0.4	Negative
1	4	Lobby 401 Office	Doorframe	Metal	Brown	None	0	0.4	Negative
1	4	Lobby 401 Office	W2	Plaster	White	None	0	0.5	Negative
1	4	Lobby 401 Office	Conduit	Metal	White	None	0	0.4	Negative
1	4	Lobby 401 Office	W3	Plaster	White	None	0	0.1	Negative
1	4	Lobby 401 Office	W4	Plaster	White	None	0	0.5	Negative
1	4	Lobby 401 Office	Ceiling	1'x1' Ceiling Tile	Not Painted	N/A	N/A	N/A	N/A
1	4	Lobby 401 Office	Floor	Concrete	Not Painted	N/A	N/A	N/A	N/A
1	4	Office 401A	W1	Wood	White	Cracking	40	0.1	Negative
1	4	Office 401A	Doorframe	Wood	Pink	Chipping	12	0.1	Negative
1	4	Office 401A	W2	Ceramic	White	None	0	0.2	Negative
1	4	Office 401A	Windowframe	Metal	White	Flaking	4	10.4	Positive
1	4	Office 401A	Radiator cover	Metal	Tan	Flaking	40	0.5	Negative
1	4	Office 401A	W3	Ceramic	White	None	0	0.1	Negative
1	4	Office 401A	Conduit	Metal	Grey	None	0	0.1	Negative
1	4	Office 401A	W4	Ceramic	White	None	0	0.1	Negative
1	4	Office 401A	Covebase	Concrete	Grey	Flaking	10	0.1	Negative
1	4	Office 401A	Ceiling	1'x1' Ceiling Tile	Not Painted	N/A	N/A	N/A	N/A
1	4	Office 401A	Floor	Concrete	Not Painted	N/A	N/A	N/A	N/A
1	4	Boy's Restroom	W1	Ceramic	White	Flaking	10	0	Negative
1	4	Boy's Restroom	Door	Metal	Brown	Friction	4	0.1	Negative
1	4	Boy's Restroom	Doorframe	Metal	Brown	Friction	2	0.6	Negative
1	4	Boy's Restroom	W2	Ceramic	White	Flaking	10	0	Negative
1	4	Boy's Restroom	W3	Ceramic	White	Flaking	5	0	Negative
1	4	Boy's Restroom	Windowframe	Metal	White	Flaking	10	12.6	Positive
1	4	Boy's Restroom	Radiator cover	Metal	Brown	Chipping	12	0	Negative

		Dates: 6/5 - 7/6/2023	Lead-Safe Certification Assessment Report							
		Inspector Name and Certificate Number: Tim Smith 057662	John Bartram High School							
		Inspection Company: BATA	2401 S 67th St, Philadelphia PA 19142							
E l e m e n t	F l o o r	On-Site Room Name	Component	Substrate Material [1]	Paint Color	Description of Paint Damage	Damage Quantity (sf) [2]	XRF Reading (mg/cm2)	XRF (positive/ negative) [3]	
1	4	Boy's Restroom	W4	Ceramic	White	Flaking	4	0.2	Negative	
1	4	Boy's Restroom	Covebase	Concrete	Grey	Friction	20	0.1	Negative	
1	4	Boy's Restroom	Ceiling	Plaster	White	Flaking	70	0	Negative	
1	4	Boy's Restroom	Floor	Concrete	Not Painted	N/A	N/A	N/A	N/A	
1	4	Girl's Restroom	W1	Ceramic	White	None	0	0.1	Negative	
1	4	Girl's Restroom	Door	Metal	Brown	None	0	0.2	Negative	
1	4	Girl's Restroom	Doorframe	Metal	Brown	Friction	1	0.8	Positive	
1	4	Girl's Restroom	W2	Ceramic	White	None	0	0.1	Negative	
1	4	Girl's Restroom	W3	Ceramic	White	None	0	0.2	Negative	
1	4	Girl's Restroom	Windowframe	Metal	White	None	0	10.3	Positive	
1	4	Girl's Restroom	Radiator cover	Metal	Brown	Chipping	8	0.2	Negative	
1	4	Girl's Restroom	W4	Ceramic	White	Flaking	1	0	Negative	
1	4	Girl's Restroom	Coat Rack	Wood	White	None	0	0.4	Negative	
1	4	Girl's Restroom	Covebase	Concrete	Grey	None	0	0.1	Negative	
1	4	Girl's Restroom	Pipe	Metal	White	None	0	11.2	Positive	
1	4	Girl's Restroom	Ceiling	Plaster	White	Flaking	2	0.5	Negative	
1	4	Girl's Restroom	Floor	Concrete	Not Painted	N/A	N/A	N/A	N/A	
1	4	Pipe Chase in Girl's Restroom	W1	Concrete	Not Painted	N/A	N/A	N/A	N/A	
1	4	Pipe Chase in Girl's Restroom	Door	Wood	Brown	None	0	0.1	Negative	
1	4	Pipe Chase in Girl's Restroom	Doorframe	Metal	Brown	None	0	0.9	Positive	
1	4	Pipe Chase in Girl's Restroom	W2	Concrete	Not Painted	N/A	N/A	N/A	N/A	
1	4	Pipe Chase in Girl's Restroom	W3	Concrete	Not Painted	N/A	N/A	N/A	N/A	
1	4	Pipe Chase in Girl's Restroom	W4	Concrete	Not Painted	N/A	N/A	N/A	N/A	
1	4	Pipe Chase in Girl's Restroom	Ceiling	Concrete	Not Painted	N/A	N/A	N/A	N/A	
1	4	Pipe Chase in Girl's Restroom	Floor	Concrete	Not Painted	N/A	N/A	N/A	N/A	
1	4	Rooftop Gym	W1	Brick	Not Painted	N/A	N/A	N/A	N/A	

		Dates: 6/5 - 7/6/2023	Lead-Safe Certification Assessment Report							
		Inspector Name and Certificate Number: Tim Smith 057662	John Bartram High School							
		Inspection Company: BATA	2401 S 67th St, Philadelphia PA 19142							
E l e m e n t	F l o o r	On-Site Room Name	Component	Substrate Material [1]	Paint Color	Description of Paint Damage	Damage Quantity (sf) [2]	XRF Reading (mg/cm ²)	XRF (positive/ negative) [3]	
1	4	Rooftop Gym	W2	Metal	White	None	0	3.1	Positive	
1	4	Rooftop Gym	W3	Brick	Not Painted	N/A	N/A	N/A	N/A	
1	4	Rooftop Gym	W4	Metal	White	None	0	3.1	Positive	
1	4	Rooftop Gym	Ceiling	Metal	White	None	0	3.1	Positive	
1	4	Rooftop Gym	Floor	Roofing	Not Painted	N/A	N/A	N/A	N/A	
1	4	Air Plenum	W1	Ceramic	Not Painted	N/A	N/A	N/A	N/A	
1	4	Air Plenum	Door	Metal	Brown	None	0	3.1	Positive	
1	4	Air Plenum	Doorframe	Metal	Brown	None	0	1	Positive	
1	4	Air Plenum	W2	Concrete	Not Painted	N/A	N/A	N/A	N/A	
1	4	Air Plenum	W3	Concrete	Not Painted	N/A	N/A	N/A	N/A	
1	4	Air Plenum	W4	Concrete	Not Painted	N/A	N/A	N/A	N/A	
1	4	Air Plenum	Ceiling	Concrete	Not Painted	N/A	N/A	N/A	N/A	
1	4	Air Plenum	Floor	Concrete	Not Painted	N/A	N/A	N/A	N/A	
1	4	Air Plenum	W1	Ceramic	Not Painted	N/A	N/A	N/A	N/A	
1	4	Air Plenum	Door	Metal	Brown	None	0	0.4	Negative	
1	4	Air Plenum	Doorframe	Metal	Brown	None	0	0.8	Positive	
1	4	Air Plenum	W2	Concrete	Not Painted	N/A	N/A	N/A	N/A	
1	4	Air Plenum	W3	Concrete	Not Painted	N/A	N/A	N/A	N/A	
1	4	Air Plenum	W4	Concrete	Not Painted	N/A	N/A	N/A	N/A	
1	4	Air Plenum	Ceiling	Concrete	Not Painted	N/A	N/A	N/A	N/A	
1	4	Air Plenum	Floor	Concrete	Not Painted	N/A	N/A	N/A	N/A	
1	4	A-Wing Fan Room	W1	Terracotta	White	Chipping	34	0.2	Negative	
1	4	A-Wing Fan Room	Door	Metal	Grey	Flaking	2	0	Negative	
1	4	A-Wing Fan Room	Doorframe	Metal	Grey	Friction	1	0.9	Positive	
1	4	A-Wing Fan Room	Exterior Fan Unit	Metal	White	Flaking	60	19.5	Positive	
1	4	A-Wing Fan Room	Fan Unit Pad	Concrete	White	Flaking	10	0.2	Negative	

		Dates: 6/5 - 7/6/2023	Lead-Safe Certification Assessment Report						
		Inspector Name and Certificate Number: Tim Smith 057662	John Bartram High School						
		Inspection Company: BATA	2401 S 67th St, Philadelphia PA 19142						
E l e m e n t	F l o o r	On-Site Room Name	Component	Substrate Material [1]	Paint Color	Description of Paint Damage	Damage Quantity (sf) [2]	XRF Reading (mg/cm2)	XRF (positive/ negative) [3]
1	4	A-Wing Fan Room	Windowframe	Metal	White	Flaking	8	15	Positive
1	4	A-Wing Fan Room	W2	Terracotta	White	Flaking	8	0	Negative
1	4	A-Wing Fan Room	W3	Terracotta	White	None	0	0.1	Negative
1	4	A-Wing Fan Room	Railing	Metal	Brown	Chipping	30	2.8	Positive
1	4	A-Wing Fan Room	Pipe	Metal	White	Chipping	8	23.1	Positive
1	4	A-Wing Fan Room	W4	Terracotta	White	Flaking	12	0.2	Negative
1	4	A-Wing Fan Room	Ceiling	Concrete	White	None	0	0.3	Negative
1	4	A-Wing Fan Room	Floor	Concrete	Not Painted	N/A	N/A	N/A	N/A
1	4	A-Wing Elevator Mechanical Room	W1	Terracotta	White	None	0	0.1	Negative
1	4	A-Wing Elevator Mechanical Room	Doorframe	Metal	Brown	Friction	4	1	Positive
1	4	A-Wing Elevator Mechanical Room	W2	Terracotta	White	Flaking	24	0.2	Negative
1	4	A-Wing Elevator Mechanical Room	Windowframe	Metal	White	Chipping	16	13.8	Positive
1	4	A-Wing Elevator Mechanical Room	W3	Terracotta	White	Flaking	30	0.1	Negative
1	4	A-Wing Elevator Mechanical Room	Conduit	Metal	White	Chipping	3	0.8	Positive
1	4	A-Wing Elevator Mechanical Room	W4	Terracotta	White	Flaking	4	0.3	Negative
1	4	A-Wing Elevator Mechanical Room	W4	Brick	White	Flaking	12	0.4	Negative
1	4	A-Wing Elevator Mechanical Room	Ceiling	Concrete	White	Flaking	12	0.6	Negative
1	4	A-Wing Elevator Mechanical Room	Beam	Metal	White	Chipping	10	15	Positive
1	4	A-Wing Elevator Mechanical Room	Floor	Concrete	Not Painted	N/A	N/A	N/A	N/A
1	4	Wing C Elevator Mechanical Room	W1	Terracotta	White	None	0	0.1	Negative
1	4	Wing C Elevator Mechanical Room	Doorframe	Metal	Brown	Friction	1	0.4	Negative
1	4	Wing C Elevator Mechanical Room	W2	Terracotta	White	None	0	0.3	Negative
1	4	Wing C Elevator Mechanical Room	Windowframe	Metal	White	Flaking	24	11.4	Positive
1	4	Wing C Elevator Mechanical Room	W3	Terracotta	White	Flaking	14	0.3	Negative
1	4	Wing C Elevator Mechanical Room	Conduit	Metal	White	Chipping	3	0.4	Negative
1	4	Wing C Elevator Mechanical Room	W4	Terracotta	White	None	0	0.1	Negative

		Dates: 6/5 - 7/6/2023	Lead-Safe Certification Assessment Report						
		Inspector Name and Certificate Number: Tim Smith 057662	John Bartram High School						
		Inspection Company: BATA	2401 S 67th St, Philadelphia PA 19142						
E l e m e n t	F l o o r	On-Site Room Name	Component	Substrate Material [1]	Paint Color	Description of Paint Damage	Damage Quantity (sf) [2]	XRF Reading (mg/cm2)	XRF (positive/ negative) [3]
1	4	Wing C Elevator Mechanical Room	Ceiling	Concrete	White	Flaking	4	0.2	Negative
1	4	Wing C Elevator Mechanical Room	Beam	Metal	White	Flaking	12	27.6	Positive
1	4	Wing C Elevator Mechanical Room	Floor	Concrete	Grey	Chipping	14	0.3	Negative
1	4	C-Wing Fan Room	W1	Terracotta	White	None	0	0.5	Negative
1	4	C-Wing Fan Room	Door	Metal	Grey	None	0	0.3	Negative
1	4	C-Wing Fan Room	Doorframe	Metal	Grey	None	0	0.7	Positive
1	4	C-Wing Fan Room	Exterior Fan Unit	Metal	Silver	Flaking	240	23.2	Positive
1	4	C-Wing Fan Room	Interior Fan Unit	Concrete	Silver	None	0	0.2	Negative
1	4	C-Wing Fan Room	Fan Unit Pad	Concrete	White	None	0	0.6	Negative
1	4	C-Wing Fan Room	Windowframe	Metal	Grey	None	0	11.4	Positive
1	4	C-Wing Fan Room	W2	Terracotta	White	None	0	0.2	Negative
1	4	C-Wing Fan Room	W3	Terracotta	White	None	0	0.2	Negative
1	4	C-Wing Fan Room	Railing	Metal	Brown	Chipping	12	0.4	Negative
1	4	C-Wing Fan Room	Pipe	Metal	White	None	0	19.7	Positive
1	4	C-Wing Fan Room	W4	Terracotta	White	None	0	0.2	Negative
1	4	C-Wing Fan Room	Ceiling	Concrete	White	Flaking	9	0.3	Negative
1	4	C-Wing Fan Room	Floor	Concrete	Grey	Cracking	20	0.2	Negative
1	4	Hallway between Stairs and the Music/Choir Room	W1	Plaster	White	Cracking	30	0.2	Negative
1	4	Hallway between Stairs and the Music/Choir Room	W2	Plaster	White	Cracking	40	0.3	Negative
1	4	Hallway between Stairs and the Music/Choir Room	Radiator cover	Metal	Brown	None	0	0	Negative
1	4	Hallway between Stairs and the Music/Choir Room	Windowframe	Metal	White	Flaking	6	1	Positive
1	4	Hallway between Stairs and the Music/Choir Room	W3-Mural wall	Plaster	Multi-Color	None	0	0.1	Negative
1	4	Hallway between Stairs and the Music/Choir Room	Covebase	Concrete	Grey	Chipping	1	0.1	Negative
1	4	Hallway between Stairs and the Music/Choir Room	W4	Plaster	White	Cracking	30	0.2	Negative
1	4	Hallway between Stairs and the Music/Choir Room	Ceiling	Plaster	White	None	0	0.2	Negative
1	4	Hallway between Stairs and the Music/Choir Room	Floor	Concrete	Not Painted	N/A	N/A	N/A	N/A

		Dates: 6/5 - 7/6/2023	Lead-Safe Certification Assessment Report						
		Inspector Name and Certificate Number: Tim Smith 057662	John Bartram High School						
		Inspection Company: BATA	2401 S 67th St, Philadelphia PA 19142						
E l e m e n t	F l o o r	On-Site Room Name	Component	Substrate Material [1]	Paint Color	Description of Paint Damage	Damage Quantity (sf) [2]	XRF Reading (mg/cm2)	XRF (positive/ negative) [3]
1	4	Stairwell B at Classroom 222	W1	Plaster	White	Cracking	20	0.3	Negative
1	4	Stairwell B at Classroom 222	Door	Metal	Blue	Chipping	4	0	Negative
1	4	Stairwell B at Classroom 222	Doorframe	Metal	Blue	Chipping	2	0	Negative
1	4	Stairwell B at Classroom 222	W2	Plaster	White	Cracking	200	0.2	Negative
1	4	Stairwell B at Classroom 222	Baluster	Metal	Brown	Chipping	6	13	Positive
1	4	Stairwell B at Classroom 222	Post	Metal	Brown	Chipping	40	10.1	Positive
1	4	Stairwell B at Classroom 222	Riser	Concrete	Brown	Friction	80	0.3	Negative
1	4	Stairwell B at Classroom 222	Stringer	Concrete	Brown	None	0	0.3	Negative
1	4	Stairwell B at Classroom 222	W3	Plaster	White	Cracking	80	0.2	Negative
1	4	Stairwell B at Classroom 222	Radiator	Metal	Brown	None	0	0.2	Negative
1	4	Stairwell B at Classroom 222	Covebase	Concrete	Brown	None	0	0.2	Negative
1	4	Stairwell B at Classroom 222	W4	Plaster	White	Flaking	100	0	Negative
1	4	Stairwell B at Classroom 222	Windowframe	Metal	White	Flaking	22	12.4	Positive
1	4	Stairwell B at Classroom 222	Conduit	Metal	White	None	0	0.7	Positive
1	4	Stairwell B at Classroom 222	Ceiling	Concrete	White	Flaking	12	0.2	Negative
1	4	Stairwell B at Classroom 222	Floor	Concrete	Not Painted	N/A	N/A	N/A	N/A
1	4	A-Wing Stairwell to the 4th Floor	W1	Terracotta	White	None	0	0.2	Negative
1	4	A-Wing Stairwell to the 4th Floor	Door	Metal	Brown	Chipping	1	0.3	Negative
1	4	A-Wing Stairwell to the 4th Floor	Doorframe	Metal	Brown	Friction	3	0.9	Positive
1	4	A-Wing Stairwell to the 4th Floor	W2	Terracotta	White	Chipping	1	0.2	Negative
1	4	A-Wing Stairwell to the 4th Floor	Riser	Concrete	Brown	Friction	30	0.5	Negative
1	4	A-Wing Stairwell to the 4th Floor	Railing	Metal	Brown	Chipping	40	2.5	Positive
1	4	A-Wing Stairwell to the 4th Floor	Pipe	Metal	White	Chipping	9	17.8	Positive
1	4	A-Wing Stairwell to the 4th Floor	W3	Terracotta	White	None	0	0	Negative
1	4	A-Wing Stairwell to the 4th Floor	W4	Terracotta	White	None	0	0.2	Negative
1	4	A-Wing Stairwell to the 4th Floor	Ceiling	Concrete	White	None	0	0.3	Negative

		Dates: 6/5 - 7/6/2023	Lead-Safe Certification Assessment Report						
		Inspector Name and Certificate Number: Tim Smith 057662	John Bartram High School						
		Inspection Company: BATA	2401 S 67th St, Philadelphia PA 19142						
E l e m e n t	F l o o r	On-Site Room Name	Component	Substrate Material [1]	Paint Color	Description of Paint Damage	Damage Quantity (sf) [2]	XRF Reading (mg/cm2)	XRF (positive/ negative) [3]
1	4	A-Wing Stairwell to the 4th Floor	Floor	Concrete	Not Painted	N/A	N/A	N/A	N/A
1	4	Stairwell C	W1	Plaster	White	Cracking	6	0	Negative
1	4	Stairwell C	Door	Metal	Blue	None	0	0	Negative
1	4	Stairwell C	Doorframe	Metal	Blue	None	0	0.1	Negative
1	4	Stairwell C	W2	Plaster	White	Flaking	20	0.2	Negative
1	4	Stairwell C	Baluster	Metal	Brown	Flaking	6	9.2	Positive
1	4	Stairwell C	Post	Metal	Brown	Chipping	4	12.5	Positive
1	4	Stairwell C	Riser	Concrete	Brown	Chipping	10	0.5	Negative
1	4	Stairwell C	Stringer	Concrete	Brown	None	0	0.5	Negative
1	4	Stairwell C	W3	Plaster	White	Flaking	4	0.2	Negative
1	4	Stairwell C	Pipe Cover	Metal	Tan	Chipping	3	0.6	Negative
1	4	Stairwell C	Pipe Insulation	Asbestos	White	None	0	0.1	Negative
1	4	Stairwell C	Radiator	Metal	Brown	Chipping	2	0	Negative
1	4	Stairwell C	Covebase	Concrete	Brown	None	0	0.2	Negative
1	4	Stairwell C	W4	Plaster	White	Flaking	24	0.1	Negative
1	4	Stairwell C	Windowframe	Metal	White	None	0	14.4	Positive
1	4	Stairwell C	Ceiling	Concrete	White	Flaking	4	0.1	Negative
1	4	Stairwell C	Floor	Concrete	Not Painted	N/A	N/A	N/A	N/A
1	4	Stairwell adjacent to Rooftop Gym (402)	W1	Plaster	White	Flaking	70	0	Negative
1	4	Stairwell adjacent to Rooftop Gym (402)	Door	Metal	Grey	None	0	0.2	Negative
1	4	Stairwell adjacent to Rooftop Gym (402)	Doorframe	Metal	Grey	None	0	0	Negative
1	4	Stairwell adjacent to Rooftop Gym (402)	W2	Plaster	White	Flaking	140	0.1	Negative
1	4	Stairwell adjacent to Rooftop Gym (402)	Windowframe	Metal	White	Flaking	30	9	Positive
1	4	Stairwell adjacent to Rooftop Gym (402)	Riser	Concrete	Brown	Flaking	120	0.7	Positive
1	4	Stairwell adjacent to Rooftop Gym (402)	Stringer	Concrete	Brown	Flaking	30	0.4	Negative
1	4	Stairwell adjacent to Rooftop Gym (402)	Post	Metal	Brown	None	0	1	Positive

		Dates: 6/5 - 7/6/2023	Lead-Safe Certification Assessment Report						
		Inspector Name and Certificate Number: Tim Smith 057662	John Bartram High School						
		Inspection Company: BATA	2401 S 67th St, Philadelphia PA 19142						
E l e m e n t	F l o o r	On-Site Room Name	Component	Substrate Material [1]	Paint Color	Description of Paint Damage	Damage Quantity (sf) [2]	XRF Reading (mg/cm2)	XRF (positive/ negative) [3]
1	4	Stairwell adjacent to Rooftop Gym (402)	Baluster	Metal	Brown	None	0	9.2	Positive
1	4	Stairwell adjacent to Rooftop Gym (402)	W3	Plaster	White	Flaking	70	0	Negative
1	4	Stairwell adjacent to Rooftop Gym (402)	Pipe	Metal	White	Flaking	8	0.3	Negative
1	4	Stairwell adjacent to Rooftop Gym (402)	Radiator cover	Metal	Brown	Flaking	3	0.1	Negative
1	4	Stairwell adjacent to Rooftop Gym (402)	W4	Plaster	White	Flaking	100	0	Negative
1	4	Stairwell adjacent to Rooftop Gym (402)	Covebase	Concrete	Brown	Flaking	15	0.2	Negative
1	4	Stairwell adjacent to Rooftop Gym (402)	Ceiling	Concrete	White	None	0	0.4	Negative
1	4	Stairwell adjacent to Rooftop Gym (402)	Floor	Concrete	Not Painted	N/A	N/A	N/A	N/A
1	5	Former Water Tank Room (above the Music/Choir Room)	W1	Terracotta	White	Flaking	100	0.2	Negative
1	5	Former Water Tank Room (above the Music/Choir Room)	Door	Metal	Brown	None	0	0.1	Negative
1	5	Former Water Tank Room (above the Music/Choir Room)	Doorframe	Metal	Brown	None	0	0.4	Negative
1	5	Former Water Tank Room (above the Music/Choir Room)	W2	Terracotta	White	Flaking	220	0.1	Negative
1	5	Former Water Tank Room (above the Music/Choir Room)	Column	Concrete	White	Chipping	80	0.5	Negative
1	5	Former Water Tank Room (above the Music/Choir Room)	Water Tank	Metal	Silver	Chipping	200	0	Negative
1	5	Former Water Tank Room (above the Music/Choir Room)	Windowframe	Metal	White	Chipping	45	14	Positive
1	5	Former Water Tank Room (above the Music/Choir Room)	W3	Terracotta	White	Flaking	120	0.1	Negative
1	5	Former Water Tank Room (above the Music/Choir Room)	Pipe	Metal	White	Chipping	60	17.6	Positive
1	5	Former Water Tank Room (above the Music/Choir Room)	Radiator	Metal	Brown	Flaking	15	0.3	Negative

		Dates: 6/5 - 7/6/2023	Lead-Safe Certification Assessment Report						
		Inspector Name and Certificate Number: Tim Smith 057662	John Bartram High School						
		Inspection Company: BATA	2401 S 67th St, Philadelphia PA 19142						
E l e m e n t	F l o o r	On-Site Room Name	Component	Substrate Material [1]	Paint Color	Description of Paint Damage	Damage Quantity (sf) [2]	XRF Reading (mg/cm2)	XRF (positive/ negative) [3]
1	5	Former Water Tank Room (above the Music/Choir Room)	Railing	Metal	Brown	Chipping	40	1.4	Positive
1	5	Former Water Tank Room (above the Music/Choir Room)	Riser	Concrete	Brown	None	0	0.6	Negative
1	5	Former Water Tank Room (above the Music/Choir Room)	W4	Terracotta	White	Flaking	260	0.1	Negative
1	5	Former Water Tank Room (above the Music/Choir Room)	Ceiling	Concrete	White	Flaking	400	0.1	Negative
1	5	Former Water Tank Room (above the Music/Choir Room)	Floor	Concrete	Not Painted	N/A	N/A	N/A	N/A
1	A	Main Attic	W1	No Access	No Access	No Access	No Access	No Access	No Access
1	A	Main Attic	W2	No Access	No Access	No Access	No Access	No Access	No Access
1	A	Main Attic	W3	No Access	No Access	No Access	No Access	No Access	No Access
1	A	Main Attic	W4	No Access	No Access	No Access	No Access	No Access	No Access
1	A	Main Attic	Ceiling	No Access	No Access	No Access	No Access	No Access	No Access
1	A	Main Attic	Floor	No Access	No Access	No Access	No Access	No Access	No Access
1	B	Girl's Gym Fan	W1	Plaster	White	None	0	0.2	Negative
1	B	Girl's Gym Fan	Conduit	Metal	White	None	0	0.3	Negative
1	B	Girl's Gym Fan	Exterior Fan Unit	Metal	Silver	Flaking	15	6.2	Positive
1	B	Girl's Gym Fan	Interior Fan Unit	Metal	Silver	None	0	2.2	Positive
1	B	Girl's Gym Fan	Railing	Metal	Grey	Chipping	6	0.8	Positive
1	B	Girl's Gym Fan	Tread	Concrete	Grey	None	0	0.1	Negative
1	B	Girl's Gym Fan	Riser	Concrete	Grey	None	0	0.1	Negative
1	B	Girl's Gym Fan	Door	Metal	Brown	Chipping	2	0.3	Negative
1	B	Girl's Gym Fan	Doorframe	Metal	Brown	Friction	6	0.6	Negative
1	B	Girl's Gym Fan	Column	Concrete	White	Flaking	8	0.1	Negative
1	B	Girl's Gym Fan	W2	Plaster	White	None	0	0.2	Negative

		Dates: 6/5 - 7/6/2023	Lead-Safe Certification Assessment Report						
		Inspector Name and Certificate Number: Tim Smith 057662	John Bartram High School						
		Inspection Company: BATA	2401 S 67th St, Philadelphia PA 19142						
Element	Floor	On-Site Room Name	Component	Substrate Material [1]	Paint Color	Description of Paint Damage	Damage Quantity (sf) [2]	XRF Reading (mg/cm2)	XRF (positive/negative) [3]
1	B	Girl's Gym Fan	W3	Plaster	White	None	0	0.3	Negative
1	B	Girl's Gym Fan	Windowframe	Wood	Grey	None	0	1	Positive
1	B	Girl's Gym Fan	W4	Plaster	White	None	0	0.3	Negative
1	B	Girl's Gym Fan	Ceiling	Concrete	White	Flaking	30	0.3	Negative
1	B	Girl's Gym Fan	Floor	Concrete	Grey	None	0	0.1	Negative
1	B	Storage B-H	W1	Plaster	Tan	None	0	0.1	Negative
1	B	Storage B-H	Doorframe	Metal	Brown	Friction	3	0.5	Negative
1	B	Storage B-H	W2	Plaster	Tan	None	0	0.1	Negative
1	B	Storage B-H	W3	Plaster	Tan	None	0	0.1	Negative
1	B	Storage B-H	Covebase	Concrete	Grey	None	0	0	Negative
1	B	Storage B-H	W4	Plaster	Tan	None	0	0.2	Negative
1	B	Storage B-H	Ceiling	Plaster	Tan	Cracking	4	0.1	Negative
1	B	Storage B-H	Floor	Concrete	Grey	None	0	0.1	Negative
1	B	Room marked 13 Custodial Services	W1	Plaster	Tan/White	None	0	0.4	Negative
1	B	Room marked 13 Custodial Services	Doorframe	Metal	Brown	Friction	5	1.8	Positive
1	B	Room marked 13 Custodial Services	W2	Plaster	Tan/White	None	0	0.4	Negative
1	B	Room marked 13 Custodial Services	Covebase	Concrete	Brown	Chipping	2	1.1	Positive
1	B	Room marked 13 Custodial Services	W3	Plaster	Tan/White	None	0	0.3	Negative
1	B	Room marked 13 Custodial Services	Pipe Cover	Metal	Tan	Flaking	2	3.1	Positive
1	B	Room marked 13 Custodial Services	Radiator	Metal	Brown	Flaking	12	0.2	Negative
1	B	Room marked 13 Custodial Services	Pipe	Metal	Tan/White	None	0	0.3	Negative
1	B	Room marked 13 Custodial Services	W4	Plaster	Tan/White	None	0	0.5	Negative
1	B	Room marked 13 Custodial Services	Ceiling	Concrete	White	None	0	0.1	Negative
1	B	Room marked 13 Custodial Services	Ceiling	2'x4' Ceiling Tile	Not Painted	N/A	N/A	N/A	N/A
1	B	Room marked 13 Custodial Services	Floor	Concrete	Brown	Friction	200	0	Negative

		Dates: 6/5 - 7/6/2023	Lead-Safe Certification Assessment Report						
		Inspector Name and Certificate Number: Tim Smith 057662	John Bartram High School						
		Inspection Company: BATA	2401 S 67th St, Philadelphia PA 19142						
E l e m e n t	F l o o r	On-Site Room Name	Component	Substrate Material [1]	Paint Color	Description of Paint Damage	Damage Quantity (sf) [2]	XRF Reading (mg/cm2)	XRF (positive/ negative) [3]
1	B	Staff Restroom inside Room marked 13 Custodial Services	W1	Plaster	Tan	Cracking	30	0.1	Negative
1	B	Staff Restroom inside Room marked 13 Custodial Services	Doorframe	Metal	Brown	Friction	4	0.4	Negative
1	B	Staff Restroom inside Room marked 13 Custodial Services	Covebase	Concrete	Brown	Flaking	20	0.2	Negative
1	B	Staff Restroom inside Room marked 13 Custodial Services	W2	Plaster	Tan	Cracking	30	0.2	Negative
1	B	Staff Restroom inside Room marked 13 Custodial Services	W3	Plaster	Tan	Flaking	20	0.1	Negative
1	B	Staff Restroom inside Room marked 13 Custodial Services	Mirror Frame	Wood	Tan	None	0	0.3	Negative
1	B	Staff Restroom inside Room marked 13 Custodial Services	W4	Plaster	Tan	Cracking	20	0.2	Negative
1	B	Staff Restroom inside Room marked 13 Custodial Services	Pipe Cover	Metal	Tan	Flaking	8	4.4	Positive
1	B	Staff Restroom inside Room marked 13 Custodial Services	Pipe Insulation	Asbestos	Tan	Alligatoring	20	0	Negative
1	B	Staff Restroom inside Room marked 13 Custodial Services	Ceiling	Concrete	Tan	None	0	0.2	Negative
1	B	Staff Restroom inside Room marked 13 Custodial Services	Floor	Concrete	Grey	friction	50	0.2	Negative
1	B	Room 12 Water Booster Pump Room	W1	Terracotta	White/Grey	None	0	4.3	Positive
1	B	Room 12 Water Booster Pump Room	Doorframe	Metal	Brown	Flaking	12	4.4	Positive
1	B	Room 12 Water Booster Pump Room	Door	Wood	Brown	Flaking	14	3.1	Positive
1	B	Room 12 Water Booster Pump Room	W2	Terracotta	White/Grey	None	0	4.3	Positive
1	B	Room 12 Water Booster Pump Room	Windowframe	Wood	Grey	Cracking	8	1.3	Positive
1	B	Room 12 Water Booster Pump Room	W3	Concrete	Grey/White	Flaking	500	0.3	Negative
1	B	Room 12 Water Booster Pump Room	W4	Brick	Grey/White	Flaking	20	10.4	Positive

		Dates: 6/5 - 7/6/2023	Lead-Safe Certification Assessment Report							
		Inspector Name and Certificate Number: Tim Smith 057662	John Bartram High School							
		Inspection Company: BATA	2401 S 67th St, Philadelphia PA 19142							
E l e m e n t	F l o o r	On-Site Room Name	Component	Substrate Material [1]	Paint Color	Description of Paint Damage	Damage Quantity (sf) [2]	XRF Reading (mg/cm2)	XRF (positive/ negative) [3]	
1	B	Room 12 Water Booster Pump Room	Pipe	Metal	White/Grey	Flaking	40	16.1	Positive	
1	B	Room 12 Water Booster Pump Room	Ceiling	Concrete	White	Flaking	30	0.2	Negative	
1	B	Room 12 Water Booster Pump Room	Floor	Concrete	Not Painted	N/A	N/A	N/A	N/A	
1	B	Building Engineer's Office	W1	Plaster	Tan/Red	None	0	1.2	Positive	
1	B	Building Engineer's Office	Doorframe	Metal	Brown	Chipping	8	0.4	Negative	
1	B	Building Engineer's Office	W2	Plaster	Tan/Red	None	0	0.1	Negative	
1	B	Building Engineer's Office	Conduit	Metal	Tan	None	0	0.1	Negative	
1	B	Building Engineer's Office	Covebase	Concrete	Grey	None	0	1.8	Positive	
1	B	Building Engineer's Office	Blackboard Frame	Wood	Tan	None	0	0.2	Negative	
1	B	Building Engineer's Office	W3	Plaster	Tan/Red	None	0	0.7	Positive	
1	B	Building Engineer's Office	Pipe Cover	Metal	Tan	None	0	2.4	Positive	
1	B	Building Engineer's Office	Pipe Insulation	Asbestos	Tan	None	0	1.9	Positive	
1	B	Building Engineer's Office	Conduit	Plastic	Tan	None	0	0.4	Negative	
1	B	Building Engineer's Office	Radiator	Metal	Brown	None	0	0	Negative	
1	B	Building Engineer's Office	W4	Plaster	Tan/Red	None	0	2.1	Positive	
1	B	Building Engineer's Office	Ceiling	Concrete	White	None	0	1.3	Positive	
1	B	Building Engineer's Office	Ceiling	2'x4' Ceiling Tile	Not Painted	N/A	N/A	N/A	N/A	
1	B	Building Engineer's Office	Floor	Concrete	Grey	None	0	0.1	Negative	
1	B	Boiler Room Area	W1	Concrete	White	Flaking	240	0.1	Negative	
1	B	Boiler Room Area	W1	CMU	White	None	0	0.2	Negative	
1	B	Boiler Room Area	Door	Metal	Grey	None	0	0.3	Negative	
1	B	Boiler Room Area	Doorframe	Metal	Grey	Flaking	5	9.4	Positive	
1	B	Boiler Room Area	W2	Concrete	White	Cracking	400	0.1	Negative	
1	B	Boiler Room Area	W2	Brick	White	Flaking	200	0.2	Negative	
1	B	Boiler Room Area	Conduit	Metal	White	None	0	0.3	Negative	

		Dates: 6/5 - 7/6/2023	Lead-Safe Certification Assessment Report						
		Inspector Name and Certificate Number: Tim Smith 057662	John Bartram High School						
		Inspection Company: BATA	2401 S 67th St, Philadelphia PA 19142						
E l e m e n t	F l o o r	On-Site Room Name	Component	Substrate Material [1]	Paint Color	Description of Paint Damage	Damage Quantity (sf) [2]	XRF Reading (mg/cm2)	XRF (positive/ negative) [3]
1	B	Boiler Room Area	Railing	Metal	Black	None	0	0.5	Negative
1	B	Boiler Room Area	Tread	Concrete	Grey	Friction	24	0.5	Negative
1	B	Boiler Room Area	Riser	Concrete	Grey	Flaking	5	0.5	Negative
1	B	Boiler Room Area	W3	Brick	White	None	0	0.1	Negative
1	B	Boiler Room Area	Pipe	Metal	White	Flaking	8	12	Positive
1	B	Boiler Room Area	W4	Brick	White	Flaking	280	0.3	Negative
1	B	Boiler Room Area	W4	Concrete	White	Flaking	100	0	Negative
1	B	Boiler Room Area	Column	Concrete	White	Flaking	230	0.2	Negative
1	B	Boiler Room Area	Beam	Metal	Black	None	0	0	Negative
1	B	Boiler Room Area	Ladder	Metal	Black	None	0	0.3	Negative
1	B	Boiler Room Area	Ceiling	Concrete	White	Flaking	480	0.2	Negative
1	B	Boiler Room Area	Floor	Concrete	Grey	None	0	0.3	Negative
1	B	Restroom inside the Building Engineer's Office	W1	Plaster	Tan	None	0	0.7	Positive
1	B	Restroom inside the Building Engineer's Office	Doorframe	Metal	Tan	None	0	0.5	Negative
1	B	Restroom inside the Building Engineer's Office	W2	Plaster	Tan	None	0	0.4	Negative
1	B	Restroom inside the Building Engineer's Office	Pipe	Metal	Tan	None	0	1	Positive
1	B	Restroom inside the Building Engineer's Office	W3	Plaster	Tan	None	0	0.7	Positive
1	B	Restroom inside the Building Engineer's Office	Mirror Frame	Wood	Tan	None	0	0.2	Negative
1	B	Restroom inside the Building Engineer's Office	W4	Plaster	Tan	None	0	0.4	Negative
1	B	Restroom inside the Building Engineer's Office	Covebase	Concrete	Grey	None	0	1.7	Positive
1	B	Restroom inside the Building Engineer's Office	Ceiling	Concrete	Tan	None	0	0.2	Negative
1	B	Restroom inside the Building Engineer's Office	Floor	Concrete	Grey	None	0	0.1	Negative
1	B	Main Electrical Room	W1	Brick	White	Chipping	12	0	Negative
1	B	Main Electrical Room	Doorframe	Metal	Brown	None	0	0.3	Negative
1	B	Main Electrical Room	Conduit	Metal	White	None	0	0.1	Negative
1	B	Main Electrical Room	W2	Concrete	White	None	0	0.2	Negative

		Dates: 6/5 - 7/6/2023	Lead-Safe Certification Assessment Report							
		Inspector Name and Certificate Number: Tim Smith 057662	John Bartram High School							
		Inspection Company: BATA	2401 S 67th St, Philadelphia PA 19142							
E l e m e n t	F l o o r	On-Site Room Name	Component	Substrate Material [1]	Paint Color	Description of Paint Damage	Damage Quantity (sf) [2]	XRF Reading (mg/cm2)	XRF (positive/ negative) [3]	
1	B	Main Electrical Room	W3	Brick	White	None	0	0	Negative	
1	B	Main Electrical Room	W4	Brick	White	None	0	0.2	Negative	
1	B	Main Electrical Room	Ceiling	Concrete	White	None	0	0.4	Negative	
1	B	Main Electrical Room	Floor	Concrete	Not Painted	N/A	N/A	N/A	N/A	
1	B	Emergency Generator Room - B Wing	W1	Plaster	Green/White	None	0	0.1	Negative	
1	B	Emergency Generator Room - B Wing	Doorframe	Metal	Brown	Friction	10	0.7	Positive	
1	B	Emergency Generator Room - B Wing	W2	Plaster	Green	None	0	0.2	Negative	
1	B	Emergency Generator Room - B Wing	Covebase	Concrete	Grey	None	0	0.7	Positive	
1	B	Emergency Generator Room - B Wing	W3	Plaster	Green	None	0	0.3	Negative	
1	B	Emergency Generator Room - B Wing	Pipe Insulation	Asbestos	Green	None	0	0.1	Negative	
1	B	Emergency Generator Room - B Wing	Radiator	Metal	Brown	Flaking	6	0.1	Negative	
1	B	Emergency Generator Room - B Wing	W4	Plaster	Green	None	0	0.2	Negative	
1	B	Emergency Generator Room - B Wing	Ceiling	Concrete	White	Flaking	3	0.1	Negative	
1	B	Emergency Generator Room - B Wing	Floor	Concrete	Grey	Friction	200	0.3	Negative	
1	B	Building Engineer's Storage Area	W1	Plaster	Tan/Pink	Flaking	12	0	Negative	
1	B	Building Engineer's Storage Area	Doorframe	Metal	Brown	Chipping	6	0.5	Negative	
1	B	Building Engineer's Storage Area	W2	Plaster	Tan/Pink	None	0	0.1	Negative	
1	B	Building Engineer's Storage Area	W3	Plaster	Tan/Pink	Efflorescence	50	0	Negative	
1	B	Building Engineer's Storage Area	W4	Plaster	Tan/Pink	None	0	0.1	Negative	
1	B	Building Engineer's Storage Area	Ceiling	Plaster	White	Cracking	30	0.2	Negative	
1	B	Building Engineer's Storage Area	Floor	Wood	Not Painted	N/A	N/A	N/A	N/A	
1	B	Security Office 16	W1	Plaster	White	Flaking	6	0	Negative	
1	B	Security Office 16	Doorframe	Metal	Brown	Chipping	6	0.2	Negative	
1	B	Security Office 16	W2	Drywall	Red	Chipping	5	0.2	Negative	
1	B	Security Office 16	W3	Plaster	White	Flaking	18	0	Negative	
1	B	Security Office 16	Pipe Cover	Metal	White	Flaking	8	2.3	Positive	

		Dates: 6/5 - 7/6/2023	Lead-Safe Certification Assessment Report						
		Inspector Name and Certificate Number: Tim Smith 057662	John Bartram High School						
		Inspection Company: BATA	2401 S 67th St, Philadelphia PA 19142						
Element	Floor	On-Site Room Name	Component	Substrate Material [1]	Paint Color	Description of Paint Damage	Damage Quantity (sf) [2]	XRF Reading (mg/cm ²)	XRF (positive/negative) [3]
1	B	Security Office 16	Pipe Insulation	Asbestos	White	None	0	0.1	Negative
1	B	Security Office 16	Conduit	Plastic	Red	None	0	0.2	Negative
1	B	Security Office 16	W4	Plaster	White	Flaking	6	0	Negative
1	B	Security Office 16	Conduit	Metal	White	None	0	0.1	Negative
1	B	Security Office 16	Ceiling	Plaster	White	Flaking	60	0	Negative
1	B	Security Office 16	Ceiling	2'x4' Ceiling Tile	Not Painted	N/A	N/A	N/A	N/A
1	B	Security Office 16	Floor	Wood	Not Painted	N/A	N/A	N/A	N/A
1	B	Custodial Staff Lounge in B Wing	W1	Plaster	Tan/Pink	Flaking	4	0.5	Negative
1	B	Custodial Staff Lounge in B Wing	Doorframe	Metal	Brown	Chipping	2	0.4	Negative
1	B	Custodial Staff Lounge in B Wing	Pipe	Metal	Tan/Pink	Chipping	1	15.9	Positive
1	B	Custodial Staff Lounge in B Wing	W2	Plaster	Tan/Pink	Friction	2	0.2	Negative
1	B	Custodial Staff Lounge in B Wing	Covebase	Concrete	Grey	Chipping	8	0	Negative
1	B	Custodial Staff Lounge in B Wing	W3	Plaster	Tan/Pink	Spalling	6	0.1	Negative
1	B	Custodial Staff Lounge in B Wing	Pipe Cover	Metal	Tan	None	0	0.5	Negative
1	B	Custodial Staff Lounge in B Wing	Pipe Insulation	Asbestos	Tan	Alligatoring	6	0	Negative
1	B	Custodial Staff Lounge in B Wing	W4	Plaster	Tan/Pink	None	0	0.3	Negative
1	B	Custodial Staff Lounge in B Wing	Ceiling	Plaster	White	None	0	0.2	Negative
1	B	Custodial Staff Lounge in B Wing	Ceiling	2'x4' Ceiling Tile	Not Painted	N/A	N/A	N/A	N/A
1	B	Custodial Staff Lounge in B Wing	Floor	Concrete	Not Painted	N/A	N/A	N/A	N/A
1	B	Storage Room marked 'B' across from Auditorium Plenum	W1	Plaster	Tan	None	0	0.1	Negative
1	B	Storage Room marked 'B' across from Auditorium Plenum	Doorframe	Metal	Brown	Friction	2	0.8	Positive
1	B	Storage Room marked 'B' across from Auditorium Plenum	W2	Plaster	Tan	None	0	0.1	Negative
1	B	Storage Room marked 'B' across from Auditorium Plenum	Covebase	Concrete	Grey	None	0	0.2	Negative

		Dates: 6/5 - 7/6/2023	Lead-Safe Certification Assessment Report						
		Inspector Name and Certificate Number: Tim Smith 057662	John Bartram High School						
		Inspection Company: BATA	2401 S 67th St, Philadelphia PA 19142						
Element	Floor	On-Site Room Name	Component	Substrate Material [1]	Paint Color	Description of Paint Damage	Damage Quantity (sf) [2]	XRF Reading (mg/cm2)	XRF (positive/negative) [3]
1	B	Storage Room marked 'B' across from Auditorium Plenum	W3	Plaster	Tan	None	0	0.1	Negative
1	B	Storage Room marked 'B' across from Auditorium Plenum	W4	Plaster	Tan	None	0	0.2	Negative
1	B	Storage Room marked 'B' across from Auditorium Plenum	Ceiling	Plaster	Tan	Cracking	4	0.4	Negative
1	B	Storage Room marked 'B' across from Auditorium Plenum	Floor	Concrete	Grey	None	0	0.1	Negative
1	B	Restroom inside Custodial Staff Lounge in B Wing	W1	Plaster	Tan	Flaking	16	0.1	Negative
1	B	Restroom inside Custodial Staff Lounge in B Wing	Doorframe	Metal	Brown	Friction	4	0.4	Negative
1	B	Restroom inside Custodial Staff Lounge in B Wing	Pipe Insulation	Asbestos	Tan	None	0	0.2	Negative
1	B	Restroom inside Custodial Staff Lounge in B Wing	W2	Plaster	Tan	Flaking	10	0	Negative
1	B	Restroom inside Custodial Staff Lounge in B Wing	Covebase	Concrete	Grey	Flaking	16	0.1	Negative
1	B	Restroom inside Custodial Staff Lounge in B Wing	Mirror Frame	Wood	Tan	Flaking	1	0.1	Negative
1	B	Restroom inside Custodial Staff Lounge in B Wing	W3	Plaster	Tan	Flaking	44	0	Negative
1	B	Restroom inside Custodial Staff Lounge in B Wing	Pipe Cover	Metal	Tan	Flaking	3	2.7	Positive
1	B	Restroom inside Custodial Staff Lounge in B Wing	W4	Plaster	Tan	Flaking	30	0	Negative
1	B	Restroom inside Custodial Staff Lounge in B Wing	Ceiling	Plaster	Tan	Cracking	10	0.3	Negative
1	B	Restroom inside Custodial Staff Lounge in B Wing	Floor	Concrete	Not Painted	N/A	N/A	N/A	N/A
1	B	Storage Room 18	W1	Brick	Tan	None	0	0.3	Negative
1	B	Storage Room 18	Grate	Metal	Black	None	0	0	Negative
1	B	Storage Room 18	Covebase	Concrete	Grey	None	0	0.1	Negative
1	B	Storage Room 18	Conduit	Metal	White	None	0	0.7	Positive
1	B	Storage Room 18	Doorframe	Metal	Brown	Friction	10	0.8	Positive
1	B	Storage Room 18	W2	Brick	Tan	Efflorescence	40	0.4	Negative
1	B	Storage Room 18	W3	Brick	Tan	None	0	0.3	Negative
1	B	Storage Room 18	W4	Brick	Tan	Cracking	5	0.3	Negative

		Dates: 6/5 - 7/6/2023	Lead-Safe Certification Assessment Report						
		Inspector Name and Certificate Number: Tim Smith 057662	John Bartram High School						
		Inspection Company: BATA	2401 S 67th St, Philadelphia PA 19142						
E l e m e n t	F l o o r	On-Site Room Name	Component	Substrate Material [1]	Paint Color	Description of Paint Damage	Damage Quantity (sf) [2]	XRF Reading (mg/cm2)	XRF (positive/ negative) [3]
1	B	Storage Room 18	Ceiling	Plaster	White	None	0	0.5	Negative
1	B	Storage Room 18	Floor	Concrete	Grey	friction	30	0	Negative
1	B	Storage Adjacent to Boy's Locker	W1	Brick	Grey	Flaking	50	0.1	Negative
1	B	Storage Adjacent to Boy's Locker	Door	Metal	Brown	Chipping	20	0.7	Positive
1	B	Storage Adjacent to Boy's Locker	Doorframe	Metal	Brown	Chipping	12	0.4	Negative
1	B	Storage Adjacent to Boy's Locker	W2	Brick	Grey	Flaking	120	0	Negative
1	B	Storage Adjacent to Boy's Locker	W3	Brick	Grey	Flaking	120	0.1	Negative
1	B	Storage Adjacent to Boy's Locker	W3	Brick	White	Chipping	120	0.1	Negative
1	B	Storage Adjacent to Boy's Locker	W4	Brick	Grey	Cracking	40	0	Negative
1	B	Storage Adjacent to Boy's Locker	Incinerator Motor	Metal	Brown	Flaking	12	0.1	Negative
1	B	Storage Adjacent to Boy's Locker	Pipe	Metal	Grey	Flaking	30	15.6	Positive
1	B	Storage Adjacent to Boy's Locker	Ceiling	Concrete	Not Painted	N/A	N/A	N/A	N/A
1	B	Storage Adjacent to Boy's Locker	Floor	Concrete	Not Painted	N/A	N/A	N/A	N/A
1	B	Storage closet in Storage Adjacent to Boy's Locker	W1	Plaster	Tan	None	0	0.2	Negative
1	B	Storage closet in Storage Adjacent to Boy's Locker	Doorframe	Metal	Brown	None	0	0.6	Negative
1	B	Storage closet in Storage Adjacent to Boy's Locker	W2	Plaster	Tan	Flaking	4	0.6	Negative
1	B	Storage closet in Storage Adjacent to Boy's Locker	W3	Plaster	Tan	Efflorescence	12	0.1	Negative
1	B	Storage closet in Storage Adjacent to Boy's Locker	W4	Plaster	Tan	Efflorescence	4	0.4	Negative
1	B	Storage closet in Storage Adjacent to Boy's Locker	Ceiling	Plaster	Tan	Flaking	1	0.4	Negative
1	B	Storage closet in Storage Adjacent to Boy's Locker	Floor	Concrete	Not Painted	N/A	N/A	N/A	N/A
1	B	Restroom inside Storage Adjacent to Boy's Locker	W1	Plaster	Tan	None	0	0.3	Negative
1	B	Restroom inside Storage Adjacent to Boy's Locker	Doorframe	Metal	Brown	Friction	2	0.5	Negative
1	B	Restroom inside Storage Adjacent to Boy's Locker	W2	Plaster	Tan	None	0	0.7	Positive
1	B	Restroom inside Storage Adjacent to Boy's Locker	Covebase	Concrete	Grey	None	0	0.3	Negative
1	B	Restroom inside Storage Adjacent to Boy's Locker	W3	Plaster	Tan	None	0	0.3	Negative
1	B	Restroom inside Storage Adjacent to Boy's Locker	W4	Plaster	Tan	None	0	0.3	Negative

		Dates: 6/5 - 7/6/2023	Lead-Safe Certification Assessment Report						
		Inspector Name and Certificate Number: Tim Smith 057662	John Bartram High School						
		Inspection Company: BATA	2401 S 67th St, Philadelphia PA 19142						
E l e m e n t	F l o o r	On-Site Room Name	Component	Substrate Material [1]	Paint Color	Description of Paint Damage	Damage Quantity (sf) [2]	XRF Reading (mg/cm2)	XRF (positive/ negative) [3]
1	B	Restroom inside Storage Adjacent to Boy's Locker	Pipe Insulation	Asbestos	Tan	None	0	0.1	Negative
1	B	Restroom inside Storage Adjacent to Boy's Locker	Ceiling	Plaster	Tan	None	0	0.1	Negative
1	B	Restroom inside Storage Adjacent to Boy's Locker	Floor	Concrete	Grey	None	0	0.2	Negative
1	B	Storage room through storage room 18	W1	Plaster	Tan	None	0	0.1	Negative
1	B	Storage room through storage room 18	Doorframe	Metal	Brown	Friction	4	0.8	Positive
1	B	Storage room through storage room 18	W2	Plaster	Tan	None	0	0.1	Negative
1	B	Storage room through storage room 18	W3	Plaster	Tan	None	0	0.1	Negative
1	B	Storage room through storage room 18	Column	Plaster	Tan	None	0	0.1	Negative
1	B	Storage room through storage room 18	W4	Plaster	Tan	None	0	0	Negative
1	B	Storage room through storage room 18	Ceiling	Plaster	Tan	None	0	0.1	Negative
1	B	Storage room through storage room 18	Floor	Concrete	Grey	Friction	400	0.2	Negative
1	B	Boy's Locker Room	W1	Ceramic	Not Painted	N/A	N/A	N/A	N/A
1	B	Boy's Locker Room	Doorframe	Metal	Brown	Chipping	1	0.7	Positive
1	B	Boy's Locker Room	W2	Ceramic	Not Painted	N/A	N/A	N/A	N/A
1	B	Boy's Locker Room	Radiator	Metal	Silver	Flaking	160	0.1	Negative
1	B	Boy's Locker Room	Pipe	Metal	White	Flaking	8	17.9	Positive
1	B	Boy's Locker Room	W3	Ceramic	Not Painted	N/A	N/A	N/A	N/A
1	B	Boy's Locker Room	W4	Ceramic	Not Painted	N/A	N/A	N/A	N/A
1	B	Boy's Locker Room	Ceiling	Concrete	Not Painted	N/A	N/A	N/A	N/A
1	B	Boy's Locker Room	Floor	Concrete	Not Painted	N/A	N/A	N/A	N/A
1	B	Pipe Chase in Boy's Locker Room	W1	No Access	No Access	No Access	No Access	No Access	No Access
1	B	Pipe Chase in Boy's Locker Room	W2	No Access	No Access	No Access	No Access	No Access	No Access
1	B	Pipe Chase in Boy's Locker Room	W3	No Access	No Access	No Access	No Access	No Access	No Access
1	B	Pipe Chase in Boy's Locker Room	W4	No Access	No Access	No Access	No Access	No Access	No Access
1	B	Pipe Chase in Boy's Locker Room	Ceiling	No Access	No Access	No Access	No Access	No Access	No Access
1	B	Pipe Chase in Boy's Locker Room	Floor	No Access	No Access	No Access	No Access	No Access	No Access

		Dates: 6/5 - 7/6/2023	Lead-Safe Certification Assessment Report							
		Inspector Name and Certificate Number: Tim Smith 057662	John Bartram High School							
		Inspection Company: BATA	2401 S 67th St, Philadelphia PA 19142							
Element	Floor	On-Site Room Name	Component	Substrate Material [1]	Paint Color	Description of Paint Damage	Damage Quantity (sf) [2]	XRF Reading (mg/cm ²)	XRF (positive/negative) [3]	
1	B	Pipe Chase in Boy's Restroom Section	W1	No Access	No Access	No Access	No Access	No Access	No Access	
1	B	Pipe Chase in Boy's Restroom Section	W2	No Access	No Access	No Access	No Access	No Access	No Access	
1	B	Pipe Chase in Boy's Restroom Section	W3	No Access	No Access	No Access	No Access	No Access	No Access	
1	B	Pipe Chase in Boy's Restroom Section	W4	No Access	No Access	No Access	No Access	No Access	No Access	
1	B	Pipe Chase in Boy's Restroom Section	Ceiling	No Access	No Access	No Access	No Access	No Access	No Access	
1	B	Pipe Chase in Boy's Restroom Section	Floor	No Access	No Access	No Access	No Access	No Access	No Access	
1	B	Classroom 2/4	W1	Drywall	White	None	0	0.1	Negative	
1	B	Classroom 2/4	Door	Wood	Black	Chipping	15	0	Negative	
1	B	Classroom 2/4	Doorframe	Metal	Brown	None	0	0.1	Negative	
1	B	Classroom 2/4	W2	Terracotta	White	Flaking	22	3.9	Positive	
1	B	Classroom 2/4	Windowframe	Wood	Brown	None	0	1.9	Positive	
1	B	Classroom 2/4	Radiator cover	Metal	Tan	Flaking	9	0.1	Negative	
1	B	Classroom 2/4	Radiator	Metal	Silver	Flaking	12	0.1	Negative	
1	B	Classroom 2/4	Conduit	Metal	White	None	0	0.2	Negative	
1	B	Classroom 2/4	Covebase	Concrete	Brown	None	0	1.6	Positive	
1	B	Classroom 2/4	W3	Drywall	White	None	0	0.1	Negative	
1	B	Classroom 2/4	W4	Terracotta	White	None	0	0.2	Negative	
1	B	Classroom 2/4	Partition	Drywall	White	None	0	0.1	Negative	
1	B	Classroom 2/4	Pipe Insulation	Fiberglass	White	None	0	0.1	Negative	
1	B	Classroom 2/4	Ceiling	Concrete	White	None	0	0.2	Negative	
1	B	Classroom 2/4	Ceiling	2'x4' Ceiling Tile	Not Painted	N/A	N/A	N/A	N/A	
1	B	Classroom 2/4	Floor	Floor Tile	Not Painted	N/A	N/A	N/A	N/A	
1	B	Classroom 2/4	Floor Grate	Metal	Brown	None	0	1.7	Positive	
1	B	Boy's Gym Fan Room	W1	Plaster	White	Flaking	20	0	Negative	
1	B	Boy's Gym Fan Room	Conduit	Metal	White	None	0	0.3	Negative	
1	B	Boy's Gym Fan Room	Pipe	Metal	White	None	0	16.7	Positive	

		Dates: 6/5 - 7/6/2023	Lead-Safe Certification Assessment Report						
		Inspector Name and Certificate Number: Tim Smith 057662	John Bartram High School						
		Inspection Company: BATA	2401 S 67th St, Philadelphia PA 19142						
E l e m e n t	F l o o r	On-Site Room Name	Component	Substrate Material [1]	Paint Color	Description of Paint Damage	Damage Quantity (sf) [2]	XRF Reading (mg/cm2)	XRF (positive/ negative) [3]
1	B	Boy's Gym Fan Room	Exterior Fan Unit	Metal	Silver	Flaking	36	2.8	Positive
1	B	Boy's Gym Fan Room	Interior Fan Unit	Metal	Silver	None	0	2	Positive
1	B	Boy's Gym Fan Room	Railing	Metal	Grey	Chipping	2	0.5	Negative
1	B	Boy's Gym Fan Room	Tread	Concrete	Grey	None	0	0.1	Negative
1	B	Boy's Gym Fan Room	Riser	Concrete	Grey	None	0	0.1	Negative
1	B	Boy's Gym Fan Room	Door	Metal	Brown	Chipping	2	0.3	Negative
1	B	Boy's Gym Fan Room	Doorframe	Metal	Brown	Friction	6	0.8	Positive
1	B	Boy's Gym Fan Room	Column	Concrete	White	None	0	0.3	Negative
1	B	Boy's Gym Fan Room	W2	Plaster	White	Cracking	10	0.2	Negative
1	B	Boy's Gym Fan Room	W3	Plaster	White	None	0	0.3	Negative
1	B	Boy's Gym Fan Room	Windowframe	Wood	Grey	None	0	0.2	Negative
1	B	Boy's Gym Fan Room	W4	Plaster	White	None	0	0.2	Negative
1	B	Boy's Gym Fan Room	Ceiling	Concrete	White	Cracking	8	0.1	Negative
1	B	Boy's Gym Fan Room	Floor	Concrete	Grey	None	0	0.1	Negative
1	B	Cafeteria Dry Storage Area	W1	CMU	Tan	None	0	0	Negative
1	B	Cafeteria Dry Storage Area	Door	Metal	Grey	None	0	0	Negative
1	B	Cafeteria Dry Storage Area	Doorframe	Metal	Grey	Chipping	4	0.5	Negative
1	B	Cafeteria Dry Storage Area	W2	CMU	Tan	None	0	0	Negative
1	B	Cafeteria Dry Storage Area	W3	Brick	Tan	None	0	0.2	Negative
1	B	Cafeteria Dry Storage Area	Cubby Door	Wood	Tan	None	0	0.1	Negative
1	B	Cafeteria Dry Storage Area	Pipe Insulation	Fiberglass	Tan	Cracking	15	0.1	Negative
1	B	Cafeteria Dry Storage Area	W4	Brick	Tan	Flaking	24	0.1	Negative
1	B	Cafeteria Dry Storage Area	Pipe	Metal	Tan	Flaking	12	15.5	Positive
1	B	Cafeteria Dry Storage Area	Ceiling	Concrete	Tan	Cracking	70	0.4	Negative
1	B	Cafeteria Dry Storage Area	Floor	Ceramic	Not Painted	N/A	N/A	N/A	N/A
1	B	Men's Staff Restroom	W1	CMU	Tan	None	0	0	Negative

		Dates: 6/5 - 7/6/2023	Lead-Safe Certification Assessment Report						
		Inspector Name and Certificate Number: Tim Smith 057662	John Bartram High School						
		Inspection Company: BATA	2401 S 67th St, Philadelphia PA 19142						
E l e m e n t	F l o o r	On-Site Room Name	Component	Substrate Material [1]	Paint Color	Description of Paint Damage	Damage Quantity (sf) [2]	XRF Reading (mg/cm2)	XRF (positive/ negative) [3]
1	B	Men's Staff Restroom	Door	Metal	Grey	None	0	0.1	Negative
1	B	Men's Staff Restroom	Doorframe	Metal	Grey	Chipping	3	0.3	Negative
1	B	Men's Staff Restroom	W2	CMU	Tan	None	0	0.3	Negative
1	B	Men's Staff Restroom	W3	CMU	Tan	Flaking	4	0.6	Negative
1	B	Men's Staff Restroom	W4	CMU	Tan	None	0	0.1	Negative
1	B	Men's Staff Restroom	Ceiling	Concrete	Not Painted	N/A	N/A	N/A	N/A
1	B	Men's Staff Restroom	Floor	Ceramic	Not Painted	N/A	N/A	N/A	N/A
1	B	Women's Staff Restroom	W1	CMU	Tan	None	0	0	Negative
1	B	Women's Staff Restroom	Door	Metal	Grey	None	0	0	Negative
1	B	Women's Staff Restroom	Doorframe	Metal	Grey	None	0	0.4	Negative
1	B	Women's Staff Restroom	W2	CMU	Tan	None	0	0.1	Negative
1	B	Women's Staff Restroom	W3	CMU	Tan	None	0	0.1	Negative
1	B	Women's Staff Restroom	W4	CMU	Tan	None	0	0.2	Negative
1	B	Women's Staff Restroom	Ceiling	Concrete	Not Painted	N/A	N/A	N/A	N/A
1	B	Women's Staff Restroom	Floor	Ceramic	Not Painted	N/A	N/A	N/A	N/A
1	B	Cafeteria Kitchen	W1	CMU	Tan	None	0	0	Negative
1	B	Cafeteria Kitchen	W1	Drywall	Tan	None	0	0	Negative
1	B	Cafeteria Kitchen	Door	Metal	Grey	Friction	2	0.1	Negative
1	B	Cafeteria Kitchen	Doorframe	Metal	Grey	Friction	4	0.2	Negative
1	B	Cafeteria Kitchen	W2	CMU	Tan	None	0	0.1	Negative
1	B	Cafeteria Kitchen	W3	CMU	Tan	None	0	0.1	Negative
1	B	Cafeteria Kitchen	Pipe Insulation	Fiberglass	Tan	Cracking	20	0.2	Negative
1	B	Cafeteria Kitchen	Railing	Metal	Brown	Friction	35	0	Negative
1	B	Cafeteria Kitchen	W4	CMU	Tan	None	0	0.1	Negative
1	B	Cafeteria Kitchen	Conduit	Metal	Tan	None	0	0.5	Negative
1	B	Cafeteria Kitchen	Ceiling	Concrete	Not Painted	N/A	N/A	N/A	N/A

		Dates: 6/5 - 7/6/2023	Lead-Safe Certification Assessment Report						
		Inspector Name and Certificate Number: Tim Smith 057662	John Bartram High School						
		Inspection Company: BATA	2401 S 67th St, Philadelphia PA 19142						
E l e m e n t	F l o o r	On-Site Room Name	Component	Substrate Material [1]	Paint Color	Description of Paint Damage	Damage Quantity (sf) [2]	XRF Reading (mg/cm ²)	XRF (positive/ negative) [3]
1	B	Cafeteria Kitchen	Floor	Ceramic	Not Painted	N/A	N/A	N/A	N/A
1	B	Kitchen Office	W1	CMU	Tan	None	0	0.3	Negative
1	B	Kitchen Office	Door	Metal	Grey	None	0	0	Negative
1	B	Kitchen Office	Doorframe	Metal	Grey	Chipping	2	0	Negative
1	B	Kitchen Office	W2	CMU	Tan	None	0	0.3	Negative
1	B	Kitchen Office	W3	CMU	Tan	None	0	0.1	Negative
1	B	Kitchen Office	W4	CMU	Tan	None	0	0	Negative
1	B	Kitchen Office	Ceiling	Concrete	Not Painted	N/A	N/A	N/A	N/A
1	B	Kitchen Office	Floor	Ceramic	Not Painted	N/A	N/A	N/A	N/A
1	B	Custodial Closet next to Kitchen Office	W1	CMU	Tan	None	0	0	Negative
1	B	Custodial Closet next to Kitchen Office	Door	Metal	Grey	None	0	0	Negative
1	B	Custodial Closet next to Kitchen Office	Doorframe	Metal	Grey	None	0	0.4	Negative
1	B	Custodial Closet next to Kitchen Office	W2	CMU	Tan	None	0	0.1	Negative
1	B	Custodial Closet next to Kitchen Office	W3	CMU	Tan	None	0	0.2	Negative
1	B	Custodial Closet next to Kitchen Office	W4	CMU	Tan	Flaking	4	0.1	Negative
1	B	Custodial Closet next to Kitchen Office	Windowframe	Wood	Grey	None	0	0.2	Negative
1	B	Custodial Closet next to Kitchen Office	Ceiling	Concrete	Not Painted	N/A	N/A	N/A	N/A
1	B	Custodial Closet next to Kitchen Office	Ceiling	2'x4' Ceiling Tile	Not Painted	N/A	N/A	N/A	N/A
1	B	Custodial Closet next to Kitchen Office	Floor	Ceramic	Not Painted	N/A	N/A	N/A	N/A
1	B	Cafeteria	W1	CMU	Tan	None	0	0.5	Negative
1	B	Cafeteria	Mural Wall	CMU	Multi-Color	None	0	0	Negative
1	B	Cafeteria	Conduit	Plastic	Tan	None	0	0.2	Negative
1	B	Cafeteria	Doorframe	Metal	Red	Chipping	3	0.1	Negative
1	B	Cafeteria	Door	Metal	Red	Chipping	6	0	Negative
1	B	Cafeteria	W2	CMU	Tan	None	0	0.1	Negative
1	B	Cafeteria	Covebase	Rubber	Brown	None	0	0	Negative

		Dates: 6/5 - 7/6/2023	Lead-Safe Certification Assessment Report							
		Inspector Name and Certificate Number: Tim Smith 057662	John Bartram High School							
		Inspection Company: BATA	2401 S 67th St, Philadelphia PA 19142							
E l e m e n t	F l o o r	On-Site Room Name	Component	Substrate Material [1]	Paint Color	Description of Paint Damage	Damage Quantity (sf) [2]	XRF Reading (mg/cm2)	XRF (positive/ negative) [3]	
1	B	Cafeteria	Column	CMU	Pink	Chipping	40	0	Negative	
1	B	Cafeteria	W3	CMU	Tan	Flaking	3	0.3	Negative	
1	B	Cafeteria	W4	CMU	Tan	None	0	0	Negative	
1	B	Cafeteria	Pipe	Metal	Tan	None	0	0.2	Negative	
1	B	Cafeteria	Ceiling	Concrete	Not Painted	N/A	N/A	N/A	N/A	
1	B	Cafeteria	Ceiling	2'x4' Ceiling Tile	Not Painted	N/A	N/A	N/A	N/A	
1	B	Cafeteria	Floor	Floor Tile	Not Painted	N/A	N/A	N/A	N/A	
1	B	Boy's Restroom near Cafeteria	W1	CMU	Tan	None	0	0.1	Negative	
1	B	Boy's Restroom near Cafeteria	Door	Metal	Red	None	0	0.1	Negative	
1	B	Boy's Restroom near Cafeteria	Doorframe	Metal	Red	None	0	0.4	Negative	
1	B	Boy's Restroom near Cafeteria	W2	CMU	Tan	None	0	0	Negative	
1	B	Boy's Restroom near Cafeteria	W3	CMU	Tan	None	0	0	Negative	
1	B	Boy's Restroom near Cafeteria	Radiator cover	Metal	Tan	Chipping	2	0	Negative	
1	B	Boy's Restroom near Cafeteria	W4	CMU	Tan	None	0	0	Negative	
1	B	Boy's Restroom near Cafeteria	Windowframe	Metal	Tan	None	0	0.3	Negative	
1	B	Boy's Restroom near Cafeteria	Covebase	Rubber	Tan	None	0	0.1	Negative	
1	B	Boy's Restroom near Cafeteria	Ceiling	Drywall	Tan	None	0	0.1	Negative	
1	B	Boy's Restroom near Cafeteria	Floor	Concrete	Grey	Chipping	60	0.1	Negative	
1	B	Girl's Restroom near Cafeteria	W1	CMU	Tan	None	0	0	Negative	
1	B	Girl's Restroom near Cafeteria	Covebase	Rubber	Tan	None	0	0.2	Negative	
1	B	Girl's Restroom near Cafeteria	Door	Metal	Red	Chipping	2	0	Negative	
1	B	Girl's Restroom near Cafeteria	Doorframe	Metal	Red	Chipping	2	0.4	Negative	
1	B	Girl's Restroom near Cafeteria	W2	CMU	Tan	None	0	0	Negative	
1	B	Girl's Restroom near Cafeteria	W3	Plaster	Tan	None	0	0.1	Negative	
1	B	Girl's Restroom near Cafeteria	W4	CMU	Tan	None	0	0	Negative	
1	B	Girl's Restroom near Cafeteria	Radiator cover	Metal	Tan	None	0	0	Negative	

		Dates: 6/5 - 7/6/2023	Lead-Safe Certification Assessment Report						
		Inspector Name and Certificate Number: Tim Smith 057662	John Bartram High School						
		Inspection Company: BATA	2401 S 67th St, Philadelphia PA 19142						
Element	Floor	On-Site Room Name	Component	Substrate Material [1]	Paint Color	Description of Paint Damage	Damage Quantity (sf) [2]	XRF Reading (mg/cm ²)	XRF (positive/negative) [3]
1	B	Girl's Restroom near Cafeteria	Stall	Composite	Tan	Flaking	14	0.2	Negative
1	B	Girl's Restroom near Cafeteria	Ceiling	Drywall	Tan	None	0	0.2	Negative
1	B	Girl's Restroom near Cafeteria	Floor	Concrete	Grey	Chipping	130	0.1	Negative
1	B	Nurse's Office/Health Suite	W1	Drywall	Tan	Flaking	6	0.1	Negative
1	B	Nurse's Office/Health Suite	W1	CMU	Tan	None	0	0.1	Negative
1	B	Nurse's Office/Health Suite	Door	Metal	Grey	Friction	1	0	Negative
1	B	Nurse's Office/Health Suite	Doorframe	Metal	Grey	None	0	0.1	Negative
1	B	Nurse's Office/Health Suite	W2	Drywall	Tan	None	0	0.1	Negative
1	B	Nurse's Office/Health Suite	W3	CMU	Tan	None	0	0.1	Negative
1	B	Nurse's Office/Health Suite	W3	Plaster	Tan	Flaking	16	0	Negative
1	B	Nurse's Office/Health Suite	Conduit	Metal	Tan	None	0	0.5	Negative
1	B	Nurse's Office/Health Suite	W4	Drywall	Tan	Flaking	2	0.1	Negative
1	B	Nurse's Office/Health Suite	Ceiling	Concrete	Not Painted	N/A	N/A	N/A	N/A
1	B	Nurse's Office/Health Suite	Ceiling	2'x4' Ceiling Tile	Not Painted	N/A	N/A	N/A	N/A
1	B	Nurse's Office/Health Suite	Floor	Floor Tile	Not Painted	N/A	N/A	N/A	N/A
1	B	Telecommunications Room adjacent to the Cafeteria	W1	Plaster	Tan	None	0	0.4	Negative
1	B	Telecommunications Room adjacent to the Cafeteria	Doorframe	Metal	Tan	Friction	6	0.7	Positive
1	B	Telecommunications Room adjacent to the Cafeteria	Conduit	Metal	Tan	None	0	0	Negative
1	B	Telecommunications Room adjacent to the Cafeteria	W2	Plaster	Tan	None	0	0.2	Negative
1	B	Telecommunications Room adjacent to the Cafeteria	Windowframe	Metal	Brown	None	0	0.7	Positive
1	B	Telecommunications Room adjacent to the Cafeteria	Covebase	Concrete	Grey	Flaking	30	0.2	Negative
1	B	Telecommunications Room adjacent to the Cafeteria	W3	Plaster	Tan	None	0	0.2	Negative
1	B	Telecommunications Room adjacent to the Cafeteria	W4	Plaster	Tan	None	0	0.2	Negative
1	B	Telecommunications Room adjacent to the Cafeteria	Ceiling	Plaster	Tan	Cracking	10	0.4	Negative
1	B	Telecommunications Room adjacent to the Cafeteria	Ceiling	2'x4' Ceiling Tile	Not Painted	N/A	N/A	N/A	N/A
1	B	Telecommunications Room adjacent to the Cafeteria	Floor	Concrete	Grey	Friction	80	0.2	Negative

		Dates: 6/5 - 7/6/2023	Lead-Safe Certification Assessment Report						
		Inspector Name and Certificate Number: Tim Smith 057662	John Bartram High School						
		Inspection Company: BATA	2401 S 67th St, Philadelphia PA 19142						
E l e m e n t	F l o o r	On-Site Room Name	Component	Substrate Material [1]	Paint Color	Description of Paint Damage	Damage Quantity (sf) [2]	XRF Reading (mg/cm ²)	XRF (positive/ negative) [3]
1	B	Narrow Hallway next to Stairwell A to Chiller Room	W1	Plaster	Tan	Cracking	14	0.2	Negative
1	B	Narrow Hallway next to Stairwell A to Chiller Room	Doorframe	Metal	Tan	Flaking	14	0.8	Positive
1	B	Narrow Hallway next to Stairwell A to Chiller Room	W2	Plaster	Tan	Flaking	30	0.3	Negative
1	B	Narrow Hallway next to Stairwell A to Chiller Room	W3	Plaster	Tan	None	0	0.3	Negative
1	B	Narrow Hallway next to Stairwell A to Chiller Room	W4	Plaster	Tan	None	0	0.3	Negative
1	B	Narrow Hallway next to Stairwell A to Chiller Room	Covebase	Concrete	Grey	Chipping	20	0	Negative
1	B	Narrow Hallway next to Stairwell A to Chiller Room	Ceiling	Plaster	Tan	Flaking	20	0.3	Negative
1	B	Narrow Hallway next to Stairwell A to Chiller Room	Ceiling	2'x4' Ceiling Tile	Not Painted	N/A	N/A	N/A	N/A
1	B	Narrow Hallway next to Stairwell A to Chiller Room	Floor	Concrete	Grey	None	0	0.1	Negative
1	B	Chiller Room next to Stairwell A	W1	Terracotta	Blue	Flaking	20	0.1	Negative
1	B	Chiller Room next to Stairwell A	Doorframe	Metal	Brown	Flaking	8	1.1	Positive
1	B	Chiller Room next to Stairwell A	Windowframe	Metal	Brown	Flaking	4	0.5	Negative
1	B	Chiller Room next to Stairwell A	Windowframe	Wood	Grey	Cracking	8	1.3	Positive
1	B	Chiller Room next to Stairwell A	W2	Terracotta	Blue	Chipping	10	0.2	Negative
1	B	Chiller Room next to Stairwell A	Covebase	Concrete	Grey	Flaking	14	0	Negative
1	B	Chiller Room next to Stairwell A	W3	Terracotta	Blue	Flaking	100	0	Negative
1	B	Chiller Room next to Stairwell A	W4	Terracotta	Blue	Flaking	100	0	Negative
1	B	Chiller Room next to Stairwell A	Ceiling	Concrete	White	None	0	0.3	Negative
1	B	Chiller Room next to Stairwell A	Floor	Concrete	Not Painted	N/A	N/A	N/A	N/A
1	B	Classroom C-5	W1	Terracotta	White	Flaking	4	6	Positive
1	B	Classroom C-5	Door	Wood	Black	Friction	2	0	Negative
1	B	Classroom C-5	Doorframe	Metal	Brown	None	0	0.6	Negative
1	B	Classroom C-5	Closet Door	Wood	Brown	Chipping	2	0.1	Negative
1	B	Classroom C-5	Closet Doorframe	Wood	Brown	None	0	0.1	Negative
1	B	Classroom C-5	Conduit	Metal	White	None	0	0.5	Negative
1	B	Classroom C-5	W2	Terracotta	White	None	0	0.6	Negative

		Dates: 6/5 - 7/6/2023	Lead-Safe Certification Assessment Report						
		Inspector Name and Certificate Number: Tim Smith 057662	John Bartram High School						
		Inspection Company: BATA	2401 S 67th St, Philadelphia PA 19142						
E l e m e n t	F l o o r	On-Site Room Name	Component	Substrate Material [1]	Paint Color	Description of Paint Damage	Damage Quantity (sf) [2]	XRF Reading (mg/cm2)	XRF (positive/ negative) [3]
1	B	Classroom C-5	Conduit	Plastic	White	None	0	1.7	Positive
1	B	Classroom C-5	Covebase	Concrete	Brown	None	0	1.7	Positive
1	B	Classroom C-5	W3	Brick	White	Cracking	6	0.1	Negative
1	B	Classroom C-5	W3	Terracotta	White	Flaking	12	0.2	Negative
1	B	Classroom C-5	Pipe Cover	Metal	White	None	0	4.7	Positive
1	B	Classroom C-5	Windowframe	Wood	Brown	Cracking	16	0.2	Negative
1	B	Classroom C-5	Radiator cover	Metal	Brown	Flaking	2	0	Negative
1	B	Classroom C-5	Pipe Insulation	Asbestos	White	None	0	0.2	Negative
1	B	Classroom C-5	W4	Drywall	White	None	0	0	Negative
1	B	Classroom C-5	Ceiling	Concrete	White	None	0	0.4	Negative
1	B	Classroom C-5	Ceiling	2'x4' Ceiling Tile	Not Painted	N/A	N/A	N/A	N/A
1	B	Classroom C-5	Grate	Metal	Brown	None	0	2.1	Positive
1	B	Classroom C-5	Floor	Floor Tile	Not Painted	N/A	N/A	N/A	N/A
1	B	Storage Room inside Classroom C-5 - Exterior Wall Side	W1	Terracotta	White	None	0	0	Negative
1	B	Storage Room inside Classroom C-5 - Exterior Wall Side	Doorframe	Metal	Brown	Chipping	2	0.3	Negative
1	B	Storage Room inside Classroom C-5 - Exterior Wall Side	Pipe Cover	Metal	White	None	0	0.4	Negative
1	B	Storage Room inside Classroom C-5 - Exterior Wall Side	Conduit	Metal	White	None	0	0.5	Negative
1	B	Storage Room inside Classroom C-5 - Exterior Wall Side	W2	CMU	White	None	0	0	Negative
1	B	Storage Room inside Classroom C-5 - Exterior Wall Side	W3	CMU	White	None	0	0.1	Negative
1	B	Storage Room inside Classroom C-5 - Exterior Wall Side	W4	CMU	White	None	0	0.3	Negative

		Dates: 6/5 - 7/6/2023	Lead-Safe Certification Assessment Report						
		Inspector Name and Certificate Number: Tim Smith 057662	John Bartram High School						
		Inspection Company: BATA	2401 S 67th St, Philadelphia PA 19142						
E l e m e n t	F l o o r	On-Site Room Name	Component	Substrate Material [1]	Paint Color	Description of Paint Damage	Damage Quantity (sf) [2]	XRF Reading (mg/cm2)	XRF (positive/ negative) [3]
1	B	Storage Room inside Classroom C-5 - Exterior Wall Side	Covebase	Concrete	Brown	None	0	0.1	Negative
1	B	Storage Room inside Classroom C-5 - Exterior Wall Side	Radiator cover	Metal	Brown	None	0	0	Negative
1	B	Storage Room inside Classroom C-5 - Exterior Wall Side	Ceiling	Concrete	White	None	0	0.3	Negative
1	B	Storage Room inside Classroom C-5 - Exterior Wall Side	Floor	Floor Tile	Not Painted	N/A	N/A	N/A	N/A
1	B	Storage Room inside Classroom C-5 - Hallway Wall Side	W1	No Access	No Access	No Access	No Access	No Access	No Access
1	B	Storage Room inside Classroom C-5 - Hallway Wall Side	Doorframe	Metal	Brown	None	0	0.4	Negative
1	B	Storage Room inside Classroom C-5 - Hallway Wall Side	W2	No Access	No Access	No Access	No Access	No Access	No Access
1	B	Storage Room inside Classroom C-5 - Hallway Wall Side	W3	No Access	No Access	No Access	No Access	No Access	No Access
1	B	Storage Room inside Classroom C-5 - Hallway Wall Side	W4	No Access	No Access	No Access	No Access	No Access	No Access
1	B	Storage Room inside Classroom C-5 - Hallway Wall Side	Ceiling	No Access	No Access	No Access	No Access	No Access	No Access
1	B	Storage Room inside Classroom C-5 - Hallway Wall Side	Floor	No Access	No Access	No Access	No Access	No Access	No Access
1	B	Girl's Restroom across from Classroom C7 (C Wing)	W1	Terracotta	White	None	0	0.2	Negative
1	B	Girl's Restroom across from Classroom C7 (C Wing)	Door	Wood	White	Chipping	4	0	Negative
1	B	Girl's Restroom across from Classroom C7 (C Wing)	Doorframe	Metal	Brown	Chipping	1	0.6	Negative
1	B	Girl's Restroom across from Classroom C7 (C Wing)	W2	Drywall	White	None	0	0.2	Negative
1	B	Girl's Restroom across from Classroom C7 (C Wing)	W3	Terracotta	White	None	0	0	Negative
1	B	Girl's Restroom across from Classroom C7 (C Wing)	Pipe Cover	Metal	White	None	0	1.5	Positive
1	B	Girl's Restroom across from Classroom C7 (C Wing)	Pipe Insulation	Asbestos	White	None	0	0	Negative

		Dates: 6/5 - 7/6/2023	Lead-Safe Certification Assessment Report						
		Inspector Name and Certificate Number: Tim Smith 057662	John Bartram High School						
		Inspection Company: BATA	2401 S 67th St, Philadelphia PA 19142						
E l e m e n t	F l o o r	On-Site Room Name	Component	Substrate Material [1]	Paint Color	Description of Paint Damage	Damage Quantity (sf) [2]	XRF Reading (mg/cm ²)	XRF (positive/ negative) [3]
1	B	Girl's Restroom across from Classroom C7 (C Wing)	Radiator cover	Metal	Brown	None	0	0.1	Negative
1	B	Girl's Restroom across from Classroom C7 (C Wing)	Radiator	Metal	Silver	None	0	0	Negative
1	B	Girl's Restroom across from Classroom C7 (C Wing)	W4	CMU	White	None	0	0	Negative
1	B	Girl's Restroom across from Classroom C7 (C Wing)	Ceiling	Concrete	White	None	0	0.1	Negative
1	B	Girl's Restroom across from Classroom C7 (C Wing)	Grate	Metal	Brown	None	0	15.7	Positive
1	B	Girl's Restroom across from Classroom C7 (C Wing)	Floor	Floor Tile	Not Painted	N/A	N/A	N/A	N/A
1	B	Pipe Chase in Girls Restroom across from Classroom C7 (C Wing)	W1	CMU	Not Painted	N/A	N/A	N/A	N/A
1	B	Pipe Chase in Girls Restroom across from Classroom C7 (C Wing)	W2	CMU	Not Painted	N/A	N/A	N/A	N/A
1	B	Pipe Chase in Girls Restroom across from Classroom C7 (C Wing)	W3	CMU	Not Painted	N/A	N/A	N/A	N/A
1	B	Pipe Chase in Girls Restroom across from Classroom C7 (C Wing)	W4	Terracotta	White	Flaking	12	0	Negative
1	B	Pipe Chase in Girls Restroom across from Classroom C7 (C Wing)	Ceiling	Concrete	Not Painted	N/A	N/A	N/A	N/A
1	B	Pipe Chase in Girls Restroom across from Classroom C7 (C Wing)	Floor	Concrete	Not Painted	N/A	N/A	N/A	N/A
1	B	Boy's Restroom across from Classroom C7 (C Wing)	W1	Ceramic	White	None	0	0.1	Negative
1	B	Boy's Restroom across from Classroom C7 (C Wing)	Doorframe	Metal	Brown	None	0	0.7	Positive
1	B	Boy's Restroom across from Classroom C7 (C Wing)	W2	Ceramic	White	None	0	0.1	Negative
1	B	Boy's Restroom across from Classroom C7 (C Wing)	W3	Ceramic	White	None	0	0.2	Negative
1	B	Boy's Restroom across from Classroom C7 (C Wing)	Pipe Cover	Metal	White	None	0	0.4	Negative
1	B	Boy's Restroom across from Classroom C7 (C Wing)	Pipe Insulation	Asbestos	White	None	0	0.1	Negative
1	B	Boy's Restroom across from Classroom C7 (C Wing)	Pipe	Metal	White	None	0	0.1	Negative
1	B	Boy's Restroom across from Classroom C7 (C Wing)	Radiator cover	Metal	Brown	None	0	0	Negative
1	B	Boy's Restroom across from Classroom C7 (C Wing)	W4	Ceramic	White	None	0	0	Negative
1	B	Boy's Restroom across from Classroom C7 (C Wing)	Ceiling	Plaster	White	None	0	0.3	Negative

		Dates: 6/5 - 7/6/2023	Lead-Safe Certification Assessment Report						
		Inspector Name and Certificate Number: Tim Smith 057662	John Bartram High School						
		Inspection Company: BATA	2401 S 67th St, Philadelphia PA 19142						
Element	Floor	On-Site Room Name	Component	Substrate Material [1]	Paint Color	Description of Paint Damage	Damage Quantity (sf) [2]	XRF Reading (mg/cm2)	XRF (positive/negative) [3]
1	B	Boy's Restroom across from Classroom C7 (C Wing)	Floor	Terrazzo	Not Painted	N/A	N/A	N/A	N/A
1	B	Pipe Chase in Boy's Restroom across from Classroom C7 (C Wing)	W1	Concrete	Not Painted	N/A	N/A	N/A	N/A
1	B	Pipe Chase in Boy's Restroom across from Classroom C7 (C Wing)	Door	Wood	Brown	Cracking	3	0.1	Negative
1	B	Pipe Chase in Boy's Restroom across from Classroom C7 (C Wing)	Doorframe	Metal	Brown	None	0	0.9	Positive
1	B	Pipe Chase in Boy's Restroom across from Classroom C7 (C Wing)	W2	Concrete	Not Painted	N/A	N/A	N/A	N/A
1	B	Pipe Chase in Boy's Restroom across from Classroom C7 (C Wing)	W3	Concrete	Not Painted	N/A	N/A	N/A	N/A
1	B	Pipe Chase in Boy's Restroom across from Classroom C7 (C Wing)	W4	Concrete	Not Painted	N/A	N/A	N/A	N/A
1	B	Pipe Chase in Boy's Restroom across from Classroom C7 (C Wing)	Ceiling	Concrete	Not Painted	N/A	N/A	N/A	N/A
1	B	Pipe Chase in Boy's Restroom across from Classroom C7 (C Wing)	Floor	Concrete	Not Painted	N/A	N/A	N/A	N/A
1	B	Storage Room with Slop Sink next to Boys Restroom across from Classroom C7 (C Wing)	W1	Plaster	White	None	0	0.1	Negative
1	B	Storage Room with Slop Sink next to Boys Restroom across from Classroom C7 (C Wing)	Doorframe	Metal	Brown	Chipping	4	0.7	Positive
1	B	Storage Room with Slop Sink next to Boys Restroom across from Classroom C7 (C Wing)	W2	Plaster	White	None	0	0.3	Negative
1	B	Storage Room with Slop Sink next to Boys Restroom across from Classroom C7 (C Wing)	W3	Plaster	White	None	0	0.3	Negative
1	B	Storage Room with Slop Sink next to Boys Restroom across from Classroom C7 (C Wing)	W4	Plaster	White	Flaking	2	0	Negative
1	B	Storage Room with Slop Sink next to Boys Restroom across from Classroom C7 (C Wing)	Sink	Ceramic	Grey	Chipping	5	32	Positive
1	B	Storage Room with Slop Sink next to Boys Restroom across from Classroom C7 (C Wing)	Covebase	Concrete	Brown	None	0	0	Negative

		Dates: 6/5 - 7/6/2023	Lead-Safe Certification Assessment Report						
		Inspector Name and Certificate Number: Tim Smith 057662	John Bartram High School						
		Inspection Company: BATA	2401 S 67th St, Philadelphia PA 19142						
E l e m e n t	F l o o r	On-Site Room Name	Component	Substrate Material [1]	Paint Color	Description of Paint Damage	Damage Quantity (sf) [2]	XRF Reading (mg/cm2)	XRF (positive/ negative) [3]
1	B	Storage Room with Slop Sink next to Boys Restroom across from Classroom C7 (C Wing)	Ceiling	Plaster	White	None	0	0.4	Negative
1	B	Storage Room with Slop Sink next to Boys Restroom across from Classroom C7 (C Wing)	Floor	Concrete	Brown	Friction	8	0.2	Negative
1	B	Storage Room next to Staff Restroom across from Classroom C7 (C Wing)	W1	Terracotta	White	None	0	0.2	Negative
1	B	Storage Room next to Staff Restroom across from Classroom C7 (C Wing)	Doorframe	Metal	Brown	None	0	0.6	Negative
1	B	Storage Room next to Staff Restroom across from Classroom C7 (C Wing)	W2	Terracotta	White	None	0	0.2	Negative
1	B	Storage Room next to Staff Restroom across from Classroom C7 (C Wing)	W3	CMU	White	None	0	0.2	Negative
1	B	Storage Room next to Staff Restroom across from Classroom C7 (C Wing)	Covebase	Concrete	Brown	None	0	0.2	Negative
1	B	Storage Room next to Staff Restroom across from Classroom C7 (C Wing)	W4	Terracotta	White	None	0	0.1	Negative
1	B	Storage Room next to Staff Restroom across from Classroom C7 (C Wing)	Ceiling	Concrete	White	None	0	0.3	Negative
1	B	Storage Room next to Staff Restroom across from Classroom C7 (C Wing)	Duct	Metal	White	None	0	0.4	Negative
1	B	Storage Room next to Staff Restroom across from Classroom C7 (C Wing)	Pipe Insulation	Asbestos	White	None	0	0.2	Negative
1	B	Storage Room next to Staff Restroom across from Classroom C7 (C Wing)	Floor	Concrete	Not Painted	N/A	N/A	N/A	N/A
1	B	Pipe Chase in Storage Room next to Staff Restroom across from Classroom C7 (C Wing)	W1	Concrete	Not Painted	N/A	N/A	N/A	N/A
1	B	Pipe Chase in Storage Room next to Staff Restroom across from Classroom C7 (C Wing)	Door	Wood	Brown	None	0	0.1	Negative
1	B	Pipe Chase in Storage Room next to Staff Restroom across from Classroom C7 (C Wing)	Doorframe	Metal	Brown	Chipping	1	1.8	Positive

		Dates: 6/5 - 7/6/2023	Lead-Safe Certification Assessment Report						
		Inspector Name and Certificate Number: Tim Smith 057662	John Bartram High School						
		Inspection Company: BATA	2401 S 67th St, Philadelphia PA 19142						
Element	Floor	On-Site Room Name	Component	Substrate Material [1]	Paint Color	Description of Paint Damage	Damage Quantity (sf) [2]	XRF Reading (mg/cm ²)	XRF (positive/negative) [3]
1	B	Pipe Chase in Storage Room next to Staff Restroom across from Classroom C7 (C Wing)	W2	Concrete	Not Painted	N/A	N/A	N/A	N/A
1	B	Pipe Chase in Storage Room next to Staff Restroom across from Classroom C7 (C Wing)	W3	Concrete	Not Painted	N/A	N/A	N/A	N/A
1	B	Pipe Chase in Storage Room next to Staff Restroom across from Classroom C7 (C Wing)	W4	Concrete	Not Painted	N/A	N/A	N/A	N/A
1	B	Pipe Chase in Storage Room next to Staff Restroom across from Classroom C7 (C Wing)	Ceiling	Concrete	Not Painted	N/A	N/A	N/A	N/A
1	B	Pipe Chase in Storage Room next to Staff Restroom across from Classroom C7 (C Wing)	Floor	Concrete	Not Painted	N/A	N/A	N/A	N/A
1	B	Staff Restroom near stairwell (C Wing)	W1	Plaster	White	None	0	0.2	Negative
1	B	Staff Restroom near stairwell (C Wing)	Doorframe	Metal	Brown	Friction	1	0.7	Positive
1	B	Staff Restroom near stairwell (C Wing)	W2	Plaster	White	Flaking	2	0.1	Negative
1	B	Staff Restroom near stairwell (C Wing)	W3	Plaster	White	None	0	0.1	Negative
1	B	Staff Restroom near stairwell (C Wing)	Covebase	Concrete	Brown	None	0	0	Negative
1	B	Staff Restroom near stairwell (C Wing)	W4	Plaster	White	None	0	0.2	Negative
1	B	Staff Restroom near stairwell (C Wing)	Pipe	Metal	Brown	None	0	0.2	Negative
1	B	Staff Restroom near stairwell (C Wing)	Ceiling	Plaster	White	None	0	0.3	Negative
1	B	Staff Restroom near stairwell (C Wing)	Floor	Floor Tile	Not Painted	N/A	N/A	N/A	N/A
1	B	Classroom C-7	W1	Terracotta	White	None	0	0.2	Negative
1	B	Classroom C-7	W1	CMU	White	None	0	0.2	Negative
1	B	Classroom C-7	Doorframe	Metal	Brown	None	0	0.5	Negative
1	B	Classroom C-7	W2	Terracotta	White	Flaking	4	2.6	Positive
1	B	Classroom C-7	W3	Terracotta	White	Flaking	20	3	Positive
1	B	Classroom C-7	Pipe Cover	Metal	Tan	Flaking	8	3.5	Positive
1	B	Classroom C-7	Pipe Insulation	Asbestos	Tan	None	0	0.1	Negative
1	B	Classroom C-7	Windowframe	Wood	Brown	Cracking	24	2.6	Positive

		Dates: 6/5 - 7/6/2023	Lead-Safe Certification Assessment Report							
		Inspector Name and Certificate Number: Tim Smith 057662	John Bartram High School							
		Inspection Company: BATA	2401 S 67th St, Philadelphia PA 19142							
Element	Floor	On-Site Room Name	Component	Substrate Material [1]	Paint Color	Description of Paint Damage	Damage Quantity (sf) [2]	XRF Reading (mg/cm2)	XRF (positive/negative) [3]	
1	B	Classroom C-7	W4	CMU	White	None	0	0.1	Negative	
1	B	Classroom C-7	Covebase	Terracotta	Brown	Chipping	30	0.1	Negative	
1	B	Classroom C-7	Ceiling	No Access	No Access	No Access	No Access	No Access	No Access	
1	B	Classroom C-7	Floor	Floor Tile	Not Painted	N/A	N/A	N/A	N/A	
1	B	Custodial Storage across from Girl's Locker Room	W1	Plaster	White	None	0	0.2	Negative	
1	B	Custodial Storage across from Girl's Locker Room	Doorframe	Metal	Brown	Friction	1	0.7	Positive	
1	B	Custodial Storage across from Girl's Locker Room	W2	Plaster	White	Flaking	2	0.1	Negative	
1	B	Custodial Storage across from Girl's Locker Room	W3	Plaster	White	None	0	0.1	Negative	
1	B	Custodial Storage across from Girl's Locker Room	Covebase	Concrete	Brown	None	0	0	Negative	
1	B	Custodial Storage across from Girl's Locker Room	W4	Plaster	White	None	0	0.2	Negative	
1	B	Custodial Storage across from Girl's Locker Room	Pipe	Metal	Brown	None	0	0.2	Negative	
1	B	Custodial Storage across from Girl's Locker Room	Ceiling	Plaster	White	None	0	0.3	Negative	
1	B	Custodial Storage across from Girl's Locker Room	Floor	Floor Tile	Not Painted	N/A	N/A	N/A	N/A	
1	B	Classroom C-8	W1	1'x1' Ceiling Tile	Grey	None	0	0.3	Negative	
1	B	Classroom C-8	Doorframe	Metal	Red	None	0	0.6	Negative	
1	B	Classroom C-8	Pipe	Metal	Grey	None	0	0.1	Negative	
1	B	Classroom C-8	W2	CMU	Grey	None	0	0	Negative	
1	B	Classroom C-8	W2	1'x1' Ceiling Tile	Grey	None	0	0.2	Negative	
1	B	Classroom C-8	W3	1'x1' Ceiling Tile	Grey	None	0	0.1	Negative	
1	B	Classroom C-8	Pipe Cover	Metal	Red	None	0	0.4	Negative	
1	B	Classroom C-8	Pipe Insulation	Asbestos	Grey	None	0	0.1	Negative	
1	B	Classroom C-8	W4	1'x1' Ceiling Tile	Grey	None	0	0.2	Negative	
1	B	Classroom C-8	Covebase	Concrete	Red	None	0	0.2	Negative	
1	B	Classroom C-8	Ceiling	1'x1' Ceiling Tile	White	None	0	0.2	Negative	
1	B	Classroom C-8	Floor	Floor Tile	Not Painted	N/A	N/A	N/A	N/A	
1	B	Storage Room inside Classroom C-8	W1	CMU	Grey	None	0	0.1	Negative	

		Dates: 6/5 - 7/6/2023	Lead-Safe Certification Assessment Report						
		Inspector Name and Certificate Number: Tim Smith 057662	John Bartram High School						
		Inspection Company: BATA	2401 S 67th St, Philadelphia PA 19142						
Element	Floor	On-Site Room Name	Component	Substrate Material [1]	Paint Color	Description of Paint Damage	Damage Quantity (sf) [2]	XRF Reading (mg/cm ²)	XRF (positive/negative) [3]
1	B	Storage Room inside Classroom C-8	Doorframe	Metal	Red	None	0	0.5	Negative
1	B	Storage Room inside Classroom C-8	W2	CMU	Grey	None	0	0	Negative
1	B	Storage Room inside Classroom C-8	W3	Plaster	Grey	Cracking	6	0.6	Negative
1	B	Storage Room inside Classroom C-8	W4	Plaster	Grey	Flaking	5	0.1	Negative
1	B	Storage Room inside Classroom C-8	Ceiling	Plaster	White	Flaking	10	0.3	Negative
1	B	Storage Room inside Classroom C-8	Floor	Floor Tile	Not Painted	N/A	N/A	N/A	N/A
1	B	Auditorium Fan Room	Ceiling	Concrete	White	None	0	0.3	Negative
1	B	Auditorium Fan Room	Floor	Concrete	Grey	None	0	0.3	Negative
1	B	Auditorium Fan Room	Exterior Fan Unit	Metal	Silver	Spalling	160	5.8	Positive
1	B	Auditorium Fan Room	Column	Concrete	Tan	None	0	0.2	Negative
1	B	Auditorium Fan Room	W1	Plaster	Tan	Flaking	8	0.1	Negative
1	B	Auditorium Fan Room	Doorframe	Metal	Brown	Chipping	10	2.1	Positive
1	B	Auditorium Fan Room	W2	Plaster	Tan	None	0	0.3	Negative
1	B	Auditorium Fan Room	W3	Plaster	Tan	Flaking	1	0.4	Negative
1	B	Auditorium Fan Room	W4	Plaster	Tan	Spalling	26	0.3	Negative
1	B	Auditorium Fan Room	Covebase	Concrete	Grey	Flaking	30	0	Negative
1	B	Auditorium Fan Room	Ceiling	Concrete	White	None	0	0.3	Negative
1	B	Auditorium Fan Room	Floor	Concrete	Grey	None	0	0.3	Negative
1	B	Pipe Shaft in 8A	W1	Brick	Not Painted	N/A	N/A	N/A	N/A
1	B	Pipe Shaft in 8A	W2	Brick	Not Painted	N/A	N/A	N/A	N/A
1	B	Pipe Shaft in 8A	W3	Brick	Not Painted	N/A	N/A	N/A	N/A
1	B	Pipe Shaft in 8A	W4	Brick	Not Painted	N/A	N/A	N/A	N/A
1	B	Pipe Shaft in 8A	Ceiling	No Access	No Access	No Access	No Access	No Access	No Access
1	B	Pipe Shaft in 8A	Floor	Concrete	Not Painted	N/A	N/A	N/A	N/A
1	B	Small pump room in fan room	Doorframe	Metal	Blue	None	0	10.7	Positive
1	B	Small pump room in fan room	Column	Concrete	Blue	Flaking	110	0.3	Negative

		Dates: 6/5 - 7/6/2023	Lead-Safe Certification Assessment Report						
		Inspector Name and Certificate Number: Tim Smith 057662	John Bartram High School						
		Inspection Company: BATA	2401 S 67th St, Philadelphia PA 19142						
Element	Floor	On-Site Room Name	Component	Substrate Material [1]	Paint Color	Description of Paint Damage	Damage Quantity (sf) [2]	XRF Reading (mg/cm ²)	XRF (positive/negative) [3]
1	B	Small pump room in fan room	W1	Terracotta	Blue	Flaking	20	0	Negative
1	B	Small pump room in fan room	Doorframe	Metal	Brown	Flaking	12	0.3	Negative
1	B	Small pump room in fan room	W2	Terracotta	Blue	Flaking	40	0.2	Negative
1	B	Small pump room in fan room	W3	Concrete	Blue	Flaking	110	0.3	Negative
1	B	Small pump room in fan room	W4	Terracotta	Blue	Flaking	30	0.5	Negative
1	B	Small pump room in fan room	Ceiling	Concrete	No Access	No Access	No Access	No Access	No Access
1	B	Small pump room in fan room	Floor	Concrete	Not Painted	N/A	N/A	N/A	N/A
1	B	Girl's Locker Room	W1	Ceramic	Not Painted	N/A	N/A	N/A	N/A
1	B	Girl's Locker Room	Doorframe	Metal	Brown	Friction	4	1	Positive
1	B	Girl's Locker Room	Wall Partition	Metal	Tan	Flaking	49	1.1	Positive
1	B	Girl's Locker Room	W2	Ceramic	Not Painted	N/A	N/A	N/A	N/A
1	B	Girl's Locker Room	W3	Ceramic	Not Painted	N/A	N/A	N/A	N/A
1	B	Girl's Locker Room	Radiator	Metal	Silver	Flaking	120	0.1	Negative
1	B	Girl's Locker Room	W4	Ceramic	Not Painted	N/A	N/A	N/A	N/A
1	B	Girl's Locker Room	Pipe	Metal	Tan	Flaking	10	13.8	Positive
1	B	Girl's Locker Room	Ceiling	Plaster	White	Cracking	40	0.2	Negative
1	B	Girl's Locker Room	Floor	Concrete	Not Painted	N/A	N/A	N/A	N/A
1	B	Storage Room in Girl's Locker Room along Exterior Wall	W1	Plaster	White	Flaking	1	0.1	Negative
1	B	Storage Room in Girl's Locker Room along Exterior Wall	Doorframe	Metal	Brown	Friction	4	0.8	Positive
1	B	Storage Room in Girl's Locker Room along Exterior Wall	Covebase	Concrete	Grey	None	0	0	Negative
1	B	Storage Room in Girl's Locker Room along Exterior Wall	W2	Plaster	White	None	0	0	Negative
1	B	Storage Room in Girl's Locker Room along Exterior Wall	W3	Plaster	White	Spalling	30	0	Negative

		Dates: 6/5 - 7/6/2023	Lead-Safe Certification Assessment Report						
		Inspector Name and Certificate Number: Tim Smith 057662	John Bartram High School						
		Inspection Company: BATA	2401 S 67th St, Philadelphia PA 19142						
E l e m e n t	F l o o r	On-Site Room Name	Component	Substrate Material [1]	Paint Color	Description of Paint Damage	Damage Quantity (sf) [2]	XRF Reading (mg/cm2)	XRF (positive/ negative) [3]
1	B	Storage Room in Girl's Locker Room along Exterior Wall	W4	Plaster	White	Flaking	60	0	Negative
1	B	Storage Room in Girl's Locker Room along Exterior Wall	Radiator	Metal	White	None	0	0.2	Negative
1	B	Storage Room in Girl's Locker Room along Exterior Wall	Pipe Insulation	Asbestos	White	None	0	0.2	Negative
1	B	Storage Room in Girl's Locker Room along Exterior Wall	Ceiling	Plaster	White	None	0	0.2	Negative
1	B	Storage Room in Girl's Locker Room along Exterior Wall	Floor	Concrete	Not Painted	N/A	N/A	N/A	N/A
1	B	Laundry Room inside Girl's Locker Room	W1	Ceramic	Not Painted	N/A	N/A	N/A	N/A
1	B	Laundry Room inside Girl's Locker Room	Doorframe	Metal	Brown	Friction	6	0.5	Negative
1	B	Laundry Room inside Girl's Locker Room	W2	Ceramic	Not Painted	N/A	N/A	N/A	N/A
1	B	Laundry Room inside Girl's Locker Room	W3	Ceramic	Not Painted	N/A	N/A	N/A	N/A
1	B	Laundry Room inside Girl's Locker Room	W4	Ceramic	Not Painted	N/A	N/A	N/A	N/A
1	B	Laundry Room inside Girl's Locker Room	Ceiling	Plaster	White	None	0	0.1	Negative
1	B	Laundry Room inside Girl's Locker Room	Ceiling	2'x4' Ceiling Tile	Not Painted	N/A	N/A	N/A	N/A
1	B	Laundry Room inside Girl's Locker Room	Floor	Concrete	Not Painted	N/A	N/A	N/A	N/A
1	B	Pipe Chase inside Laundry Room inside Girl's Locker Room	W1	Concrete	Not Painted	N/A	N/A	N/A	N/A
1	B	Pipe Chase inside Laundry Room inside Girl's Locker Room	Doorframe	Metal	Brown	None	0	0.8	Positive
1	B	Pipe Chase inside Laundry Room inside Girl's Locker Room	W2	Concrete	Not Painted	N/A	N/A	N/A	N/A
1	B	Pipe Chase inside Laundry Room inside Girl's Locker Room	W3	Concrete	Not Painted	N/A	N/A	N/A	N/A
1	B	Pipe Chase inside Laundry Room inside Girl's Locker Room	W4	Concrete	Not Painted	N/A	N/A	N/A	N/A

		Dates: 6/5 - 7/6/2023	Lead-Safe Certification Assessment Report						
		Inspector Name and Certificate Number: Tim Smith 057662	John Bartram High School						
		Inspection Company: BATA	2401 S 67th St, Philadelphia PA 19142						
Element	Floor	On-Site Room Name	Component	Substrate Material [1]	Paint Color	Description of Paint Damage	Damage Quantity (sf) [2]	XRF Reading (mg/cm ²)	XRF (positive/negative) [3]
1	B	Pipe Chase inside Laundry Room inside Girl's Locker Room	Ceiling	Concrete	No Access	No Access	No Access	No Access	No Access
1	B	Pipe Chase inside Laundry Room inside Girl's Locker Room	Floor	Concrete	Not Painted	N/A	N/A	N/A	N/A
1	B	Shower Room inside Girl's Locker Room	W1	Ceramic	Not Painted	N/A	N/A	N/A	N/A
1	B	Shower Room inside Girl's Locker Room	Doorframe	Metal	Brown	None	0	1.3	Positive
1	B	Shower Room inside Girl's Locker Room	Door	Metal	Brown	None	0	0.2	Negative
1	B	Shower Room inside Girl's Locker Room	W2	Concrete	White	None	0	0	Negative
1	B	Shower Room inside Girl's Locker Room	Pipe Insulation	Asbestos	White	None	0	0.2	Negative
1	B	Shower Room inside Girl's Locker Room	W3	Ceramic	Not Painted	N/A	N/A	N/A	N/A
1	B	Shower Room inside Girl's Locker Room	W4	Ceramic	Not Painted	N/A	N/A	N/A	N/A
1	B	Shower Room inside Girl's Locker Room	Ceiling	Plaster	White	None	0	0.1	Negative
1	B	Shower Room inside Girl's Locker Room	Floor	Concrete	Not Painted	N/A	N/A	N/A	N/A
1	B	Restroom inside Girl's Locker Room (next to Stairwell to 1st Floor Gym)	W1	Ceramic	Not Painted	N/A	N/A	N/A	N/A
1	B	Restroom inside Girl's Locker Room (next to Stairwell to 1st Floor Gym)	Doorframe	Metal	Brown	None	0	0.8	Positive
1	B	Restroom inside Girl's Locker Room (next to Stairwell to 1st Floor Gym)	W2	Ceramic	Not Painted	N/A	N/A	N/A	N/A
1	B	Restroom inside Girl's Locker Room (next to Stairwell to 1st Floor Gym)	W3	Ceramic	Not Painted	N/A	N/A	N/A	N/A
1	B	Restroom inside Girl's Locker Room (next to Stairwell to 1st Floor Gym)	W4	Ceramic	Not Painted	N/A	N/A	N/A	N/A
1	B	Restroom inside Girl's Locker Room (next to Stairwell to 1st Floor Gym)	Ceiling	Plaster	White	None	0	0.2	Negative
1	B	Restroom inside Girl's Locker Room (next to Stairwell to 1st Floor Gym)	Floor	Concrete	Not Painted	N/A	N/A	N/A	N/A
1	B	Storage Room in Girl's Locker Room near Stairwell	W1	Plaster	White	None	0	0.1	Negative
1	B	Storage Room in Girl's Locker Room near Stairwell	Covebase	Concrete	Grey	Chipping	8	0.2	Negative

		Dates: 6/5 - 7/6/2023	Lead-Safe Certification Assessment Report						
		Inspector Name and Certificate Number: Tim Smith 057662	John Bartram High School						
		Inspection Company: BATA	2401 S 67th St, Philadelphia PA 19142						
E l e m e n t	F l o o r	On-Site Room Name	Component	Substrate Material [1]	Paint Color	Description of Paint Damage	Damage Quantity (sf) [2]	XRF Reading (mg/cm ²)	XRF (positive/ negative) [3]
1	B	Storage Room in Girl's Locker Room near Stairwell	Doorframe	Metal	Brown	Friction	2	0.9	Positive
1	B	Storage Room in Girl's Locker Room near Stairwell	W2	Plaster	White	None	0	0.2	Negative
1	B	Storage Room in Girl's Locker Room near Stairwell	W3	Plaster	White	Cracking	6	0.2	Negative
1	B	Storage Room in Girl's Locker Room near Stairwell	W4	Plaster	White	None	0	0.1	Negative
1	B	Storage Room in Girl's Locker Room near Stairwell	Ceiling	Plaster	White	Flaking	30	0.2	Negative
1	B	Storage Room in Girl's Locker Room near Stairwell	Floor	Concrete	Grey	Friction	55	0.4	Negative
1	B	Auditorium Supply Plenum (below Auditorium)	W1	Terracotta	Not Painted	N/A	N/A	N/A	N/A
1	B	Auditorium Supply Plenum (below Auditorium)	Doorframe	Metal	Brown	Friction	6	1.5	Positive
1	B	Auditorium Supply Plenum (below Auditorium)	Door	Metal	Brown	None	0	0.1	Negative
1	B	Auditorium Supply Plenum (below Auditorium)	W2	Terracotta	Not Painted	N/A	N/A	N/A	N/A
1	B	Auditorium Supply Plenum (below Auditorium)	Railing	Metal	Grey	Chipping	12	0.1	Negative
1	B	Auditorium Supply Plenum (below Auditorium)	Riser	Concrete	Grey	Friction	8	0.4	Negative
1	B	Auditorium Supply Plenum (below Auditorium)	Tread	Concrete	Grey	Friction	28	0.2	Negative
1	B	Auditorium Supply Plenum (below Auditorium)	W3	Concrete	Not Painted	N/A	N/A	N/A	N/A
1	B	Auditorium Supply Plenum (below Auditorium)	W4	Concrete	Not Painted	N/A	N/A	N/A	N/A
1	B	Auditorium Supply Plenum (below Auditorium)	Ceiling	Concrete	Not Painted	N/A	N/A	N/A	N/A
1	B	Auditorium Supply Plenum (below Auditorium)	Floor	Concrete	Not Painted	N/A	N/A	N/A	N/A
1	B	Office marked B-C across from Girls Locker Room	W1	Plaster	White/Pink	Flaking	9	2.4	Positive
1	B	Office marked B-C across from Girls Locker Room	Doorframe	Metal	Brown	Friction	6	1	Positive
1	B	Office marked B-C across from Girls Locker Room	Conduit	Plastic	White	None	0	0.6	Negative
1	B	Office marked B-C across from Girls Locker Room	W2	Plaster	White/Pink	Cracking	6	3.7	Positive
1	B	Office marked B-C across from Girls Locker Room	Pipe	Metal	White	Flaking	7	14.4	Positive
1	B	Office marked B-C across from Girls Locker Room	Conduit	Metal	White	None	0	0.4	Negative
1	B	Office marked B-C across from Girls Locker Room	Coat Rack	Wood	White	None	0	0.4	Negative
1	B	Office marked B-C across from Girls Locker Room	W3	Plaster	White/Pink	Flaking	10	1.8	Positive
1	B	Office marked B-C across from Girls Locker Room	Covebase	Concrete	Grey	Flaking	12	0.2	Negative

		Dates: 6/5 - 7/6/2023	Lead-Safe Certification Assessment Report						
		Inspector Name and Certificate Number: Tim Smith 057662	John Bartram High School						
		Inspection Company: BATA	2401 S 67th St, Philadelphia PA 19142						
Element	Floor	On-Site Room Name	Component	Substrate Material [1]	Paint Color	Description of Paint Damage	Damage Quantity (sf) [2]	XRF Reading (mg/cm2)	XRF (positive/negative) [3]
1	B	Office marked B-C across from Girls Locker Room	Radiator	Metal	Brown	Flaking	8	0	Negative
1	B	Office marked B-C across from Girls Locker Room	Pipe Cover	Metal	Pink	Flaking	9	0.4	Negative
1	B	Office marked B-C across from Girls Locker Room	Pipe Insulation	Asbestos	White	None	0	3.6	Positive
1	B	Office marked B-C across from Girls Locker Room	W4	Plaster	White/Pink	Flaking	2	1.4	Positive
1	B	Office marked B-C across from Girls Locker Room	Ceiling	Plaster	White	Flaking	30	4.7	Positive
1	B	Office marked B-C across from Girls Locker Room	Ceiling	2'x4' Ceiling Tile	Not Painted	N/A	N/A	N/A	N/A
1	B	Office marked B-C across from Girls Locker Room	Floor	Concrete	Brown	None	0	0.2	Negative
1	B	Restroom inside Office marked B-C across from Girls Locker Room	W1	Plaster	White	Flaking	50	3.4	Positive
1	B	Restroom inside Office marked B-C across from Girls Locker Room	Doorframe	Metal	Brown	Friction	2	0.6	Negative
1	B	Restroom inside Office marked B-C across from Girls Locker Room	W2	Plaster	White	Flaking	12	1.9	Positive
1	B	Restroom inside Office marked B-C across from Girls Locker Room	Covebase	Concrete	Grey	Flaking	24	0.4	Negative
1	B	Restroom inside Office marked B-C across from Girls Locker Room	W3	Plaster	White	Flaking	14	2.1	Positive
1	B	Restroom inside Office marked B-C across from Girls Locker Room	Radiator	Metal	Brown	Flaking	8	0.1	Negative
1	B	Restroom inside Office marked B-C across from Girls Locker Room	W4	Plaster	White	Flaking	18	2.9	Positive
1	B	Restroom inside Office marked B-C across from Girls Locker Room	Pipe Insulation	Asbestos	White	None	0	1.5	Positive
1	B	Restroom inside Office marked B-C across from Girls Locker Room	Mirror Frame	Wood	White	None	0	0.2	Negative
1	B	Restroom inside Office marked B-C across from Girls Locker Room	Ceiling	Plaster	White	Flaking	60	1.9	Positive
1	B	Restroom inside Office marked B-C across from Girls Locker Room	Floor	Concrete	Grey	None	0	0.1	Negative

		Dates: 6/5 - 7/6/2023	Lead-Safe Certification Assessment Report						
		Inspector Name and Certificate Number: Tim Smith 057662	John Bartram High School						
		Inspection Company: BATA	2401 S 67th St, Philadelphia PA 19142						
E l e m e n t	F l o o r	On-Site Room Name	Component	Substrate Material [1]	Paint Color	Description of Paint Damage	Damage Quantity (sf) [2]	XRF Reading (mg/cm2)	XRF (positive/ negative) [3]
1	B	Storage Room marked B-G across from Auditorium Supply Plenum	W1	Plaster	Tan	None	0	0.1	Negative
1	B	Storage Room marked B-G across from Auditorium Supply Plenum	Doorframe	Metal	Brown	Friction	3	0.7	Positive
1	B	Storage Room marked B-G across from Auditorium Supply Plenum	W2	Plaster	Tan	None	0	0.1	Negative
1	B	Storage Room marked B-G across from Auditorium Supply Plenum	W3	Plaster	Tan	None	0	0	Negative
1	B	Storage Room marked B-G across from Auditorium Supply Plenum	W4	Plaster	Tan	None	0	0	Negative
1	B	Storage Room marked B-G across from Auditorium Supply Plenum	Ceiling	Plaster	Tan	None	0	0.4	Negative
1	B	Storage Room marked B-G across from Auditorium Supply Plenum	Floor	Concrete	Grey	Friction	14	0.2	Negative
1	B	Classroom C-1	W1	Drywall	White	None	0	0.1	Negative
1	B	Classroom C-1	Doorframe	Metal	Brown	Friction	2	0.1	Negative
1	B	Classroom C-1	Door	Wood	Black	Chipping	8	0	Negative
1	B	Classroom C-1	Conduit	Plastic	White	None	0	0.1	Negative
1	B	Classroom C-1	W2	Terracotta	White	None	0	0.1	Negative
1	B	Classroom C-1	Pipe Cover	Metal	Blue	Flaking	3	2.4	Positive
1	B	Classroom C-1	Pipe Insulation	Asbestos	White	None	0	0	Negative
1	B	Classroom C-1	Radiator cover	Metal	Brown	Chipping	8	0.2	Negative
1	B	Classroom C-1	Conduit	Metal	White	None	0	0.1	Negative
1	B	Classroom C-1	Windowframe	Wood	Brown	None	0	0.4	Negative
1	B	Classroom C-1	W3	Terracotta	White	None	0	9.1	Positive
1	B	Classroom C-1	W4	Terracotta	White	Flaking	1	5.7	Positive
1	B	Classroom C-1	Pipe	Metal	White	None	0	1.7	Positive
1	B	Classroom C-1	Duct	Metal	White	Flaking	5	0.1	Negative

		Dates: 6/5 - 7/6/2023	Lead-Safe Certification Assessment Report							
		Inspector Name and Certificate Number: Tim Smith 057662	John Bartram High School							
		Inspection Company: BATA	2401 S 67th St, Philadelphia PA 19142							
Element	Floor	On-Site Room Name	Component	Substrate Material [1]	Paint Color	Description of Paint Damage	Damage Quantity (sf) [2]	XRF Reading (mg/cm ²)	XRF (positive/negative) [3]	
1	B	Classroom C-1	Covebase	Concrete	Brown	Flaking	15	2.8	Positive	
1	B	Classroom C-1	Ceiling	Concrete	White	Flaking	160	0.2	Negative	
1	B	Classroom C-1	Ceiling	2'x4' Ceiling Tile	Not Painted	N/A	N/A	N/A	N/A	
1	B	Classroom C-1	Grate	Metal	Brown	None	0	7.7	Positive	
1	B	Classroom C-1	Floor	Floor Tile	Not Painted	N/A	N/A	N/A	N/A	
1	B	Classroom C-2	W1	Drywall	White	None	0	0.1	Negative	
1	B	Classroom C-2	Door	Wood	Green	Flaking	8	0	Negative	
1	B	Classroom C-2	Doorframe	Metal	Brown	Friction	2	0	Negative	
1	B	Classroom C-2	W2	Terracotta	White	Flaking	1	3.2	Positive	
1	B	Classroom C-2	Covebase	Concrete	Brown	Flaking	12	0.1	Negative	
1	B	Classroom C-2	Pipe Cover	Metal	White	Flaking	10	1.4	Positive	
1	B	Classroom C-2	Pipe Insulation	Asbestos	White	None	0	0	Negative	
1	B	Classroom C-2	W3	Terracotta	White	None	0	0	Negative	
1	B	Classroom C-2	Radiator cover	Metal	Brown	Chipping	16	0.3	Negative	
1	B	Classroom C-2	Windowframe	Wood	Brown	None	0	1.4	Positive	
1	B	Classroom C-2	Conduit	Metal	White	Flaking	1	0.2	Negative	
1	B	Classroom C-2	W4	Terracotta	White	Flaking	16	2.9	Positive	
1	B	Classroom C-2	Ceiling	Concrete	Not Painted	N/A	N/A	N/A	N/A	
1	B	Classroom C-2	Ceiling	2'x4' Ceiling Tile	Not Painted	N/A	N/A	N/A	N/A	
1	B	Classroom C-2	Floor	Floor Tile	Not Painted	N/A	N/A	N/A	N/A	
1	B	Classroom C-2	Floor Grate	Metal	Brown	None	0	5.8	Positive	
1	B	Classroom C-3	W1	Drywall	Green	None	0	0.1	Negative	
1	B	Classroom C-3	Doorframe	Metal	Brown	Friction	5	0.1	Negative	
1	B	Classroom C-3	Door	Wood	Brown	Friction	3	0.1	Negative	
1	B	Classroom C-3	W2	CMU	White	None	0	0.1	Negative	
1	B	Classroom C-3	W2	Terracotta	Purple	None	0	0.2	Negative	

		Dates: 6/5 - 7/6/2023	Lead-Safe Certification Assessment Report						
		Inspector Name and Certificate Number: Tim Smith 057662	John Bartram High School						
		Inspection Company: BATTA	2401 S 67th St, Philadelphia PA 19142						
Element	Floor	On-Site Room Name	Component	Substrate Material [1]	Paint Color	Description of Paint Damage	Damage Quantity (sf) [2]	XRF Reading (mg/cm ²)	XRF (positive/negative) [3]
1	B	Classroom C-3	W3	Drywall	Purple	None	0	0	Negative
1	B	Classroom C-3	W4	Terracotta	Purple	Flaking	20	6.9	Positive
1	B	Classroom C-3	Pipe Cover	Metal	White	Flaking	9	4.7	Positive
1	B	Classroom C-3	Pipe Insulation	Asbestos	White	None	0	0.1	Negative
1	B	Classroom C-3	Radiator cover	Metal	Brown	Flaking	6	0.3	Negative
1	B	Classroom C-3	Conduit	Metal	White	None	0	0.3	Negative
1	B	Classroom C-3	Windowframe	Wood	Brown	None	0	0.2	Negative
1	B	Classroom C-3	Covebase	Concrete	Brown	Flaking	30	2.2	Positive
1	B	Classroom C-3	W4	Brick	Purple	None	0	0.1	Negative
1	B	Classroom C-3	Ceiling	Concrete	White	Flaking	60	0.3	Negative
1	B	Classroom C-3	Ceiling	2'x4' Ceiling Tile	Not Painted	N/A	N/A	N/A	N/A
1	B	Classroom C-3	Floor	Floor Tile	Not Painted	N/A	N/A	N/A	N/A
1	B	Classroom C-3	Floor Grate	Metal	Brown	None	0	7.7	Positive
1	B	Crawl Space in Basement	W1	No Access	No Access	No Access	No Access	No Access	No Access
1	B	Crawl Space in Basement	W2	No Access	No Access	No Access	No Access	No Access	No Access
1	B	Crawl Space in Basement	W3	No Access	No Access	No Access	No Access	No Access	No Access
1	B	Crawl Space in Basement	W4	No Access	No Access	No Access	No Access	No Access	No Access
1	B	Crawl Space in Basement	Ceiling	No Access	No Access	No Access	No Access	No Access	No Access
1	B	Crawl Space in Basement	Floor	No Access	No Access	No Access	No Access	No Access	No Access
1	B	Corridor 1 Elevator (A Wing)	W1	Metal	Not Painted	N/A	N/A	N/A	N/A
1	B	Corridor 1 Elevator (A Wing)	W2	Metal	Purple	Chipping	1	0.2	Negative
1	B	Corridor 1 Elevator (A Wing)	Door	Metal	Brown	None	0	0.2	Negative
1	B	Corridor 1 Elevator (A Wing)	Doorframe	Metal	Brown	None	0	0.2	Negative
1	B	Corridor 1 Elevator (A Wing)	W3	Metal	Purple	Chipping	1	0.1	Negative
1	B	Corridor 1 Elevator (A Wing)	W4	Metal	Purple	Chipping	1	0	Negative
1	B	Corridor 1 Elevator (A Wing)	Ceiling	Metal	White	Chipping	1	0.2	Negative

		Dates: 6/5 - 7/6/2023	Lead-Safe Certification Assessment Report						
		Inspector Name and Certificate Number: Tim Smith 057662	John Bartram High School						
		Inspection Company: BATA	2401 S 67th St, Philadelphia PA 19142						
Element	Floor	On-Site Room Name	Component	Substrate Material [1]	Paint Color	Description of Paint Damage	Damage Quantity (sf) [2]	XRF Reading (mg/cm ²)	XRF (positive/negative) [3]
1	B	Corridor 1 Elevator (A Wing)	Floor	Floor Tile	Not Painted	N/A	N/A	N/A	N/A
1	B	Corridor 3 Elevator (C Wing)	W1	Metal	Not Painted	N/A	N/A	N/A	N/A
1	B	Corridor 3 Elevator (C Wing)	W2	Metal	Yellow	Chipping	12	0.1	Negative
1	B	Corridor 3 Elevator (C Wing)	Door	Metal	Blue	None	0	0	Negative
1	B	Corridor 3 Elevator (C Wing)	Doorframe	Metal	Blue	Chipping	5	0.5	Negative
1	B	Corridor 3 Elevator (C Wing)	W3	Metal	Yellow	Chipping	30	0	Negative
1	B	Corridor 3 Elevator (C Wing)	W4	Metal	Yellow	Chipping	12	0	Negative
1	B	Corridor 3 Elevator (C Wing)	Ceiling	Metal	White	None	0	0	Negative
1	B	Corridor 3 Elevator (C Wing)	Floor	Floor Tile	Not Painted	N/A	N/A	N/A	N/A
1	B	Hallway from Health Suite to Cafeteria	W1	Plaster	White	None	0	0.1	Negative
1	B	Hallway from Health Suite to Cafeteria	W2	Plaster	White	None	0	0.2	Negative
1	B	Hallway from Health Suite to Cafeteria	Locker	Metal	Red	Chipping	20	0.3	Negative
1	B	Hallway from Health Suite to Cafeteria	Conduit	Plastic	White	None	0	0.3	Negative
1	B	Hallway from Health Suite to Cafeteria	W3	Plaster	White	None	0	0.2	Negative
1	B	Hallway from Health Suite to Cafeteria	Covebase	Concrete	Brown	None	0	0.1	Negative
1	B	Hallway from Health Suite to Cafeteria	W4	Plaster	White	Chipping	12	0.3	Negative
1	B	Hallway from Health Suite to Cafeteria	Pipe Insulation	Fiberglass	White	None	0	0.1	Negative
1	B	Hallway from Health Suite to Cafeteria	Ceiling	Plaster	White	None	0	0.3	Negative
1	B	Hallway from Health Suite to Cafeteria	Ceiling	2'x4' Ceiling Tile	Not Painted	N/A	N/A	N/A	N/A
1	B	Hallway from Health Suite to Cafeteria	Floor	Concrete	Not Painted	N/A	N/A	N/A	N/A
1	B	B-Wing Hallway 15-17	W1	Plaster	White	None	0	0	Negative
1	B	B-Wing Hallway 15-17	Locker	Metal	Red	None	0	0.1	Negative
1	B	B-Wing Hallway 15-17	W2	Plaster	White	None	0	0.1	Negative
1	B	B-Wing Hallway 15-17	Pipe	Metal	Yellow	None	0	0	Negative
1	B	B-Wing Hallway 15-17	Radiator cover	Metal	Brown	None	0	0.1	Negative
1	B	B-Wing Hallway 15-17	Covebase	Concrete	Red	None	0	0.2	Negative

		Dates: 6/5 - 7/6/2023	Lead-Safe Certification Assessment Report							
		Inspector Name and Certificate Number: Tim Smith 057662	John Bartram High School							
		Inspection Company: BATTA	2401 S 67th St, Philadelphia PA 19142							
Element	Floor	On-Site Room Name	Component	Substrate Material [1]	Paint Color	Description of Paint Damage	Damage Quantity (sf) [2]	XRF Reading (mg/cm2)	XRF (positive/negative) [3]	
1	B	B-Wing Hallway 15-17	Pipe Cover	Metal	White	Flaking	4	3	Positive	
1	B	B-Wing Hallway 15-17	Pipe Insulation	Asbestos	White	None	0	0.3	Negative	
1	B	B-Wing Hallway 15-17	W3	Plaster	White	None	0	0.2	Negative	
1	B	B-Wing Hallway 15-17	W4	Plaster	White	None	0	0.2	Negative	
1	B	B-Wing Hallway 15-17	Ceiling	Plaster	White	None	0	0.4	Negative	
1	B	B-Wing Hallway 15-17	Ceiling	2'x4' Ceiling Tile	Not Painted	N/A	N/A	N/A	N/A	
1	B	B-Wing Hallway 15-17	Ceiling	1'x1' Ceiling Tile	White	None	0	0.1	Negative	
1	B	B-Wing Hallway 15-17	Floor	Concrete	Not Painted	N/A	N/A	N/A	N/A	
1	B	C-Wing Hallway 1-7	W1	Plaster	White	None	0	0.1	Negative	
1	B	C-Wing Hallway 1-7	W2	Plaster	White	Efflorescence	2	0.3	Negative	
1	B	C-Wing Hallway 1-7	W3	Drywall	White	None	0	0.1	Negative	
1	B	C-Wing Hallway 1-7	W4	Plaster	White	None	0	0.5	Negative	
1	B	C-Wing Hallway 1-7	Radiator cover	Metal	Brown	Friction	8	0.1	Negative	
1	B	C-Wing Hallway 1-7	Covebase	Concrete	Brown	None	0	0	Negative	
1	B	C-Wing Hallway 1-7	Conduit	Metal	White	None	0	0.4	Negative	
1	B	C-Wing Hallway 1-7	Ceiling	Plaster	White	None	0	0.1	Negative	
1	B	C-Wing Hallway 1-7	Ceiling	2'x4' Ceiling Tile	Not Painted	N/A	N/A	N/A	N/A	
1	B	C-Wing Hallway 1-7	Ceiling	1'x1' Ceiling Tile	White	None	0	0	Negative	
1	B	C-Wing Hallway 1-7	Floor	Concrete	Not Painted	N/A	N/A	N/A	N/A	
1	B	Main Hallway 7-28	W1	Plaster	White	Cracking	4	0.1	Negative	
1	B	Main Hallway 7-28	Locker	Metal	Red	Chipping	50	0.1	Negative	
1	B	Main Hallway 7-28	W2	Plaster	White	None	0	0.1	Negative	
1	B	Main Hallway 7-28	W3	Plaster	White	Flaking	2	0.1	Negative	
1	B	Main Hallway 7-28	Mural Wall	Plaster	Multi-Color	Cracking	5	0	Negative	
1	B	Main Hallway 7-28	W4	Plaster	White	None	0	0.1	Negative	
1	B	Main Hallway 7-28	Radiator cover	Metal	Brown	Friction	8	0.1	Negative	

		Dates: 6/5 - 7/6/2023	Lead-Safe Certification Assessment Report							
		Inspector Name and Certificate Number: Tim Smith 057662	John Bartram High School							
		Inspection Company: BATA	2401 S 67th St, Philadelphia PA 19142							
Element	Floor	On-Site Room Name	Component	Substrate Material [1]	Paint Color	Description of Paint Damage	Damage Quantity (sf) [2]	XRF Reading (mg/cm2)	XRF (positive/negative) [3]	
1	B	Main Hallway 7-28	Covebase	Concrete	Brown	Chipping	60	0.1	Negative	
1	B	Main Hallway 7-28	Pipe Cover	Metal	White	Flaking	4	1.9	Positive	
1	B	Main Hallway 7-28	Pipe Insulation	Asbestos	White	None	0	0.2	Negative	
1	B	Main Hallway 7-28	Ceiling	Plaster	White	None	0	0.1	Negative	
1	B	Main Hallway 7-28	Ceiling	2'x4' Ceiling Tile	Not Painted	N/A	N/A	N/A	N/A	
1	B	Main Hallway 7-28	Ceiling	1'x1' Ceiling Tile	White	None	0	0.1	Negative	
1	B	Main Hallway 7-28	Floor	Concrete	Not Painted	N/A	N/A	N/A	N/A	
1	B	Stairwell adjacent to Cafeteria Storage	W1	Plaster	White	None	0	0.1	Negative	
1	B	Stairwell adjacent to Cafeteria Storage	Door	Metal	Brown	Chipping	2	0.1	Negative	
1	B	Stairwell adjacent to Cafeteria Storage	Doorframe	Metal	Brown	Chipping	4	0.5	Negative	
1	B	Stairwell adjacent to Cafeteria Storage	W2	Plaster	White	Flaking	6	0.4	Negative	
1	B	Stairwell adjacent to Cafeteria Storage	Radiator cover	Metal	Brown	None	0	0.5	Negative	
1	B	Stairwell adjacent to Cafeteria Storage	W3	Plaster	White	None	0	0	Negative	
1	B	Stairwell adjacent to Cafeteria Storage	Door	Metal	Blue	Chipping	2	0.1	Negative	
1	B	Stairwell adjacent to Cafeteria Storage	Doorframe	Metal	Blue	None	0	0.2	Negative	
1	B	Stairwell adjacent to Cafeteria Storage	W4	Plaster	White	Cracking	12	3.4	Positive	
1	B	Stairwell adjacent to Cafeteria Storage	Riser	Concrete	Brown	None	0	0.5	Negative	
1	B	Stairwell adjacent to Cafeteria Storage	Covebase	Concrete	Brown	None	0	0.4	Negative	
1	B	Stairwell adjacent to Cafeteria Storage	Stringer	Concrete	Brown	None	0	0.4	Negative	
1	B	Stairwell adjacent to Cafeteria Storage	Post	Concrete	Brown	None	0	14.5	Positive	
1	B	Stairwell adjacent to Cafeteria Storage	Tread	Concrete	Brown	None	0	0.2	Negative	
1	B	Stairwell adjacent to Cafeteria Storage	Baluster	Metal	Brown	None	0	7.7	Positive	
1	B	Stairwell adjacent to Cafeteria Storage	Pipe Cover	Metal	Tan	Chipping	3	4.4	Positive	
1	B	Stairwell adjacent to Cafeteria Storage	Pipe Insulation	Asbestos	Tan	None	0	0.1	Negative	
1	B	Stairwell adjacent to Cafeteria Storage	Ceiling	Concrete	White	None	0	0.3	Negative	
1	B	Stairwell adjacent to Cafeteria Storage	Floor	Concrete	Grey	Friction	105	0.3	Negative	

		Dates: 6/5 - 7/6/2023	Lead-Safe Certification Assessment Report						
		Inspector Name and Certificate Number: Tim Smith 057662	John Bartram High School						
		Inspection Company: BATA	2401 S 67th St, Philadelphia PA 19142						
E l e m e n t	F l o o r	On-Site Room Name	Component	Substrate Material [1]	Paint Color	Description of Paint Damage	Damage Quantity (sf) [2]	XRF Reading (mg/cm ²)	XRF (positive/ negative) [3]
1	B	Stairwell B adjacent to Room. 16	W1	Plaster	White	Flaking	9	0.1	Negative
1	B	Stairwell B adjacent to Room. 16	Door	Metal	Red	Chipping	3	0.1	Negative
1	B	Stairwell B adjacent to Room. 16	Doorframe	Metal	Red	None	0	0	Negative
1	B	Stairwell B adjacent to Room. 16	W2	Plaster	White	Cracking	6	0.3	Negative
1	B	Stairwell B adjacent to Room. 16	Radiator cover	Metal	Brown	None	0	0.6	Negative
1	B	Stairwell B adjacent to Room. 16	W3	Plaster	White	Chipping	5	0.5	Negative
1	B	Stairwell B adjacent to Room. 16	Windowframe	Metal	White	Chipping	1	10.3	Positive
1	B	Stairwell B adjacent to Room. 16	W4	Plaster	White	Cracking	8	0.1	Negative
1	B	Stairwell B adjacent to Room. 16	Conduit	Metal	White	None	0	0.4	Negative
1	B	Stairwell B adjacent to Room. 16	Riser	Concrete	Brown	Friction	20	0.3	Negative
1	B	Stairwell B adjacent to Room. 16	Covebase	Concrete	Brown	None	0	0.6	Negative
1	B	Stairwell B adjacent to Room. 16	Stringer	Concrete	Brown	None	0	0.9	Positive
1	B	Stairwell B adjacent to Room. 16	Post	Metal	Brown	Chipping	1	16.4	Positive
1	B	Stairwell B adjacent to Room. 16	Baluster	Metal	Brown	None	0	6.2	Positive
1	B	Stairwell B adjacent to Room. 16	Ceiling	Concrete	White	None	0	0.2	Negative
1	B	Stairwell B adjacent to Room. 16	Floor	Concrete	Grey	None	0	0.2	Negative
1	B	Stairwell A adjacent to Cafeteria	W1	Plaster	White	Cracking	16	0.4	Negative
1	B	Stairwell A adjacent to Cafeteria	Door	Metal	Red	Chipping	6	0.1	Negative
1	B	Stairwell A adjacent to Cafeteria	Doorframe	Metal	Red	Chipping	3	0.1	Negative
1	B	Stairwell A adjacent to Cafeteria	Pipe	Metal	White	None	0	7.1	Positive
1	B	Stairwell A adjacent to Cafeteria	W2	Plaster	White	Cracking	12	0.5	Negative
1	B	Stairwell A adjacent to Cafeteria	Radiator cover	Metal	Brown	Flaking	12	0.5	Negative
1	B	Stairwell A adjacent to Cafeteria	Covebase	Concrete	Brown	Flaking	30	0.5	Negative
1	B	Stairwell A adjacent to Cafeteria	Post	Metal	Brown	Chipping	2	21.3	Positive
1	B	Stairwell A adjacent to Cafeteria	Stringer	Concrete	Brown	None	0	0.3	Negative
1	B	Stairwell A adjacent to Cafeteria	Riser	Concrete	Brown	Chipping	24	0.4	Negative

		Dates: 6/5 - 7/6/2023	Lead-Safe Certification Assessment Report						
		Inspector Name and Certificate Number: Tim Smith 057662	John Bartram High School						
		Inspection Company: BATA	2401 S 67th St, Philadelphia PA 19142						
E l e m e n t	F l o o r	On-Site Room Name	Component	Substrate Material [1]	Paint Color	Description of Paint Damage	Damage Quantity (sf) [2]	XRF Reading (mg/cm2)	XRF (positive/ negative) [3]
1	B	Stairwell A adjacent to Cafeteria	Baluster	Metal	Brown	None	0	9.5	Positive
1	B	Stairwell A adjacent to Cafeteria	W3	Plaster	White	Flaking	1	0	Negative
1	B	Stairwell A adjacent to Cafeteria	W4	Plaster	White	Cracking	45	0.2	Negative
1	B	Stairwell A adjacent to Cafeteria	Ceiling	Concrete	White	Flaking	26	0.3	Negative
1	B	Stairwell A adjacent to Cafeteria	Floor	Concrete	Grey	None	0	0.2	Negative
1	B	Stairwell C adjacent to Classroom C-8	W1	Plaster	White	Flaking	5	0.6	Negative
1	B	Stairwell C adjacent to Classroom C-8	Door	Metal	Blue	Friction	8	0	Negative
1	B	Stairwell C adjacent to Classroom C-8	Doorframe	Metal	Blue	Friction	4	0.1	Negative
1	B	Stairwell C adjacent to Classroom C-8	Pipe	Metal	White	None	0	16	Positive
1	B	Stairwell C adjacent to Classroom C-8	W2	Plaster	White	Cracking	20	0.1	Negative
1	B	Stairwell C adjacent to Classroom C-8	Radiator cover	Metal	Brown	Flaking	8	0.5	Negative
1	B	Stairwell C adjacent to Classroom C-8	Covebase	Concrete	Brown	Cracking	18	0.1	Negative
1	B	Stairwell C adjacent to Classroom C-8	Post	Metal	Brown	None	0	15.3	Positive
1	B	Stairwell C adjacent to Classroom C-8	Stringer	Concrete	Brown	None	0	0.6	Negative
1	B	Stairwell C adjacent to Classroom C-8	Riser	Concrete	Brown	Friction	20	0.4	Negative
1	B	Stairwell C adjacent to Classroom C-8	Baluster	Metal	Brown	None	0	11.2	Positive
1	B	Stairwell C adjacent to Classroom C-8	W3	Plaster	White	Flaking	4	0	Negative
1	B	Stairwell C adjacent to Classroom C-8	Windowframe	Metal	Tan	Chipping	6	12.7	Positive
1	B	Stairwell C adjacent to Classroom C-8	W4	Plaster	White	Flaking	12	0	Negative
1	B	Stairwell C adjacent to Classroom C-8	Ceiling	Concrete	White	None	0	0.3	Negative
1	B	Stairwell C adjacent to Classroom C-8	Floor	Concrete	Grey	None	0	0.2	Negative
1	B	Stairwell inside Girl's Locker Room to 1st Floor Gym	W1	Plaster	White	None	0	0	Negative
1	B	Stairwell inside Girl's Locker Room to 1st Floor Gym	W2	Ceramic	Not Painted	N/A	N/A	N/A	N/A
1	B	Stairwell inside Girl's Locker Room to 1st Floor Gym	Post	Metal	Brown	None	0	7.9	Positive
1	B	Stairwell inside Girl's Locker Room to 1st Floor Gym	Baluster	Metal	Brown	None	0	6.9	Positive
1	B	Stairwell inside Girl's Locker Room to 1st Floor Gym	Riser	Concrete	Brown	None	0	0.6	Negative

		Dates: 6/5 - 7/6/2023	Lead-Safe Certification Assessment Report						
		Inspector Name and Certificate Number: Tim Smith 057662	John Bartram High School						
		Inspection Company: BATA	2401 S 67th St, Philadelphia PA 19142						
E l e m e n t	F l o o r	On-Site Room Name	Component	Substrate Material [1]	Paint Color	Description of Paint Damage	Damage Quantity (sf) [2]	XRF Reading (mg/cm2)	XRF (positive/ negative) [3]
1	B	Stairwell inside Girl's Locker Room to 1st Floor Gym	Stringer	Concrete	Brown	None	0	0.7	Positive
1	B	Stairwell inside Girl's Locker Room to 1st Floor Gym	W3	Plaster	White	None	0	0.5	Negative
1	B	Stairwell inside Girl's Locker Room to 1st Floor Gym	W4	Plaster	White	Efflorescence	4	0.3	Negative
1	B	Stairwell inside Girl's Locker Room to 1st Floor Gym	Ceiling	Plaster	White	None	0	0	Negative
1	B	Stairwell inside Girl's Locker Room to 1st Floor Gym	Floor	Concrete	Not Painted	N/A	N/A	N/A	N/A
1	B	Stairwell inside Boy's Locker Room to 1st Floor Gym	W1	Plaster	White	None	0	0.2	Negative
1	B	Stairwell inside Boy's Locker Room to 1st Floor Gym	W2	Ceramic	Not Painted	N/A	N/A	N/A	N/A
1	B	Stairwell inside Boy's Locker Room to 1st Floor Gym	Post	Metal	Brown	None	0	4.7	Positive
1	B	Stairwell inside Boy's Locker Room to 1st Floor Gym	Baluster	Metal	Brown	None	0	4.5	Positive
1	B	Stairwell inside Boy's Locker Room to 1st Floor Gym	Riser	Concrete	Brown	None	0	1	Positive
1	B	Stairwell inside Boy's Locker Room to 1st Floor Gym	Stringer	Concrete	Brown	None	0	0.6	Negative
1	B	Stairwell inside Boy's Locker Room to 1st Floor Gym	W3	Plaster	White	Efflorescence	4	0.6	Negative
1	B	Stairwell inside Boy's Locker Room to 1st Floor Gym	W4	Plaster	White	None	0	0.6	Negative
1	B	Stairwell inside Boy's Locker Room to 1st Floor Gym	Ceiling	Plaster	White	None	0	0.4	Negative
1	B	Stairwell inside Boy's Locker Room to 1st Floor Gym	Floor	Concrete	Not Painted	N/A	N/A	N/A	N/A
1	B	Pipe Chase below stairwell inside Boy's Locker Room	W1	No Access	No Access	No Access	No Access	No Access	No Access
1	B	Pipe Chase below stairwell inside Boy's Locker Room	W2	No Access	No Access	No Access	No Access	No Access	No Access
1	B	Pipe Chase below stairwell inside Boy's Locker Room	W3	No Access	No Access	No Access	No Access	No Access	No Access
1	B	Pipe Chase below stairwell inside Boy's Locker Room	W4	No Access	No Access	No Access	No Access	No Access	No Access
1	B	Pipe Chase below stairwell inside Boy's Locker Room	Ceiling	No Access	No Access	No Access	No Access	No Access	No Access
1	B	Pipe Chase below stairwell inside Boy's Locker Room	Floor	No Access	No Access	No Access	No Access	No Access	No Access
1	B	Stairwell adjacent to C-1	W1	Plaster	White	Cracking	6	0.6	Negative
1	B	Stairwell adjacent to C-1	Doorframe	Metal	Blue	Friction	2	0	Negative
1	B	Stairwell adjacent to C-1	Door	Metal	Blue	Friction	6	0.1	Negative
1	B	Stairwell adjacent to C-1	W2	Plaster	White	None	0	0.1	Negative
1	B	Stairwell adjacent to C-1	Post	Metal	Brown	None	0	11.6	Positive

		Dates: 6/5 - 7/6/2023	Lead-Safe Certification Assessment Report							
		Inspector Name and Certificate Number: Tim Smith 057662	John Bartram High School							
		Inspection Company: BATA	2401 S 67th St, Philadelphia PA 19142							
E l e m e n t	F l o o r	On-Site Room Name	Component	Substrate Material [1]	Paint Color	Description of Paint Damage	Damage Quantity (sf) [2]	XRF Reading (mg/cm2)	XRF (positive/ negative) [3]	
1	B	Stairwell adjacent to C-1	Baluster	Metal	Brown	None	0	8.1	Positive	
1	B	Stairwell adjacent to C-1	Stringer	Metal	Brown	None	0	0.5	Negative	
1	B	Stairwell adjacent to C-1	Riser	Concrete	Brown	Chipping	30	0.4	Negative	
1	B	Stairwell adjacent to C-1	W3	Plaster	White	Flaking	4	0.5	Negative	
1	B	Stairwell adjacent to C-1	W4	Plaster	White	None	0	0.5	Negative	
1	B	Stairwell adjacent to C-1	Conduit	Metal	White	None	0	0.1	Negative	
1	B	Stairwell adjacent to C-1	Radiator cover	Metal	Brown	None	0	0.1	Negative	
1	B	Stairwell adjacent to C-1	Covebase	Concrete	Brown	Flaking	8	0.1	Negative	
1	B	Stairwell adjacent to C-1	Ceiling	Concrete	White	None	0	0.4	Negative	
1	B	Stairwell adjacent to C-1	Floor	Concrete	Not Painted	N/A	N/A	N/A	N/A	
14	1	Area 1	W1	Plaster	Grey	Flaking	200	1.7	Positive	
14	1	Area 1	Door	Metal	Grey	Friction	12	0.1	Negative	
14	1	Area 1	Doorframe	Metal	Grey	Friction	20	0.5	Negative	
14	1	Area 1	Pipe	Metal	Grey	Flaking	12	0.5	Negative	
14	1	Area 1	W2	Plaster	Multi-Color	Flaking	700	0.7	Positive	
14	1	Area 1	Conduit	Metal	Grey	Flaking	40	0.3	Negative	
14	1	Area 1	Work Bench	Metal	Grey	Flaking	20	2.2	Positive	
14	1	Area 1	W3	CMU	Grey	None	0	0	Negative	
14	1	Area 1	W4	CMU	Grey	Flaking	12	0.1	Negative	
14	1	Area 1	Sink	Ceramic	Grey	Flaking	4	0.3	Negative	
14	1	Area 1	Ceiling	Concrete	Not Painted	N/A	N/A	N/A	N/A	
14	1	Area 1	Floor	Concrete	Not Painted	N/A	N/A	N/A	N/A	
14	1	Area 2	W1	CMU	White	None	0	0.2	Negative	
14	1	Area 2	Doorframe	Metal	Black	None	0	0	Negative	
14	1	Area 2	W2	Plaster	White	Flaking	400	0.9	Positive	
14	1	Area 2	Conduit	Metal	White	Flaking	20	0.3	Negative	

		Dates: 6/5 - 7/6/2023	Lead-Safe Certification Assessment Report							
		Inspector Name and Certificate Number: Tim Smith 057662	John Bartram High School							
		Inspection Company: BATA	2401 S 67th St, Philadelphia PA 19142							
E l e m e n t	F l o o r	On-Site Room Name	Component	Substrate Material [1]	Paint Color	Description of Paint Damage	Damage Quantity (sf) [2]	XRF Reading (mg/cm2)	XRF (positive/ negative) [3]	
14	1	Area 2	Pipe	Metal	White	Flaking	80	0.1	Negative	
14	1	Area 2	W3	Brick	White	Flaking	440	4.5	Positive	
14	1	Area 2	Electrical Panel	Metal	Tan	Flaking	20	0	Negative	
14	1	Area 2	W4	CMU	White	None	0	0.1	Negative	
14	1	Area 2	Ceiling	Concrete	Not Painted	N/A	N/A	N/A	N/A	
14	1	Area 2	Floor	Concrete	Not Painted	N/A	N/A	N/A	N/A	
14	1	Storage 1	W1-Exterior	Metal	Tan	Cracking	8	0.2	Negative	
14	1	Storage 1	Door	Metal	Tan	Flaking	10	0.1	Negative	
14	1	Storage 1	W2-Exterior	Metal	Tan	None	0	1	Positive	
14	1	Storage 1	W3-Exterior	Metal	Tan	No Access	No Access	No Access	No Access	
14	1	Storage 1	W4-Exterior	Metal	Tan	None	0	0.1	Negative	
14	1	Storage 1	Pad	Concrete	Tan	None	0	0.3	Negative	
14	1	Storage 1	Ceiling	Metal	No Access	No Access	No Access	No Access	No Access	
14	1	Storage 1	Floor	Concrete	No Access	No Access	No Access	No Access	No Access	
14	1	Storage 2	W1-Exterior	Metal	Tan	Cracking	8	0.2	Negative	
14	1	Storage 2	Door	Metal	Tan	Flaking	10	0.1	Negative	
14	1	Storage 2	W2-Exterior	Metal	Tan	Flaking	5	0.1	Negative	
14	1	Storage 2	W3-Exterior	Metal	Tan	None	0	0.3	Negative	
14	1	Storage 2	W4-Exterior	Metal	Tan	No Access	No Access	No Access	No Access	
14	1	Storage 2	Pad	Concrete	Tan	None	0	0.3	Negative	
14	1	Storage 2	Ceiling	Metal	No Access	No Access	No Access	No Access	No Access	
14	1	Storage 2	Floor	Concrete	No Access	No Access	No Access	No Access	No Access	
14	1	Women's Restroom	W1	CMU	White	None	0	0	Negative	
14	1	Women's Restroom	Door	Wood	Green	Flaking	6	0.6	Negative	
14	1	Women's Restroom	Doorframe	Metal	Grey	Flaking	10	0	Negative	
14	1	Women's Restroom	Conduit	Metal	White	Chipping	1	0.2	Negative	

		Dates: 6/5 - 7/6/2023	Lead-Safe Certification Assessment Report						
		Inspector Name and Certificate Number: Tim Smith 057662	John Bartram High School						
		Inspection Company: BATA	2401 S 67th St, Philadelphia PA 19142						
E l e m e n t	F l o o r	On-Site Room Name	Component	Substrate Material [1]	Paint Color	Description of Paint Damage	Damage Quantity (sf) [2]	XRF Reading (mg/cm2)	XRF (positive/ negative) [3]
14	1	Women's Restroom	Radiator	Metal	Tan	Chipping	2	0.5	Negative
14	1	Women's Restroom	W2	CMU	White	None	0	0.1	Negative
14	1	Women's Restroom	Pipe	Metal	White	Flaking	4	0.1	Negative
14	1	Women's Restroom	W3	CMU	White	None	0	0.1	Negative
14	1	Women's Restroom	Cabinet	Metal	Green	Flaking	12	9.4	Positive
14	1	Women's Restroom	W4	Brick	White	Cracking	6	0.1	Negative
14	1	Women's Restroom	Ceiling	Transite	White	Flaking	16	0.3	Negative
14	1	Women's Restroom	Floor	Concrete	Not Painted	N/A	N/A	N/A	N/A
14	1	Men's Restroom	W1	CMU	White	None	0	0.1	Negative
14	1	Men's Restroom	Door	Wood	Grey	Flaking	10	0.1	Negative
14	1	Men's Restroom	Doorframe	Metal	Grey	Flaking	15	0.4	Negative
14	1	Men's Restroom	Conduit	Metal	White	None	0	0.2	Negative
14	1	Men's Restroom	W2	CMU	White	None	0	0.1	Negative
14	1	Men's Restroom	Radiator	Metal	Tan	Chipping	1	0.2	Negative
14	1	Men's Restroom	Pipe	Metal	White	Cracking	3	0.1	Negative
14	1	Men's Restroom	W3	Brick	White	Flaking	12	0.3	Negative
14	1	Men's Restroom	W4	CMU	White	None	0	0.2	Negative
14	1	Men's Restroom	Stall	Wood	White	None	0	0.1	Negative
14	1	Men's Restroom	Ceiling	Transite	White	None	0	0	Negative
14	1	Men's Restroom	Floor	Concrete	Grey	Cracking	40	0.5	Negative
14	1	Office	W1	Metal	Tan	Flaking	16	0.1	Negative
14	1	Office	Door	Metal	Grey	Flaking	12	0.4	Negative
14	1	Office	Doorframe	Metal	Grey	Flaking	2	0	Negative
14	1	Office	Conduit	Metal	Tan	Chipping	6	0.3	Negative
14	1	Office	Window Sash	Wood	Tan	None	0	0.2	Negative
14	1	Office	W2	Metal	Tan	Flaking	30	0.2	Negative

		Dates: 6/5 - 7/6/2023	Lead-Safe Certification Assessment Report							
		Inspector Name and Certificate Number: Tim Smith 057662	John Bartram High School							
		Inspection Company: BATA	2401 S 67th St, Philadelphia PA 19142							
E l e m e n t	F l o o r	On-Site Room Name	Component	Substrate Material [1]	Paint Color	Description of Paint Damage	Damage Quantity (sf) [2]	XRF Reading (mg/cm2)	XRF (positive/ negative) [3]	
14	1	Office	Peg Board	Wood	Tan	None	0	0.1	Negative	
14	1	Office	W3	CMU	Tan	None	0	0	Negative	
14	1	Office	W4	Metal	Tan	Flaking	4	0.2	Negative	
14	1	Office	Cabinet	Metal	Brown	None	0	0.3	Negative	
14	1	Office	Ceiling	Metal	Not Painted	N/A	N/A	N/A	N/A	
14	1	Office	Floor	Carpet	Not Painted	N/A	N/A	N/A	N/A	
14	1	Pump room	W1	CMU	White	None	0	0.1	Negative	
14	1	Pump room	Door	Wood	Grey	Chipping	2	0.2	Negative	
14	1	Pump room	Doorframe	Metal	Grey	Chipping	6	0.4	Negative	
14	1	Pump room	Conduit	Metal	White	Flaking	8	0.3	Negative	
14	1	Pump room	Pipe	Metal	White	Flaking	6	0.2	Negative	
14	1	Pump room	W2	CMU	White	None	0	0.1	Negative	
14	1	Pump room	W3	CMU	White	None	0	0.1	Negative	
14	1	Pump room	W4	CMU	White	None	0	0	Negative	
14	1	Pump room	Ceiling	Concrete	Not Painted	N/A	N/A	N/A	N/A	
14	1	Pump room	Floor	Concrete	Not Painted	N/A	N/A	N/A	N/A	
14	1	Shop	W1	CMU	White	None	0	0.2	Negative	
14	1	Shop	Door	Wood	Green	Flaking	1	0.8	Positive	
14	1	Shop	Doorframe	Metal	Grey	Flaking	8	0.2	Negative	
14	1	Shop	Conduit	Metal	White	Flaking	2	0.2	Negative	
14	1	Shop	W2	CMU	White	None	0	0.1	Negative	
14	1	Shop	W3	CMU	White	None	0	0.5	Negative	
14	1	Shop	W4	CMU	White	None	0	0.1	Negative	
14	1	Shop	Ceiling	Concrete	Not Painted	N/A	N/A	N/A	N/A	
14	1	Shop	Floor	Concrete	Not Painted	N/A	N/A	N/A	N/A	
14	1	Locker Room	W1	CMU	White	None	0	0.1	Negative	

		Dates: 6/5 - 7/6/2023	Lead-Safe Certification Assessment Report						
		Inspector Name and Certificate Number: Tim Smith 057662	John Bartram High School						
		Inspection Company: BATA	2401 S 67th St, Philadelphia PA 19142						
E l e m e n t	F l o o r	On-Site Room Name	Component	Substrate Material [1]	Paint Color	Description of Paint Damage	Damage Quantity (sf) [2]	XRF Reading (mg/cm2)	XRF (positive/ negative) [3]
14	1	Locker Room	Door	Wood	Brown	None	0	0.1	Negative
14	1	Locker Room	Doorframe	Metal	Brown	None	0	0.3	Negative
14	1	Locker Room	W2	CMU	White	None	0	0.2	Negative
14	1	Locker Room	W3	CMU	White	None	0	0.1	Negative
14	1	Locker Room	W4	CMU	White	None	0	0	Negative
14	1	Locker Room	Ceiling	Concrete	Not Painted	N/A	N/A	N/A	N/A
14	1	Locker Room	Floor	Concrete	Not Painted	N/A	N/A	N/A	N/A
14	1	Area 3	W1	Plaster	Multi-Color	Cracking	200	1.4	Positive
14	1	Area 3	Bay Doorframe	Metal	Brown	None	0	0	Negative
14	1	Area 3	Conduit	Metal	White	Flaking	30	0.2	Negative
14	1	Area 3	Pipe	Metal	White	Flaking	20	0.4	Negative
14	1	Area 3	W2	CMU	White	None	0	0	Negative
14	1	Area 3	Sink	Ceramic	Grey	Flaking	4	0.3	Negative
14	1	Area 3	W3	CMU	White	None	0	0.1	Negative
14	1	Area 3	W4	CMU	White	None	0	0	Negative
14	1	Area 3	Ceiling	Concrete	Not Painted	N/A	N/A	N/A	N/A
14	1	Area 3	Floor	Concrete	Not Painted	N/A	N/A	N/A	N/A
14	1	Shed	W1	Wood	Not Painted	N/A	N/A	N/A	N/A
14	1	Shed	Door	Wood	White	None	0	0	Negative
14	1	Shed	W2	Wood	Not Painted	N/A	N/A	N/A	N/A
14	1	Shed	W3	Wood	Not Painted	N/A	N/A	N/A	N/A
14	1	Shed	W4	Wood	Not Painted	N/A	N/A	N/A	N/A
14	1	Shed	Ceiling	Wood	Not Painted	N/A	N/A	N/A	N/A
14	1	Shed	Floor	Wood	Not Painted	N/A	N/A	N/A	N/A
14	1	Space 1	W1	No Access	No Access	No Access	No Access	No Access	No Access
14	1	Space 1	W2	No Access	No Access	No Access	No Access	No Access	No Access

		Dates: 6/5 - 7/6/2023	Lead-Safe Certification Assessment Report						
		Inspector Name and Certificate Number: Tim Smith 057662	John Bartram High School						
		Inspection Company: BATA	2401 S 67th St, Philadelphia PA 19142						
E l e m e n t	F l o o r	On-Site Room Name	Component	Substrate Material [1]	Paint Color	Description of Paint Damage	Damage Quantity (sf) [2]	XRF Reading (mg/cm2)	XRF (positive/ negative) [3]
14	1	Space 1	W3	No Access	No Access	No Access	No Access	No Access	No Access
14	1	Space 1	W4	No Access	No Access	No Access	No Access	No Access	No Access
14	1	Space 1	Ceiling	No Access	No Access	No Access	No Access	No Access	No Access
14	1	Space 1	Floor	No Access	No Access	No Access	No Access	No Access	No Access
14	1	Space 2	W1	No Access	No Access	No Access	No Access	No Access	No Access
14	1	Space 2	W2	No Access	No Access	No Access	No Access	No Access	No Access
14	1	Space 2	W3	No Access	No Access	No Access	No Access	No Access	No Access
14	1	Space 2	W4	No Access	No Access	No Access	No Access	No Access	No Access
14	1	Space 2	Ceiling	No Access	No Access	No Access	No Access	No Access	No Access
14	1	Space 2	Floor	No Access	No Access	No Access	No Access	No Access	No Access
14	1	Space 3	W1	No Access	No Access	No Access	No Access	No Access	No Access
14	1	Space 3	W2	No Access	No Access	No Access	No Access	No Access	No Access
14	1	Space 3	W3	No Access	No Access	No Access	No Access	No Access	No Access
14	1	Space 3	W4	No Access	No Access	No Access	No Access	No Access	No Access
14	1	Space 3	Ceiling	No Access	No Access	No Access	No Access	No Access	No Access
14	1	Space 3	Floor	No Access	No Access	No Access	No Access	No Access	No Access
14	1	Area 4	W1	No Access	No Access	No Access	No Access	No Access	No Access
14	1	Area 4	W2	No Access	No Access	No Access	No Access	No Access	No Access
14	1	Area 4	W3	No Access	No Access	No Access	No Access	No Access	No Access
14	1	Area 4	W4	No Access	No Access	No Access	No Access	No Access	No Access
14	1	Area 4	Ceiling	No Access	No Access	No Access	No Access	No Access	No Access
14	1	Area 4	Floor	No Access	No Access	No Access	No Access	No Access	No Access

[1] If the substrate is an undamaged ceramic tile that is unpainted, please note that in the comments. If undamaged ceramic tile is painted and the paint is damaged, a paint chip sample should be collected to determine whether or not the paint is lead-based.

[2] With the exception of "No Access," the entry should be numerical. For example, if there is no damage enter "0."

[3] Positive damaged lead-based paint requires a negative or positive entry in the asbestos paint sampled column. If no data, sampling, and analysis are required.