

		Dates: August 24 - September 19, 2022		Lead-Safe Certification Assessment Report						
		Inspector Name and Certificate Number: Kevin Rumbol 006794		Harding School						
		Inspection Company: ACER Associates, LLC		2000 Wakeling Street, Philadelphia, PA 19124						
Element	Floor	Space #	On-Site Room Name	Component	Substrate Material	Color	Description of Damage	Damage Quantity (sf)	XRF Reading (mg/cm2)	XRF (positive/negative)
1	B	004B	Gas Generator Room next to Rear of Boiler Room	Floor	Concrete	Gray	None	0	0.01	Negative
1	B	004B	Gas Generator Room next to Rear of Boiler Room	W1	Concrete	Green	None	0	0.02	Negative
1	B	004B	Gas Generator Room next to Rear of Boiler Room	W2	Concrete	Green	None	0	0.04	Negative
1	B	004B	Gas Generator Room next to Rear of Boiler Room	W3	Concrete	Green	None	0	0.01	Negative
1	B	004B	Gas Generator Room next to Rear of Boiler Room	W4	Concrete	Green	None	0	0	Negative
1	B	004B	Gas Generator Room next to Rear of Boiler Room	Ceiling	Concrete	White	N/A	0	0	Negative
1	B	004B	Gas Generator Room next to Rear of Boiler Room	Stringer	Metal	Gray	None	0	0	Negative
1	B	004B	Gas Generator Room next to Rear of Boiler Room	Tread	Metal	Black	None	0	0.02	Negative
1	B	004B	Gas Generator Room next to Rear of Boiler Room	Railing	Metal	Gray	None	0	0	Negative
1	B	004B	Gas Generator Room next to Rear of Boiler Room	Door	Metal	Brown	None	0	0	Negative
1	B	004B	Gas Generator Room next to Rear of Boiler Room	Door Frame	Metal	Brown	N/A	0	0	Negative
1	B	004B	Gas Generator Room next to Rear of Boiler Room	Window Frame	Wood	Brown	None	0	6	Positive
1	B	004B	Gas Generator Room next to Rear of Boiler Room	Pipe	Metal	Yellow	None	0	0	Negative
1	B	002B	Boiler Room	Floor	Concrete	Gray	N/A	0	0	Negative
1	B	002B	Boiler Room	W1	Brick	Green	None	0	0.02	Negative
1	B	002B	Boiler Room	W1	Concrete	Green	None	0	0.13	Negative
1	B	002B	Boiler Room	W2	Concrete	Green	None	0	0	Negative
1	B	002B	Boiler Room	W3	Concrete	Green	None	0	0.07	Negative
1	B	002B	Boiler Room	W4	Brick	Green	None	0	0.02	Negative
1	B	002B	Boiler Room	W4	Concrete	Green	None	0	0.06	Negative
1	B	002B	Boiler Room	Ceiling	Concrete	White	N/A	0	0.11	Negative
1	B	002B	Boiler Room	Door Frame	Wood	White	Flaking	20	14.7	Positive
1	B	002B	Boiler Room	Tread	Concrete	Gray	None	0	3.7	Positive
1	B	002B	Boiler Room	Riser	Concrete	Gray	None	0	15.3	Positive
1	B	002B	Boiler Room	Railing	Metal	Brown	Flaking	1	31.4	Positive
1	B	002C	Large Storage Room to Left of Boiler Room	Floor	Concrete	Gray	N/A	0	0	Negative
1	B	002C	Large Storage Room to Left of Boiler Room	W1	Concrete	Green	None	0	0	Negative
1	B	002C	Large Storage Room to Left of Boiler Room	W2	Concrete	Green	None	0	0	Negative
1	B	002C	Large Storage Room to Left of Boiler Room	W3	Concrete	Green	None	0	0	Negative
1	B	002C	Large Storage Room to Left of Boiler Room	W4	Concrete	Green	None	0	0	Negative
1	B	002C	Large Storage Room to Left of Boiler Room	Ceiling	Concrete	White	N/A	0	0	Negative
1	B	S01	Stairwell near Electrical Room and Boiler Room	Floor	Concrete	Gray	Flaking	12	3.5	Positive
1	B	S01	Stairwell near Electrical Room and Boiler Room	W1	Brick	White	Flaking	4	4.4	Positive
1	B	S01	Stairwell near Electrical Room and Boiler Room	W2	N/A	N/A	N/A	0	N/A	N/A
1	B	S01	Stairwell near Electrical Room and Boiler Room	W3	Brick	White	Flaking	22	4.4	Positive
1	B	S01	Stairwell near Electrical Room and Boiler Room	W4	Brick	White	Flaking	15	4.4	Positive
1	B	S01	Stairwell near Electrical Room and Boiler Room	Ceiling	Concrete	White	Flaking	22	10	Positive
1	B	S01	Stairwell near Electrical Room and Boiler Room	Pipe	Metal	White	Flaking	1	2.5	Positive
1	B	S01	Stairwell near Electrical Room and Boiler Room	Railing	Metal	Brown	Flaking	11	26.2	Positive

		Dates: August 24 - September 19, 2022		Lead-Safe Certification Assessment Report						
		Inspector Name and Certificate Number: Kevin Rumbol 006794		Harding School						
		Inspection Company: ACER Associates, LLC		2000 Wakeling Street, Philadelphia, PA 19124						
Element	Floor	Space #	On-Site Room Name	Component	Substrate Material	Color	Description of Damage	Damage Quantity (sf)	XRF Reading (mg/cm2)	XRF (positive/negative)
1	B	S01	Stairwell near Electrical Room and Boiler Room	Tread	Concrete	Gray	Flaking	2	18	Positive
1	B	S01	Stairwell near Electrical Room and Boiler Room	Riser	Concrete	Gray	None	0	13	Positive
1	B	S01	Stairwell near Electrical Room and Boiler Room	Door	Metal	Brown	None	0	0	Negative
1	B	S01	Stairwell near Electrical Room and Boiler Room	Door Frame	Metal	Brown	None	0	0	Negative
1	B	003B	Electrical Room next to Boiler Room	Floor	Concrete	Gray	None	0	0	Negative
1	B	003B	Electrical Room next to Boiler Room	W1	Brick	Green	Flaking	70	8.6	Positive
1	B	003B	Electrical Room next to Boiler Room	W1	Concrete	Green	Flaking	10	5.8	Positive
1	B	003B	Electrical Room next to Boiler Room	W2	Concrete	Green	Flaking	168	5.8	Positive
1	B	003B	Electrical Room next to Boiler Room	W3	Brick	Green	Flaking	45	8.6	Positive
1	B	003B	Electrical Room next to Boiler Room	W3	Concrete	White	Flaking	3	5.8	Positive
1	B	003B	Electrical Room next to Boiler Room	W4	Concrete	Green	Flaking	110	5.8	Positive
1	B	003B	Electrical Room next to Boiler Room	Ceiling	Concrete	White	Flaking	540	3.5	Positive
1	B	003B	Electrical Room next to Boiler Room	Pipe	Metal	White	Flaking	20	1.2	Positive
1	B	003B	Electrical Room next to Boiler Room	Railing	Metal	Brown	Flaking	2	27.4	Positive
1	B	003B	Electrical Room next to Boiler Room	Tread	Concrete	Gray	Flaking	1	13.8	Positive
1	B	003B	Electrical Room next to Boiler Room	Riser	Concrete	Gray	Flaking	2	17.9	Positive
1	B	003B	Electrical Room next to Boiler Room	Door	Metal	Brown	None	0	0	Negative
1	B	003B	Electrical Room next to Boiler Room	Door Frame	Metal	Brown	N/A	0	0	Negative
1	B	1	Auditorium Fan next to Electrical Room	Floor	Concrete	Gray	Cracking	0	0	Negative
1	B	1	Auditorium Fan next to Electrical Room	W1	Concrete	White	Flaking	0	0.2	Negative
1	B	1	Auditorium Fan next to Electrical Room	W1	Brick	Yellow	Flaking	0	0.2	Negative
1	B	1	Auditorium Fan next to Electrical Room	W2	Concrete	Yellow	Flaking	0	0.3	Negative
1	B	1	Auditorium Fan next to Electrical Room	W2	Brick	Yellow	Flaking	0	0.5	Negative
1	B	1	Auditorium Fan next to Electrical Room	W3	Concrete	Yellow	Flaking	0	0.3	Negative
1	B	1	Auditorium Fan next to Electrical Room	W4	Concrete	White	Flaking	0	0.1	Negative
1	B	1	Auditorium Fan next to Electrical Room	W4	Brick	Yellow	Flaking	0	0.6	Negative
1	B	1	Auditorium Fan next to Electrical Room	Ceiling	Concrete	White	Cracking	0	0.3	Negative
1	B	1	Auditorium Fan next to Electrical Room	Pipe	Metal	White	Flaking	8	0.8	Positive
1	B	1	Auditorium Fan next to Electrical Room	Duct	Metal	Silver	None	0	2.1	Positive
1	B	1	Auditorium Fan next to Electrical Room	Fan Unit Exterior	Metal	Silver	Flaking	18	2.5	Positive
1	B	1	Auditorium Fan next to Electrical Room	Flywheel	Metal	Gray	None	0	0	Negative
1	B	1	Auditorium Fan next to Electrical Room	Fan Motor	Metal	Green	None	0	0.2	Negative
1	B	1	Auditorium Fan next to Electrical Room	Airwash Floor	Concrete	Gray	Blistering	10	13.4	Positive
1	B	1	Auditorium Fan next to Electrical Room	Baffle	Metal	Gold	Cracking	0	0.2	Negative
1	B	1	Auditorium Fan next to Electrical Room	Airwash Interior	Metal	Silver	Cracking	20	12.2	Positive
1	B	1	Auditorium Fan next to Electrical Room	Airwash Interior	Metal	Orange	Flaking	20	13.2	Positive
1	B	1	Auditorium Fan next to Electrical Room	Rollup Door	Metal	Gray	None	0	0	Negative
1	B	1	Auditorium Fan next to Electrical Room	Column	Concrete	Yellow	Flaking	0	0.4	Negative

		Dates: August 24 - September 19, 2022		Lead-Safe Certification Assessment Report						
		Inspector Name and Certificate Number: Kevin Rumbol 006794		Harding School						
		Inspection Company: ACER Associates, LLC		2000 Wakeling Street, Philadelphia, PA 19124						
Element	Floor	Space #	On-Site Room Name	Component	Substrate Material	Color	Description of Damage	Damage Quantity (sf)	XRF Reading (mg/cm2)	XRF (positive/negative)
1	B	1	Auditorium Fan next to Electrical Room	Door	Metal	Brown	None	0	0	Negative
1	B	1	Auditorium Fan next to Electrical Room	Door Casing	Metal	Brown	None	0	0	Negative
1	B	1	Auditorium Fan next to Electrical Room	Door Stop	Metal	Brown	None	0	0	Negative
1	B	1	Auditorium Fan next to Electrical Room	Door Jamb	Metal	Brown	None	0	0	Negative
1	B	1	Auditorium Fan next to Electrical Room	Railing	Metal	Gray	None	0	0	Negative
1	B	001A	Fan Room Intake Hallway b/t Fan Rooms	Floor	Concrete	Gray	N/A	0	0	Negative
1	B	001A	Fan Room Intake Hallway b/t Fan Rooms	W1	Brick	White	None	0	0.03	Negative
1	B	001A	Fan Room Intake Hallway b/t Fan Rooms	W1	Concrete	Green	None	0	0.01	Negative
1	B	001A	Fan Room Intake Hallway b/t Fan Rooms	W2	Brick	White	None	0	0.03	Negative
1	B	001A	Fan Room Intake Hallway b/t Fan Rooms	W2	Concrete	Green	None	0	0.07	Negative
1	B	001A	Fan Room Intake Hallway b/t Fan Rooms	W3	Brick	White	None	0	0.02	Negative
1	B	001A	Fan Room Intake Hallway b/t Fan Rooms	W3	Concrete	Green	None	0	0	Negative
1	B	001A	Fan Room Intake Hallway b/t Fan Rooms	W4	Brick	White	None	0	0.02	Negative
1	B	001A	Fan Room Intake Hallway b/t Fan Rooms	W4	Concrete	Green	None	0	0.06	Negative
1	B	001A	Fan Room Intake Hallway b/t Fan Rooms	Ceiling	Concrete	White	N/A	0	0	Negative
1	B	001A	Fan Room Intake Hallway b/t Fan Rooms	Fan Unit Exterior	Metal	White	Flaking	4	2.4	Positive
1	B	001A	Fan Room Intake Hallway b/t Fan Rooms	Pipe	Metal	White	Flaking	4	1.4	Positive
1	B	001A	Fan Room Intake Hallway b/t Fan Rooms	Door	Metal	Brown	N/A	0	0	Negative
1	B	001A	Fan Room Intake Hallway b/t Fan Rooms	Door Frame	Metal	Brown	N/A	0	0	Negative
1	B	001B	Fan Room next to First Floor Stairs	Floor	Concrete	Gray	Flaking	20	0.2	Negative
1	B	001B	Fan Room next to First Floor Stairs	W1	Brick	White	Flaking	22	0.2	Negative
1	B	001B	Fan Room next to First Floor Stairs	W1	Concrete	Green	Flaking	6	0.3	Negative
1	B	001B	Fan Room next to First Floor Stairs	W2	Brick	White	Flaking	120	0.1	Negative
1	B	001B	Fan Room next to First Floor Stairs	W3	Brick	White	Flaking	300	0.1	Negative
1	B	001B	Fan Room next to First Floor Stairs	W3	Concrete	Green	Flaking	10	0.3	Negative
1	B	001B	Fan Room next to First Floor Stairs	W4	Brick	White	Flaking	30	0.1	Negative
1	B	001B	Fan Room next to First Floor Stairs	W4	Concrete	Green	Flaking	4	0.4	Negative
1	B	001B	Fan Room next to First Floor Stairs	Ceiling	Concrete	White	Flaking	550	No Access	No Access
1	B	001B	Fan Room next to First Floor Stairs	Fan Unit Exterior	Metal	Silver	Flaking	15	3.2	Positive
1	B	001B	Fan Room next to First Floor Stairs	Pipe	Metal	White	Flaking	10	0.1	Negative
1	B	001B	Fan Room next to First Floor Stairs	Railing	Metal	Brown	Flaking	6	7.1	Positive
1	B	001B	Fan Room next to First Floor Stairs	Tread	Concrete	Gray	Flaking	2	2.7	Positive
1	B	001B	Fan Room next to First Floor Stairs	Riser	Concrete	Gray	None	0	12.5	Positive
1	B	001B	Fan Room next to First Floor Stairs	Door	Metal	Brown	Peeling	0	0	Negative
1	B	001B	Fan Room next to First Floor Stairs	Door Casing	Metal	Brown	Peeling	0	0	Negative
1	B	001B	Fan Room next to First Floor Stairs	Door Casing	Wood	Brown	Peeling	0	0	Negative
1	B	001B	Fan Room next to First Floor Stairs	Door Jamb	Metal	Brown	Peeling	0	0	Negative

		Dates: August 24 - September 19, 2022		Lead-Safe Certification Assessment Report						
		Inspector Name and Certificate Number: Kevin Rumbol 006794		Harding School						
		Inspection Company: ACER Associates, LLC		2000 Wakeling Street, Philadelphia, PA 19124						
Element	Floor	Space #	On-Site Room Name	Component	Substrate Material	Color	Description of Damage	Damage Quantity (sf)	XRF Reading (mg/cm2)	XRF (positive/negative)
1	B	001B	Fan Room next to First Floor Stairs	Door Stop	Metal	Brown	Peeling	0	0.1	Negative
1	B	001B	Fan Room next to First Floor Stairs	Airwash Door	Metal	Gray	None	0	7.4	Positive
1	B	001B	Fan Room next to First Floor Stairs	Airwash Interior	Metal	Gray	None	0	3	Positive
1	B	001B	Fan Room next to First Floor Stairs	Airwash Interior	Metal	Orange	None	0	4.1	Positive
1	B	001B	Fan Room next to First Floor Stairs	Baffle	Metal	Gold	Peeling	0	0.4	Negative
1	B	001B	Fan Room next to First Floor Stairs	Airwash Floor	Metal	Silver	Peeling	40	7	Positive
1	B	001B	Fan Room next to First Floor Stairs	Duct	Metal	White	None	0	2.1	Positive
1	B	001B	Fan Room next to First Floor Stairs	Fan Motor	Metal	Green	None	0	0.1	Negative
1	B	001B	Fan Room next to First Floor Stairs	Flywheel	Metal	Gray	None	0	0.1	Negative
1	B	5B	Intake Chamber next to Fan Room	Floor	Concrete	Gray	Cracking	0	0.1	Negative
1	B	5B	Intake Chamber next to Fan Room	W1	Brick	White	Cracking	0	0.2	Negative
1	B	5B	Intake Chamber next to Fan Room	W1	Concrete	White	Cracking	0	0	Negative
1	B	5B	Intake Chamber next to Fan Room	W2	Brick	White	Cracking	0	0.1	Negative
1	B	5B	Intake Chamber next to Fan Room	W2	Concrete	White	Cracking	0	0.3	Negative
1	B	5B	Intake Chamber next to Fan Room	W3	Brick	White	Cracking	0	0.1	Negative
1	B	5B	Intake Chamber next to Fan Room	W3	Concrete	White	Cracking	0	0.2	Negative
1	B	5B	Intake Chamber next to Fan Room	W4	Brick	White	Cracking	0	0.2	Negative
1	B	5B	Intake Chamber next to Fan Room	W4	Concrete	White	Cracking	0	0.2	Negative
1	B	5B	Intake Chamber next to Fan Room	Ceiling	Concrete	No Access	No Access	No Access	No Access	No Access
1	B	5B	Intake Chamber next to Fan Room	Door	Wood	Brown	Flaking	2	20.3	Positive
1	B	5B	Intake Chamber next to Fan Room	Door Casing	Wood	Brown	Flaking	2	10.1	Positive
1	B	5B	Intake Chamber next to Fan Room	Fan Unit Exterior	Metal	Green	Flaking	4	3.5	Positive
1	B	5B	Intake Chamber next to Fan Room	Rollup Door	Metal	White	Flaking	20	7.9	Positive
1	B	007B	Fan Room on Wakeling Street side	Floor	Concrete	Gray	Cracking	0	0.3	Negative
1	B	007B	Fan Room on Wakeling Street side	W1	Brick	White	Cracking	0	0	Negative
1	B	007B	Fan Room on Wakeling Street side	W1	Concrete	Yellow	None	0	0.2	Negative
1	B	007B	Fan Room on Wakeling Street side	W2	Brick	White	Cracking	0	0.1	Negative
1	B	007B	Fan Room on Wakeling Street side	W3	Brick	White	Cracking	0	0.6	Negative
1	B	007B	Fan Room on Wakeling Street side	W3	Concrete	White	Cracking	0	0.1	Negative
1	B	007B	Fan Room on Wakeling Street side	W4	Brick	White	Cracking	0	0.1	Negative
1	B	007B	Fan Room on Wakeling Street side	W4	Concrete	White	Cracking	0	0.3	Negative
1	B	007B	Fan Room on Wakeling Street side	Ceiling	Concrete	White	Cracking	0	0.4	Negative
1	B	007B	Fan Room on Wakeling Street side	Railing	Metal	Brown	Flaking	6	7.1	Positive
1	B	007B	Fan Room on Wakeling Street side	Tread	Metal	Gray	Flaking	2	6.8	Positive
1	B	007B	Fan Room on Wakeling Street side	Fan Unit Exterior	Metal	Gray	Flaking	18	6	Positive
1	B	007B	Fan Room on Wakeling Street side	Door	Metal	Brown	None	0	0.1	Negative
1	B	007B	Fan Room on Wakeling Street side	Door Casing	Metal	Brown	None	0	0	Negative

		Dates: August 24 - September 19, 2022		Lead-Safe Certification Assessment Report						
		Inspector Name and Certificate Number: Kevin Rumbol 006794		Harding School						
		Inspection Company: ACER Associates, LLC		2000 Wakeling Street, Philadelphia, PA 19124						
Element	Floor	Space #	On-Site Room Name	Component	Substrate Material	Color	Description of Damage	Damage Quantity (sf)	XRF Reading (mg/cm2)	XRF (positive/negative)
1	B	007B	Fan Room on Wakeling Street side	Door Jamb	Metal	Brown	None	0	0	Negative
1	B	007B	Fan Room on Wakeling Street side	Door Stop	Metal	Brown	None	0	0	Negative
1	B	007B	Fan Room on Wakeling Street side	Stringer	Concrete	Gray	Cracking	0	0.1	Negative
1	B	007B	Fan Room on Wakeling Street side	Riser	Concrete	Gray	Cracking	0	0.3	Negative
1	B	007B	Fan Room on Wakeling Street side	Column	Concrete	White	Cracking	0	0.4	Negative
1	B	007B	Fan Room on Wakeling Street side	Airwash Interior	Metal	Black	Cracking	50	5.7	Positive
1	B	007B	Fan Room on Wakeling Street side	Baffle	Metal	Gold	Cracking	0	0.2	Negative
1	B	007B	Fan Room on Wakeling Street side	Pipe	Metal	Gray	Cracking	0	0.1	Negative
1	B	007B	Fan Room on Wakeling Street side	Duct	Metal	White	None	0	3.5	Positive
1	B	007B	Fan Room on Wakeling Street side	Return Plenum Walls	Concrete	Yellow	None	0	0.3	Negative
1	B	007B	Fan Room on Wakeling Street side	Return Plenum Floor	Concrete	Gray	None	0	0.2	Negative
1	3	319	Classroom 319	Floor	N/A	N/A	N/A	0	N/A	N/A
1	3	319	Classroom 319	W1	Plaster	Tan	Flaking	10	15.9	Positive
1	3	319	Classroom 319	W2	Plaster	Tan	None	0	15.9	Positive
1	3	319	Classroom 319	W3	Plaster	Tan	None	0	15.9	Positive
1	3	319	Classroom 319	W4	Plaster	Tan	None	0	15.9	Positive
1	3	319	Classroom 319	Ceiling	Plaster	Tan	Flaking	386	35.7	Positive
1	3	319	Classroom 319	Pipe	Metal	Tan	Cracking	5	24	Positive
1	3	319	Classroom 319	Radiator	Metal	Silver	None	0	0.5	Negative
1	3	319B	Women's Restroom next to Classroom 319	Floor	N/A	N/A	N/A	0	N/A	N/A
1	3	319B	Women's Restroom next to Classroom 319	W1	N/A	N/A	N/A	0	N/A	N/A
1	3	319B	Women's Restroom next to Classroom 319	W2	Plaster	Tan	Chipping	1	27.8	Positive
1	3	319B	Women's Restroom next to Classroom 319	W3	Plaster	Tan	Chipping	6	27.8	Positive
1	3	319B	Women's Restroom next to Classroom 319	W4	Plaster	Tan	Chipping	3	27.8	Positive
1	3	319B	Women's Restroom next to Classroom 319	Ceiling	Plaster	Tan	Flaking	77	33.4	Positive
1	3	319C	Women's Restroom next to Classroom 319	Floor	N/A	N/A	N/A	0	N/A	N/A
1	3	319C	Women's Restroom next to Classroom 319	W1	Plaster	Tan	None	0	27.1	Positive
1	3	319C	Women's Restroom next to Classroom 319	W2	Plaster	Tan	Efflorescence	5	27.1	Positive
1	3	319C	Women's Restroom next to Classroom 319	W3	Plaster	Tan	Flaking	8	27.1	Positive
1	3	319C	Women's Restroom next to Classroom 319	W4	Plaster	Tan	None	0	27.1	Positive
1	3	319C	Women's Restroom next to Classroom 319	Ceiling	Plaster	Tan	Cracking	5	23.1	Positive
1	3	319C	Women's Restroom next to Classroom 319	Wall Baseboard	Concrete	Gray	Chipping	5	1.4	Positive
1	3	319C	Women's Restroom next to Classroom 319	Pipe	Metal	Tan	Chipping	10	22.6	Positive
1	3	320	Classroom 320	Floor	N/A	N/A	N/A	0	N/A	N/A
1	3	320	Classroom 320	W1	Plaster	Yellow	Chipping	5	15.8	Positive
1	3	320	Classroom 320	W2	Plaster	Yellow	None	0	15.8	Positive
1	3	320	Classroom 320	W3	Plaster	Yellow	Flaking	26	15.8	Positive

		Dates: August 24 - September 19, 2022		Lead-Safe Certification Assessment Report							
		Inspector Name and Certificate Number: Kevin Rumbol 006794		Harding School							
		Inspection Company: ACER Associates, LLC		2000 Wakeling Street, Philadelphia, PA 19124							
Element	Floor	Space #	On-Site Room Name	Component	Substrate Material	Color	Description of Damage	Damage Quantity (sf)	XRF Reading (mg/cm2)	XRF (positive/negative)	
1	3	320	Classroom 320	W4	Plaster	Yellow	None	0	15.8	Positive	
1	3	320	Classroom 320	Radiator	Metal	Silver	Chipping	32	1	Positive	
1	3	320	Classroom 320	Ceiling	Plaster	Tan	Flaking	7	34.1	Positive	
1	3	320	Classroom 320	Baseboard	Wood	Brown	None	0	0.14	Negative	
1	3	320	Classroom 320	Door Frame	Wood	Brown	N/A	0	0.14	Negative	
1	3	321	Classroom 321	Floor	N/A	N/A	N/A	0	N/A	N/A	
1	3	321	Classroom 321	W1	Plaster	Blue	Chipping	1	24	Positive	
1	3	321	Classroom 321	W2	Plaster	Blue	None	0	24	Positive	
1	3	321	Classroom 321	W3	Plaster	Blue	Efflorescence	15	24	Positive	
1	3	321	Classroom 321	W4	Plaster	Blue	None	0	24	Positive	
1	3	321	Classroom 321	Ceiling	N/A	N/A	N/A	0	N/A	N/A	
1	3	321	Classroom 321	Radiator	Metal	Silver	None	0	0.01	Negative	
1	3	321	Classroom 321	Pipe	Metal	Blue	None	0	0.08	Negative	
1	3	321	Classroom 321	Baseboard	Wood	Brown	None	0	0.11	Negative	
1	3	321	Classroom 321	Door Frame	Wood	Brown	N/A	0	0.05	Negative	
1	3	322	Classroom 322	Floor	N/A	N/A	N/A	0	N/A	N/A	
1	3	322	Classroom 322	W1	Plaster	Tan	None	0	18.8	Positive	
1	3	322	Classroom 322	W2	Plaster	Tan	Chipping	1	18.8	Positive	
1	3	322	Classroom 322	W3	Plaster	Tan	Efflorescence	16	18.8	Positive	
1	3	322	Classroom 322	W4	Plaster	Tan	None	0	18.8	Positive	
1	3	322	Classroom 322	Ceiling	Plaster	Tan	Flaking	682	5.8	Positive	
1	3	322	Classroom 322	Radiator	Metal	Silver	None	0	0.5	Negative	
1	3	322	Classroom 322	Baseboard	Wood	Brown	None	0	0.13	Negative	
1	3	322	Classroom 322	Chalkboard Frame	Wood	Brown	None	0	0.1	Negative	
1	3	322	Classroom 322	Door Frame	Wood	Brown	N/A	0	0.04	Negative	
1	3	322	Classroom 322	Door	Wood	Brown	N/A	0	0.06	Negative	
1	3	323	Classroom 323	Floor	N/A	N/A	N/A	0	N/A	N/A	
1	3	323	Classroom 323	W1	Plaster	Blue	Chipping	3	12.5	Positive	
1	3	323	Classroom 323	W2	Plaster	Blue	None	0	12.5	Positive	
1	3	323	Classroom 323	W3	Plaster	Blue	Flaking	16	12.5	Positive	
1	3	323	Classroom 323	W4	Plaster	Blue	None	0	12.5	Positive	
1	3	323	Classroom 323	Ceiling	N/A	N/A	N/A	0	N/A	N/A	
1	3	323	Classroom 323	Radiator	Metal	Silver	None	0	0.01	Negative	
1	3	323	Classroom 323	Baseboard	Wood	Brown	None	0	0.12	Negative	
1	3	323	Classroom 323	Chalkboard Frame	Wood	Brown	None	0	0.08	Negative	
1	3	323	Classroom 323	Door Frame	Wood	Brown	N/A	0	0.05	Negative	
1	3	323	Classroom 323	Door	Wood	Brown	N/A	0	0.03	Negative	

		Dates: August 24 - September 19, 2022		Lead-Safe Certification Assessment Report							
		Inspector Name and Certificate Number: Kevin Rumbol 006794		Harding School							
		Inspection Company: ACER Associates, LLC		2000 Wakeling Street, Philadelphia, PA 19124							
Element	Floor	Space #	On-Site Room Name	Component	Substrate Material	Color	Description of Damage	Damage Quantity (sf)	XRF Reading (mg/cm ²)	XRF (positive/negative)	
1	3	324	Classroom 324	W1	Plaster	Tan	Chipping	10	18.5	Positive	
1	3	324	Classroom 324	W2	Plaster	Tan	Chipping	8	18.5	Positive	
1	3	324	Classroom 324	W3	Plaster	Tan	Flaking	16	18.5	Positive	
1	3	324	Classroom 324	W4	Plaster	Tan	None	0	18.5	Positive	
1	3	324	Classroom 324	Ceiling	Plaster	Tan	Flaking	836	35.2	Positive	
1	3	324	Classroom 324	Radiator	Metal	Silver	Chipping	32	0.7	Positive	
1	3	324	Classroom 324	Baseboard	Wood	Brown	None	0	0.07	Negative	
1	3	324	Classroom 324	Window Frame	Wood	Brown	N/A	0	0.09	Negative	
1	3	324	Classroom 324	Door Frame	Wood	Brown	N/A	0	0.12	Negative	
1	3	324	Classroom 324	Chalkboard Frame	Wood	Brown	None	0	0.04	Negative	
1	3	325	Classroom 325	Floor	N/A	N/A	N/A	0	N/A	N/A	
1	3	325	Classroom 325	W1	Plaster	Tan	None	0	16.3	Positive	
1	3	325	Classroom 325	W2	Plaster	Tan	Flaking	1	16.3	Positive	
1	3	325	Classroom 325	W3	Plaster	Tan	Flaking	10	16.3	Positive	
1	3	325	Classroom 325	W4	Plaster	Tan	None	0	16.3	Positive	
1	3	325	Classroom 325	Ceiling	Plaster	Tan	Flaking	714	33.3	Positive	
1	3	325	Classroom 325	Radiator	Metal	Silver	None	0	0.03	Negative	
1	3	326	Classroom 326	Floor	N/A	N/A	N/A	0	N/A	N/A	
1	3	326	Classroom 326	W1	Plaster	Tan	Chipping	5	21.1	Positive	
1	3	326	Classroom 326	W2	Plaster	Tan	Flaking	20	21.1	Positive	
1	3	326	Classroom 326	W3	Plaster	Tan	Flaking	6	21.1	Positive	
1	3	326	Classroom 326	W4	Plaster	Tan	Cracking	2	21.1	Positive	
1	3	326	Classroom 326	Ceiling	Plaster	Tan	Flaking	325	36.6	Positive	
1	3	326	Classroom 326	Radiator	Metal	Silver	None	0	0.02	Negative	
1	3	326	Classroom 326	Door Frame	Wood	Brown	N/A	0	0.05	Negative	
1	3	326	Classroom 326	Door	Wood	Brown	N/A	0	0.05	Negative	
1	3	326	Classroom 326	Chalkboard Frame	Wood	Brown	None	0	0.11	Negative	
1	3	326A	Men's Restroom next to Classroom 326	Floor	N/A	N/A	N/A	0	N/A	N/A	
1	3	326A	Men's Restroom next to Classroom 326	W1	Plaster	Tan	None	0	17.3	Positive	
1	3	326A	Men's Restroom next to Classroom 326	W2	Plaster	Tan	Flaking	2	17.3	Positive	
1	3	326A	Men's Restroom next to Classroom 326	W3	Plaster	Tan	Efflorescence	6	17.3	Positive	
1	3	326A	Men's Restroom next to Classroom 326	W4	Plaster	Tan	None	0	17.3	Positive	
1	3	326A	Men's Restroom next to Classroom 326	Ceiling	Plaster	Tan	Flaking	180	25.3	Positive	
1	3	326A	Men's Restroom next to Classroom 326	Radiator	Metal	Silver	None	0	0.5	Negative	
1	3	326A	Men's Restroom next to Classroom 326	Baseboard	Wood	Brown	None	0	0.16	Negative	
1	3	326B	Men's Restroom next to Classroom 326	Floor	N/A	N/A	N/A	0	N/A	N/A	
1	3	326B	Men's Restroom next to Classroom 326	W1	Plaster	Tan	Efflorescence	1	29.5	Positive	

		Dates: August 24 - September 19, 2022		Lead-Safe Certification Assessment Report							
		Inspector Name and Certificate Number: Kevin Rumbol 006794		Harding School							
		Inspection Company: ACER Associates, LLC		2000 Wakeling Street, Philadelphia, PA 19124							
Element	Floor	Space #	On-Site Room Name	Component	Substrate Material	Color	Description of Damage	Damage Quantity (sf)	XRF Reading (mg/cm2)	XRF (positive/negative)	
1	3	326B	Men's Restroom next to Classroom 326	W2	Plaster	Tan	None	0	29.5	Positive	
1	3	326B	Men's Restroom next to Classroom 326	W3	Plaster	Tan	Flaking	2	29.5	Positive	
1	3	326B	Men's Restroom next to Classroom 326	W4	Plaster	Tan	Flaking	3	29.5	Positive	
1	3	326B	Men's Restroom next to Classroom 326	Ceiling	Plaster	Tan	Flaking	5	25.6	Positive	
1	3	326B	Men's Restroom next to Classroom 326	Baseboard	Wood	Brown	Chipping	6	2	Positive	
1	3	326B	Men's Restroom next to Classroom 326	Radiator	Metal	Silver	None	0	0.6	Negative	
1	3	302	Classroom 302	Floor	N/A	N/A	N/A	0	N/A	N/A	
1	3	302	Classroom 302	W1	Plaster	Blue	Chipping	5	15.3	Positive	
1	3	302	Classroom 302	W2	Plaster	Blue	None	0	15.3	Positive	
1	3	302	Classroom 302	W3	Plaster	Blue	Flaking	16	15.3	Positive	
1	3	302	Classroom 302	W4	Plaster	Blue	Flaking	1	15.3	Positive	
1	3	302	Classroom 302	Ceiling	Plaster	Tan	Flaking	500	39.8	Positive	
1	3	302	Classroom 302	Radiator	Metal	Silver	None	0	0.4	Negative	
1	3	302	Classroom 302	Chalkboard Frame	Wood	Brown	None	0	0.05	Negative	
1	3	302	Classroom 302	Baseboard	Wood	Brown	None	0	0.06	Negative	
1	3	302	Classroom 302	Door Frame	Wood	Brown	N/A	0	0.05	Negative	
1	3	302	Classroom 302	Window Frame	Wood	Brown	N/A	0	0.05	Negative	
1	3	S33	Stairs across from Classroom 302	Floor	N/A	N/A	N/A	0	N/A	N/A	
1	3	S33	Stairs across from Classroom 302	W1	Concrete	Tan	Cracking	5	33.1	Positive	
1	3	S33	Stairs across from Classroom 302	W2	Concrete	Tan	Cracking	5	33.1	Positive	
1	3	S33	Stairs across from Classroom 302	W2	Plaster	Tan	Cracking	3	32.5	Positive	
1	3	S33	Stairs across from Classroom 302	W3	Concrete	Tan	Cracking	1	33.1	Positive	
1	3	S33	Stairs across from Classroom 302	Ceiling	Plaster	Tan	Chipping	205	1	Positive	
1	3	S33	Stairs across from Classroom 302	Stair Riser	Concrete	Brown	Flaking	1	10.3	Positive	
1	3	S33	Stairs across from Classroom 302	Stair Tread	Concrete	Brown	None	0	0.05	Negative	
1	3	S33	Stairs across from Classroom 302	Stair Stringer	Concrete	Brown	None	0	10.7	Positive	
1	3	S33	Stairs across from Classroom 302	Stair Newel Post	Metal	Brown	Chipping	8	2.5	Positive	
1	3	S33	Stairs across from Classroom 302	Stair Ballaster	Metal	Brown	Chipping	15	4.8	Positive	
1	3	S36	Fire Stair	Floor	Concrete	Gray	Flaking	42	2.2	Positive	
1	3	S36	Fire Stair	Ceiling	Concrete	White	Flaking	165	16.4	Positive	
1	3	S36	Fire Stair	W1	Brick	White	Flaking	55	27.8	Positive	
1	3	S36	Fire Stair	W2	Brick	White	Flaking	62	27.8	Positive	
1	3	S36	Fire Stair	W3	Brick	White	Flaking	75	27.8	Positive	
1	3	S36	Fire Stair	W4	Brick	White	Flaking	36	27.8	Positive	
1	3	S36	Fire Stair	Stair Riser	Concrete	Gray	Chipping	2	2.9	Positive	
1	3	S36	Fire Stair	Stair Tread	Concrete	Gray	Chipping	1	3.8	Positive	
1	3	S36	Fire Stair	Stair Stringer	Concrete	Gray	Chipping	2	2.5	Positive	

		Dates: August 24 - September 19, 2022		Lead-Safe Certification Assessment Report						
		Inspector Name and Certificate Number: Kevin Rumbol 006794		Harding School						
		Inspection Company: ACER Associates, LLC		2000 Wakeling Street, Philadelphia, PA 19124						
Element	Floor	Space #	On-Site Room Name	Component	Substrate Material	Color	Description of Damage	Damage Quantity (sf)	XRF Reading (mg/cm2)	XRF (positive/negative)
1	3	S36	Fire Stair	Stair Railing	Metal	Gray	Chipping	4	2.5	Positive
1	3	S36	Fire Stair	Divider	Metal	Gray	Chipping	0	0.6	Negative
1	3	S36	Fire Stair	Window Frame	Metal	Brown	None	0	0	Negative
1	3	S36	Fire Stair	Grate	Metal	Gray	Flaking	6	26.8	Positive
1	3	S36	Fire Stair	Pipe	Metal	White	Flaking	8	15.8	Positive
1	3	S36	Fire Stair	Door	Metal	Brown	None	0	0	Negative
1	3	S36	Fire Stair	Door Frame	Metal	Brown	None	0	0	Negative
1	3	S35	Fire Stair	Floor	Concrete	Gray	Flaking	0	0.4	Negative
1	3	S35	Fire Stair	Ceiling	Concrete	White	Flaking	17	2.5	Positive
1	3	S35	Fire Stair	W1	Brick	White	Flaking	42	11.1	Positive
1	3	S35	Fire Stair	W2	Brick	White	Flaking	21	11.1	Positive
1	3	S35	Fire Stair	W3	Brick	White	Flaking	13	11.1	Positive
1	3	S35	Fire Stair	W4	Brick	White	Flaking	22	11.1	Positive
1	3	S35	Fire Stair	Stair Riser	Concrete	Gray	Chipping	6	2.9	Positive
1	3	S35	Fire Stair	Stair Tread	Concrete	Gray	Chipping	2	2	Positive
1	3	S35	Fire Stair	Stair Stringer	Concrete	Gray	None	0	4.2	Positive
1	3	S35	Fire Stair	Stair Railing	Metal	Gray	None	0	0.4	Negative
1	3	S35	Fire Stair	Divider	Metal	Gray	None	0	0.21	Negative
1	3	S35	Fire Stair	Window Frame	Metal	Brown	None	0	0	Negative
1	3	S35	Fire Stair	Grate	Metal	Gray	Flaking	12	35	Positive
1	3	S35	Fire Stair	Pipe	Metal	Gray	Flaking	4	2.8	Positive
1	3	S35	Fire Stair	Door	Metal	Brown	None	0	0	Negative
1	3	S35	Fire Stair	Door Frame	Metal	Brown	None	0	0	Negative
1	3	304	Classroom 304	Floor	N/A	N/A	N/A	0	N/A	N/A
1	3	304	Classroom 304	W1	Plaster	Blue	Chipping	5	19.4	Positive
1	3	304	Classroom 304	W2	Plaster	Blue	None	0	19.4	Positive
1	3	304	Classroom 304	W3	Plaster	Blue	Flaking	16	19.4	Positive
1	3	304	Classroom 304	W4	Plaster	Blue	None	0	19.4	Positive
1	3	304	Classroom 304	Ceiling	Plaster	Tan	Flaking	325	36.6	Positive
1	3	304	Classroom 304	Radiator	Metal	Silver	None	0	0.02	Negative
1	3	304	Classroom 304	Baseboard	Wood	Brown	None	0	0.04	Negative
1	3	304	Classroom 304	Chalkboard Frame	Wood	Brown	None	0	0.07	Negative
1	3	304	Classroom 304	Window Frame	Wood	Brown	N/A	0	0.05	Negative
1	3	304	Classroom 304	Door Frame	Wood	Brown	N/A	0	0.03	Negative
1	3	300	Boy's Restroom across from Classroom 304	Floor	N/A	N/A	N/A	0	N/A	N/A
1	3	300	Boy's Restroom across from Classroom 304	W1	N/A	N/A	N/A	0	N/A	N/A
1	3	300	Boy's Restroom across from Classroom 304	W2	N/A	N/A	N/A	0	N/A	N/A
1	3	300	Boy's Restroom across from Classroom 304	W3	N/A	N/A	N/A	0	N/A	N/A

		Dates: August 24 - September 19, 2022		Lead-Safe Certification Assessment Report						
		Inspector Name and Certificate Number: Kevin Rumbol 006794		Harding School						
		Inspection Company: ACER Associates, LLC		2000 Wakeling Street, Philadelphia, PA 19124						
Element	Floor	Space #	On-Site Room Name	Component	Substrate Material	Color	Description of Damage	Damage Quantity (sf)	XRF Reading (mg/cm2)	XRF (positive/negative)
1	3	300	Boy's Restroom across from Classroom 304	W4	N/A	N/A	N/A	0	N/A	N/A
1	3	300	Boy's Restroom across from Classroom 304	Ceiling	Plaster	Tan	None	0	0	Negative
1	3	300A	Custodial Closet across from Classroom 304	Floor	No Access	No Access	No Access	No Access	No Access	No Access
1	3	300A	Custodial Closet across from Classroom 304	W1	No Access	No Access	No Access	No Access	No Access	No Access
1	3	300A	Custodial Closet across from Classroom 304	W2	No Access	No Access	No Access	No Access	No Access	No Access
1	3	300A	Custodial Closet across from Classroom 304	W3	No Access	No Access	No Access	No Access	No Access	No Access
1	3	300A	Custodial Closet across from Classroom 304	W4	No Access	No Access	No Access	No Access	No Access	No Access
1	3	300A	Custodial Closet across from Classroom 304	Ceiling	No Access	No Access	No Access	No Access	No Access	No Access
1	3	300PC	Pipe Chase	Floor	N/A	N/A	N/A	0	N/A	N/A
1	3	300PC	Pipe Chase	W1	N/A	N/A	N/A	0	N/A	N/A
1	3	300PC	Pipe Chase	W2	N/A	N/A	N/A	0	N/A	N/A
1	3	300PC	Pipe Chase	W3	N/A	N/A	N/A	0	N/A	N/A
1	3	300PC	Pipe Chase	W4	N/A	N/A	N/A	0	N/A	N/A
1	3	300PC	Pipe Chase	Ceiling	N/A	N/A	N/A	0	N/A	N/A
1	3	301	Classroom 301	Floor	Concrete	Brown	None	0	0.01	Negative
1	3	301	Classroom 301	W1	Brick	Tan	Chipping	1	17.8	Positive
1	3	301	Classroom 301	W2	Sheetrock	Tan	N/A	0	0.02	Negative
1	3	301	Classroom 301	W3	Brick	Tan	Chipping	1	17.8	Positive
1	3	301	Classroom 301	W4	Sheetrock	Tan	N/A	0	0.02	Negative
1	3	301	Classroom 301	Ceiling	N/A	N/A	N/A	0	N/A	N/A
1	3	301	Classroom 301	Baseboard	Concrete	Tan	Chipping	26	2.3	Positive
1	3	301	Classroom 301	Radiator Cover	Metal	Tan	N/A	0	0.01	Negative
1	3	301	Classroom 301	Door Frame	Wood	Brown	N/A	0	0.03	Negative
1	3	301	Classroom 301	Door	Wood	Brown	N/A	0	0.02	Negative
1	3	301A	Classroom 301 Closet	Floor	No Access	No Access	No Access	0	N/A	No Access
1	3	301A	Classroom 301 Closet	W1	No Access	No Access	No Access	0	N/A	No Access
1	3	301A	Classroom 301 Closet	W2	No Access	No Access	No Access	0	N/A	No Access
1	3	301A	Classroom 301 Closet	W3	CMU	No Access	No Access	0	N/A	No Access
1	3	301A	Classroom 301 Closet	W4	No Access	No Access	No Access	0	N/A	No Access
1	3	301A	Classroom 301 Closet	Ceiling	No Access	No Access	No Access	0	N/A	No Access
1	3	305	Classroom 305	Floor	Wood	Clear	N/A	0	N/A	N/A
1	3	305	Classroom 305	W1	Plaster	Blue	Chipping	6	28.5	Positive
1	3	305	Classroom 305	W2	Plaster	Blue	Flaking	7	28.5	Positive
1	3	305	Classroom 305	W3	Plaster	Blue	Flaking	16	28.5	Positive
1	3	305	Classroom 305	W4	Plaster	Blue	None	0	28.5	Positive
1	3	305	Classroom 305	Ceiling	Plaster	Tan	Flaking	682	36.2	Positive
1	3	305	Classroom 305	Radiator	Metal	Silver	None	0	0.04	Negative
1	3	305	Classroom 305	Baseboard	Wood	Brown	None	0	0.07	Negative

		Dates: August 24 - September 19, 2022		Lead-Safe Certification Assessment Report						
		Inspector Name and Certificate Number: Kevin Rumbol 006794		Harding School						
		Inspection Company: ACER Associates, LLC		2000 Wakeling Street, Philadelphia, PA 19124						
Element	Floor	Space #	On-Site Room Name	Component	Substrate Material	Color	Description of Damage	Damage Quantity (sf)	XRF Reading (mg/cm2)	XRF (positive/negative)
1	3	305	Classroom 305	Chalkboard Frame	Wood	Brown	None	0	0.03	Negative
1	3	305	Classroom 305	Window Frame	Wood	Brown	N/A	0	0.05	Negative
1	3	305	Classroom 305	Door Frame	Wood	Brown	N/A	0	0.03	Negative
1	3	303	Vice Principal Office 303	Floor	N/A	N/A	N/A	0	N/A	N/A
1	3	303	Vice Principal Office 303	W1	Brick	Tan	None	0	15.5	Positive
1	3	303	Vice Principal Office 303	W2	Brick	Tan	None	0	15.5	Positive
1	3	303	Vice Principal Office 303	W3	Brick	Tan	Efflorescence	2	15.5	Positive
1	3	303	Vice Principal Office 303	W4	Brick	Tan	None	0	15.5	Positive
1	3	303	Vice Principal Office 303	Ceiling	Plaster	Tan	Cracking	244	31.7	Positive
1	3	303	Vice Principal Office 303	Baseboard	Concrete	Tan	Chipping	20	1.1	Positive
1	3	303	Vice Principal Office 303	Radiator Cover	Metal	Tan	N/A	0	0.02	Negative
1	3	S34	Stairs across from Classroom 305	Floor	N/A	N/A	N/A	0	N/A	N/A
1	3	S34	Stairs across from Classroom 305	W2	Concrete	Tan	Flaking	3	7.9	Positive
1	3	S34	Stairs across from Classroom 305	W3	Concrete	Tan	Cracking	3	7.9	Positive
1	3	S34	Stairs across from Classroom 305	W4	Concrete	Tan	Cracking	6	7.9	Positive
1	3	S34	Stairs across from Classroom 305	Ceiling	Plaster	Tan	Chipping	305	3.7	Positive
1	3	S34	Stairs across from Classroom 305	Stair Riser	Concrete	Brown	Flaking	3	9.1	Positive
1	3	S34	Stairs across from Classroom 305	Stair Stringer	Concrete	Brown	None	0	5.3	Positive
1	3	S34	Stairs across from Classroom 305	Stair Tread	Concrete	Brown	None	0	0.06	Negative
1	3	S34	Stairs across from Classroom 305	Stair Newel Post	Metal	Brown	Chipping	6	15.9	Positive
1	3	S34	Stairs across from Classroom 305	Stair Ballaster	Metal	Brown	Chipping	15	10.1	Positive
1	3	306	Classroom 306	Floor	N/A	N/A	N/A	0	N/A	N/A
1	3	306	Classroom 306	W1	Plaster	Tan	Flaking	2	14.2	Positive
1	3	306	Classroom 306	W2	Plaster	Tan	Flaking	8	14.2	Positive
1	3	306	Classroom 306	W3	Plaster	Tan	Flaking	8	14.2	Positive
1	3	306	Classroom 306	W4	N/A	N/A	N/A	0	N/A	N/A
1	3	306	Classroom 306	Ceiling	Plaster	Tan	Flaking	528	35	Positive
1	3	306	Classroom 306	Pipe	Metal	Tan	Cracking	1	22.8	Positive
1	3	306	Classroom 306	Radiator	Metal	Silver	None	0	0.3	Negative
1	3	306	Classroom 306	Baseboard	Wood	Brown	None	0	0.13	Negative
1	3	306	Classroom 306	Chalkboard Frame	Wood	Brown	None	0	0.07	Negative
1	3	306	Classroom 306	Door Frame	Wood	Brown	N/A	0	0.06	Negative
1	3	307A	Classroom 307A and 307B	Floor	N/A	N/A	N/A	0	N/A	N/A
1	3	307A	Classroom 307A and 307B	W1	Plaster	Purple	Flaking	3	17.2	Positive
1	3	307A	Classroom 307A and 307B	W2	N/A	N/A	N/A	0	N/A	N/A
1	3	307A	Classroom 307A and 307B	W3	Plaster	Blue	Flaking	16	17.2	Positive

		Dates: August 24 - September 19, 2022		Lead-Safe Certification Assessment Report						
		Inspector Name and Certificate Number: Kevin Rumbol 006794		Harding School						
		Inspection Company: ACER Associates, LLC		2000 Wakeling Street, Philadelphia, PA 19124						
Element	Floor	Space #	On-Site Room Name	Component	Substrate Material	Color	Description of Damage	Damage Quantity (sf)	XRF Reading (mg/cm2)	XRF (positive/negative)
1	3	307A	Classroom 307A and 307B	W4	N/A	N/A	N/A	0	N/A	N/A
1	3	307A	Classroom 307A and 307B	Ceiling	Plaster	Tan	Flaking	670	39.9	Positive
1	3	307A	Classroom 307A and 307B	Chalkboard Frame	Wood	Brown	Chipping	3	1.6	Positive
1	3	307A	Classroom 307A and 307B	Radiator	Metal	Silver	None	0	0.13	Negative
1	3	307A	Classroom 307A and 307B	Door Frame	Wood	Brown	N/A	0	0.08	Negative
1	3	308A	Classroom 308	Floor	N/A	N/A	N/A	0	N/A	N/A
1	3	308A	Classroom 308	W1	Plaster	Blue	Flaking	4	25.7	Positive
1	3	308A	Classroom 308	W2	N/A	N/A	N/A	0	N/A	N/A
1	3	308A	Classroom 308	W3	Plaster	Blue	Flaking	16	25.7	Positive
1	3	308A	Classroom 308	W4	N/A	N/A	N/A	0	N/A	N/A
1	3	308A	Classroom 308	Ceiling	Plaster	Tan	Flaking	800	40.3	Positive
1	3	309	Classroom 309	Floor	N/A	N/A	N/A	0	N/A	N/A
1	3	309	Classroom 309	W1	Plaster	Blue	None	0	12.4	Positive
1	3	309	Classroom 309	W2	Plaster	Blue	Chipping	2	12.4	Positive
1	3	309	Classroom 309	W3	Plaster	Blue	Flaking	12	12.4	Positive
1	3	309	Classroom 309	W4	Plaster	Blue	Flaking	2	12.4	Positive
1	3	309	Classroom 309	Ceiling	Plaster	Tan	Flaking	742	38.9	Positive
1	3	309	Classroom 309	Baseboard	Wood	Brown	None	0	0	Negative
1	3	309	Classroom 309	Radiator	Metal	Silver	None	0	0	Negative
1	3	309	Classroom 309	Door Frame	Wood	White	N/A	0	0	Negative
1	3	309	Classroom 309	Chalkboard Frame	Wood	White	None	0	0	Negative
1	3	309A	Classroom 309 Closet	Floor	N/A	N/A	N/A	0	N/A	N/A
1	3	309A	Classroom 309 Closet	W1	Plaster	Tan	None	0	12.7	Positive
1	3	309A	Classroom 309 Closet	W2	Plaster	Tan	Efflorescence	35	12.7	Positive
1	3	309A	Classroom 309 Closet	W3	Plaster	Tan	Efflorescence	45	12.7	Positive
1	3	309A	Classroom 309 Closet	W4	Plaster	Tan	Efflorescence	2	12.7	Positive
1	3	309A	Classroom 309 Closet	Ceiling	Plaster	Tan	Flaking	15	28.9	Positive
1	3	309A	Classroom 309 Closet	Door Frame	Metal	Silver	N/A	0	0	Negative
1	3	310	Classroom 310	Floor	N/A	N/A	N/A	0	N/A	N/A
1	3	310	Classroom 310	W1	Plaster	Blue	Chipping	2	10.4	Positive
1	3	310	Classroom 310	W2	Plaster	Blue	Chipping	2	10.4	Positive
1	3	310	Classroom 310	W3	Plaster	Blue	Flaking	14	10.4	Positive
1	3	310	Classroom 310	W4	Plaster	Blue	Chipping	2	10.4	Positive
1	3	310	Classroom 310	Ceiling	Plaster	Tan	Flaking	1000	37.2	Positive
1	3	310	Classroom 310	Radiator	Metal	Silver	Chipping	40	0.8	Positive
1	3	310	Classroom 310	Door Frame	Wood	Brown	N/A	0	0	Negative

		Dates: August 24 - September 19, 2022		Lead-Safe Certification Assessment Report						
		Inspector Name and Certificate Number: Kevin Rumbol 006794		Harding School						
		Inspection Company: ACER Associates, LLC		2000 Wakeling Street, Philadelphia, PA 19124						
Element	Floor	Space #	On-Site Room Name	Component	Substrate Material	Color	Description of Damage	Damage Quantity (sf)	XRF Reading (mg/cm ²)	XRF (positive/negative)
1	3	310	Classroom 310	Chalkboard Frame	Wood	Brown	None	0	0	Negative
1	3	310	Classroom 310	Baseboard	Wood	Brown	None	0	0	Negative
1	3	310A	Classroom 310 Closet	Floor	N/A	N/A	N/A	0	N/A	N/A
1	3	310A	Classroom 310 Closet	W1	Plaster	Blue	Cracking	20	18	Positive
1	3	310A	Classroom 310 Closet	W2	Plaster	Blue	Flaking	3	18	Positive
1	3	310A	Classroom 310 Closet	W3	Plaster	Blue	Efflorescence	60	18	Positive
1	3	310A	Classroom 310 Closet	W4	Plaster	Blue	Flaking	15	18	Positive
1	3	310A	Classroom 310 Closet	Ceiling	Plaster	Tan	Flaking	28	36.6	Positive
1	3	311	Classroom 311	Floor	N/A	N/A	N/A	0	N/A	N/A
1	3	311	Classroom 311	W1	Plaster	Blue	Chipping	5	25.6	Positive
1	3	311	Classroom 311	W2	Plaster	Blue	Chipping	8	25.6	Positive
1	3	311	Classroom 311	W3	Plaster	Blue	Efflorescence	10	25.6	Positive
1	3	311	Classroom 311	W4	Plaster	Blue	None	0	25.6	Positive
1	3	311	Classroom 311	Radiator	Metal	Silver	None	0	0	Negative
1	3	311	Classroom 311	Ceiling	Plaster	Tan	Flaking	880	39	Positive
1	3	311B	Small Storage Closet in Classroom 311	Floor	N/A	N/A	N/A	0	N/A	N/A
1	3	311B	Small Storage Closet in Classroom 311	W1	Plaster	Tan	Flaking	2	12.1	Positive
1	3	311B	Small Storage Closet in Classroom 311	W2	Plaster	Tan	Flaking	4	12.1	Positive
1	3	311B	Small Storage Closet in Classroom 311	W3	Plaster	Tan	Flaking	1	12.1	Positive
1	3	311B	Small Storage Closet in Classroom 311	W4	Plaster	Tan	Flaking	2	12.1	Positive
1	3	311B	Small Storage Closet in Classroom 311	Ceiling	Plaster	Tan	Flaking	15	9.6	Positive
1	3	311A	Large Storage Closet in Classroom 311	Floor	N/A	N/A	N/A	0	N/A	N/A
1	3	311A	Large Storage Closet in Classroom 311	W1	Plaster	Tan	Flaking	10	28.3	Positive
1	3	311A	Large Storage Closet in Classroom 311	W2	Plaster	Tan	Flaking	10	28.3	Positive
1	3	311A	Large Storage Closet in Classroom 311	W3	Plaster	Tan	Cracking	90	28.3	Positive
1	3	311A	Large Storage Closet in Classroom 311	W4	Plaster	Tan	Flaking	8	28.3	Positive
1	3	311A	Large Storage Closet in Classroom 311	Pipe	Metal	Tan	None	0	0.4	Negative
1	3	311A	Large Storage Closet in Classroom 311	Ceiling	Plaster	Tan	Flaking	110	27	Positive
1	3	312	Classroom 312	Floor	N/A	N/A	N/A	0	N/A	N/A
1	3	312	Classroom 312	W1	Plaster	Blue	Chipping	8	7.3	Positive
1	3	312	Classroom 312	W2	Plaster	Blue	Flaking	10	7.3	Positive
1	3	312	Classroom 312	W3	Plaster	Blue	Cracking	1	7.3	Positive
1	3	312	Classroom 312	W4	Plaster	Blue	Cracking	3	7.3	Positive
1	3	312	Classroom 312	Ceiling	Plaster	Tan	Flaking	264	41.5	Positive
1	3	312	Classroom 312	Radiator	Metal	Silver	None	0	0	Negative
1	3	312	Classroom 312	Door Casing	Metal	Tan	N/A	0	0	Negative
1	3	313	Classroom 313	Floor	N/A	N/A	N/A	0	N/A	N/A
1	3	313	Classroom 313	W1	Plaster	Blue	Cracking	3	10.6	Positive

		Dates: August 24 - September 19, 2022		Lead-Safe Certification Assessment Report							
		Inspector Name and Certificate Number: Kevin Rumbol 006794		Harding School							
		Inspection Company: ACER Associates, LLC		2000 Wakeling Street, Philadelphia, PA 19124							
Element	Floor	Space #	On-Site Room Name	Component	Substrate Material	Color	Description of Damage	Damage Quantity (sf)	XRF Reading (mg/cm2)	XRF (positive/negative)	
1	3	313	Classroom 313	W2	Plaster	Blue	None	0	10.6	Positive	
1	3	313	Classroom 313	W3	Plaster	Blue	Flaking	21	10.6	Positive	
1	3	313	Classroom 313	W4	Plaster	Blue	Flaking	7	10.6	Positive	
1	3	313	Classroom 313	Ceiling	Plaster	Tan	Flaking	880	34	Positive	
1	3	313	Classroom 313	Radiator	Metal	Silver	None	0	0	Negative	
1	3	313	Classroom 313	Baseboard	Wood	Brown	None	0	0	Negative	
1	3	314	Classroom 314	Floor	N/A	N/A	N/A	0	N/A	N/A	
1	3	314	Classroom 314	W1	Plaster	Tan	Chipping	4	17.6	Positive	
1	3	314	Classroom 314	W2	Plaster	Tan	None	0	17.6	Positive	
1	3	314	Classroom 314	W3	Plaster	Tan	Flaking	13	17.6	Positive	
1	3	314	Classroom 314	W4	Plaster	Tan	Flaking	2	17.6	Positive	
1	3	314	Classroom 314	Ceiling	Plaster	Tan	Flaking	704	33.4	Positive	
1	3	314	Classroom 314	Baseboard	Wood	Brown	None	0	0	Negative	
1	3	314	Classroom 314	Window Frame	Wood	Brown	N/A	0	0	Negative	
1	3	314	Classroom 314	Door Frame	Wood	Brown	N/A	0	0	Negative	
1	3	315	Office 315	Floor	N/A	N/A	N/A	0	N/A	N/A	
1	3	315	Office 315	W1	Brick	Tan	None	0	0	Negative	
1	3	315	Office 315	W2	Plaster	Tan	Chipping	2	7.3	Positive	
1	3	315	Office 315	W3	Plaster	Tan	None	0	7.3	Positive	
1	3	315	Office 315	W4	CMU	Tan	None	0	0	Negative	
1	3	315	Office 315	W4	Sheetrock	Tan	N/A	0	0	Negative	
1	3	315	Office 315	Ceiling	N/A	N/A	N/A	0	N/A	N/A	
1	3	315	Office 315	Baseboard	Concrete	Tan	Chipping	11	3.7	Positive	
1	3	S31	Stairs Next to Classroom 315	Floor	Concrete	Brown	None	0	0	Negative	
1	3	S31	Stairs Next to Classroom 315	W1	Concrete	Tan	Flaking	1	22.5	Positive	
1	3	S31	Stairs Next to Classroom 315	W2	Concrete	Tan	Cracking	9	7.9	Positive	
1	3	S31	Stairs Next to Classroom 315	W3	Concrete	Tan	Cracking	7	7.9	Positive	
1	3	S31	Stairs Next to Classroom 315	W4	Concrete	Tan	Cracking	90	7.9	Positive	
1	3	S31	Stairs Next to Classroom 315	Ceiling	Plaster	Tan	Chipping	236	21.9	Positive	
1	3	S31	Stairs Next to Classroom 315	Stair Newel Post	Metal	Brown	Chipping	11	8.6	Positive	
1	3	S31	Stairs Next to Classroom 315	Stair Ballaster	Metal	Brown	Chipping	15	4.4	Positive	
1	3	S31	Stairs Next to Classroom 315	Stair Stringer	Concrete	Brown	None	0	6.1	Positive	
1	3	S31	Stairs Next to Classroom 315	Stair Riser	Concrete	Brown	None	0	1.4	Positive	
1	3	S31	Stairs Next to Classroom 315	Stair Tread	Concrete	Brown	None	0	1.4	Positive	
1	3	S31	Stairs Next to Classroom 315	Radiator	Metal	Silver	None	0	0	Negative	
1	3	S31	Stairs Next to Classroom 315	Door	Metal	Red	N/A	0	0	Negative	
1	3	S31	Stairs Next to Classroom 315	Door Frame	Metal	Red	N/A	0	0	Negative	
1	3	S32	Stairs across from Classroom 318	Floor	Concrete	Brown	None	0	0.04	Negative	

		Dates: August 24 - September 19, 2022		Lead-Safe Certification Assessment Report						
		Inspector Name and Certificate Number: Kevin Rumbol 006794		Harding School						
		Inspection Company: ACER Associates, LLC		2000 Wakeling Street, Philadelphia, PA 19124						
Element	Floor	Space #	On-Site Room Name	Component	Substrate Material	Color	Description of Damage	Damage Quantity (sf)	XRF Reading (mg/cm2)	XRF (positive/negative)
1	3	S32	Stairs across from Classroom 318	W1	Plaster	Tan	Efflorescence	3	33.6	Positive
1	3	S32	Stairs across from Classroom 318	W2	Concrete	Tan	Cracking	8	33.6	Positive
1	3	S32	Stairs across from Classroom 318	W3	Plaster	Tan	None	0	33.6	Positive
1	3	S32	Stairs across from Classroom 318	W4	Concrete	Tan	Cracking	12	33.6	Positive
1	3	S32	Stairs across from Classroom 318	Ceiling	Plaster	Tan	Chipping	5	5.8	Positive
1	3	S32	Stairs across from Classroom 318	Stair Stringer	Concrete	Brown	Chipping	1	8.9	Positive
1	3	S32	Stairs across from Classroom 318	Stair Newel Post	Metal	Brown	Chipping	8	6.6	Positive
1	3	S32	Stairs across from Classroom 318	Stair Ballaster	Metal	Brown	Chipping	21	6.9	Positive
1	3	S32	Stairs across from Classroom 318	Stair Tread	Concrete	Brown	None	0	7.5	Positive
1	3	S32	Stairs across from Classroom 318	Stair Riser	Concrete	Brown	None	0	7.5	Positive
1	3	S32	Stairs across from Classroom 318	Radiator	Metal	Silver	None	0	0	Negative
1	3	317	Classroom 317	Floor	N/A	N/A	N/A	0	N/A	N/A
1	3	317	Classroom 317	W1	Brick	Blue	Chipping	2	3.2	Positive
1	3	317	Classroom 317	W2	CMU	Blue	None	0	0.07	Negative
1	3	317	Classroom 317	W3	Brick	Blue	Chipping	4	3.2	Positive
1	3	317	Classroom 317	W4	Brick	Blue	None	0	3.2	Positive
1	3	317	Classroom 317	Ceiling	Plaster	Tan	Flaking	625	33.2	Positive
1	3	317	Classroom 317	Baseboard	Concrete	Blue	Chipping	34	2.2	Positive
1	3	317	Classroom 317	Radiator Cover	Metal	Blue	N/A	0	0.07	Negative
1	3	318A	Girl's Restroom next to Classroom 317	Floor	N/A	N/A	N/A	0	N/A	N/A
1	3	318A	Girl's Restroom next to Classroom 317	W1	Plaster	Tan	None	0	23	Positive
1	3	318A	Girl's Restroom next to Classroom 317	W2	Plaster	Tan	Cracking	3	23	Positive
1	3	318A	Girl's Restroom next to Classroom 317	W3	Plaster	Tan	None	0	23	Positive
1	3	318A	Girl's Restroom next to Classroom 317	W4	Plaster	Tan	Flaking	2	23	Positive
1	3	318A	Girl's Restroom next to Classroom 317	Ceiling	Sheetrock	N/A	N/A	0	0	Negative
1	3	316	Classroom 316	Floor	N/A	N/A	N/A	0	N/A	N/A
1	3	316	Classroom 316	W1	Plaster	Tan	Chipping	1	7.6	Positive
1	3	316	Classroom 316	W2	Plaster	Tan	None	0	7.6	Positive
1	3	316	Classroom 316	W3	Plaster	Tan	Flaking	14	7.6	Positive
1	3	316	Classroom 316	W4	Plaster	Tan	None	0	7.6	Positive
1	3	316	Classroom 316	Ceiling	Plaster	Tan	Flaking	637	27.8	Positive
1	3	316	Classroom 316	Radiator Cover	Metal	Tan	N/A	0	0	Negative
1	3	316	Classroom 316	Baseboard	Wood	Brown	None	0	0	Negative
1	3	318	Classroom 318	Floor	N/A	N/A	N/A	0	N/A	N/A
1	3	318	Classroom 318	W1	Plaster	Tan	Chipping	5	21.2	Positive
1	3	318	Classroom 318	W2	Plaster	Tan	Chipping	2	21.2	Positive
1	3	318	Classroom 318	W3	Plaster	Tan	Flaking	30	21.2	Positive

		Dates: August 24 - September 19, 2022		Lead-Safe Certification Assessment Report							
		Inspector Name and Certificate Number: Kevin Rumbol 006794		Harding School							
		Inspection Company: ACER Associates, LLC		2000 Wakeling Street, Philadelphia, PA 19124							
Element	Floor	Space #	On-Site Room Name	Component	Substrate Material	Color	Description of Damage	Damage Quantity (sf)	XRF Reading (mg/cm2)	XRF (positive/negative)	
1	3	318	Classroom 318	W4	Plaster	Tan	None	0	21.2	Positive	
1	3	318	Classroom 318	Ceiling	Plaster	Tan	Flaking	499	32.1	Positive	
1	3	318	Classroom 318	Baseboard	Wood	Brown	None	0	0	Negative	
1	3	318	Classroom 318	Radiator	Metal	Silver	None	0	0	Negative	
1	3	318	Classroom 318	Door Frame	Wood	Brown	N/A	0	0	Negative	
1	3	318	Classroom 318	Door	Wood	Brown	N/A	0	0	Negative	
1	3	318	Classroom 318	Window Frame	Wood	Brown	N/A	0	0	Negative	
1	3	318	Classroom 318	Chalkboard Frame	Wood	Brown	None	0	0	Negative	
1	3	318B	Custodial Closet across from Classroom 318	Floor	No Access	No Access	No Access	No Access	No Access	No Access	
1	3	318B	Custodial Closet across from Classroom 318	W1	No Access	No Access	No Access	No Access	No Access	No Access	
1	3	318B	Custodial Closet across from Classroom 318	W2	No Access	No Access	No Access	No Access	No Access	No Access	
1	3	318B	Custodial Closet across from Classroom 318	W3	No Access	No Access	No Access	No Access	No Access	No Access	
1	3	318B	Custodial Closet across from Classroom 318	W4	No Access	No Access	No Access	No Access	No Access	No Access	
1	3	318B	Custodial Closet across from Classroom 318	Ceiling	No Access	No Access	No Access	No Access	No Access	No Access	
1	3	H316	3rd Floor Hallways	Floor	N/A	N/A	N/A	0	N/A	N/A	
1	3	H316	3rd Floor Hallways	W1	Plaster	Tan	Cracking	73	11.1	Positive	
1	3	H316	3rd Floor Hallways	W2	Plaster	Tan	None	0	11.1	Positive	
1	3	H316	3rd Floor Hallways	W3	Plaster	Tan	Flaking	122	11.1	Positive	
1	3	H316	3rd Floor Hallways	W4	Plaster	Tan	None	0	11.1	Positive	
1	3	H316	3rd Floor Hallways	Ceiling	Plaster	Tan	Flaking	1033	26.9	Positive	
1	3	H316	3rd Floor Hallways	Baseboard	Concrete	Brown	Chipping	15	2.3	Positive	
1	3	H316	3rd Floor Hallways	Radiator	Metal	Silver	None	0	0.5	Negative	
1	3	H316	3rd Floor Hallways	Chair Rail	Wood	Brown	N/A	0	0	Negative	
1	3	H316	3rd Floor Hallways	Lockers	Metal	Red	N/A	0	0	Negative	
1	3	H316	3rd Floor Hallways	Door Frame	Wood	Brown	N/A	0	0	Negative	
1	3	H315	3rd Floor Hallways	Floor	N/A	N/A	N/A	0	N/A	N/A	
1	3	H315	3rd Floor Hallways	W2	Plaster	Tan	Flaking	4	12.5	Positive	
1	3	H315	3rd Floor Hallways	W4	Plaster	Tan	Chipping	4	12.5	Positive	
1	3	H315	3rd Floor Hallways	Ceiling	Plaster	Tan	Flaking	482	29.7	Positive	
1	3	H315	3rd Floor Hallways	Baseboard	Concrete	Brown	Chipping	15	2.3	Positive	
1	3	H315	3rd Floor Hallways	Door	Wood	Brown	N/A	0	0	Negative	
1	3	H315	3rd Floor Hallways	Door Frame	Wood	Brown	N/A	0	0	Negative	
1	3	H315	3rd Floor Hallways	Lockers	Metal	Red	N/A	0	0	Negative	
1	3	H315	3rd Floor Hallways	Chair Rail	Wood	Brown	N/A	0	0	Negative	
1	3	H314	3rd Floor Hallways	Floor	N/A	N/A	N/A	0	N/A	N/A	
1	3	H314	3rd Floor Hallways	W1	Plaster	Tan	Flaking	103	12.7	Positive	
1	3	H314	3rd Floor Hallways	W2	Plaster	Tan	None	0	12.7	Positive	
1	3	H314	3rd Floor Hallways	W3	Plaster	Tan	Flaking	69	12.7	Positive	

		Dates: August 24 - September 19, 2022		Lead-Safe Certification Assessment Report							
		Inspector Name and Certificate Number: Kevin Rumbol 006794		Harding School							
		Inspection Company: ACER Associates, LLC		2000 Wakeling Street, Philadelphia, PA 19124							
Element	Floor	Space #	On-Site Room Name	Component	Substrate Material	Color	Description of Damage	Damage Quantity (sf)	XRF Reading (mg/cm2)	XRF (positive/negative)	
1	3	H314	3rd Floor Hallways	W4	Plaster	Tan	None	0	12.7	Positive	
1	3	H314	3rd Floor Hallways	Ceiling	Plaster	Tan	Flaking	910	25.2	Positive	
1	3	H314	3rd Floor Hallways	Baseboard	Concrete	Brown	Chipping	14	4.1	Positive	
1	3	H314	3rd Floor Hallways	Radiator	Metal	Silver	None	0	0	Negative	
1	3	H314	3rd Floor Hallways	Lockers	Metal	Red	N/A	0	0	Negative	
1	3	H314	3rd Floor Hallways	Door Frame	Wood	Brown	N/A	0	0	Negative	
1	3	H314	3rd Floor Hallways	Door	Wood	Brown	N/A	0	0	Negative	
1	3	H314	3rd Floor Hallways	Chair Rail	Wood	Brown	N/A	0	0	Negative	
1	3	H313	3rd Floor Hallways	Floor	N/A	N/A	N/A	0	N/A	N/A	
1	3	H313	3rd Floor Hallways	W2	Plaster	Tan	Cracking	4	14.3	Positive	
1	3	H313	3rd Floor Hallways	W4	Plaster	Tan	Chipping	8	14.3	Positive	
1	3	H313	3rd Floor Hallways	Ceiling	Plaster	Tan	Flaking	344	32.5	Positive	
1	3	H313	3rd Floor Hallways	Baseboard	Concrete	Brown	Chipping	9	2.4	Positive	
1	3	H313	3rd Floor Hallways	Chair Rail	Wood	Brown	N/A	0	0	Negative	
1	3	H313	3rd Floor Hallways	Door Frame	Wood	Brown	N/A	0	0	Negative	
1	2	224	Classroom 224	Floor	N/A	N/A	N/A	0	N/A	N/A	
1	2	224	Classroom 224	W1	Plaster	Blue	Chipping	3	26.2	Positive	
1	2	224	Classroom 224	W2	Plaster	Blue	Efflorescence	19	26.2	Positive	
1	2	224	Classroom 224	W3	Plaster	Blue	Flaking	16	26.2	Positive	
1	2	224	Classroom 224	W4	Plaster	Blue	Chipping	1	26.2	Positive	
1	2	224	Classroom 224	Ceiling	Plaster	Tan	Flaking	160	22.8	Positive	
1	2	224	Classroom 224	Pipe	Metal	Blue	Chipping	5	12.9	Positive	
1	2	224	Classroom 224	Radiator	Metal	Silver	None	0	0.6	Negative	
1	2	224	Classroom 224	Baseboard	Wood	Brown	None	0	0	Negative	
1	2	224	Classroom 224	Door Frame	Wood	Brown	N/A	0	0	Negative	
1	2	223	Classroom 223	Floor	N/A	N/A	N/A	0	N/A	N/A	
1	2	223	Classroom 223	W1	Plaster	Blue	None	0	1.6	Positive	
1	2	223	Classroom 223	W2	Plaster	Blue	Chipping	3	1.6	Positive	
1	2	223	Classroom 223	W3	Plaster	Blue	Flaking	16	1.6	Positive	
1	2	223	Classroom 223	W4	Plaster	Blue	None	0	1.6	Positive	
1	2	223	Classroom 223	Ceiling	Plaster	Tan	Flaking	35	28	Positive	
1	2	223	Classroom 223	Radiator	Metal	Silver	None	0	0.6	Negative	
1	2	222	Classroom 222	Floor	N/A	N/A	N/A	0	N/A	N/A	
1	2	222	Classroom 222	W1	Plaster	Blue	Chipping	9	20.7	Positive	
1	2	222	Classroom 222	W2	Plaster	Blue	Chipping	5	20.7	Positive	
1	2	222	Classroom 222	W3	Plaster	Blue	Flaking	26	20.7	Positive	
1	2	222	Classroom 222	W4	Plaster	Blue	Chipping	1	20.7	Positive	
1	2	222	Classroom 222	Ceiling	Plaster	Tan	Flaking	65	25.5	Positive	
1	2	222	Classroom 222	Radiator	Metal	Silver	Chipping	32	0.8	Positive	

			Dates: August 24 - September 19, 2022	Lead-Safe Certification Assessment Report							
			Inspector Name and Certificate Number: Kevin Rumbol 006794	Harding School							
			Inspection Company: ACER Associates, LLC	2000 Wakeling Street, Philadelphia, PA 19124							
Element	Floor	Space #	On-Site Room Name	Component	Substrate Material	Color	Description of Damage	Damage Quantity (sf)	XRF Reading (mg/cm2)	XRF (positive/negative)	
1	2	222	Classroom 222	Baseboard	Wood	Brown	None	0	0	Negative	
1	2	222	Classroom 222	Chalkboard Frame	Wood	Brown	None	0	0	Negative	
1	2	222	Classroom 222	Door Frame	Wood	Brown	N/A	0	0	Negative	
1	2	221	Classroom 221	Floor	N/A	N/A	N/A	0	N/A	N/A	
1	2	221	Classroom 221	W1	Plaster	Blue	Chipping	1	32.5	Positive	
1	2	221	Classroom 221	W2	Plaster	Blue	Chipping	7	32.5	Positive	
1	2	221	Classroom 221	W3	Plaster	Blue	Flaking	22	32.5	Positive	
1	2	221	Classroom 221	W4	Plaster	Blue	Chipping	14	32.5	Positive	
1	2	221	Classroom 221	Ceiling	Plaster	Tan	Flaking	70	33.9	Positive	
1	2	221	Classroom 221	Radiator	Metal	Silver	Chipping	24	1	Positive	
1	2	221	Classroom 221	Chalkboard Frame	Wood	Brown	None	0	0	Negative	
1	2	221	Classroom 221	Door Frame	Wood	Brown	N/A	0	0	Negative	
1	2	221	Classroom 221	Baseboard	Wood	Brown	None	0	0	Negative	
1	2	220	Classroom 220	Floor	N/A	N/A	N/A	0	N/A	N/A	
1	2	220	Classroom 220	W1	Plaster	Blue	Chipping	3	28.8	Positive	
1	2	220	Classroom 220	W2	Plaster	Blue	Chipping	2	28.8	Positive	
1	2	220	Classroom 220	W3	Plaster	Blue	Chipping	13	28.8	Positive	
1	2	220	Classroom 220	W4	Plaster	Blue	Chipping	6	28.8	Positive	
1	2	220	Classroom 220	Ceiling	Plaster	Tan	Flaking	265	36.9	Positive	
1	2	220	Classroom 220	Radiator	Metal	Silver	Chipping	7	0.9	Positive	
1	2	220	Classroom 220	Pipe	Metal	Tan	Chipping	6	24.1	Positive	
1	2	220	Classroom 220	Door Frame	Wood	Brown	N/A	0	0	Negative	
1	2	220	Classroom 220	Baseboard	Wood	Brown	None	0	0	Negative	
1	2	220	Classroom 220	Window Frame	Wood	Brown	N/A	0	0	Negative	
1	2	229	Storage Closet across from Classroom 220	Floor	No Access	No Access	No Access	0	N/A	No Access	
1	2	229	Storage Closet across from Classroom 220	W1	No Access	No Access	No Access	0	N/A	No Access	
1	2	229	Storage Closet across from Classroom 220	W2	No Access	No Access	No Access	0	N/A	No Access	
1	2	229	Storage Closet across from Classroom 220	W3	No Access	No Access	No Access	0	N/A	No Access	
1	2	229	Storage Closet across from Classroom 220	W4	No Access	No Access	No Access	0	N/A	No Access	
1	2	229	Storage Closet across from Classroom 220	Ceiling	No Access	No Access	No Access	0	N/A	No Access	
1	2	219	Classroom 219	Floor	N/A	N/A	N/A	0	N/A	N/A	
1	2	219	Classroom 219	W1	Plaster	Blue	Chipping	6	19.4	Positive	
1	2	219	Classroom 219	W2	Plaster	Blue	Chipping	7	19.4	Positive	
1	2	219	Classroom 219	W3	Plaster	Blue	Flaking	23	19.4	Positive	
1	2	219	Classroom 219	W4	Plaster	Blue	Chipping	2	19.4	Positive	
1	2	219	Classroom 219	Ceiling	Plaster	Tan	Flaking	273	36	Positive	
1	2	219	Classroom 219	Radiator	Metal	Silver	Chipping	28	1	Positive	

		Dates: August 24 - September 19, 2022		Lead-Safe Certification Assessment Report						
		Inspector Name and Certificate Number: Kevin Rumbol 006794		Harding School						
		Inspection Company: ACER Associates, LLC		2000 Wakeling Street, Philadelphia, PA 19124						
Element	Floor	Space #	On-Site Room Name	Component	Substrate Material	Color	Description of Damage	Damage Quantity (sf)	XRF Reading (mg/cm2)	XRF (positive/negative)
1	2	219	Classroom 219	Pipe	Metal	Blue	Chipping	7	1.8	Positive
1	2	219	Classroom 219	Baseboard	Wood	Brown	None	0	0	Negative
1	2	219	Classroom 219	Chalkboard Frame	Wood	Brown	None	0	0	Negative
1	2	219	Classroom 219	Door Frame	Wood	Brown	N/A	0	0	Negative
1	2	218	Classroom 218	Floor	N/A	N/A	N/A	0	N/A	N/A
1	2	218	Classroom 218	W1	Plaster	Blue	Chipping	4	19	Positive
1	2	218	Classroom 218	W2	Plaster	Blue	Chipping	20	19	Positive
1	2	218	Classroom 218	W3	Plaster	Blue	Flaking	67	19	Positive
1	2	218	Classroom 218	W4	Plaster	Blue	None	0	19	Positive
1	2	218	Classroom 218	Ceiling	Plaster	Tan	Flaking	125	25.7	Positive
1	2	218	Classroom 218	Baseboard	Wood	Brown	None	0	0	Negative
1	2	218	Classroom 218	Radiator	Metal	Silver	None	0	0	Negative
1	2	218	Classroom 218	Door Frame	Wood	Brown	N/A	0	0	Negative
1	2	218	Classroom 218	Chalkboard Frame	Wood	Brown	Chipping	8	1.6	Positive
1	2	217	Classroom 217	Floor	N/A	N/A	N/A	0	N/A	N/A
1	2	217	Classroom 217	W1	Plaster	Blue	None	0	19.5	Positive
1	2	217	Classroom 217	W2	Plaster	Blue	None	0	19.5	Positive
1	2	217	Classroom 217	W3	Plaster	Blue	Flaking	24	19.5	Positive
1	2	217	Classroom 217	W4	Plaster	Blue	Flaking	18	19.5	Positive
1	2	217	Classroom 217	Radiator	Metal	Silver	None	0	0	Negative
1	2	217	Classroom 217	Baseboard	Wood	Brown	None	0	0	Negative
1	2	217	Classroom 217	Chalkboard Frame	Wood	Brown	None	0	0	Negative
1	2	217	Classroom 217	Door Frame	Wood	Brown	N/A	0	0	Negative
1	2	217	Classroom 217	Ceiling	Plaster	Tan	Flaking	135	20.1	Positive
1	2	216A	Women's Restroom next to Classroom 217	Floor	N/A	N/A	N/A	0	N/A	N/A
1	2	216A	Women's Restroom next to Classroom 217	W1	Plaster	Tan	Cracking	12	21.4	Positive
1	2	216A	Women's Restroom next to Classroom 217	W2	Plaster	Tan	Cracking	50	24.9	Positive
1	2	216A	Women's Restroom next to Classroom 217	W3	Plaster	Tan	Flaking	17	24.9	Positive
1	2	216A	Women's Restroom next to Classroom 217	W4	Plaster	Tan	Chipping	30	24.9	Positive
1	2	216A	Women's Restroom next to Classroom 217	Ceiling	Plaster	Tan	Flaking	180	31.7	Positive
1	2	216A	Women's Restroom next to Classroom 217	Radiator	Metal	Silver	Chipping	16	1	Positive
1	2	216B	Women's Restroom next to Classroom 217	Floor	N/A	N/A	N/A	0	N/A	N/A
1	2	216B	Women's Restroom next to Classroom 217	W1	Plaster	Tan	Flaking	15	22.5	Positive
1	2	216B	Women's Restroom next to Classroom 217	W2	Plaster	Tan	Flaking	3	22.5	Positive
1	2	216B	Women's Restroom next to Classroom 217	W3	Plaster	Tan	Chipping	24	22.5	Positive
1	2	216B	Women's Restroom next to Classroom 217	W4	Plaster	Tan	Chipping	6	22.5	Positive

			Dates: August 24 - September 19, 2022	Lead-Safe Certification Assessment Report						
			Inspector Name and Certificate Number: Kevin Rumbol 006794	Harding School						
			Inspection Company: ACER Associates, LLC	2000 Wakeling Street, Philadelphia, PA 19124						
Element	Floor	Space #	On-Site Room Name	Component	Substrate Material	Color	Description of Damage	Damage Quantity (sf)	XRF Reading (mg/cm2)	XRF (positive/negative)
1	2	216B	Women's Restroom next to Classroom 217	Ceiling	Plaster	Tan	Flaking	26	26.5	Positive
1	2	216B	Women's Restroom next to Classroom 217	Baseboard	Concrete	Gray	Chipping	7	2	Positive
1	2	216B	Women's Restroom next to Classroom 217	Pipe	Metal	Tan	Flaking	25	2.7	Positive
1	2	216	Classroom 216	Floor	N/A	N/A	N/A	0	N/A	N/A
1	2	216	Classroom 216	W1	Plaster	Green	Chipping	9	11.2	Positive
1	2	216	Classroom 216	W2	Plaster	Green	Chipping	5	11.2	Positive
1	2	216	Classroom 216	W3	Plaster	Green	Flaking	26	11.2	Positive
1	2	216	Classroom 216	W4	Plaster	Green	None	0	11.2	Positive
1	2	216	Classroom 216	Ceiling	Plaster	Tan	Flaking	416	27	Positive
1	2	216	Classroom 216	Door Frame	Wood	Brown	Chipping	3	0.6	Negative
1	2	216	Classroom 216	Chalkboard Frame	Wood	Brown	Chipping	5	2	Positive
1	2	NP6	Custodial Closet across from 216	Floor	No Access	No Access	No Access	0	N/A	No Access
1	2	NP6	Custodial Closet across from 216	W1	No Access	No Access	No Access	0	N/A	No Access
1	2	NP6	Custodial Closet across from 216	W2	No Access	No Access	No Access	0	N/A	No Access
1	2	NP6	Custodial Closet across from 216	W3	No Access	No Access	No Access	0	N/A	No Access
1	2	NP6	Custodial Closet across from 216	W4	No Access	No Access	No Access	0	N/A	No Access
1	2	NP6	Custodial Closet across from 216	Ceiling	No Access	No Access	No Access	0	N/A	No Access
1	2	S22	Stairs across from Classroom 216	Floor	Concrete	Brown	Chipping	1	5.5	Positive
1	2	S22	Stairs across from Classroom 216	W1	Plaster	Tan	Chipping	2	26.2	Positive
1	2	S22	Stairs across from Classroom 216	W2	Plaster	Tan	Flaking	37	26.2	Positive
1	2	S22	Stairs across from Classroom 216	W3	Plaster	Tan	Flaking	7	26.2	Positive
1	2	S22	Stairs across from Classroom 216	W4	Plaster	Tan	Flaking	7	26.2	Positive
1	2	S22	Stairs across from Classroom 216	Ceiling	Plaster	Tan	Efflorescence	60	17.9	Positive
1	2	S22	Stairs across from Classroom 216	Stringer	Concrete	Brown	Chipping	3	6.8	Positive
1	2	S22	Stairs across from Classroom 216	Riser	Concrete	Brown	None	0	6	Positive
1	2	S22	Stairs across from Classroom 216	Tread	Concrete	Brown	None	0	0.05	Negative
1	2	S22	Stairs across from Classroom 216	Stair Newel Post	Metal	Brown	Chipping	12	6	Positive
1	2	S22	Stairs across from Classroom 216	Balusters	Metal	Brown	Chipping	5	7.5	Positive
1	2	S26	Fire Stair	Floor	Concrete	Gray	Flaking	22	0.9	Positive
1	2	S26	Fire Stair	Ceiling	Concrete	White	Flaking	35	12.5	Positive
1	2	S26	Fire Stair	W1	Brick	White	Flaking	45	2.4	Positive
1	2	S26	Fire Stair	W2	Brick	White	Flaking	75	2.4	Positive
1	2	S26	Fire Stair	W3	Brick	White	Flaking	45	2.4	Positive
1	2	S26	Fire Stair	W4	Brick	White	Flaking	64	2.4	Positive
1	2	S26	Fire Stair	Stair Riser	Concrete	Gray	Chipping	8	3	Positive
1	2	S26	Fire Stair	Stair Tread	Concrete	Gray	Chipping	4	2.8	Positive
1	2	S26	Fire Stair	Stair Stringer	Concrete	Gray	Chipping	2	2.8	Positive

		Dates: August 24 - September 19, 2022		Lead-Safe Certification Assessment Report						
		Inspector Name and Certificate Number: Kevin Rumbol 006794		Harding School						
		Inspection Company: ACER Associates, LLC		2000 Wakeling Street, Philadelphia, PA 19124						
E l e m e n t	Floor	Space #	On-Site Room Name	Component	Substrate Material	Color	Description of Damage	Damage Quantity (sf)	XRF Reading (mg/cm2)	XRF (positive/negative)
1	2	S26	Fire Stair	Stair Railing	Metal	Gray	Chipping	2	1.4	Positive
1	2	S26	Fire Stair	Divider	Metal	Gray	Chipping	2	6.6	Positive
1	2	S26	Fire Stair	Window Frame	Metal	Brown	N/A	0	0	Negative
1	2	S26	Fire Stair	Grate	Metal	Gray	Flaking	8	24.9	Positive
1	2	S26	Fire Stair	Pipe	Metal	White	Flaking	18	14.6	Positive
1	2	S26	Fire Stair	Door	Metal	Brown	N/A	0	0	Negative
1	2	S26	Fire Stair	Door Frame	Metal	Brown	N/A	0	0	Negative
1	2	S25	Fire Stair	Floor	Concrete	Gray	None	0	0.4	Negative
1	2	S25	Fire Stair	W1	Brick	White	Flaking	25	1.8	Positive
1	2	S25	Fire Stair	W2	Brick	White	Flaking	42	1.8	Positive
1	2	S25	Fire Stair	W3	Brick	White	Flaking	28	1.8	Positive
1	2	S25	Fire Stair	W4	Brick	White	Flaking	67	1.8	Positive
1	2	S25	Fire Stair	Ceiling	Concrete	White	Flaking	5	2.1	Positive
1	2	S25	Fire Stair	Stair Riser	Concrete	Gray	Chipping	2	3.7	Positive
1	2	S25	Fire Stair	Stair Tread	Concrete	Gray	Chipping	1	2.9	Positive
1	2	S25	Fire Stair	Stair Stringer	Concrete	Gray	None	0	3.2	Positive
1	2	S25	Fire Stair	Stair Railing	Metal	Gray	None	0	0.05	Positive
1	2	S25	Fire Stair	Divider	Metal	Gray	Chipping	0	0.19	Negative
1	2	S25	Fire Stair	Window Frame	Metal	Brown	N/A	0	0	Negative
1	2	S25	Fire Stair	Grate	Metal	Gray	Flaking	8	24.9	Positive
1	2	S25	Fire Stair	Pipe	Metal	Gray	Flaking	18	14.6	Positive
1	2	S25	Fire Stair	Door	Metal	Brown	N/A	0	0	Negative
1	2	S25	Fire Stair	Door Frame	Metal	Brown	N/A	0	0	Negative
1	2	215A	Girl's Restroom next to Classroom 215	Floor	Concrete	Brown	None	0	0	Negative
1	2	215A	Girl's Restroom next to Classroom 215	W1	Plaster	Tan	N/A	0	18.2	Positive
1	2	215A	Girl's Restroom next to Classroom 215	W2	Plaster	Tan	Cracking	3	18.2	Positive
1	2	215A	Girl's Restroom next to Classroom 215	W3	Plaster	Tan	N/A	0	18.2	Positive
1	2	215A	Girl's Restroom next to Classroom 215	W4	Plaster	Tan	Cracking	5	18.2	Positive
1	2	215A	Girl's Restroom next to Classroom 215	Pipe	Metal	Tan	None	0	0	Negative
1	2	215A	Girl's Restroom next to Classroom 215	Baseboard	Concrete	Brown	None	0	0	Negative
1	2	215A	Girl's Restroom next to Classroom 215	Ceiling	No Access	No Access	No Access	0	N/A	No Access
1	2	215B	Classroom 215 Closet	Floor	No Access	No Access	No Access	0	N/A	No Access
1	2	215B	Classroom 215 Closet	W1	No Access	No Access	No Access	0	N/A	No Access
1	2	215B	Classroom 215 Closet	W2	Brick	No Access	No Access	0	N/A	No Access
1	2	215B	Classroom 215 Closet	W3	CMU	No Access	No Access	0	N/A	No Access
1	2	215B	Classroom 215 Closet	W4	No Access	No Access	No Access	0	N/A	No Access
1	2	215B	Classroom 215 Closet	Ceiling	Plaster	White	Flaking	5	27.6	Positive
1	2	215	Classroom 215	Floor	N/A	N/A	N/A	0	N/A	N/A
1	2	215	Classroom 215	W1	Brick	Tan	Chipping	1	1	Positive

		Dates: August 24 - September 19, 2022		Lead-Safe Certification Assessment Report							
		Inspector Name and Certificate Number: Kevin Rumbol 006794		Harding School							
		Inspection Company: ACER Associates, LLC		2000 Wakeling Street, Philadelphia, PA 19124							
Element	Floor	Space #	On-Site Room Name	Component	Substrate Material	Color	Description of Damage	Damage Quantity (sf)	XRF Reading (mg/cm2)	XRF (positive/negative)	
1	2	215	Classroom 215	W2	Sheetrock	Tan	N/A	0	0	Negative	
1	2	215	Classroom 215	W3	Brick	Tan	Chipping	1	1	Positive	
1	2	215	Classroom 215	W4	Brick	Tan	None	0	1	Positive	
1	2	215	Classroom 215	Ceiling	Plaster	Tan	Flaking	92	23.7	Positive	
1	2	215	Classroom 215	Baseboard	Concrete	Green	Chipping	15	1.4	Positive	
1	2	214	Classroom 214	Floor	N/A	N/A	N/A	0	N/A	N/A	
1	2	214	Classroom 214	W1	Plaster	Tan	Chipping	43	23.6	Positive	
1	2	214	Classroom 214	W2	Plaster	Tan	None	0	23.6	Positive	
1	2	214	Classroom 214	W3	Plaster	Tan	Flaking	30	23.6	Positive	
1	2	214	Classroom 214	W4	Plaster	Tan	Chipping	1	23.6	Positive	
1	2	214	Classroom 214	Baseboard	Wood	Brown	None	0	0	Negative	
1	2	214	Classroom 214	Chalkboard frame	Metal	Brown	None	0	0	Negative	
1	2	214	Classroom 214	Door Frame	Metal	Brown	N/A	0	0	Negative	
1	2	214	Classroom 214	Door	Metal	Brown	N/A	0	0	Negative	
1	2	214	Classroom 214	Radiator	Metal	Silver	None	0	0.6	Negative	
1	2	214	Classroom 214	Ceiling	Plaster	Tan	Flaking	72	28.7	Positive	
1	2	213	Office 213	Floor	N/A	N/A	N/A	0	N/A	N/A	
1	2	213	Office 213	W1	Brick	Blue	Flaking	2	8.8	Positive	
1	2	213	Office 213	W2	Brick	Blue	Flaking	4	8.8	Positive	
1	2	213	Office 213	W3	Brick	Blue	Chipping	2	8.8	Positive	
1	2	213	Office 213	W4	CMU	Blue	None	0	0.06	Negative	
1	2	213	Office 213	W4	Sheetrock	Blue	N/A	0	0	Negative	
1	2	213	Office 213	Ceiling	Plaster	Tan	Flaking	385	30.5	Positive	
1	2	213	Office 213	Radiator Cover	Metal	Blue	N/A	0	0	Negative	
1	2	213	Office 213	Baseboard	Concrete	Blue	Chipping	8	1.3	Positive	
1	2	213A	Closet in Office 213	Floor	N/A	N/A	N/A	0	N/A	N/A	
1	2	213A	Closet in Office 213	W1	Drywall	Blue	N/A	0	0	Negative	
1	2	213A	Closet in Office 213	W2	Brick	Blue	Chipping	15	8.6	Positive	
1	2	213A	Closet in Office 213	W3	CMU	Blue	None	0	0	Negative	
1	2	213A	Closet in Office 213	W4	Drywall	Blue	N/A	0	0	Negative	
1	2	213A	Closet in Office 213	Ceiling	Plaster	Blue	Chipping	1	30.5	Positive	
1	2	213A	Closet in Office 213	Pipe	Metal	Blue	Chipping	4	3.3	Positive	
1	2	213A	Closet in Office 213	Door Frame	Metal	Blue	N/A	0	0	Negative	
1	2	213A	Closet in Office 213	Shelf	Wood	Blue	N/A	0	0	Negative	
1	2	S21	Stairs Next to Office 213	Floor	Concrete	Brown	Cracking	2	1.8	Positive	
1	2	S21	Stairs Next to Office 213	W1	Plaster	Tan	Cracking	4	26.9	Positive	
1	2	S21	Stairs Next to Office 213	W2	Plaster	Tan	Cracking	65	26.9	Positive	
1	2	S21	Stairs Next to Office 213	W3	Plaster	Tan	Cracking	11	26.9	Positive	

			Dates: August 24 - September 19, 2022	Lead-Safe Certification Assessment Report							
			Inspector Name and Certificate Number: Kevin Rumbol 006794	Harding School							
			Inspection Company: ACER Associates, LLC	2000 Wakeling Street, Philadelphia, PA 19124							
Element	Floor	Space #	On-Site Room Name	Component	Substrate Material	Color	Description of Damage	Damage Quantity (sf)	XRF Reading (mg/cm2)	XRF (positive/negative)	
1	2	S21	Stairs Next to Office 213	W4	Plaster	Tan	Cracking	36	26.9	Positive	
1	2	S21	Stairs Next to Office 213	Ceiling	Plaster	Tan	Flaking	50	14.3	Positive	
1	2	S21	Stairs Next to Office 213	Stringer	Concrete	Brown	None	0	6.5	Positive	
1	2	S21	Stairs Next to Office 213	Stair Newel Post	Metal	Brown	Chipping	5	13.5	Positive	
1	2	S21	Stairs Next to Office 213	Balusters	Metal	Brown	Chipping	4	8.2	Positive	
1	2	212	Classroom 212	Floor	N/A	N/A	N/A	0	N/A	N/A	
1	2	212	Classroom 212	W1	Plaster	Green	Flaking	1	18.4	Positive	
1	2	212	Classroom 212	W2	Plaster	Green	Chipping	38	18.4	Positive	
1	2	212	Classroom 212	W3	Plaster	Green	Chipping	26	18.4	Positive	
1	2	212	Classroom 212	W4	Plaster	Green	Flaking	5	18.4	Positive	
1	2	212	Classroom 212	Ceiling	Plaster	Tan	Flaking	115	24.8	Positive	
1	2	212	Classroom 212	Radiator	Metal	Silver	Chipping	19	0.9	Positive	
1	2	212	Classroom 212	Pipe	Metal	Green	Flaking	5	31.8	Positive	
1	2	211	Classroom 211	Floor	N/A	N/A	N/A	0	N/A	N/A	
1	2	211	Classroom 211	W1	Plaster	Blue	Chipping	2	10.1	Positive	
1	2	211	Classroom 211	W2	Plaster	Blue	Chipping	1	10.1	Positive	
1	2	211	Classroom 211	W3	Plaster	Blue	Flaking	30	10.1	Positive	
1	2	211	Classroom 211	W4	Plaster	Blue	Flaking	16	10.1	Positive	
1	2	211	Classroom 211	Ceiling	Plaster	Tan	Flaking	208	33.8	Positive	
1	2	211	Classroom 211	Radiator	Metal	Silver	Chipping	14	1.3	Positive	
1	2	211	Classroom 211	Pipe	Metal	Blue	Chipping	3	24.1	Positive	
1	2	209	Library	Floor	N/A	N/A	N/A	0	N/A	N/A	
1	2	209	Library	W1	Plaster	Blue	None	0	13.7	Positive	
1	2	209	Library	W2	Plaster	Blue	None	0	13.7	Positive	
1	2	209	Library	W3	Plaster	Blue	Efflorescence	9	13.7	Positive	
1	2	209	Library	W4	Plaster	Blue	None	0	13.7	Positive	
1	2	209	Library	Baseboard	Wood	Brown	None	0	0.07	Negative	
1	2	209	Library	Door Frame	Metal	Tan	N/A	0	0.07	Negative	
1	2	209	Library	Ceiling	Plaster	Tan	Flaking	980	28.4	Positive	
1	2	209A	Storage Room in Library Left Rear	Floor	N/A	N/A	N/A	0	N/A	N/A	
1	2	209A	Storage Room in Library Left Rear	W1	Plaster	Green	None	0	20.1	Positive	
1	2	209A	Storage Room in Library Left Rear	W2	Plaster	Green	None	0	20.1	Positive	
1	2	209A	Storage Room in Library Left Rear	W3	Plaster	Green	Chipping	2	20.1	Positive	
1	2	209A	Storage Room in Library Left Rear	W4	Plaster	Tan	Flaking	20	20.1	Positive	
1	2	209A	Storage Room in Library Left Rear	Ceiling	Plaster	Tan	Flaking	162	30.7	Positive	
1	2	209B	Storage Closet in Library near Main Lobby	Floor	N/A	N/A	N/A	0	N/A	N/A	
1	2	209B	Storage Closet in Library near Main Lobby	W1	Plaster	Green	Flaking	6	21.6	Positive	
1	2	209B	Storage Closet in Library near Main Lobby	W2	Plaster	Green	Flaking	50	21.6	Positive	

		Dates: August 24 - September 19, 2022		Lead-Safe Certification Assessment Report							
		Inspector Name and Certificate Number: Kevin Rumbol 006794		Harding School							
		Inspection Company: ACER Associates, LLC		2000 Wakeling Street, Philadelphia, PA 19124							
Element	Floor	Space #	On-Site Room Name	Component	Substrate Material	Color	Description of Damage	Damage Quantity (sf)	XRF Reading (mg/cm ²)	XRF (positive/negative)	
1	2	209B	Storage Closet in Library near Main Lobby	W3	Plaster	Green	Flaking	33	21.6	Positive	
1	2	209B	Storage Closet in Library near Main Lobby	W4	Plaster	Green	Flaking	20	21.6	Positive	
1	2	209B	Storage Closet in Library near Main Lobby	Baseboard	Wood	Brown	None	0	0.02	Negative	
1	2	209B	Storage Closet in Library near Main Lobby	Door Frame	Wood	Brown	N/A	0	0.08	Negative	
1	2	209B	Storage Closet in Library near Main Lobby	Ceiling	Plaster	Tan	Flaking	5	28.6	Positive	
1	2	228	Auditorium Balcony	Floor	N/A	N/A	N/A	0	N/A	N/A	
1	2	228	Auditorium Balcony	W1	Plaster	Tan	Flaking	22	15.1	Positive	
1	2	228	Auditorium Balcony	W2	Plaster	Tan	Flaking	61	15.1	Positive	
1	2	228	Auditorium Balcony	W3	Wood	Tan	Flaking	16	12.8	Positive	
1	2	228	Auditorium Balcony	W4	Plaster	Tan	Flaking	85	15.1	Positive	
1	2	228	Auditorium Balcony	Ceiling	Plaster	Tan	Flaking	450	14.6	Positive	
1	2	228	Auditorium Balcony	Ceiling Trim	Plaster	Tan	Flaking	330	15	Positive	
1	2	228	Auditorium Balcony	Riser	Plaster	Brown	Flaking	384	9.4	Positive	
1	2	228	Auditorium Balcony	Radiator	Metal	Silver	Flaking	30	0.8	Positive	
1	2	228	Auditorium Balcony	Wall Trim	Wood	Tan	None	0	5.5	Positive	
1	2	228	Auditorium Balcony	Window Casing	Wood	Tan	Chipping	4	9.5	Positive	
1	2	228	Auditorium Balcony	Window Sill	Wood	Tan	Chipping	40	2.3	Positive	
1	2	S27	Main Entrance Lobby and Stairs	Floor	N/A	N/A	N/A	0	N/A	N/A	
1	2	S27	Main Entrance Lobby and Stairs	W1	Plaster	Tan	None	0	2.9	Positive	
1	2	S27	Main Entrance Lobby and Stairs	W2	Plaster	Tan	None	0	2.9	Positive	
1	2	S27	Main Entrance Lobby and Stairs	W3	Plaster	Tan	Cracking	4	2.9	Positive	
1	2	S27	Main Entrance Lobby and Stairs	W4	Plaster	Tan	Cracking	2	2.9	Positive	
1	2	S27	Main Entrance Lobby and Stairs	Ceiling	Plaster	Tan	None	2	33.6	Positive	
1	2	S27	Main Entrance Lobby and Stairs	Ceiling Trim	Wood	White	Cracking	6	32.8	Positive	
1	2	208	Main Office	Floor	N/A	N/A	N/A	0	N/A	N/A	
1	2	208	Main Office	W1	Plaster	Blue	None	0	29.4	Positive	
1	2	208	Main Office	W2	Plaster	Blue	Flaking	2	29.4	Positive	
1	2	208	Main Office	W3	Plaster	Blue	Flaking	20	29.4	Positive	
1	2	208	Main Office	W4	Sheetrock	Purple	N/A	0	0.01	Negative	
1	2	208	Main Office	Baseboard	Wood	Black	None	0	0.19	Negative	
1	2	208	Main Office	Door Frame	Metal	Purple	N/A	0	0.05	Negative	
1	2	208	Main Office	Door	Wood	Tan	N/A	0	0	Negative	
1	2	208	Main Office	Ceiling	Plaster	Tan	Flaking	100	39.6	Positive	
1	2	208I	Computer Server MDF and Storage Closet in Main Office	Floor	N/A	N/A	N/A	0	N/A	N/A	
1	2	208I	Computer Server MDF and Storage Closet in Main Office	W1	Plaster	Tan	None	0	35	Positive	
1	2	208I	Computer Server MDF and Storage Closet in Main Office	W2	Plaster	Tan	None	0	35	Positive	

		Dates: August 24 - September 19, 2022		Lead-Safe Certification Assessment Report						
		Inspector Name and Certificate Number: Kevin Rumbol 006794		Harding School						
		Inspection Company: ACER Associates, LLC		2000 Wakeling Street, Philadelphia, PA 19124						
Element	Floor	Space #	On-Site Room Name	Component	Substrate Material	Color	Description of Damage	Damage Quantity (sf)	XRF Reading (mg/cm2)	XRF (positive/negative)
1	2	208I	Computer Server MDF and Storage Closet in Main Office	W3	Plaster	Tan	None	0	35	Positive
1	2	208I	Computer Server MDF and Storage Closet in Main Office	W4	Plaster	Tan	None	0	35	Positive
1	2	208I	Computer Server MDF and Storage Closet in Main Office	Ceiling	Plaster	Tan	None	0	39	Positive
1	2	208I	Computer Server MDF and Storage Closet in Main Office	Baseboard	Wood	Brown	None	0	0	Negative
1	2	208I	Computer Server MDF and Storage Closet in Main Office	Radiator	Metal	Silver	Chipping	5	4.3	Positive
1	2	208A	Principal's Office	Floor	N/A	N/A	N/A	0	N/A	N/A
1	2	208A	Principal's Office	W1	Sheetrock	Tan	N/A	0	0	Negative
1	2	208A	Principal's Office	W2	Plaster	Tan	None	0	26	Positive
1	2	208A	Principal's Office	W3	Sheetrock	Tan	N/A	0	0	Negative
1	2	208A	Principal's Office	W4	Plaster	Tan	None	0	28	Positive
1	2	208A	Principal's Office	Door Frame	Metal	Green	N/A	0	0.03	Negative
1	2	208A	Principal's Office	Baseboard	Wood	Brown	None	0	0.14	Negative
1	2	208A	Principal's Office	Ceiling	Plaster	Tan	Flaking	116	36.6	Positive
1	2	208J	Principal's Office Restroom	Floor	No Access	No Access	No Access	0	N/A	No Access
1	2	208J	Principal's Office Restroom	W1	No Access	No Access	No Access	0	N/A	No Access
1	2	208J	Principal's Office Restroom	W2	No Access	No Access	No Access	0	N/A	No Access
1	2	208J	Principal's Office Restroom	W3	No Access	No Access	No Access	0	N/A	No Access
1	2	208J	Principal's Office Restroom	W4	No Access	No Access	No Access	0	N/A	No Access
1	2	208J	Principal's Office Restroom	Ceiling	No Access	No Access	No Access	0	N/A	No Access
1	2	208H	Principal's Conference Room adjacent to Principal's Office	Floor	N/A	N/A	N/A	0	N/A	N/A
1	2	208H	Principal's Conference Room adjacent to Principal's Office	W1	Plaster	Tan	Chipping	3	32.8	Positive
1	2	208H	Principal's Conference Room adjacent to Principal's Office	W2	Sheetrock	Tan	N/A	0	0	Negative
1	2	208H	Principal's Conference Room adjacent to Principal's Office	W3	Sheetrock	Tan	N/A	0	0	Negative
1	2	208H	Principal's Conference Room adjacent to Principal's Office	W4	Sheetrock	Tan	N/A	0	0	Negative
1	2	208H	Principal's Conference Room adjacent to Principal's Office	Baseboard	Wood	Brown	None	0	0	Negative
1	2	208H	Principal's Conference Room adjacent to Principal's Office	Door Frame	Wood	Brown	N/A	0	0	Negative
1	2	208H	Principal's Conference Room adjacent to Principal's Office	Door	Wood	Brown	N/A	0	0	Negative

		Dates: August 24 - September 19, 2022		Lead-Safe Certification Assessment Report						
		Inspector Name and Certificate Number: Kevin Rumbol 006794		Harding School						
		Inspection Company: ACER Associates, LLC		2000 Wakeling Street, Philadelphia, PA 19124						
Element	Floor	Space #	On-Site Room Name	Component	Substrate Material	Color	Description of Damage	Damage Quantity (sf)	XRF Reading (mg/cm2)	XRF (positive/negative)
1	2	208H	Principal's Conference Room adjacent to Principal's Office	Ceiling	Plaster	Tan	Flaking	110	31.7	Positive
1	2	208B	Office to Left of Principal's Conference Room	Floor	N/A	N/A	N/A	0	N/A	N/A
1	2	208B	Office to Left of Principal's Conference Room	W1	Sheetrock	Tan	N/A	0	0	Negative
1	2	208B	Office to Left of Principal's Conference Room	W2	Sheetrock	Tan	N/A	0	0	Negative
1	2	208B	Office to Left of Principal's Conference Room	W3	Plaster	Tan	Flaking	6	31.8	Positive
1	2	208B	Office to Left of Principal's Conference Room	W4	Sheetrock	Tan	N/A	0	0	Negative
1	2	208B	Office to Left of Principal's Conference Room	Baseboard	Wood	Brown	None	0	0	Negative
1	2	208B	Office to Left of Principal's Conference Room	Door Frame	Metal	Tan	N/A	0	0	Negative
1	2	208B	Office to Left of Principal's Conference Room	Radiator Cover	Metal	Tan	N/A	0	0	Negative
1	2	208B	Office to Left of Principal's Conference Room	Ceiling	Plaster	Tan	Flaking	96	36.4	Positive
1	2	208C	Office to Right side of Principal's Conference Room	Floor	N/A	N/A	N/A	0	N/A	N/A
1	2	208C	Office to Right side of Principal's Conference Room	W1	Sheetrock	Tan	N/A	0	0	Negative
1	2	208C	Office to Right side of Principal's Conference Room	W2	Sheetrock	Tan	N/A	0	0	Negative
1	2	208C	Office to Right side of Principal's Conference Room	W3	Plaster	Tan	Cracking	10	26.7	Positive
1	2	208C	Office to Right side of Principal's Conference Room	W4	Sheetrock	Tan	N/A	0	0	Negative
1	2	208C	Office to Right side of Principal's Conference Room	Baseboard	Wood	Tan	None	0	0	Negative
1	2	208C	Office to Right side of Principal's Conference Room	Door Frame	Metal	Blue	N/A	0	0	Negative
1	2	208C	Office to Right side of Principal's Conference Room	Radiator Cover	Metal	Blue	N/A	0	0	Negative
1	2	208C	Office to Right side of Principal's Conference Room	Ceiling	Plaster	Tan	Flaking	60	33.2	Positive
1	2	208D	Office to Left of Conference Room 208	Floor	N/A	N/A	N/A	0	N/A	N/A
1	2	208D	Office to Left of Conference Room 208	W1	Sheetrock	Tan	N/A	0	0	Negative
1	2	208D	Office to Left of Conference Room 208	W2	Plaster	Tan	None	0	25.2	Positive
1	2	208D	Office to Left of Conference Room 208	W3	Plaster	Tan	Chipping	2	25.2	Positive
1	2	208D	Office to Left of Conference Room 208	W4	Sheetrock	Tan	N/A	0	0	Negative
1	2	208D	Office to Left of Conference Room 208	Baseboard	Wood	Brown	None	0	0	Negative
1	2	208D	Office to Left of Conference Room 208	Door Frame	Metal	Tan	N/A	0	0	Negative
1	2	208D	Office to Left of Conference Room 208	Ceiling	Plaster	Tan	Flaking	60	34.9	Positive
1	2	208G	Conference Room next to Conference Room 208 near Principal's Office	Floor	N/A	N/A	N/A	0	N/A	N/A
1	2	208G	Conference Room next to Conference Room 208 near Principal's Office	W1	Plaster	Tan	Chipping	2	25.7	Positive
1	2	208G	Conference Room next to Conference Room 208 near Principal's Office	W2	Sheetrock	Tan	N/A	0	0	Negative
1	2	208G	Conference Room next to Conference Room 208 near Principal's Office	W3	Sheetrock	Tan	N/A	0	0	Negative
1	2	208G	Conference Room next to Conference Room 208 near Principal's Office	W4	Sheetrock	Tan	N/A	0	0	Negative
1	2	208G	Conference Room next to Conference Room 208 near Principal's Office	Baseboard	Wood	Brown	None	0	0	Negative

		Dates: August 24 - September 19, 2022		Lead-Safe Certification Assessment Report						
		Inspector Name and Certificate Number: Kevin Rumbol 006794		Harding School						
		Inspection Company: ACER Associates, LLC		2000 Wakeling Street, Philadelphia, PA 19124						
Element	Floor	Space #	On-Site Room Name	Component	Substrate Material	Color	Description of Damage	Damage Quantity (sf)	XRF Reading (mg/cm2)	XRF (positive/negative)
1	2	208G	Conference Room next to Conference Room 208 near Principal's Office	Partition Wall	Wood	Tan	N/A	0	0	Negative
1	2	208G	Conference Room next to Conference Room 208 near Principal's Office	Door Frame	Metal	Tan	N/A	0	0	Negative
1	2	208G	Conference Room next to Conference Room 208 near Principal's Office	Ceiling	Plaster	Tan	Flaking	165	33.2	Positive
1	2	208E	Office in Center of Conference Room 208	Floor	No Access	No Access	No Access	No Access	No Access	No Access
1	2	208E	Office in Center of Conference Room 208	W1	No Access	No Access	No Access	No Access	No Access	No Access
1	2	208E	Office in Center of Conference Room 208	W2	No Access	No Access	No Access	No Access	No Access	No Access
1	2	208E	Office in Center of Conference Room 208	W3	No Access	No Access	No Access	No Access	No Access	No Access
1	2	208E	Office in Center of Conference Room 208	W4	No Access	No Access	No Access	No Access	No Access	No Access
1	2	208E	Office in Center of Conference Room 208	Ceiling	No Access	No Access	No Access	No Access	No Access	No Access
1	2	208F	Office to Right of Conference Room 208	Floor	N/A	N/A	None	0	N/A	N/A
1	2	208F	Office to Right of Conference Room 208	W1	Sheetrock	Tan	None	0	0	Negative
1	2	208F	Office to Right of Conference Room 208	W2	Sheetrock	Tan	None	0	0	Negative
1	2	208F	Office to Right of Conference Room 208	W3	Plaster	Tan	Chipping	2	1.6	Positive
1	2	208F	Office to Right of Conference Room 208	W4	Sheetrock	Tan	None	0	0	Negative
1	2	208F	Office to Right of Conference Room 208	Baseboard	Wood	Brown	None	0	0	Negative
1	2	208F	Office to Right of Conference Room 208	Radiator Cover	Metal	Tan	None	0	0	Negative
1	2	208F	Office to Right of Conference Room 208	Door Frame	Metal	Tan	N/A	0	0	Negative
1	2	208F	Office to Right of Conference Room 208	Ceiling	Plaster	Tan	Flaking	100	25.7	Positive
1	2	207	Office 207	Floor	N/A	N/A	N/A	0	N/A	N/A
1	2	207	Office 207	W1	Plaster	Blue	Chipping	1	28.5	Positive
1	2	207	Office 207	W2	Sheetrock	Tan	N/A	0	0	Negative
1	2	207	Office 207	W3	Plaster	Blue	Flaking	1	32.9	Positive
1	2	207	Office 207	W4	Plaster	Blue	Flaking	2	26.8	Positive
1	2	207	Office 207	Ceiling	Plaster	Tan	Flaking	220	29.1	Positive
1	2	207	Office 207	Baseboard	Wood	Brown	None	0	0	Negative
1	2	207	Office 207	Radiator Cover	Metal	Blue	N/A	0	0	Negative
1	2	206	Nurse's Office Foyer Lobby 206	Floor	N/A	N/A	None	0	N/A	N/A
1	2	206	Nurse's Office Foyer Lobby 206	W1	Sheetrock	Tan	None	0	0	Negative
1	2	206	Nurse's Office Foyer Lobby 206	W2	Sheetrock	Tan	None	0	0	Negative
1	2	206	Nurse's Office Foyer Lobby 206	W3	Sheetrock	Tan	None	0	0	Negative
1	2	206	Nurse's Office Foyer Lobby 206	W4	Plaster	Tan	None	0	12.8	Positive
1	2	206	Nurse's Office Foyer Lobby 206	Door Frame	Metal	Tan	N/A	0	0	Negative
1	2	206	Nurse's Office Foyer Lobby 206	Baseboard	Concrete	Brown	None	0	2.9	Positive
1	2	206	Nurse's Office Foyer Lobby 206	Ceiling	Plaster	Tan	Flaking	160	30.2	Positive
1	2	206A	Nurse's Office	Floor	N/A	N/A	N/A	0	N/A	N/A
1	2	206A	Nurse's Office	W1	Sheetrock	Tan	N/A	0	0	Negative

		Dates: August 24 - September 19, 2022		Lead-Safe Certification Assessment Report							
		Inspector Name and Certificate Number: Kevin Rumbol 006794		Harding School							
		Inspection Company: ACER Associates, LLC		2000 Wakeling Street, Philadelphia, PA 19124							
Element	Floor	Space #	On-Site Room Name	Component	Substrate Material	Color	Description of Damage	Damage Quantity (sf)	XRF Reading (mg/cm2)	XRF (positive/negative)	
1	2	206A	Nurse's Office	W2	Sheetrock	Tan	N/A	0	0	Negative	
1	2	206A	Nurse's Office	W3	Plaster	Tan	Flaking	6	1.9	Positive	
1	2	206A	Nurse's Office	W4	Plaster	Tan	None	0	1.9	Positive	
1	2	206A	Nurse's Office	Radiator	Metal	Silver	None	0	0	Negative	
1	2	206A	Nurse's Office	Baseboard	Wood	Tan	None	0	0	Negative	
1	2	206A	Nurse's Office	Door Frame	Metal	Tan	N/A	0	0	Negative	
1	2	206A	Nurse's Office	Cabinet	Wood	Blue	None	0	15.6	Positive	
1	2	206A	Nurse's Office	Ceiling	Plaster	Tan	Flaking	100	30.1	Positive	
1	2	206F	Nurse's Office Restroom	Floor	N/A	N/A	N/A	0	N/A	N/A	
1	2	206F	Nurse's Office Restroom	W1	Plaster	Tan	Cracking	1	24.5	Positive	
1	2	206F	Nurse's Office Restroom	W2	Plaster	Tan	Cracking	3	24.5	Positive	
1	2	206F	Nurse's Office Restroom	W3	Plaster	Tan	Flaking	2	24.5	Positive	
1	2	206F	Nurse's Office Restroom	W4	Plaster	Tan	Flaking	2	24.5	Positive	
1	2	206F	Nurse's Office Restroom	Ceiling	Plaster	Tan	Chipping	1	1.6	Positive	
1	2	206F	Nurse's Office Restroom	Baseboard	Concrete	Tan	Chipping	2	3	Positive	
1	2	206F	Nurse's Office Restroom	Pipe	Metal	Tan	Chipping	12	20.1	Positive	
1	2	206F	Nurse's Office Restroom	Door	Wood	Tan	Chipping	4	19.6	Positive	
1	2	206F	Nurse's Office Restroom	Door Casing	Wood	Tan	Chipping	1	16.8	Positive	
1	2	206B	Nurse's Office Patient Room	Floor	N/A	N/A	N/A	0	N/A	N/A	
1	2	206B	Nurse's Office Patient Room	W1	Sheetrock	Blue	N/A	0	0	Negative	
1	2	206B	Nurse's Office Patient Room	W2	Sheetrock	Blue	N/A	0	0	Negative	
1	2	206B	Nurse's Office Patient Room	W3	Sheetrock	Blue	N/A	0	0	Negative	
1	2	206B	Nurse's Office Patient Room	W4	Plaster	Blue	Chipping	1	21.9	Positive	
1	2	206B	Nurse's Office Patient Room	Radiator Cover	Metal	Tan	N/A	0	0	Negative	
1	2	206B	Nurse's Office Patient Room	Baseboard	Wood	Brown	None	0	0	Negative	
1	2	206B	Nurse's Office Patient Room	Door Casing	Metal	Blue	N/A	0	0	Negative	
1	2	206B	Nurse's Office Patient Room	Ceiling	Plaster	Tan	Flaking	90	33.8	Positive	
1	2	206D	Corner office in Room 206 next to Nurse Office	Floor	N/A	N/A	N/A	0	N/A	N/A	
1	2	206D	Corner office in Room 206 next to Nurse Office	W1	Sheetrock	Tan	N/A	0	0	Negative	
1	2	206D	Corner office in Room 206 next to Nurse Office	W2	Plaster	Tan	Efflorescence	12	10.1	Positive	
1	2	206D	Corner office in Room 206 next to Nurse Office	W3	Plaster	Tan	Efflorescence	2	13.7	Positive	
1	2	206D	Corner office in Room 206 next to Nurse Office	W4	Sheetrock	Tan	N/A	0	0	Negative	
1	2	206D	Corner office in Room 206 next to Nurse Office	Radiator Cover	Metal	Tan	N/A	0	0	Negative	
1	2	206D	Corner office in Room 206 next to Nurse Office	Baseboard	Wood	Brown	None	0	0	Negative	
1	2	206D	Corner office in Room 206 next to Nurse Office	Door Casing	Metal	Tan	N/A	0	0	Negative	
1	2	206D	Corner office in Room 206 next to Nurse Office	Ceiling	Plaster	Tan	Flaking	70	34.8	Positive	
1	2	206C	Corner Office Closet	Floor	N/A	N/A	N/A	0	N/A	N/A	
1	2	206C	Corner Office Closet	W1	N/A	N/A	N/A	0	N/A	N/A	
1	2	206C	Corner Office Closet	W2	Plaster	Tan	Cracking	8	34.2	Positive	

		Dates: August 24 - September 19, 2022		Lead-Safe Certification Assessment Report						
		Inspector Name and Certificate Number: Kevin Rumbol 006794		Harding School						
		Inspection Company: ACER Associates, LLC		2000 Wakeling Street, Philadelphia, PA 19124						
Element	Floor	Space #	On-Site Room Name	Component	Substrate Material	Color	Description of Damage	Damage Quantity (sf)	XRF Reading (mg/cm ²)	XRF (positive/negative)
1	2	206C	Corner Office Closet	W3	Brick	N/A	None	0	N/A	N/A
1	2	206C	Corner Office Closet	W4	N/A	N/A	N/A	0	N/A	N/A
1	2	206C	Corner Office Closet	Ceiling	Plaster	Tan	Flaking	65	34.2	Positive
1	2	206E	Office at end of Room 206 Foyer next to Corner Office	Floor	N/A	N/A	N/A	0	N/A	N/A
1	2	206E	Office at end of Room 206 Foyer next to Corner Office	W1	Sheetrock	Tan	N/A	0	0	Negative
1	2	206E	Office at end of Room 206 Foyer next to Corner Office	W2	Plaster	Tan	None	0	23.2	Positive
1	2	206E	Office at end of Room 206 Foyer next to Corner Office	W3	Plaster	Tan	Chipping	11	23.2	Positive
1	2	206E	Office at end of Room 206 Foyer next to Corner Office	W4	Plaster	Tan	None	0	23.2	Positive
1	2	206E	Office at end of Room 206 Foyer next to Corner Office	Ceiling	Plaster	Tan	Flaking	55	33.6	Positive
1	2	206E	Office at end of Room 206 Foyer next to Corner Office	Baseboard	Wood	Brown	None	0	0	Negative
1	2	206E	Office at end of Room 206 Foyer next to Corner Office	Door Frame	Wood	Brown	N/A	0	0	Negative
1	2	205	Classroom 205	Floor	N/A	N/A	N/A	0	N/A	N/A
1	2	205	Classroom 205	W1	Plaster	Tan	Chipping	13	22.3	Positive
1	2	205	Classroom 205	W2	Plaster	Tan	Chipping	1	22.3	Positive
1	2	205	Classroom 205	W3	Plaster	Tan	Flaking	17	22.3	Positive
1	2	205	Classroom 205	W4	Wood	Brown	N/A	0	0	Negative
1	2	205	Classroom 205	Ceiling	Plaster	Tan	Flaking	40	31.5	Positive
1	2	205	Classroom 205	Baseboard	Wood	Brown	None	0	0	Negative
1	2	205	Classroom 205	Chalkboard Frame	Wood	Brown	None	0	0	Negative
1	2	205	Classroom 205	Window Frame	Wood	Brown	N/A	0	0	Negative
1	2	205	Classroom 205	Door Frame	Wood	Brown	N/A	0	0	Negative
1	2	205	Classroom 205	Radiator	Metal	Silver	None	0	0.6	Negative
1	2	S24	Stairs Next to Office 203A	Floor	Concrete	Brown	Chipping	1	2.7	Positive
1	2	S24	Stairs Next to Office 203A	W1	Plaster	Tan	Cracking	3	24	Positive
1	2	S24	Stairs Next to Office 203A	W2	Plaster	Tan	None	0	24	Positive
1	2	S24	Stairs Next to Office 203A	W3	Plaster	Tan	Cracking	14	24	Positive
1	2	S24	Stairs Next to Office 203A	W4	Plaster	Tan	Cracking	15	24	Positive
1	2	S24	Stairs Next to Office 203A	Ceiling	Plaster	Tan	Cracking	88	16.3	Positive
1	2	S24	Stairs Next to Office 203A	Riser	Concrete	Brown	Chipping	2	7.3	Positive
1	2	S24	Stairs Next to Office 203A	Stair Newel Post	Metal	Brown	Chipping	4	17	Positive
1	2	S24	Stairs Next to Office 203A	Stringer	Concrete	Brown	None	0	6.5	Positive
1	2	S24	Stairs Next to Office 203A	Tread	Concrete	Brown	None	0	0.2	Negative
1	2	S24	Stairs Next to Office 203A	Radiator	Metal	Silver	None	0	0	Negative
1	2	S24	Stairs Next to Office 203A	Balusters	Metal	Brown	Chipping	4	9.4	Positive
1	2	203	Office 203A	Floor	N/A	N/A	N/A	0	N/A	N/A
1	2	203	Office 203A	W1	Brick	Tan	Chipping	2	11.6	Positive
1	2	203	Office 203A	W2	Sheetrock	Blue	N/A	0	0	Negative

		Dates: August 24 - September 19, 2022		Lead-Safe Certification Assessment Report							
		Inspector Name and Certificate Number: Kevin Rumbol 006794		Harding School							
		Inspection Company: ACER Associates, LLC		2000 Wakeling Street, Philadelphia, PA 19124							
Element	Floor	Space #	On-Site Room Name	Component	Substrate Material	Color	Description of Damage	Damage Quantity (sf)	XRF Reading (mg/cm2)	XRF (positive/negative)	
1	2	203	Office 203A	W3	Brick	Tan	Chipping	10	11.6	Positive	
1	2	203	Office 203A	W4	Brick	Tan	Chipping	5	11.6	Positive	
1	2	203	Office 203A	Ceiling	Plaster	Tan	Flaking	340	28	Positive	
1	2	203	Office 203A	Baseboard	Concrete	Tan	Chipping	10	5.3	Positive	
1	2	203B	Office 203B	Floor	N/A	N/A	N/A	0	N/A	N/A	
1	2	203B	Office 203B	W1	Brick	Tan	Chipping	2	12.9	Positive	
1	2	203B	Office 203B	W2	CMU	Tan	None	0	0.07	Negative	
1	2	203B	Office 203B	W3	Brick	Tan	Chipping	5	12.9	Positive	
1	2	203B	Office 203B	W4	Sheetrock	Tan	N/A	0	0	Negative	
1	2	203B	Office 203B	Ceiling	Plaster	Tan	Flaking	16	27.2	Positive	
1	2	203B	Office 203B	Radiator Cover	Metal	Tan	N/A	0	0	Negative	
1	2	203B	Office 203B	Baseboard	Concrete	Tan	Chipping	12	1.5	Positive	
1	2	201	Office 201	Floor	N/A	N/A	N/A	0	N/A	N/A	
1	2	201	Office 201	W1	Brick	Blue	Flaking	3	9	Positive	
1	2	201	Office 201	W2	Brick	Blue	Flaking	1	9	Positive	
1	2	201	Office 201	W3	Brick	Blue	Flaking	5	9	Positive	
1	2	201	Office 201	W4	CMU	Blue	None	0	0	Negative	
1	2	201	Office 201	Ceiling	Plaster	Tan	Flaking	210	26.7	Positive	
1	2	201	Office 201	Radiator Cover	Metal	Blue	N/A	0	0	Negative	
1	2	201	Office 201	Baseboard	Concrete	Blue	Flaking	12	4.7	Positive	
1	2	201B	Office 201 Closet	Floor	N/A	N/A	N/A	0	N/A	N/A	
1	2	201B	Office 201 Closet	W1	Sheetrock	Blue	N/A	0	0	Negative	
1	2	201B	Office 201 Closet	W2	Sheetrock	Blue	N/A	0	0	Negative	
1	2	201B	Office 201 Closet	W3	Brick	Blue	Chipping	7	21	Positive	
1	2	201B	Office 201 Closet	W4	Brick	Blue	Chipping	2	21	Positive	
1	2	201B	Office 201 Closet	Door Frame	Metal	Blue	N/A	0	0	Negative	
1	2	201B	Office 201 Closet	Ceiling	Plaster	Blue	Flaking	8	26.7	Positive	
1	2	204	Classroom 204	Floor	N/A	N/A	N/A	0	N/A	N/A	
1	2	204	Classroom 204	W1	Plaster	Blue	None	0	20.9	Positive	
1	2	204	Classroom 204	W2	Plaster	Blue	None	0	20.9	Positive	
1	2	204	Classroom 204	W3	Plaster	Blue	Flaking	30	20.9	Positive	
1	2	204	Classroom 204	W4	Plaster	Blue	None	0	20.9	Positive	
1	2	204	Classroom 204	Ceiling	Plaster	Tan	Flaking	65	30.2	Positive	
1	2	204	Classroom 204	Radiator	Metal	Silver	Chipping	16	0.9	Positive	
1	2	204	Classroom 204	Baseboard	Wood	Brown	None	0	0	Negative	
1	2	204	Classroom 204	Chalkboard frame	Wood	Brown	None	0	0	Negative	
1	2	200A	Custodial Closet across from Classroom 204	Floor	No Access	No Access	No Access	0	N/A	No Access	
1	2	200A	Custodial Closet across from Classroom 204	W1	No Access	No Access	No Access	0	N/A	No Access	

		Dates: August 24 - September 19, 2022		Lead-Safe Certification Assessment Report						
		Inspector Name and Certificate Number: Kevin Rumbol 006794		Harding School						
		Inspection Company: ACER Associates, LLC		2000 Wakeling Street, Philadelphia, PA 19124						
Element	Floor	Space #	On-Site Room Name	Component	Substrate Material	Color	Description of Damage	Damage Quantity (sf)	XRF Reading (mg/cm2)	XRF (positive/negative)
1	2	200A	Custodial Closet across from Classroom 204	W2	No Access	No Access	No Access	0	N/A	No Access
1	2	200A	Custodial Closet across from Classroom 204	W3	No Access	No Access	No Access	0	N/A	No Access
1	2	200A	Custodial Closet across from Classroom 204	W4	No Access	No Access	No Access	0	N/A	No Access
1	2	200A	Custodial Closet across from Classroom 204	Ceiling	No Access	No Access	No Access	0	N/A	No Access
1	2	200	Boy's Restroom across from Classroom 204	Floor	Concrete	Brown	None	0	0.05	Negative
1	2	200	Boy's Restroom across from Classroom 204	W1	Plaster	Tan	None	0	19.8	Positive
1	2	200	Boy's Restroom across from Classroom 204	W2	Plaster	Tan	None	0	19.8	Positive
1	2	200	Boy's Restroom across from Classroom 204	W3	Plaster	Tan	None	0	19.8	Positive
1	2	200	Boy's Restroom across from Classroom 204	W4	Plaster	Tan	None	0	19.8	Positive
1	2	200	Boy's Restroom across from Classroom 204	Ceiling	Plaster	Tan	N/A	0	0	Negative
1	2	200	Boy's Restroom across from Classroom 204	Baseboard	Concrete	Brown	None	0	0	Negative
1	2	202	Classroom 202	Floor	N/A	N/A	N/A	0	N/A	N/A
1	2	202	Classroom 202	W1	Plaster	Tan	None	0	23.7	Positive
1	2	202	Classroom 202	W2	Plaster	Tan	None	0	23.7	Positive
1	2	202	Classroom 202	W3	Plaster	Tan	Chipping	14	23.7	Positive
1	2	202	Classroom 202	W4	Plaster	Tan	Chipping	1	23.7	Positive
1	2	202	Classroom 202	Ceiling	Plaster	Tan	Flaking	144	33.6	Positive
1	2	202	Classroom 202	Radiator	Metal	Silver	Flaking	28	0.9	Positive
1	2	202	Classroom 202	Baseboard	Wood	Brown	None	0	0	Negative
1	2	202	Classroom 202	Door Frame	Wood	Brown	N/A	0	0	Negative
1	2	S23	Stairs across from Classroom 202	Floor	N/A	N/A	N/A	0	N/A	N/A
1	2	S23	Stairs across from Classroom 202	W1	Plaster	Tan	Chipping	2	25.7	Positive
1	2	S23	Stairs across from Classroom 202	W2	Plaster	Tan	None	0	25.7	Positive
1	2	S23	Stairs across from Classroom 202	W3	Plaster	Tan	Cracking	2	25.7	Positive
1	2	S23	Stairs across from Classroom 202	W4	Plaster	Tan	None	0	25.7	Positive
1	2	S23	Stairs across from Classroom 202	Ceiling	Plaster	Tan	Cracking	31	1.6	Positive
1	2	S23	Stairs across from Classroom 202	Radiator	Metal	Silver	Chipping	18	3	Positive
1	2	S23	Stairs across from Classroom 202	Riser	Concrete	Brown	Chipping	3	2.6	Positive
1	2	S23	Stairs across from Classroom 202	Tread	Concrete	Brown	Chipping	3	0.11	Negative
1	2	S23	Stairs across from Classroom 202	Stair Newel Post	Metal	Brown	Chipping	12	8	Positive
1	2	S23	Stairs across from Classroom 202	Balusters	Metal	Brown	Chipping	5	5.9	Positive
1	2	225	Men's Restroom next to Classroom 202	Floor	N/A	N/A	N/A	0	N/A	N/A
1	2	225	Men's Restroom next to Classroom 202	W1	Plaster	Blue	None	0	5.7	Positive
1	2	225	Men's Restroom next to Classroom 202	W2	Plaster	Blue	Chipping	4	5.7	Positive
1	2	225	Men's Restroom next to Classroom 202	W3	Plaster	Blue	Flaking	8	5.7	Positive
1	2	225	Men's Restroom next to Classroom 202	W4	Plaster	Blue	Chipping	1	5.7	Positive
1	2	225	Men's Restroom next to Classroom 202	Ceiling	Plaster	Tan	Flaking	93	25.8	Positive
1	2	225	Men's Restroom next to Classroom 202	Radiator	Metal	Silver	Chipping	5	11.7	Positive

		Dates: August 24 - September 19, 2022		Lead-Safe Certification Assessment Report						
		Inspector Name and Certificate Number: Kevin Rumbol 006794		Harding School						
		Inspection Company: ACER Associates, LLC		2000 Wakeling Street, Philadelphia, PA 19124						
Element	Floor	Space #	On-Site Room Name	Component	Substrate Material	Color	Description of Damage	Damage Quantity (sf)	XRF Reading (mg/cm2)	XRF (positive/negative)
1	2	225	Men's Restroom next to Classroom 202	Pipe	Metal	Blue	Chipping	10	24.8	Positive
1	2	225A	Men's Restroom next to Classroom 202	Floor	N/A	N/A	N/A	0	N/A	N/A
1	2	225A	Men's Restroom next to Classroom 202	W1	Plaster	Tan	Cracking	5	27.6	Positive
1	2	225A	Men's Restroom next to Classroom 202	W2	Plaster	Tan	None	0	27.6	Positive
1	2	225A	Men's Restroom next to Classroom 202	W3	Plaster	Tan	Cracking	4	27.6	Positive
1	2	225A	Men's Restroom next to Classroom 202	W4	Plaster	Tan	Flaking	14	27.6	Positive
1	2	225A	Men's Restroom next to Classroom 202	Ceiling	Plaster	Tan	Chipping	1	35.7	Positive
1	2	225A	Men's Restroom next to Classroom 202	Pipe	Metal	Tan	Flaking	15	19.8	Positive
1	2	H210	2nd Floor Hallways	Floor	N/A	N/A	N/A	0	N/A	N/A
1	2	H210	2nd Floor Hallways	W1	Plaster	Tan	Chipping	80	8.2	Positive
1	2	H210	2nd Floor Hallways	W3	Plaster	Tan	Chipping	24	8.2	Positive
1	2	H210	2nd Floor Hallways	Ceiling	Plaster	Tan	Flaking	1241	26.2	Positive
1	2	H210	2nd Floor Hallways	Radiator	Metal	Silver	Chipping	14	0.8	Positive
1	2	H210	2nd Floor Hallways	Chair Rail	Wood	Brown	N/A	0	0.06	Negative
1	2	H210	2nd Floor Hallways	Baseboard	Concrete	Brown	None	0	0.7	Positive
1	2	H210	2nd Floor Hallways	Locker	Metal	Red	N/A	0	0.01	Negative
1	2	H211	2nd Floor Hallways	Floor	N/A	N/A	N/A	0	N/A	N/A
1	2	H211	2nd Floor Hallways	W2	Plaster	Tan	Peeling	14	10.7	Positive
1	2	H211	2nd Floor Hallways	W4	Plaster	Tan	Peeling	3	10.7	Positive
1	2	H211	2nd Floor Hallways	Ceiling	Plaster	Tan	Flaking	416	28.2	Positive
1	2	H29	2nd Floor Hallways	Floor	N/A	N/A	N/A	0	N/A	N/A
1	2	H29	2nd Floor Hallways	W2	Plaster	Tan	Chipping	1	9.2	Positive
1	2	H29	2nd Floor Hallways	W4	Plaster	Tan	Chipping	2	9.2	Positive
1	2	H29	2nd Floor Hallways	Ceiling	Plaster	Tan	Flaking	396	30.5	Positive
1	2	H29	2nd Floor Hallways	Baseboard	Concrete	Brown	Chipping	2	3	Positive
1	2	H212A	2nd Floor Hallways	Floor	N/A	N/A	N/A	0	N/A	N/A
1	2	H212	2nd Floor Hallway 211 to 206	W1	Plaster	Tan	Chipping	33	11	Positive
1	2	H212	2nd Floor Hallway 211 to 206	W3	Plaster	Tan	Flaking	110	11	Positive
1	2	H212	2nd Floor Hallway 211 to 206	Ceiling	Plaster	Tan	Flaking	252	30.9	Positive
1	2	H212	2nd Floor Hallway 211 to 206	Radiator	Metal	Silver	Chipping	33	0.9	Positive
1	2	H212	2nd Floor Hallway 211 to 206	Baseboard	Concrete	Brown	Chipping	3	3.5	Positive
1	2	H212A	2nd Floor Hallways	Chair Rail	Wood	Brown	N/A	0	0.12	Negative
1	2	H212A	2nd Floor Hallways	Door	Metal	Brown	N/A	0	0	Negative
1	2	H212A	2nd Floor Hallways	Door Frame	Metal	Brown	N/A	0	0.04	Negative
1	2	H212B	2nd Floor Hallways	Floor	N/A	N/A	N/A	0	N/A	N/A
1	2	H212B	2nd Floor Hallways	W2	Plaster	Tan	None	0	33.5	Positive
1	2	H212B	2nd Floor Hallways	W4	Plaster	Tan	None	0	33.5	Positive
1	2	H212	2nd Floor Hallways	Ceiling Trim	Wood	Tan	Flaking	12	27.6	Positive
1	2	H212B	2nd Floor Hallways	Door	Metal	Tan	N/A	0	0.02	Negative

		Dates: August 24 - September 19, 2022		Lead-Safe Certification Assessment Report							
		Inspector Name and Certificate Number: Kevin Rumbol 006794		Harding School							
		Inspection Company: ACER Associates, LLC		2000 Wakeling Street, Philadelphia, PA 19124							
Element	Floor	Space #	On-Site Room Name	Component	Substrate Material	Color	Description of Damage	Damage Quantity (sf)	XRF Reading (mg/cm2)	XRF (positive/negative)	
1	2	H212B	2nd Floor Hallways	Door Frame	Metal	Tan	N/A	0	0.02	Negative	
1	2	H212C	2nd Floor Hallways	Floor	N/A	N/A	N/A	0	N/A	N/A	
1	2	H212C	2nd Floor Hallways	W4	Plaster	Tan	None	0	10.2	Positive	
1	2	H212C	2nd Floor Hallways	Chair Rail	Wood	Brown	N/A	0	0.06	Negative	
1	2	H212C	2nd Floor Hallways	Door Frame	Metal	Brown	N/A	0	0.04	Negative	
1	1	S17	Main Lobby Stairs	Floor	Terazzo	N/A	N/A	0	N/A	N/A	
1	1	S17	Main Lobby Stairs	W1	Plaster	Tan	Flaking	3	37.6	Positive	
1	1	S17	Main Lobby Stairs	W2	Plaster	Tan	Flaking	4	37.6	Positive	
1	1	S17	Main Lobby Stairs	W3	Plaster	Tan	Flaking	2	37.6	Positive	
1	1	S17	Main Lobby Stairs	W4	Plaster	Tan	Flaking	2	37.6	Positive	
1	1	S17	Main Lobby Stairs	Ceiling	Plaster	White	Flaking	18	5	Positive	
1	1	S17	Main Lobby Stairs	Door	Metal	Tan	None	0	0	Negative	
1	1	S17	Main Lobby Stairs	Door Casing	Metal	Tan	N/A	0	0	Negative	
1	1	S17	Main Lobby Stairs	Radiator	Metal	Silver	None	0	0.16	Negative	
1	1	S17	Main Lobby Stairs	Stair Newel Post	Metal	Red	None	0	0	Negative	
1	1	122A	Women's Restroom in Main Lobby	Floor	12" x 12" Floor Tile	N/A	N/A	0	N/A	N/A	
1	1	S17A	Women's Restroom in Main Lobby	W1	Plaster	Tan	Flaking	2	26	Positive	
1	1	S17A	Women's Restroom in Main Lobby	W2	Plaster	Tan	Flaking	4	26	Positive	
1	1	S17A	Women's Restroom in Main Lobby	W3	Plaster	Tan	Flaking	1	26	Positive	
1	1	S17A	Women's Restroom in Main Lobby	W4	Plaster	Tan	Flaking	26	26	Positive	
1	1	S17A	Women's Restroom in Main Lobby	Ceiling	Plaster	Tan	Flaking	8	21	Positive	
1	1	S17A	Women's Restroom in Main Lobby	Baseboard	Concrete	Brown	Flaking	5	1.9	Positive	
1	1	122A	Women's Restroom in Main Lobby	Door Frame	Metal	Pink	N/A	0	0	Negative	
1	1	122B	Men's Restroom in Main Lobby	Floor	12" x 12" Floor Tile	N/A	N/A	0	N/A	N/A	
1	1	106C	Men's Restroom in Main Lobby	W1	Plaster	Tan	Flaking	2	32	Positive	
1	1	106C	Men's Restroom in Main Lobby	W2	Plaster	Tan	Flaking	10	32	Positive	
1	1	106C	Men's Restroom in Main Lobby	W3	Plaster	Tan	Flaking	2	32	Positive	
1	1	106C	Men's Restroom in Main Lobby	W4	Plaster	Tan	Flaking	4	32	Positive	
1	1	106C	Men's Restroom in Main Lobby	Ceiling	Plaster	Tan	Flaking	20	28	Positive	
1	1	106C	Men's Restroom in Main Lobby	Baseboard	Concrete	Brown	Flaking	5	2.2	Positive	
1	1	122B	Men's Restroom in Main Lobby	Door Frame	Metal	Pink	N/A	0	0	Negative	
1	1	106C	Men's Restroom in Main Lobby	Pipe Cover	Metal	Brown	Flaking	4	2	Positive	
1	1	122B	Men's Restroom in Main Lobby	Pipe	Metal	Brown	None	0	0.01	Negative	
1	1	H19	Hallway at the Front Entrance	Floor	Terazzo	N/A	N/A	0	N/A	N/A	
1	1	H19	Hallway at the Front Entrance	W1	Plaster	Tan	Flaking	15	32.8	Positive	
1	1	H19	Hallway at the Front Entrance	W2	Plaster	Tan	N/A	0	32.8	Positive	
1	1	H19	Hallway at the Front Entrance	W3	Plaster	Tan	Flaking	4	32.8	Positive	
1	1	H19	Hallway at the Front Entrance	W4	Plaster	Tan	N/A	0	32.8	Positive	

		Dates: August 24 - September 19, 2022		Lead-Safe Certification Assessment Report							
		Inspector Name and Certificate Number: Kevin Rumbol 006794		Harding School							
		Inspection Company: ACER Associates, LLC		2000 Wakeling Street, Philadelphia, PA 19124							
Element	Floor	Space #	On-Site Room Name	Component	Substrate Material	Color	Description of Damage	Damage Quantity (sf)	XRF Reading (mg/cm2)	XRF (positive/negative)	
1	1	H19	Hallway at the Front Entrance	Ceiling	Plaster	Tan	Flaking	20	26.1	Positive	
1	1	H19	Hallway at the Front Entrance	Door	Metal	Tan	None	0	0	Negative	
1	1	H19	Hallway at the Front Entrance	Door Frame	Metal	Tan	N/A	0	0	Negative	
1	1	H1	Hallway Across Stairwell #1 S13	W2	Plaster	Tan	Cracking	1	25.3	Positive	
1	1	H1	Hallway Across Stairwell #1 S13	W3	Plaster	Tan	Cracking	1	25.3	Positive	
1	1	H1	Hallway Across Stairwell #1 S13	W4	Plaster	Tan	Cracking	3	25.3	Positive	
1	1	H1	Hallway Across Stairwell #1 S13	Radiator	Metal	Silver	Flaking	5	5.6	Positive	
1	1	H1	Hallway Across Stairwell #1 S13	Ceiling	Plaster	Tan	Flaking	85	26.6	Positive	
1	1	H1	Hallway at Rear	Floor	Concrete	N/A	N/A	0	N/A	N/A	
1	1	H1	Hallway at Rear	Chair Rail	Wood	Brown	None	0	0	Negative	
1	1	H1	Hallway Across Stairwell #1 S13	Baseboard	Concrete	Brown	Cracking	3	6	Positive	
1	1	118	Auditorium	Floor	Wood	N/A	N/A	0	N/A	N/A	
1	1	118	Auditorium	W1	Plaster	Tan	Flaking	10	18.5	Positive	
1	1	118	Auditorium	W2	Plaster	Tan	Flaking	62	18.5	Positive	
1	1	118	Auditorium	W3	Plaster	Tan	Flaking	10	18.5	Positive	
1	1	118	Auditorium	W4	Plaster	Tan	Flaking	70	18.5	Positive	
1	1	118	Auditorium	Ceiling	Plaster	Tan	Flaking	400	25.5	Positive	
1	1	118	Auditorium	Wall Chair Rail	Wood	Tan	Flaking	35	19.6	Positive	
1	1	118A	Auditorium Stage	Floor	Wood	N/A	N/A	0	N/A	N/A	
1	1	118A	Auditorium Stage	W1	Plaster	Tan	Flaking	1	17.5	Positive	
1	1	118A	Auditorium Stage	W2	Plaster	Tan	Flaking	5	17.5	Positive	
1	1	118A	Auditorium Stage	W3	Plaster	Tan	Flaking	25	17.5	Positive	
1	1	118A	Auditorium Stage	W4	Plaster	Tan	None	0	17.5	Positive	
1	1	118A	Auditorium Stage	Ceiling	Plaster	Tan	Flaking	40	No Access	No Access	
1	1	118C	Auditorium Stage Right Rear Storage Room	Floor	Wood	N/A	N/A	0	N/A	N/A	
1	1	118C	Auditorium Stage Right Rear Storage Room	W1	Plaster	Tan	Partially Inaccessible	6	20.1	Positive	
1	1	118C	Auditorium Stage Right Rear Storage Room	W2	Plaster	Tan	Partially Inaccessible	8	20.1	Positive	
1	1	118C	Auditorium Stage Right Rear Storage Room	W3	Plaster	Tan	Partially Inaccessible	18	20.1	Positive	
1	1	118C	Auditorium Stage Right Rear Storage Room	W4	Plaster	Tan	Partially Inaccessible	0	20.1	Positive	
1	1	118C	Auditorium Stage Right Rear Storage Room	Ceiling	Plaster	Tan	Flaking	32	20.6	Positive	
1	1	118C	Auditorium Stage Right Rear Storage Room	Door	Wood	Tan	Flaking	6	22.4	Positive	
1	1	118C	Auditorium Stage Right Rear Storage Room	Door Frame	Wood	Tan	N/A	0	0	Negative	
1	1	118C	Auditorium Stage Right Rear Storage Room	Pipe	Metal	Tan	Flaking	12	22.8	Positive	
1	1	118C	Auditorium Stage Right Rear Storage Room	Baseboard	Wood	Brown	Partially Inaccessible	1	6.4	Positive	
1	1	118C	Auditorium Stage Right Rear Storage Room	Window	Wood	Tan	Flaking	6	7.2	Positive	
1	1	118C	Auditorium Stage Right Rear Storage Room	Window Frame	Wood	Tan	None	0	12.4	Positive	
1	1	118B	Auditorium Stage Left Rear Storage Room	Floor	Wood	N/A	N/A	0	N/A	N/A	
1	1	118B	Auditorium Stage Left Rear Storage Room	W1	Plaster	Tan	Flaking	22	21.3	Positive	
1	1	118B	Auditorium Stage Left Rear Storage Room	W2	Plaster	Tan	Flaking	7	21.3	Positive	

		Dates: August 24 - September 19, 2022		Lead-Safe Certification Assessment Report							
		Inspector Name and Certificate Number: Kevin Rumbol 006794		Harding School							
		Inspection Company: ACER Associates, LLC		2000 Wakeling Street, Philadelphia, PA 19124							
Element	Floor	Space #	On-Site Room Name	Component	Substrate Material	Color	Description of Damage	Damage Quantity (sf)	XRF Reading (mg/cm2)	XRF (positive/negative)	
1	1	118B	Auditorium Stage Left Rear Storage Room	W3	Plaster	Tan	Flaking	12	21.3	Positive	
1	1	118B	Auditorium Stage Left Rear Storage Room	W4	Plaster	Tan	Flaking	8	21.3	Positive	
1	1	118B	Auditorium Stage Left Rear Storage Room	Ceiling	Plaster	Tan	Flaking	30	25.6	Positive	
1	1	118B	Auditorium Stage Left Rear Storage Room	Door	Wood	Tan	Flaking	10	19.6	Positive	
1	1	118B	Auditorium Stage Left Rear Storage Room	Door Frame	Wood	Tan	N/A	0	0	Negative	
1	1	118B	Auditorium Stage Left Rear Storage Room	Pipe	Metal	Tan	Flaking	16	19	Positive	
1	1	118B	Auditorium Stage Left Rear Storage Room	Baseboard	Wood	Brown	Flaking	4	21.2	Positive	
1	1	H15	Hallway to Right of Auditorium	Floor	Wood	N/A	N/A	0	N/A	N/A	
1	1	H15	Hallway to Right of Auditorium	W1	Plaster	Tan	N/A	0	32	Positive	
1	1	H15	Hallway to Right of Auditorium	W2	Plaster	Tan	Flaking	15	32	Positive	
1	1	H15	Hallway to Right of Auditorium	W3	Plaster	Tan	N/A	0	32	Positive	
1	1	H15	Hallway to Right of Auditorium	W4	Plaster	Tan	Flaking	160	32	Positive	
1	1	H15	Hallway to Right of Auditorium	Ceiling	Plaster	Tan	Flaking	440	29.1	Positive	
1	1	H15	Hallway to Right of Auditorium	Door	Wood	Tan	Flaking	6	24.7	Positive	
1	1	H15	Hallway to Right of Auditorium	Door Casing	Wood	Tan	Flaking	4	25.7	Positive	
1	1	H15	Hallway to Right of Auditorium	Radiator	Metal	Silver	Flaking	18	4.7	Positive	
1	1	H15	Hallway to Right of Auditorium	Wall Chair Rail	Wood	Tan	Flaking	50	19.8	Positive	
1	1	H6	Hallway to Left of Auditorium	Floor	Wood	N/A	N/A	0	N/A	N/A	
1	1	H6	Hallway to Left of Auditorium	W1	Plaster	Tan	Flaking	2	32	Positive	
1	1	H6	Hallway to Left of Auditorium	W2	Plaster	Tan	Flaking	70	32	Positive	
1	1	H6	Hallway to Left of Auditorium	W3	Plaster	Tan	Flaking	0	32	Positive	
1	1	H6	Hallway to Left of Auditorium	W4	Plaster	Tan	Flaking	25	32	Positive	
1	1	H6	Hallway to Left of Auditorium	Ceiling	Plaster	Tan	Flaking	600	34.2	Positive	
1	1	H6	Hallway to Left of Auditorium	Door	Wood	Tan	Flaking	6	23	Positive	
1	1	H6	Hallway to Left of Auditorium	Door Casing	Wood	Tan	Flaking	4	23.5	Positive	
1	1	H6	Hallway to Left of Auditorium	Radiator	Metal	Silver	Flaking	18	3	Positive	
1	1	H6	Hallway to Left of Auditorium	Wall Chair Rail	Wood	Tan	Flaking	70	19.8	Positive	
1	1	107	Classroom 107	Floor	12" x 12" Floor Tile	N/A	N/A	0	N/A	N/A	
1	1	107	Classroom 107	W1	Plaster	Blue	N/A	0	23.8	Positive	
1	1	107	Classroom 107	W2	Plaster	Blue	N/A	0	23.8	Positive	
1	1	107	Classroom 107	W3	Plaster	Blue	N/A	0	23.8	Positive	
1	1	107	Classroom 107	W4	Plaster	Blue	N/A	0	23.8	Positive	
1	1	107	Classroom 107	Ceiling	Plaster	Tan	Flaking	505	26.9	Positive	
1	1	107	Classroom 107	Baseboard	Concrete	Brown	Flaking	8	1.2	Positive	
1	1	107	Classroom 107	Radiator	Metal	Silver	Flaking	12	5.1	Positive	
1	1	107C	Classroom 107 Storage Closet left side	Floor	12" x 12" Floor Tile	N/A	N/A	0	N/A	N/A	
1	1	107C	Classroom 107 Storage Closet left side	W1	Plaster	Tan	Partially Inaccessible	44	9.9	Positive	
1	1	107C	Classroom 107 Storage Closet left side	W2	Plaster	Tan	Partially Inaccessible	0	9.9	Positive	
1	1	107C	Classroom 107 Storage Closet left side	W3	Plaster	Tan	Partially Inaccessible	18	9.9	Positive	

Dates: August 24 - September 19, 2022

Lead-Safe Certification Assessment Report

Inspector Name and Certificate Number:
Kevin Rumbol 006794

Harding School

Inspection Company: ACER Associates, LLC

2000 Wakeling Street, Philadelphia, PA 19124

Element	Floor	Space #	On-Site Room Name	Component	Substrate Material	Color	Description of Damage	Damage Quantity (sf)	XRF Reading (mg/cm2)	XRF (positive/negative)
1	1	107C	Classroom 107 Storage Closet left side	W4	Plaster	Tan	Partially Inaccessible	35	9.9	Positive
1	1	107C	Classroom 107 Storage Closet left side	Ceiling	Plaster	Tan	Partially Inaccessible	0	N/A	No Access
1	1	107B	Classroom 107 Storage Closet With Windows	Floor	N/A	N/A	N/A	0	N/A	N/A
1	1	107B	Classroom 107 Storage Closet With Windows	W1	Plaster	Tan	Partially Inaccessible	5	16.3	Positive
1	1	107B	Classroom 107 Storage Closet With Windows	W2	Plaster	Tan	Partially Inaccessible	20	16.3	Positive
1	1	107B	Classroom 107 Storage Closet With Windows	W3	Plaster	Tan	Partially Inaccessible	0	16.3	Positive
1	1	107B	Classroom 107 Storage Closet With Windows	W4	Plaster	Tan	Partially Inaccessible	2	16.3	Positive
1	1	107B	Classroom 107 Storage Closet With Windows	Ceiling	Plaster	Tan	Partially Inaccessible	10	N/A	No Access
1	1	107A	Classroom 107 Storage near front of class	Floor	Concrete	Gray	Partially Inaccessible	0	0	Negative
1	1	107A	Classroom 107 Storage near front of class	W1	Plaster	Tan	Partially Inaccessible	3	33.4	Positive
1	1	107A	Classroom 107 Storage near front of class	W2	Plaster	Tan	Partially Inaccessible	5	33.4	Positive
1	1	107A	Classroom 107 Storage near front of class	W3	Plaster	Tan	Partially Inaccessible	8	33.4	Positive
1	1	107A	Classroom 107 Storage near front of class	W4	Plaster	Tan	Partially Inaccessible	0	33.4	Positive
1	1	107A	Classroom 107 Storage near front of class	Ceiling	Plaster	Tan	Partially Inaccessible	0	N/A	No Access
1	1	107A	Classroom 107 Storage near front of class	Door Casing	Metal	Tan	N/A	0	0	Negative
1	1	108	Classroom 108	Floor	Concrete	N/A	N/A	0	N/A	N/A
1	1	108	Classroom 108	W1	Plaster	Tan	Flaking	2	25.9	Positive
1	1	108	Classroom 108	W2	Plaster	Tan	N/A	0	25.9	Positive
1	1	108	Classroom 108	W2	Sheetrock	Tan	N/A	0	0	Negative
1	1	108	Classroom 108	W3	Plaster	Tan	Flaking	2	25.9	Positive
1	1	108	Classroom 108	W4	Plaster	Tan	Flaking	3	25.9	Positive
1	1	108	Classroom 108	Ceiling	Plaster	Tan	Flaking	220	24.1	Positive
1	1	108	Classroom 108	Baseboard	Concrete	Brown	Flaking	15	1.3	Positive
1	1	108	Classroom 108	Radiator	Metal	Silver	Flaking	8	5.3	Positive
1	1	108A	Classroom 108 Restroom	Floor	Ceramic Tile	N/A	N/A	0	N/A	N/A
1	1	108A	Classroom 108 Restroom	W1	Sheetrock	Tan	N/A	0	0	Negative
1	1	108A	Classroom 108 Restroom	W2	Plaster	Tan	N/A	0	25.1	Positive
1	1	108A	Classroom 108 Restroom	W3	Plaster	Tan	N/A	0	25.1	Positive
1	1	108A	Classroom 108 Restroom	W4	Sheetrock	Tan	N/A	0	0	Negative
1	1	108A	Classroom 108 Restroom	Ceiling	Plaster	Tan	Flaking	20	24.1	Positive
1	1	108B	Classroom 108 Storage near front of class	Floor	9"x9" Floor Tile	N/A	N/A	0	N/A	N/A
1	1	108B	Classroom 108 Storage near front of class	W1	Plaster	Tan	Flaking	5	18.4	Positive
1	1	108B	Classroom 108 Storage near front of class	W2	Plaster	Tan	Flaking	10	18.4	Positive
1	1	108B	Classroom 108 Storage near front of class	W3	Plaster	Tan	Flaking	12	18.4	Positive
1	1	108B	Classroom 108 Storage near front of class	W4	Plaster	Tan	Flaking	2	18.4	Positive
1	1	108B	Classroom 108 Storage near front of class	Ceiling	Plaster	Tan	Flaking	2	16.8	Positive
1	1	108C	Classroom 108 Storage Closet With Windows	Floor	9"x9" Floor Tile	N/A	N/A	0	N/A	N/A
1	1	108C	Classroom 108 Storage Closet With Windows	W1	Plaster	Tan	Flaking	15	13.1	Positive
1	1	108C	Classroom 108 Storage Closet With Windows	W2	Plaster	Tan	Partially Inaccessible	0	13.1	Positive

		Dates: August 24 - September 19, 2022		Lead-Safe Certification Assessment Report							
		Inspector Name and Certificate Number: Kevin Rumbol 006794		Harding School							
		Inspection Company: ACER Associates, LLC		2000 Wakeling Street, Philadelphia, PA 19124							
Element	Floor	Space #	On-Site Room Name	Component	Substrate Material	Color	Description of Damage	Damage Quantity (sf)	XRF Reading (mg/cm2)	XRF (positive/negative)	
1	1	108C	Classroom 108 Storage Closet With Windows	W3	Plaster	Tan	Flaking	8	13.1	Positive	
1	1	108C	Classroom 108 Storage Closet With Windows	W4	Plaster	Tan	Flaking	5	13.1	Positive	
1	1	108C	Classroom 108 Storage Closet With Windows	Ceiling	Plaster	Tan	Flaking	4	16.9	Positive	
1	1	109	Classroom 109	Floor	12" x 12" Floor Tile	N/A	N/A	0	N/A	N/A	
1	1	109	Classroom 109	W1	Plaster	Blue	None	0	31.1	Positive	
1	1	109	Classroom 109	W2	Plaster	Blue	None	0	31.1	Positive	
1	1	109	Classroom 109	W3	Plaster	Blue	None	0	31.1	Positive	
1	1	109	Classroom 109	W4	Plaster	Blue	None	0	31.1	Positive	
1	1	109	Classroom 109	Ceiling	Plaster	Tan	Flaking	367	32.2	Positive	
1	1	109	Classroom 109	Baseboard	Wood	Brown	None	0	14	Positive	
1	1	109	Classroom 109	Door Frame	Metal	Brown	N/A	0	0	Negative	
1	1	109	Classroom 109	Window Sill	Wood	Brown	None	0	4.3	Positive	
1	1	109	Classroom 109	Window Frame	Metal	Brown	None	0	0	Negative	
1	1	109	Classroom 109	Pipe	Metal	Blue	None	0	33.9	Positive	
1	1	109	Classroom 109	Pipe Chase Cover	Metal	Brown	None	0	6.6	Positive	
1	1	109A	Storage in Classroom 109	Floor	12" x 12" Floor Tile	N/A	N/A	0	N/A	N/A	
1	1	109A	Storage in Classroom 109	W1	Plaster	Blue	None	0	36.3	Positive	
1	1	109A	Storage in Classroom 109	W2	Plaster	Blue	None	0	36.3	Positive	
1	1	109A	Storage in Classroom 109	W3	Plaster	Blue	Flaking	3	36.3	Positive	
1	1	109A	Storage in Classroom 109	W4	Plaster	Blue	None	0	36.3	Positive	
1	1	109A	Storage in Classroom 109	Ceiling	Plaster	Tan	Flaking	32	13.9	Positive	
1	1	109A	Storage in Classroom 109	Door	Wood	Brown	None	0	0.05	Negative	
1	1	109A	Storage in Classroom 109	Door Frame	Wood	Brown	N/A	0	0.06	Negative	
1	1	109A	Storage in Classroom 109	Radiator	Metal	Silver	Flaking	1	5.5	Positive	
1	1	109A	Storage in Classroom 109	Baseboard	Wood	Brown	None	0	1.6	Positive	
1	1	109A	Storage in Classroom 109	Pipe Chase Cover	Metal	Brown	None	0	2.4	Positive	
1	1	H17	Hallway from Classroom 107 to Classroom 109	Floor	Concrete	N/A	N/A	0	N/A	N/A	
1	1	H17	Hallway from Classroom 107 to Classroom 109	W1	Plaster	Tan	Cracking	18	10.3	Positive	
1	1	H17	Hallway from Classroom 107 to Classroom 109	W2	Plaster	Tan	Cracking	2	10.3	Positive	
1	1	H17	Hallway from Classroom 107 to Classroom 109	W3	Plaster	Tan	Cracking	23	10.3	Positive	
1	1	H17	Hallway from Classroom 107 to Classroom 109	W4	Plaster	Tan	None	0	10.3	Positive	
1	1	H17	Hallway from Classroom 107 to Classroom 109	Door Frame	Wood	Brown	N/A	0	0.02	Negative	
1	1	H17	Hallway from Classroom 107 to Classroom 109	Ceiling	Plaster	Tan	Flaking	980	24.3	Positive	
1	1	H17	Hallway from Classroom 107 to Classroom 109	Chair Rail	Wood	Brown	None	0	0.05	Negative	
1	1	H17	Hallway from Classroom 107 to Classroom 109	Baseboard	Concrete	Brown	Chipping	15	4.1	Positive	
1	1	H17	Hallway from Classroom 107 to Classroom 109	Locker	Metal	Red	N/A	0	0.03	Negative	
1	1	H17	Hallway from Classroom 107 to Classroom 109	Door	Metal	Brown	N/A	0	0.02	Negative	

		Dates: August 24 - September 19, 2022		Lead-Safe Certification Assessment Report						
		Inspector Name and Certificate Number: Kevin Rumbol 006794		Harding School						
		Inspection Company: ACER Associates, LLC		2000 Wakeling Street, Philadelphia, PA 19124						
Element	Floor	Space #	On-Site Room Name	Component	Substrate Material	Color	Description of Damage	Damage Quantity (sf)	XRF Reading (mg/cm2)	XRF (positive/negative)
1	1	117	Girl's Gymnasium	Floor	Rubber	N/A	N/A	0	N/A	N/A
1	1	117	Girl's Gymnasium	W1	Brick	Red	Flaking	30	8.8	Positive
1	1	117	Girl's Gymnasium	W2	Brick	Red	Flaking	50	8.8	Positive
1	1	117	Girl's Gymnasium	W3	Brick	Red	Flaking	30	8.8	Positive
1	1	117	Girl's Gymnasium	W4	Brick	Red	Flaking	160	8.8	Positive
1	1	117	Girl's Gymnasium	Ceiling	Metal	Tan	Flaking	720	15.4	Positive
1	1	117	Girl's Gymnasium	Ceiling	Concrete	Tan	Flaking	315	8.1	Positive
1	1	117	Girl's Gymnasium	Pipe	Metal	Tan	Flaking	8	6.9	Positive
1	1	117	Girl's Gymnasium	Radiator	Metal	Silver	Flaking	20	4.3	Positive
1	1	117	Girl's Gymnasium	Door	Metal	Brown	N/A	0	0	Negative
1	1	117	Girl's Gymnasium	Door Casing	Metal	Brown	N/A	0	0	Negative
1	1	117A	Girl's Gym Locker Room	Floor	12" x 12" Floor Tile	N/A	N/A	0	N/A	N/A
1	1	117A	Girl's Gym Locker Room	W1	Brick	Tan	None	0	11.6	Positive
1	1	117A	Girl's Gym Locker Room	W1	Sheetrock	Tan	N/A	0	0	Negative
1	1	117A	Girl's Gym Locker Room	W2	Brick	Tan	Flaking	5	11.6	Positive
1	1	117A	Girl's Gym Locker Room	W3	Brick	Tan	Flaking	6	11.6	Positive
1	1	117A	Girl's Gym Locker Room	W4	Brick	Tan	Flaking	8	11.6	Positive
1	1	117A	Girl's Gym Locker Room	Ceiling	Concrete	Tan	Flaking	580	7	Positive
1	1	117A	Girl's Gym Locker Room	Radiator	Metal	Silver	Flaking	9	1.3	Positive
1	1	117A	Girl's Gym Locker Room	Baseboard	Concrete	Brown	N/A	0	0	Negative
1	1	117A	Girl's Gym Locker Room	Pipe	Metal	Tan	None	0	0.22	Negative
1	1	117A	Girl's Gym Locker Room	Railing	Metal	Red	Flaking	15	14.3	Positive
1	1	117A	Girl's Gym Locker Room	Stair Newel Post	Metal	Brown	Flaking	2	6.3	Positive
1	1	117A	Girl's Gym Locker Room	Balluster	Metal	Gray	Flaking	2	12.6	Positive
1	1	117A	Girl's Gym Locker Room	Tread	Concrete	Brown	None	0	0.01	Negative
1	1	117A	Girl's Gym Locker Room	Riser	Concrete	Brown	None	0	0.01	Negative
1	1	117A	Girl's Gym Locker Room	Stringer	Concrete	Brown	None	0	0.17	Negative
1	1	117D	Storage Room in Girl's Gym Locker Room	Floor	Concrete	Gray	N/A	0	0.01	Negative
1	1	117D	Storage Room in Girl's Gym Locker Room	W1	Sheetrock	Tan	N/A	0	0	Negative
1	1	117D	Storage Room in Girl's Gym Locker Room	W2	Brick	Tan	None	0	6.8	Positive
1	1	117D	Storage Room in Girl's Gym Locker Room	W3	Ceramic	N/A	N/A	0	N/A	N/A
1	1	117D	Storage Room in Girl's Gym Locker Room	W4	Brick	Tan	None	0	6.8	Positive
1	1	117D	Storage Room in Girl's Gym Locker Room	Ceiling	Concrete	Tan	Flaking	15	8.8	Positive
1	1	117D	Storage Room in Girl's Gym Locker Room	Pipe	Metal	Tan	Flaking	5	5.6	Positive
1	1	117D	Storage Room in Girl's Gym Locker Room	Door Casing	Metal	Gray	N/A	0	0	Negative
1	1	117E	Restroom in Girl's Gym Locker Room	Floor	Concrete	Gray	N/A	0	0.09	Negative
1	1	117E	Restroom in Girl's Gym Locker Room	W1	Ceramic	N/A	N/A	0	N/A	N/A
1	1	117E	Restroom in Girl's Gym Locker Room	W2	Ceramic	N/A	N/A	0	N/A	N/A

Dates: August 24 - September 19, 2022

Lead-Safe Certification Assessment Report

Inspector Name and Certificate Number:
Kevin Rumbol 006794

Harding School

Inspection Company: ACER Associates, LLC

2000 Wakeling Street, Philadelphia, PA 19124

Element	Floor	Space #	On-Site Room Name	Component	Substrate Material	Color	Description of Damage	Damage Quantity (sf)	XRF Reading (mg/cm ²)	XRF (positive/negative)
1	1	117E	Restroom in Girl's Gym Locker Room	W3	Ceramic	N/A	N/A	0	N/A	N/A
1	1	117E	Restroom in Girl's Gym Locker Room	W4	Ceramic	N/A	N/A	0	N/A	N/A
1	1	117E	Restroom in Girl's Gym Locker Room	Ceiling	Concrete	Tan	Flaking	45	5.9	Positive
1	1	117E	Restroom in Girl's Gym Locker Room	Radiator	Metal	Silver	Flaking	1	4.7	Positive
1	1	117E	Restroom in Girl's Gym Locker Room	Door	Metal	Brown	N/A	0	0	Negative
1	1	117E	Restroom in Girl's Gym Locker Room	Door Frame	Metal	Brown	N/A	0	0	Negative
1	1	117B	Front Storage Closet in Gym next to Doors	Floor	Concrete	N/A	N/A	0	N/A	N/A
1	1	117B	Front Storage Closet in Gym next to Doors	W1	Brick	Tan	Flaking	15	6.4	Positive
1	1	117B	Front Storage Closet in Gym next to Doors	W2	Brick	Tan	Flaking	4	6.4	Positive
1	1	117B	Front Storage Closet in Gym next to Doors	W3	Brick	Tan	Flaking	26	6.4	Positive
1	1	117B	Front Storage Closet in Gym next to Doors	W4	Brick	Tan	Flaking	4	6.4	Positive
1	1	117B	Front Storage Closet in Gym next to Doors	Ceiling	Concrete	Tan	Flaking	1	5.2	Positive
1	1	117B	Front Storage Closet in Gym next to Doors	Door	Metal	Brown	N/A	0	0	Negative
1	1	117B	Front Storage Closet in Gym next to Doors	Door Frame	Metal	Brown	N/A	0	0	Negative
1	1	117B	Front Storage Closet in Gym next to Doors	Pipe	Metal	Tan	Flaking	3	2.3	Positive
1	1	117B	Front Storage Closet in Gym next to Doors	Baseboard	Concrete	Gray	Flaking	6	1	Positive
1	1	117E	Storage Room in Girl's Gym	Floor	No Access	No Access	No Access	No Access	No Access	No Access
1	1	117E	Storage Room in Girl's Gym	W1	No Access	No Access	No Access	No Access	No Access	No Access
1	1	117E	Storage Room in Girl's Gym	W2	No Access	No Access	No Access	No Access	No Access	No Access
1	1	117E	Storage Room in Girl's Gym	W3	No Access	No Access	No Access	No Access	No Access	No Access
1	1	117E	Storage Room in Girl's Gym	W4	No Access	No Access	No Access	No Access	No Access	No Access
1	1	117E	Storage Room in Girl's Gym	Ceiling	No Access	No Access	No Access	No Access	No Access	No Access
1	1	S19	Girl's Gym Stairs	Floor	Concrete	N/A	N/A	0	N/A	N/A
1	1	S19	Girl's Gym Stairs	W1	Brick	Tan	Flaking	1	1.3	Positive
1	1	S19	Girl's Gym Stairs	W2	Brick	Tan	Flaking	72	1.3	Positive
1	1	S19	Girl's Gym Stairs	W3	Brick	Tan	Flaking	40	1.3	Positive
1	1	S19	Girl's Gym Stairs	W4	Brick	Tan	Flaking	43	1.3	Positive
1	1	S19	Girl's Gym Stairs	Ceiling	Concrete	Tan	Flaking	85	5.3	Positive
1	1	S19	Girl's Gym Stairs	Riser	Concrete	Brown	Flaking	20	2.8	Positive
1	1	S19	Girl's Gym Stairs	Tread	Concrete	Brown	Flaking	13	3.7	Positive
1	1	S19	Girl's Gym Stairs	Railing	Metal	Silver	None	0	0.24	Negative
1	1	S19	Girl's Gym Stairs	Radiator	Metal	Tan	Flaking	3	3.9	Positive
1	1	S19	Girl's Gym Stairs	Door	Metal	Brown	None	0	0	Negative
1	1	S19	Girl's Gym Stairs	Door Frame	Metal	Brown	N/A	0	0	Negative
1	1	117C	Storage Closet under gym stairs	Floor	No Access	No Access	No Access	No Access	No Access	No Access
1	1	117C	Storage Closet under gym stairs	W1	No Access	No Access	No Access	No Access	No Access	No Access
1	1	117C	Storage Closet under gym stairs	W2	No Access	No Access	No Access	No Access	No Access	No Access
1	1	117C	Storage Closet under gym stairs	W3	Brick	No Access	No Access	No Access	No Access	No Access
1	1	117C	Storage Closet under gym stairs	W4	No Access	No Access	No Access	No Access	No Access	No Access

		Dates: August 24 - September 19, 2022		Lead-Safe Certification Assessment Report						
		Inspector Name and Certificate Number: Kevin Rumbol 006794		Harding School						
		Inspection Company: ACER Associates, LLC		2000 Wakeling Street, Philadelphia, PA 19124						
Element	Floor	Space #	On-Site Room Name	Component	Substrate Material	Color	Description of Damage	Damage Quantity (sf)	XRF Reading (mg/cm2)	XRF (positive/negative)
1	1	117C	Storage Closet under gym stairs	Ceiling	Concrete	No Access	No Access	No Access	No Access	No Access
1	1	117D	Storage Closet at Center of Gym Stairs	Floor	Concrete	N/A	N/A	0	N/A	N/A
1	1	117D	Storage Closet at Center of Gym Stairs	W1	Brick	Tan	None	0	0.03	Negative
1	1	117D	Storage Closet at Center of Gym Stairs	W2	Brick	Tan	None	0	0.03	Negative
1	1	117D	Storage Closet at Center of Gym Stairs	W3	Brick	Tan	None	0	0.03	Negative
1	1	117D	Storage Closet at Center of Gym Stairs	W3	Concrete	Tan	None	0	0.01	Negative
1	1	117D	Storage Closet at Center of Gym Stairs	W4	Brick	Tan	None	0	0.03	Negative
1	1	117D	Storage Closet at Center of Gym Stairs	Ceiling	Concrete	Tan	None	0	0.02	Negative
1	1	117D	Storage Closet at Center of Gym Stairs	Door	Metal	Brown	N/A	0	0	Negative
1	1	117D	Storage Closet at Center of Gym Stairs	Door Frame	Metal	Brown	N/A	0	0	Negative
1	1	110	Classroom 110	Floor	12" x 12" Floor Tile	N/A	N/A	0	N/A	N/A
1	1	110	Classroom 110	W1	Plaster	Tan	None	0	32.9	Positive
1	1	110	Classroom 110	W2	Plaster	Tan	None	0	32.9	Positive
1	1	110	Classroom 110	W3	Plaster	Tan	None	0	32.9	Positive
1	1	110	Classroom 110	W4	Plaster	Tan	None	0	32.9	Positive
1	1	110	Classroom 110	Ceiling	Plaster	Tan	Flaking	90	31.5	Positive
1	1	110	Classroom 110	Radiator	Metal	Silver	Flaking	6	4.1	Positive
1	1	110	Classroom 110	Baseboard	Concrete	Brown	Flaking	6	1.3	Positive
1	1	110A	Classroom 110 Storage Closet	Floor	No Access	No Access	No Access	No Access	No Access	No Access
1	1	110A	Classroom 110 Storage Closet	W1	No Access	No Access	No Access	No Access	No Access	No Access
1	1	110A	Classroom 110 Storage Closet	W2	No Access	No Access	No Access	No Access	No Access	No Access
1	1	110A	Classroom 110 Storage Closet	W3	No Access	No Access	No Access	No Access	No Access	No Access
1	1	110A	Classroom 110 Storage Closet	W4	No Access	No Access	No Access	No Access	No Access	No Access
1	1	110A	Classroom 110 Storage Closet	Ceiling	No Access	No Access	No Access	No Access	No Access	No Access
1	1	S11	Stairs across from Classroom 110	Floor	Concrete	Brown	Flaking	2	5.5	Positive
1	1	S11	Stairs across from Classroom 110	W1	Plaster	Tan	None	0	30.2	Positive
1	1	S11	Stairs across from Classroom 110	W2	Plaster	Tan	None	0	30.2	Positive
1	1	S11	Stairs across from Classroom 110	W3	Plaster	Tan	Flaking	5	30.2	Positive
1	1	S11	Stairs across from Classroom 110	W4	Plaster	Tan	Flaking	1	30.2	Positive
1	1	S11	Stairs across from Classroom 110	Ceiling	Plaster	Tan	Flaking	50	24.3	Positive
1	1	S11	Stairs across from Classroom 110	Stringer	Concrete	Brown	Flaking	0	12.5	Positive
1	1	S11	Stairs across from Classroom 110	Tread	Concrete	Brown	Flaking	2	7	Positive
1	1	S11	Stairs across from Classroom 110	Riser	Concrete	Brown	Flaking	5	1.9	Positive
1	1	S11	Stairs across from Classroom 110	Radiator	Metal	Brown	None	0	0.4	Negative
1	1	S11	Stairs across from Classroom 110	Door	Metal	Red	N/A	0	0	Negative
1	1	S11	Stairs across from Classroom 110	Door Frame	Metal	Red	N/A	0	0	Negative
1	1	112	Classroom 112	Floor	12" x 12" Floor Tile	N/A	N/A	0	N/A	N/A
1	1	112	Classroom 112	W1	Plaster	Tan	Flaking	5	28.3	Positive
1	1	112	Classroom 112	W2	Plaster	Tan	Flaking	12	28.3	Positive

Dates: August 24 - September 19, 2022

Lead-Safe Certification Assessment Report

Inspector Name and Certificate Number:
Kevin Rumbol 006794

Harding School

Inspection Company: ACER Associates, LLC

2000 Wakeling Street, Philadelphia, PA 19124

Element	Floor	Space #	On-Site Room Name	Component	Substrate Material	Color	Description of Damage	Damage Quantity (sf)	XRF Reading (mg/cm ²)	XRF (positive/negative)
1	1	112	Classroom 112	W3	Plaster	Tan	Flaking	10	28.3	Positive
1	1	112	Classroom 112	W4	Plaster	Tan	Flaking	2	28.3	Positive
1	1	112	Classroom 112	Ceiling	Plaster	Tan	Flaking	170	28.3	Positive
1	1	112	Classroom 112	Baseboard	Wood	Black	N/A	0	0.02	Negative
1	1	112	Classroom 112	Radiator	Metal	Silver	None	0	0.4	Negative
1	1	111	Classroom 111	Floor	12" x 12" Floor Tile	N/A	N/A	0	N/A	N/A
1	1	111	Classroom 111	W1	Brick	Blue	None	0	1.9	Positive
1	1	111	Classroom 111	W2	Sheetrock	Blue	N/A	0	0.01	Negative
1	1	111	Classroom 111	W3	Brick	Blue	None	0	1.9	Positive
1	1	111	Classroom 111	W4	CMU	Blue	None	0	0.09	Negative
1	1	111	Classroom 111	Ceiling	Plaster	Tan	Flaking	180	26.9	Positive
1	1	111	Classroom 111	Baseboard	Wood	Black	N/A	0	0.11	Negative
1	1	111	Classroom 111	Radiator	Metal	Blue	None	0	0.03	Negative
1	1	111	Classroom 111	Door Frame	Wood	Brown	N/A	0	0.03	Negative
1	1	113	Classroom 113	Floor	9"x9" Floor Tile	N/A	N/A	0	N/A	N/A
1	1	113	Classroom 113	W1	Brick	Tan	Flaking	3	1.5	Positive
1	1	113	Classroom 113	W2	CMU	Tan	None	0	0.1	Negative
1	1	113	Classroom 113	W3	Brick	Tan	Flaking	3	1.5	Positive
1	1	113	Classroom 113	W4	Brick	Tan	Flaking	2	1.5	Positive
1	1	113	Classroom 113	W4	Sheetrock	Tan	N/A	0	0.05	Negative
1	1	113	Classroom 113	Ceiling	Plaster	Tan	Flaking	128	23.9	Positive
1	1	113	Classroom 113	Radiator	Metal	Tan	None	0	0.08	Negative
1	1	113	Classroom 113	Baseboard	Concrete	Brown	Flaking	4	1.2	Positive
1	1	113A	Girls Restroom next to Classroom 113	Floor	Concrete	Brown	N/A	0	0.01	Negative
1	1	113A	Girls Restroom next to Classroom 113	W1	Plaster	Tan	Flaking	2	20.5	Positive
1	1	113A	Girls Restroom next to Classroom 113	W2	Plaster	Tan	Flaking	3	20.5	Positive
1	1	113A	Girls Restroom next to Classroom 113	W3	Plaster	Tan	Flaking	2	20.5	Positive
1	1	113A	Girls Restroom next to Classroom 113	W4	Plaster	Tan	Flaking	2	20.5	Positive
1	1	113A	Girls Restroom next to Classroom 113	Ceiling	Sheetrock	Tan	N/A	0	0	Negative
1	1	113A	Girls Restroom next to Classroom 113	Door	Wood	Brown	None	0	0	Negative
1	1	113A	Girls Restroom next to Classroom 113	Baseboard	Concrete	Brown	N/A	0	0	Negative
1	1	113A	Girls Restroom next to Classroom 113	Pipe	Metal	Tan	None	0	0	Negative
1	1	112A	Classroom 114	Floor	12" x 12" Floor Tile	N/A	N/A	0	N/A	N/A
1	1	112A	Classroom 114	W1	Plaster	Tan	Flaking	3	21.1	Positive
1	1	112A	Classroom 114	W2	Plaster	Tan	Flaking	9	21.1	Positive
1	1	112A	Classroom 114	W3	Plaster	Tan	Flaking	40	21.1	Positive
1	1	112A	Classroom 114	W4	Plaster	Tan	Flaking	5	21.1	Positive
1	1	112A	Classroom 114	Ceiling	1x1 Ceiling Tile	N/A	N/A	0	N/A	N/A
1	1	112A	Classroom 114	Radiator	Metal	Silver	Flaking	4	2	Positive

		Dates: August 24 - September 19, 2022		Lead-Safe Certification Assessment Report							
		Inspector Name and Certificate Number: Kevin Rumbol 006794		Harding School							
		Inspection Company: ACER Associates, LLC		2000 Wakeling Street, Philadelphia, PA 19124							
Element	Floor	Space #	On-Site Room Name	Component	Substrate Material	Color	Description of Damage	Damage Quantity (sf)	XRF Reading (mg/cm2)	XRF (positive/negative)	
1	1	112A	Classroom 114	Baseboard	Concrete	Brown	Flaking	4	3.7	Positive	
1	1	113B	Classroom next to Exit doors to Wakeling Street	Floor	9"x9" Floor Tile	N/A	N/A	0	N/A	N/A	
1	1	113B	Storage Room in Exit Foyer Near S12	W1	Brick	Tan	Partially Inaccessible	4	3	Positive	
1	1	113B	Storage Room in Exit Foyer Near S12	W2	Brick	Tan	Partially Inaccessible	1	3	Positive	
1	1	113B	Storage Room in Exit Foyer Near S12	W3	Brick	Tan	Partially Inaccessible	2	3	Positive	
1	1	113B	Storage Room in Exit Foyer Near S12	W4	Brick	Tan	Partially Inaccessible	3	3	Positive	
1	1	113B	Classroom next to Exit doors to Wakeling Street	Ceiling	Plaster	Tan	No Access	No Access	No Access	No Access	
1	1	113B	Storage Room in Exit Foyer Near S12	Pipe Cover	Metal	Brown	Flaking	36	4	Positive	
1	1	113B	Classroom next to Exit doors to Wakeling Street	Door	Metal	Brown	N/A	0	0	Negative	
1	1	113B	Classroom next to Exit doors to Wakeling Street	Door Frame	Metal	Brown	N/A	0	0	Negative	
1	1	113B	Classroom next to Exit doors to Wakeling Street	Pipe	Metal	Silver	None	0	0.02	Negative	
1	1	113C	Custodial Closet across from Classroom 114	Floor	Concrete	N/A	N/A	0	N/A	N/A	
1	1	113C	Custodial Closet across from Classroom 114	W1	Plaster	Tan	Flaking	2	25.8	Positive	
1	1	113C	Custodial Closet across from Classroom 114	W2	Plaster	Tan	Flaking	6	25.8	Positive	
1	1	113C	Custodial Closet across from Classroom 114	W3	Plaster	Tan	Flaking	6	25.8	Positive	
1	1	113C	Custodial Closet across from Classroom 114	W4	Plaster	Tan	Flaking	1	25.8	Positive	
1	1	113C	Custodial Closet across from Classroom 114	Ceiling	Plaster	Tan	Flaking	20	25.9	Positive	
1	1	113C	Custodial Closet across from Classroom 114	Pipe	Metal	Tan	Flaking	12	30.8	Positive	
1	1	113PC	Pipe Chase in Custodial Closet across from Classroom 114	Floor	N/A	N/A	N/A	0	N/A	N/A	
1	1	113PC	Pipe Chase in Custodial Closet across from Classroom 114	W1	N/A	N/A	N/A	0	N/A	N/A	
1	1	113PC	Pipe Chase in Custodial Closet across from Classroom 114	W2	N/A	N/A	N/A	0	N/A	N/A	
1	1	113PC	Pipe Chase in Custodial Closet across from Classroom 114	W3	N/A	N/A	N/A	0	N/A	N/A	
1	1	113PC	Pipe Chase in Custodial Closet across from Classroom 114	W4	N/A	N/A	N/A	0	N/A	N/A	
1	1	113PC	Pipe Chase in Custodial Closet across from Classroom 114	Ceiling	N/A	N/A	N/A	0	N/A	N/A	
1	1	113D	Storage Room across from Classroom 114	Floor	No Access	No Access	N/A	0	N/A	No Access	
1	1	113D	Storage Room across from Classroom 114	W1	No Access	No Access	N/A	0	N/A	No Access	
1	1	113D	Storage Room across from Classroom 114	W2	No Access	No Access	N/A	0	N/A	No Access	
1	1	113D	Storage Room across from Classroom 114	W3	No Access	No Access	N/A	0	N/A	No Access	
1	1	113D	Storage Room across from Classroom 114	W4	No Access	No Access	N/A	0	N/A	No Access	
1	1	113D	Storage Room across from Classroom 114	Ceiling	No Access	No Access	N/A	0	N/A	No Access	
1	1	113E	Storage Closet in Stairs across from Classroom 114	Floor	No Access	No Access	N/A	0	N/A	No Access	
1	1	113E	Storage Closet in Stairs across from Classroom 114	W1	No Access	No Access	N/A	0	N/A	No Access	
1	1	113E	Storage Closet in Stairs across from Classroom 114	W2	No Access	No Access	N/A	0	N/A	No Access	
1	1	113E	Storage Closet in Stairs across from Classroom 114	W3	No Access	No Access	N/A	0	N/A	No Access	

		Dates: August 24 - September 19, 2022		Lead-Safe Certification Assessment Report						
		Inspector Name and Certificate Number: Kevin Rumbol 006794		Harding School						
		Inspection Company: ACER Associates, LLC		2000 Wakeling Street, Philadelphia, PA 19124						
Element	Floor	Space #	On-Site Room Name	Component	Substrate Material	Color	Description of Damage	Damage Quantity (sf)	XRF Reading (mg/cm2)	XRF (positive/negative)
1	1	113E	Storage Closet in Stairs across from Classroom 114	W4	No Access	No Access	N/A	0	N/A	No Access
1	1	113E	Storage Closet in Stairs across from Classroom 114	Ceiling	No Access	No Access	N/A	0	N/A	No Access
1	1	S12	Stairs across from Classroom 114	Floor	Concrete	Brown	Flaking	2	4	Positive
1	1	S12	Stairs across from Classroom 114	W1	Plaster	Tan	None	0	27.8	Positive
1	1	S12	Stairs across from Classroom 114	W2	Plaster	Tan	Flaking	1	27.8	Positive
1	1	S12	Stairs across from Classroom 114	W3	Plaster	Tan	Flaking	15	27.8	Positive
1	1	S12	Stairs across from Classroom 114	W4	Plaster	Tan	Flaking	2	27.8	Positive
1	1	S12	Stairs across from Classroom 114	Ceiling	Plaster	Tan	Flaking	10	34.6	Positive
1	1	S12	Stairs across from Classroom 114	Stringer	Concrete	Brown	Flaking	2	7.7	Positive
1	1	S12	Stairs across from Classroom 114	Tread	Concrete	Brown	Flaking	5	7.5	Positive
1	1	S12	Stairs across from Classroom 114	Riser	Concrete	Brown	Flaking	2	8.2	Positive
1	1	S12	Stairs across from Classroom 114	Balluster	Metal	Brown	Flaking	4	24.8	Positive
1	1	S12	Stairs across from Classroom 114	Stair Newel Post	Metal	Brown	Flaking	3	6.2	Positive
1	1	S12	Stairs across from Classroom 114	Radiator	Metal	Brown	None	0	0.13	Negative
1	1	S12	Stairs across from Classroom 114	Door	Metal	Red	N/A	0	0	Negative
1	1	S12	Stairs across from Classroom 114	Door Frame	Metal	Red	N/A	0	0	Negative
1	1	H14	Hallway from Classroom 110 to Storage Room across from Classroom 114	Floor	Concrete	N/A	N/A	0	N/A	N/A
1	1	H14	Hallway from Classroom 110 to Storage Room across from Classroom 114	W2	Plaster	Tan	Cracking	22	23.4	Positive
1	1	H14	Hallway from Classroom 110 to Storage Room across from Classroom 114	W4	Plaster	Tan	Cracking	15	23.4	Positive
1	1	H14	Hallway from Classroom 110 to Storage Room across from Classroom 114	Door Frame	Wood	Brown	N/A	0	0.08	Negative
1	1	H14	Hallway from Classroom 110 to Storage Room across from Classroom 114	Ceiling	Plaster	Tan	Flaking	60	31.2	Positive
1	1	H14	Hallway from Classroom 110 to Storage Room across from Classroom 114	Chair Rail	Wood	Brown	None	0	0.05	Negative
1	1	H14	Hallway from Classroom 110 to Storage Room across from Classroom 114	Baseboard	Concrete	Brown	Chipping	8	2.1	Positive
1	1	H14	Hallway from Classroom 110 to Storage Room across from Classroom 114	Door	Wood	Brown	None	0	0	Negative
1	1	114	Principal's Restroom near exit to Wakeling Street on 1st Floor	Floor	Concrete	Gray	N/A	0	N/A	Negative
1	1	114	Custodial Staff Breakroom	W1	Brick	Tan	Flaking	72	10.4	Positive
1	1	114	Custodial Staff Breakroom	W2	Brick	Tan	Flaking	70	10.4	Positive
1	1	114	Custodial Staff Breakroom	W3	Brick	Tan	Flaking	180	10.4	Positive
1	1	114	Custodial Staff Breakroom	W4	Brick	Tan	Flaking	130	10.4	Positive
1	1	114	Custodial Staff Breakroom	Ceiling	Concrete	Tan	Flaking	240	10.6	Positive

		Dates: August 24 - September 19, 2022		Lead-Safe Certification Assessment Report						
		Inspector Name and Certificate Number: Kevin Rumbol 006794		Harding School						
		Inspection Company: ACER Associates, LLC		2000 Wakeling Street, Philadelphia, PA 19124						
E l e m e n t	Floor	Space #	On-Site Room Name	Component	Substrate Material	Color	Description of Damage	Damage Quantity (sf)	XRF Reading (mg/cm ²)	XRF (positive/negative)
1	1	114	Principal's Restroom near exit to Wakeling Street on 1st Floor	Door	Metal	Brown	N/A	0	0	Negative
1	1	114	Principal's Restroom near exit to Wakeling Street on 1st Floor	Door Casing	Metal	Tan	N/A	0	0	Negative
1	1	114	Principal's Restroom near exit to Wakeling Street on 1st Floor	Radiator	Metal	Silver	None	0	0.13	Negative
1	1	115	Storage Area to left of Walking Street Exit	Floor	No Access	No Access	N/A	0	N/A	No Access
1	1	115	Storage Area to left of Walking Street Exit	W1	No Access	No Access	N/A	0	N/A	No Access
1	1	115	Storage Area to left of Walking Street Exit	W2	No Access	No Access	N/A	0	N/A	No Access
1	1	115	Storage Area to left of Walking Street Exit	W3	Brick	No Access	N/A	0	N/A	No Access
1	1	115	Storage Area to left of Walking Street Exit	W4	No Access	No Access	N/A	0	N/A	No Access
1	1	115	Storage Area to left of Walking Street Exit	Ceiling	No Access	No Access	N/A	0	N/A	No Access
1	1	NP5	Storage Room in Girl's Cafetorium Rear	Floor	No Access	No Access	N/A	0	N/A	N/A
1	1	NP5	Storage Room in Girl's Cafetorium Rear	W1	No Access	No Access	N/A	0	N/A	N/A
1	1	NP5	Storage Room in Girl's Cafetorium Rear	W2	No Access	No Access	N/A	0	N/A	N/A
1	1	NP5	Storage Room in Girl's Cafetorium Rear	W3	Brick	No Access	N/A	0	N/A	N/A
1	1	NP5	Storage Room in Girl's Cafetorium Rear	W4	No Access	No Access	N/A	0	N/A	N/A
1	1	NP5	Storage Room in Girl's Cafetorium Rear	Ceiling	No Access	No Access	N/A	0	N/A	N/A
1	1	116	Girl's Cafeteria	Floor	12" x 12" Floor Tile	N/A	N/A	0	N/A	N/A
1	1	116	Girl's Cafeteria	W1	Brick	Red	None	0	0.12	Negative
1	1	116	Girl's Cafeteria	W2	CMU	Red	None	0	0.04	Negative
1	1	116	Girl's Cafeteria	W3	Brick	Red	None	0	0.09	Negative
1	1	116	Girl's Cafeteria	W4	Brick	Red	None	0	0.4	Negative
1	1	116	Girl's Cafeteria	Ceiling	1x1 Ceiling Tile	N/A	N/A	0	N/A	N/A
1	1	116	Girl's Cafeteria	Column	Brick	Tan	N/A	0	0.3	Negative
1	1	116	Girl's Cafeteria	Door	Metal	Brown	N/A	0	0	Negative
1	1	116	Girl's Cafeteria	Door Casing	Metal	Brown	N/A	0	0	Negative
1	1	116	Girl's Cafeteria	Duct	Metal	White	Flaking	4	19.6	Positive
1	1	116D	Girl's Cafeteria Storage Closet Near Entrance	Floor	No Access	No Access	N/A	0	N/A	N/A
1	1	116D	Girl's Cafeteria Storage Closet Near Entrance	W1	No Access	No Access	N/A	0	N/A	N/A
1	1	116D	Girl's Cafeteria Storage Closet Near Entrance	W2	No Access	No Access	N/A	0	N/A	N/A
1	1	116D	Girl's Cafeteria Storage Closet Near Entrance	W3	Brick	No Access	N/A	0	N/A	N/A
1	1	116D	Girl's Cafeteria Storage Closet Near Entrance	W4	No Access	No Access	N/A	0	N/A	N/A
1	1	116D	Girl's Cafeteria Storage Closet Near Entrance	Ceiling	No Access	No Access	N/A	0	N/A	N/A
1	1	116A	Girl's Cafeteria Food Counter Area	Floor	Concrete	N/A	N/A	0	N/A	N/A
1	1	116A	Girl's Cafeteria Food Counter Area	W1	Brick	Tan	None	0	7	Positive
1	1	116A	Girl's Cafeteria Food Counter Area	W2	Brick	Tan	None	0	7	Positive
1	1	116A	Girl's Cafeteria Food Counter Area	W3	Brick	Tan	None	0	7	Positive
1	1	116A	Girl's Cafeteria Food Counter Area	W4	CMU	Tan	None	0	0	Negative

		Dates: August 24 - September 19, 2022		Lead-Safe Certification Assessment Report							
		Inspector Name and Certificate Number: Kevin Rumbol 006794		Harding School							
		Inspection Company: ACER Associates, LLC		2000 Wakeling Street, Philadelphia, PA 19124							
Element	Floor	Space #	On-Site Room Name	Component	Substrate Material	Color	Description of Damage	Damage Quantity (sf)	XRF Reading (mg/cm2)	XRF (positive/negative)	
1	1	116A	Girl's Cafeteria Food Counter Area	Ceiling	Plaster	Tan	Flaking	3	14.7	Positive	
1	1	116A	Girl's Cafeteria Food Counter Area	Column	Brick	Tan	None	0	0.07	Negative	
1	1	116A	Girl's Cafeteria Food Counter Area	Door	Wood	Clear	None	0	0	Negative	
1	1	116A	Girl's Cafeteria Food Counter Area	Door Casing	Metal	Gray	N/A	0	0.02	Negative	
1	1	116A	Girl's Cafeteria Food Counter Area	Duct	Metal	Red	Flaking	50	20.5	Positive	
1	1	H13	Hallway from Principals Restroom to Girls Cafeteria	Floor	Concrete	N/A	N/A	0	N/A	N/A	
1	1	H13	Hallway from Principals Restroom to Girls Cafeteria	W1	Plaster	Tan	Chipping	22	11.1	Positive	
1	1	H13	Hallway from Principals Restroom to Girls Cafeteria	W2	Plaster	Tan	Cracking	1	11.1	Positive	
1	1	H13	Hallway from Principals Restroom to Girls Cafeteria	W3	Plaster	Tan	Flaking	91	11.1	Positive	
1	1	H13	Hallway from Principals Restroom to Girls Cafeteria	W4	Plaster	Tan	None	0	11.1	Positive	
1	1	H13	Hallway from Principals Restroom to Girls Cafeteria	Radiator	Metal	Silver	Chipping	6	6	Positive	
1	1	H13	Hallway from Principals Restroom to Girls Cafeteria	Door Frame	Wood	Brown	N/A	0	0	Negative	
1	1	H13	Hallway from Principals Restroom to Girls Cafeteria	Ceiling	Plaster	Tan	Flaking	385	30.7	Positive	
1	1	H13	Hallway from Principals Restroom to Girls Cafeteria	Chair Rail	Wood	Brown	None	0	0.06	Negative	
1	1	H13	Hallway from Principals Restroom to Girls Cafeteria	Baseboard	Concrete	Brown	Chipping	35	6.2	Positive	
1	1	H13	Hallway from Principals Restroom to Girls Cafeteria	Railing	Metal	Silver	None	0	0.15	Negative	
1	1	H13	Hallway from Principals Restroom to Girls Cafeteria	Door	Metal	Brown	N/A	0	0	Negative	
1	1	119	Kitchen	Floor	Concrete	N/A	N/A	0	N/A	N/A	
1	1	119	Kitchen	W1	Brick	Tan	Flaking	1	4.6	Positive	
1	1	119	Kitchen	W2	Brick	Tan	Flaking	2	4.6	Positive	
1	1	119	Kitchen	W3	Brick	Tan	Flaking	3	4.6	Positive	
1	1	119	Kitchen	W4	Brick	Tan	None	0	4.6	Positive	
1	1	119	Kitchen	Ceiling	Plaster	Tan	Flaking	45	11	Positive	
1	1	119	Kitchen	Column	Brick	Tan	N/A	0	0.07	Negative	
1	1	119	Kitchen	Door	Wood	Clear	None	0	0.08	Negative	
1	1	119	Kitchen	Door Casing	Wood	Clear	N/A	0	0.08	Negative	
1	1	119	Kitchen	Duct	Metal	Red	Flaking	148	18	Positive	
1	1	119B	Restroom/Lockers in Kitchen	Floor	No Access	No Access	No Access	0	N/A	No Access	
1	1	119B	Restroom/Lockers in Kitchen	W1	No Access	No Access	No Access	0	N/A	No Access	
1	1	119B	Restroom/Lockers in Kitchen	W2	No Access	No Access	No Access	0	N/A	No Access	
1	1	119B	Restroom/Lockers in Kitchen	W3	Brick	No Access	No Access	0	N/A	No Access	
1	1	119B	Restroom/Lockers in Kitchen	W4	No Access	No Access	No Access	0	N/A	No Access	
1	1	119B	Restroom/Lockers in Kitchen	Ceiling	Concrete	No Access	No Access	0	N/A	No Access	
1	1	119C	Office in Kitchen	Floor	No Access	No Access	No Access	0	N/A	No Access	
1	1	119C	Office in Kitchen	W1	No Access	No Access	No Access	0	N/A	No Access	
1	1	119C	Office in Kitchen	W2	No Access	No Access	No Access	0	N/A	No Access	
1	1	119C	Office in Kitchen	W3	No Access	No Access	No Access	0	N/A	No Access	
1	1	119C	Office in Kitchen	W4	No Access	No Access	No Access	0	N/A	No Access	
1	1	119C	Office in Kitchen	Ceiling	No Access	No Access	No Access	0	N/A	No Access	

		Dates: August 24 - September 19, 2022		Lead-Safe Certification Assessment Report						
		Inspector Name and Certificate Number: Kevin Rumbol 006794		Harding School						
		Inspection Company: ACER Associates, LLC		2000 Wakeling Street, Philadelphia, PA 19124						
Element	Floor	Space #	On-Site Room Name	Component	Substrate Material	Color	Description of Damage	Damage Quantity (sf)	XRF Reading (mg/cm2)	XRF (positive/negative)
1	1	119A	Kitchen Large Center Storage Area	Floor	N/A	N/A	None	0	N/A	N/A
1	1	119A	Kitchen Large Center Storage Area	W1	Plaster	Tan	Cracking	24	25.7	Positive
1	1	119A	Kitchen Large Center Storage Area	W2	Plaster	Tan	Cracking	10	25.7	Positive
1	1	119A	Kitchen Large Center Storage Area	W3	CMU	Tan	None	0	0.02	Negative
1	1	119A	Kitchen Large Center Storage Area	W4	CMU	Tan	None	0	0.01	Negative
1	1	119A	Kitchen Large Center Storage Area	Ceiling	Plaster	Tan	Flaking	16	20.7	Positive
1	1	119A	Kitchen Large Center Storage Area	Door	Metal	Brown	N/A	0	0.02	Negative
1	1	119A	Kitchen Large Center Storage Area	Door Frame	Metal	Brown	N/A	0	0.06	Negative
1	1	119A	Kitchen Large Center Storage Area	Baseboard	Concrete	Gray	Chipping	10	1.7	Positive
1	1	120A	Boy's Cafeteria Food Counter Area	Floor	Concrete	Gray	None	0	N/A	Positive
1	1	120A	Boy's Cafeteria Food Counter Area	W1	Brick	Tan	Flaking	2	1	Positive
1	1	120A	Boy's Cafeteria Food Counter Area	W2	CMU	Tan	None	0	0.03	Negative
1	1	120A	Boy's Cafeteria Food Counter Area	W3	Brick	Tan	None	0	1	Positive
1	1	120A	Boy's Cafeteria Food Counter Area	W4	Brick	Tan	None	0	1	Positive
1	1	120A	Boy's Cafeteria Food Counter Area	Ceiling	Plaster	Tan	Flaking	15	17.7	Positive
1	1	120A	Boy's Cafeteria Food Counter Area	Column	Brick	Tan	N/A	0	0.3	Negative
1	1	120A	Boy's Cafeteria Food Counter Area	Door	Wood	Clear	None	0	0.02	Negative
1	1	120A	Boy's Cafeteria Food Counter Area	Door Casing	Wood	Clear	N/A	0	0.02	Negative
1	1	120A	Boy's Cafeteria Food Counter Area	Duct	Metal	Red	Flaking	64	20	Positive
1	1	120	Boy's Cafeteria	Floor	12" x 12" Floor Tile	N/A	N/A	0	N/A	N/A
1	1	120	Boy's Cafeteria	W1	Brick	Red	None	0	1.3	Positive
1	1	120	Boy's Cafeteria	W2	Brick	Red	None	0	1.3	Positive
1	1	120	Boy's Cafeteria	W3	Brick	Red	Flaking	2	1.3	Positive
1	1	120	Boy's Cafeteria	W4	CMU	Red	None	0	0	Negative
1	1	120	Boy's Cafeteria	Ceiling	Concrete	Black	None	0	0.05	Negative
1	1	120	Boy's Cafeteria	Column	Brick	Red	N/A	0	0	Negative
1	1	120	Boy's Cafeteria	Door	Metal	Brown	N/A	0	0	Negative
1	1	120	Boy's Cafeteria	Door Casing	Metal	Brown	N/A	0	0	Negative
1	1	120	Boy's Cafeteria	Duct	Metal	White	Flaking	26	18	Positive
1	1	100	Upper Part of Fan Room	Floor	N/A	N/A	N/A	0	N/A	N/A
1	1	100	Upper Part of Fan Room	W1	N/A	N/A	N/A	0	N/A	N/A
1	1	100	Upper Part of Fan Room	W2	N/A	N/A	N/A	0	N/A	N/A
1	1	100	Upper Part of Fan Room	W3	N/A	N/A	N/A	0	N/A	N/A
1	1	100	Upper Part of Fan Room	W4	N/A	N/A	N/A	0	N/A	N/A
1	1	100	Upper Part of Fan Room	Ceiling	N/A	N/A	N/A	0	N/A	N/A
1	1	100A	Corner Custodial Clock in and out Office	Floor	Concrete	Gray	N/A	0	0.1	Negative
1	1	100A	Corner Custodial Clock in and out Office	W1	Brick	Tan	Flaking	30	9.1	Positive
1	1	100A	Corner Custodial Clock in and out Office	W2	Brick	Tan	Flaking	120	9.1	Positive
1	1	100A	Corner Custodial Clock in and out Office	W3	Brick	Tan	Flaking	105	9.1	Positive

		Dates: August 24 - September 19, 2022		Lead-Safe Certification Assessment Report						
		Inspector Name and Certificate Number: Kevin Rumbol 006794		Harding School						
		Inspection Company: ACER Associates, LLC		2000 Wakeling Street, Philadelphia, PA 19124						
Element	Floor	Space #	On-Site Room Name	Component	Substrate Material	Color	Description of Damage	Damage Quantity (sf)	XRF Reading (mg/cm2)	XRF (positive/negative)
1	1	100A	Corner Custodial Clock in and out Office	W4	Brick	Tan	Flaking	250	9.1	Positive
1	1	100A	Corner Custodial Clock in and out Office	W4	Sheetrock	Tan	N/A	0	0	Negative
1	1	100A	Corner Custodial Clock in and out Office	Ceiling	Concrete	Tan	Flaking	200	10.8	Positive
1	1	100A	Corner Custodial Clock in and out Office	Radiator	Metal	Silver	None	0	0.6	Negative
1	1	100A	Corner Custodial Clock in and out Office	Pipe	Metal	Silver	Flaking	14	3.5	Positive
1	1	100A	Corner Custodial Clock in and out Office	Window Frame	Wood	Brown	None	0	0.05	Negative
1	1	100A	Corner Custodial Clock in and out Office	Door Frame	Metal	Brown	N/A	0	0	Negative
1	1	100A	Corner Custodial Clock in and out Office	Window	Wood	Tan	Flaking	2	8.2	Positive
1	1	100A	Corner Custodial Clock in and out Office	Window Casing	Wood	Tan	Flaking	4	11	Positive
1	1	100A	Corner Custodial Clock in and out Office	Door	Metal	Brown	N/A	0	0	Negative
1	1	H12	Hallway from Boys Cafeteria to Corner Custodial Clock in and out Office	Floor	Concrete	N/A	N/A	0	N/A	N/A
1	1	H12	Hallway from Boys Cafeteria to Corner Custodial Clock in and out Office	W1	Plaster	Tan	Chipping	1	14.4	Positive
1	1	H12	Hallway from Boys Cafeteria to Corner Custodial Clock in and out Office	W2	Plaster	Tan	Cracking	12	14.4	Positive
1	1	H12	Hallway from Boys Cafeteria to Corner Custodial Clock in and out Office	W3	Plaster	Tan	Flaking	2	14.4	Positive
1	1	H12	Hallway from Boys Cafeteria to Corner Custodial Clock in and out Office	W4	Plaster	Tan	None	0	14.4	Positive
1	1	H12	Hallway from Boys Cafeteria to Corner Custodial Clock in and out Office	Radiator	Metal	Silver	Chipping	4	3.7	Positive
1	1	H12	Hallway from Boys Cafeteria to Corner Custodial Clock in and out Office	Door Frame	Wood	Brown	N/A	0	0.08	Negative
1	1	H12	Hallway from Boys Cafeteria to Corner Custodial Clock in and out Office	Ceiling	Plaster	Tan	Flaking	415	26.6	Positive
1	1	H12	Hallway from Boys Cafeteria to Corner Custodial Clock in and out Office	Chair Rail	Wood	Brown	None	0	0.4	Negative
1	1	H12	Hallway from Boys Cafeteria to Corner Custodial Clock in and out Office	Baseboard	Concrete	Brown	Chipping	6	6.5	Positive
1	1	H12	Hallway from Boys Cafeteria to Corner Custodial Clock in and out Office	Railing	Metal	Silver	None	0	0.4	Negative
1	1	H12	Hallway from Boys Cafeteria to Corner Custodial Clock in and out Office	Door	Metal	Brown	N/A	0	0	Negative
1	1	102	Classroom 102	Floor	N/A	N/A	N/A	0	N/A	N/A
1	1	102	Classroom 102	W1	Brick	Blue	Chipping	1	3.4	Positive
1	1	102	Classroom 102	W2	Sheetrock	Tan	N/A	0	0.06	Negative
1	1	102	Classroom 102	W3	Brick	Blue	None	0	3.4	Positive
1	1	102	Classroom 102	W4	Brick	Blue	None	0	3.4	Positive
1	1	102	Classroom 102	Ceiling	Plaster	Tan	Flaking	821	29.1	Positive
1	1	102	Classroom 102	Radiator	Metal	Silver	Chipping	14	5.8	Positive

		Dates: August 24 - September 19, 2022		Lead-Safe Certification Assessment Report							
		Inspector Name and Certificate Number: Kevin Rumbol 006794		Harding School							
		Inspection Company: ACER Associates, LLC		2000 Wakeling Street, Philadelphia, PA 19124							
Element	Floor	Space #	On-Site Room Name	Component	Substrate Material	Color	Description of Damage	Damage Quantity (sf)	XRF Reading (mg/cm2)	XRF (positive/negative)	
1	1	102	Classroom 102	Baseboard	Concrete	Brown	Chipping	3	1.4	Positive	
1	1	102	Classroom 102	Electrical Panel	Metal	Blue	N/A	0	0.37	Negative	
1	1	102A	Closet in Classroom 102	Floor	No Access	No Access	No Access	No Access	No Access	No Access	
1	1	102A	Closet in Classroom 102	W1	No Access	No Access	No Access	No Access	No Access	No Access	
1	1	102A	Closet in Classroom 102	W2	No Access	No Access	No Access	No Access	No Access	No Access	
1	1	102A	Closet in Classroom 102	W3	Brick	No Access	No Access	No Access	No Access	No Access	
1	1	102A	Closet in Classroom 102	W4	No Access	No Access	No Access	No Access	No Access	No Access	
1	1	102A	Closet in Classroom 102	Ceiling	No Access	No Access	No Access	No Access	No Access	No Access	
1	1	S13	Stairs across from Classroom 102	Floor	Concrete	Brown	None	0	1.2	Positive	
1	1	S13	Stairs across from Classroom 102	W1	Plaster	Tan	Flaking	1	31.4	Positive	
1	1	S13	Stairs across from Classroom 102	W2	Plaster	Tan	Flaking	1	31.4	Positive	
1	1	S13	Stairs across from Classroom 102	W3	Plaster	Tan	Flaking	3	31.4	Positive	
1	1	S13	Stairs across from Classroom 102	W4	Plaster	Tan	None	0	31.4	Positive	
1	1	S13	Stairs across from Classroom 102	Ceiling	Plaster	Tan	Flaking	10	32.3	Positive	
1	1	S13	Stairs across from Classroom 102	Stringer	Concrete	Brown	Flaking	8	6.7	Positive	
1	1	S13	Stairs across from Classroom 102	Tread	Concrete	Brown	Flaking	7	5.4	Positive	
1	1	S13	Stairs across from Classroom 102	Riser	Concrete	Brown	Flaking	11	7.6	Positive	
1	1	S13	Stairs across from Classroom 102	Balluster	Metal	Brown	Flaking	4	15.9	Positive	
1	1	S13	Stairs across from Classroom 102	Stair Newel Post	Metal	Brown	Flaking	4	8.8	Positive	
1	1	S13	Stairs across from Classroom 102	Radiator	Metal	Brown	None	0	0.4	Negative	
1	1	S13	Stairs across from Classroom 102	Door	Metal	Red	N/A	0	0	Negative	
1	1	S13	Stairs across from Classroom 102	Door Frame	Metal	Red	N/A	0	0	Negative	
1	1	S13A	Closet in Stair across from Classroom 102 (Paint Room)	Floor	No Access	No Access	N/A	0	N/A	No Access	
1	1	S13A	Closet in Stair across from Classroom 102 (Paint Room)	W1	No Access	No Access	N/A	0	N/A	No Access	
1	1	S13A	Closet in Stair across from Classroom 102 (Paint Room)	W2	No Access	No Access	N/A	0	N/A	No Access	
1	1	S13A	Closet in Stair across from Classroom 102 (Paint Room)	W3	No Access	No Access	N/A	0	N/A	No Access	
1	1	S13A	Closet in Stair across from Classroom 102 (Paint Room)	W4	No Access	No Access	N/A	0	N/A	No Access	
1	1	S13A	Closet in Stair across from Classroom 102 (Paint Room)	Ceiling	No Access	No Access	N/A	0	N/A	No Access	
1	1	101AB	Storage Closet across from Classroom 102	Floor	No Access	No Access	N/A	0	N/A	No Access	
1	1	101AB	Storage Closet across from Classroom 102	W1	No Access	No Access	N/A	0	N/A	No Access	
1	1	101AB	Storage Closet across from Classroom 102	W2	No Access	No Access	N/A	0	N/A	No Access	
1	1	101AB	Storage Closet across from Classroom 102	W3	No Access	No Access	N/A	0	N/A	No Access	
1	1	101AB	Storage Closet across from Classroom 102	W4	No Access	No Access	N/A	0	N/A	No Access	

			Dates: August 24 - September 19, 2022	Lead-Safe Certification Assessment Report						
			Inspector Name and Certificate Number: Kevin Rumbol 006794	Harding School						
			Inspection Company: ACER Associates, LLC	2000 Wakeling Street, Philadelphia, PA 19124						
Element	Floor	Space #	On-Site Room Name	Component	Substrate Material	Color	Description of Damage	Damage Quantity (sf)	XRF Reading (mg/cm2)	XRF (positive/negative)
1	1	101AB	Storage Closet across from Classroom 102	Ceiling	No Access	No Access	N/A	0	N/A	No Access
1	1	101C	Custodial Closet across from Classroom 102	Floor	No Access	No Access	N/A	0	N/A	No Access
1	1	101C	Custodial Closet across from Classroom 102	W1	No Access	No Access	N/A	0	N/A	No Access
1	1	101C	Custodial Closet across from Classroom 102	W2	No Access	No Access	N/A	0	N/A	No Access
1	1	101C	Custodial Closet across from Classroom 102	W3	No Access	No Access	N/A	0	N/A	No Access
1	1	101C	Custodial Closet across from Classroom 102	W4	No Access	No Access	N/A	0	N/A	No Access
1	1	101C	Custodial Closet across from Classroom 102	Ceiling	No Access	No Access	N/A	0	N/A	No Access
1	1	101CPC	Pipe Chase in Custodial Closet across from Classroom 102	Floor	N/A	N/A	N/A	0	N/A	N/A
1	1	101CPC	Pipe Chase in Custodial Closet across from Classroom 102	W1	N/A	N/A	N/A	0	N/A	N/A
1	1	101CPC	Pipe Chase in Custodial Closet across from Classroom 102	W2	N/A	N/A	N/A	0	N/A	N/A
1	1	101CPC	Pipe Chase in Custodial Closet across from Classroom 102	W3	N/A	N/A	N/A	0	N/A	N/A
1	1	101CPC	Pipe Chase in Custodial Closet across from Classroom 102	W4	N/A	N/A	N/A	0	N/A	N/A
1	1	101CPC	Pipe Chase in Custodial Closet across from Classroom 102	Ceiling	N/A	N/A	N/A	0	N/A	N/A
1	1	101A	Boy's Restroom across from Classroom 102	Floor	Concrete	Brown	N/A	0	0.01	Negative
1	1	101A	Boy's Restroom across from Classroom 102	W1	Plaster	Tan	Chipping	1	17	Positive
1	1	101A	Boy's Restroom across from Classroom 102	W2	Plaster	Tan	Chipping	1	17	Positive
1	1	101A	Boy's Restroom across from Classroom 102	W3	Plaster	Tan	Cracking	3	17	Positive
1	1	101A	Boy's Restroom across from Classroom 102	W4	Plaster	Tan	None	0	17	Positive
1	1	101A	Boy's Restroom across from Classroom 102	Door	Wood	Brown	None	0	0	Negative
1	1	101A	Boy's Restroom across from Classroom 102	Baseboard	Concrete	Brown	N/A	0	0.01	Negative
1	1	101A	Boy's Restroom across from Classroom 102	Pipe	Metal	Tan	None	0	0	Negative
1	1	101A	Boy's Restroom across from Classroom 102	Ceiling	Sheetrock	Tan	N/A	0	0	Negative
1	1	101	Classroom 101 (Police Room)	Floor	N/A	N/A	N/A	0	N/A	N/A
1	1	101	Classroom 101 (Police Room)	W1	Brick	Tan	Chipping	1	2	Positive
1	1	101	Classroom 101 (Police Room)	W2	Sheetrock	Tan	N/A	0	0.06	Negative
1	1	101	Classroom 101 (Police Room)	W3	Brick	Tan	None	0	2	Positive
1	1	101	Classroom 101 (Police Room)	W4	CMU	Tan	None	0	0.1	Negative
1	1	101	Classroom 101 (Police Room)	Ceiling	Plaster	Tan	Flaking	156	25.5	Positive
1	1	101	Classroom 101 (Police Room)	Radiator Cover	Metal	Tan	N/A	0	0.01	Negative
1	1	101	Classroom 101 (Police Room)	Baseboard	Concrete	Brown	Chipping	8	1.8	Positive
1	1	101B	Closet in Classroom 101/ Police Room	Floor	N/A	N/A	N/A	0	N/A	N/A
1	1	101B	Closet in Classroom 101/ Police Room	W1	Sheetrock	Tan	N/A	0	0.06	Negative
1	1	101B	Closet in Classroom 101/ Police Room	W2	Brick	Tan	Chipping	10	3.9	Positive
1	1	101B	Closet in Classroom 101/ Police Room	W3	Brick	Tan	Chipping	184	3.9	Positive

		Dates: August 24 - September 19, 2022		Lead-Safe Certification Assessment Report						
		Inspector Name and Certificate Number: Kevin Rumbol 006794		Harding School						
		Inspection Company: ACER Associates, LLC		2000 Wakeling Street, Philadelphia, PA 19124						
Element	Floor	Space #	On-Site Room Name	Component	Substrate Material	Color	Description of Damage	Damage Quantity (sf)	XRF Reading (mg/cm2)	XRF (positive/negative)
1	1	101B	Closet in Classroom 101/ Police Room	W4	Brick	Tan	Chipping	40	3.9	Positive
1	1	101B	Closet in Classroom 101/ Police Room	Door Frame	Metal	Green	N/A	0	0.05	Negative
1	1	101B	Closet in Classroom 101/ Police Room	Ceiling	Plaster	Tan	Flaking	5	22.6	Positive
1	1	101BE	Building Engineer's Office	Floor	N/A	N/A	N/A	0	N/A	N/A
1	1	101BE	Building Engineer's Office	W1	N/A	N/A	N/A	0	N/A	N/A
1	1	101BE	Building Engineer's Office	W2	N/A	N/A	N/A	0	N/A	N/A
1	1	101BE	Building Engineer's Office	W3	N/A	N/A	N/A	0	N/A	N/A
1	1	101BE	Building Engineer's Office	W4	N/A	N/A	N/A	0	N/A	N/A
1	1	101BE	Building Engineer's Office	Ceiling	N/A	N/A	N/A	0	N/A	N/A
1	1	103	Classroom 103	Floor	N/A	N/A	N/A	0	N/A	N/A
1	1	103	Classroom 103	W1	Brick	Tan	Chipping	1	2	Positive
1	1	103	Classroom 103	W2	Sheetrock	Tan	None	0	0.09	Negative
1	1	103	Classroom 103	W2	CMU	Tan	None	0	0.12	Negative
1	1	103	Classroom 103	W3	Brick	Tan	Chipping	5	2	Positive
1	1	103	Classroom 103	W4	Brick	Tan	Chipping	1	2	Positive
1	1	103	Classroom 103	Ceiling	Plaster	Tan	Flaking	415	19.9	Positive
1	1	103	Classroom 103	Baseboard	Concrete	Brown	Chipping	12	2.6	Positive
1	1	103	Classroom 103	Radiator Cover	Metal	Tan	N/A	0	0.01	Negative
1	1	103A	Classroom 103 Closet	Floor	N/A	N/A	N/A	0	N/A	N/A
1	1	103A	Classroom 103 Closet	W1	Metal	Green	N/A	0	0.05	Negative
1	1	103A	Classroom 103 Closet	W2	Brick	Green	None	0	1.9	Positive
1	1	103A	Classroom 103 Closet	W3	CMU	Green	None	0	0.07	Negative
1	1	103A	Classroom 103 Closet	W4	Sheetrock	Green	N/A	0	0.06	Negative
1	1	103A	Classroom 103 Closet	Ceiling	Plaster	Green	None	0	19.9	Positive
1	1	103A	Classroom 103 Closet	Duct	Metal	Green	None	0	0.09	Negative
1	1	104	Classroom 104	Floor	N/A	N/A	N/A	0	N/A	N/A
1	1	104	Classroom 104	W1	Brick	Blue	None	0	1.1	Positive
1	1	104	Classroom 104	W2	Brick	Blue	None	0	1.1	Positive
1	1	104	Classroom 104	W3	Brick	Blue	Chipping	1	1.1	Positive
1	1	104	Classroom 104	W4	Brick	Tan	None	0	0.09	Negative
1	1	104	Classroom 104	Ceiling	Plaster	Tan	Flaking	440	33.6	Positive
1	1	104	Classroom 104	Baseboard	Concrete	Brown	Chipping	23	1.1	Positive
1	1	104A	Classroom 104 Closet	Floor	N/A	N/A	N/A	0	N/A	N/A
1	1	104A	Classroom 104 Closet	W1	Brick	Tan	None	0	0.09	Negative
1	1	104A	Classroom 104 Closet	W2	Brick	Tan	None	0	0.11	Negative
1	1	104A	Classroom 104 Closet	W3	Brick	Tan	None	0	0.12	Negative
1	1	104A	Classroom 104 Closet	W4	Brick	Tan	None	0	0.04	Negative
1	1	104A	Classroom 104 Closet	Ceiling	Plaster	Tan	Flaking	32	1.1	Positive
1	1	104A	Classroom 104 Closet	Radiator	Metal	Silver	None	0	0.22	Negative

		Dates: August 24 - September 19, 2022		Lead-Safe Certification Assessment Report						
		Inspector Name and Certificate Number: Kevin Rumbol 006794		Harding School						
		Inspection Company: ACER Associates, LLC		2000 Wakeling Street, Philadelphia, PA 19124						
Element	Floor	Space #	On-Site Room Name	Component	Substrate Material	Color	Description of Damage	Damage Quantity (sf)	XRF Reading (mg/cm2)	XRF (positive/negative)
1	1	S14	Stairs across from Classroom 104	Floor	Concrete	Brown	Flaking	4	2.4	Positive
1	1	S14	Stairs across from Classroom 104	W1	Plaster	Tan	None	0	33.2	Positive
1	1	S14	Stairs across from Classroom 104	W2	Plaster	Tan	Flaking	10	33.2	Positive
1	1	S14	Stairs across from Classroom 104	W3	Plaster	Tan	Flaking	2	33.2	Positive
1	1	S14	Stairs across from Classroom 104	W4	Plaster	Tan	None	0	33.2	Positive
1	1	S14	Stairs across from Classroom 104	Ceiling	Plaster	Tan	Flaking	45	16.8	Positive
1	1	S14	Stairs across from Classroom 104	Stringer	Concrete	Brown	Flaking	1	8.5	Positive
1	1	S14	Stairs across from Classroom 104	Tread	Concrete	Brown	Flaking	2	6.2	Positive
1	1	S14	Stairs across from Classroom 104	Riser	Concrete	Brown	Flaking	4	7.1	Positive
1	1	S14	Stairs across from Classroom 104	Stair Newel Post	Metal	Brown	Flaking	4	8.8	Positive
1	1	S14	Stairs across from Classroom 104	Balluster	Metal	Brown	Flaking	5	15.9	Positive
1	1	S14	Stairs across from Classroom 104	Radiator	Metal	Brown	None	0	0.03	Negative
1	1	S14	Stairs across from Classroom 104	Door	Metal	Red	N/A	0	0	Negative
1	1	S14	Stairs across from Classroom 104	Door Frame	Metal	Red	N/A	0	0	Negative
1	1	H18	Hallway from Classroom 102 to Classroom 104	Floor	Concrete	N/A	N/A	0	N/A	N/A
1	1	H18	Hallway from Classroom 102 to Classroom 104	Chair Rail	Wood	Brown	None	0	0.12	Negative
1	1	H18	Hallway from Classroom 102 to Classroom 104	W2	Plaster	Tan	Flaking	44	10.7	Positive
1	1	H18	Hallway from Classroom 102 to Classroom 104	Baseboard	Concrete	Brown	Chipping	10	7.8	Positive
1	1	H18	Hallway from Classroom 102 to Classroom 104	W4	Plaster	Tan	Flaking	9	10.7	Positive
1	1	H18	Hallway from Classroom 102 to Classroom 104	Ceiling	Plaster	Tan	Flaking	265	25.9	Positive
1	1	H18	Hallway from Classroom 102 to Classroom 104	Door Casing	Wood	Brown	N/A	0	0.15	Negative
1	1	105	Classroom 105A	Floor	12" x 12" Floor Tile	N/A	N/A	0	N/A	N/A
1	1	105	Classroom 105A	Floor	Concrete	Brown	Flaking	4	1.1	Positive
1	1	105	Classroom 105A	W1	Sheetrock	Tan	N/A	0	0	Negative
1	1	105	Classroom 105A	W1	Brick	Tan	Flaking	4	4.1	Positive
1	1	105	Classroom 105A	W2	Brick	Tan	Flaking	1	4.1	Positive
1	1	105	Classroom 105A	W3	Brick	Tan	Flaking	2	4.1	Positive
1	1	105	Classroom 105A	W4	Brick	Tan	Flaking	1	4.1	Positive
1	1	105	Classroom 105A	Ceiling	Plaster	Tan	Flaking	520	30.3	Positive
1	1	105	Classroom 105A	Radiator	Metal	Silver	Flaking	10	6.1	Positive
1	1	105	Classroom 105A	Baseboard	Concrete	Brown	Flaking	3	1.2	Positive
1	1	105	Classroom 105A	Pipe Cover	Metal	Brown	Flaking	1	2.2	Positive
1	1	105	Classroom 105A	Window Frame	Wood	Brown	None	0	0.03	Negative
1	1	105A	Classroom 105B	Floor	12" x 12" Floor Tile	N/A	N/A	0	N/A	N/A
1	1	105A	Classroom 105B	Floor	Concrete	Brown	Flaking	3	1.3	Positive
1	1	105A	Classroom 105B	W1	Sheetrock	Tan	N/A	0	0	Negative
1	1	105A	Classroom 105B	W2	Brick	Tan	Flaking	1	3.2	Positive
1	1	105A	Classroom 105B	W3	Brick	Tan	None	0	3.2	Positive

		Dates: August 24 - September 19, 2022		Lead-Safe Certification Assessment Report							
		Inspector Name and Certificate Number: Kevin Rumbol 006794		Harding School							
		Inspection Company: ACER Associates, LLC		2000 Wakeling Street, Philadelphia, PA 19124							
Element	Floor	Space #	On-Site Room Name	Component	Substrate Material	Color	Description of Damage	Damage Quantity (sf)	XRF Reading (mg/cm2)	XRF (positive/negative)	
1	1	105A	Classroom 105B	W3	CMU	Tan	None	0	0	Negative	
1	1	105A	Classroom 105B	W4	Brick	Tan	Flaking	1	3.2	Positive	
1	1	105A	Classroom 105B	W4	Plaster	Tan	Flaking	6	25.9	Positive	
1	1	105A	Classroom 105B	W4	Concrete	Tan	None	0	0	Negative	
1	1	105A	Classroom 105B	Ceiling	Plaster	Tan	Flaking	468	25.3	Positive	
1	1	105A	Classroom 105B	Baseboard	Concrete	Brown	Flaking	6	1.6	Positive	
1	1	105A	Classroom 105B	Pipe Cover	Metal	Brown	Flaking	2	1	Positive	
1	1	105A	Classroom 105B	Radiator	Metal	Silver	None	0	5.8	Positive	
1	1	105A	Classroom 105B	Door Frame	Metal	Brown	N/A	0	0.02	Negative	
1	1	105A	Classroom 105B	Pipe	Metal	Tan	None	0	0.11	Negative	
1	1	106B	Office 106B	Floor	12" x 12" Floor Tile	N/A	N/A	0	N/A	N/A	
1	1	106E	Office 106B	Floor	Concrete	Gray	Flaking	13	3.2	Positive	
1	1	106B	Office 106B	W1	Sheetrock	Green	N/A	0	0	Negative	
1	1	106B	Office 106B	W2	Brick	Green	None	0	2.3	Positive	
1	1	106B	Office 106B	W3	Brick	Green	None	0	2.3	Positive	
1	1	106E	Office 106B	W4	Brick	Green	Flaking	2	2.3	Positive	
1	1	106E	Office 106B	Ceiling	Plaster	Tan	Flaking	308	26.8	Positive	
1	1	106B	Office 106B	Door Frame	Metal	Gray	N/A	0	0	Negative	
1	1	106E	Office 106B	Baseboard	Concrete	Blue	Flaking	5	1	Positive	
1	1	106E	Office 106B	Radiator	Metal	Silver	Flaking	4	3.6	Positive	
1	1	106E	Office 106B	Pipe Cover	Metal	Brown	Flaking	2	2.6	Positive	
1	1	106C	Closet in Office 106B	Floor	Concrete	Gray	N/A	0	0.01	Negative	
1	1	106F	Closet in Office 106B	W1	Plaster	Tan	Flaking	25	23.6	Positive	
1	1	106C	Closet in Office 106B	W2	Plaster	Tan	None	0	23.6	Positive	
1	1	106F	Closet in Office 106B	W3	Plaster	Tan	Flaking	42	23.6	Positive	
1	1	106F	Closet in Office 106B	W4	Plaster	Tan	Flaking	42	23.6	Positive	
1	1	106C	Closet in Office 106B	W4	Sheetrock	Tan	None	0	0	Negative	
1	1	106F	Closet in Office 106B	Ceiling	Plaster	Tan	Flaking	130	22.8	Positive	
1	1	106C	Closet in Office 106B	Door Frame	Metal	Tan	N/A	0	0	Negative	
1	1	106F	Closet in Office 106B	Radiator	Metal	Silver	Flaking	1	3.1	Positive	
1	1	106C	Closet in Office 106B	Baseboard	Concrete	Gray	None	0	11.9	Positive	
1	1	106C	Closet in Office 106B	Pipe	Metal	Tan	None	0	0.11	Negative	
1	1	106A	Classroom 106A	Floor	12" x 12" Floor Tile	N/A	N/A	0	N/A	N/A	
1	1	106	Classroom 106A	Floor	Concrete	Gray	Flaking	5	3.4	Positive	
1	1	106A	Classroom 106A	W1	Sheetrock	Green	N/A	0	0	Negative	
1	1	106A	Classroom 106A	W2	Brick	Green	None	0	1.8	Positive	
1	1	106A	Classroom 106A	W3	Brick	Green	None	0	1.8	Positive	
1	1	106A	Classroom 106A	W4	Brick	Green	None	0	1.8	Positive	
1	1	106	Classroom 106A	Ceiling	Plaster	Tan	Flaking	336	29	Positive	

		Dates: August 24 - September 19, 2022		Lead-Safe Certification Assessment Report						
		Inspector Name and Certificate Number: Kevin Rumbol 006794		Harding School						
		Inspection Company: ACER Associates, LLC		2000 Wakeling Street, Philadelphia, PA 19124						
Element	Floor	Space #	On-Site Room Name	Component	Substrate Material	Color	Description of Damage	Damage Quantity (sf)	XRF Reading (mg/cm2)	XRF (positive/negative)
1	1	106A	Classroom 106A	Door Frame	Metal	Gray	N/A	0	0.01	Negative
1	1	106	Classroom 106A	Baseboard	Concrete	Gray	Flaking	2	2.3	Positive
1	1	106	Classroom 106A	Radiator	Metal	Silver	Flaking	4	4.5	Positive
1	1	106	Classroom 106A	Pipe Cover	Metal	Brown	Flaking	2	2.3	Positive
1	1	106D	Classroom 106A Storage Closet with windows	Floor	Wood	N/A	N/A	0	N/A	N/A
1	1	106A	Classroom 106A Storage Closet with windows	W1	Brick	Green	Partially Inaccessible	2	1.9	Positive
1	1	106A	Classroom 106A Storage Closet with windows	W2	Brick	Green	Partially Inaccessible	2	1.9	Positive
1	1	106D	Classroom 106A Storage Closet with windows	W3	CMU	Green	None	0	0.04	Negative
1	1	106D	Classroom 106A Storage Closet with windows	W4	Brick	Green	Partially Inaccessible	0	1.9	Positive
1	1	106A	Classroom 106A Storage Closet with windows	Ceiling	Plaster	White	Flaking	15	10.5	Positive
1	1	106A	Classroom 106A Storage Closet with windows	Pipe Cover	Metal	Gray	Flaking	1	2.7	Positive
1	1	106E	Classroom 106A Storage Closet without Windows	Floor	Wood	N/A	N/A	0	N/A	N/A
1	1	106E	Classroom 106A Storage Closet without Windows	W1	Brick	Tan	None	0	0.3	Negative
1	1	106E	Classroom 106A Storage Closet without Windows	W2	Brick	Tan	None	0	0.08	Negative
1	1	106E	Classroom 106A Storage Closet without Windows	W2	CMU	Tan	None	0	0	Negative
1	1	106B	Classroom 106A Storage Closet without Windows	W3	Plaster	Tan	Flaking	4	29.8	Positive
1	1	106E	Classroom 106A Storage Closet without Windows	W4	Brick	Black	None	0	0	Negative
1	1	106B	Classroom 106A Storage Closet without Windows	W4	Plaster	Tan	Flaking	5	6.9	Positive
1	1	106B	Classroom 106A Storage Closet without Windows	Ceiling	Plaster	Black	Flaking	11	10.1	Positive
1	1	106B	Classroom 106A Storage Closet without Windows	Pipe Cover	Metal	Gray	Flaking	2	3.7	Positive
1	1	106E	Classroom 106A Storage Closet without Windows	Door Frame	Metal	Gray	N/A	0	0	Negative
1	1	105C	Office across from Classroom 105B	Floor	Concrete	N/A	N/A	0	N/A	N/A
1	1	105C	Office across from Classroom 105B	W1	N/A	N/A	N/A	0	N/A	N/A
1	1	105C	Office across from Classroom 105B	W2	N/A	N/A	N/A	0	N/A	N/A
1	1	105C	Office across from Classroom 105B	W3	Brick	N/A	N/A	0	N/A	N/A
1	1	105C	Office across from Classroom 105B	W4	N/A	N/A	N/A	0	N/A	N/A
1	1	105C	Office across from Classroom 105B	Ceiling	Concrete	N/A	N/A	0	N/A	N/A
1	1	H110	Hallway from Classroom 105A to Classroom 106A	Floor	Concrete	N/A	N/A	0	N/A	N/A
1	1	H110	Hallway from Classroom 105A to Classroom 106A	W1	Plaster	Tan	Cracking	12	14.9	Positive
1	1	H110	Hallway from Classroom 105A to Classroom 106A	W2	Plaster	Tan	Cracking	10	14.9	Positive
1	1	H110	Hallway from Classroom 105A to Classroom 106A	W3	Plaster	Tan	Chipping	3	14.9	Positive
1	1	H110	Hallway from Classroom 105A to Classroom 106A	W4	Plaster	Tan	Cracking	1	14.9	Positive
1	1	H110	Hallway from Classroom 105A to Classroom 106A	Ceiling	Plaster	Tan	Flaking	65	13.8	Positive
1	1	H110	Hallway from Classroom 105A to Classroom 106A	Door	Wood	Brown	None	0	0.04	Negative
1	1	H110	Hallway from Classroom 105A to Classroom 106A	Door Frame	Wood	Brown	N/A	0	0.05	Negative
1	1	H110	Hallway from Classroom 105A to Classroom 106A	Chair Rail	Wood	Brown	None	0	0	Negative
1	1	H110	Hallway from Classroom 105A to Classroom 106A	Baseboard	Concrete	Brown	Chipping	8	7.6	Positive
1	1	H110	Hallway from Classroom 105A to Classroom 106A	Locker	Metal	Red	Flaking	0	0.01	Negative
1	1	121	Boy's Gymnasium	Floor	Rubber	N/A	N/A	0	N/A	N/A

		Dates: August 24 - September 19, 2022		Lead-Safe Certification Assessment Report						
		Inspector Name and Certificate Number: Kevin Rumbol 006794		Harding School						
		Inspection Company: ACER Associates, LLC		2000 Wakeling Street, Philadelphia, PA 19124						
Element	Floor	Space #	On-Site Room Name	Component	Substrate Material	Color	Description of Damage	Damage Quantity (sf)	XRF Reading (mg/cm2)	XRF (positive/negative)
1	1	121	Boy's Gymnasium	W1	Brick	Tan	Flaking	5	2.7	Positive
1	1	121	Boy's Gymnasium	W2	Brick	Tan	Flaking	18	2.7	Positive
1	1	121	Boy's Gymnasium	W3	Brick	Tan	Flaking	5	2.7	Positive
1	1	121	Boy's Gymnasium	W4	Brick	Tan	Flaking	25	2.7	Positive
1	1	121	Boy's Gymnasium	Ceiling	Metal	Tan	Flaking	800	3.7	Positive
1	1	121	Boy's Gymnasium	Ceiling	Concrete	Tan	Flaking	475	3.3	Positive
1	1	121	Boy's Gymnasium	Window	Wood	Green	None	0	0	Negative
1	1	121	Boy's Gymnasium	Window Frame	Wood	Green	None	0	0.4	Negative
1	1	121	Boy's Gymnasium	Pipe	Metal	Tan	Flaking	9	4.6	Positive
1	1	121	Boy's Gymnasium	Radiator	Metal	Silver	Flaking	40	3.1	Positive
1	1	121A	Boy's Gym Teacher Office	Floor	Wood	N/A	N/A	0	N/A	N/A
1	1	121A	Boy's Gym Teacher Office	W1	Brick	Tan	Flaking	35	2.7	Positive
1	1	121A	Boy's Gym Teacher Office	W2	Brick	Tan	Flaking	12	2.7	Positive
1	1	121A	Boy's Gym Teacher Office	W3	Brick	Tan	Flaking	70	2.7	Positive
1	1	121A	Boy's Gym Teacher Office	W4	Brick	Tan	Flaking	18	2.7	Positive
1	1	121A	Boy's Gym Teacher Office	Ceiling	Concrete	Tan	Flaking	22	7.4	Positive
1	1	121A	Boy's Gym Teacher Office	Pipe	Metal	Tan	Flaking	12	3.1	Positive
1	1	121A	Boy's Gym Teacher Office	Door	Metal	Brown	N/A	0	0	Negative
1	1	121A	Boy's Gym Teacher Office	Door Frame	Metal	Brown	N/A	0	0	Negative
1	1	121AB	Storage Closet in Boy's Gym Teacher Office	Floor	Brick	N/A	N/A	0	N/A	N/A
1	1	121AB	Storage Closet in Boy's Gym Teacher Office	W1	Brick	N/A	N/A	0	N/A	N/A
1	1	121AB	Storage Closet in Boy's Gym Teacher Office	W2	Brick	N/A	N/A	0	N/A	N/A
1	1	121AB	Storage Closet in Boy's Gym Teacher Office	W3	Brick	N/A	N/A	0	N/A	N/A
1	1	121AB	Storage Closet in Boy's Gym Teacher Office	W4	Brick	N/A	N/A	0	N/A	N/A
1	1	121AB	Storage Closet in Boy's Gym Teacher Office	Ceiling	Concrete	N/A	N/A	0	N/A	N/A
1	1	121B	Storage in Front of Boy's Gym	Floor	Wood	N/A	N/A	0	N/A	N/A
1	1	121B	Storage in Front of Boy's Gym	W1	Brick	Tan	Partially Inaccessible	1	3.3	Positive
1	1	121B	Storage in Front of Boy's Gym	W2	Brick	Tan	Partially Inaccessible	1	3.3	Positive
1	1	121B	Storage in Front of Boy's Gym	W3	Brick	Tan	Partially Inaccessible	1	3.3	Positive
1	1	121B	Storage in Front of Boy's Gym	W4	Brick	Tan	Partially Inaccessible	1	3.3	Positive
1	1	121B	Storage in Front of Boy's Gym	Ceiling	Concrete	Tan	Partially Inaccessible	1	5.4	Positive
1	1	121B	Storage in Front of Boy's Gym	Pipe	Metal	Tan	Partially Inaccessible	1	4.3	Positive
1	1	121B	Storage in Front of Boy's Gym	Door	Metal	Brown	None	0	0	Negative
1	1	121B	Storage in Front of Boy's Gym	Door Frame	Metal	Brown	N/A	0	0	Negative
1	1	121D	Boy's Locker Room near Gym	Floor	12" x 12" Floor Tile	N/A	N/A	0	N/A	N/A
1	1	121D	BE's Office Former Boy's Locker Room near Gym	W1	Brick	Tan	Flaking	2	6.3	Positive
1	1	121D	BE's Office Former Boy's Locker Room near Gym	W2	Brick	Tan	Flaking	5	6.3	Positive
1	1	121D	BE's Office Former Boy's Locker Room near Gym	W3	Brick	Tan	Flaking	3	6.3	Positive
1	1	121D	Boy's Locker Room near Gym	W4	Brick	Tan	None	0	6.3	Positive

		Dates: August 24 - September 19, 2022		Lead-Safe Certification Assessment Report						
		Inspector Name and Certificate Number: Kevin Rumbol 006794		Harding School						
		Inspection Company: ACER Associates, LLC		2000 Wakeling Street, Philadelphia, PA 19124						
Element	Floor	Space #	On-Site Room Name	Component	Substrate Material	Color	Description of Damage	Damage Quantity (sf)	XRF Reading (mg/cm2)	XRF (positive/negative)
1	1	121D	BE's Office Former Boy's Locker Room near Gym	Ceiling	Concrete	Tan	Flaking	600	4.2	Positive
1	1	121D	BE's Office Former Boy's Locker Room near Gym	Radiator	Metal	Silver	Flaking	2	4	Positive
1	1	121D	Boy's Locker Room near Gym	Baseboard	Concrete	Gray	N/A	0	0.02	Negative
1	1	121D	BE's Office Former Boy's Locker Room near Gym	Pipe	Metal	Tan	Flaking	12	2.3	Positive
1	1	121D	Boy's Locker Room near Gym	Railing	Metal	Gray	None	0	0.2	Negative
1	1	121D	BE's Office Former Boy's Locker Room near Gym	Stair Newel Post	Metal	Gray	Flaking	2	7.3	Positive
1	1	121D	BE's Office Former Boy's Locker Room near Gym	Balluster	Metal	Gray	Flaking	1	10.1	Positive
1	1	121D	BE's Office Former Boy's Locker Room near Gym	Tread	Concrete	Gray	Flaking	5	1.1	Positive
1	1	121D	BE's Office Former Boy's Locker Room near Gym	Riser	Concrete	Gray	Flaking	3	1	Positive
1	1	121D	Boy's Locker Room near Gym	Stringer	Concrete	Gray	None	0	0.8	Positive
1	1	121C	Boy's Locker Room Storage Room	Floor	Concrete	Gray	N/A	0	0.01	Negative
1	1	121C	Boy's Locker Room Storage Room	W1	Ceramic	N/A	N/A	0	N/A	N/A
1	1	121C	Boy's Locker Room Storage Room	W2	Ceramic	N/A	N/A	0	N/A	N/A
1	1	121C	Boy's Locker Room Storage Room	W3	Ceramic	N/A	N/A	0	N/A	N/A
1	1	121C	Boy's Locker Room Storage Room	W4	Ceramic	N/A	N/A	0	N/A	N/A
1	1	121C	Boy's Locker Room Storage Room	Ceiling	Concrete	Tan	Flaking	75	7.6	Positive
1	1	121C	Boy's Locker Room Storage Room	Pipe	Metal	Tan	None	0	0.14	Negative
1	1	121E	Restroom Inside Boy's Locker Room	Floor	Concrete	Gray	N/A	0	0.01	Negative
1	1	121E	Restroom Inside Boy's Locker Room	W1	Ceramic	N/A	N/A	0	N/A	N/A
1	1	121E	Restroom Inside Boy's Locker Room	W2	Ceramic	N/A	N/A	0	N/A	N/A
1	1	121E	Restroom Inside Boy's Locker Room	W3	Brick	Tan	None	0	0	Negative
1	1	121E	Restroom Inside Boy's Locker Room	W4	Brick	Tan	None	0	0	Negative
1	1	121E	Restroom Inside Boy's Locker Room	Ceiling	Concrete	Gray	None	0	4.5	Positive
1	1	121E	Restroom Inside Boy's Locker Room	Radiator	Metal	Silver	None	0	0.3	Negative
1	1	121E	Restroom Inside Boy's Locker Room	Door	Metal	Brown	N/A	0	0	Negative
1	1	121E	Restroom Inside Boy's Locker Room	Door Frame	Metal	Brown	N/A	0	0	Negative
1	1	121E	Restroom Inside Boy's Locker Room	Stall	Marble	Black	N/A	0	0	Negative
1	1	S18A	Storage in Boy's Gym Stairs at Base	Floor	Wood	N/A	N/A	0	N/A	N/A
1	1	S18A	Storage in Boy's Gym Stairs at Base	W1	Plaster	Tan	Partially Inaccessible	40	17.3	Positive
1	1	S18A	Storage in Boy's Gym Stairs at Base	W2	Plaster	Tan	Partially Inaccessible	15	17.3	Positive
1	1	S18A	Storage in Boy's Gym Stairs at Base	W3	Plaster	Tan	Partially Inaccessible	50	17.3	Positive
1	1	S18A	Storage in Boy's Gym Stairs at Base	W4	Plaster	Tan	Partially Inaccessible	55	17.3	Positive
1	1	S18A	Storage in Boy's Gym Stairs at Base	Ceiling	Concrete	Tan	Partially Inaccessible	60	8.3	Positive
1	1	S18A	Storage in Boy's Gym Stairs at Base	Door	Metal	Brown	N/A	0	0	Negative
1	1	S18A	Storage in Boy's Gym Stairs at Base	Door Frame	Metal	Brown	N/A	0	0	Negative
1	1	S18B	Storage at top of Boy's Gym Stairs	Floor	Concrete	N/A	N/A	0	N/A	N/A
1	1	S18B	Storage at top of Boy's Gym Stairs	W1	Brick	Tan	Flaking	28	1.3	Positive
1	1	S18B	Storage at top of Boy's Gym Stairs	W2	Brick	Tan	Flaking	4	1.3	Positive

		Dates: August 24 - September 19, 2022		Lead-Safe Certification Assessment Report							
		Inspector Name and Certificate Number: Kevin Rumbol 006794		Harding School							
		Inspection Company: ACER Associates, LLC		2000 Wakeling Street, Philadelphia, PA 19124							
Element	Floor	Space #	On-Site Room Name	Component	Substrate Material	Color	Description of Damage	Damage Quantity (sf)	XRF Reading (mg/cm2)	XRF (positive/negative)	
1	1	S18B	Storage at top of Boy's Gym Stairs	W3	Brick	Tan	Flaking	5	1.3	Positive	
1	1	S18B	Storage at top of Boy's Gym Stairs	W4	Brick	Tan	Flaking	4	1.3	Positive	
1	1	S18B	Storage at top of Boy's Gym Stairs	Ceiling	Concrete	Tan	None	0	0.06	Negative	
1	1	S18B	Storage at top of Boy's Gym Stairs	Door	Metal	Brown	N/A	0	0	Negative	
1	1	S18B	Storage at top of Boy's Gym Stairs	Door Frame	Metal	Brown	N/A	0	0	Negative	
1	1	S18	Boy's Gym Stairs	Floor	Concrete	N/A	N/A	0	N/A	N/A	
1	1	S18	Boy's Gym Stairs	W1	Brick	Tan	None	0	11.4	Positive	
1	1	S18	Boy's Gym Stairs	W2	Brick	Tan	Flaking	5	11.4	Positive	
1	1	S18	Boy's Gym Stairs	W3	Brick	Tan	Flaking	10	11.4	Positive	
1	1	S18	Boy's Gym Stairs	W4	Brick	Tan	None	0	11.4	Positive	
1	1	S18	Boy's Gym Stairs	Ceiling	Concrete	Tan	Flaking	14	5.8	Positive	
1	1	S18	Boy's Gym Stairs	Door	Metal	Brown	N/A	0	0	Negative	
1	1	S18	Boy's Gym Stairs	Door Frame	Metal	Brown	N/A	0	0	Negative	
1	1	S18	Boy's Gym Stairs	Radiator	Metal	Silver	Flaking	10	1.8	Positive	
1	1	S18	Boy's Gym Stairs	Tread	Concrete	Brown	Flaking	4	9.3	Positive	
1	1	S18	Boy's Gym Stairs	Riser	Concrete	Brown	Flaking	6	7.6	Positive	
1	1	S18	Boy's Gym Stairs	Railing	Metal	Gray	None	0	0.24	Negative	
1	1	S19-1	Fire Escape Stairs throughout near Wakeling Street Side	Floor	N/A	N/A	N/A	0	N/A	N/A	
1	1	S19-1	Fire Escape Stairs throughout near Wakeling Street Side	W1	N/A	N/A	N/A	0	N/A	N/A	
1	1	S19-1	Fire Escape Stairs throughout near Wakeling Street Side	W2	N/A	N/A	N/A	0	N/A	N/A	
1	1	S19-1	Fire Escape Stairs throughout near Wakeling Street Side	W3	N/A	N/A	N/A	0	N/A	N/A	
1	1	S19-1	Fire Escape Stairs throughout near Wakeling Street Side	W4	N/A	N/A	N/A	0	N/A	N/A	
1	1	S19-1	Fire Escape Stairs throughout near Wakeling Street Side	Ceiling	N/A	N/A	N/A	0	N/A	N/A	
1	1	S19-2	Fire Escape Stairs throughout near Margaret Street Side	Floor	N/A	N/A	N/A	0	N/A	N/A	
1	1	S19-2	Fire Escape Stairs throughout near Margaret Street Side	W1	N/A	N/A	N/A	0	N/A	N/A	
1	1	S19-2	Fire Escape Stairs throughout near Margaret Street Side	W2	N/A	N/A	N/A	0	N/A	N/A	
1	1	S19-2	Fire Escape Stairs throughout near Margaret Street Side	W3	N/A	N/A	N/A	0	N/A	N/A	
1	1	S19-2	Fire Escape Stairs throughout near Margaret Street Side	W4	N/A	N/A	N/A	0	N/A	N/A	
1	1	S19-2	Fire Escape Stairs throughout near Margaret Street Side	Ceiling	N/A	N/A	N/A	0	N/A	N/A	

			Dates: August 24 - September 19, 2022	Lead-Safe Certification Assessment Report						
			Inspector Name and Certificate Number: Kevin Rumbol 006794	Harding School						
			Inspection Company: ACER Associates, LLC	2000 Wakeling Street, Philadelphia, PA 19124						
E l e m e n t	Floor	Space #	On-Site Room Name	Component	Substrate Material	Color	Description of Damage	Damage Quantity (sf)	XRF Reading (mg/cm2)	XRF (positive/negative)
1	EX	EXT	Exterior Building Walls	Floor	N/A	N/A	N/A	0	N/A	N/A
1	EX	EXT	Exterior Building Walls	W1	N/A	N/A	N/A	0	N/A	N/A
1	EX	EXT	Exterior Building Walls	W2	N/A	N/A	N/A	0	N/A	N/A
1	EX	EXT	Exterior Building Walls	W3	N/A	N/A	N/A	0	N/A	N/A
1	EX	EXT	Exterior Building Walls	W4	N/A	N/A	N/A	0	N/A	N/A
1	EX	EXT	Exterior Building Walls	Ceiling	N/A	N/A	N/A	0	N/A	N/A
1	R	ROOF	Roof	Floor	N/A	N/A	N/A	0	N/A	N/A
1	R	ROOF	Roof	W1	N/A	N/A	N/A	0	N/A	N/A
1	R	ROOF	Roof	W2	N/A	N/A	N/A	0	N/A	N/A
1	R	ROOF	Roof	W3	N/A	N/A	N/A	0	N/A	N/A
1	R	ROOF	Roof	W4	N/A	N/A	N/A	0	N/A	N/A
1	R	ROOF	Roof	Ceiling	N/A	N/A	N/A	0	N/A	N/A
1	A	AT	Attic-3rd Floor Stairwell	Floor	N/A	N/A	N/A	0	N/A	N/A
1	A	AT	Attic-3rd Floor Stairwell	W1	N/A	N/A	N/A	0	N/A	N/A
1	A	AT	Attic-3rd Floor Stairwell	W2	N/A	N/A	N/A	0	N/A	N/A
1	A	AT	Attic-3rd Floor Stairwell	W3	N/A	N/A	N/A	0	N/A	N/A
1	A	AT	Attic-3rd Floor Stairwell	W4	N/A	N/A	N/A	0	N/A	N/A
1	A	AT	Attic-3rd Floor Stairwell	Ceiling	N/A	N/A	N/A	0	N/A	N/A
1	C	CS	Crawl Space	Floor	N/A	N/A	N/A	0	N/A	N/A
1	C	CS	Crawl Space	W1	N/A	N/A	N/A	0	N/A	N/A
1	C	CS	Crawl Space	W2	N/A	N/A	N/A	0	N/A	N/A
1	C	CS	Crawl Space	W3	N/A	N/A	N/A	0	N/A	N/A
1	C	CS	Crawl Space	W4	N/A	N/A	N/A	0	N/A	N/A
1	C	CS	Crawl Space	Ceiling	N/A	N/A	N/A	0	N/A	N/A
1	C	CS	Crawl Space	Floor	N/A	N/A	N/A	0	N/A	N/A