			Dates: 3/13/2023 to 7/21/2023		Lead-S	afe Certi	fication Asse	essment F	Report	
			Inspector Name and PA License Number: Lawrence Jackson 003683		Pai	kway Ce	nter City Mic	Idle Colle	ge	
			Inspection Company: USA Environmental Management Inc				treet, Philad			
Е			munugomont mo							
l e m e n	F 1 0	Snore #	Oneite Ream Name	Component	Substrate Material	Paint Color	Description of	Damage Quantity (sf)	XRF Reading	XRF (positive/
1	6	Space # 600	Onsite Room Name Girl's Restroom on Brandywine Street Side	W1	Plaster	White	Damage Flaking	10	(mg/cm2) 7	negative) Positive
1	6	600	Girl's Restroom on Brandywine Street Side	W2	Plaster	White	Flaking	3	6.6	Positive
1	6	600	Girl's Restroom on Brandywine Street Side	W3	Plaster	White	Flaking	5	0.0	Negative
1	6	600	Girl's Restroom on Brandywine Street Side	W4	Plaster	White	Flaking	5	7.4	Positive
1	6	600	Girl's Restroom on Brandywine Street Side	Ceiling	Plaster	White	Flaking	10	8.1	Positive
1	6	600	Girl's Restroom on Brandywine Street Side	Floor	Concrete	White	None	0	0.1	Negative
1	6	600	Girl's Restroom on Brandywine Street Side	Radiator	Metal	Gray	None	0	0.1	Negative
1	6	600	Girl's Restroom on Brandywine Street Side	Window Frame	Metal	White	None	0	0.2	Negative
1	6	600	Girl's Restroom on Brandywine Street Side	Door	Metal	White	None	0	0	Negative
1	6	600	Girl's Restroom on Brandywine Street Side	Door Frame	Metal	White	None	0	0	Negative
- '	0	000	Pipe Chase behind Toilets in Girl's Restroom on						-	
1	6	600A	Brandywine Street Side	W1	Brick	Unpainted	N/A	N/A	N/A	N/A
1	6	600A	Pipe Chase behind Toilets in Girl's Restroom on Brandywine Street Side	W2	Brick	Unpainted	N/A	N/A	N/A	N/A
1	6	600A	Pipe Chase behind Toilets in Girl's Restroom on Brandywine Street Side	W3	Brick	Unpainted	N/A	N/A	N/A	N/A
1	6	600A	Pipe Chase behind Toilets in Girl's Restroom on Brandywine Street Side	W4	Brick	Unpainted	N/A	N/A	N/A	N/A
1	6	600A	Pipe Chase behind Toilets in Girl's Restroom on Brandywine Street Side	Ceiling	Brick	Unpainted	N/A	N/A	N/A	N/A
1	6	600A	Pipe Chase behind Toilets in Girl's Restroom on Brandywine Street Side	Floor	Brick	Unpainted	N/A	N/A	N/A	N/A
1	6	600B	Pipe Chase between Restrooms in Girl's Restroom on Brandywine Street Side	W1	Brick	Unpainted	N/A	N/A	N/A	N/A
1	6	600B	Pipe Chase between Restrooms in Girl's Restroom on Brandywine Street Side	W2	Brick	Unpainted	N/A	N/A	N/A	N/A
1	6	600B	Pipe Chase between Restrooms in Girl's Restroom on Brandywine Street Side	W3	Brick	Unpainted	N/A	N/A	N/A	N/A
1	6	600B	Pipe Chase between Restrooms in Girl's Restroom on Brandywine Street Side	W4	Brick	Unpainted	N/A	N/A	N/A	N/A
1	6	600B	Pipe Chase between Restrooms in Girl's Restroom on Brandywine Street Side	Ceiling	Brick	Unpainted	N/A	N/A	N/A	N/A
1	6	600B	Pipe Chase between Restrooms in Girl's Restroom on Brandywine Street Side	Floor	Brick	Unpainted	N/A	N/A	N/A	N/A
1	6	601	Boy's Restroom on Brandywine Street Side	W1	Plaster	Tan	Flaking	20	0.1	Negative
1	6	601	Boy's Restroom on Brandywine Street Side	W2	Plaster	Tan	Flaking	50	7.1	Positive
1	6	601	Boy's Restroom on Brandywine Street Side	W3	Plaster	Tan	Flaking	50	8.3	Positive
1	6	601	Boy's Restroom on Brandywine Street Side	W4	Plaster	Tan	Flaking	40	7.2	Positive
1	6	601	Boy's Restroom on Brandywine Street Side	Ceiling	Plaster	Tan	Flaking	30	4	Positive
1	6	601	Boy's Restroom on Brandywine Street Side	Floor	Concrete	Gray	None	0	4.4	Positive

Inspection Name and PA License Number: Lawrence Jackson 003683 Parkway Center City Middle College		D	Dates: 3/13/2023 to 7/21/2023		Lead-S	afe Certi	fication Asse	essment l	Report	
Inspection Company: USA Environmental Management Inc		Ir	nspector Name and PA License Number:							
Sample		L	awrence Jackson 003683		Pai	rkway Ce	nter City Mic	idle Colle	ge	
Component Comp		Ir	nspection Company: USA Environmental		5 40 N				10400	
Seco # Seco # Seco # Seco # Component Substrato Material Paint Color Description of Damage Cuantity (sf) Component Substrato Material Paint Color Damage Cuantity (sf) Component Substrato Material Paint Color Damage Cuantity (sf) Component Component Substrato Material Color Damage Cuantity (sf) Color		N	Management Inc		540 Nor	tn 13tn S	treet, Philad	eipnia, P	4 19123	
m e 0 0 n 0 0 c 1 v 7 Space # Description of 1 v 7 Obstite Room Name Component Component Component Substrate Material Paint Color Damage Quantity (st) XRF Reading (mg/cm2) (mg/cm2) 1										
t r Space # Onsite Room Name Component Component Substrate Material Paint Color Damage Quantity (ef) (mg/cm2) 1 6 6 601 Boy's Restroom on Brandywine Street Side Medal Gray Flaking 3 0.5 1 6 6 601 Boy's Restroom on Brandywine Street Side Window Frame Medal White None 0 0 1 6 6 601 Boy's Restroom on Brandywine Street Side Door Medal White None 0 0 1 6 6 601 Boy's Restroom on Brandywine Street Side Door Frame Medal White None 0 0 0 1 6 6 602 Large Center Classroom W1 Plaster White Flaking 50 0.1 1 6 6 602 Large Center Classroom W3 Plaster White Flaking 80 0 1 6 6 602 Large Center Classroom W4 Plaster White Flaking 80 1.1 1 6 6 602 Large Center Classroom Floor 12 x 12 Floor Tile Unpanted N/A N/A 1 6 6 602 Large Center Classroom Floor 12 x 12 Floor Tile Unpanted N/A							Description of	Damage	XRF Reading	XRF (positive/
1 6 601 Boy's Restroom on Brandywine Street Side Radiator Metal Gray Flaking 3 0.5 1 6 601 Boy's Restroom on Brandywine Street Side Door Metal White None 0 0 1 6 601 Boy's Restroom on Brandywine Street Side Door Metal White None 0 0 0 1 6 601 Boy's Restroom on Brandywine Street Side Door Frame Metal White None 0 0 0 1 6 602 Large Center Classroom W1 Plaster White Flaking 50 0.1 1 6 602 Large Center Classroom W2 Plaster White Flaking 80 0 1 6 602 Large Center Classroom W3 Plaster White Flaking 80 0 1 6 602 Large Center Classroom W4 Plaster White Flaking 80 0 1 6 602 Large Center Classroom W4 Plaster White Flaking 80 1.1 1 6 602 Large Center Classroom Celling Plaster White Flaking 700 0.2 1 6 602 Large Center Classroom Celling Plaster White Flaking 700 10.2 1 6 602 Large Center Classroom Floor Tax 12 Floor Tile Tax 1	расе	ace#	Onsite Room Name	Component	Substrate Material	Paint Color				negative)
1 6 601 Boy's Restroom on Brandywine Street Side Door Metal White None 0 0 0 1 1 6 602 Large Center Classroom W1 Plaster White Flaking 50 0.1 1 6 602 Large Center Classroom W2 Plaster White Flaking 80 0 0 1 1 6 602 Large Center Classroom W3 Plaster White Flaking 80 0 0 1 1 6 602 Large Center Classroom W3 Plaster White Flaking 80 0 0 1 1 6 602 Large Center Classroom W4 Plaster White Flaking 80 0 1.1 1 6 602 Large Center Classroom W4 Plaster White Flaking 80 1.1 1 6 602 Large Center Classroom W4 Plaster White Flaking 100 0.2 1 6 602 Large Center Classroom Floor 12 x 12 Floor Tile Unpainted N/A N/A	601	601 B	Boy's Restroom on Brandywine Street Side	Radiator	Metal	Gray	Flaking		0.5	Negative
1	601	601 B	Boy's Restroom on Brandywine Street Side	Window Frame	Metal	White	None	0	0	Negative
1 6 602	601	601 B	Boy's Restroom on Brandywine Street Side	Door	Metal	White	None	0	0	Negative
1	601	601 B	Boy's Restroom on Brandywine Street Side	Door Frame	Metal	White	None	0	0.1	Negative
1	602	602 La	arge Center Classroom		Plaster		Flaking			Negative
1	602	602 La	arge Center Classroom	W2	Plaster	White	Flaking	80	0	Negative
1 6 602	602	602 L	arge Center Classroom		Plaster	White	Flaking			Positive
1	602	602 L	arge Center Classroom	W4	Plaster	White	Flaking			Negative
1	602	602 L	arge Center Classroom							Positive
1			arge Center Classroom							N/A
1 6 603 Staff Restroom on Green Street Side W2 Plaster Tan Flaking 50 0 1 6 603 Staff Restroom on Green Street Side W3 Plaster Tan Flaking 50 0 1 6 603 Staff Restroom on Green Street Side W4 Plaster Tan Flaking 40 0 1 6 603 Staff Restroom on Green Street Side Ceiling Plaster Tan Flaking 30 0 1 6 603 Staff Restroom on Green Street Side Floor Ceramic Unpainted N/A N/A N/A 1 6 603 Staff Restroom on Green Street Side Floor Ceramic Unpainted N/A N/A N/A 1 6 603 Staff Restroom on Green Street Side Window Frame Metal White None 0 0 1 6 605 Closet near Studett Restrooms W1 Plaster White	602	602 L	arge Center Classroom			,				Positive
1 6 603 Staff Restroom on Green Street Side W3 Plaster Tan Flaking 50 0 1 6 603 Staff Restroom on Green Street Side W4 Plaster Tan Flaking 30 0 1 6 603 Staff Restroom on Green Street Side Floor Ceramic Unpainted N/A	603	603 S	Staff Restroom on Green Street Side							Negative
1 6 603 Staff Restroom on Green Street Side W4 Plaster Tan Flaking 40 0 1 6 603 Staff Restroom on Green Street Side Ceiling Plaster Tan Flaking 30 0 1 6 603 Staff Restroom on Green Street Side Floor Ceramic Unpainted N/A N/A N/A 1 6 603 Staff Restroom on Green Street Side Radiator Metal Gray Flaking 3 4.4 1 6 603 Staff Restroom on Green Street Side Window Frame Metal White None 0										Negative
1 6 603 Staff Restroom on Green Street Side Ceiling Plaster Tan Flaking 30 0 1 6 603 Staff Restroom on Green Street Side Floor Ceramic Unpainted N/A										Negative
1										Negative
1 6 603 Staff Restroom on Green Street Side Radiator Metal Gray Flaking 3 4.4 1 6 603 Staff Restroom on Green Street Side Window Frame Metal White None 0 0 1 6 605 Closet near Student Restrooms W1 Plaster White Flaking 3 9.5 1 6 605 Closet near Student Restrooms W2 Plaster White Flaking 4 0.1 1 6 605 Closet near Student Restrooms W4 No Access No Access<										Negative
1 6 603 Staff Restroom on Green Street Side Window Frame Metal White None 0 0 1 6 605 Closet near Student Restrooms W1 Plaster White Flaking 3 9.5 1 6 605 Closet near Student Restrooms W2 Plaster White Flaking 4 0.1 1 6 605 Closet near Student Restrooms W4 No Access No Acce										N/A
1 6 605 Closet near Student Restrooms W1 Plaster White Flaking 3 9.5 1 6 605 Closet near Student Restrooms W2 Plaster White Flaking 4 0.1 1 6 605 Closet near Student Restrooms W4 No Access No A						,				Positive
1 6 605 Closet near Student Restrooms W4 No Access No Acces No Acces No Acces No Acces No Acces No Access No Acces No Acces No Acces No Acces No Acces No Acces No Access No Acces										Negative
16605Closet near Student RestroomsW4No AccessNo AccessNo AccessNo AccessNo Access16605Closet near Student RestroomsFloorNo AccessNo AccessNo AccessNo Access16605Closet near Student RestroomsFloorNo AccessNo AccessNo AccessNo Access16605Closet near Student RestroomsShelfWoodWhiteNone0016605Closet near Student RestroomsShelf SupportWoodWhiteNone00.116605Closet near Student RestroomsDoorMetalWhiteNone0016605Closet near Student RestroomsDoor FrameMetalWhiteNone0016605Closet near Student RestroomsDoor FrameMetalWhiteNone0016606Penthouse Mechanical RoomW1PlasterGrayFlaking100016606Penthouse Mechanical RoomW3PlasterGrayFlaking50016606Penthouse Mechanical RoomW4PlasterWhiteFlaking100016606Penthouse Mechanical RoomW2PlasterWhiteFlaking50016606Penthouse Mechanical RoomW3PlasterWhiteFlaking <t< td=""><td></td><td></td><td></td><td></td><td></td><td></td><td>,</td><td>-</td><td></td><td>Positive</td></t<>							,	-		Positive
16605Closet near Student RestroomsCeilingNo AccessNo AccessNo AccessNo AccessNo Access16605Closet near Student RestroomsFloorNo AccessNo AccessNo AccessNo Access16605Closet near Student RestroomsShelfWoodWhiteNone0016605Closet near Student RestroomsDoorMetalWhiteNone0016605Closet near Student RestroomsDoor FrameMetalWhiteNone0016605Closet near Student RestroomsDoor FrameMetalWhiteNone0016606Penthouse Mechanical RoomW1PlasterGrayFlaking100016606Penthouse Mechanical RoomW2PlasterGrayFlaking50016606Penthouse Mechanical RoomW4PlasterGrayFlaking80016606Penthouse Mechanical RoomW4PlasterGrayFlaking60016606Penthouse Mechanical RoomW1PlasterWhiteFlaking100016606Penthouse Mechanical RoomW2PlasterWhiteFlaking50016606Penthouse Mechanical RoomW3PlasterWhiteFlaking450										Negative
16605Closet near Student RestroomsFloorNo AccessNo AccessNo AccessNo Access16605Closet near Student RestroomsShelfWoodWhiteNone016605Closet near Student RestroomsShelf SupportWoodWhiteNone00.116605Closet near Student RestroomsDoorMetalWhiteNone0016605Closet near Student RestroomsDoor FrameMetalWhiteNone0016605Closet near Student RestroomsDoor FrameMetalWhiteNone0016606Penthouse Mechanical RoomW1PlasterGrayFlaking100016606Penthouse Mechanical RoomW2PlasterGrayFlaking50016606Penthouse Mechanical RoomW4PlasterGrayFlaking60016606Penthouse Mechanical RoomW1PlasterWhiteFlaking100016606Penthouse Mechanical RoomW2PlasterWhiteFlaking50016606Penthouse Mechanical RoomW3PlasterWhiteFlaking45016606Penthouse Mechanical RoomW4PlasterWhiteFlaking450									<u> </u>	No Access
1 6 605 Closet near Student Restrooms Shelf Wood White None 0 1 6 605 Closet near Student Restrooms Door Metal White None 0 0.1 1 6 605 Closet near Student Restrooms Door Metal White None 0 0 1 6 605 Closet near Student Restrooms Door Frame Metal White None 0 0 1 6 605 Closet near Student Restrooms Door Frame Metal White None 0 0 1 6 605 Closet near Student Restrooms Door Frame Metal White None 0 0 1 6 606 Penthouse Mechanical Room W1 Plaster Gray Flaking 100 0 1 6 606 Penthouse Mechanical Room W4 Plaster Gray Flaking 80 0 0										No Access
1 6 605 Closet near Student Restrooms Shelf Support Wood White None 0 0.1 1 6 605 Closet near Student Restrooms Door Metal White None 0 0 1 6 605 Closet near Student Restrooms Door Frame Metal White None 0 0 1 6 606 Penthouse Mechanical Room W1 Plaster Gray Flaking 100 0 1 6 606 Penthouse Mechanical Room W3 Plaster Gray Flaking 80 0 1 6 606 Penthouse Mechanical Room W4 Plaster Gray Flaking 60 0 1 6 606 Penthouse Mechanical Room W1 Plaster White Flaking 100 0 1 6 606 Penthouse Mechanical Room W2 Plaster White Flaking 50 0 <									.	No Access
1 6 605 Closet near Student Restrooms Door Metal White None 0 0 1 6 605 Closet near Student Restrooms Door Frame Metal White None 0 0 1 6 606 Penthouse Mechanical Room W1 Plaster Gray Flaking 100 0 1 6 606 Penthouse Mechanical Room W2 Plaster Gray Flaking 50 0 1 6 606 Penthouse Mechanical Room W4 Plaster Gray Flaking 60 0 1 6 606 Penthouse Mechanical Room W1 Plaster White Flaking 100 0 1 6 606 Penthouse Mechanical Room W2 Plaster White Flaking 50 0 1 6 606 Penthouse Mechanical Room W2 Plaster White Flaking 45 0										Negative
1 6 605 Closet near Student Restrooms Door Frame Metal White None 0 0 1 6 606 Penthouse Mechanical Room W1 Plaster Gray Flaking 100 0 1 6 606 Penthouse Mechanical Room W2 Plaster Gray Flaking 50 0 1 6 606 Penthouse Mechanical Room W3 Plaster Gray Flaking 80 0 1 6 606 Penthouse Mechanical Room W4 Plaster White Flaking 60 0 1 6 606 Penthouse Mechanical Room W2 Plaster White Flaking 50 0 1 6 606 Penthouse Mechanical Room W3 Plaster White Flaking 45 0 1 6 606 Penthouse Mechanical Room W3 Plaster White Flaking 45 0									.	Negative
1 6 606 Penthouse Mechanical Room W1 Plaster Gray Flaking 100 0 1 6 606 Penthouse Mechanical Room W2 Plaster Gray Flaking 50 0 1 6 606 Penthouse Mechanical Room W3 Plaster Gray Flaking 80 0 1 6 606 Penthouse Mechanical Room W4 Plaster Gray Flaking 60 0 1 6 606 Penthouse Mechanical Room W1 Plaster White Flaking 100 0 1 6 606 Penthouse Mechanical Room W2 Plaster White Flaking 50 0 1 6 606 Penthouse Mechanical Room W3 Plaster White Flaking 45 0 1 6 606 Penthouse Mechanical Room W4 Plaster White Flaking 45 0										Negative
1 6 606 Penthouse Mechanical Room W2 Plaster Gray Flaking 50 0 1 6 606 Penthouse Mechanical Room W3 Plaster Gray Flaking 80 0 1 6 606 Penthouse Mechanical Room W4 Plaster Gray Flaking 60 0 1 6 606 Penthouse Mechanical Room W1 Plaster White Flaking 100 0 1 6 606 Penthouse Mechanical Room W2 Plaster White Flaking 50 0 1 6 606 Penthouse Mechanical Room W3 Plaster White Flaking 45 0 1 6 606 Penthouse Mechanical Room W4 Plaster White Flaking 40 0								_		Negative
1 6 606 Penthouse Mechanical Room W3 Plaster Gray Flaking 80 0 1 6 606 Penthouse Mechanical Room W4 Plaster Gray Flaking 60 0 1 6 606 Penthouse Mechanical Room W1 Plaster White Flaking 100 0 1 6 606 Penthouse Mechanical Room W2 Plaster White Flaking 50 0 1 6 606 Penthouse Mechanical Room W3 Plaster White Flaking 45 0 1 6 606 Penthouse Mechanical Room W4 Plaster White Flaking 40 0										Negative
1 6 606 Penthouse Mechanical Room W4 Plaster Gray Flaking 60 0 1 6 606 Penthouse Mechanical Room W1 Plaster White Flaking 100 0 1 6 606 Penthouse Mechanical Room W2 Plaster White Flaking 50 0 1 6 606 Penthouse Mechanical Room W3 Plaster White Flaking 45 0 1 6 606 Penthouse Mechanical Room W4 Plaster White Flaking 40 0										Negative
1 6 606 Penthouse Mechanical Room W1 Plaster White Flaking 100 0 1 6 606 Penthouse Mechanical Room W2 Plaster White Flaking 50 0 1 6 606 Penthouse Mechanical Room W3 Plaster White Flaking 45 0 1 6 606 Penthouse Mechanical Room W4 Plaster White Flaking 40 0										Negative
1 6 606 Penthouse Mechanical Room W2 Plaster White Flaking 50 0 1 6 606 Penthouse Mechanical Room W3 Plaster White Flaking 45 0 1 6 606 Penthouse Mechanical Room W4 Plaster White Flaking 40 0						,				Negative Negative
1 6 606 Penthouse Mechanical Room W3 Plaster White Flaking 45 0 1 6 606 Penthouse Mechanical Room W4 Plaster White Flaking 40 0									·	Negative
1 6 606 Penthouse Mechanical Room W4 Plaster White Flaking 40 0										Negative
1 0 000 I distribute incommission (com										Negative
1 6 606 Penthouse Mechanical Room Ceiling Concrete White Flaking 400 0	606		Penthouse Mechanical Room	Ceiling	Concrete	White	Flaking	400	0	Negative
1 6 606 Penthouse Mechanical Room Floor Concrete Unpainted N/A N/A N/A										N/A

			Dates: 3/13/2023 to 7/21/2023		Lead-S	afe Certi	fication Asse	essment F	Report	
			Inspector Name and PA License Number:				4 014 141		•	
			Lawrence Jackson 003683		Pai	rkway Ce	nter City Mic	idie Colle	ge	
			Inspection Company: USA Environmental		= 40.11	41 4041 0	4 4 51 11 1		10100	
			Management Inc		540 Nor	th 13th S	treet, Philad	elphia, P <i>i</i>	A 19123	
E			_					•		
е	F									
m e	I									XRF
n	0						Description of	Damage	XRF Reading	(positive/
t	r	Space #	Onsite Room Name	Component	Substrate Material	Paint Color	Damage	Quantity (sf)	(mg/cm2)	negative)
1	6	606	Penthouse Mechanical Room	Door	Metal	Gray	None	0	0	Negative
1	6	606	Penthouse Mechanical Room	Door Frame	Metal	Gray	None	0	0	Negative
1	6	E2	Freight Elevator	W1	No Access	No Access	No Access	No Access	No Access	No Access
1	6	E2	Freight Elevator	W2	No Access	No Access	No Access	No Access	No Access	No Access
1	6	E2	Freight Elevator	W3	No Access	No Access	No Access	No Access	No Access	No Access
1	6	E2	Freight Elevator	W4	No Access	No Access	No Access	No Access	No Access	No Access
1	6	E2	Freight Elevator	Ceiling	No Access	No Access	No Access	No Access	No Access	No Access
1	6	E2	Freight Elevator	Floor	No Access	No Access	No Access	No Access	No Access	No Access
1	6	S65	Fire Tower on Green Street Side	W1	Brick	White	None	0	4.4	Positive
1	6	S65	Fire Tower on Green Street Side	W2	Brick	White	None	0	6.7	Positive
1	6	S65	Fire Tower on Green Street Side	W3	Brick	White	None	0	7.6	Positive
1	6	S65	Fire Tower on Green Street Side	W4	Brick	White	None	0	6.3	Positive
1	6	S65	Fire Tower on Green Street Side	Ceiling	Concrete	White	None	0	No access	No Access
1	6	S65	Fire Tower on Green Street Side	Floor	Concrete	Gray	None	0	0	Negative
1	6	S65	Fire Tower on Green Street Side	Door	Metal	Brown	None	0	0	Negative
1	6	S65	Fire Tower on Green Street Side	Door Frame	Metal	Brown	None	0	0.1	Negative
1	6	S65	Fire Tower on Green Street Side	Window Frame	Metal	Brown	Flaking	4	4.4	Positive
1	6	S65	Fire Tower on Green Street Side	Handrail	Metal	Brown	None	0	5.1	Positive
1	6	S65	Fire Tower on Green Street Side	Stair Riser	Concrete	Grey	None	0	1.4	Positive
1	6	S65	Fire Tower on Green Street Side	Stair Tread	Concrete Concrete	Grey Grev	None None	0	0.1 1.8	Negative Positive
1	6	S65	Fire Tower on Green Street Side	Stair Stringer	Brick	White	None	0	5.4	Positive
1	6	S66	Fire Tower on Brandywine Street Side	W1 W2	Brick	White	None	0	6.1	
1	6	S66 S66	Fire Tower on Brandywine Street Side	W3	Brick	White	None	0	5.8	Positive Positive
1	6	S66	Fire Tower on Brandywine Street Side Fire Tower on Brandywine Street Side	W4	Brick	White	None	0	6.3	Positive
1	6	S66	Fire Tower on Brandywine Street Side	Ceiling	Concrete	White	Flaking	40	6.9	Positive
1	6	S66	Fire Tower on Brandywine Street Side	Floor	Concrete	Gray	None	0	0.9	Negative
1	6	S66	Fire Tower on Brandywine Street Side	Door	Metal	Brown	None	0	0.1	Negative
1	6	S66	Fire Tower on Brandywine Street Side	Door Frame	Metal	Brown	None	0	0.1	Negative
1	6	S66	Fire Tower on Brandywine Street Side	Window Frame	Metal	Brown	Flaking	6	5	Positive
1	6	S66	Fire Tower on Brandywine Street Side	Handrail	Metal	Brown	Chipping	10	0.7	Positive
1	6	S66	Fire Tower on Brandywine Street Side	Stair Riser	Concrete	Gray	None	0	2	Positive
1	6	S66	Fire Tower on Brandywine Street Side	Stair Tread	Concrete	Gray	None	0	0.1	Negative
1	6	S66	Fire Tower on Brandywine Street Side	Stair Stringer	Concrete	Gray	None	0	2.4	Positive
1	5	509	Girl's Restroom adjacent to Kitchen	W1	Plaster	White	Flaking	30	8.1	Positive
1	5	509	Girl's Restroom adjacent to Kitchen	W2	Plaster	White	Flaking	10	0	Negative
1	5	509	Girl's Restroom adjacent to Kitchen	W3	Plaster	White	Flaking	30	6.2	Positive
1	5	509	Girl's Restroom adjacent to Kitchen	W4	Plaster	White	Flaking	15	0.1	Negative

			Dates: 3/13/2023 to 7/21/2023		Lead-S	afe Certi	fication Asse	essment F	Report	
			Inspector Name and PA License Number:		_				•	
			Lawrence Jackson 003683		Pai	rkway Ce	nter City Mic	idle Colle	ge	
			Inspection Company: USA Environmental							
			Management Inc		540 Nor	th 13th S	treet, Philad	elphia, P <i>l</i>	A 19123	
E							·			
e	F									
m	1									
е	0									XRF
n	o r	Space #	Onsite Room Name	Component	Substrate Material	Paint Color	Description of Damage	Damage Quantity (sf)	XRF Reading (mg/cm2)	(positive/ negative)
1	5	509	Girl's Restroom adjacent to Kitchen	Ceiling	Plaster	White	Cracking	60	0.1	Negative
1	5	509	Girl's Restroom adjacent to Kitchen	Floor	Concrete	Gray	None	0	0.1	Negative
1	5	509	Girl's Restroom adjacent to Kitchen	Radiator	Metal	Gray	Flaking	1	0	Negative
1	5	509	Girl's Restroom adjacent to Kitchen	Door	Wood	Varnish	None	0	0	Negative
1	5	509	Girl's Restroom adjacent to Kitchen	Door Casing	Wood	Brown	None	0	0.1	Negative
1	5	509	Girl's Restroom adjacent to Kitchen	Window Casing	Wood	Brown	None	0	0.2	Negative
1	5	509A	Pipe Chase in Girl's Restroom adjacent to Kitchen	W1	Concrete	Unpainted	N/A	N/A	N/A	N/A
1	5	509A	Pipe Chase in Girl's Restroom adjacent to Kitchen	W2	Concrete	Unpainted	N/A	N/A	N/A	N/A
1	5	509A	Pipe Chase in Girl's Restroom adjacent to Kitchen	W3	Concrete	Unpainted	N/A	N/A	N/A	N/A
1	5	509A	Pipe Chase in Girl's Restroom adjacent to Kitchen	W4	Concrete	Unpainted	N/A	N/A	N/A	N/A
1	5	509A	Pipe Chase in Girl's Restroom adjacent to Kitchen	Ceiling	Brick	Unpainted	N/A	N/A	N/A	N/A
1	5	509A	Pipe Chase in Girl's Restroom adjacent to Kitchen	Floor	No Access	No Access	N/A	N/A	N/A	N/A
1	5	509A	Pipe Chase in Girl's Restroom adjacent to Kitchen	Door	Wood	Brown	Chipping	1	0	Negative
1	5	509A	Pipe Chase in Girl's Restroom adjacent to Kitchen	Door Frame	Wood	Brown	Chipping	1	0	Negative
1	5	508	Lunch Director's Office	W1	Plaster	White	Flaking	20	10.9	Positive
1	5	508	Lunch Director's Office	W2	Plaster	White	Flaking	20	1.2	Positive
1	5	508	Lunch Director's Office	W3	Plaster	White	Flaking	40	10.6	Positive
1	5	508	Lunch Director's Office	W4	Plaster	White	Flaking	5	10.9	Positive
1	5	508	Lunch Director's Office	Ceiling	Plaster	Tan	Flaking	100	11.8	Positive
1	5	508	Lunch Director's Office	Floor	9 x 9 floor tile	Unpainted	N/A	N/A	N/A	N/A
1	5	508	Lunch Director's Office	Door	Wood	Brown	Friction	2	0.1	Negative
1	5	508	Lunch Director's Office	Door Casing	Wood	Brown	Friction	3	0.1	Negative
1	5	508	Lunch Director's Office	Chair Rail	Wood	Brown	None	0	0.1	Negative
1	5	508	Lunch Director's Office	Baseboard	Wood	Brown	None	0	0.1	Negative
1	5	508	Lunch Director's Office	Window Casing	Wood	Brown	Alligatoring	5	0.1	Negative
1	5	508	Lunch Director's Office	Window Aprop	Wood Wood	Brown Brown	None None	0	0.1 0.1	Negative
1	5 5	508 508	Lunch Director's Office	Window Apron Radiator	vvood Metal	Gray	None	0	4.2	Negative Positive
1	5	508 508A	Lunch Director's Office Lunch Director's Office Restroom	W1	Plaster	White	Flaking	20	4.2	Positive
1	5	508A 508A	Lunch Director's Office Restroom Lunch Director's Office Restroom	W2	Plaster	White	Efflorescence	60	7.7	Positive
1	5	508A	Lunch Director's Office Restroom	W3	Plaster	White	Flaking	20	0.4	Negative
1	5	508A	Lunch Director's Office Restroom	W4	Plaster	White	Flaking	20	0.5	Negative
1	5	508A	Lunch Director's Office Restroom	Ceiling	Plaster	Tan	Cracking	80	2	positive
1	5	508A	Lunch Director's Office Restroom	Floor	9 x 9 floor tile	Unpainted	N/A	N/A	N/A	N/A
1	5	508A	Lunch Director's Office Restroom	Door	Wood	Brown	None	0	0.1	Negative
1	5	508A	Lunch Director's Office Restroom	Door Casing	Wood	Brown	Friction	1	0.1	Negative
1	5	508A	Lunch Director's Office Restroom	Window Casing	Wood	Brown	Flaking	3	0.1	Negative
1	5	508A	Lunch Director's Office Restroom	Window Sill	Wood	Brown	None	0	0.5	Negative

			Dates: 3/13/2023 to 7/21/2023		Lead-S	afe Certi	fication Asse	essment l	Report	
			Inspector Name and PA License Number:		D	.1	4 O'4 NI'-	1-11- 0-11-		
			Lawrence Jackson 003683		Pai	rkway Ce	nter City Mic	idle Colle	ge	
			Inspection Company: USA Environmental		E 40 No.	4h 404h 0	tuant Dhilad	alabia Di	10400	
			Management Inc		540 NOr	tn 13tn 5	treet, Philad	eipnia, P	19123	
E										
l e	F									
m	i									
е	0									XRF
n	0						Description of	Damage	XRF Reading	(positive/
t	r	Space #	Onsite Room Name	Component	Substrate Material	Paint Color	Damage	Quantity (sf)	(mg/cm2)	negative)
1	5	508A	Lunch Director's Office Restroom	Window Apron Radiator	Wood Metal	Brown	None	3	0.1	Negative
1	5	508A	Lunch Director's Office Restroom	W1	Plaster	Gray White	Flaking None	0	3.7 1.4	Positive Positive
1	5	507 507	Lunch Assistant Room Lunch Assistant Room	W2	Plaster	White	None	0	10.2	Positive
1	5	507	Lunch Assistant Room	W3	Plaster	White	None	0	7.5	Positive
1	5	507	Lunch Assistant Room	W4	Plaster	White	None	0	9.1	Positive
1	5	507	Lunch Assistant Room	Ceiling	Plaster	White	None	0	11.1	Positive
1	5	507	Lunch Assistant Room	Floor	Wood	Unpainted	N/A	N/A	N/A	N/A
1	5	507	Lunch Assistant Room	Window Casing	Wood	Brown	None	0	0.1	Negative
1	5	507	Lunch Assistant Room	Window Sill	Wood	Brown	None	0	0	Negative
1	5	507	Lunch Assistant Room	Window Apron	Wood	Brown	None	0	0.1	Negative
1	5	507	Lunch Assistant Room	Baseboard	Wood	Brown	None	0	0.1	Negative
1	5	507	Lunch Assistant Room	Chair Rail	Wood	Brown	None	0	0	Negative
1	5	507	Lunch Assistant Room	Radiator	Metal	Gray	Flaking	3	3.4	Positive
1	5	507	Lunch Assistant Room	Door	Wood	Brown	Friction	2	0.1	Negative
1	5	507	Lunch Assistant Room	Door Casing	Wood	Brown	None	0	0	Negative
1	5	507A	Lunch Assistant Room Restroom	W1	Plaster	White	Flaking	10	11.2	Positive
1	5	507A	Lunch Assistant Room Restroom	W2	Plaster	White	Flaking	10	10.5	Positive
1	5	507A	Lunch Assistant Room Restroom	W3	Plaster	White	Flaking	5	1.8	Positive
1	5	507A	Lunch Assistant Room Restroom	W4	Plaster	White	None	0	12.6	Positive
1	5	507A	Lunch Assistant Room Restroom	Ceiling	Plaster	White	None	0	10	Positive
1	5	507A	Lunch Assistant Room Restroom	Floor	9 x 9 floor tile	Unpainted	N/A	N/A	N/A	N/A
1	5	507A	Lunch Assistant Room Restroom	Radiator	Metal Wood	Gray	Chipping	3	3.5	Positive
1	5	507A 507A	Lunch Assistant Room Restroom Lunch Assistant Room Restroom	Window Casing Window Sill	Wood	Brown Brown	None None	0	0.1	Negative
<u> </u>	1 5	507A	Lunch Assistant Room Restroom	Williaow Sili	vvood	DIOWII	None	1 0	0.1	Negative
				Window Apron	Wood	Brown	None	0	0.1	Negative
1	5	507A	Lunch Assistant Room Restroom	,						ŭ
1	5	507B	Kitchen Storage Room adjacent to Fire Tower	W1	Plaster	White	Flaking	20	11.5	Positive
1	5	507B	Kitchen Storage Room adjacent to Fire Tower	W2	Plaster	White	Flaking	15	12.5	Positive
1	5	507B	Kitchen Storage Room adjacent to Fire Tower	W3	Plaster	White	Flaking	5	11.9	Positive
1	5	507B	Kitchen Storage Room adjacent to Fire Tower	W4	Plaster	White	None	0	12.5	Positive
1	5	507B	Kitchen Storage Room adjacent to Fire Tower	Ceiling	Plaster	White	Cracking	15	13.2	Positive
1	5	507B	Kitchen Storage Room adjacent to Fire Tower	Floor	Wood	Unpainted	N/A	N/A	N/A	N/A
1	5	507B	Kitchen Storage Room adjacent to Fire Tower	Radiator	Metal	Gray	Flaking	5	0.1	Negative
1	5	507B	Kitchen Storage Room adjacent to Fire Tower	Window Casing	Wood	Brown	Alligatoring	6	0.2	Negative
1	5	507B	Kitchen Storage Room adjacent to Fire Tower	Window Aprop	Wood	Brown	None	0	0.1 0.2	Negative
1	5	507B	Kitchen Storage Room adjacent to Fire Tower	Window Apron	Wood	Brown	None	1 0	U.Z	Negative

			Dates: 3/13/2023 to 7/21/2023		Lead-S	afe Certi	fication Asse	essment F	Report	
			Inspector Name and PA License Number:		_				•	
			Lawrence Jackson 003683		Pai	rkway Ce	nter City Mic	ldle Colle	ge	
			Inspection Company: USA Environmental							
			Management Inc		540 Nor	th 13th S	treet, Philad	elphia, P <i>l</i>	A 19123	
Е							•			
1										
е	F									
m e	I									XRF
n	0						Description of	Damage	XRF Reading	(positive/
t	r	Space #	Onsite Room Name	Component	Substrate Material	Paint Color	Damage	Quantity (sf)	(mg/cm2)	negative)
1	5	507B	Kitchen Storage Room adjacent to Fire Tower	Baseboard	Wood	Gray	None	0	0	Negative
1	5	S55	Fire Tower adjacent to Kitchen Dry Storage	W1	Brick	White	None	0	9.2	Positive
1	5	S55	Fire Tower adjacent to Kitchen Dry Storage	W2	Brick	White	None	0	10	Positive
1	5	S55	Fire Tower adjacent to Kitchen Dry Storage	W3	Brick	White	None	0	6.7	Positive
1	5	S55	Fire Tower adjacent to Kitchen Dry Storage	W4	Brick	White	None	0	8.1	Positive
1	5	S55	Fire Tower adjacent to Kitchen Dry Storage	Ceiling	Concrete	White	Flaking	140	0.2	Negative
1	5	S55	Fire Tower adjacent to Kitchen Dry Storage	Floor	Concrete	Gray	None	0	1.6	Positive
1	5	S55	Fire Tower adjacent to Kitchen Dry Storage	Drain Pipe	Metal	Brown	Flaking	24	10	Positive
1	5	S55	Fire Tower adjacent to Kitchen Dry Storage	Security Gate	Metal	Brown	Flaking	100	10	Positive
1	5	S55	Fire Tower adjacent to Kitchen Dry Storage	Handrail	Metal	Brown	Chipping	8	2.1	Positive
1	5	S55	Fire Tower adjacent to Kitchen Dry Storage	Stair Riser	Concrete	Gray	None	0	1	Positive
1	5	S55	Fire Tower adjacent to Kitchen Dry Storage	Stair Treads	Concrete	Gray	None	0	0.3	Negative
1	5	S55	Fire Tower adjacent to Kitchen Dry Storage	Stair Stringer	Concrete	Gray	None	0	2.2	Positive
1	5	506A	Art Supply and Drying Room	W1	Sheetrock	Gray	None	0	0	Negative
1	5	506A	Art Supply and Drying Room	W2	Plaster	Gray	Flaking	15	0.3	Negative
1	5	506A	Art Supply and Drying Room	W3	Sheetrock	Gray	None	0	0	Negative
1	5	506A	Art Supply and Drying Room	W4	Plaster	Gray	Flaking	4	9.9	Positive
1	5	506A	Art Supply and Drying Room	Ceiling	Plaster	White	Cracking	40	9.5	Positive
1	5	506A	Art Supply and Drying Room	Floor	Tile	Unpainted	N/A	N/A	N/A	N/A
1	5	506A	Art Supply and Drying Room	Radiator	Metal	Gray	Flaking	5	3.9	Positive
1	5	506A	Art Supply and Drying Room	Window Casing	Wood	Brown	Alligatoring	20	0.5	Negative
1	5	506A	Art Supply and Drying Room	Window Sill	Wood	Brown	Friction	20	0	Negative
1	5	506A	Art Supply and Drying Room	Window Apron	Wood	Brown	None	0	0	Negative
1	5	506B	Art Supply and Drying Room Kiln Room	W1	Plaster	White	None	0	0.2	Negative
1	5	506B	Art Supply and Drying Room Kiln Room	W2	Plaster	White	None	0	11.8	Positive
1	5	506B	Art Supply and Drying Room Kiln Room	W3	Wood	White	None	0	0	Negative
1	5	506B	Art Supply and Drying Room Kiln Room	W4	Plaster	White	None	0	0.2	Negative
1	5	506B	Art Supply and Drying Room Kiln Room	Ceiling	Plaster	White	None	0	11.8	Positive
1	5	506B	Art Supply and Drying Room Kiln Room	Floor	12 x 12 Floor Tile	Unpainted	N/A	N/A	N/A	N/A
1	5	506B	Art Supply and Drying Room Kiln Room	Radiator	Metal	Gray	None	0	3	Positive
1	5	506B	Art Supply and Drying Room Kiln Room	Window Casing	Wood	Brown	None	0	0.1	Negative
1	5	506B	Art Supply and Drying Room Kiln Room	Window Sill	Wood	Brown	None	0	0.1	Negative
1	5	506B	Art Supply and Drying Room Kiln Room	Window Apron	Wood	Brown	None	0	0.1	Negative
1	5	506	Classroom 506 Art Room	W1 W2	Sheetrock	White	None	10	9.2	Negative
1	5	506	Classroom 506 Art Room	W3	Plaster	White White	Efflorescence	5	9.2	Positive
1	5	506	Classroom 506 Art Room	W4	Plaster		Flaking		9.1	Positive
1	5	506	Classroom 506 Art Room		Plaster	White White	Flaking	40	9.1	Positive Positive
1	5	506	Classroom 506 Art Room	Ceiling	Plaster	vvriite	Cracking	40	10.5	Positive

			Dates: 3/13/2023 to 7/21/2023		Lead-S	afe Certi	fication Asse	essment l	Report	
			Inspector Name and PA License Number:		D	.1	4 O'4 NI'-	1-11- 0-11-		
			Lawrence Jackson 003683		Par	'kway Ce	nter City Mic	idle Colle	ge	
			Inspection Company: USA Environmental		5 40 N				10100	
			Management Inc		540 Nor	tn 13tn S	treet, Philad	eipnia, P <i>i</i>	19123	
E										
	F									
e m	[
e	0									XRF
n	0						Description of	Damage	XRF Reading	(positive/
t	r	Space #	Onsite Room Name	Component	Substrate Material	Paint Color	Damage	Quantity (sf)	(mg/cm2)	negative)
1	5	506	Classroom 506 Art Room	Floor	12 x 12 Floor Tile	Unpainted	N/A	N/A	N/A	N/A
1	5	506	Classroom 506 Art Room	Radiator	Metal	Gray	Flaking	10	3.8	Positive
1	5	506	Classroom 506 Art Room	Radiator	Metal	Gray	Flaking	· ·	4.3	Positive
1	5	506	Classroom 506 Art Room	Door	Wood	Brown	Friction	1	0	Negative
1	5	506	Classroom 506 Art Room	Door Casing	Metal	Brown	Friction	1	0.1	Negative
1	5	506	Classroom 506 Art Room	Window Casing	Wood	Brown	Alligatoring	5	0.1	Negative
1	5	506	Classroom 506 Art Room	Window Sill	Wood	Brown	Flaking	5	0.1	Negative
1	5	506	Classroom 506 Art Room	Window Apron	Wood	Brown	None	0	0.1	Negative
1	5	S53	Stairwell adjacent to Classroom 506 Art Room	W1	Plaster	Gray	None	0	7.1	Positive
1	5	S53	Stairwell adjacent to Classroom 506 Art Room	W2	Plaster	Gray	None	0	0	Negative
1	5	S53	Stairwell adjacent to Classroom 506 Art Room	W3	Plaster	Gray	None	0	12	Positive
1	5	S53	Stairwell adjacent to Classroom 506 Art Room	W4	Brick	Unpainted	N/A	N/A	N/A	N/A
1	5	S53	Stairwell adjacent to Classroom 506 Art Room	Ceiling	Plaster	White	None	0	10.7	Positive
1	5	S53	Stairwell adjacent to Classroom 506 Art Room	Floor	Concrete	Gray	None	0	1.9	Positive
1	5	S53	Stairwell adjacent to Classroom 506 Art Room	Stair Treads	Concrete	Gray	None	0	1	Positive
1	5	S53	Stairwell adjacent to Classroom 506 Art Room	Stair Riser	Concrete	Gray	None	0	1.2	Positive
1	5	S53	Stairwell adjacent to Classroom 506 Art Room	Stair Stringer	Concrete	Gray	None	0	2.3	Positive
1	5	S53	Stairwell adjacent to Classroom 506 Art Room	Newel Post	Metal	Brown	None	0	7.4	Positive
1	5	S53	Stairwell adjacent to Classroom 506 Art Room	Radiator Door	Metal Metal	Gray Brown	None None	0	0.8	Positive
1	5	S53 S53	Stairwell adjacent to Classroom 506 Art Room	Door Casing	Metal	Brown	None	0	6.8	Negative Positive
1	5	505C	Stairwell adjacent to Classroom 506 Art Room Vestibule outside Storage Room 505B	W1	Sheetrock	Gray	None	0	0.8	Negative
1	5	505C	Vestibule outside Storage Room 505B	W2	Sheetrock	Gray	None	0	0	Negative
1	5	505C	Vestibule outside Storage Room 505B	W3	Sheetrock	Gray	None	0	0	Negative
1	5	505C	Vestibule outside Storage Room 505B	W4	Brick	Unpainted	N/A	N/A	N/A	N/A
1	5	505C	Vestibule outside Storage Room 505B	Ceiling	No Access	No Access	No Access	No Access	No Access	No Access
1	5	505C	Vestibule outside Storage Room 505B	Door Casing	Wood	Brown	None	0	0.1	Negative
1	5	505B	Storage Room 505B	W1	Plaster	Gray	Flaking	5	9.4	Positive
1	5	505B	Storage Room 505B	W2	Plaster	Gray	Flaking	10	6.8	Positive
1	5	505B	Storage Room 505B	W3	Plaster	Gray	None	0	11.3	Positive
1	5	505B	Storage Room 505B	W4	Sheetrock	Gray	None	0	0	Negative
1	5	505B	Storage Room 505B	Ceiling	Plaster	Tan	Cracking	25	10.9	Positive
1	5	505B	Storage Room 505B	Floor	Wood	Unpainted	N/A	N/A	N/A	N/A
1	5	505B	Storage Room 505B	Radiator	Metal	Gray	Flaking	3	5.5	Positive
1	5	505B	Storage Room 505B	Radiator	Metal	Gray	Flaking	3	3.6	Positive
1	5	505B	Storage Room 505B	Window Casing	Wood	Brown	None	0	0.2	Negative
1	5	505B	Storage Room 505B	Window Sill	Wood	Gray	None	0	0.1	Negative

			Dates: 3/13/2023 to 7/21/2023		Lead-S	afe Certi	fication Asse	essment F	Report	
			Inspector Name and PA License Number:		D	.1	4 O'4 NI'-			
			Lawrence Jackson 003683		Pai	rkway Ce	nter City Mid	iale Colle	ge	
			Inspection Company: USA Environmental		E40 Nor	th 12th C	treet, Philade	olobia D/	10122	
<u> </u>		1	Management Inc		540 NOI	เมางเมง	treet, Pillau	eipilia, P	19123	
E I e m	F									
е	0									XRF
n	o r	Space #	Onsite Room Name	Component	Substrate Material	Paint Color	Description of Damage	Damage Quantity (sf)	XRF Reading (mg/cm2)	(positive/ negative)
1	5	505B	Storage Room 505B	Window Apron	Wood	Gray	None	Quantity (ST)	0.1	Negative
1	5	505B	Storage Room 505B	Baseboard	Wood	Gray	None	0	0.1	Negative
1	5	505B	Storage Room 505B	Door Casing	Metal	Tan	None	0	0.1	Negative
1	5	505A	Classroom 505 - Science Classroom	Door	Wood	Varnish	None	0	0.1	Negative
1	5	505A	Classroom 505 - Science Classroom	Door Casing	Wood	Brown	None	0	0.1	Negative
1	5	505A	Classroom 505 - Science Classroom	W1	Sheetrock	White	None	0	0	Negative
1	5	505A	Classroom 505 - Science Classroom	W2	Plaster	White	Cracking	25	1.2	Positive
1	5	505A	Classroom 505 - Science Classroom	W3	Sheetrock	White	None	0	0	Negative
1	5	505A	Classroom 505 - Science Classroom	W4	Plaster	Blue	None	0	0	Negative
1	5	505A	Classroom 505 - Science Classroom	Ceiling	Plaster	White	Cracking	100	10.1	Positive
1	5	505A	Classroom 505 - Science Classroom	Floor	12 x 12 Floor Tile	Unpainted	N/A	N/A	N/A	N/A
1	5	505A	Classroom 505 - Science Classroom	Radiator	Metal	Gray	None	0	4.8	Positive
1	5	505A	Classroom 505 - Science Classroom	Radiator	Metal	Gray	None	0	3.6	Positive
1	5	505A	Classroom 505 - Science Classroom	Radiator	Metal	Gray	None	0	0.1	Negative
1	5	505A	Classroom 505 - Science Classroom	Window Sill	Wood	Brown	None	0	0.1	Negative
1	5	505A	Classroom 505 - Science Classroom	Window Casing	Wood	Brown	None	0	0.1	Negative
1	5	505A	Classroom 505 - Science Classroom	Window Apron	Wood	Brown	None	0	0.1	Negative
1	5	505A	Classroom 505 - Science Classroom	Baseboard	Wood	Brown	None	0	0	Negative
1	5	504A	Hallway to Science Lab Prep Room between Classrooms 505A and 504	W1	Sheetrock	Beige	None	0	0	Negative
1	5	504A	Hallway to Science Lab Prep Room between Classrooms 505A and 504	W2	Sheetrock	Beige	None	0	0	Negative
1	5	504A	Hallway to Science Lab Prep Room between Classrooms 505A and 504	W3	Sheetrock	Beige	None	0	0	Negative
1	5	504A	Hallway to Science Lab Prep Room between Classrooms 505A and 504	W4	Sheetrock	Beige	None	0	0	Negative
1	5	504A	Hallway to Science Lab Prep Room between Classrooms 505A and 504	Ceiling	No Access	No Access	No Access	No Access	No Access	No Access
1	5	504A	Hallway to Science Lab Prep Room between Classrooms 505A and 504	Floor	12 x 12 Floor Tile	Unpainted	N/A	N/A	N/A	N/A
1	5	504B	Science Lab Prep Room between Classrooms 505A and 504	W1	Plaster	Beige	Flaking	5	11.5	Positive
1	5	504B	Science Lab Prep Room between Classrooms 505A and 504	W2	Sheetrock	Beige	None	0	0	Negative
1	5	504B	Science Lab Prep Room between Classrooms 505A and 504	W3	Sheetrock	Beige	None	0	0	Negative
1	5	504B	Science Lab Prep Room between Classrooms 505A and 504	W4	Sheetrock	Beige	None	0	0	Negative
1	5	504B	Science Lab Prep Room between Classrooms 505A and 504	Ceiling	No Access	No Access	No Access	N/A	N/A	N/A

			Dates: 3/13/2023 to 7/21/2023		Lead-S	afe Certi	fication Asse	essment l	Report	
			Inspector Name and PA License Number:				4 0'4 11'			
			Lawrence Jackson 003683		Pai	'kway Ce	nter City Mic	idie Colle	ege	
			Inspection Company: USA Environmental		= 40 N				10100	
			Management Inc		540 Nor	th 13th S	treet, Philad	elphia, PA	A 19123	
E										
	F									
e m	[
e	0									XRF
n	0						Description of	Damage	XRF Reading	(positive/
t	r	Space #	Onsite Room Name	Component	Substrate Material	Paint Color	Damage	Quantity (sf)	(mg/cm2)	negative)
1	5	504B	Science Lab Prep Room between Classrooms 505A and 504	Floor	Wood	Unpainted	N/A	N/A	N/A	N/A
1	5	504B	Science Lab Prep Room between Classrooms 505A and 504	Radiator	Metal	Gray	None	0	3.2	Positive
1	5	504B	Science Lab Prep Room between Classrooms 505A and 504	Window Casing	Wood	Brown	None	0	0.1	Negative
1	5	504B	Science Lab Prep Room between Classrooms 505A and 504	Window Sill	Wood	Brown	None	0	0.2	Negative
1	5	504B	Science Lab Prep Room between Classrooms 505A and 504	Window Apron	Wood	Brown	None	0	0.1	Negative
1	5	504B	Science Lab Prep Room between Classrooms 505A and 504	Baseboard	Wood	Brown	None	0	0	Negative
1	5	504C	Service Closet adjacent to Science Lab Prep Room	W1	Sheetrock	Tan	None	0	0.1	Negative
1	5	504C	Service Closet adjacent to Science Lab Prep Room	W2	Ceramic	Unpainted	N/A	N/A	N/A	N/A
1	5	504C	Service Closet adjacent to Science Lab Prep Room	W3	Sheetrock	Tan	None	0	0.1	Negative
1	5	504C	Service Closet adjacent to Science Lab Prep Room	W4	Sheetrock	Tan	None	0	0.1	Negative
1	5	504C	Service Closet adjacent to Science Lab Prep Room	Ceiling	No Access	No Access	No Access	N/A	N/A	N/A
1	5	504C	Service Closet adjacent to Science Lab Prep Room	Floor	Ceramic	Unpainted	N/A	N/A	N/A	N/A
1	5	504C	Service Closet adjacent to Science Lab Prep Room	Door	Wood	Varnish	None	0	0	Negative
1	5	504C	Service Closet adjacent to Science Lab Prep Room	Door Casing	Metal	Brown	None	0	0.1	Negative
1	5	504D	Staff Restroom near Science Lab Prep Room	W1	Sheetrock	Tan	None	0	0.6	Negative
1	5	504D	Staff Restroom near Science Lab Prep Room	W2	Ceramic	Unpainted	N/A	N/A	N/A	N/A
1	5	504D	Staff Restroom near Science Lab Prep Room	W3	Sheetrock	Tan	None	0	0.1	Negative
1	5	504D	Staff Restroom near Science Lab Prep Room	W4	Sheetrock	Tan	None	0	0	Negative
1	5	504D	Staff Restroom near Science Lab Prep Room	Ceiling Floor	No Access	No Access	No Access N/A	N/A N/A	N/A N/A	N/A N/A
1	5	504D 504D	Staff Restroom near Science Lab Prep Room Staff Restroom near Science Lab Prep Room	Door	Ceramic Wood	Unpainted Varnish	None	0	0 0	Negative
1	5	504D 504D	Staff Restroom near Science Lab Prep Room Staff Restroom near Science Lab Prep Room	Door Casing	Metal	Brown	None	0	0.1	Negative
1	5	504D 504	Classroom 504	W1	Sheetrock	White	Flaking	1	0.1	Negative
1	5	504	Classroom 504	W2	Plaster	White	Flaking	20	6	Positive
1	5	504	Classroom 504	W2 W3	Plaster	White	Flaking	25	0	Negative
1	5	504	Classroom 504	W4	Plaster	Green	Efflorescence	10	0	Negative
1	5	504	Classroom 504	Ceiling	Plaster	White	Alligatoring	60	7.7	Positive
1	5	504	Classroom 504	Door	Wood	Varnish	None	0	0.1	Negative
1	5	504	Classroom 504	Door Casing	Wood	Brown	None	0	0.1	Negative
1	5	504	Classroom 504	Window Casing	Wood	Brown	None	0	0.2	Negative
1	5	504	Classroom 504	Window Sill	Wood	Brown	None	0	0.3	Negative
1	5	504	Classroom 504	Window Apron	Wood	Brown	None	0	0.1	Negative
1	5	504	Classroom 504	Floor	12 x 12 Floor Tile	Unpainted	N/A	N/A	N/A	N/A

			Dates: 3/13/2023 to 7/21/2023		Lead-S	afe Certi	fication Asse	essment l	Report	
			Inspector Name and PA License Number:		Pai	rkway Co	nter City Mic	Idla Calla	- -	
			Lawrence Jackson 003683 Inspection Company: USA Environmental		rai	Kway Ce	inter Only Will	idle Colle	ge	
			Management Inc		540 Nor	th 13th S	treet, Philad	elphia, P	A 19123	
E I e m e n t	F I o o r	Space #	Onsite Room Name	Component	Substrate Material	Paint Color	Description of Damage	Damage Quantity (sf)	XRF Reading (mg/cm2)	XRF (positive/ negative)
1	5	504	Classroom 504	Radiator	Metal	Gray	None	0	5	Positive
1	5	504	Classroom 504	Radiator	Metal	Gray	None	0	3.9	Positive
1	5	504	Classroom 504	Radiator	Metal	Gray	None	0	5.4	Positive
1	5	S54	Stairwell adjacent to Classroom 504	W1	Plaster	Gray	None	0	10.3	Positive
1	5	S54	Stairwell adjacent to Classroom 504	W2	Plaster	Gray	None	0	0.3	Negative
1	5	S54	Stairwell adjacent to Classroom 504	W3	Plaster	Gray	None	0	10.2	Positive
1	5	S54	Stairwell adjacent to Classroom 504	Door Frame	Metal	Brown	None	0	5.4	Positive
1	5	S54	Stairwell adjacent to Classroom 504	Door	Metal	Gray	None	0	0	Negative
1	5	S54	Stairwell adjacent to Classroom 504	Newel Post	Metal	Brown	None	0	6.9	Positive
1	5	S54	Stairwell adjacent to Classroom 504	Handrail	Wood	Brown	None	0	0	Negative
1	5	S54	Stairwell adjacent to Classroom 504	Ceiling	Plaster	White	Flaking	3	8.8	Positive
1	5	S54	Stairwell adjacent to Classroom 504	Floor	Concrete	Gray	None	0	1.9	Positive
1	5	503A	Classroom 503	W1	Plaster	White	Flaking	2	0.1	Negative
1	5	503A	Classroom 503	W1	Plaster	Gray	Flaking	2	0.2	Negative
1	5	503A	Classroom 503	W2	Plaster	Gray	Flaking	5	8.8	Positive
1	5	503A	Classroom 503	W2	Plaster	Black	None	0	9.9	Positive
1	5	503A	Classroom 503	W3	Sheetrock	Green	None	0	0	Negative
1	5	503A	Classroom 503	W3 W4	Wood	Brown	None	0	0 0.2	Negative
1	5	503A	Classroom 503		Plaster	Brown	None	_		Negative
1	5	503A	Classroom 503	W4	Plaster Plaster	White White	None	20	10.9 11.6	Positive
1	5	503A	Classroom 503	Ceiling			Cracking N/A	N/A	11.6 N/A	Positive
1	5	503A	Classroom 503	Floor	12 x 12 Floor Tile	Unpainted	Flaking			N/A
1	5	503A	Classroom 503	Radiator Door	Metal Wood	Gray Varnish	None	5	6.8	Positive
1	5	503A 503A	Classroom 503 Classroom 503	Door Casing	Wood	Varnish Varnish	None	0	0	Negative
 +	5		Classroom 503 Classroom 503	Window Casing	Wood	Varnish Varnish	None	0	0.3	Negative Negative
1		503A	Classroom 503 Classroom 503	Window Casing Window Sill	Wood	Varnish	None	0	0.3	Negative
1	5	503A 503A	Classroom 503	Window Apron	Wood	Varnish	None	0	0.3	Negative
1	5	503A 503	Teacher's Lounge adjacent to Classroom 503	W1	Sheetrock	White	Flaking	10	0.1	Negative
1	5	503	Teacher's Lounge adjacent to Classroom 503	W2	Plaster	White	Flaking	40	8.8	Positive
1	5	503	Teacher's Lounge adjacent to Classroom 503	W3	Sheetrock	White	Flaking	10	0.0	Negative
1	5	503	Teacher's Lounge adjacent to Classroom 503	W4	Plaster	White	Flaking	30	9.6	Positive
1	5	503	Teacher's Lounge adjacent to Classroom 503	Ceiling	Plaster	White	Cracking	40	9.5	Positive
1	5	503	Teacher's Lounge adjacent to Classroom 503	Floor	Concrete	Unpainted	N/A	N/A	N/A	N/A
1	5	503	Teacher's Lounge adjacent to Classroom 503	Radiator	Metal	Gray	Flaking	10	5.5	Positive
1	5	503	Teacher's Lounge adjacent to Classroom 503	Radiator	Metal	Gray	Flaking	10	3.7	Positive
1	5	503	Teacher's Lounge adjacent to Classroom 503	Door	Wood	Varnish	None	0	0.7	Negative
1	5	503	Teacher's Lounge adjacent to Classroom 503	Door Casing	Wood	Varnish	None	0	0	Negative

			Dates: 3/13/2023 to 7/21/2023		Lead-S	afe Certi	fication Asse	essment F	Report	
			Inspector Name and PA License Number:		Do	deres Co	ndon Citur Mio			
			Lawrence Jackson 003683		Pai	rkway Ce	nter City Mic	iale Colle	ge	
			Inspection Company: USA Environmental Management Inc		540 Nor	th 13th S	treet, Philad	elphia, PA	A 19123	
E I e m e n t	F I o o r	Space #	Onsite Room Name	Component	Substrate Material	Paint Color	Description of Damage	Damage Quantity (sf)	XRF Reading (mg/cm2)	XRF (positive/ negative)
1	5	503	Teacher's Lounge adjacent to Classroom 503	Window Casing	Wood	Varnish	None	0	0.3	Negative
1	5	503	Teacher's Lounge adjacent to Classroom 503	Window Sill	Wood	Varnish	None	0	0.5	Negative
1	5	503	Teacher's Lounge adjacent to Classroom 503	Window Apron	Wood	Varnish	None	0	0.3	Negative
1	5	502	Classroom 502	W1	Sheetrock	White	None	0	0	Negative
1	5	502	Classroom 502	W2	Plaster	White	Flaking	5	9.7	Positive
1	5	502	Classroom 502	W3	Plaster	White	None	0	10.6	Positive
1	5	502	Classroom 502	W4	Plaster	White	Flaking	10	13.2	Positive
1	5	502	Classroom 502	Ceiling	Plaster	White	Cracking	30	9.3	Positive
1	5	502	Classroom 502	Floor	12 x 12 Floor Tile	Unpainted	N/A	N/A	N/A	N/A
1	5	502	Classroom 502	Radiator	Metal	Gray	Flaking	2	5.8	Positive
1	5	502	Classroom 502	Radiator	Metal	Gray	Flaking	4	4.2	Positive
1	5	502	Classroom 502	Door	Wood	Varnish	None	0	0	Negative
1	5	502	Classroom 502	Door Casing	Wood	Brown	None	0	0.1	Negative
1	5	502	Classroom 502	Window Casing	Wood	Brown	None	0	0.3	Negative
1	5	502	Classroom 502	Window Sill	Wood	Brown	None	0	0.3	Negative
1	5	502	Classroom 502	Window Apron	Wood	Brown	None	0	0	Negative
1	5	S56	Fire Tower adjacent to Classroom 502	W1	Brick	White	None	0	4.7	Positive
1	5	S56	Fire Tower adjacent to Classroom 502	W2	Brick	White	None	0	3.7	Positive
1	5	S56	Fire Tower adjacent to Classroom 502	W3	Brick	White	None	0	5.5	Positive
1	5	S56	Fire Tower adjacent to Classroom 502	W4	Brick	White	None	0	5.4	Positive
1	5	S56	Fire Tower adjacent to Classroom 502	Door	Metal	Brown	None	0	0	Negative
1	5	S56	Fire Tower adjacent to Classroom 502	Door Casing	Metal	Brown	None	0	0.4	Negative
1	5	S56	Fire Tower adjacent to Classroom 502	Ceiling	Concrete	White	Flaking	40	5.1	Positive
1	5	S56	Fire Tower adjacent to Classroom 502	Floor	Concrete	Gray	None	0	1.4	Positive
1	5	S56	Fire Tower adjacent to Classroom 502	Security Gate	Metal	Brown	Flaking	100	2.9	Positive
1	5	S56	Fire Tower adjacent to Classroom 502	Drain Pipe	Metal	Brown	Flaking	24	0.15	Negative
1	5	S56	Fire Tower adjacent to Classroom 502	Handrail	Metal	Brown	Chipping	10	0.5	Negative
1	5	S56	Fire Tower adjacent to Classroom 502	Stair Riser	Concrete	Gray	None	0	2.8	Positive
1	5	S56	Fire Tower adjacent to Classroom 502	Stair Treads	Concrete	Gray	None	0	2	Positive
1	5	S56	Fire Tower adjacent to Classroom 502	Stair Stringer	Concrete	Gray	None	0	2	Positive
1	5	501	Classroom 501	W1	Plaster	Gray	Flaking	3	8.7	Positive
1	5	501	Classroom 501	W2	Plaster	Gray	Efflorescence	20	8.7	Positive
1	5	501	Classroom 501	W3	Plaster	Gray	Efflorescence	20	9.1	Positive
1	5	501	Classroom 501	W4	Plaster	Gray	Flaking	20	11.4	Positive
1	5	501	Classroom 501	Ceiling	Plaster	White	Efflorescence	720	10.9	Positive
1	5	501	Classroom 501	Floor	Wood	Unpainted	N/A	N/A	N/A	N/A
1	5	501	Classroom 501	Radiator	Metal	Gray	Flaking	10	4.2	Positive
1	5	501	Classroom 501	Radiator Cover	Metal	Gray	None	0	0	Negative

			Dates: 3/13/2023 to 7/21/2023		Lead-S	afe Certi	fication Asse	essment l	Report	
			Inspector Name and PA License Number:		D	.1	4 O'4 NI'-	1-11- 0-11-		
			Lawrence Jackson 003683		Pai	rkway Ce	nter City Mic	iale Colle	ge	
			Inspection Company: USA Environmental		E40 Nor	th 12th C	troot Dhilad	alphia D/	10422	
		•	Management Inc		540 NO r	tn 13th 5	treet, Philad	eipnia, P	19123	
E I e m	F									
e	0									XRF
n	0						Description of	Damage	XRF Reading	(positive/
t	r	Space #	Onsite Room Name	Component	Substrate Material	Paint Color	Damage	Quantity (sf)	(mg/cm2)	negative)
1	5	501	Classroom 501	Door	Wood	Varnish	None	0	0.1	Negative
1	5	501	Classroom 501	Door Casing	Wood	Varnish	None	0	0.1	Negative
1	5	501	Classroom 501	Window Casing	Wood	Varnish	None	0	0.1	Negative
1	5	501	Classroom 501	Window Aprop	Wood Wood	Varnish Varnish	None None	0	0.2	Negative
1	5	501 501A	Classroom 501	Window Apron W1	vvood Plaster	White	Flaking	120	0	Negative Negative
1	5	501A 501A	Classroom 501 Pipe Chase Classroom 501 Pipe Chase	W2	Brick	Unpainted	N/A	N/A	N/A	Negative N/A
1	5	501A 501A	Classroom 501 Pipe Chase	W3	Brick	Unpainted	N/A N/A	N/A	N/A	N/A
1	5	501A	Classroom 501 Pipe Chase	W4	No Access	No Access	No Access	No Access	No Access	No Access
1	5	501A	Classroom 501 Pipe Chase	Ceiling	No Access	No Access	No Access	No Access	No Access	No Access
1	5	501A	Classroom 501 Pipe Chase	Floor	No Access	No Access	No Access	No Access	No Access	No Access
1	5	511	Boy's Restroom adjacent to Classroom 501	W1	Plaster	White	None	0	5.8	Positive
1	5	511	Boy's Restroom adjacent to Classroom 501	W2	Plaster	White	None	0	8.1	Positive
1	5	511	Boy's Restroom adjacent to Classroom 501	W3	Plaster	White	None	0	11.3	Positive
1	5	511	Boy's Restroom adjacent to Classroom 501	W4	Plaster	White	None	0	7.7	Positive
1	5	511	Boy's Restroom adjacent to Classroom 501	Ceiling	Concrete	White	Cracking	1	0	Negative
1	5	511	Boy's Restroom adjacent to Classroom 501	Floor	Concrete	Gray	None	0	0	Negative
1	5	511	Boy's Restroom adjacent to Classroom 501	Radiator	Metal	Gray	Flaking	1	0	Negative
1	5	511	Boy's Restroom adjacent to Classroom 501	Door	Wood	Brown	None	0	0	Negative
1	5	511	Boy's Restroom adjacent to Classroom 501	Door Casing	Wood	Brown	None	0	0.1	Negative
1	5	511B	Pipe Chase in Boy's Restroom adjacent to Classroom 501	W1	No Access	No Access	No Access	No Access	No Access	No Access
1	5	511B	Pipe Chase in Boy's Restroom adjacent to Classroom 501	W2	No Access	No Access	No Access	No Access	No Access	No Access
1	5	511B	Pipe Chase in Boy's Restroom adjacent to Classroom 501	W3	No Access	No Access	No Access	No Access	No Access	No Access
1	5	511B	Pipe Chase in Boy's Restroom adjacent to Classroom 501	W4	No Access	No Access	No Access	No Access	No Access	No Access
1	5	511B	Pipe Chase in Boy's Restroom adjacent to Classroom 501	Ceiling	No Access	No Access	No Access	N/A	N/A	N/A
1	5	511B	Pipe Chase in Boy's Restroom adjacent to Classroom 501	Floor	No Access	No Access	No Access	No Access	No Access	No Access
1	5	511B	Pipe Chase in Boy's Restroom adjacent to Classroom 501	Door	Wood	Brown	None	0	0.1	Negative
1	5	511B	Pipe Chase in Boy's Restroom adjacent to Classroom 501	Door Casing	Wood	Brown	None	0	0.1	Negative
1	5	511A	Pipe Shaft adjacent to Kitchen	W1	Brick	Unpainted	N/A	N/A	N/A	N/A
1	5	511A	Pipe Shaft adjacent to Kitchen	W2	Brick	Unpainted	N/A	N/A	N/A	N/A
1	5	511A	Pipe Shaft adjacent to Kitchen	W3	Brick	Unpainted	N/A	N/A	N/A	N/A

			Dates: 3/13/2023 to 7/21/2023	Lead-Safe Certification Assessment Report						
			Inspector Name and PA License Number: Lawrence Jackson 003683		Pai	rkway Ce	nter City Mid	Idle Colle	ge	
			Inspection Company: USA Environmental Management Inc				treet, Philad		•	
E I e m e n t	F I o o r	Space #	Onsite Room Name	Component	Substrate Material	Paint Color	Description of Damage	Damage Quantity (sf)	XRF Reading (mg/cm2)	XRF (positive/ negative)
1	5	511A	Pipe Shaft adjacent to Kitchen	W4	Brick	Unpainted	N/A	N/A	N/A	N/A
1	5	511A	Pipe Shaft adjacent to Kitchen	Ceiling	Brick	Unpainted	N/A	N/A	N/A	N/A
1	5	511A	Pipe Shaft adjacent to Kitchen	Floor	No Access	No Access	None	N/A	N/A	N/A
1	5	511A	Pipe Shaft adjacent to Kitchen	Door	Wood	Varnish	None	0	0	Negative
1	5	511A	Pipe Shaft adjacent to Kitchen	Door Casing	Wood	Varnish	None	0	0.1	Negative
1	5	512	Cafeteria	W1	Plaster	White	Flaking	10	7.3	Positive
1	5	512	Cafeteria	W2	Plaster	White	Flaking	6	10.1	Positive
1	5	512	Cafeteria	W3	Plaster	White	Flaking	4	8.9	Positive
1	5	512	Cafeteria	W4	Plaster	White	Flaking	2	7.1	Positive
1	5	512	Cafeteria	Ceiling	Plaster	White	Flaking	80	8.1	Positive
1	5	512	Cafeteria	Floor	Wood	Unpainted	N/A	N/A	N/A	N/A
1	5	512	Cafeteria	Radiator	Metal	Gray	Flaking	5	2.5	Positive
1	5	512	Cafeteria	Radiator	Metal	Gray	Flaking	5	1.5	Positive
1	5	512	Cafeteria	Radiator	Metal	Gray	Flaking	5	1.9	Positive
1	5	512	Cafeteria	Radiator	Metal	Gray	Flaking	5	2.9	Positive
1	5	512	Cafeteria	Radiator	Metal	Gray	Flaking	5	0.5	Negative
1	5	512	Cafeteria	Radiator	Metal	Gray	Flaking	5	1.7	Positive
1	5	512	Cafeteria	Baseboard	Wood	Brown	None	0	0	Negative
1	5	512	Cafeteria	Window Casing	Metal	Brown	None	0	1.9	Positive
1	5	512	Cafeteria	Window Casing	Metal	Brown	None	0	5.9	Positive
1	5	510	Kitchen	W1	Plaster	White	None	0	20.3	Positive
1	5	510	Kitchen	W2	Plaster	White	None	0	12.4	Positive
1	5	510	Kitchen	W3	Plaster	White	None	0	13.9	Positive
1	5	510	Kitchen	W4	Plaster	White	None	0	17	Positive
1	5	510	Kitchen	Ceiling	Plaster	White	No Access	No Access	No Access	No Access
1	5	510	Kitchen	Floor	Ceramic Tile	Unpainted	N/A	N/A	N/A	N/A
1	5	510	Kitchen	Radiator	Metal	Gray	None	0	0	Negative
1	5	510	Kitchen	Radiator	Metal	Gray	Flaking	1	0.1	Negative
1	5	510	Kitchen	Window Casing	Wood	Varnish	None	0	0.4	Negative
1	5	510	Kitchen	Door	Wood	Varnish	None	0	0	Negative
1	5	510	Kitchen	Door Casing	Wood	Varnish	None	0	0	Negative
1	5	ST512	Stairway adjacent to cafeteria serving line	W1	Plaster	Tan	Flaking	300	0.8	Positive
1	5	ST512	Stairway adjacent to cafeteria serving line	W2	Plaster	Tan	Flaking	100	0.1	Negative
1	5	ST512	Stairway adjacent to cafeteria serving line	W3	Plaster	Tan	Flaking	100	0.1	Negative
1	5	ST512	Stairway adjacent to cafeteria serving line	W4	Plaster	Tan	None	0	0.1	Negative
1	5	ST512	Stairway adjacent to cafeteria serving line	Ceiling	Plaster	Tan	Chipping	250	No Access	Assumed
1	5	H51	Hallway outside Kitchen to Classroom 503	W1	Plaster	Gray	None	0	0.2	Negative
1	5	H51	Hallway outside Kitchen to Classroom 503	W2	Plaster	Gray	None	0	8.2	Positive

			Dates: 3/13/2023 to 7/21/2023		Lead-S	afe Certi	fication Asse	essment F	Report	
			Inspector Name and PA License Number:						_	
			Lawrence Jackson 003683		Pai	rkway Ce	nter City Mid	iale Colle	ge	
			Inspection Company: USA Environmental Management Inc		540 Nor	th 13th S	treet, Philad	elphia. PA	A 19123	
E I e m	F I o						,	•		XRF
n t	o r	Space #	Onsite Room Name	Component	Substrate Material	Paint Color	Description of Damage	Damage Quantity (sf)	XRF Reading (mg/cm2)	(positive/ negative)
1	5	H51	Hallway outside Kitchen to Classroom 503	W3	Plaster	Gray	None	0	0.4	Negative
1	5	H51	Hallway outside Kitchen to Classroom 503	W4	Plaster	Gray	None	0	0.4	Negative
1	5	H51	Hallway outside Kitchen to Classroom 503	Ceiling	Plaster	Tan	Flaking	30	11.9	Positive
1	5	H51	Hallway outside Kitchen to Classroom 503	Floor	Concrete	Gray	None	0	0.9	Positive
1	5	H51	Hallway outside Kitchen to Classroom 503	Floor	Metal	Brown	None	0	0.1	Negative
1	5	H51	Hallway outside Kitchen to Classroom 503	Floor	Metal	Brown	None	0	0.1	Negative
1	5	h51	Hallway outside Kitchen to Classroom 503	Radiators	Metal	Gray	Flaking	5	0.9	Positive
1	5	H51	Hallway outside Kitchen to Classroom 503	Radiators	Metal	Gray	Flaking	3	1.1	Positive
1	5	H51	Hallway outside Kitchen to Classroom 503	Radiators	Metal	Gray	Flaking	2	0.9	Positive
1	5	H51	Hallway outside Kitchen to Classroom 503	Locker	Metal	Brown	None	0	0.1	Negative
1	5	H51	Hallway outside Kitchen to Classroom 503	Locker	Metal	Green	None	0	0	Negative
1	5	H51PCS	Pipe/Cable Shaft in Hallway next to Classroom 502	W1	No Access	No Access	No Access	No Access	No Access	No Access
1	5	H51PCS	Pipe/Cable Shaft in Hallway next to Classroom 502	W2	No Access	No Access	No Access	No Access	No Access	No Access
1	5	H51PCS	Pipe/Cable Shaft in Hallway next to Classroom 502	W3	No Access	No Access	No Access	No Access	No Access	No Access
1	5	H51PCS	Pipe/Cable Shaft in Hallway next to Classroom 502	W4	No Access	No Access	No Access	No Access	No Access	No Access
1	5	H51PCS	Pipe/Cable Shaft in Hallway next to Classroom 502	Door	Wood	Brown	None	0	0.1	Negative
1	5	H51PCS	Pipe/Cable Shaft in Hallway next to Classroom 502	Door Casing	Wood	Brown	None	0	0.1	Negative
1	5	H53	Hallway outside Classrooms 504 to 505B	W1	Plaster	Gray	None	0	10.2	Positive
1	5	H53	Hallway outside Classrooms 504 to 505B	W2	Plaster	Gray	None	0	7.6	Positive
1	5	H53	Hallway outside Classrooms 504 to 505B	W3	Plaster	Gray	None	0	10.5	Positive
1	5	H53	Hallway outside Classrooms 504 to 505B	W4	Plaster	Gray	None	0	9.7	Positive
1	5	H53	Hallway outside Classrooms 504 to 505B	Ceiling	Plaster	Tan	Cracking	200	13	Positive
1	5	H53	Hallway outside Classrooms 504 to 505B	Floor	Concrete	Gray	None	0	3.1	Positive
1	5	H53	Hallway outside Classrooms 504 to 505B	Electrical Panel	Metal	Gray	None	0	0	Negative
1	5	H53	Hallway outside Classrooms 504 to 505B	Electrical Panel	Metal	Brown	None	0	2.3	Positive
1	5	H53PCS1	Pipe/Cable Shaft in Hallway next to Stairwell by Classroom 504	W1	Brick	Unpainted	N/A	N/A	N/A	N/A
1	5	H53PCS1	Pipe/Cable Shaft in Hallway next to Stairwell by Classroom 504	W2	Brick	Unpainted	N/A	N/A	N/A	N/A
1	5	H53PCS1	Pipe/Cable Shaft in Hallway next to Stairwell by Classroom 504	W3	Brick	Unpainted	N/A	N/A	N/A	N/A
1	5	H53PCS1	Pipe/Cable Shaft in Hallway next to Stairwell by Classroom 504	W4	Brick	Unpainted	N/A	N/A	N/A	N/A
1	5	H53PCS1	Pipe/Cable Shaft in Hallway next to Stairwell by Classroom 504	Door	Wood	Brown	None	0	0	Negative
1	5	H53PCS1	Pipe/Cable Shaft in Hallway next to Stairwell by Classroom 504	Door Casing	Wood	Brown	None	0	0.2	Negative

			Dates: 3/13/2023 to 7/21/2023		Lead-S	afe Certi	fication Asse	essment l	Report	
			Inspector Name and PA License Number:				4 0:4 14:		•	
			Lawrence Jackson 003683		Pai	rkway Ce	nter City Mic	idle Colle	ge	
			Inspection Company: USA Environmental		540 N	41- 4041- 0	4 4 Dl. !! - al	- l l-: - D/	10400	
			Management Inc		540 Nor	tn 13tn S	treet, Philad	eipnia, P <i>i</i>	19123	
E I e	F									
m e										XRF
n	0						Description of	Damage	XRF Reading	(positive/
t	r	Space #	Onsite Room Name	Component	Substrate Material	Paint Color	Damage	Quantity (sf)	(mg/cm2)	negative)
1	5	H53PCS2	Pipe/Cable Shaft in Hallway over Hydration Station near Classroom 504	W1	Brick	Unpainted	N/A	N/A	N/A	N/A
1	5	H53PCS2	Pipe/Cable Shaft in Hallway over Hydration Station near Classroom 504	W2	Brick	Unpainted	N/A	N/A	N/A	N/A
1	5	H53PCS2	Pipe/Cable Shaft in Hallway over Hydration Station near Classroom 504	W3	Brick	Unpainted	N/A	N/A	N/A	N/A
1	5	H53PCS2	Pipe/Cable Shaft in Hallway over Hydration Station near Classroom 504	W4	Brick	Unpainted	N/A	N/A	N/A	N/A
1	5	H53PCS2	Pipe/Cable Shaft in Hallway over Hydration Station near Classroom 504	Door	Wood	Brown	None	0	0	Negative
1	5	H53PCS2	Pipe/Cable Shaft in Hallway over Hydration Station near Classroom 504	Door Casing	Wood	Brown	None	0	0.1	Negative
1	5	H53PCS3	Pipe/Cable Shaft in Hallway next to Stairwell by Classroom 505	W1	Brick	Unpainted	N/A	N/A	N/A	N/A
1	5	H53PCS3	Pipe/Cable Shaft in Hallway next to Stairwell by Classroom 505	W2	Brick	Unpainted	N/A	N/A	N/A	N/A
1	5	H53PCS3	Pipe/Cable Shaft in Hallway next to Stairwell by Classroom 505	W3	Brick	Unpainted	N/A	N/A	N/A	N/A
1	5	H53PCS3	Pipe/Cable Shaft in Hallway next to Stairwell by Classroom 505	W4	Brick	Unpainted	N/A	N/A	N/A	N/A
1	5	H53PCS3	Pipe/Cable Shaft in Hallway next to Stairwell by Classroom 505	Door	Wood	Brown	None	0	0	Negative
1	5	H53PCS3	Pipe/Cable Shaft in Hallway next to Stairwell by Classroom 505	Door Casing	Wood	Brown	None	0	0.2	Negative
1	5	H52	Hallway outside Classroom 506 to Kitchen	W1	Plaster	White	None	0	11.8	Positive
1	5	H52	Hallway outside Classroom 506 to Kitchen	W2	Plaster	White	None	0	5.1	Positive
1	5	H52	Hallway outside Classroom 506 to Kitchen	W3	Plaster	White	None	0	8.8	Positive
1	5	H52	Hallway outside Classroom 506 to Kitchen	W4 Ceiling	Plaster Plaster	White Tan	None Flaking	100	9.7 11.2	Positive Positive
1	5	H52 H52	Hallway outside Classroom 506 to Kitchen Hallway outside Classroom 506 to Kitchen	Floor	Plaster	Gray	None	0	11.2	Positive
1	5	H52	Hallway outside Classroom 506 to Kitchen	Radiator	Metal	Gray	None	0	2.4	Positive
1	5	H52	Hallway outside Classroom 506 to Kitchen	Radiator	Metal	Gray	None	0	1	Positive
1	5	H52	Hallway outside Classroom 506 to Kitchen	Radiator	Metal	Gray	None	0	0.3	Negative
1	5	H52	Hallway outside Classroom 506 to Kitchen	Door Electrical Panel	Metal	Gray	None	0	8	Positive
1	5	H52PCS	Pipe/Cable Shaft in Hallway next to Classroom 506	W1	Concrete	Unpainted	N/A	N/A	N/A	N/A
1	5	H52PCS	Pipe/Cable Shaft in Hallway next to Classroom 506	W2	Terracotta	Unpainted	N/A	N/A	N/A	N/A
1	5	H52PCS	Pipe/Cable Shaft in Hallway next to Classroom 506	W3	Terracotta	Unpainted	N/A	N/A	N/A	N/A
1	5	H52PCS	Pipe/Cable Shaft in Hallway next to Classroom 506	W4	Terracotta	Unpainted	N/A	N/A	N/A	N/A
1	5	H52PCS	Pipe/Cable Shaft in Hallway next to Classroom 506	Door	Wood	Brown	None	0	0.1	Negative

			Dates: 3/13/2023 to 7/21/2023		Lead-S	afe Certi	fication Asso	essment l	Report	
			Inspector Name and PA License Number: Lawrence Jackson 003683		Pai	rkway Ce	nter City Mic	ddle Colle	ge	
			Inspection Company: USA Environmental Management Inc				treet, Philad			
E I e m e n t	F I O O r	Space #	Onsite Room Name	Component	Substrate Material	Paint Color	Description of Damage	Damage Quantity (sf)	XRF Reading (mg/cm2)	XRF (positive/ negative)
1	5	H52PCS	Pipe/Cable Shaft in Hallway next to Classroom 506	Door Casing	Wood	Brown	None	0	0.1	Negative
1	4	412A	Storage Room near Classroom 411	W1	Plaster	White	Flaking	300	9.9	positive
1	4	412A	Storage Room near Classroom 411	W2	Plaster	White	Flaking	150	8.9	positive
1	4	412A	Storage Room near Classroom 411	W3	Plaster	White	None	0	0.2	Negative
1	4	412A	Storage Room near Classroom 411	W4	Plaster	White	Flaking	20	1.6	Positive
1	4	412A	Storage Room near Classroom 411	Door	Wood	Varnish	None	0	0	Negative
1	4	412A	Storage Room near Classroom 411	Door Casing	Wood	Varnish	None	0	0.1	Negative
1	4	412A	Storage Room near Classroom 411	Ceiling	Plaster	White	Flaking	100	10	Positive
1	4	412A	Storage Room near Classroom 411	Radiator	Metal	Gray	None	0	0	Negative
1	4	412A	Storage Room near Classroom 411	Radiator 2 Cover	Metal	Gray	None	0	0	Negative
1	4	412A	Storage Room near Classroom 411	Window sill	Wood	Varnish	None	0	0.1	Negative
1	4	412A	Storage Room near Classroom 411	Window Casing	Wood	Varnish	None	0	0.1	Negative
1	4	412A	Storage Room near Classroom 411	Window Apron	Wood	Varnish	None	0	0.1	Negative
1	4	S412	Stairs between Cafeteria and Storage Room near Classroom 411	W1	Plaster	Gray	None	0	10	Positive
1	4	S412	Stairs between Cafeteria and Storage Room near Classroom 411	W2	Plaster	Gray	None	0	7.41	Positive
1	4	S412	Stairs between Cafeteria and Storage Room near Classroom 411	W3	Plaster	Gray	Flaking	5	9	Positive
1	4	S412	Stairs between Cafeteria and Storage Room near Classroom 411	W4	Plaster	Gray	None	0	9.3	Positive
1	4	S412	Stairs between Cafeteria and Storage Room near Classroom 411	Floor	Concrete	Gray	None	0	2.12	Positive
1	4	S412	Stairs between Cafeteria and Storage Room near Classroom 411	Ceiling	Plaster	White	None	0	11.5	Positive
1	4	S412	Stairs between Cafeteria and Storage Room near Classroom 411	Stair Tread	Concrete	Gray	None	0	1.1	Positive
1	4	S412	Stairs between Cafeteria and Storage Room near Classroom 411	Stair Riser	Concrete	Gray	None	0	5.3	Positive
1	4	S412	Stairs between Cafeteria and Storage Room near Classroom 411	Stair Stringer	Concrete	Gray	None	0	6.4	Positive
1	4	S412	Stairs between Cafeteria and Storage Room near Classroom 411	Floor	Concrete	Gray	None	0	2.12	Positive
1	4	412	Girl's Restroom next to Classroom 411	W1	Plaster	Tan	None	0	0	Negative
1	4	412	Girl's Restroom next to Classroom 411	W2	Plaster	Tan	None	0	0	Negative
1	4	412	Girl's Restroom next to Classroom 411	W3	Plaster	Tan	None	0	8.9	Positive
1	4	412	Girl's Restroom next to Classroom 411	W4	Plaster	Tan	None	0	7.8	Positive
1	4	412	Girl's Restroom next to Classroom 411	Ceiling	Concrete	White	Flaking	10	8.5	Positive
1	4	412	Girl's Restroom next to Classroom 411	Floor	Concrete	Gray	None	0	0	Negative

			Dates: 3/13/2023 to 7/21/2023		Lead-S	afe Certi	fication Asse	essment l	Report	
			Inspector Name and PA License Number:		D	.1	4 O!4 N!:-	1-11- 0-11-		
			Lawrence Jackson 003683		Pai	rkway Ce	nter City Mic	iale Colle	ege	
			Inspection Company: USA Environmental Management Inc		540 Nor	th 13th S	treet, Philad	elphia, PA	A 19123	
E I e m	F						,			
e n t	o o r	Space #	Onsite Room Name	Component	Substrate Material	Paint Color	Description of Damage	Damage Quantity (sf)	XRF Reading (mg/cm2)	XRF (positive/ negative)
1	4	412	Girl's Restroom next to Classroom 411	Radiator	Metal	Gray	Cracking	5	0.3	Negative
1	4	412	Girl's Restroom next to Classroom 411	Door	Wood	Brown	None	0	0	Negative
1	4	412	Girl's Restroom next to Classroom 411	Door Casing	Wood	Brown	None	0	0.1	Negative
1	4	412B	Pipe Chase in Girl's Restroom next to Classroom 411	Door	Wood	Tan	None	0	0.1	Negative
1	4	412B	Pipe Chase in Girl's Restroom next to Classroom 411	Door Casing	Wood	Tan	None	0	0	Negative
1	4	412B	Pipe Chase in Girl's Restroom next to Classroom 411	W1	Concrete	Unpainted	N/A	N/A	N/A	N/A
1	4	412B	Pipe Chase in Girl's Restroom next to Classroom 411	W2	Concrete	Unpainted	N/A	N/A	N/A	N/A
1	4	412B	Pipe Chase in Girl's Restroom next to Classroom 411	W3	Concrete	Unpainted	N/A	N/A	N/A	N/A
1	4	412B	Pipe Chase in Girl's Restroom next to Classroom 411	W4	Concrete	Unpainted	N/A	N/A	N/A	N/A
1	4	411	Classroom 411	W1	Plaster	Gray	Flaking	100	0.1	Negative
1	4	411	Classroom 411	W2	Plaster	Gray	Flaking	50	0.1	Negative
1	4	411	Classroom 411	W3	Plaster	Gray	Efflorescence	60	10.7	Positive
1	4	411	Classroom 411	W4	Plaster	Gray	Flaking	25	10.9	Positive
1	4	411	Classroom 411	Ceiling	Plaster	Tan	Flaking	300	1.2	Positive
1	4	411	Classroom 411	Floor	Wood	Unpainted	N/A	N/A	N/A	N/A
1	4	411	Classroom 411	Radiator	Metal	Gray	Flaking	10	0.2	Negative
1	4	411	Classroom 411	Radiator	Metal	Gray	Flaking	10	3.1	Positive
1	4	411	Classroom 411	Radiator	Metal	Gray	Flaking	10	3.2	Positive
1	4	411	Classroom 411	Door	Wood	Varnish	None	0	0	Negative
1	4	411	Classroom 411	Door Casing	Wood	Varnish	None	0	0.1	Negative
1	4	411	Classroom 411	Window Casing	Wood	Varnish	None	0	0.2	Negative
1	4	411	Classroom 411	Window Sill	Wood	Varnish	None	0	0.4	Negative
1	4	411	Classroom 411	Window Apron	Wood	Varnish	None	0	0.2	Negative
1	4	411	Classroom 411	Baseboard	Wood	Brown	None	0	0	Negative
1	4	S45	Fire Tower adjacent to Classroom 411	W1	Brick	White	None	0	5.8	Positive
1	4	S45	Fire Tower adjacent to Classroom 411	W2	Brick	White	None	0	8.2	Positive
1	4	S45	Fire Tower adjacent to Classroom 411	W3	Brick	White	None	0	10.1	Positive
1	4	S45	Fire Tower adjacent to Classroom 411	W4	Brick	White	None	0	8.5	Positive
1	4	S45	Fire Tower adjacent to Classroom 411	Ceiling	Concrete	White	Flaking	10	11.6	Positive
1	4	S45	Fire Tower adjacent to Classroom 411	Floor	Concrete	Gray	None	0	1.5	Positive
1	4	S45	Fire Tower adjacent to Classroom 411	Door	Metal	Brown	Flaking	5	0.1	Negative
1	4	S45	Fire Tower adjacent to Classroom 411	Door Casing	Metal	Brown	Flaking	5	0.3	Negative
1	4	S45	Fire Tower adjacent to Classroom 411	Drain Pipe	Metal	Brown	Flaking	24	23.4	Positive
1	4	S45	Fire Tower adjacent to Classroom 411	Security Gate	Metal	Brown	Flaking	100	26.4	Positive
1	4	S45	Fire Tower adjacent to Classroom 411	Handrail	Metal	Brown	Chipping	10	8	Positive
1	4	S45	Fire Tower adjacent to Classroom 411	Stair Riser	Concrete	Gray	None	0	1.3	Positive
1	4	S45	Fire Tower adjacent to Classroom 411	Stair Tread	Concrete	Gray	None	0	0.2	Negative
1	4	S45	Fire Tower adjacent to Classroom 411	Stair Stringer	Concrete	Gray	None	0	1.8	Positive

			Dates: 3/13/2023 to 7/21/2023	Lead-Safe Certification Assessment Report Parkway Center City Middle College						
			Inspector Name and PA License Number:		Pai	rkway Co	nter City Mid	Idla Calla		
			Lawrence Jackson 003683		rai	Kway Ce	Titel City Wild	idle Colle	ge	
			Inspection Company: USA Environmental Management Inc		540 Nor	th 13th S	treet, Philade	elphia, PA	A 19123	
E I e m e n	F I o	Succe #	Oneite Ream Name	Commonant	Sub-atropte Material	Boint Color	Description of	Damage	XRF Reading	XRF (positive/
1	4	Space # 410B	Onsite Room Name Office and Restroom 410B	Component W1	Substrate Material Plaster	Paint Color Green	Damage Cracking	Quantity (sf)	(mg/cm2) 21.1	negative) Positive
1	4	410B 410B	Office and Restroom 410B	W2	Plaster	Green	Flaking	40	20.3	Positive
1	4	410B	Office and Restroom 410B	W3	Plaster	Green	Flaking	10	24.9	Positive
1	4	410B	Office and Restroom 410B	W4	Plaster	Green	None	0	15.4	Positive
1	4	410B	Office and Restroom 410B	Ceiling	Plaster	Green	None	0	20.6	Positive
1	4	410B	Office and Restroom 410B	Floor	Wood	Unpainted	N/A	N/A	N/A	N/A
1	4	410B	Office and Restroom 410B	Door	Wood	Varnish	None	0	0	Negative
1	4	410B	Office and Restroom 410B	Door Casing	Wood	Varnish	None	0	0.1	Negative
1	4	410B	Office and Restroom 410B	Window Casing	Wood	Varnish	None	0	0.6	Negative
1	4	410B	Office and Restroom 410B	Window Sill	Wood	Varnish	None	0	0.2	Negative
1	4	410B	Office and Restroom 410B	Window Apron	Wood	Varnish	None	0	0.1	Negative
1	4	410B	Office and Restroom 410B	Chair Rail	Wood	Varnish	None	0	0.2	Negative
1	4	410B	Office and Restroom 410B	Baseboard	Wood	Brown	None	0	0.2	Negative
1	4	410B	Office and Restroom 410B	Crown Molding	Wood	Brown	None	0	0.2	Negative
1	4	410	Classroom 410	W1	Plaster	White	Flaking	15	8.8	Positive
1	4	410	Classroom 410	W2	Plaster	White	Efflorescence	70	5.4	Positive
1	4	410	Classroom 410	W3	Plaster	White	Flaking	10	0.1	Negative
1	4	410	Classroom 410	W4	Plaster	White	Efflorescence	15	0.1	Negative
1	4	410	Classroom 410	Ceiling	Plaster	Tan	Flaking	60	16.2	Positive
1	4	410	Classroom 410	Floor	Wood	Unpainted	N/A	N/A	N/A	N/A
1	4	410	Classroom 410	Radiator	Metal	Gray	Flaking	1	1	Positive
1	4	410	Classroom 410	Radiator	Metal	Gray	Flaking	5	3	Positive
1	4	410	Classroom 410	Baseboard	Wood	Brown	None	0	0.1	Negative
1	4	410	Classroom 410	Electrical Panel Door	Metal	White	Flaking	5	0	Negative
1	4	410	Classroom 410	Door	Wood	Varnish	None	0	0	Negative
1	4	410	Classroom 410	Door Casing	Wood	Varnish	None	0	0	Negative
1	4	410	Classroom 410	Window Casing	Wood	Varnish	None	0	0.5	Negative
1	4	410	Classroom 410	Window Sill	Wood	Varnish	None	0	0.1	Negative
1	4	410	Classroom 410	Window Apron	Wood	Varnish	None	0	0.1	Negative
1	4	410A	Classroom 410 Storage Closet	W1	Plaster	White	No Access	No Access	No Access	No Access
1	4	410A	Classroom 410 Storage Closet	W2	Plaster	White	None	0	12.2	Positive
1	4	410A	Classroom 410 Storage Closet	W3	Plaster	White	None	0	8.7	Positive
1	4	410A	Classroom 410 Storage Closet	W4	Plaster	White	None	0	13.7	Positive
1	4	410A	Classroom 410 Storage Closet	Ceiling	Plaster	White	None	0	No Access	No Access
1	4	410A	Classroom 410 Storage Closet	Floor	Wood	Unpainted	N/A	N/A	N/A	N/A
1	4	410A	Classroom 410 Storage Closet	Door	Wood	Varnish	None	0	0	Negative
1	4	410A	Classroom 410 Storage Closet	Door Casing	Wood	Varnish	None	0	0.1	Negative

			Dates: 3/13/2023 to 7/21/2023	Lead-Safe Certification Assessment Report Number: Parkway Center City Middle College						
			Inspector Name and PA License Number: Lawrence Jackson 003683		Pai	rkwav Ce	nter City Mic	dle Colle	ae	
			Inspection Company: USA Environmental				treet, Philad			
	1	1	Management Inc		340 NOI	1131113	ireei, Pilliau	eipilia, P	19123	
E I e m e n t	F I o o	Space #	Onsite Room Name	Component	Substrate Material	Paint Color	Description of Damage	Damage Quantity (sf)	XRF Reading (mg/cm2)	XRF (positive/ negative)
1	4	410A	Classroom 410 Storage Closet	Baseboard	Wood	Brown	None	0	0.2	Negative
1	4	409	Classroom 409	W1	Plaster	Gray	None	0	0.1	Negative
1	4	409	Classroom 409	W2	Plaster	Gray	Efflorescence	10	4.4	Positive
1	4	409	Classroom 409	W3	Plaster	Gray	Cracking	8	8.5	Positive
1	4	409	Classroom 409	W4	Plaster	Gray	Cracking	3	7.9	Positive
1	4	409	Classroom 409	Ceiling	Plaster	Tan	Flaking	75	8.2	Positive
1	4	409	Classroom 409	Floor	Wood	Unpainted	N/A	N/A	N/A	N/A
1	4	409	Classroom 409	Radiator	Metal	Gray	Flaking	5	0	Negative
1	4	409	Classroom 409	Radiator	Metal	Gray	Flaking	5	2.1	Positive
1	4	409	Classroom 409	Drain Pipe	Metal	Gray	None	0	0.1	Negative
1	4	409	Classroom 409	Baseboard	Wood	Brown	None	0	0.1	Negative
1	4	409	Classroom 409	Door	Wood	Varnish	None	0	0	Negative
1	4	409	Classroom 409	Door Casing	Wood	Varnish	None	0	0.3	Negative
1	4	409	Classroom 409	Window Casing	Wood	Varnish	None	0	0.1	Negative
1	4	409	Classroom 409	Window Sill	Wood	Varnish	None	0	0.3	Negative
1	4	409	Classroom 409	Window Apron	Wood	Varnish	None	0	0	Negative
1	4	S43	Stairwell adjacent to Classroom 408	W1	Plaster	Gray	None	0	18.4	Positive
1	4	S43	Stairwell adjacent to Classroom 408	W2	Plaster	Gray	None	0	0.4	Negative
1	4	S43	Stairwell adjacent to Classroom 408	W3	Plaster	Gray	None	0	21.7	Positive
1	4	S43	Stairwell adjacent to Classroom 408	Ceiling	Plaster	Gray	None	0	18.9	Positive
1	4	S43	Stairwell adjacent to Classroom 408	Floor	Concrete	Gray	None	0	0.9	Positive
1	4	S43	Stairwell adjacent to Classroom 408	Door	Metal	Brown	None	0	0	Negative
1	4	S43	Stairwell adjacent to Classroom 408	Door Casing	Metal	Brown	None	0	2.3	Positive
1	4	S43	Stairwell adjacent to Classroom 408	Stair Tread	Concrete	Gray	None	0	0.4	Negative
1	4	S43	Stairwell adjacent to Classroom 408	Stair Riser	Concrete	Gray	None	0	1.8	Positive
1	4	S43	Stairwell adjacent to Classroom 408	Stair Stringer	Concrete	Gray	None	0	3.4	Positive
1	4	S43	Stairwell adjacent to Classroom 408	Radiator	Metal	Gray	None	0	0.6	Negative
1	4	S43	Stairwell adjacent to Classroom 408	Newel Post	Metal	Brown	None	0	7.6	Positive
1	4	S43	Stairwell adjacent to Classroom 408	Spindle	Metal	Gray	None	0	10.2	Positive
1	4	S43	Stairwell adjacent to Classroom 408	Electrical Panel Door	Metal	Gray	None	0	0.1	Negative
1	4	408	Classroom 408	W1	Plaster	Gray	Efflorescence	100	10.6	Positive
1	4	408	Classroom 408	W2	Plaster	Gray	Efflorescence	50	6.5	Positive
1	4	408	Classroom 408	W3	Plaster	Gray	None	0	0	Negative
1	4	408	Classroom 408	W4	Plaster	Gray	Flaking	20	10.2	Positive
1	4	408	Classroom 408	Ceiling	Plaster	Tan	Flaking	50	22.3	Positive
1	4	408	Classroom 408	Floor	Wood	Unpainted	N/A	N/A	N/A	N/A
1	4	408	Classroom 408	Radiator	Metal	Gray	Flaking	10	5.3	Positive

			Dates: 3/13/2023 to 7/21/2023	Lead-Safe Certification Assessment Report						
			Inspector Name and PA License Number: Lawrence Jackson 003683		Paı	rkway Ce	nter City Mic	ddle Colle	ge	
			Inspection Company: USA Environmental Management Inc		540 Nor	th 13th S	treet, Philad	elphia, P	A 19123	
E I e m e n t	F I o o r	Space #	Onsite Room Name	Component	Substrate Material	Paint Color	Description of Damage	Damage Quantity (sf)	XRF Reading (mg/cm2)	XRF (positive/ negative)
1	4	408	Classroom 408	Radiator	Metal	Gray	Flaking	5	1.5	Positive
1	4	408	Classroom 408	Door	Wood	Varnish	None	0	0	Negative
1	4	408	Classroom 408	Door Casing	Wood	Varnish	None	0	0	Negative
1	4	408	Classroom 408	Window Sill	Wood	Varnish	None	0	0.5	Negative
1	4	408	Classroom 408	Window Apron	Wood	Varnish	None	0	0.2	Negative
1	4	408	Classroom 408	Baseboard	Wood	Brown	None	0	0.1	Negative
1	4	408	Classroom 408	Window Casing	Wood	Varnish	None	0	0.3	Negative
1	4	407	Classroom 407	W1	Plaster	Gray	None	0	0.2	Negative
1	4	407	Classroom 407	W2	Plaster	Gray	Efflorescence	50	12.6	Positive
1	4	407	Classroom 407	W3	Plaster	Gray	Flaking	40	0.1	Negative
1	4	407	Classroom 407	W4	Plaster	Gray	Flaking	30	11	Positive
1	4	407	Classroom 407	Ceiling	Plaster	Tan	Flaking	100	24.8	Positive
1	4	407	Classroom 407	Floor	Wood	Unpainted	N/A	N/A	N/A	N/A
1	4	407	Classroom 407	Radiator	Metal	Gray	Flaking	15	3.1	Positive
1	4	407	Classroom 407	Radiator	Metal	Gray	Flaking	10	3.8	Positive
1	4	407	Classroom 407	Door	Wood	Varnish	None	0	0.2	Negative
1	4	407	Classroom 407	Door Casing	Wood	Varnish	None	0	0.1	Negative
1	4	407	Classroom 407	Window Casing	Wood	Varnish	None	0	0.2	Negative
1	4	407	Classroom 407	Window Sill	Wood	Varnish	None	0	0	Negative
1	4	407	Classroom 407	Window Apron	Wood	Varnish	None	0	0.1	Negative
1	4	407	Classroom 407	Baseboard	Wood	Brown	None	0	0.2	Negative
1	4	407A	Service Closet across from Classroom 407	W1	Plaster	White	Cracking	10	14.9	Positive
1	4	407A	Service Closet across from Classroom 407	W2	Plaster	White	Cracking	15	7.8	Positive
1	4	407A	Service Closet across from Classroom 407	W3	Plaster	White	Cracking	15	5.4	Positive
1	4	407A	Service Closet across from Classroom 407	W4	Plaster	White	None	0	5.8	Positive
1	4	407A	Service Closet across from Classroom 407	Ceiling	Plaster	White	No Access	No Access	No Access	No Access
1	4	407A	Service Closet across from Classroom 407	Floor	Concrete	Unpainted	N/A	N/A	N/A	N/A
1	4	407A	Service Closet across from Classroom 407	Door	Wood	Varnish	None	0	0.1	Negative
1	4	407A	Service Closet across from Classroom 407	Door Casing	Wood	Varnish	None	0	0.1	Negative
1	4	407A	Service Closet across from Classroom 407	Drain Pipe	Metal	White	None	0	14.9	Positive
1	4	406A	Teacher's Lounge adjacent to Classroom 407	W1	Plaster	Gray	Cracking	5	0.1	Negative
1	4	406A	Teacher's Lounge adjacent to Classroom 407	W2	Plaster	Gray	Cracking	10	9.4	Positive
1	4	406A	Teacher's Lounge adjacent to Classroom 407	W3	Plaster	Gray	Cracking	10	0.1	Negative
1	4	406A	Teacher's Lounge adjacent to Classroom 407	W4	Plaster	Gray	Cracking	2	0.1	Negative
1	4	406A	Teacher's Lounge adjacent to Classroom 407	Ceiling	Plaster	Tan	Cracking	75	18.7	Positive
1	4	406A	Teacher's Lounge adjacent to Classroom 407	Floor	Wood	Unpainted	N/A	N/A	N/A	N/A
1	4	406A	Teacher's Lounge adjacent to Classroom 407	Radiator	Metal	Gray	Flaking	5	0.1	Negative
1	4	406A 406A	Teacher's Lounge adjacent to Classroom 407	Door	Wood	Varnish	None	0	0.1	Negative
\sqsubseteq	-	400A	reactions buttings adjacent to Classicum 401	1 200	, , , , , , , , , , , , , , , , , , ,	Varriion	140110			racgative

			Dates: 3/13/2023 to 7/21/2023		Lead-S	afe Certi	fication Asse	essment l	Report	
			Inspector Name and PA License Number:		Des	dans Ca	nata n Cita i Mia			
			Lawrence Jackson 003683		Pai	rkway Ce	nter City Mic	iale Colle	ege	
			Inspection Company: USA Environmental Management Inc		540 Nor	th 13th S	treet, Philad	elphia, PA	A 19123	
E I e	F									
m e n	0 0 r	Space #	Onsite Room Name	Component	Substrate Material	Paint Color	Description of Damage	Damage Quantity (sf)	XRF Reading (mg/cm2)	XRF (positive/ negative)
1	4	406A	Teacher's Lounge adjacent to Classroom 407	Door Casing	Wood	Varnish	None	Quantity (SI)	(Hig/CHI2) 0	Negative
1	4	406A	Teacher's Lounge adjacent to Classroom 407	Window Casing	Wood	Varnish	None	0	0.3	Negative
1	4	406A	Teacher's Lounge adjacent to Classroom 407	Window Sill	Wood	Varnish	None	0	0.3	Negative
1	4	406A	Teacher's Lounge adjacent to Classroom 407	Window Apron	Wood	Varnish	None	0	0	Negative
1	4	406A	Teacher's Lounge adjacent to Classroom 407	Baseboard	Wood	Brown	None	0	0	Negative
1	4	406A	Teacher's Lounge adjacent to Classroom 407	Chair Rail	Wood	Varnish	None	0	0.1	Negative
1	4	406B	Teacher's Lounge adjacent to Classroom 407 Closet	W1	Plaster	White	Flaking	30	6.2	Positive
1	4	406B	Teacher's Lounge adjacent to Classroom 407 Closet	W2	Plaster	White	Flaking	50	6.1	Positive
1	4	406B	Teacher's Lounge adjacent to Classroom 407 Closet	W3	Plaster	White	Flaking	10	9.3	Positive
1	4	406B	Teacher's Lounge adjacent to Classroom 407 Closet	W4	Plaster	Tan	No Access	No Access	No Access	No Access
1	4	406B	Teacher's Lounge adjacent to Classroom 407 Closet	Ceiling	Plaster	White	No Access	No Access	No Access	No Access
1	4	406B	Teacher's Lounge adjacent to Classroom 407 Closet	Door	Wood	Brown	None	0	0	Negative
1	4	406B	Teacher's Lounge adjacent to Classroom 407 Closet	Door Casing	Wood	Brown	None	0	0	Negative
1	4	406D	Teacher's Lounge adjacent to Classroom 407 Restroom	W1	Plaster	White	Flaking	10	0.1	Negative
1	4	406D	Teacher's Lounge adjacent to Classroom 407 Restroom	W2	Plaster	White	Flaking	5	6.3	Positive
1	4	406D	Teacher's Lounge adjacent to Classroom 407 Restroom	W3	Plaster	White	Flaking	5	0.1	Negative
1	4	406D	Teacher's Lounge adjacent to Classroom 407 Restroom	W4	Plaster	White	None	0	0.1	Negative
1	4	406D	Teacher's Lounge adjacent to Classroom 407 Restroom	Floor	Concrete	Gray	Friction	5	0	Negative
1	4	406D	Teacher's Lounge adjacent to Classroom 407 Restroom	Ceiling	Plaster	White	None	0	No Access	No Access
1	4	406	Classroom 406	W1	Plaster	White	Flaking	50	9.1	Positive
1	4	406	Classroom 406	W2	Plaster	White	Flaking	60	10.2	Positive
1	4	406	Classroom 406	W3	Sheetrock	White	None	0	0	Negative
1	4	406	Classroom 406	W4	Plaster	White	Flaking	200	9.9	Positive
1	4	406	Classroom 406	Ceiling	Plaster	Tan	Flaking	200	21.1	Positive
1	4	406	Classroom 406	Floor	Wood	Unpainted	N/A	N/A	N/A	N/A
1	4	406	Classroom 406	Radiator	Metal	Gray	Flaking	5	4	Positive
1	4	406	Classroom 406	Radiator	Metal	Gray	Flaking	10	6	Positive
1	4	406	Classroom 406	Door	Wood	Varnish	None	0	0	Negative
1	4	406	Classroom 406	Door Casing	Wood	Varnish	None	0	0.1	Negative
1	4	406	Classroom 406	Window Casing	Wood	Varnish	None	0	0.4	Negative
1	4	406	Classroom 406	Window Aprop	Wood	Varnish	None	0	0.2	Negative
1	4	406	Classroom 406	Window Apron	Wood	Varnish	None	0		Negative
1	4	406	Classroom 406	Baseboard	Wood	Brown	None	1 0	0.1	Negative

		Inspector Name and PA License Number: Lawrence Jackson 003683		Number: Devices Contain Office Minds Contained						
			Parkway Center City Middle College							
		Inspection Company: USA Environmental Management Inc						•		
E	Space #	Onsite Room Name	Component	Substrate Material	Paint Color	Description of Damage	Damage Quantity (sf)	XRF Reading (mg/cm2)	XRF (positive/ negative)	
1 4	406C	Closet across from Classroom 406	W1	Plaster	White	None	0	2.8	Positive	
1 4	406C	Closet across from Classroom 406	W2	Plaster	White	None	0	5.5	Positive	
1 4	406C	Closet across from Classroom 406	W3	Plaster	White	None	0	5.3	Positive	
1 4	406C	Closet across from Classroom 406	W4	Plaster	White	None	0	4.2	Positive	
1 4	406C	Closet across from Classroom 406	Floor	Concrete	Unpainted	N/A	N/A	N/A	N/A	
1 4	406C	Closet across from Classroom 406	Ceiling	Plaster	White	No Access	No Access	No Access	No Access	
1 4	406C	Closet across from Classroom 406	Door	Wood	Varnish	None	0	0.1	Negative	
1 4	406C	Closet across from Classroom 406	Door Casing	Wood	Varnish	None	0	0.2	Negative	
1 4	405	Classroom 405	W1	Plaster	White	Flaking	10	0.2	Negative	
1 4	405	Classroom 405	W2	Plaster	White	Efflorescence	50	8.7	Positive	
1 4	405	Classroom 405	W3	Plaster	White	Cracking	5	8.8	Positive	
1 4	405	Classroom 405	W4	Sheetrock	White	Cracking	6	0	Negative	
1 4	405	Classroom 405	Ceiling	Plaster	Tan	Cracking	50	20.9	Positive	
1 4	405	Classroom 405	Floor	Wood	Unpainted	N/A	N/A	N/A	N/A	
1 4	405	Classroom 405	Radiator	Metal	Gray	Flaking	5	3.5	Positive	
1 4	405	Classroom 405	Radiator	Metal	Gray	Flaking	5	3.5	Positive	
1 4	405	Classroom 405	Door Casing	Metal	Brown	None	0	0.0	Negative	
1 4	405	Classroom 405	Door	Wood	Brown	None	0	0	Negative	
1 4	405	Classroom 405	Baseboard	Wood	Brown	None	0	0.1	Negative	
1 4	405	Classroom 405	Window Casing	Wood	Varnish	None	0	0.4	Negative	
1 4	405	Classroom 405	Window Sill	Wood	Varnish	None	0	0.3	Negative	
1 4	405	Classroom 405	Window Apron	Wood	Varnish	None	0	0.1	Negative	
1 4	405A	Classroom 405 Copy Room	W1	Sheetrock	White	None	0	0	Negative	
1 4	405A	Classroom 405 Copy Room	W2	Plaster	White	Efflorescence	30	5.8	Positive	
1 4	405A	Classroom 405 Copy Room	W3	Sheetrock	White	None	0	0	Negative	
1 4	405A	Classroom 405 Copy Room	W4	Sheetrock	White	None	0	0	Negative	
1 4	405A	Classroom 405 Copy Room	Floor	Wood	Unpainted	N/A	N/A	N/A	N/A	
1 4	405A	Classroom 405 Copy Room	Ceiling	Plaster	Tan	Flaking	50	19.6	Positive	
1 4	405A	Classroom 405 Copy Room	Door	Wood	Varnish	None	0	0	Negative	
1 4	405A	Classroom 405 Copy Room	Door Casing	Metal	Brown	None	0	0	Negative	
1 4	405A	Classroom 405 Copy Room	Window Casing	Wood	Varnish	None	0	0.4	Negative	
1 4	405A	Classroom 405 Copy Room	Window Sill	Wood	Varnish	None	0	0.2	Negative	
1 4	405A	Classroom 405 Copy Room	Window Apron	Wood	Varnish	None	0	0.2	Negative	
1 4	405A	Classroom 405 Copy Room	Baseboard	Wood	Brown	None	0	0	Negative	
1 4	405B	Classroom 405 Vestibule	W1	Sheetrock	White	None	0	0	Negative	
1 4	405B	Classroom 405 Vestibule	W2	Sheetrock	White	None	0	0	Negative	
1 4	405B	Classroom 405 Vestibule	W3	Sheetrock	White	None	0	0	Negative	
1 4	405B	Classroom 405 Vestibule	W4	Plaster	White	Cracking	20	10.1	Positive	

			Dates: 3/13/2023 to 7/21/2023							
			Inspector Name and PA License Number:		Da	d O -		Jalla Oalla		
			Lawrence Jackson 003683		Par	rkway ce	nter City Mic	iale Colle	ege	
			Inspection Company: USA Environmental Management Inc		540 Nor	th 13th S	treet, Philad	elphia, P	A 19123	
E I e	F						·			
m e n	0						Description of	Damage	XRF Reading	XRF (positive/
t	r	Space #	Onsite Room Name	Component	Substrate Material	Paint Color	Damage .	Quantity (sf)	(mg/cm2)	negative)
1	4	405B	Classroom 405 Vestibule	Ceiling	Plaster	Tan	Cracking	10	17.4	Positive
1	4	405B	Classroom 405 Vestibule	Floor	Wood	Unpainted	N/A	N/A	N/A	N/A
1	4	405B	Classroom 405 Vestibule	Door	Wood	Varnish	None	0	0	Negative
1	4	405B	Classroom 405 Vestibule	Door Casing	Wood	Varnish	None	0	0.1	Negative
1	4	405B	Classroom 405 Vestibule	Baseboard	Wood	Brown	None	0	0	Negative
1	4	S44	Stairwell adjacent to Classroom 405	W1	Plaster	White	None	0	9	Positive
1	4	S44	Stairwell adjacent to Classroom 405	W2	Plaster	White	None	0	2.8	Positive
1	4	S44	Stairwell adjacent to Classroom 405	W3	Plaster	White	None	0	12.7	Positive
1	4	S44	Stairwell adjacent to Classroom 405	Stair Tread	Concrete	Gray	None	0	0.1	Negative
1	4	S44	Stairwell adjacent to Classroom 405	Stair Riser	Concrete	Gray	None	0	0.9	Positive
1	4	S44	Stairwell adjacent to Classroom 405	Stair Stringer	Concrete	Gray	None	0	1.7	Positive
1	4	404	Classroom 404	W1	Plaster	Gray	None	0	9	Positive
1	4	404	Classroom 404	W2	Plaster	Gray	Flaking	10	0	Negative
1	4	404	Classroom 404	W3	Plaster	Gray	None	0	7	Positive
1	4	404	Classroom 404	W4	Plaster	Gray	None	0	8.6	Positive
1	4	404	Classroom 404	Ceiling	Plaster	Tan	None	0	11.3	Positive
1	4	404	Classroom 404	Floor	Wood	Unpainted	N/A	N/A	N/A	N/A
1	4	404	Classroom 404	Radiator	Metal	Gray	Flaking	3	2.6	Positive
1	4	404	Classroom 404	Radiator	Metal	Gray	Flaking	10	5.1	Positive
1	4	404	Classroom 404	Baseboard	Wood	Brown	None	0	0.1	Negative
1	4	404	Classroom 404	Door	Wood	Varnish	None	0	0	Negative
1	4	404	Classroom 404	Door Casing	Wood	Varnish	None	0	0.1	Negative
1	4	404	Classroom 404	Window Casing	Wood	Varnish	None	0	0.4	Negative
1	4	404	Classroom 404	Window Sill	Wood	Varnish	None	0	0.2	Negative
1	4	404	Classroom 404	Window Apron	Wood	Varnish	None	0	0.1	Negative
1	4	403	Classroom 403	W1	Plaster	Gray	Flaking	3	9.1	Positive
1	4	403	Classroom 403	W2	Plaster	Gray	Flaking	15	7	Positive
1	4	403	Classroom 403	W3	Plaster	Gray	Flaking	5	5.1	Positive
1	4	403	Classroom 403	W4	Plaster	Gray	Flaking	5	7.1	Positive
1	4	403	Classroom 403	Ceiling	Plaster	Tan	Cracking	75	11.4	Positive
1	4	403	Classroom 403	Floor	Wood	Unpainted	N/A	N/A	N/A	N/A
1	4	403	Classroom 403	Radiator	Metal	Gray	Flaking	3	3.8	Positive
1	4	403	Classroom 403	Radiator	Metal	Gray	Flaking	3	4	Positive
1	4	403	Classroom 403	Door	Wood	Varnish	None	0	0	Negative
1	4	403	Classroom 403	Door Casing	Wood	Varnish	None	0	0.1	Negative
1	4	403	Classroom 403	Window Casing	Wood	Varnish	None	0	0.4	Negative
1	4	403	Classroom 403	Window Sill	Wood	Varnish	None	0	0.3	Negative
1	4	403	Classroom 403	Window Apron	Wood	Varnish	None	0	0.1	Negative

			Dates: 3/13/2023 to 7/21/2023		Lead-S	afe Certi	fication Asse	essment l	Report	
			Inspector Name and PA License Number:		Do	dans Ca				
			Lawrence Jackson 003683		Pai	rkway Ce	nter City Mid	iale Colle	ge	
			Inspection Company: USA Environmental		E 40 No.	4h 404h 0	treet Dhiled	alabia Di	10400	
			Management Inc		540 NOr	tn 13tn 5	treet, Philade	eipnia, P	19123	
l E										
	F									
e m	[
e	0									XRF
n	0						Description of	Damage	XRF Reading	(positive/
t	r	Space #	Onsite Room Name	Component	Substrate Material	Paint Color	Damage	Quantity (sf)	(mg/cm2)	negative)
1	4	403	Classroom 403	Baseboard	Wood	Brown	None	0	0.2	Negative
1	4	402	Classroom 402	W1	Plaster	Gray	Flaking	10	0.2	Negative
1	4	402	Classroom 402	W2	Plaster	Gray	Cracking	15	7	Positive
1	4	402	Classroom 402	W3 W4	Plaster Plaster	Gray Gray	Cracking Cracking	10 4	0.1 8.1	Negative Positive
1	4	402 402	Classroom 402 Classroom 402	Ceiling	Plaster	Tan	Flaking	50	11.3	Positive
1	4	402	Classroom 402 Classroom 402	Floor	Wood	Unpainted	N/A	N/A	N/A	N/A
1	4	402	Classroom 402	Radiator	Metal	Gray	Flaking	5	5.3	Positive
1	4	402	Classroom 402	Radiator	Metal	Gray	Flaking	3	4.5	Positive
1	4	402	Classroom 402	Baseboard	Wood	Brown	None	0	0	Negative
1	4	402	Classroom 402	Door	Wood	Varnish	None	0	0.1	Negative
1	4	402	Classroom 402	Door Casing	Wood	Brown	None	0	0.2	Negative
1	4	402	Classroom 402	Window Casing	Wood	Brown	None	0	0.2	Negative
1	4	402	Classroom 402	Window Sill	Wood	Brown	None	0	0.4	Negative
1	4	402	Classroom 402	Window Apron	Wood	Brown	None	0	0.1	Negative
1	4	S46	Fire Tower adjacent to Classroom 402	W1	Brick	White	None	0	3.6	Positive
1	4	S46	Fire Tower adjacent to Classroom 402	W2	Brick	White	None	0	3.7	Positive
1	4	S46	Fire Tower adjacent to Classroom 402	W3	Brick	White	None	0	4.1	Positive
1	4	S46	Fire Tower adjacent to Classroom 402	W4	Brick	White	None	0	4.2	Positive
1	4	S46	Fire Tower adjacent to Classroom 402	Ceiling	Concrete	White	Flaking	5	7.3	Positive
1	4	S46	Fire Tower adjacent to Classroom 402	Floor	Concrete	Gray	None	0	1	Positive
1	4	S46	Fire Tower adjacent to Classroom 402	Security Gate	Metal	Brown	Flaking	120	3.6	Positive
1	4	S46	Fire Tower adjacent to Classroom 402	Drain Pipe	Metal	Brown	Flaking	24	22.6	Positive
1	4	401	Classroom 401	W1	Plaster	Gray	Efflorescence	20	9.6	Positive
1	4	401	Classroom 401	W2	Plaster	Gray	Cracking	20 25	0.1	Negative
1	4	401	Classroom 401	W3 W4	Plaster	Gray	Cracking	25 5	9.2 8.8	Positive
1	4	401	Classroom 401	Ceiling	Plaster Plaster	Gray Tan	Cracking Flaking	50	10.6	Positive Positive
1	4	401 401	Classroom 401 Classroom 401	Floor	9 x 9 floor tile	Unpainted	N/A	N/A	10.6 N/A	N/A
1	4	401A	Classroom 401 Pipe Chase	Door	Wood	Varnish	None	0	0.1	Negative
1	4	401A 401A	Classroom 401 Pipe Chase	Door Casing	Wood	Varnish	None	0	0.1	Negative
1	4	401A 401A	Classroom 401 Pipe Chase	W1	Plaster	White	Moisture Damage	160	2.8	Positive
1	4	401A	Classroom 401 Pipe Chase	W2	Terracotta	Unpainted	N/A	N/A	N/A	N/A
1	4	401A	Classroom 401 Pipe Chase	W3	Terracotta	Unpainted	N/A	N/A	N/A	N/A
1	4	401A	Classroom 401 Pipe Chase	W4	Terracotta	Unpainted	N/A	N/A	N/A	N/A
1	4	401A	Classroom 401 Pipe Chase	Floor	Concrete	Unpainted	N/A	N/A	N/A	N/A
1	4	401A	Classroom 401 Pipe Chase	Ceiling	Concrete	White	Flaking	30	18.9	Positive
1	4	413	Boy's Restroom adjacent to Classroom 401	W1	Plaster	White	Flaking	2	5.6	Positive

			Dates: 3/13/2023 to 7/21/2023		Lead-S	afe Certi	fication Asse	essment l	Report	
			Inspector Name and PA License Number:		D.s.	-l	4 O!4 NA!			
			Lawrence Jackson 003683		Pai	rkway Ce	nter City Mid	iale Colle	ge	
			Inspection Company: USA Environmental Management Inc		540 Nor	th 13th S	treet, Philad	elphia, PA	A 19123	
E I	_						·			
e m e	F I o									XRF
n t	o r	Space #	Onsite Room Name	Component	Substrate Material	Paint Color	Description of Damage	Damage Quantity (sf)	XRF Reading (mg/cm2)	(positive/ negative)
1	4	413	Boy's Restroom adjacent to Classroom 401	Ŵ2	Plaster	White	Flaking	4	4.8	Positive
1	4	413	Boy's Restroom adjacent to Classroom 401	W3	Plaster	White	Flaking	20	0.8	Positive
1	4	413	Boy's Restroom adjacent to Classroom 401	W4	Plaster	White	Chipping	10	4.8	Positive
1	4	413	Boy's Restroom adjacent to Classroom 401	Ceiling	Concrete	White	Cracking	20	7.4	Positive
1	4	413	Boy's Restroom adjacent to Classroom 401	Floor	Concrete	Gray	None	0	0	Negative
1	4	413	Boy's Restroom adjacent to Classroom 401	Radiator	Metal	Gray	Flaking	5	2	Positive
1	4	413A	Pipe Chase in Boy's Restroom adjacent to Classroom 401	Door	Wood	Brown	Chipping	1	0	Negative
1	4	413A	Pipe Chase in Boy's Restroom adjacent to Classroom 401	Door Casing	Wood	Brown	Chipping	1	0	Negative
1	4	413A	Pipe Chase in Boy's Restroom adjacent to Classroom 401	W1	Concrete	Unpainted	N/A	N/A	N/A	N/A
1	4	413A	Pipe Chase in Boy's Restroom adjacent to Classroom 401	W2	Concrete	Unpainted	N/A	N/A	N/A	N/A
1	4	413A	Pipe Chase in Boy's Restroom adjacent to Classroom 401	W3	Concrete	Unpainted	N/A	N/A	N/A	N/A
1	4	413A	Pipe Chase in Boy's Restroom adjacent to Classroom 401	W4	Concrete	Unpainted	N/A	N/A	N/A	N/A
1	4	413B	Pipe Shaft adjacent to 4th Floor Boy's Restroom	W1	Brick	White	None	0	0	Negative
1	4	413B	Pipe Shaft adjacent to 4th Floor Boy's Restroom	W2	Brick	White	None	0	0	Negative
1	4	413B	Pipe Shaft adjacent to 4th Floor Boy's Restroom	W3	Brick	White	None	0	0	Negative
1	4	413B	Pipe Shaft adjacent to 4th Floor Boy's Restroom	Door	Wood	Varnish	None	0	0	Negative
1	4	413B	Pipe Shaft adjacent to 4th Floor Boy's Restroom	Door Casing	Wood	Varnish	None	0	0	Negative
1	4	H41A	Hallway outside 4th Floor Boy's Restroom	W1	Plaster	Gray	Cracking	2	9.9	Positive
1	4	H41A	Hallway outside 4th Floor Boy's Restroom	W2	Plaster	Gray	Flaking	1	0	Negative
1	4	H41A	Hallway outside 4th Floor Boy's Restroom	W3	Plaster	Gray	Flaking	10	6.6	Positive
1	4	H41A	Hallway outside 4th Floor Boy's Restroom	W4	Plaster	Gray	None	0	4.8	Positive
1	4	H41A	Hallway outside 4th Floor Boy's Restroom	Floor	Concrete	Gray	None	0	0.1	Negative
1	4	H41A	Hallway outside 4th Floor Boy's Restroom	Ceiling	Plaster	Tan	None	0	9.6	Positive
1	4	H41A	Hallway outside 4th Floor Boy's Restroom	Stair Tread	Concrete	Gray	None	0	2.9	Positive
1	4	H41	Hallway outside Classrooms 401 to 404	W1	Plaster	Gray	Flaking	6	4.6	Positive
1	4	H41	Hallway outside Classrooms 401 to 404	W2	Plaster	Gray	None	0	9.4	Positive
1	4	H41	Hallway outside Classrooms 401 to 404	W3	Plaster	Gray	None	0	10.2	Positive
1	4	H41	Hallway outside Classrooms 401 to 404	W4	Plaster	Gray	None	0 40	0.4	Negative
1	4	H41	Hallway outside Classrooms 401 to 404	Ceiling Floor	Plaster	Tan	Efflorescence		10.7	Positive
1	4	H41 H41	Hallway outside Classrooms 401 to 404	Lockers	Concrete Metal	Gray Blue	None None	0	0.2	Negative Negative
1	4	H41PCS	Hallway outside Classrooms 401 to 404	Door	Wood	Varnish	None	0	0.2	Negative
1	4	H41PCS H41PCS	Pipe/Cable Shaft in Hallway next to Classroom 402 Pipe/Cable Shaft in Hallway next to Classroom 402	Door Casing	Wood	Varnish	None	0	0.2	Negative
	4	<u>П41РСЭ</u>	Tribe/Cable Shall in Hallway flext to Classroom 402	L Door Casing	vvoou	varriisti	NULLE		U.Z	inegalive

			Dates: 3/13/2023 to 7/21/2023		Lead-S	afe Certi	fication Asse	essment l	Report	
			Inspector Name and PA License Number:		Pai	rkway Co	nter City Mid	Idla Calla	.00	
			Lawrence Jackson 003683		rai	kway Ce	inter City wild	idle Colle	ge	
			Inspection Company: USA Environmental Management Inc		540 Nor	th 13th S	treet, Philad	elphia, PA	A 19123	
E I e m e n	F I o						Description of	Damage	XRF Reading	XRF (positive/
t	r	Space #	Onsite Room Name	Component	Substrate Material	Paint Color	Damage	Quantity (sf)	(mg/cm2)	negative)
1	4	H41PCS	Pipe/Cable Shaft in Hallway next to Classroom 402	W1	Terracotta	Unpainted	N/A	N/A	N/A	N/A
1	4	H41PCS H41PCS	Pipe/Cable Shaft in Hallway next to Classroom 402	W2 W3	Terracotta Terracotta	Unpainted Unpainted	N/A N/A	N/A N/A	N/A N/A	N/A N/A
1	4	H41PCS	Pipe/Cable Shaft in Hallway next to Classroom 402 Pipe/Cable Shaft in Hallway next to Classroom 402	W4	No Access	No Access	No Access	No Access	No Access	No Access
1	4	H43	Hallway outside Classrooms 405 to 408	W1	Plaster	Gray	None	0	8.8	Positive
1	4	H43	Hallway outside Classrooms 405 to 408	W2	Plaster	Gray	None	0	11.2	Positive
1	4	H43	Hallway outside Classrooms 405 to 408	W3	Plaster	Gray	None	0	11.2	Positive
1	4	H43	Hallway outside Classrooms 405 to 408	W4	Plaster	Gray	None	0	8.6	Positive
1	4	H43	Hallway outside Classrooms 405 to 408	Ceiling	Plaster	Tan	Flaking	200	18.5	Positive
1	4	H43	Hallway outside Classrooms 405 to 408	Floor	Concrete	Gray	None	0	0	Negative
1	4	H43PCS1	Pipe/Cable Shaft in Hallway next to Stairwell by Classroom 405	Door	Wood	Varnish	None	0	0.1	Negative
1	4	H43PCS1	Pipe/Cable Shaft in Hallway next to Stairwell by Classroom 405	Door Casing	Wood	Varnish	None	0	0.2	Negative
1	4	H43PCS1	Pipe/Cable Shaft in Hallway next to Stairwell by Classroom 405	W1	No Access	No Access	No Access	No Access	No Access	No Access
1	4	H43PCS1	Pipe/Cable Shaft in Hallway next to Stairwell by Classroom 405	W2	No Access	No Access	No Access	No Access	No Access	No Access
1	4	H43PCS1	Pipe/Cable Shaft in Hallway next to Stairwell by Classroom 405	W3	No Access	No Access	No Access	No Access	No Access	No Access
1	4	H43PCS1	Pipe/Cable Shaft in Hallway next to Stairwell by Classroom 405	W4	No Access	No Access	No Access	No Access	No Access	No Access
1	4	H43PCS2	Pipe/Cable Shaft in Hallway above Hydration Station near Classroom 405	Door	Wood	Varnish	None	0	0.1	Negative
1	4	H43PCS2	Pipe/Cable Shaft in Hallway above Hydration Station near Classroom 405	Door Casing	Wood	Varnish	None	0	0.1	Negative
1	4	H43PCS2	Pipe/Cable Shaft in Hallway above Hydration Station near Classroom 405	No Access	No Access	No Access	No Access	No Access	No Access	No Access
1	4	H43PCS2	Pipe/Cable Shaft in Hallway above Hydration Station near Classroom 405 Pipe/Cable Shaft in Hallway above Hydration Station	No Access	No Access	No Access	No Access	No Access	No Access	No Access
1	4	H43PCS2	near Classroom 405 Pipe/Cable Shaft in Hallway above Hydration Station	No Access	No Access	No Access	No Access	No Access	No Access	No Access
1	4	H43PCS2	near Classroom 405 Pipe/Cable Shaft in Hallway next to Stairwell by	No Access	No Access	No Access	No Access	No Access	No Access	No Access
1	4	H43PCS3	Classroom 408 Pipe/Cable Shaft in Hallway next to Stairwell by	Door	Wood	Varnish	None	0	0.1	Negative
1	4	H43PCS3	Classroom 408	Door Casing	Wood	Varnish	None	0	0.1	Negative
1	4	H43PCS3	Pipe/Cable Shaft in Hallway next to Stairwell by Classroom 408	W1	No Access	No Access	No Access	No Access	No Access	No Access

			Dates: 3/13/2023 to 7/21/2023		Lead-S	afe Certi	fication Asse	essment l	Report	
			Inspector Name and PA License Number:				4 014 14			
			Lawrence Jackson 003683		Pai	rkway Ce	nter City Mic	idie Colle	ege	
			Inspection Company: USA Environmental		- 40 11					
			Management Inc		540 Nor	th 13th S	treet, Philad	elphia, P <i>l</i>	A 19123	
Е										
	l _									
е	F									
m e	I 0									XRF
n	0						Description of	Damage	XRF Reading	(positive/
t	r	Space #	Onsite Room Name	Component	Substrate Material	Paint Color	Damage	Quantity (sf)	(mg/cm2)	negative)
			Pipe/Cable Shaft in Hallway next to Stairwell by	W2	No Access	No Access	No Access	No Access	No Access	No Access
1	4	H43PCS3	Classroom 408	***	1407100033	1407100033	1407100035	1407100033	1407100000	1407100033
	١,	11400000	Pipe/Cable Shaft in Hallway next to Stairwell by	W3	No Access	No Access	No Access	No Access	No Access	No Access
1	4	H43PCS3	Classroom 408							
1	4	H43PCS3	Pipe/Cable Shaft in Hallway next to Stairwell by Classroom 408	W4	No Access	No Access	No Access	No Access	No Access	No Access
1	4	H42	Hallway outside Classrooms 409 to 411	W1	Plaster	Gray	None	0	25.8	Positive
1	4	H42	Hallway outside Classrooms 409 to 411	W2	Plaster	Gray	None	0	18.9	Positive
1	4	H42	Hallway outside Classrooms 409 to 411	W3	Plaster	Gray	Cracking	1	21	Positive
1	4	H42	Hallway outside Classrooms 409 to 411	W4	Plaster	Gray	None	0	14.9	Positive
1	4	H42	Hallway outside Classrooms 409 to 411	Ceiling	Plaster	Tan	Flaking	100	17	Positive
1	4	H42	Hallway outside Classrooms 409 to 411	Floor	Concrete	Gray	None	0	1.7	Positive
1	4	H42	Hallway outside Classrooms 409 to 411	Radiator	Metal	Gray	Flaking	5	1.7	Positive
1	4	H42	Hallway outside Classrooms 409 to 411	Radiator	Metal	Gray	Flaking	5	2	Positive
1	4	H42	Hallway outside Classrooms 409 to 411	Radiator	Metal	Gray	Flaking	5	3.2	Positive
1	4	H42	Hallway outside Classrooms 409 to 411	Lockers	Metal	Blue	None	0	0.4	Negative
1	4	H42PCS	Pipe/Cable Shaft in Hallway next to Classroom 409	Door	Wood	Varnish	None	0	0	Negative
1	4	H42PCS	Pipe/Cable Shaft in Hallway next to Classroom 409	Door Casing	Wood	Varnish	None	0	0	Negative
1	4	H42PCS	Pipe/Cable Shaft in Hallway next to Classroom 409	W1	Brick	Unpainted	N/A	N/A	N/A	N/A
1	4	H42PCS	Pipe/Cable Shaft in Hallway next to Classroom 409	W2	Brick	Unpainted	N/A	N/A	N/A	N/A
1	4	H42PCS	Pipe/Cable Shaft in Hallway next to Classroom 409	W3	Brick	Unpainted	N/A	N/A	N/A	N/A
1	4	H42PCS	Pipe/Cable Shaft in Hallway next to Classroom 409	W4	No Access	No Access	No Access	No Access	No Access	No Access
1	4	H42A	Hallway outside 4th Floor Girl's Restroom	W1	Plaster	Gray	None	0	16.2	Positive
1	4	H42A	Hallway outside 4th Floor Girl's Restroom	W2	Plaster	Gray	None	0	7.6	Positive
1	4	H42A	Hallway outside 4th Floor Girl's Restroom	W3	Plaster	Gray	None	0	17.6	Positive
1	4	H42A	Hallway outside 4th Floor Girl's Restroom	W4	Plaster	Gray	None	0	16.5	Positive
1	4	H42A	Hallway outside 4th Floor Girl's Restroom	Ceiling Floor	Plaster	Tan	Flaking	15 0	19.6	Positive
1	4	H42A	Hallway outside 4th Floor Girl's Restroom		Concrete	Gray Pink	None	0	1.2	Positive
1	4	H42A	Hallway outside 4th Floor Girl's Restroom	Elevator Door Elevator Door	Metal		None	-	0.1	Negative
1	4	H42A	Hallway outside 4th Floor Girl's Restroom	Frame	Metal	Pink	None	0	0	Negative
1	4	H42A	Hallway outside 4th Floor Girl's Restroom	Stair Tread	Concrete	Gray	None	0	0.4	Negative
1	4	H42A	Hallway outside 4th Floor Girl's Restroom	Stair Riser	Concrete	Gray	None	0	4.4	Positive
1	4	H42A	Hallway outside 4th Floor Girl's Restroom	Stair Stringer	Concrete	Gray	None	0	1.3	Positive
1	3	313B	Pipe Shaft adjacent to 3rd Floor Boy's Restroom	No Access	No Access	No Access	No Access	No Access	No Access	No Access
1	3	313B	Pipe Shaft adjacent to 3rd Floor Boy's Restroom	No Access	No Access	No Access	No Access	No Access	No Access	No Access
1	3	313B	Pipe Shaft adjacent to 3rd Floor Boy's Restroom	No Access	No Access No Access	No Access No Access	No Access	No Access No Access	No Access	No Access
1	3	313B	Pipe Shaft adjacent to 3rd Floor Boy's Restroom	No Access			No Access		No Access	No Access
1	3	313B	Pipe Shaft adjacent to 3rd Floor Boy's Restroom	No Access	No Access	No Access	No Access	No Access	No Access	No Access

			Dates: 3/13/2023 to 7/21/2023		Lead-S	afe Certi	fication Asso	essment l	Report	
			Inspector Name and PA License Number:		Do	dansa Ca	otor City Mi			
			Lawrence Jackson 003683		Par	kway ce	nter City Mic	adie Colle	ege	
			Inspection Company: USA Environmental Management Inc		540 Nor	th 13th S	treet, Philad	elphia, PA	A 19123	
E I e m	F									
e n t	o o r	Space #	Onsite Room Name	Component	Substrate Material	Paint Color	Description of Damage	Damage Quantity (sf)	XRF Reading (mg/cm2)	XRF (positive/ negative)
1	3	313B	Pipe Shaft adjacent to 3rd Floor Boy's Restroom	No Access	No Access	No Access	No Access	No Access	No Access	No Access
1	3	313	Boy's Restroom adjacent to Classroom 301	Ceiling	Concrete	White	Cracking	5	0	Negative
1	3	313	Boy's Restroom adjacent to Classroom 301	W1	Plaster	White	Cracking	8	15.3	Positive
1	3	313	Boy's Restroom adjacent to Classroom 301	W2	Plaster	White	Cracking	5	6	Positive
1	3	313	Boy's Restroom adjacent to Classroom 301	W3	Plaster	White	Cracking	10	1	Positive
1	3	313	Boy's Restroom adjacent to Classroom 301	W4	Plaster	White	Cracking	10	17.7	Positive
1	3	313	Boy's Restroom adjacent to Classroom 301	Door	Wood	Brown	None	0	0	Negative
1	3	313	Boy's Restroom adjacent to Classroom 301	Door Frame	Wood	Brown	None	0	0	Negative
1	3	313	Boy's Restroom adjacent to Classroom 301	Window Casing	Wood	Brown	None	0	0.3	Negative
1	3	313	Boy's Restroom adjacent to Classroom 301	Radiator	Metal	Gray	Flaking	10	0	Negative
1	3	313	Boy's Restroom adjacent to Classroom 301	Floor	Concrete	Gray	None	0	0	Negative
1	3	313	Boy's Restroom adjacent to Classroom 301	Drain Pipe	Metal	Brown	Flaking	12	0.8	Positive
1	3	313A	Pipe Chase in Boy's Restroom adjacent to Classroom 301	W1	Concrete	Unpainted	N/A	N/A	N/A	N/A
1	3	313A	Pipe Chase in Boy's Restroom adjacent to Classroom 301	W2	Concrete	Unpainted	N/A	N/A	N/A	N/A
1	3	313A	Pipe Chase in Boy's Restroom adjacent to Classroom 301	W3	Concrete	Unpainted	N/A	N/A	N/A	N/A
1	3	313A	Pipe Chase in Boy's Restroom adjacent to Classroom 301	W4	Concrete	Unpainted	N/A	N/A	N/A	N/A
1	3	313A	Pipe Chase in Boy's Restroom adjacent to Classroom 301	Door	Wood	Varnish	None	0	0	Negative
1	3	313A	Pipe Chase in Boy's Restroom adjacent to Classroom 301	Door Frame	Wood	Varnish	None	0	0	Negative
1	3	301	Classroom 301	Ceiling	Plaster	Tan	Cracking	20	16.4	Positive
1	3	301	Classroom 301	W1	Plaster	Gray	None	0	19.7	Positive
1	3	301	Classroom 301	W2	Plaster	Gray	Peeling	10	13.4	Positive
1	3	301	Classroom 301	W3	Plaster	Gray	None	0	16.6	Positive
1	3	301	Classroom 301	W4	Plaster	Gray	None	0	16.1	Positive
1	3	301	Classroom 301	Door	Wood	Varnish	None	0	0	Negative
1	3	301	Classroom 301	Door Frame	Wood	Varnish	None	0	0.1	Negative
1	3	301	Classroom 301	Floor	9 x 9 floor tile	Unpainted	N/A	N/A	N/A	N/A
1	3	301	Classroom 301	Window Casing	Wood	Varnish	None	N/A	0.3	Negative
1	3	301	Classroom 301	Window Sill	Wood	Varnish	None	N/A	0.1	Negative
1	3	301	Classroom 301	Window Apron	Wood	Varnish	None	N/A	0.2	Negative
1	3	301	Classroom 301	Radiator	Metal	Gray	Flaking	5	6.3	Positive
1	3	301	Classroom 301	Radiator	Metal	Gray	Flaking	3	0	Negative
1	3	301	Classroom 301	Radiator	Metal	Gray	Flaking	10	5.5	Positive
1	3	301B	Classroom 301 Pipe Chase	W1	Plaster	White	Cracking	8	10	Positive

			Dates: 3/13/2023 to 7/21/2023		Lead-S	afe Certi	fication Asse	essment l	Report	
			Inspector Name and PA License Number:		D	.1	4 O'4 M'-	1-11- 0-11-		
			Lawrence Jackson 003683		Pai	rkway Ce	nter City Mic	iale Colle	ge	
			Inspection Company: USA Environmental		5 40 N	40 0			10100	
			Management Inc		540 Nor	tn 13tn S	treet, Philad	eipnia, P	4 19123	
E										
!	_									
e m	F									
e	6									XRF
n	0						Description of	Damage	XRF Reading	(positive/
t	r	Space #	Onsite Room Name	Component	Substrate Material	Paint Color	Damage	Quantity (sf)	(mg/cm2)	negative)
1	3	301B	Classroom 301 Pipe Chase	W2	Terracotta	Unpainted	N/A	N/A	N/A	N/A
1	3	301B	Classroom 301 Pipe Chase	W3	Terracotta	Unpainted	N/A	N/A	N/A	N/A
1	3	301B	Classroom 301 Pipe Chase	W4	Terracotta	Unpainted	N/A	N/A	N/A	N/A
1	3	301B	Classroom 301 Pipe Chase	Door	Wood	Varnish	None	0	0	Negative
1	3	301B	Classroom 301 Pipe Chase	Door Frame	Wood	Varnish	None	0	0	Negative
1	3	S36	Fire Tower adjacent to Classroom 302	W1 W2	Brick	White	None	0	7.4	Positive
1	3	S36 S36	Fire Tower adjacent to Classroom 302	W2 W3	Brick Brick	White White	None None	0	6.7 8.7	Positive Positive
1	3	S36 S36	Fire Tower adjacent to Classroom 302 Fire Tower adjacent to Classroom 302	W4	Brick	White	None	0	5.1	Positive
1	3	S36	Fire Tower adjacent to Classroom 302	Ceiling	Concrete	White	None	0	9	Positive
1	3	S36	Fire Tower adjacent to Classroom 302	Floor	Concrete	Gray	None	0	1.4	Positive
1	3	S36	Fire Tower adjacent to Classroom 302	Door	Metal	Brown	None	0	0.2	Negative
1	3	S36	Fire Tower adjacent to Classroom 302	Door Frame	Metal	Brown	None	0	0.5	Negative
1	3	S36	Fire Tower adjacent to Classroom 302	Drain Pipe	Metal	Brown	Flaking	12	0.5	Positive
1	3	S36	Fire Tower adjacent to Classroom 302	Security Gate	Metal	Brown	Flaking	40	0.1	Negative
1	3	S36	Fire Tower adjacent to Classroom 302	Handrail	Metal	Brown	None	10	0.8	Positive
1	3	S36	Fire Tower adjacent to Classroom 302	Stair Riser	Concrete	Gray	None	0	1	Positive
1	3	S36	Fire Tower adjacent to Classroom 302	Stair Tread	Concrete	Gray	None	0	0.3	Negative
1	3	S36	Fire Tower adjacent to Classroom 302	Stair Stringer	Concrete	Gray	None	0	2.4	Positive
1	3	302A	Office 301A	W1	Plaster	Blue	Flaking	3	0	Negative
1	3	302A	Office 301A	W2	Plaster	Blue	Flaking	10	9.2	Positive
1	3	302A	Office 301A	W3	Plaster	Blue	Flaking	6	0.1	Negative
1	3	302A	Office 301A	W4	Plaster	Blue	Flaking	4	0.1	Negative
1	3	302A	Office 301A	Ceiling	Plaster	Tan	Flaking	100	19.2	Positive
1	3	302A	Office 301A	Radiator	Metal	Gray	Flaking	10	4.1	Positive
1	3	302A	Office 301A	Door	Wood	Varnish	None	0	0.1	Negative
1	3	302A	Office 301A	Door Frame	Wood	Varnish	None	0	0.1	Negative
1	3	302A	Office 301A	Window Casing	Wood	Varnish	None	0	0.6	Negative
1	3	302A	Office 301A	Window Sill	Wood	Varnish	None	0	0.3	Negative
1	3	302A	Office 301A	Window Apron	Wood	Varnish	None	0	0.1	Negative
1	3	302	Classroom 302	W1	Plaster	White	Flaking	1	13.8	Positive
1	3	302	Classroom 302	W2	Plaster	White	Flaking	20	11.8	Positive
1	3	302	Classroom 302	W3	Plaster	White	Flaking	20	0	Negative
1	3	302	Classroom 302	W4	Plaster	White	Flaking	10 400	14.4	Positive
1	3	302	Classroom 302	Ceiling Floor	Plaster Wood	Tan Unpainted	Flaking N/A	400 N/A	23.5 N/A	Positive N/A
1	3	302 302	Classroom 302 Classroom 302	Door	Wood	Varnish	N/A None	N/A 0	N/A 0	Negative
1	3	302		Door Frame	Wood	Varnish	None	0	0.1	Negative
1	3	302	Classroom 302	DOOL FLAILIE	vvoou	varriisii	None	U	U. I	ivegative

			Dates: 3/13/2023 to 7/21/2023		Lead-S	afe Certi	fication Asse	essment l	Report			
			Inspector Name and PA License Number: Lawrence Jackson 003683	Parkway Center City Middle College								
			Inspection Company: USA Environmental									
E			Management Inc		340 1401	11 13111 3	tieet, Filliau	ipilia, r <i>r</i>	13123			
l e m e n	F I o o r	Space #	Onsite Room Name	Component	Substrate Material	Paint Color	Description of Damage	Damage Quantity (sf)	XRF Reading (mg/cm2)	XRF (positive/ negative)		
1	3	302	Classroom 302	Radiator	Metal	Gray	Flaking	10	7	Positive		
1	3	302	Classroom 302	Radiator	Metal	Gray	Flaking	10	6.4	Positive		
1	3	302	Classroom 302	Window Casing	Wood	Varnish	None	0	0.5	Negative		
1	3	302	Classroom 302	Window Sill	Wood	Varnish	None	0	0.2	Negative		
1	3	302	Classroom 302	Window Apron	Wood	Varnish	None	0	0.1	Negative		
1	3	303	Classroom 303	Ceiling	Plaster	Tan	Chipping	20	17.8	Positive		
1	3	303	Classroom 303	W1	Plaster	Gray	None	0	0.2	Negative		
1	3	303	Classroom 303	W2	Plaster	Gray	None	0	10.2	Positive		
1	3	303	Classroom 303	W3	Plaster	Gray	None	0	18.7	Positive		
1	3	303	Classroom 303	W4	Plaster	Gray	Flaking	25	13.6	Positive		
1	3	303	Classroom 303	Door	Wood	Varnish	None	0	0	Negative		
1	3	303	Classroom 303	Door Frame	Wood	Varnish	None	0	0.1	Negative		
1	3	303	Classroom 303	Window Casing	Wood	Varnish	None	0	0.4	Negative		
1	3	303	Classroom 303	Window Sill	Wood	Varnish	None	0	0.3	Negative		
1	3	303	Classroom 303	Window Apron	Wood	Varnish	None	0	0.1	Negative		
1	3	303	Classroom 303	Radiators	Metal	Gray	Flaking	5	3.3	Positive		
1	3	303	Classroom 303	Radiators	Metal	Gray	Flaking	5	3.9	Positive		
1	3	303	Classroom 303	Baseboard	Wood	Brown	None	0	0	Negative		
1	3	303A	Office 303A	Ceiling	Plaster	Tan	Flaking	50	18.6	Positive		
1	3	303A	Office 303A	W1	Plaster	Blue	Flaking	25	18.9	Positive		
1	3	303A	Office 303A	W2	Plaster	Blue	Flaking	10	11.3	Positive		
1	3	303A	Office 303A	W3	Plaster	Blue	None	0	0.1	Negative		
1	3	303A	Office 303A	W4	Plaster	Blue	Flaking	3	14.2	Positive		
1	3	303A	Office 303A	Door	Wood	Varnish	None	0	0	Negative		
1	3	303A	Office 303A	Door Frame	Wood	Varnish	None	0	0	Negative		
1	3	303A	Office 303A	Window Casing	Wood	Varnish	None	0	0.2	Negative		
1	3	303A	Office 303A	Window Sill	Wood	Varnish	None	0	0.2	Negative		
1	3	303A	Office 303A	Window Apron	Wood	Varnish	None	0	0.1	Negative		
1	3	303A	Office 303A	Baseboard	Wood	Varnish	None	0	0	Negative		
1	3	303A	Office 303A	Radiator	Metal	Gray	None	0	3.7	Positive		
1	3	S34	Stairwell adjacent to Classroom 304	W1	Plaster	Gray	None	0	17.1	Positive		
1	3	S34	Stairwell adjacent to Classroom 304	W2	Plaster	Gray	None	0	15.5	Positive		
1	3	S34	Stairwell adjacent to Classroom 304	W3	Plaster	Gray	None	0	18.1	Positive		
1	3	S34	Stairwell adjacent to Classroom 304	Floor	Concrete	Gray	None	0	1.7	Positive		
1	3	S34	Stairwell adjacent to Classroom 304	Door	Metal	Brown	None	0	0	Negative		
1	3	S34	Stairwell adjacent to Classroom 304	Door Frame	Metal	Brown	None	0	4.4	Positive		
1	3	S34	Stairwell adjacent to Classroom 304	Stair Tread	Concrete	Gray	None	0	0.6	Negative		
1	3	S34	Stairwell adjacent to Classroom 304	Stair Riser	Concrete	Gray	None	0	1.3	Positive		

			Dates: 3/13/2023 to 7/21/2023		Lead-S	afe Certi	fication Asse	essment l	Report	
			Inspector Name and PA License Number:		Do	dayay Ca	ntor City Mic			
			Lawrence Jackson 003683		Par	rkway ce	nter City Mic	iale Colle	ege	
			Inspection Company: USA Environmental Management Inc		540 Nor	th 13th S	treet, Philad	elphia, PA	A 19123	
E I e	F		-							
m e n	0						Description of	Damage	XRF Reading	XRF (positive/
t	r	Space #	Onsite Room Name	Component	Substrate Material	Paint Color	Damage	Quantity (sf)	(mg/cm2)	negative)
1	3	S34	Stairwell adjacent to Classroom 304	Stair Stringer	Concrete	Gray	None	0	1.3	Positive
1	3	S34	Stairwell adjacent to Classroom 304	Spindle	Metal	Gray	None	0	7.7	Positive
1	3	S34	Stairwell adjacent to Classroom 304	Post	Metal	Brown	None	0	9	Positive
1	3	S34	Stairwell adjacent to Classroom 304	Ceiling	Plaster	White	None	0	19.1	Positive
1	3	304	Classroom 304	Ceiling	Plaster	Tan	Flaking	400	23.2	Positive
1	3	304	Classroom 304	W1	Plaster	Gray	None	0	16.5	Positive
1	3	304	Classroom 304	W2	Plaster	Gray	Flaking	50	19.5	Positive
1	3	304	Classroom 304	W3	Plaster	Gray	Flaking	20	19	Positive
1	3	304	Classroom 304	W4	Plaster	Gray	Flaking	30	23.9	Positive
1	3	304	Classroom 304	Door	Wood	Brown	None	0	0.1	Negative
1	3	304	Classroom 304	Door Frame	Wood	Brown	None	0	0.1	Negative
1	3	304	Classroom 304	Baseboard	Wood	Brown	None	0	0.2	Negative
1	3	304	Classroom 304	Window Casing	Wood	Brown	None	0	0	Negative
1	3	304	Classroom 304	Window Apron	Wood	Brown	None	0	0.1	Negative
1	3	304	Classroom 304	Window Sill	Wood	Brown	None	0	0.3	Negative
1	3	304	Classroom 304	Radiator	Metal	Gray	Flaking	10	7.3	Positive
1	3	304	Classroom 304	Radiator	Metal	Gray	Flaking	10	7.1	Positive
1	3	304A	Classroom 304 Office	W1	Plaster	White	None	0	20	Positive
1	3	304A	Classroom 304 Office	W2	Plaster	White	Flaking	40	18.5	Positive
1	3	304A	Classroom 304 Office	W3	Plaster	White	Flaking	40	0.3	Negative
1	3	304A	Classroom 304 Office	W4	Plaster	White	None	0	16.1	Positive
1	3	304A	Classroom 304 Office	Ceiling	Plaster	Tan	None	-	20.5	Positive
1	3	304A	Classroom 304 Office	Floor Door	Wood Wood	Unpainted Varnish	N/A None	N/A 0	N/A 0	N/A
1	3	304A 304A	Classroom 304 Office	Door Frame	Wood	Varnish	None	0	0.1	Negative
1	3	304A 304A	Classroom 304 Office Classroom 304 Office	Window Casing	Wood	Varnish	None	0	0.1	Negative Negative
1	3	304A 304A		Window Casing Window Sill	Wood	Varnish	None	0	0.3	Negative
1	3	304A 304A	Classroom 304 Office Classroom 304 Office	Window Apron	Wood	Varnish	None	0	0.3	Negative
1	3	304A 304A	Classroom 304 Office	Baseboard	Wood	Brown	None	0	0.2	Negative
	3	304A 304A	Classroom 304 Office	Radiator	Metal	Gray	None	0	3.2	Positive
	3	304A 304A	Classroom 304 Office	Steam Pipe	Metal	Gray	None	0	16.7	Positive
1	3	304A 304B	Classroom 304 Office Left Closet	W1	Plaster	White	None	0	5.2	Positive
1	3	304B	Classroom 304 Office Left Closet	W2	Plaster	White	None	0	4.6	Positive
1	3	304B	Classroom 304 Office Left Closet	W3	Plaster	White	None	0	6	Positive
1	3	304B	Classroom 304 Office Left Closet	W4	Plaster	White	None	0	4	Positive
1	3	304B	Classroom 304 Office Left Closet	Ceiling	Plaster	No Access	None	N/A	N/A	No Access
1	3	304B	Classroom 304 Office Left Closet	Floor	Wood	Unpainted	N/A	N/A	N/A	N/A
1	3	304B	Classroom 304 Office Left Closet	Door	Wood	Varnish	None	0	0	Negative

			Dates: 3/13/2023 to 7/21/2023		Lead-S	afe Certi	fication Asse	essment l	Report	
			Inspector Name and PA License Number:		D.s.	d O -	4 a O!4 NA! a	Idla Oalla		
			Lawrence Jackson 003683		Pai	rkway ce	nter City Mid	iale Colle	ege	
			Inspection Company: USA Environmental Management Inc		540 Nor	th 13th S	treet, Philad	elphia, PA	A 19123	
E I e	F									
m e	1 0						Description of	Damaga	XRF Reading	XRF
n t	o r	Space #	Onsite Room Name	Component	Substrate Material	Paint Color	Description of Damage	Damage Quantity (sf)	(mg/cm2)	(positive/ negative)
1	3	304B	Classroom 304 Office Left Closet	Door Frame	Wood	Varnish	None	0	0.2	Negative
1	3	304B	Classroom 304 Office Left Closet	Baseboard	Wood	Brown	None	0	0.2	Negative
1	3	304C	Classroom 304 Office Right Closet	W1	Plaster	White	None	0	3.3	Positive
1	3	304C	Classroom 304 Office Right Closet	W2	Plaster	White	None	0	1.9	Positive
1	3	304C	Classroom 304 Office Right Closet	W3	Plaster	White	None	0	2.2	Positive
1	3	304C	Classroom 304 Office Right Closet	W4	Plaster	White	None	0	2.3	Positive
1	3	304C	Classroom 304 Office Right Closet	Floor	Wood	Unpainted	N/A	N/A	N/A	N/A
1	3	304C	Classroom 304 Office Right Closet	Ceiling	Plaster	No Access	None	N/A	N/A	No Access
1	3	304C	Classroom 304 Office Right Closet	Door	Wood	Varnish	None	0	0	Negative
1	3	304C	Classroom 304 Office Right Closet	Door Frame	Wood	Varnish	None	0	0.1	Negative
1	3	304C	Classroom 304 Office Right Closet	Baseboard	Wood	No Access	None	0	N/A	N/A
1	3	305	Classroom 305	W1	Wood	Varnish	None	0	0	Negative
1	3	305	Classroom 305	W2	Plaster	Gray	Efflorescence	20	22.3	Positive
1	3	305	Classroom 305	W3	Plaster	Gray	Efflorescence	5	18.7	Positive
1	3	305	Classroom 305	W4	Plaster	Gray	None	0	3.3	Positive
1	3	305	Classroom 305	Floor	Wood	Unpainted	N/A	N/A	N/A	N/A
1	3	305	Classroom 305	Ceiling	Plaster	Tan	None	0	21.2	Positive
1	3	305	Classroom 305	Radiator	Metal	Gray	Flaking	10	5.2	Positive
1	3	305	Classroom 305	Door	Wood	Varnish	None	0	0.1	Negative
1	3	305	Classroom 305	Door Frame	Wood	Varnish	None	0	0	Negative
1	3	305	Classroom 305	Window Casing	Wood	Varnish	None	0	0.3	Negative
1	3	305	Classroom 305	Window Sill	Wood	Varnish	None	0	0.2	Negative
1	3	305	Classroom 305	Window Apron	Wood	Varnish	None	0	0.1	Negative
1	3	305A	Closet across from Classroom 305	Door	Wood	Varnish	None	0	0.1	Negative
1	3	305A	Closet across from Classroom 305	Door Frame	Wood	Varnish	None	0	0.1	Negative
1	3	305A	Closet across from Classroom 305	W1	Plaster	White	No Access	No Access	No Access	No Access
1	3	305A	Closet across from Classroom 305	W2	Plaster	White	No Access	No Access	No Access	No Access
1	3	305A	Closet across from Classroom 305	W3	Plaster	White	No Access	No Access	No Access	No Access
1	3	305A	Closet across from Classroom 305	W4	Plaster	White	No Access	No Access	No Access	No Access
1	3	305A	Closet across from Classroom 305	Ceiling	Plaster	White	No Access	No Access	No Access	No Access
1	3	305A	Closet across from Classroom 305	Floor	Concrete	No Access	No Access	N/A	N/A	N/A
1	3	306A	Custodial Closet across from Classroom 306	W1	Plaster	White	None	0	2.6	Positive
1	3	306A	Custodial Closet across from Classroom 306	W2	Plaster	White	None	0	5.5	Positive
1	3	306A	Custodial Closet across from Classroom 306	W3	Plaster	White	None	0	4.7	Positive
1	3	306A	Custodial Closet across from Classroom 306	W4	Plaster	White	None	0	3.5	Positive
1	3	306A	Custodial Closet across from Classroom 306	Ceiling	Plaster	White	None	0	N/A	N/A
1	3	306A	Custodial Closet across from Classroom 306	Floor	Concrete	Unpainted	N/A	N/A	N/A	N/A
1	3	306A	Custodial Closet across from Classroom 306	Door	Wood	Varnish	None	0	0.1	Negative

			Dates: 3/13/2023 to 7/21/2023		Lead-S	afe Certi	fication Asse	essment l	Report			
			Inspector Name and PA License Number:	Parkway Center City Middle College								
			Lawrence Jackson 003683		Pai	kway ce	niter City with	idle Colle	ge			
			Inspection Company: USA Environmental Management Inc		540 Nor	th 13th S	treet, Philad	elphia, P	A 19123			
E I e m e n t	F	Space #	Onsite Room Name	Component	Substrate Material	Paint Color	Description of Damage	Damage Quantity (sf)	XRF Reading (mg/cm2)	XRF (positive/ negative)		
1	3	306A	Custodial Closet across from Classroom 306	Door Frame	Wood	Varnish	None	0	0.2	Negative		
1	3	306A	Custodial Closet across from Classroom 306	Shelf Support	Wood	White	None	0	0	Negative		
1	3	306	Classroom 306	W1	Wood	Varnish	None	0	0.1	Negative		
1	3	306	Classroom 306	W2	Plaster	White	Flaking	10	10	Positive		
1	3	306	Classroom 306	W3	Wood	Varnish	No Access	No Access	0	Negative		
1	3	306	Classroom 306	W4	Plaster	White	Flaking	5	10	Positive		
1	3	306	Classroom 306	Ceiling	Plaster	White	Flaking	10	10	Positive		
1	3	306	Classroom 306	Door	Wood	Varnish	None	0	0	Negative		
1	3	306	Classroom 306	Door Frame	Wood	Varnish	None	0	0	Negative		
1	3	306	Classroom 306	Drain Pipe	Metal	White	Flaking	8	0.3	Negative		
1	3	306	Classroom 306	Radiator	Metal	Gray	Chipping	8	2.2	Positive		
1	3	306	Classroom 306	Window Sill	Wood	Varnish	None	0	0.1	Negative		
1	3	306	Classroom 306	Window Casing	Wood	Varnish	None	0	0.2	Negative		
1	3	306	Classroom 306	Window Apron	Wood	Varnish	None	0	0.1 20.5	Negative		
1	3	307	Classroom 307	W1	Plaster	White	Flaking	15		Positive		
1	3	307	Classroom 307	W2 W3	Plaster Wood	White	Flaking	15 0	18.9 0.1	Positive		
1	3	307	Classroom 307	W4	Plaster	Varnish White	None	20	18.9	Negative Positive		
1	3	307	Classroom 307		Plaster	Tan	Flaking Flaking	50	22.9	Positive		
1	3	307	Classroom 307	Ceiling Baseboard	Wood	Brown	None	0	0.1			
1	3	307	Classroom 307	Door	Wood	Varnish	None	0	0.1	Negative Negative		
1	3	307	Classroom 307	Door Frame	Wood	Varnish	None	0	0.1	Negative		
1	3	307 307	Classroom 307 Classroom 307	Window Casing	Wood	Varnish	None	0	0.1	Positive		
1	3	307	Classroom 307	Window Casing Window Sill	Wood	Varnish	None	0	0.9	Negative		
1	3	307	Classroom 307	Window Apron	Wood	Varnish	None	0	0.2	Negative		
1	3	307	Classroom 307	Radiator	Metal	Gray	Flaking	10	3.3	Positive		
1	3	307	Classroom 307	Radiator	Metal	Gray	Flaking	10	3.1	Positive		
1	3	307	Classroom 307	Radiator	Metal	Gray	Flaking	10	1.4	Positive		
1	3	S33	Stairwell adjacent to Classroom 308	W1	Plaster	Gray	None	0	15.3	Positive		
1	3	S33	Stairwell adjacent to Classroom 308	W2	Plaster	Gray	Efflorescence	10	0	Negative		
1	3	S33	Stairwell adjacent to Classroom 308	W3	Plaster	Gray	None	0	22.1	Positive		
1	3	S33	Stairwell adjacent to Classroom 308	Floor	Concrete	Gray	None	0	1.1	Positive		
1	3	S33	Stairwell adjacent to Classroom 308	Door	Metal	Brown	None	0	0	Negative		
1	3	S33	Stairwell adjacent to Classroom 308	Door Frame	Metal	Brown	None	0	4.4	Positive		
1	3	S33	Stairwell adjacent to Classroom 308	Stair Tread	Concrete	Gray	None	0	0.3	Negative		
1	3	S33	Stairwell adjacent to Classroom 308	Stair Riser	Concrete	Gray	None	0	1.7	Positive		
1	3	S33	Stairwell adjacent to Classroom 308	Stair Stringer	Concrete	Gray	None	0	2.4	Positive		
1	3	S33	Stairwell adjacent to Classroom 308	Spindle	Metal	Gray	None	0	7.2	Positive		

			Dates: 3/13/2023 to 7/21/2023		Lead-S	afe Certi	fication Asse	essment l	Report	
			Inspector Name and PA License Number:						•	
			Lawrence Jackson 003683		Pai	rkway Ce	nter City Mic	iale Colle	ege	
			Inspection Company: USA Environmental Management Inc		540 Nor	th 13th S	treet, Philad	elphia, P	A 19123	
E I e m e	F						·			XRF
n	0	S #	Onsite Room Name	Commonant	Cubatuata Matarial	Beint Color	Description of	Damage	XRF Reading	(positive/
1	3	Space #	Stairwell adjacent to Classroom 308	Component Post	Substrate Material Metal	Paint Color Brown	Damage None	Quantity (sf)	(mg/cm2) 6.7	negative) Positive
1	3	S33	Stairwell adjacent to Classroom 308	Ceiling	Plaster	White	None	0	19.4	Positive
1	3	308	Classroom 308	W1	Plaster	Blue	Flaking	2	16.9	Positive
1	3	308	Classroom 308	W2	Plaster	Gray	None	0	15.3	Positive
1	3	308	Classroom 308	W3	Plaster	Gray	None	0	20.2	Positive
1	3	308	Classroom 308	W4	Plaster	Gray	None	0	22.9	Positive
1	3	308	Classroom 308	Ceiling	Plaster	Tan	Chipping	40	23.9	Positive
1	3	308	Classroom 308	Baseboard	Wood	Brown	None	0	0.1	Negative
1	3	308	Classroom 308	Door	Wood	Varnish	None	0	0.1	Negative
1	3	308	Classroom 308	Door Frame	Wood	Varnish	None	0	0.1	Negative
1	3	308	Classroom 308	Window Casing	Wood	Varnish	None	0	0.5	Negative
1	3	308	Classroom 308	Window Sill	Wood	Varnish	None	0	0.1	Negative
1	3	308	Classroom 308	Window Apron	Wood	Varnish	None	0	0.1	Negative
1	3	308	Classroom 308	Radiator	Metal	Gray	Flaking	5	3.4	Positive
1	3	308	Classroom 308	Radiator	Metal	Gray	Flaking	5	4.9	Positive
1	3	308	Classroom 308	Radiator	Metal	Gray	None	0	3.5	Positive
1	3	309	Weight Room 309	W1	Plaster	White	Flaking	40	18.6	Positive
1	3	309	Weight Room 309	W2	Plaster	White	Efflorescence	40	9.8	Positive
1	3	309	Weight Room 309	W3	Plaster	White	None	0	0	Negative
1	3	309	Weight Room 309	W4	Plaster	White	None	0	15.2	Positive
1	3	309	Weight Room 309	Ceiling	Plaster	Tan	Flaking	200	0.4	Negative
1	3	309	Weight Room 309	Door	Wood	Varnish	None	0	0.2	Negative
1	3	309	Weight Room 309	Door Frame	Wood	Varnish	None	0	0.1	Negative
1	3	309	Weight Room 309	Baseboard	Wood	Varnish	None	0	0.1	Negative
1	3	309	Weight Room 309	Window Casing	Wood	Varnish	None	0	0.4	Negative
1	3	309	Weight Room 309	Window Sill	Wood	Varnish	None	0	0.2	Negative
1	3	309	Weight Room 309	Window Apron	Wood	Varnish	None	0	0	Negative
1	3	309	Weight Room 309	Radiator Cover	Metal	Gray	None	0	0	Negative
1	3	309	Weight Room 309	Radiator	Metal	Gray	Flaking	5	4.4	Positive
1	3	309	Weight Room 309	Radiator	Metal	Gray	Flaking	5	0.4	Negative
1	3	S35	Fire Tower adjacent to Classroom 309	W1	Brick	White	None	0	8.2	Positive
1	3	S35	Fire Tower adjacent to Classroom 309	W2	Brick	White	None	0	10	Positive
1	3	S35	Fire Tower adjacent to Classroom 309	W3	Brick	White	None	0	13.8	Positive
1	3	S35	Fire Tower adjacent to Classroom 309	W4	Brick	White	None	0	5.3	Positive
1	3	S35	Fire Tower adjacent to Classroom 309	Ceiling	Concrete	White	Flaking	15	9.1	Positive
1	3	S35	Fire Tower adjacent to Classroom 309	Floor	Concrete	Gray	None	0	1.7	Positive
1	3	S35	Fire Tower adjacent to Classroom 309	Door	Metal	Brown	Flaking	5	0	Negative
1	3	S35	Fire Tower adjacent to Classroom 309	Door Frame	Metal	Brown	Flaking	12	0.4	Negative

			Dates: 3/13/2023 to 7/21/2023		Lead-S	afe Certi	fication Asse	essment l	Report	
			Inspector Name and PA License Number:		D-	-l O -	4 Oi4 Mid			
			Lawrence Jackson 003683		Pai	rkway Ce	nter City Mid	iale Colle	ege	
			Inspection Company: USA Environmental Management Inc		540 Nor	th 13th S	treet, Philade	elphia, PA	A 19123	
E I e	F						·	•		
m e n t	0 0 r	Space #	Onsite Room Name	Component	Substrate Material	Paint Color	Description of Damage	Damage Quantity (sf)	XRF Reading (mg/cm2)	XRF (positive/ negative)
1	3	S35	Fire Tower adjacent to Classroom 309	Security Gate	Metal	Brown	Flaking	100	28.3	Positive
1	3	S35	Fire Tower adjacent to Classroom 309	Drain Pipe	Metal	Brown	Flaking	24	1.3	Positive
1	3	S35	Fire Tower adjacent to Classroom 309	Handrail	Metal	Brown	Chipping	14	2.7	Positive
1	3	S35	Fire Tower adjacent to Classroom 309	Stair Riser	Concrete	Gray	None	0	1.7	Positive
1	3	S35	Fire Tower adjacent to Classroom 309	Stair Tread	Concrete	Gray	None	0	0.9	Positive
1	3	S35	Fire Tower adjacent to Classroom 309	Stair Stringer	Concrete	Gray	None	0	2.5	Positive
1	3	310	Classroom 310	W1	Plaster	Gray	Flaking	20	20.3	Positive
1	3	310	Classroom 310	W2	Plaster	Gray	Flaking	15	22.7	Positive
1	3	310	Classroom 310	W3	Plaster	Gray	Flaking	5	0	Negative
1	3	310	Classroom 310	W4	Plaster	Gray	None	0	0.1	Negative
1	3	310	Classroom 310	Ceiling	Plaster	Tan	Flaking	200	18.3	Positive
1	3	310	Classroom 310	Door	Wood	Varnish	None	0	0	Negative
1	3	310	Classroom 310	Door Frame	Wood	Varnish	None	0	0.1	Negative
1	3	310	Classroom 310	Window Casing	Wood	Varnish	None	0	0.7	Positive
1	3	310	Classroom 310	Window Sill	Wood	Varnish	None	0	0.2	Negative
1	3	310	Classroom 310	Window Apron	Wood	Varnish	None	0	0.2	Negative
1	3	310	Classroom 310	Chair Rail	Wood	Varnish	None	0	0.2	Negative
1	3	310	Classroom 310	Crown Molding	Wood	Varnish	None	0	0.4	Negative
1	3	310	Classroom 310	Baseboard	Wood	Brown	None	0	0	Negative
1	3	310	Classroom 310	Radiator	Metal	Gray	Flaking	5	4.6	Positive
1	3	310	Classroom 310	Radiator	Metal	Gray	Flaking	5	7	Positive
1	3	310	Classroom 310	Radiator	Metal	Gray	Flaking	5	3.7	Positive
1	3	310	Classroom 310	Closet Door	Wood	Blue	None	0	0.1	Negative
1	3	311	Girl's Restroom adjacent to Classroom 310	W1	Plaster	White	None	0	12.2	Positive
1	3	311	Girl's Restroom adjacent to Classroom 310	W2	Plaster	White	None	0	15.7	Positive
1	3	311	Girl's Restroom adjacent to Classroom 310	W3 W4	Plaster	White	None	0	0	Negative
1	3	311	Girl's Restroom adjacent to Classroom 310		Plaster Plaster	White White	Flaking None	5	0.2	Negative
1	3	311	Girl's Restroom adjacent to Classroom 310	Ceiling				0	0.2	Negative
<u> </u>	3	311	Girl's Restroom adjacent to Classroom 310	Floor	Concrete	Gray	None			Negative
1	3	311	Girl's Restroom adjacent to Classroom 310	Door Frame	Wood Wood	Varnish	None	0	0.1	Negative
1	3	311	Girl's Restroom adjacent to Classroom 310	Door Frame		Brown	None			Negative
1	3	311	Girl's Restroom adjacent to Classroom 310	Radiator	Metal Wood	Gray	Flaking	10	0 0.2	Negative
1	3	311	Girl's Restroom adjacent to Classroom 310	Window Casing		Varnish	None			Negative
1	3	311	Girl's Restroom adjacent to Classroom 310	Window Aprop	Wood Wood	Varnish	None	0	0.2	Negative
1	3	311	Girl's Restroom adjacent to Classroom 310	Window Apron	vvood	Varnish	None	U	U	Negative
1	3	311A	Pipe Chase in Girl's Restroom adjacent to Classroom 310	Door	Wood	White	None	0	0	Negative

			Dates: 3/13/2023 to 7/21/2023		Lead-S	afe Certi	fication Asse	essment l	Report	
			Inspector Name and PA License Number:				4 014 141		•	
			Lawrence Jackson 003683		Pai	rkway Ce	nter City Mic	idle Colle	ge	
			Inspection Company: USA Environmental		5 40 N	4041 0			10100	
			Management Inc		540 Nor	tn 13tn S	treet, Philad	eipnia, PA	A 19123	
E										
e	F									
m	1									
е	0						Danaminetian of	D	VDE Danding	XRF
n t	o r	Space #	Onsite Room Name	Component	Substrate Material	Paint Color	Description of Damage	Damage Quantity (sf)	XRF Reading (mg/cm2)	(positive/ negative)
	<u> </u>	орцоо л	Pipe Chase in Girl's Restroom adjacent to Classroom					, , ,	, <u> </u>	•
1	3	311A	310	Door Frame	Wood	White	None	0	0	Negative
1	3	311A	Pipe Chase in Girl's Restroom adjacent to Classroom 310	W1	Concrete	Unpainted	N/A	N/A	N/A	N/A
1	3	311A	Pipe Chase in Girl's Restroom adjacent to Classroom 310	W2	Concrete	Unpainted	N/A	N/A	N/A	N/A
1	3	311A	Pipe Chase in Girl's Restroom adjacent to Classroom 310	W3	Concrete	Unpainted	N/A	N/A	N/A	N/A
1	3	311A	Pipe Chase in Girl's Restroom adjacent to Classroom 310	W4	Concrete	Unpainted	N/A	N/A	N/A	N/A
1	3	316	Gymnasium	W1	Plaster	White	None	0	23.8	Positive
1	3	316	Gymnasium	W2	Plaster	White	None	0	17.8	Positive
1	3	316	Gymnasium	W3	Plaster	White	None	0	0.1	Negative
1	3	316	Gymnasium	W4	Plaster	White	None	0	18.2	Positive
1	3	316	Gymnasium	Ceiling	Concrete	White	Cracking	40	No Access	Assumed
1	3	316	Gymnasium	Covebase	Concrete	Brown	None	0	12.6	Positive
1	3	316	Gymnasium	Door	Wood	Varnish	None	0	0.1	Negative
1	3	316	Gymnasium	Door Frame	Metal	Gray	None	0	0.5	Negative
1	3	316	Gymnasium	Radiator	Metal	Gray	No Access	No Access	No Access	No Access
1	3	316	Gymnasium	Radiator	Metal	Gray	No Access	No Access	No Access	No Access
1	3	316	Gymnasium	Radiator	Metal	Gray	No Access	No Access	No Access	No Access
1	3	316	Gymnasium	Radiator	Metal	Gray	No Access	No Access	No Access	No Access
1	3	316	Gymnasium	Radiator	Metal	Gray	No Access	No Access	No Access	No Access
1	3	316	Gymnasium	Radiator W1	Metal Plaster	Gray Tan	No Access	No Access	No Access 0	No Access
1	3	S316	Stairwell to Gymnasium Balcony	W2		Tan	Flaking	40 0	16.2	Negative
1	3	S316 S316	Stairwell to Gymnasium Balcony Stairwell to Gymnasium Balcony	W3	Plaster Plaster	Tan	None None	0	16.2	Positive Positive
1	3	S316 S316	Stairwell to Gymnasium Balcony Stairwell to Gymnasium Balcony	Door	Wood	Varnish	None	0	0	Negative
1	3	S316	Stairwell to Gymnasium Balcony Stairwell to Gymnasium Balcony	Door Frame	Wood	Varnish	None	0	0	Negative
1	4	414	Gymnasium Balcony	No Access	No Access	No Access	No Access	No Access	No Access	No Access
1	4	414	Gymnasium Balcony	No Access	No Access	No Access	No Access	No Access	No Access	No Access
1	4	414	Gymnasium Balcony	No Access	No Access	No Access	No Access	No Access	No Access	No Access
1	4	414	Gymnasium Balcony	No Access	No Access	No Access	No Access	No Access	No Access	No Access
1	4	414	Gymnasium Balcony	No Access	No Access	No Access	No Access	No Access	No Access	No Access
1	4	414	Gymnasium Balcony	No Access	No Access	No Access	No Access	No Access	No Access	No Access
1	3	314	Gymnasium Office on Boy's Side	W1	Plaster	Blue	None	0	12.2	Positive
1	3	314	Gymnasium Office on Boy's Side	W2	Plaster	Blue	None	0	11.1	Positive
1	3	314	Gymnasium Office on Boy's Side	W3	Plaster	Blue	None	0	14.4	Positive
1	3	314	Gymnasium Office on Boy's Side	W4	Plaster	Blue	None	0	10.3	Positive

			Dates: 3/13/2023 to 7/21/2023		Lead-S	afe Certi	fication Asse	essment l	Report	
			Inspector Name and PA License Number:							
			Lawrence Jackson 003683		Pai	rkway Ce	nter City Mic	idle Colle	ge	
			Inspection Company: USA Environmental		E40 Non	th 12th C	treet, Philad	alphia D	10122	
L	1		Management Inc		540 NOI	เมางเมง	treet, Pillau	eipilia, P	19123	
E I e m	F									
e n	0						Description of	Damage	XRF Reading	XRF (positive/
t	r	Space #	Onsite Room Name	Component	Substrate Material	Paint Color	Damage	Quantity (sf)	(mg/cm2)	negative)
1	3	314	Gymnasium Office on Boy's Side	Ceiling	Plaster	Blue	None	0	12.4	Positive
1	3	314	Gymnasium Office on Boy's Side	Door	Wood	Varnish	None	0	0.1	Negative
1	3	314	Gymnasium Office on Boy's Side	Door Frame	Wood	Varnish	None	0	0.1	Negative
1	3	314	Gymnasium Office on Boy's Side	Window Casing	Wood	Varnish	None	0	0.3	Negative
1	3	314	Gymnasium Office on Boy's Side	Window Sill	Wood	Varnish	None	_	0.1	Negative
1	3	314	Gymnasium Office on Boy's Side	Window Apron	Wood Wood	Varnish	None	0	0.1	Negative
1	3	314	Gymnasium Office on Boy's Side	Baseboard Radiator	vvood Metal	Brown	None Flaking	10	0.4	Negative Negative
1	3	314 314A	Gymnasium Office on Boy's Side Gymnasium Office on Boy's Side Restroom	W1	Plaster	Gray Blue	None	0	7.3	Positive
1	3	314A 314A	, ,	W2	Plaster	Blue	None	0	7.3 8	Positive
1	3	314A 314A	Gymnasium Office on Boy's Side Restroom Gymnasium Office on Boy's Side Restroom	W3	Plaster	Blue	None	0	9.3	Positive
1	3	314A 314A	Gymnasium Office on Boy's Side Restroom	W4	Plaster	Blue	None	0	7.8	Positive
1	3	314A	Gymnasium Office on Boy's Side Restroom	Ceiling	Plaster	White	None	0	8	Positive
1	3	314A	Gymnasium Office on Boy's Side Restroom	Duct	Metal	White	None	0	9.2	Positive
1	3	314A	Gymnasium Office on Boy's Side Restroom	Window Sill	Wood	Varnish	None	0	0.1	Negative
1	3	314A	Gymnasium Office on Boy's Side Restroom	Window Casing	Wood	Varnish	None	0	0.1	Negative
1	3	314A	Gymnasium Office on Boy's Side Restroom	Window Apron	Wood	Varnish	None	0	0.1	Negative
1	3	314A	Gymnasium Office on Boy's Side Restroom	Door	Wood	Varnish	None	0	0.1	Negative
1	3	314A	Gymnasium Office on Boy's Side Restroom	Door Frame	Wood	Varnish	None	0	0.1	Negative
1	3	314A	Gymnasium Office on Boy's Side Restroom	Radiator	Metal	Gray	Chipping	10	2	Positive
1	3	315	Gymnasium Office on Girl's Side	W1	Plaster	Blue	None	0	14.5	Positive
1	3	315	Gymnasium Office on Girl's Side	W2	Plaster	Blue	None	0	15	Positive
1	3	315	Gymnasium Office on Girl's Side	W3	Plaster	Blue	None	0	11.3	Positive
1	3	315	Gymnasium Office on Girl's Side	W4	Plaster	Blue	None	0	16.4	Positive
1	3	315	Gymnasium Office on Girl's Side	Ceiling	Plaster	White	None	0	12	Positive
1	3	315	Gymnasium Office on Girl's Side	Baseboard	Wood	Brown	None	0	0.2	Negative
1	3	315	Gymnasium Office on Girl's Side	Door	Wood	Varnish	None	0	0	Negative
1	3	315	Gymnasium Office on Girl's Side	Door Frame	Wood	Varnish	None	0	0	Negative
1	3	315	Gymnasium Office on Girl's Side	Window Casing	Wood	Varnish	None	0	0.4	Negative
1	3	315	Gymnasium Office on Girl's Side	Window Sill	Wood	Varnish	None	0	0	Negative
1	3	315	Gymnasium Office on Girl's Side	Window Apron	Wood	Varnish	None	0	0.1	Negative
1	3	315	Gymnasium Office on Girl's Side	Chair Rail	Wood	Varnish	None	0	0.1	Negative
1	3	315	Gymnasium Office on Girl's Side	Radiator	Metal	Gray	Flaking	3	0.2	Negative
1	3	315A	Gymnasium Office on Girl's Side Restroom	W1	Plaster	White	None	0	12.9	Positive
1	3	315A	Gymnasium Office on Girl's Side Restroom	W2	Plaster	White	None	0	9.8	Positive
1	3	315A	Gymnasium Office on Girl's Side Restroom	W3	Plaster	White	None	0	14.3	Positive
1	3	315A	Gymnasium Office on Girl's Side Restroom	W4	Plaster	White	None	0	7.7	Positive
1	3	315A	Gymnasium Office on Girl's Side Restroom	Ceiling	Plaster	White	None	0	14.7	Positive

			Dates: 3/13/2023 to 7/21/2023		Lead-S	afe Certi	fication Asse	essment l	Report	
			Inspector Name and PA License Number:		Do	dayor Co	ntor City Mic		-	
			Lawrence Jackson 003683		Pai	rkway Ce	nter City Mic	iale Colle	ge	
			Inspection Company: USA Environmental Management Inc		540 Nor	th 13th S	treet, Philad	elphia, PA	A 19123	
E I e	F									
m e n t	0 0 r	Space #	Onsite Room Name	Component	Substrate Material	Paint Color	Description of Damage	Damage Quantity (sf)	XRF Reading (mg/cm2)	XRF (positive/ negative)
1	3	315A	Gymnasium Office on Girl's Side Restroom	Door Frame	Wood	Varnish	None	0	0.1	Negative
1	3	315A	Gymnasium Office on Girl's Side Restroom	Baseboard	Wood	Brown	None	0	0.2	Negative
1	3	312	Boy's Locker Room	W1	Plaster	White	None	0	0.3	Negative
1	3	312	Boy's Locker Room	W2	CMU	White	None	0	0.1	Negative
1	3	312	Boy's Locker Room	W3	Marble	Unpainted	N/A	N/A	N/A	N/A
1	3	312	Boy's Locker Room	W4	Plaster	White	Efflorescence	16	10.2	Positive
1	3	312	Boy's Locker Room	Floor	Concrete	Gray	None	0	0.2	Negative
1	3	312	Boy's Locker Room	Ceiling	Plaster	Gray	Efflorescence	70	12.1	Positive
1	3	312	Boy's Locker Room	Radiator	Concrete	Gray	Flaking	10	0.1	Negative
1	3	312	Boy's Locker Room	Sanitary Line	Concrete	White	Flaking	10	0.2	Negative
1	3	312	Boy's Locker Room	Door	Wood	Varnish	None	0	0.1	Negative
1	3	312	Boy's Locker Room	Door Frame	Wood	Varnish	None	0	0	Negative
1	3	312	Boy's Locker Room	Radiator	Metal	Gray	None	0	0.9	Positive
1	3	312	Boy's Locker Room	Duct	Metal	White	None	0	10.5	Positive
1	3	312A	Boy's Locker Room Storage Room	W1	Marble	Unpainted	N/A	N/A	N/A	N/A
1	3	312A	Boy's Locker Room Storage Room	W2	Marble	Unpainted	N/A	N/A	N/A	N/A
1	3	312A	Boy's Locker Room Storage Room	W3	CMU	White	None	0	0	Negative
1	3	312A	Boy's Locker Room Storage Room	W4	Marble	Unpainted	N/A	N/A	N/A	N/A
1	3	312A	Boy's Locker Room Storage Room	Ceiling	Plaster	White	Flaking	10	8	Positive
1	3	312A	Boy's Locker Room Storage Room	Floor	Concrete	Grey	None	0	0.4	Negative
1	3	312B	Boy's Locker Room Storage Closet	W1	Plaster	Tan	None	0	6.2	Positive
1	3	312B	Boy's Locker Room Storage Closet	W2	Plaster	Tan	Flaking	25	7	Positive
1	3	312B	Boy's Locker Room Storage Closet	W3	Plaster	Tan	Flaking	25	7.9	Positive
1	3	312B	Boy's Locker Room Storage Closet	W4	Plaster	Tan	Flaking	5	6.2	Positive
1	3	312B	Boy's Locker Room Storage Closet	Ceiling	Plaster	White	Flaking	10	5.9	Positive
1	3	312B	Boy's Locker Room Storage Closet	Drain Pipe	Metal	White	Flaking	8	8.5	Positive
1	3	312B	Boy's Locker Room Storage Closet	Door	Wood	Brown	None	0	0.1	Negative
1	3	312B	Boy's Locker Room Storage Closet	Door Frame	Wood	Brown	None	0	0.1	Negative
1	3	312C	Closet adjacent to Boy's Locker Room	W1	Plaster	Tan	None	0	3.1	Positive
1	3	312C	Closet adjacent to Boy's Locker Room	W2	Plaster	Tan	None	0	0.2	Negative
1	3	312C	Closet adjacent to Boy's Locker Room	W3	Plaster	Tan	None	0	1.6	Positive
1	3	312C	Closet adjacent to Boy's Locker Room	W4	Plaster	Tan	None	0	0.5	Negative
1	3	312C	Closet adjacent to Boy's Locker Room	Door	Wood	Varnish	None	0	0.1	Negative
1	3	312C	Closet adjacent to Boy's Locker Room	Door Frame	Wood	Varnish	None	0	0.1	Negative
1	3	312C	Closet adjacent to Boy's Locker Room	Ceiling	Plaster	Tan	Cracking	3	2.7	Positive
1	3	312D	Girl's Locker Room	Door	Wood	Varnish	None	0	0.1	Negative
1	3	312D	Girl's Locker Room	Door Frame	Wood	Varnish	None	0	0.1	Negative

			Dates: 3/13/2023 to 7/21/2023	Lead-Safe Certification Assessment Report Parkway Center City Middle College						
			Inspector Name and PA License Number:		D.s.	d O -	4 O!4 NA!	Idla Oalla		
			Lawrence Jackson 003683		Par	rkway Ce	nter City Mile	iale Colle	ge	
			Inspection Company: USA Environmental Management Inc		540 Nor	th 13th S	treet, Philad	elphia, PA	A 19123	
E I e	F									
m e n	0						Description of	Damage	XRF Reading	XRF (positive/
l "t	r	Space #	Onsite Room Name	Component	Substrate Material	Paint Color	Damage	Quantity (sf)	(mg/cm2)	negative)
1	3	312D	Girl's Locker Room	W1	Wood	White	None	0	0.1	Negative
1	3	312D	Girl's Locker Room	W2	CMU	White	None	0	0.2	Negative
1	3	312D	Girl's Locker Room	W3	Plaster	White	None	0	0.1	Negative
1	3	312D	Girl's Locker Room	W4	Plaster	White	Efflorescence	40	9.2	Positive
1	3	312D	Girl's Locker Room	Ceiling	Concrete	White	Flaking	60	16.4	Positive
1	3	312D	Girl's Locker Room	Radiator	Metal	Gray	Flaking	10	0.1	Negative
1	3	312D	Girl's Locker Room	Sanitary Line	Metal	White	Flaking	20	3	Positive
1	3	312D	Girl's Locker Room	Floor	Concrete	Gray	None	0	0.1	Negative
1	3	312D	Girl's Locker Room	Window Casing	Wood	Varnish	None	0	0.4	Negative
1	3	312D	Girl's Locker Room	Window Sill	Wood	Varnish	None	0	0.4	Negative
1	3	312E	Girl's Locker Room Storage Room	W1	Marble	Unpainted	N/A	N/A	N/A	N/A
1	3	312E	Girl's Locker Room Storage Room	W2	Marble	Unpainted	N/A	N/A	N/A	N/A
1	3	312E	Girl's Locker Room Storage Room	W3	CMU	White	None	0	0	Negative
1	3	312E	Girl's Locker Room Storage Room	W4	Marble	Unpainted	N/A	N/A	N/A	N/A
1	3	312E	Girl's Locker Room Storage Room	Ceiling	Plaster	No Access	No Access	No Access	No Access	No Access
1	3	312E	Girl's Locker Room Storage Room	Door	Wood	Varnish	None	0	0	Negative
1	3	312E	Girl's Locker Room Storage Room	Door Frame	Metal	Gray	None	0	0	Negative
1	3	312E	Girl's Locker Room Storage Room	Drain Pipe	Metal	White	Flaking	10	0.1	Negative
1	3	312E	Girl's Locker Room Storage Room	Floor	Concrete	Gray	None	0	0.1	Negative
1	3	312F	Girl's Locker Room Storage Closet	W1	Plaster	Tan	Cracking	15	5.9	Positive
1	3	312F	Girl's Locker Room Storage Closet	W2	Plaster	Tan	Cracking	15	6.2	Positive
1	3	312F	Girl's Locker Room Storage Closet	W3	Plaster	Tan	None	0	6.7	Positive
1	3	312F	Girl's Locker Room Storage Closet	W4	Plaster	Tan	None	0	6.7	Positive
1	3	312F	Girl's Locker Room Storage Closet	Ceiling	Plaster	Tan	Flaking	20	7.1	Positive
1	3	312F	Girl's Locker Room Storage Closet	Door	Wood	Varnish	None	0	0.1	Negative
1	3	312F	Girl's Locker Room Storage Closet	Door Frame	Wood	Varnish	None	0	0.1	Negative
1	3	312F	Girl's Locker Room Storage Closet	Drain Pipe	Metal	White	Flaking	10	0	Negative
1	3	H31A	Hallway outside 3rd Floor Boy's Restroom	W1	Plaster	Gray	Flaking	10	0.1	Negative
1	3	H31A	Hallway outside 3rd Floor Boy's Restroom	W2	Plaster	Gray	None	0	17.3	Positive
1	3	H31A	Hallway outside 3rd Floor Boy's Restroom	W3	Plaster	Gray	Flaking	10	9.3	Positive
1	3	H31A	Hallway outside 3rd Floor Boy's Restroom	W4	Plaster	Gray	None	0	1.1	Positive
1	3	H31A	Hallway outside 3rd Floor Boy's Restroom	Ceiling	Plaster	Tan	None	0	15.1	Positive
1	3	H31A	Hallway outside 3rd Floor Boy's Restroom	Covebase	Concrete	Gray	None	0	1.6	Positive
1	3	H31A	Hallway outside 3rd Floor Boy's Restroom	Stair Tread	Concrete	Blue	None	0	4.3	Positive
1	3	H31A	Hallway outside 3rd Floor Boy's Restroom	Stair Riser	Concrete	Blue	None	0	7.4	Positive
1	3	H31A	Hallway outside 3rd Floor Boy's Restroom	Stair Stringer	Concrete	Blue	None	0	3.8	Positive
1	3	H31	Hallway outside Classroom 301 to Office 303A	W1	Plaster	Gray	None	0	0	Negative
1	3	H31	Hallway outside Classroom 301 to Office 303A	W2	Plaster	Gray	None	0	17.5	Positive

			Dates: 3/13/2023 to 7/21/2023		Lead-S	afe Certi	fication Asse	essment F	Report	
			Inspector Name and PA License Number:						•	
			Lawrence Jackson 003683		Pai	kway ce	nter City Mic	idle Colle	ge	
			Inspection Company: USA Environmental		E40 Nor	th 12th C	treat Dhilad	alabia D/	10422	
		1	Management Inc		540 NO r	tn 13tn 5	treet, Philad	eipnia, P	19123	
E										
e	F									
m	1									
e	0							_		XRF
n t	o r	Space #	Onsite Room Name	Component	Substrate Material	Paint Color	Description of Damage	Damage Quantity (sf)	XRF Reading (mg/cm2)	(positive/ negative)
1	3	H31	Hallway outside Classroom 301 to Office 303A	W3	Plaster	Gray	None	0	23.9	Positive
1	3	H31	Hallway outside Classroom 301 to Office 303A	W4	Plaster	Gray	None	0	0	Negative
1	3	H31	Hallway outside Classroom 301 to Office 303A	Floor	Concrete	Gray	None	0	1.7	Positive
1	3	H31	Hallway outside Classroom 301 to Office 303A	Ceiling	Plaster	Tan	Peeling	100	21.8	Positive
1	3	H31	Hallway outside Classroom 301 to Office 303A	Lockers	Metal	Red	None	0	0	Negative
1	3	H31	Hallway outside Classroom 301 to Office 303A	Radiators	Metal	Gray	None	0	0.1	Negative
1	3	H31	Hallway outside Classroom 301 to Office 303A	Radiators	Metal	Gray	None	0	2.1	Positive
1	3	H31	Hallway outside Classroom 301 to Office 303A	Radiators	Metal	Gray	None	0	2.4	Positive
1	3	H31	Hallway outside Classroom 301 to Office 303A	Electrical Panel	Metal	Gray	None	0	3.5	Positive
1	3	H31PCS	Pipe/Cable Shaft in Hallway next to Classroom 302	Door	Wood	Varnish	None	0	0	Negative
1	3	H31PCS	Pipe/Cable Shaft in Hallway next to Classroom 302	Door Frame	Wood	Varnish	None	0	0.1	Negative
1	3	H31PCS	Pipe/Cable Shaft in Hallway next to Classroom 302	W1	Concrete	Unpainted	N/A	N/A	N/A	N/A
1	3	H31PCS	Pipe/Cable Shaft in Hallway next to Classroom 302	W2	Terracotta	Unpainted	N/A	N/A	N/A	N/A
1	3	H31PCS	Pipe/Cable Shaft in Hallway next to Classroom 302	W3	Concrete	Unpainted	N/A	N/A	N/A	N/A
1	3	H31PCS	Pipe/Cable Shaft in Hallway next to Classroom 302	W4	Concrete	Unpainted	N/A	N/A	N/A	N/A
1	3	H33	Hallway from Classrooms 304 to 307	W1	Plaster	Gray	None	0	18.7	Positive
1	3	H33	Hallway from Classrooms 304 to 307	W2	Plaster	Gray	None	0	19.3	Positive
1	3	H33	Hallway from Classrooms 304 to 307	W3	Plaster	Gray	None	0	21.3	Positive
1	3	H33	Hallway from Classrooms 304 to 307	W4	Plaster	Gray	None	0	19.4	Positive
1	3	H33	Hallway from Classrooms 304 to 307	Ceiling	Plaster	Tan	Cracking	100	20.1	Positive
1	3	H33	Hallway from Classrooms 304 to 307	Floor	Concrete	Gray	None	0	1.9	Positive
1	3	H33	Hallway from Classrooms 304 to 307	Elevator Door	Metal	White	None	0	0.1	Negative
1	3	H33	Hallway from Classrooms 304 to 307	Elevator Door Frame	Metal	White	None	0	0.2	Negative
1	3	H33	Hallway from Classrooms 304 to 307	Crown Molding	Wood	Varnish	None	0	0	Negative
1	3	H33A	Stairs to Gym	W1	Plaster	Gray	None	0	16.5	Positive
1	3	H33A	Stairs to Gym	W2	Plaster	Gray	None	0	0.1	Negative
1	3	H33A	Stairs to Gym	W3	Plaster	Gray	None	0	19.5	Positive
1	3	H33A	Stairs to Gym	Ceiling	Plaster	Tan	None	0	14.8	Positive
1	3	H33A	Stairs to Gym	Door	Wood	Varnish	None	0	0	Negative
1	3	H33A	Stairs to Gym	Door Frame	Metal	Gray	None	0	0.5	Negative
1	3	H33A	Stairs to Gym	Stair Tread	Concrete	Gray	None	0	0.5	Negative
1	3	H33A	Stairs to Gym	Stair Riser	Concrete	Gray	None	0	1.3	Positive
1	3	H33A	Stairs to Gym	Stair Stringer	Concrete	Gray	None	0	1.4	Positive
1	3	H33A	Stairs to Gym	CoveBase	Concrete	Gray	None	0	5.1	Positive
1	3	H33PCS1	Pipe/Cable Shaft in Hallway next to Stairwell by Classroom 304	Door	Wood	Varnish	None	0	0	Negative

Inspector Name and PA License Number: Lawrence Jackson 003883 Inspection Company: USA Environmental Management Inc				Dates: 3/13/2023 to 7/21/2023		Lead-S	afe Certi	fication Asse	essment l	Report	
Image: Class Company: USA Environmental S40 North 13th Street, Philadelphia, PA 19123 S40 North 13th Street, Philadelphia, Philadelphi				•		Do	dayor Co	ntor City Mid		-	
Namagement inc						Pai	rkway Ce	nter City Mic	iale Colle	ge	
Fig.						540 Nor	th 13th S	troot Philade	olnhia P	19123	
The color The	_	Ι		Management Inc		370 1101	11 13111 0	treet, i illiad	ipilia, i z	13123	
No No No No No No No No	l e	1									
To Space # Onsite Room Name	l l										XRF
1 3 H33PGS1 Classroom 304 Pige-Cable Shaft in Hallway next to Stainvell by No Access No	n	1	Snace #	Onsite Room Name	Component	Substrate Material	Paint Color				
1 3 H33PCS1 Classroom 304 Classroom 305 Classroom 305 Classroom 305 Classroom 305 Classroom 306 Classroom 306 Classroom 306 Classroom 306 Classroom 306 Classroom 307 Classroom 308 Classroom 307 Classroom 308 Classroom 307 Classroom 307 Classroom 307 Classroom 308 Classroom 307 Classroom 308 Classroom 307 Classroom 308 Classroom 307 Classroom 308 Classroom 308 Classroom 308 Classroom	-	-	Space #		•				<u> </u>	, <u> </u>	
1 3 H33PCSI Classroom 304 No Access No Acc	1	3	H33PCS1		Door Frame	vvood	varnisn	none	U	0	negative
1 3 H33PCSI Pipe/Gable Shart in Hallway next to Stainwell by No Access	1	3	H33PCS1		No Access	No Access	No Access	N/A	N/A	No Access	No Access
1 3				Pipe/Cable Shaft in Hallway next to Stairwell by	No Access	No Access	No Access	N/A	N/A		No Access
1 3 H33PCS1 Classroom 304	1	3	H33PCS1							No Access	
1 3 H33PCS1 Classroom 304 Pipe/Cable Shaft in Hallway above Hydration Station Door Wood Varnish None 0 0.1 Negative	1	3	H33PCS1	Classroom 304	No Access	No Access	No Access	N/A	N/A	No Access	No Access
1 3 H33PCS2 near Classroom 304	1	3	H33PCS1		No Access	No Access	No Access	N/A	N/A	No Access	No Access
1 3 H33PCS2 Piper/Cable Shaft in Hallway above Hydration Station Door Frame Wood Varnish None 0 0.3 Negative	1	3	H33PCS2		Door	Wood	Varnish	None	0	0.1	Negative
1 3 H33PCS2 Pipe/Cable Shaft in Hallway above Hydration Station W1 No Access No Access No Access Ni A Ni A Ni A Ni A				Pipe/Cable Shaft in Hallway above Hydration Station	Door Frame	Wood	Varnish	None	0	0.3	Negative
1 3 H33PCS2 Pipe/Cable Shaft in Hallway above Hydration Station near Classroom 304 Pipe/Cable Shaft in Hallway above Hydration Station near Classroom 304 Pipe/Cable Shaft in Hallway above Hydration Station near Classroom 304 Pipe/Cable Shaft in Hallway above Hydration Station near Classroom 304 Pipe/Cable Shaft in Hallway above Hydration Station near Classroom 304 Pipe/Cable Shaft in Hallway next to Stainwell by no Access No Acc				Pipe/Cable Shaft in Hallway above Hydration Station	W1	No Access	No Access	No Access	N/A	N/A	N/A
1 3 H33PCS2 near Classroom 304	1	3	H33PCS2								
1 3 H33PCS2 near Classroom 304 W3 No Access No Acces	1	3	H33PCS2	near Classroom 304	W2	No Access	No Access	No Access	N/A	N/A	N/A
1 3 H33PCS2 Pipe/Cable Shaft in Hallway above Hydration Station M4 No Access	1	3	H33PCS2	, ,	W3	No Access	No Access	No Access	N/A	N/A	N/A
1 3 H33PCS3 Pipe/Cable Shaft in Hallway next to Stairwell by Classroom 307 Door Frame Wood Varnish None 0 0.1 Negative	1	3	H33PCS2		W4	No Access	No Access	No Access	N/A	N/A	N/A
Pipe/Cable Shaft in Hallway next to Stairwell by Classroom 307 No Access				Pipe/Cable Shaft in Hallway next to Stairwell by	Door	Wood	Varnish	None	0	0.1	Negative
1 3 H33PCS3 Pipe/Cable Shaft in Hallway next to Stairwell by Classroom 307 No Access No Acce				Pipe/Cable Shaft in Hallway next to Stairwell by	Door Frame	Wood	Varnish	None	0	0.2	Negative
1 3 H33PCS3 Classroom 307 No Access No Acces				Pipe/Cable Shaft in Hallway next to Stairwell by	No Access	No Access	No Access	N/A	N/A		No Access
1 3 H33PCS3 Classroom 307 No Access No Access <td>1</td> <td>3</td> <td>H33PCS3</td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td>No Access</td> <td></td>	1	3	H33PCS3							No Access	
1 3 H33PCS3 Classroom 307 No Access No Access <td>1</td> <td>3</td> <td>H33PCS3</td> <td>Classroom 307</td> <td>No Access</td> <td>No Access</td> <td>No Access</td> <td>N/A</td> <td>N/A</td> <td>No Access</td> <td>No Access</td>	1	3	H33PCS3	Classroom 307	No Access	No Access	No Access	N/A	N/A	No Access	No Access
1 3 H33PCS3 Classroom 307 No Access No Access <td>1</td> <td>3</td> <td>H33PCS3</td> <td>Classroom 307</td> <td>No Access</td> <td>No Access</td> <td>No Access</td> <td>N/A</td> <td>N/A</td> <td>No Access</td> <td>No Access</td>	1	3	H33PCS3	Classroom 307	No Access	No Access	No Access	N/A	N/A	No Access	No Access
1 3 H32 Hallway from Classrooms 308 to 310 W1 Plaster Gray None 0 19.6 Positive 1 3 H32 Hallway from Classrooms 308 to 310 W2 Plaster Gray None 0 25.6 Positive 1 3 H32 Hallway from Classrooms 308 to 310 W3 Plaster Gray None 0 15.4 Positive 1 3 H32 Hallway from Classrooms 308 to 310 W4 Plaster Gray None 0 28.4 Positive 1 3 H32 Hallway from Classrooms 308 to 310 Ceiling Plaster Tan Cracking 100 19.7 Positive 1 3 H32 Hallway from Classrooms 308 to 310 Floor Concrete Gray None 0 1.5 Positive	1	3	H33PCS3		No Access	No Access	No Access	N/A	N/A	No Access	No Access
1 3 H32 Hallway from Classrooms 308 to 310 W3 Plaster Gray None 0 15.4 Positive 1 3 H32 Hallway from Classrooms 308 to 310 W4 Plaster Gray None 0 28.4 Positive 1 3 H32 Hallway from Classrooms 308 to 310 Ceiling Plaster Tan Cracking 100 19.7 Positive 1 3 H32 Hallway from Classrooms 308 to 310 Floor Concrete Gray None 0 1.5 Positive	1	3	H32				Gray			19.6	
1 3 H32 Hallway from Classrooms 308 to 310 W4 Plaster Gray None 0 28.4 Positive 1 3 H32 Hallway from Classrooms 308 to 310 Ceiling Plaster Tan Cracking 100 19.7 Positive 1 3 H32 Hallway from Classrooms 308 to 310 Floor Concrete Gray None 0 1.5 Positive	-			,		 	,			<u> </u>	
1 3 H32 Hallway from Classrooms 308 to 310 Ceiling Plaster Tan Cracking 100 19.7 Positive 1 3 H32 Hallway from Classrooms 308 to 310 Floor Concrete Gray None 0 1.5 Positive	-			,			,				
1 3 H32 Hallway from Classrooms 308 to 310 Floor Concrete Gray None 0 1.5 Positive		-		,			,		_		
, , , , , , , , , , , , , , , , , , , ,	1			,							
	1	3	H32	Hallway from Classrooms 308 to 310 Hallway from Classrooms 308 to 310	Lockers	Metal	Red	None	0	0	Negative

			Dates: 3/13/2023 to 7/21/2023		Lead-S	afe Certi	fication Asse	essment l	Report	
			Inspector Name and PA License Number:				4 014 141		•	
			Lawrence Jackson 003683		Pai	'kway Ce	nter City Mid	idie Colle	ge	
			Inspection Company: USA Environmental		540 N	41- 4041- 0	Anna A Dhilla d	- l l-: - D/	10400	
			Management Inc		540 Nor	tn 13tn S	treet, Philad	eipnia, P	4 19123	
E										
e	F									
m	1									
е	0						-			XRF
n	o r	Space #	Onsite Room Name	Component	Substrate Material	Paint Color	Description of Damage	Damage Quantity (sf)	XRF Reading (mg/cm2)	(positive/ negative)
1	3	H32	Hallway from Classrooms 308 to 310	Radiator	Metal	Gray	Flaking	2	1.2	Positive
1	3	H32	Hallway from Classrooms 308 to 310	Radiator	Metal	Gray	None	0	0.2	Negative
1	3	H32	Hallway from Classrooms 308 to 310	Radiator	Metal	Gray	Flaking	2	1	Positive
1	3	H32	Hallway from Classrooms 308 to 310	Crown Molding	Wood	Varnish	None	0	0.4	Negative
1	3	H32PCS	Pipe/Cable Shaft in Hallway next to Classroom 308	Door	Wood	Varnish	None	0	0	Negative
1	3	H32PCS	Pipe/Cable Shaft in Hallway next to Classroom 308	Door Frame	Wood	Varnish	None	0	0	Negative
1	3	H32PCS	Pipe/Cable Shaft in Hallway next to Classroom 308	W1	Concrete	Unpainted	N/A	N/A	N/A	N/A
1	3	H32PCS	Pipe/Cable Shaft in Hallway next to Classroom 308	W2	Terracotta	Unpainted	N/A	N/A	N/A	N/A
1	3	H32PCS	Pipe/Cable Shaft in Hallway next to Classroom 308	W3	Terracotta	Unpainted	N/A	N/A	N/A	N/A
1	3	H32PCS	Pipe/Cable Shaft in Hallway next to Classroom 308	W4	No Access	No Access	N/A	N/A	No Access	No Access
1	3	H32A	Hallway outside 3rd Floor Girl's Restroom	W1	Plaster	Gray	None	0	21.9	Positive
1	3	H32A	Hallway outside 3rd Floor Girl's Restroom	W2	Plaster	Gray	None	0	18.8	Positive
1	3	H32A	Hallway outside 3rd Floor Girl's Restroom	W3	Plaster	Gray	None	0	20.6	Positive
1	3	H32A	Hallway outside 3rd Floor Girl's Restroom	W4	Plaster	Gray	None	0	25.9	Positive
1	3	H32A	Hallway outside 3rd Floor Girl's Restroom	Floor	Concrete	Gray	None	0	1.5	Positive
1	3	H32A	Hallway outside 3rd Floor Girl's Restroom	Ceiling	Plaster	White	None	0	20.9	Positive
1	3	H32A	Hallway outside 3rd Floor Girl's Restroom	Stair Tread	Concrete	Gray	None	0	2	Positive
1	3	H32A	Hallway outside 3rd Floor Girl's Restroom	Stair Riser	Concrete	Gray	None	0	6.1	Positive
1	3	H32A	Hallway outside 3rd Floor Girl's Restroom	Stair Stringer	Concrete	Gray	None	0	5.4	Positive
1	3	H32A	Hallway outside 3rd Floor Girl's Restroom	Elevator Door	Metal	Pink	None	0	0	Negative
1	3	H32A	Hallway outside 3rd Floor Girl's Restroom	Elevator Door Frame	Metal	Pink	Flaking	5	0.1	Negative
1	3	H32A	Hallway outside 3rd Floor Girl's Restroom	Crown Molding	Wood	Varnish	None	0	0.3	Negative
1	2	212B	Pipe Shaft adjacent to 2nd Floor Boy's Restroom	Door	Wood	Brown	None	0	0.1	Negative
1	2	212B	Pipe Shaft adjacent to 2nd Floor Boy's Restroom	Door Frame	Wood	Brown	None	0	0.1	Negative
1	2	212B	Pipe Shaft adjacent to 2nd Floor Boy's Restroom	No Access	No Access	No Access	No Access	No Access	No Access	No Access
1	2	212B	Pipe Shaft adjacent to 2nd Floor Boy's Restroom	No Access	No Access	No Access	No Access	No Access	No Access	No Access
1	2	212B	Pipe Shaft adjacent to 2nd Floor Boy's Restroom	No Access	No Access	No Access	No Access	No Access	No Access	No Access
1	2	212B	Pipe Shaft adjacent to 2nd Floor Boy's Restroom	No Access	No Access	No Access	No Access	No Access	No Access	No Access
1	2	212	Boy's Restroom adjacent to Office Suite 201	W1	Plaster	White	Flaking	5	13.9	Positive
1	2	212	Boy's Restroom adjacent to Office Suite 201	W2	Plaster	White	Flaking	15	0	Negative
1	2	212	Boy's Restroom adjacent to Office Suite 201	W3 W4	Plaster	White	Flaking	25	12.6	Positive
1	2	212	Boy's Restroom adjacent to Office Suite 201		Plaster Concrete	White White	Flaking	40	13.3 11.4	Positive
1	2	212 212	Boy's Restroom adjacent to Office Suite 201	Ceiling Floor	Concrete	vvnite Grav	None None	0	0.9	Positive Positive
1	2	212	Boy's Restroom adjacent to Office Suite 201	Door	Wood	Gray Brown	None	0	0.9	Negative
1	2	212	Boy's Restroom adjacent to Office Suite 201 Boy's Restroom adjacent to Office Suite 201	Door Frame	Wood	Brown	None	0	0.1	Negative
1	2	212	Boy's Restroom adjacent to Office Suite 201 Boy's Restroom adjacent to Office Suite 201	Window Casing	Wood	Brown	None	0	0.2	Negative
1		212	Doy's Restroom adjacent to Office Suite 201	I WILLOW Casing	vvoou	DIUWII	INUITE	l 0	U.5	inegative

			Dates: 3/13/2023 to 7/21/2023		Lead-S	afe Certi	fication Asse	essment l	Report	
			Inspector Name and PA License Number:				4 0:4 14:		•	
			Lawrence Jackson 003683		Pai	rkway Ce	nter City Mic	idle Colle	ge	
			Inspection Company: USA Environmental		540 N	41- 4041- 0	4 4. Dl. !!!	- l l-: - D	10100	
			Management Inc		540 Nor	tn 13tn S	treet, Philad	eipnia, P <i>i</i>	19123	
E										
	F									
e m	[
e	0									XRF
n	0						Description of	Damage	XRF Reading	(positive/
t	r	Space #	Onsite Room Name	Component	Substrate Material	Paint Color	Damage	Quantity (sf)	(mg/cm2)	negative)
1	2	212	Boy's Restroom adjacent to Office Suite 201	Radiator	Metal	Gray	Flaking	20	0	Negative
1	2	212	Boy's Restroom adjacent to Office Suite 201	Drain Pipe	Metal	Gray	Flaking	8	10	Positive
1	2	212A	Pipe Chase in Boy's Restroom adjacent to Office Suite 201	Door	Wood	Varnish	None	0	0.1	Negative
1	2	212A	Pipe Chase in Boy's Restroom adjacent to Office Suite 201	Door Frame	Wood	Varnish	None	0	0.1	Negative
1	2	212A	Pipe Chase in Boys Restroom adjacent to Office Suite 201	W1	Terracotta	Unpainted	N/A	N/A	N/A	N/A
1	2	212A	Pipe Chase in Boy's Restroom adjacent to Office Suite 201	W2	Plaster	White	None	0	10	Positive
1	2	212A	Pipe Chase in Boy's Restroom adjacent to Office Suite 201	W3	Plaster	White	None	0	10	Positive
1	2	212A	Pipe Chase in Boy's Restroom adjacent to Office Suite 201	W4	Terracotta	Unpainted	N/A	N/A	N/A	N/A
1	2	201D	Office Suite 201 Common Area	W1	Wood	White	None	0	0	Negative
1	2	201D	Office Suite 201 Common Area	W2	Wood	White	None	0	0	Negative
1	2	201D	Office Suite 201 Common Area	W3	Plaster	White	None	0	0	Negative
1	2	201D	Office Suite 201 Common Area	W4	Plaster	White	None	0	0.2	Negative
1	2	201D	Office Suite 201 Common Area	Ceiling	Plaster	Tan	Flaking	50	23.4	Positive
1	2	201D	Office Suite 201 Common Area	Floor	9 x 9 floor tile	Unpainted	N/A	N/A	N/A	N/A
1	2	201D	Office Suite 201 Common Area	Door	Wood	Varnish	None	0	0	Negative
1	2	201D	Office Suite 201 Common Area	Door Frame	Wood	Varnish	None	0	0	Negative
1	2	201E	Office Suite 201 Common Area Pipe Chase	W1	Terracotta	Unpainted	N/A	N/A	N/A	N/A
1	2	201E	Office Suite 201 Common Area Pipe Chase	W2	Plaster	Tan	None	0	20.9	Positive
1	2	201E	Office Suite 201 Common Area Pipe Chase	W3 W4	Plaster	Tan	None N/A	0 N/A	15.3 N/A	Positive N/A
1	2	201E	Office Suite 201 Common Area Pipe Chase	Door	Terracotta Wood	Unpainted Varnish	None	0 0	0.1	
1	2	201E 201E	Office Suite 201 Common Area Pipe Chase	Door Frame	Wood	Varnish	None	0	0.1	Negative Negative
1	2	201E 201E	Office Suite 201 Common Area Pipe Chase Office Suite 201 Common Area Pipe Chase	Floor	Linoleum	Unpainted	N/A	N/A	N/A	Negative N/A
1	2	201E	Office Suite 201 Common Area Pipe Chase	Ceiling	Plaster	Tan	No Access	No Access	No Access	No Access
1	2	201E	Office Suite 201 Right Office	W1	Wood	Green	None	0	0	Negative
1	2	201A 201A	Office Suite 201 Right Office	W2	Plaster	Green	Cracking	50	23.1	Positive
1	2	201A	Office Suite 201 Right Office	W3	Plaster	Green	Cracking	5	26.1	Positive
1	2	201A	Office Suite 201 Right Office	W4	Plaster	Green	Flaking	5	0.1	Negative
1	2	201A	Office Suite 201 Right Office	Ceiling	Plaster	Tan	Flaking	50	15.9	Positive
1	2	201A	Office Suite 201 Right Office	Radiator	Metal	Gray	Flaking	12	4.3	Positive
1	2	201A	Office Suite 201 Right Office	Floor	9 x 9 floor tile	Unpainted	N/A	N/A	N/A	N/A
1	2	201A	Office Suite 201 Right Office	Door	Wood	Varnish	None	0	0.1	Negative
1	2	201A	Office Suite 201 Right Office	Door Frame	Wood	Varnish	None	0	0.2	Negative

			Dates: 3/13/2023 to 7/21/2023		Lead-S	afe Certi	fication Asse	essment F	Report	
			Inspector Name and PA License Number:		_				•	
			Lawrence Jackson 003683		Pai	rkway Ce	nter City Mic	ldle Colle	ge	
			Inspection Company: USA Environmental							
			Management Inc		540 Nor	th 13th S	treet, Philad	elphia, P <i>l</i>	A 19123	
Е										
I	_									
e	F									
m e										XRF
'n	0						Description of	Damage	XRF Reading	(positive/
t	r	Space #	Onsite Room Name	Component	Substrate Material	Paint Color	Damage	Quantity (sf)	(mg/cm2)	negative)
1	2	201A	Office Suite 201 Right Office	Window Sill	Wood	Varnish	None	0	0	Negative
1	2	201A	Office Suite 201 Right Office	Window Casing	Wood	Varnish	None	0	0.4	Negative
1	2	201A	Office Suite 201 Right Office	Window Apron	Wood	Varnish	None	0	0.2	Negative
1	2	201B	Office Suite 201 Center Right Office	W1	Wood	White	None	0	0.1	Negative
1	2	201B	Office Suite 201 Center Right Office	W2	Plaster	White	Flaking	5	0.2	Negative
1	2	201B	Office Suite 201 Center Right Office	W3	Wood	White	None	0	0.2	Negative
1	2	201B	Office Suite 201 Center Right Office	W4	Wood	White	None	0	0	Negative
1	2	201B	Office Suite 201 Center Right Office	Ceiling	Plaster	Tan	Flaking	25	18.3	Positive
1	2	201B	Office Suite 201 Center Right Office	Floor	9 x 9 floor tile	Unpainted	N/A	N/A	N/A	N/A
1	2	201B	Office Suite 201 Center Right Office	Door	Wood	Varnish	None	0	0.1	Negative
1	2	201B	Office Suite 201 Center Right Office	Door Frame	Wood	Varnish	None	0	0	Negative
1	2	201B	Office Suite 201 Center Right Office	Window Casing	Wood	Varnish	None	0	0.1	Negative
1	2	201B	Office Suite 201 Center Right Office	Window Sill	Wood	Varnish	None	0	0.1	Negative
1	2	201B	Office Suite 201 Center Right Office	Window Apron	Wood	Varnish	None	0	0.1	Negative
1	2	201B	Office Suite 201 Center Right Office	Radiator	Metal	Gray	Flaking	8	0.1	Negative
1	2	201B	Office Suite 201 Center Right Office	Drain Pipe	Metal	White	Flaking	4	22.4	Positive
1	2	201C	Office Suite 201 Center Left Office	W1	Wood	Blue	None	0	0	Negative
1	2	201C	Office Suite 201 Center Left Office	W2 W3	Plaster Plaster	Blue Blue	Flaking Flaking	10	0.4 25	Negative Positive
1	2	201C	Office Suite 201 Center Left Office	W4	Wood	Blue	None	0	0	Negative
1	2	201C 201C	Office Suite 201 Center Left Office	Ceiling	Plaster	Tan	Efflorescence	15	20.8	Positive
1	2	201C 201C	Office Suite 201 Center Left Office	Floor	9 x 9 floor tile	Unpainted	N/A	N/A	N/A	N/A
1	2	201C 201C	Office Suite 201 Center Left Office Office Suite 201 Center Left Office	Door	Wood	Varnish	None	0	0	Negative
1	2	201C	Office Suite 201 Center Left Office	Door Frame	Wood	Varnish	None	0	0.1	Negative
1	2	201C	Office Suite 201 Center Left Office	Window Casing	Wood	Varnish	None	0	0.1	Negative
1	2	201C	Office Suite 201 Center Left Office	Window Sill	Wood	Varnish	None	0	0.2	Negative
1	2	201C	Office Suite 201 Center Left Office	Window Apron	Wood	Varnish	None	0	0.1	Negative
1	2	201C	Office Suite 201 Center Left Office	Radiator	Metal	Gray	Flaking	5	3.6	Positive
1	2	2010	Office Suite 201 Left Office	W1	Plaster	Blue	None	0	6.6	Positive
1	2	201	Office Suite 201 Left Office	W2	Plaster	Blue	None	0	8.2	Positive
1	2	201	Office Suite 201 Left Office	W3	Wood	Blue	None	0	0	Negative
1	2	201	Office Suite 201 Left Office	W4	Wood	Blue	None	0	0	Negative
1	2	201	Office Suite 201 Left Office	Floor	9 x 9 floor tile	Unpainted	N/A	N/A	N/A	N/A
1	2	201	Office Suite 201 Left Office	Ceiling	Plaster	Tan	Flaking	15	18.9	Positive
1	2	201	Office Suite 201 Left Office	Door	Wood	Varnish	None	0	0.1	Negative
1	2	201	Office Suite 201 Left Office	Door Frame	Wood	Varnish	None	0	0.1	Negative
1	2	201	Office Suite 201 Left Office	Window Casing	Wood	Varnish	None	0	0.3	Negative
1	2	201	Office Suite 201 Left Office	Window Sill	Wood	Varnish	None	0	0.3	Negative

			Dates: 3/13/2023 to 7/21/2023		Lead-S	afe Certi	fication Asse	essment F	Report	
			Inspector Name and PA License Number:		_		4 014 5.51			
			Lawrence Jackson 003683		Pai	rkway Ce	nter City Mic	idie Colle	ge	
			Inspection Company: USA Environmental							
			Management Inc		540 Nor	th 13th S	treet, Philad	elphia, P <i>l</i>	A 19123	
Е							•	i •		
1										
е	F									
m e	0									XRF
n	0						Description of	Damage	XRF Reading	(positive/
t	r	Space #	Onsite Room Name	Component	Substrate Material	Paint Color	Damage	Quantity (sf)	(mg/cm2)	negative)
1	2	201	Office Suite 201 Left Office	Window Apron	Wood	Varnish	None	0	0.1	Negative
1	2	201	Office Suite 201 Left Office	Radiator	Metal	Gray	None	0	0.9	Positive
1	2	201	Office Suite 201 Left Office	Wall Baseboard	Plaster	Brown	None	0	5.8	Positive
1	2	S26	Fire Tower adjacent to Classroom 202	W1	Brick	White	None	0	7.6	Positive
1	2	S26	Fire Tower adjacent to Classroom 202	W2	Brick	White	None	0	6.7	Positive
1	2	S26	Fire Tower adjacent to Classroom 202	W3	Brick	White	None	0	5.8	Positive
1	2	S26	Fire Tower adjacent to Classroom 202	W4	Brick	White	None	0	9.8	Positive
1	2	S26	Fire Tower adjacent to Classroom 202	Ceiling	Concrete	White	None	0	11.4	Positive
1	2	S26	Fire Tower adjacent to Classroom 202	Floor	Concrete	Gray	None	0	3.4	Positive
1	2	S26	Fire Tower adjacent to Classroom 202	Door	Metal	Brown	None	0	0.1	Negative
1	2	S26	Fire Tower adjacent to Classroom 202	Door Frame	Metal	Brown	None	0	0.4	Negative
1	2	S26	Fire Tower adjacent to Classroom 202	Security Gate	Metal	Brown	Flaking	100	5.9	Positive
1	2	S26	Fire Tower adjacent to Classroom 202	Drain Pipe	Metal	Brown	Flaking	24	1	Positive
1	2	S26 S26	Fire Tower adjacent to Classroom 202 Fire Tower adjacent to Classroom 202	Handrail Stair Riser	Metal Concrete	Brown Gray	Chipping	10 0	2.5	Positive Positive
1	2	S26	Fire Tower adjacent to Classroom 202	Stair Treads	Concrete	Gray	None None	0	0.2	Negative
1	2	S26	Fire Tower adjacent to Classroom 202	Stair Stringer	Concrete	Gray	None	0	2.3	Positive
1	2	202	Classroom 202	W1	Plaster	White	None	0	9.4	Positive
1	2	202	Classroom 202	W2	Plaster	White	None	0	2.5	Positive
1	2	202	Classroom 202	W3	Plaster	White	Cracking	8	25.6	Positive
1	2	202	Classroom 202	W4	Plaster	White	Flaking	50	11.7	Positive
1	2	202	Classroom 202	Ceiling	Plaster	Tan	Flaking	250	22.1	Positive
1	2	202	Classroom 202	Floor	Wood	Unpainted	N/A	N/A	N/A	N/A
1	2	202	Classroom 202	Door	Wood	Varnish	None	0	0	Negative
1	2	202	Classroom 202	Door Frame	Wood	Varnish	None	0	0.1	Negative
1	2	202	Classroom 202	Window Casing	Wood	Varnish	None	0	0.2	Negative
1	2	202	Classroom 202	Window Sill	Wood	Varnish	None	0	0.2	Negative
1	2	202	Classroom 202	Window Apron	Wood	Varnish	None	0	0.1	Negative
1	2	202	Classroom 202	Baseboard	Wood	Brown	Cracking	10	0.3	Negative
1	2	202	Classroom 202	Radiator	Metal	Gray	Flaking	10	3.4	Positive
1	2	202	Classroom 202	Radiator	Metal	Gray	Flaking	15	3.5	Positive
1	2	203	Classroom 203	W1	Plaster	White	None	0	11.5	Positive
1	2	203	Classroom 203	W2	Plaster	Blue	Flaking	10	14.5	Positive
1	2	203	Classroom 203	W3	Plaster	White	None	0	21.7	Positive
1	2	203	Classroom 203	W4	Plaster	White	Flaking	20	5.4	Positive
1	2	203	Classroom 203	Ceiling	Plaster	Tan	None	0	20.8	Positive
1	2	203	Classroom 203	Floor	Wood	Unpainted	N/A	N/A	N/A	N/A
1	2	203	Classroom 203	Baseboard	Wood	Varnish	None	0	0.1	Negative

			Dates: 3/13/2023 to 7/21/2023		Lead-S	afe Certi	fication Asse	essment F	Report	
			Inspector Name and PA License Number:		Pai	kway Co	nter City Mid	Idla Calla		
			Lawrence Jackson 003683		rai	kway Ce	Titel City wild	idle Colle	ge	
			Inspection Company: USA Environmental Management Inc		540 Nor	th 13th S	treet, Philade	elphia, PA	A 19123	
E	_						,			
e m e n	F I 0 0						Description of	Damage	XRF Reading	XRF (positive/
t	r	Space #	Onsite Room Name	Component	Substrate Material	Paint Color	Damage .	Quantity (sf)	(mg/cm2)	negative)
1	2	203	Classroom 203	Door	Wood	Varnish	None	0	0	Negative
1	2	203	Classroom 203	Door Frame	Wood	Varnish	None	0	0	Negative
1	2	203	Classroom 203	Window Casing	Wood	Varnish	None	0	0.3	Negative
1	2	203	Classroom 203	Window Sill	Wood	Varnish	None	0	0.2	Negative
1	2	203	Classroom 203	Window Apron	Wood	Varnish	None	0	0.1	Negative
1	2	203	Classroom 203	Radiator	Metal	Gray	Flaking	10	4.5	Positive
1	2	203	Classroom 203	Radiator	Metal	Gray	Flaking	10	3.7	Positive
1	2	204	Classroom 204	W1	Plaster	Gray	None	0	10.8	Positive
1	2	204	Classroom 204	W2	Plaster	Gray	None	0	13.7	Positive
1	2	204	Classroom 204	W3	Plaster	Gray	None	0	21.4	Positive
1	2	204	Classroom 204	W4	Plaster	Gray	None	0	21.4	Positive
1	2	204	Classroom 204	Ceiling	Plaster	Tan	Flaking	300	19.6	Positive
1	2	204	Classroom 204	Floor	Wood	Unpainted	N/A	N/A	N/A	N/A
1	2	204	Classroom 204	Baseboard	Wood	Brown	None	0	0.1	Negative
1	2	204	Classroom 204	Chair Rail	Wood	Varnish	None	0	0.2	Negative
1	2	204	Classroom 204	Door	Wood	Varnish	None	0	0	Negative
1	2	204	Classroom 204	Door Frame	Wood	Varnish	None	0	0	Negative
1	2	204	Classroom 204	Window Casing	Wood	Varnish	None	0	0.4	Negative
1	2	204	Classroom 204	Window Sill	Wood	Varnish	None	0	0.3	Negative
1	2	204	Classroom 204	Window Apron	Wood	Varnish	None	0	0.1	Negative
1	2	204	Classroom 204	Radiator	Metal	Gray	Flaking	10	2.5	Positive
1	2	204	Classroom 204	Radiator	Metal	Gray	Flaking	5	5.4	Positive
1	2	S24	Stairwell adjacent to Main Office	W1	Plaster	Gray	None	0	15.9	Positive
1	2	S24	Stairwell adjacent to Main Office	W2	Plaster	Gray	None	0	18.2	Positive
1	2	S24	Stairwell adjacent to Main Office	W3	Plaster	Gray	None	0	19.5	Positive
1	2	S24	Stairwell adjacent to Main Office	Ceiling	Plaster	Gray	None	0	18.9	Positive
1	2	S24	Stairwell adjacent to Main Office	Floor	Concrete	Gray	None	0	0.8	Positive
1	2	S24	Stairwell adjacent to Main Office	Stair Treads	Concrete	Gray	None	0	0.4	Negative
1	2	S24	Stairwell adjacent to Main Office	Stair Riser	Concrete	Gray	None	0	1.5	Positive
1	2	S24	Stairwell adjacent to Main Office	Stair Stringer	Concrete	Gray	None	0	1.1	Positive
1	2	S24	Stairwell adjacent to Main Office	Post	Metal	Brown	None	0	10.1	Positive
1	2	S24	Stairwell adjacent to Main Office	Spindle	Metal	Brown	None	0	7.1	Positive
1	2	S24	Stairwell adjacent to Main Office	Door	Metal	Brown	None	0	0	Negative
1	2	S24	Stairwell adjacent to Main Office	Door Frame	Metal	Brown	None	0	7.2	Positive
1	2	S24	Stairwell adjacent to Main Office	Radiator	Metal	Gray	None	0	1.1	Positive
1	2	204E	Main Distribution Frame Room located in Stairwell adjacent to Main Office	Door	Wood	Varnish	None	0	0.1	Negative

			Dates: 3/13/2023 to 7/21/2023		Lead-S	afe Certi	fication Asse	essment l	Report	
			Inspector Name and PA License Number:				4 014 141		-	
			Lawrence Jackson 003683		Pai	rkway Ce	nter City Mid	idie Colle	ge	
			Inspection Company: USA Environmental		= 40 N				10100	
			Management Inc		540 Nor	th 13th S	treet, Philade	elphia, P <i>i</i>	A 19123	
Е										
I	_									
e m	F									
e	0									XRF
n	0						Description of	Damage	XRF Reading	(positive/
t	r	Space #	Onsite Room Name	Component	Substrate Material	Paint Color	Damage	Quantity (sf)	(mg/cm2)	negative)
1	2	204E	Main Distribution Frame Room located in Stairwell adjacent to Main Office	Door Frame	Wood	Varnish	None	0	0.1	Negative
1	2	204E	Main Distribution Frame Room located in Stairwell adjacent to Main Office	No Access	No Access	No Access	No Access	No Access	No Access	No Access
1	2	204E	Main Distribution Frame Room located in Stairwell adjacent to Main Office	No Access	No Access	No Access	No Access	No Access	No Access	No Access
1	2	204E	Main Distribution Frame Room located in Stairwell adjacent to Main Office	No Access	No Access	No Access	No Access	No Access	No Access	No Access
1	2	204E	Main Distribution Frame Room located in Stairwell adjacent to Main Office	No Access	No Access	No Access	No Access	No Access	No Access	No Access
1	2	204C	Main Office	W1	Plaster	Gray	None	0	9.1	Positive
1	2	204C	Main Office	W1	Plaster	Purple	None	0	27.2	Positive
1	2	204C	Main Office	W2	Plaster	Purple	None	0	21.6	Positive
1	2	204C	Main Office	W3	Plaster	Gray	None	0	20.7	Positive
1	2	204C	Main Office	W3	Plaster	Purple	None	0	26.3	Positive
1	2	204C	Main Office	W4	Plaster	Gray	None	0	24.4	Positive
1	2	204C	Main Office	W4	Plaster	Purple	None	0	24.2	Positive
1	2	204C	Main Office	Ceiling Floor	Plaster	Tan	None N/A	0	19.2 N/A	Positive N/A
1	2	204C	Main Office Main Office	Door	12 x 12 Floor Tile Wood	Unpainted Varnish	N/A None	N/A 0	N/A 0	
1	2	204C	Main Office	Door Frame	Wood	Varnish	None	0	0.1	Negative Negative
1	2	204C 204C	Main Office	Window Casing	Wood	Varnish	None	0	0.1	Negative
1	2	204C 204C	Main Office	Window Casing	Wood	Varnish	None	0	0.3	Negative
1	2	204C	Main Office	Window Apron	Wood	Varnish	None	0	0.2	Negative
1	2	204C	Main Office	Chair Rail	Wood	Varnish	None	0	0.2	Negative
1	2	204C	Main Office	Radiator	Metal	Gray	Flaking	8	3.2	Positive
1	2	204C	Main Office	Baseboard	Wood	Brown	None	0	0.2	Negative
1	2	204B	Main Office Copy Room	W1	Plaster	White	None	0	28.6	Positive
1	2	204B	Main Office Copy Room	W2	Plaster	White	None	0	28.3	Positive
1	2	204B	Main Office Copy Room	W3	Plaster	White	None	0	27.8	Positive
1	2	204B	Main Office Copy Room	W4	Plaster	White	None	0	28.2	Positive
1	2	204B	Main Office Copy Room	Ceiling	Plaster	Tan	None	0	18	Positive
1	2	204B	Main Office Copy Room	Floor	12 x 12 Floor Tile	Unpainted	N/A	N/A	N/A	N/A
1	2	204B	Main Office Copy Room	Baseboard	Wood	Brown	None	0	0.1	Negative
1	2	204B	Main Office Copy Room	Chair Rail	Wood	Varnish	None	0	0.1	Negative
1	2	204B	Main Office Copy Room	Radiator	Metal	Grey	Flaking	3	2.8	Positive
1	2	204B	Main Office Copy Room	Door	Wood	Varnish	None	0	0.1	Negative
1	2	204B	Main Office Copy Room	Door frame	Wood	Varnish	None	0	0.1	Negative
1	2	204B	Main Office Copy Room	Window Casing	Wood	Varnish	None	0	0.2	Negative

			Dates: 3/13/2023 to 7/21/2023		Lead-S	afe Certi	fication Asse	essment l	Report	
			Inspector Name and PA License Number:		Pai	kway Co	nter City Mic	Idla Calla		
			Lawrence Jackson 003683		гаі	Kway Ce	inter City wiit	idle Colle	ye	
			Inspection Company: USA Environmental Management Inc		540 Nor	th 13th S	treet, Philad	elphia, PA	A 19123	
E I e	F									
m e n	0 0						Description of	Damage	XRF Reading	XRF (positive/
l "t	r	Space #	Onsite Room Name	Component	Substrate Material	Paint Color	Damage	Quantity (sf)	(mg/cm2)	negative)
1	2	204B	Main Office Copy Room	Window Sill	Wood	Varnish	None	0	0.1	Negative
1	2	204B	Main Office Copy Room	Window Apron	Wood	Varnish	None	0	0.2	Negative
1	2	204F	Main Office Closet with Sink	Door	Wood	Varnish	None	0	0.1	Negative
1	2	204F	Main Office Closet with Sink	Door Frame	Wood	Varnish	None	0	0.1	Negative
1	2	204F	Main Office Closet with Sink	W1	Plaster	Green	None	0	21.3	Positive
1	2	204F	Main Office Closet with Sink	W2	Plaster	Green	None	0	19.3	Positive
1	2	204F	Main Office Closet with Sink	W3	Plaster	Green	None	0	22.1	Positive
1	2	204F	Main Office Closet with Sink	W4	No Access	Green	None	0	No Access	No Access
1	2	204F	Main Office Closet with Sink	Floor	12 x 12 Floor Tile	Unpainted	N/A	N/A	N/A	N/A
1	2	204F	Main Office Closet with Sink	Ceiling	Plaster	Green	None	0	No Access	No Access
1	2	204G	Main Office Storage Closet	Door	Wood	Varnish	None	0	0.1	Negative
1	2	204G	Main Office Storage Closet	Door Frame	Wood	Varnish	None	0	0.1	Negative
1	2	204G	Main Office Storage Closet	W1	Plaster	Tan	None	0	21.1	Positive
1	2	204G	Main Office Storage Closet	W2	Plaster	Tan	None	0	21.4	Positive
1	2	204G	Main Office Storage Closet	W3	Plaster	Tan	None	0	21.8	Positive
1	2	204G	Main Office Storage Closet	W4	Plaster	Tan	None	0	26.7	Positive
1	2	204G	Main Office Storage Closet	Shelf	Wood	Varnish	None	0	0.1	Negative
1	2	204A	Principal's Office	W1	Plaster	Brown	None	0	26.4	Positive
1	2	204A	Principal's Office	W1	Plaster	Yellow	None	0	26.3	Positive
1	2	204A	Principal's Office	W2	Plaster	Brown	None	0	26	Positive
1	2	204A	Principal's Office	W2	Plaster	Yellow	None	0	28.6	Positive
1	2	204A	Principal's Office	W2	Plaster	Red	None	0	25.7	Positive
1	2	204A	Principal's Office	W3	Plaster	Yellow	None	0	20.6	Positive
1	2	204A	Principal's Office	W3	Plaster	Brown	None	0	31	Positive
1	2	204A	Principal's Office	W4	Plaster	Yellow	None	0	24.9	Positive
1	2	204A	Principal's Office	W4	Plaster	Brown	None	0	25	Positive
1	2	204A	Principal's Office	W4	Plaster	Red	None	0	22.9	Positive
1	2	204A	Principal's Office	Ceiling	Plaster	Tan	None	0	26.5	Positive
1	2	204A	Principal's Office	Floor	12 x 12 Floor Tile	Unpainted	N/A	N/A	N/A	N/A
1	2	204A	Principal's Office	Baseboard	Wood	Brown	None	0	0.1	Negative
1	2	204A	Principal's Office	Chair Rail	Wood	Brown	None	0	0.2	Negative
1	2	204A	Principal's Office	Radiator	Metal	Gray	None	0	0	Negative
1	2	204A	Principal's Office	Radiator	Metal	Gray	Flaking	10	0.7	Positive
1	2	204A	Principal's Office	Door	Wood	Varnish	None	0	0	Negative
1	2	204A	Principal's Office	Door frame	Wood	Varnish	None	0	0.1	Negative
1	2	204A	Principal's Office	Window Casing	Wood	Brown	None	0	0.4	Negative

			Dates: 3/13/2023 to 7/21/2023	Lead-Safe Certification Assessment Report						
			Inspector Name and PA License Number:		D	.1	4 O'4 NI'-	1-11- 0-11-		
			Lawrence Jackson 003683		Pai	rkway Ce	nter City Mic	iale Colle	ge	
			Inspection Company: USA Environmental Management Inc		540 Nor	th 13th S	treet, Philad	elphia, PA	A 19123	
E I e	F						,			
m e n t	0 0 r	Space #	Onsite Room Name	Component	Substrate Material	Paint Color	Description of Damage	Damage Quantity (sf)	XRF Reading (mg/cm2)	XRF (positive/ negative)
1	2	204A	Principal's Office	Window Apron	Wood	Brown	None	0	0.1	Negative
1	2	204A	Principal's Office	Window Apron	Wood	Brown	None	0	0.1	Negative
1	2	204D	Principal's Office Restroom	W1	Plaster	Red	None	0	22.8	Positive
1	2	204D	Principal's Office Restroom	W2	Plaster	Yellow	None	0	0.1	Negative
1	2	204D	Principal's Office Restroom	W3	Plaster	Red	None	0	2.4	Positive
1	2	204D	Principal's Office Restroom	W4	Plaster	Yellow	None	0	22.7	Positive
1	2	204D	Principal's Office Restroom	Door	Wood	Varnish	None	0	0	Negative
1	2	204D	Principal's Office Restroom	Door Frame	Wood	Brown	None	0	2.2	Positive
1	2	204D	Principal's Office Restroom	Window Casing	Wood	Brown	None	0	0	Negative
1	2	204D	Principal's Office Restroom	Window Sill	Wood	Brown	None	0	0.2	Negative
1	2	204D	Principal's Office Restroom	Window Apron	Wood	Brown	None	0	0	Negative
1	2	204D	Principal's Office Restroom	Baseboard	Wood	Brown	None	0	0.2	Negative
1	2	204D	Principal's Office Restroom	Ceiling	No Access	No Access	No Access	No Access	No Access	No Access
1	2	204D	Principal's Office Restroom	Floor	12 x 12 Floor Tile	Unpainted	N/A	N/A	N/A	N/A
1	2	204H	Principal's Office Closet	W1	Plaster	Multi	None	0	2.5	Positive
1	2	204H	Principal's Office Closet	W2	Plaster	Multi	None	0	3	Positive
1	2	204H	Principal's Office Closet	W3	Plaster	Multi	None	0	2.5	Positive
1	2	204H	Principal's Office Closet	W4	Plaster	Multi	None	0	No Access	No Access
1	2	204H	Principal's Office Closet	Ceiling	Plaster	Tan	None	0	None	No Access
1	2	204H	Principal's Office Closet	Door Frame	Wood	Varnish	None	0	0.1	Negative
1	2	213	Auditorium Balcony	W1	Plaster	White	Cracking	20	20.2	Positive
1	2	213	Auditorium Balcony	W3	Plaster	White	Efflorescence	40	19.6	Positive
1	2	213	Auditorium Balcony	W4	Plaster	White	Cracking	60	21.1	Positive
1	2	213	Auditorium Balcony	Ceiling	Plaster	White	Flaking	20	0.9	Positive
1	2	213	Auditorium Balcony	Floor	Linoleum	Unpainted	N/A N/A	N/A	N/A N/A	N/A
1	2	213	Auditorium Balcony	Baseboard	Wood	Unpainted		N/A		N/A
1	2	213	Auditorium Balcony	Window Casing	Wood Wood	Varnish	None	0	15.6 13.8	Positive
1	2	213	Auditorium Balcony	Window Aprop	Wood	Varnish	None	0	14.2	Positive
1	2	213	Auditorium Balcony	Window Apron		Varnish	None	0	14.2	Positive
1	2	213	Auditorium Balcony	Side Panel Door	Plaster Wood	White White	None None	0	14.0	Positive Positive
1	2	213	Auditorium Balcony					0	-	
1	2	213	Auditorium Balcony	Door Frame Kick Plate	Wood Wood	White White	None None	0	16.8 11.4	Positive Positive
1	2	213	Auditorium Balcony					100	11.4	
1	2	213	Auditorium Balcony	Cornice	Plaster	White	Efflorescence	3		Positive
1	2	213A	Auditorium Balcony Projection Room	W1 W2	Plaster	White	Chipping		19.9 22.7	Positive
1	2	213A	Auditorium Balcony Projection Room	W3	Plaster Plaster	White White	Flaking	10	19.7	Positive Positive
1	2	213A	Auditorium Balcony Projection Room				Flaking	5	20.2	
1	2	213A	Auditorium Balcony Projection Room	W4	Plaster	White	Flaking	5	20.2	Positive

Inspector Name and PA License Number: Lawrence Jackson 003683 Inspection Company: USA Environmental Management Inc S40 North 13th Street, Philadelphia, PA 19123	Lead-Safe Certification Assessment Report						
Inspection Company: USA Environmental Management Inc							
F							
1	XRF (positive/ negative)						
1 2 213A Auditorium Balcony Projection Room Door Wood Varnish None 0 0 0 0 1 2 213A Auditorium Balcony Projection Room Door Frame Wood Varnish None 0 0 0 0 1 2 213A Auditorium Balcony Projection Room Baseboard Concrete Gray None 0 0 0 0 1 1 2 213A Auditorium Balcony Projection Room Drain Pipe Metal White Flaking 5 0 0 0 1 2 213A Auditorium Balcony Projection Room Drain Pipe Metal White Flaking 5 0 0 0 1 2 205 IMC 205 W2 Plaster White None 0 32 2 2 2 2 2 2 2 2	Positive						
1	N/A						
1	Negative						
1	Negative						
1	Negative						
1	Negative						
1 2 205 IMC 205 W3 Plaster White None 0 32 1 2 205 IMC 205 W4 Plaster White None 0 27.7 1 2 205 IMC 205 Ceiling Plaster Tan None 0 19.6 1 2 205 IMC 205 Door Wood Unpainted N/A N/A N/A 1 2 205 IMC 205 Door Wood Varnish None 0 0 0 1 2 205 IMC 205 Door Frame Wood Varnish None 0 0 0 1 2 205 IMC 205 Window Sill Wood Varnish None 0 0.4 1 2 205 IMC 205 Window Sill Wood Varnish None 0 0.1 1 2 205 IMC 205 Radiator<	Positive						
1	Positive						
1	Positive						
1	Positive						
1 2 205 IMC 205 Door Wood Varnish None 0 0 0 1 2 205 IMC 205 Door Frame Wood Varnish None 0 0.2 1 2 205 IMC 205 MC 205 Window Casing Wood Varnish None 0 0.4 1 2 205 IMC 205 MC 205 Window Sill Wood Varnish None 0 0.3 1 2 205 IMC 205 Window Sill Wood Varnish None 0 0.3 1 2 205 IMC 205 Window Apron Wood Varnish None 0 0.1 1 2 205 IMC 205 Radiator Metal Gray Flaking 5 2.9 1 2 205 IMC 205 Radiator Metal Gray Flaking 2 2.5 1 2 205 IMC 205 Radiator Metal Gray Flaking 4 0.3 1 2 205 IMC 205 Radiator Metal Gray Flaking 4 0.3 1 2 205 IMC 205 Radiator Metal Gray Flaking 4 0.3 1 2 205 IMC 205 Radiator Metal Gray Flaking 4 0.3 1 2 205 IMC 205 Radiator Metal Gray Flaking 4 0.3 1 2 205 IMC 205 Radiator Metal Gray Flaking 4 0.3 1 2 205 IMC 205 Radiator Metal Gray Flaking 4 0.3 1 2 205 IMC 205 Radiator Metal Gray Flaking 4 0.3 1 2 205 IMC 205 Radiator Metal Gray Flaking 4 0.3 1 2 205 IMC 205 MC 2	Positive						
1 2 205 IMC 205 Door Wood Varnish None 0 0 0 1 2 205 IMC 205 Door Frame Wood Varnish None 0 0.2 1 2 205 IMC 205 Window Casing Wood Varnish None 0 0.4 1 2 205 IMC 205 Window Sill Wood Varnish None 0 0.3 1 2 205 IMC 205 Window Sill Wood Varnish None 0 0.3 1 2 205 IMC 205 Window Apron Wood Varnish None 0 0.1 1 2 205 IMC 205 Radiator Metal Gray Flaking 5 2.9 1 2 205 IMC 205 Radiator Metal Gray Flaking 2 2.5 1 2 205 IMC 205 Radiator Metal Gray Flaking 4 0.3 1 2 205 IMC 205 Radiator Metal Gray Flaking 4 0.3 1 2 205 IMC 205 Radiator Metal Gray Flaking 4 0.3 1 2 205 IMC 205 Radiator Metal Gray Flaking 4 0.3 1 2 205 IMC 205 Radiator Metal Gray Flaking 4 0.3 1 2 205 IMC 205 Radiator Metal Gray Flaking 4 0.3 1 2 205 IMC 205 Radiator Metal Gray Flaking 4 0.3 1 2 205 IMC 205 Radiator Metal Gray Flaking 4 0.3 1 2 205 IMC 205 Radiator Metal Gray Flaking 4 0.3 1 2 205 IMC 205 MC 205 Grice Wood Brown None 0 0.1 1 2 205 IMC 205 Office W1 Plaster White Cracking 10 20.7 1 2 205 IMC 205 Office W2 Plaster White Cracking 1 18.9 1 2 205 IMC 205 Office Floor Wood Unpainted N/A N/A N/A 1 2 205 IMC 205 Office Celling Plaster Tan Flaking 15 23.1 1 2 205 IMC 205 Office Door Frame Wood Varnish None 0 0.1	N/A						
1 2 205 IMC 205 Window Casing Wood Varnish None 0 0.4 1 2 205 IMC 205 Window Sill Wood Varnish None 0 0.3 1 2 205 IMC 205 Window Apron Wood Varnish None 0 0.1 1 2 205 IMC 205 Radiator Metal Gray Flaking 5 2.9 1 2 205 IMC 205 Radiator Metal Gray Flaking 2 2.5 1 2 205 IMC 205 Radiator Metal Gray Flaking 4 0.3 1 2 205 IMC 205 Radiator Metal Gray Flaking 4 0.3 1 2 205 IMC 205 Radiator Metal Gray Flaking 4 0.3 1 2 205 IMC 205 Grown Molding Wood Brown None 0 3.7 1 2 205 IMC 205 Baseboard Wood Brown None 0 0.1 1 2 205A IMC 205 Office W1 Plaster White Cracking 10 20.7 1 2 205A IMC 205 Office W2 Plaster White Cracking 20 25.4 1 2 205A IMC 205 Office W3 Plaster White Cracking 20 25.4 1 2 205A IMC 205 Office W4 Plaster White Cracking 1 18.9 1 2 205A IMC 205 Office Floor Wood Unpainted N/A N/A N/A 1 2 205A IMC 205 Office Door Wood Varnish None 0 0.1 1 2 205A IMC 205 Office Door Door Wood Varnish None 0 0.1 1 2 205A IMC 205 Office Door Door Wood Varnish None 0 0.1 1 2 205A IMC 205 Office Door Door Wood Varnish None 0 0.1 1 2 205A IMC 205 Office Door Door Wood Varnish None 0 0.1 1 2 205A IMC 205 Office Door Door Wood Varnish None 0 0.1 2 205A IMC 205 Office Door Door Wood Varnish None 0 0.1 3 3 3 3 3 3 3 3 3	Negative						
1 2 205 IMC 205 Window Casing Wood Varnish None 0 0.4 1 2 205 IMC 205 Window Sill Wood Varnish None 0 0.3 1 2 205 IMC 205 Window Apron Wood Varnish None 0 0.1 1 2 205 IMC 205 Radiator Metal Gray Flaking 5 2.9 1 2 205 IMC 205 Radiator Metal Gray Flaking 2 2.5 1 2 205 IMC 205 Radiator Metal Gray Flaking 4 0.3 1 2 205 IMC 205 Radiator Metal Gray Flaking 4 0.3 1 2 205 IMC 205 Radiator Metal Gray Flaking 4 0.3 1 2 205 IMC 205 Grown Molding Wood Brown None 0 3.7 1 2 205 IMC 205 Baseboard Wood Brown None 0 0.1 1 2 205A IMC 205 Office W1 Plaster White Cracking 10 20.7 1 2 205A IMC 205 Office W2 Plaster White Cracking 20 25.4 1 2 205A IMC 205 Office W3 Plaster White Cracking 20 25.4 1 2 205A IMC 205 Office W4 Plaster White Cracking 1 18.9 1 2 205A IMC 205 Office Floor Wood Unpainted N/A N/A N/A 1 2 205A IMC 205 Office Door Wood Varnish None 0 0.1 1 2 205A IMC 205 Office Door Door Wood Varnish None 0 0.1 1 2 205A IMC 205 Office Door Door Wood Varnish None 0 0.1 1 2 205A IMC 205 Office Door Door Wood Varnish None 0 0.1 1 2 205A IMC 205 Office Door Door Wood Varnish None 0 0.1 1 2 205A IMC 205 Office Door Door Wood Varnish None 0 0.1 2 205A IMC 205 Office Door Door Wood Varnish None 0 0.1 3 3 3 3 3 3 3 3 3	Negative						
1 2 205 IMC 205 Window Apron Wood Varnish None 0 0.1 1 2 205 IMC 205 Radiator Metal Gray Flaking 5 2.9 1 2 205 IMC 205 Radiator Metal Gray Flaking 2 2.5 1 2 205 IMC 205 Radiator Metal Gray Flaking 4 0.3 1 2 205 IMC 205 Radiator Metal Gray Flaking 4 0.3 1 2 205 IMC 205 Radiator Metal Gray Flaking 4 0.3 1 2 205 IMC 205 Baseboard Wood Brown None 0 0.1 1 2 205A IMC 205 Office W1 Plaster White Cracking 10 20.7 1 2 205A IMC 205 Office W3	Negative						
1 2 205 IMC 205 Window Apron Wood Varnish None 0 0.1 1 2 205 IMC 205 Radiator Metal Gray Flaking 5 2.9 1 2 205 IMC 205 Radiator Metal Gray Flaking 2 2.5 1 2 205 IMC 205 Radiator Metal Gray Flaking 4 0.3 1 2 205 IMC 205 Radiator Metal Gray Flaking 4 0.3 1 2 205 IMC 205 Radiator Metal Gray Flaking 4 0.3 1 2 205 IMC 205 Baseboard Wood Brown None 0 0.1 1 2 205A IMC 205 Office W1 Plaster White Cracking 10 20.7 1 2 205A IMC 205 Office W3	Negative						
1 2 205 IMC 205 Radiator Metal Gray Flaking 5 2.9 1 2 205 IMC 205 Radiator Metal Gray Flaking 2 2.5 1 2 205 IMC 205 Radiator Metal Gray Flaking 4 0.3 1 2 205 IMC 205 Crown Molding Wood Brown None 0 3.7 1 2 205 IMC 205 Baseboard Wood Brown None 0 0.1 1 2 205A IMC 205 Office W1 Plaster White Cracking 10 20.7 1 2 205A IMC 205 Office W2 Plaster White Cracking 20 25.4 1 2 205A IMC 205 Office W4 Plaster White Cracking 1 18.9 1 2 205A IMC 205 Office	Negative						
1 2 205 IMC 205 Radiator Metal Gray Flaking 2 2.5 1 2 205 IMC 205 Radiator Metal Gray Flaking 4 0.3 1 2 205 IMC 205 Crown Molding Wood Brown None 0 3.7 1 2 205 IMC 205 Baseboard Wood Brown None 0 0.1 1 2 205A IMC 205 Office W1 Plaster White Cracking 10 20.7 1 2 205A IMC 205 Office W2 Plaster White Cracking 20 25.4 1 2 205A IMC 205 Office W3 Plaster White None 0 22.9 1 2 205A IMC 205 Office Floor Wood Upainted N/A N/A N/A 1 2 205A IMC 205 Office	Positive						
1 2 205 IMC 205 Radiator Metal Gray Flaking 4 0.3 1 2 205 IMC 205 Crown Molding Wood Brown None 0 3.7 1 2 205 IMC 205 Baseboard Wood Brown None 0 0.1 1 2 205A IMC 205 Office W1 Plaster White Cracking 10 20.7 1 2 205A IMC 205 Office W2 Plaster White Cracking 20 25.4 1 2 205A IMC 205 Office W3 Plaster White None 0 22.9 1 2 205A IMC 205 Office W4 Plaster White Cracking 1 18.9 1 2 205A IMC 205 Office Floor Wood Unpainted N/A N/A N/A 1 2 205A IMC 205 Office <td>Positive</td>	Positive						
1 2 205 IMC 205 Crown Molding Wood Brown None 0 3.7 1 2 205 IMC 205 Baseboard Wood Brown None 0 0.1 1 2 205A IMC 205 Office W1 Plaster White Cracking 10 20.7 1 2 205A IMC 205 Office W2 Plaster White Cracking 20 25.4 1 2 205A IMC 205 Office W3 Plaster White None 0 22.9 1 2 205A IMC 205 Office W4 Plaster White Cracking 1 18.9 1 2 205A IMC 205 Office Floor Wood Unpainted N/A N/A N/A 1 2 205A IMC 205 Office Door Wood Varnish None 0 0 1 2 205A IMC 205 Office <td>Negative</td>	Negative						
1 2 205 IMC 205 Baseboard Wood Brown None 0 0.1 1 2 205A IMC 205 Office W1 Plaster White Cracking 10 20.7 1 2 205A IMC 205 Office W2 Plaster White Cracking 20 25.4 1 2 205A IMC 205 Office W3 Plaster White None 0 22.9 1 2 205A IMC 205 Office W4 Plaster White Cracking 1 18.9 1 2 205A IMC 205 Office Floor Wood Unpainted N/A N/A N/A 1 2 205A IMC 205 Office Ceiling Plaster Tan Flaking 15 23.1 1 2 205A IMC 205 Office Door Wood Varnish None 0 0.1	Positive						
1 2 205A IMC 205 Office W1 Plaster White Cracking 10 20.7 1 2 205A IMC 205 Office W2 Plaster White Cracking 20 25.4 1 2 205A IMC 205 Office W3 Plaster White None 0 22.9 1 2 205A IMC 205 Office W4 Plaster White Cracking 1 18.9 1 2 205A IMC 205 Office Floor Wood Unpainted N/A N/A N/A 1 2 205A IMC 205 Office Ceiling Plaster Tan Flaking 15 23.1 1 2 205A IMC 205 Office Door Wood Varnish None 0 0 1 2 205A IMC 205 Office Door Frame Wood Varnish None 0 0.1	Negative						
1 2 205A IMC 205 Office W2 Plaster White Cracking 20 25.4 1 2 205A IMC 205 Office W3 Plaster White None 0 22.9 1 2 205A IMC 205 Office W4 Plaster White Cracking 1 18.9 1 2 205A IMC 205 Office Floor Wood Unpainted N/A N/A N/A 1 2 205A IMC 205 Office Ceiling Plaster Tan Flaking 15 23.1 1 2 205A IMC 205 Office Door Wood Varnish None 0 0 1 2 205A IMC 205 Office Door Frame Wood Varnish None 0 0.1	Positive						
1 2 205A IMC 205 Office W3 Plaster White None 0 22.9 1 2 205A IMC 205 Office W4 Plaster White Cracking 1 18.9 1 2 205A IMC 205 Office Floor Wood Unpainted N/A N/A N/A 1 2 205A IMC 205 Office Ceiling Plaster Tan Flaking 15 23.1 1 2 205A IMC 205 Office Door Wood Varnish None 0 0 1 2 205A IMC 205 Office Door Frame Wood Varnish None 0 0.1	Positive						
1 2 205A IMC 205 Office W4 Plaster White Cracking 1 18.9 1 2 205A IMC 205 Office Floor Wood Unpainted N/A N/A N/A 1 2 205A IMC 205 Office Ceiling Plaster Tan Flaking 15 23.1 1 2 205A IMC 205 Office Door Wood Varnish None 0 0 1 2 205A IMC 205 Office Door Frame Wood Varnish None 0 0.1	Positive						
1 2 205A IMC 205 Office Floor Wood Unpainted N/A N/A N/A 1 2 205A IMC 205 Office Ceiling Plaster Tan Flaking 15 23.1 1 2 205A IMC 205 Office Door Wood Varnish None 0 0 1 2 205A IMC 205 Office Door Frame Wood Varnish None 0 0.1	Positive						
1 2 205A IMC 205 Office Ceiling Plaster Tan Flaking 15 23.1 1 2 205A IMC 205 Office Door Wood Varnish None 0 0 1 2 205A IMC 205 Office Door Frame Wood Varnish None 0 0.1	N/A						
1 2 205A IMC 205 Office Door Wood Varnish None 0 0 1 2 205A IMC 205 Office Door Frame Wood Varnish None 0 0.1	Positive						
1 2 205A IMC 205 Office Door Frame Wood Varnish None 0 0.1	Negative						
	Negative						
	Positive						
1 2 205A IMC 205 Office Window Sill Wood Varnish None 0 0.2	Negative						
1 2 205A IMC 205 Office Window Apron Wood Varnish None 0 0.1	Negative						
1 2 205A IMC 205 Office Baseboard Wood Brown None 0 0.7	Positive						
1 2 205A IMC 205 Office Radiator Metal Gray Flaking 5 3.4	Positive						
1 2 S23 Stairwell adjacent to Classroom 206 W1 Plaster Gray None 0 16.7	Positive						
1 2 S23 Stairwell adjacent to Classroom 206 W2 Plaster Gray None 0 21.3	Positive						
1 2 S23 Stairwell adjacent to Classroom 206 W3 Plaster Gray None 0 19	Positive						

			Dates: 3/13/2023 to 7/21/2023	Lead-Safe Certification Assessment Report						
			Inspector Name and PA License Number:				4 014 141		•	
			Lawrence Jackson 003683		Pai	'kway Ce	nter City Mic	idie Colle	ge	
			Inspection Company: USA Environmental							
			Management Inc		540 Nor	th 13th S	treet, Philad	elphia, P <i>i</i>	A 19123	
E I							·			
е	F									
m e	I									XRF
n	0						Description of	Damage	XRF Reading	(positive/
t	r	Space #	Onsite Room Name	Component	Substrate Material	Paint Color	Damage	Quantity (sf)	(mg/cm2)	negative)
1	2	S23	Stairwell adjacent to Classroom 206	Ceiling	Plaster	White	None	0	16.4	Positive
1	2	S23	Stairwell adjacent to Classroom 206	Door	Metal	Brown	None	0	0	Negative
1	2	S23	Stairwell adjacent to Classroom 206	Door Frame	Metal	Brown	None	0	6.4	Positive
1	2	S23	Stairwell adjacent to Classroom 206	Radiator	Metal	Gray	Flaking	6	0.6	Negative
1	2	S23	Stairwell adjacent to Classroom 206	Stair Treads	Concrete	Gray	None	0	0.5	Negative
1	2	S23	Stairwell adjacent to Classroom 206	Stair Riser	Concrete	Gray	None	0	1.3	Positive
1	2	S23	Stairwell adjacent to Classroom 206	Stair Stringer	Concrete	Gray	None	0	0.9	Positive
1	2	S23	Stairwell adjacent to Classroom 206	Floor	Concrete	Gray	None	0	1.4	Positive
1	2	S23	Stairwell adjacent to Classroom 206	Post	Metal	Brown	None	0	10.9	Positive
1	2	S23	Stairwell adjacent to Classroom 206	Spindle	Metal	Gray	None	0	8.8	Positive
1	2	S23	Stairwell adjacent to Classroom 206	Panel Box	Metal	Gray	None	0	0	Negative
1	2	206	Classroom 206	W1	Plaster	Gray	Cracking	5	16.6	Positive
1	2	206	Classroom 206	W2	Plaster	Gray	Cracking	80	15.7	Positive
1	2	206	Classroom 206	W3	Plaster	Gray	None	0	9.1	Positive
1	2	206	Classroom 206	W4	Plaster	Gray	None	0	22.5	Positive
1	2	206	Classroom 206	Ceiling	Plaster	Tan	Flaking	300	18	Positive
1	2	206	Classroom 206	Floor	Wood	Unpainted	N/A	N/A	N/A	N/A
1	2	206	Classroom 206	Door	Wood	Varnish	None	0	0	Negative
1	2	206	Classroom 206	Door Frame	Wood	Varnish	None	0	0	Negative
1	2	206	Classroom 206	Window Sill	Wood Wood	Varnish	None	0	0	Negative
1	2	206	Classroom 206	Window Casing	Wood	Varnish Varnish	None None	0	0.3 0.1	Negative
1	2	206	Classroom 206	Window Apron	Metal		None	0	0.1	Negative
	2	206	Classroom 206	Radiator Radiator	Metal	Gray	Flaking	6	2.5	Negative Positive
1	2	206 206	Classroom 206 Classroom 206	Baseboard	Wood	Gray Brown	Cracking	6	0	Negative
1	2	206	Classroom 207	W1	Plaster	Gray	None	0	22.6	Positive
1	2	207	Classroom 207	W2	Plaster	Gray	None	0	12.1	Positive
1	2	207	Classroom 207	W3	Plaster	Gray	None	0	0	Negative
1	2	207	Classroom 207	W4	Plaster	Gray	None	0	14.3	Positive
1	2	207	Classroom 207	Ceiling	Plaster	Tan	Flaking	500	20.8	Positive
1	2	207	Classroom 207	Floor	Wood	Unpainted	N/A	N/A	N/A	N/A
1	2	207	Classroom 207	Door	Wood	Varnish	None	0	0.1	Negative
1	2	207	Classroom 207	Door Frame	Wood	Varnish	None	0	0	Negative
1	2	207	Classroom 207	Window Casing	Wood	Varnish	None	0	0.6	Negative
1	2	207	Classroom 207	Window Sill	Wood	Brown	None	0	0.2	Negative
1	2	207	Classroom 207	Window Apron	Wood	Brown	None	0	0.2	Negative
1	2	207	Classroom 207	Radiator	Metal	Black	None	0	0	Negative
1	2	207	Classroom 207	Radiator	Metal	Black	Flaking	3	1.5	Positive

			Dates: 3/13/2023 to 7/21/2023	Lead-Safe Certification Assessment Report						
			Inspector Name and PA License Number:		Pai	rkway Co	nter City Mid	Idla Calla	ue	
			Lawrence Jackson 003683		ı aı	Kway Oc	inter Only Wild	idie Oolie	ge	
			Inspection Company: USA Environmental Management Inc		540 Nor	th 13th S	treet, Philade	elphia. PA	19123	
E			Wanagement inc		7 17 1131				1.0.20	
ī										
е	F									
m	l I									VDE
e n	0						Description of	Damage	XRF Reading	XRF (positive/
t "	r	Space #	Onsite Room Name	Component	Substrate Material	Paint Color	Damage	Quantity (sf)	(mg/cm2)	negative)
1	2	207	Classroom 207	Baseboard	Wood	Brown	None	0	0.1	Negative
1	2	208	Classroom 208	W1	Plaster	Gray	None	0	24.5	Positive
1	2	208	Classroom 208	W2	Plaster	Gray	None	0	10.7	Positive
1	2	208	Classroom 208	W3	Plaster	Gray	None	0	0.3	Negative
1	2	208	Classroom 208	W4	Plaster	Gray	None	0	13.4	Positive
1	2	208	Classroom 208	Floor	Wood	Unpainted	N/A	N/A	N/A	N/A
1	2	208	Classroom 208	Ceiling	Plaster	Tan	Cracking	100	25.1	Positive
1	2	208	Classroom 208	Door	Wood	Varnish	None	0	0.1	Negative
1	2	208	Classroom 208	Door Frame	Wood	Varnish	None	0	0.1	Negative
1	2	208	Classroom 208	Window Casing	Wood	Varnish	None	0	0.3	Negative
1	2	208	Classroom 208	Window Sill	Wood	Varnish	None	0	0.3	Negative
1	2	208	Classroom 208	Window Apron	Wood	Varnish	None	0	0	Negative
1	2	208	Classroom 208	Radiator	Metal	Gray	Flaking	6	3	Positive
1	2	208	Classroom 208	Radiator	Metal	Gray	Flaking	5	3.2	Positive
1	2	208	Classroom 208	Baseboard	Wood	Brown	None	0	0.1	Negative
1	2	S25	Fire Tower adjacent to Classroom 208	W1	Brick	White	None	0	7.8	Positive
1	2	S25	Fire Tower adjacent to Classroom 208	W2 W3	Brick	White	None	0	9.6	Positive
1	2	S25	Fire Tower adjacent to Classroom 208	W4	Brick Brick	White White	None None	0	11.1 7.1	Positive Positive
1	2	S25	Fire Tower adjacent to Classroom 208	Ceiling	Concrete	White	None	0	13.9	Positive
1	2	S25 S25	Fire Tower adjacent to Classroom 208 Fire Tower adjacent to Classroom 208	Floor	Concrete	Gray	None	0	2	Positive
1	2	S25	Fire Tower adjacent to Classroom 208	Door	Metal	Brown	None	0	0	Negative
1	2	S25	Fire Tower adjacent to Classroom 208	Door Frame	Metal	Brown	None	0	0.4	Negative
1	2	S25	Fire Tower adjacent to Classroom 208	Security Gate	Metal	Brown	Flaking	100	32	Positive
1	2	S25	Fire Tower adjacent to Classroom 208	Drain Pipe	Metal	Brown	Flaking	24	26.7	Positive
<u> </u>			•	Handrail	Metal	Brown	Chipping	8	4.5	Positive
1	2	S25	Fire Tower adjacent to Classroom 208							
1	2	S25	Fire Tower adjacent to Classroom 208	Stair Riser	Concrete	Gray	None	0	1.7	Positive
1	2	S25	Fire Tower adjacent to Classroom 208	Stair Tread	Concrete	Gray	None	0	0.7	Positive
1	2	S25	Fire Tower adjacent to Classroom 208	Stair Stringer	Concrete	Gray	None	0	1.4	Positive
1	2	209A	Nurse's Main Office	W1	Plaster	White	None	0	19.5	Positive
1	2	209A	Nurse's Main Office	W2	Plaster	White	None	0	18.9	Positive
1	2	209A	Nurse's Main Office	W3	Plaster	White	Cracking	10	18.7	Positive
1	2	209A	Nurse's Main Office	W4	Plaster	White	None	0	0.2	Negative
1	2	209A	Nurse's Main Office	Ceiling	Plaster	Tan	Cracking	5	19.7	Positive
1	2	209A	Nurse's Main Office	Floor	Wood	Unpainted	N/A	N/A	N/A	N/A
1	2	209A	Nurse's Main Office	Door	Wood	Varnish	None	0	0	Negative
1	2	209A	Nurse's Main Office	Door Frame	Wood	Varnish	None	0	0.1	Negative

			Dates: 3/13/2023 to 7/21/2023	Lead-Safe Certification Assessment Report						
			Inspector Name and PA License Number:		Da	d O -		Idla Oalla		
			Lawrence Jackson 003683		Par	rkway Ce	nter City Mic	iale Colle	ge	
			Inspection Company: USA Environmental Management Inc		540 Nor	th 13th S	treet, Philad	elphia, PA	A 19123	
E I							·			
e	F									
m e										XRF
n	0						Description of	Damage	XRF Reading	(positive/
t	r	Space #	Onsite Room Name	Component	Substrate Material	Paint Color	Damage	Quantity (sf)	(mg/cm2)	negative)
1	2	209A	Nurse's Main Office	Window Casing	Wood	Varnish	None	0	0.4	Negative
1	2	209A	Nurse's Main Office	Window Sill	Wood	Varnish	None	0	0.2	Negative
1	2	209A	Nurse's Main Office	Window Apron	Wood	Varnish	None	0	0.2	Negative
1	2	209A	Nurse's Main Office	Radiator	Metal	Gray	Flaking	5	0	Negative
1	2	209A	Nurse's Main Office	Baseboard	Wood Wood	Brown Brown	None None	0	0.5	Negative
1	2	209A	Nurse's Main Office	Crown Molding Drain Pipe	Metal	Brown	None	0	0.5	Negative
1	2	209A 209	Nurse's Main Office Nurse's Student Patient Room	W1	Plaster	White	Cracking	20	0.5	Negative Negative
1	2	209	Nurse's Student Patient Room Nurse's Student Patient Room	W1 W2	Plaster	White	Cracking	5	22.4	Positive
1	2	209	Nurse's Student Patient Room	W2 W3	Plaster	White	Cracking	10	0.4	Negative
1	2	209	Nurse's Student Patient Room	W4	Plaster	White	Cracking	15	20	Positive
1	2	209	Nurse's Student Patient Room	Ceiling	Plaster	White	Flaking	100	0.6	Negative
1	2	209	Nurse's Student Patient Room	Floor	Wood	Unpainted	N/A	N/A	N/A	N/A
1	2	209	Nurse's Student Patient Room	Door	Wood	Varnish	None	0	0	Negative
1	2	209	Nurse's Student Patient Room	Door Frame	Wood	Varnish	None	0	0	Negative
1	2	209	Nurse's Student Patient Room	Window Casing	Wood	Varnish	None	0	0.4	Negative
1	2	209	Nurse's Student Patient Room	Window Sill	Wood	Varnish	None	0	0.2	Negative
1	2	209	Nurse's Student Patient Room	Window Apron	Wood	Varnish	None	0	0.2	Negative
1	2	209	Nurse's Student Patient Room	Baseboard	Wood	Brown	None	0	0.3	Negative
1	2	209	Nurse's Student Patient Room	Radiator	Metal	Gray	Flaking	10	0	Negative
1	2	209	Nurse's Student Patient Room	Drain Pipe	Metal	White	Flaking	5	25.3	Positive
1	2	209B	Nurse's Office Restroom	W1	Plaster	White	None	0	0.2	Negative
1	2	209B	Nurse's Office Restroom	W2	Plaster	White	None	0	0	Negative
1	2	209B	Nurse's Office Restroom	W3	Plaster	White	None	0	0	Negative
1	2	209B	Nurse's Office Restroom	W4	Plaster	White	Flaking	2	0	Negative
1	2	209B	Nurse's Office Restroom	Floor	Concrete	Gray	Flaking	4	0.2	Negative
1	2	209B	Nurse's Office Restroom	Ceiling	Plaster	White	None	0	No Access	N/A
1	2	209B	Nurse's Office Restroom	Door	Wood	Varnish	None	0	0	Negative
1	2	209B	Nurse's Office Restroom	Door Frame	Wood	Varnish	None	0	0	Negative
1	2	209B	Nurse's Office Restroom	Window Casing	Wood	Varnish	None	0	0.1	Negative
1	2	209B	Nurse's Office Restroom	Window Sill	Wood	Varnish	None	0	0	Negative
1	2	210C	Vestibule outside Nurse's Office and Staff Lounge	W1	Plaster	White	Flaking	5	25.9	Positive
1	2	210C	Vestibule outside Nurse's Office and Staff Lounge	W2	Plaster	White	Flaking	2	20.1	Positive
1	2	210C	Vestibule outside Nurse's Office and Staff Lounge	W3	Plaster	White	None	0	0.1	Negative
1	2	210C	Vestibule outside Nurse's Office and Staff Lounge	W4	Plaster	White	None	0	20.3	Positive
1	2	210C	Vestibule outside Nurse's Office and Staff Lounge	Ceiling	Plaster	Tan	Flaking	40	20.3	Positive
1	2	210C	Vestibule outside Nurse's Office and Staff Lounge	Floor	Wood	Unpainted	N/A None	N/A 0	N/A 0	N/A Nogativo
1	2	210C	Vestibule outside Nurse's Office and Staff Lounge	Baseboard	Wood	Brown	None	1 0		Negative

To Space # Onsite Room Name				Dates: 3/13/2023 to 7/21/2023	Lead-Safe Certification Assessment Report						
						Par	dayay Ca	ntor City Mid	Idla Calla		
Second Color						Pai	kway ce	Titel City wild	idle Colle	ge	
Component Substrate Material Paint Color Damage Quantity (sf) Component Component Substrate Material Paint Color Damage Quantity (sf) Component Comp						540 Nor	th 13th S	treet, Philad	elphia, PA	A 19123	
No. Component Substrate Material Paint Color Description of Damage Component Component Component Substrate Material Paint Color Damage Countity (sf) (mg/cm2)	Е							•	'		
No. Component Substrate Material Paint Color Description of Damage Component Component Component Substrate Material Paint Color Damage Countity (sf) (mg/cm2)	I	_									
No. Component Substrate Material Paint Color Damage Quantity (ef) Component Component Substrate Material Paint Color Damage Quantity (ef) Component Component Component Substrate Material Paint Color Damage Quantity (ef) Component	1 -										
n t c Space # Onsite Room Name Component Substrate Material Paint Color Description of Damage (puantity (rff) (mg/cm²) XRF Reading (mg/cm²) (positive (mg/cm²) 1 2 2 210 Vestbule outside Nurse's Office and Staff Lounge Door Frame Wood Varnish None 0 0.1 Negative (mg/cm²) 1 2 2 210 Staff Lounge adjacent to Nurse's Office W2 Plaster White Flaking 5 4.9 Positive Nurse's Office 1 2 2 210 Staff Lounge adjacent to Nurse's Office W3 Plaster White None 0 0 0.23.2 Positive Nurse's Office 1 2 2 210 Staff Lounge adjacent to Nurse's Office Ceiling Plaster White None 0 0 Negative Nurse's Office 1 2 2 210 Staff Lounge adjacent to Nurse's Office Door Wood Varnish None 0 0.1 Negative Nurse's Office 1 2 2 210 Staff Lounge adjacent to Nurse's Office Wood Wood Varnish None 0 0.1 Negative Nurse's Office	1										YRF
The content of the	•	l						Description of	Damage	XRF Reading	(positive/
1	t	_	Space #	Onsite Room Name	Component	Substrate Material	Paint Color				negative)
1	1	2	210C	Vestibule outside Nurse's Office and Staff Lounge	Door Frame	Wood	Varnish	None	0	0.1	Negative
1	1	2	210	Staff Lounge adjacent to Nurse's Office	W1	Plaster	White		5	19.6	Positive
1 2 210 Staff Lounge adjacent to Nurse's Office Calling Plaster Tan Flaking 100 0.3 Negativ 1 2 210 Staff Lounge adjacent to Nurse's Office Door Wood Varnish None 0 0.1 Negativ 1 2 210 Staff Lounge adjacent to Nurse's Office Door Wood Varnish None 0 0.1 Negativ 1 2 210 Staff Lounge adjacent to Nurse's Office Door Wood Varnish None 0 0.1 Negativ 1 2 210 Staff Lounge adjacent to Nurse's Office Window Casing Wood Varnish None 0 0.3 Negativ 1 2 210 Staff Lounge adjacent to Nurse's Office Window Sill Wood Varnish None 0 0.4 Negativ 1 2 210 Staff Lounge adjacent to Nurse's Office Window Native Window Varnish None 0 0.4 Negativ 1 2 210 Staff Lounge adjacent to Nurse's Office Baseboard Wood Varnish None 0 0.1 Negativ 1 2 210 Staff Lounge adjacent to Nurse's Office Baseboard Wood Varnish None 0 0.1 Negativ 1 2 210 Staff Lounge adjacent to Nurse's Office Radiator Metal Gray Flaking 10 0.9 Positiv 1 2 210 Staff Lounge adjacent to Nurse's Office Radiator Metal White Flaking 10 0.9 Positiv 1 2 210 Staff Lounge adjacent to Nurse's Office Radiator Metal White Flaking 10 0.9 Positiv 1 2 210 Staff Lounge adjacent to Nurse's Office Restroom W1 Plaster White Flaking 5 0.5 Negativ 1 2 210 Staff Lounge adjacent to Nurse's Office Restroom W2 Plaster White Flaking 5 0.5 Negativ 1 2 210 Staff Lounge adjacent to Nurse's Office Restroom W2 Plaster White Flaking 20 6.1 Positiv 1 2 210 Staff Lounge adjacent to Nurse's Office Restroom W3 Plaster White Flaking 20 6.1 Positiv 1 2 210 Staff Lounge adjacent to Nurse's Office Restroom W3 Plaster White Flaking 20 6.1 Positiv 1 2 210 Staff Lounge adjacent to Nurse's Office Restroom Radiator Metal Gray Flaking 2	1	2	210	Staff Lounge adjacent to Nurse's Office	W2	Plaster	White	Flaking	5	4.9	Positive
1	1	2	210	Staff Lounge adjacent to Nurse's Office	_	Plaster	White	None	0	23.2	Positive
1 2 210 Staff Lounge adjacent to Nurse's Office Door Frame Wood Varnish None 0 0.1 Negativ	1	2	210	Staff Lounge adjacent to Nurse's Office	W4	Plaster	White	None	0	0	Negative
1 2 210 Staff Lounge adjacent to Nurse's Office Window Casing Wood Varnish None 0 0.1 Negativ	1	2	210	Staff Lounge adjacent to Nurse's Office	Ceiling	Plaster	Tan	Flaking	100	0.3	Negative
1	1	2	210	Staff Lounge adjacent to Nurse's Office			Varnish	None			Negative
1 2 210 Staff Lounge adjacent to Nurse's Office Window Still Wood Varnish None 0 0.4 Negativ	1	2	210	Staff Lounge adjacent to Nurse's Office		Wood	Varnish				Negative
1	1			Staff Lounge adjacent to Nurse's Office		Wood				0.3	Negative
1	1			U j	Window Sill					-	Negative
1	1			ŭ ,					_		Negative
1	1		210	Staff Lounge adjacent to Nurse's Office	Baseboard	Wood				0.1	Negative
1	1										Negative
1 2 210A Staff Lounge adjacent to Nurse's Office Restroom W1 Plaster White Flaking 5 0.5 Negative 1 2 210A Staff Lounge adjacent to Nurse's Office Restroom W2 Plaster White Flaking 20 6.1 Positive 1 2 210A Staff Lounge adjacent to Nurse's Office Restroom W4 Plaster White None 0 12.4 Positive 1 2 210A Staff Lounge adjacent to Nurse's Office Restroom Celling Plaster White None 0 12.4 Positive 1 2 210A Staff Lounge adjacent to Nurse's Office Restroom Floor Ceramic Unpainted N/A	1			ŭ ,			,				Positive
1 2 210A Staff Lounge adjacent to Nurse's Office Restroom W2 Plaster White Flaking 20 6.1 Positive 1 2 210A Staff Lounge adjacent to Nurse's Office Restroom W3 Plaster White Flaking 4 0 Negative 1 2 210A Staff Lounge adjacent to Nurse's Office Restroom W4 Plaster White None 0 0 12.4 Positive 1 2 210A Staff Lounge adjacent to Nurse's Office Restroom Celling Plaster White No Access N/A	1										Positive
1 2 210A Staff Lounge adjacent to Nurse's Office Restroom W3 Plaster White Flaking 4 0 Negative 1 2 210A Staff Lounge adjacent to Nurse's Office Restroom W4 Plaster White None 0 12.4 Positive 1 2 210A Staff Lounge adjacent to Nurse's Office Restroom Celling Plaster White No Access N/A											Negative
1 2 210A Staff Lounge adjacent to Nurse's Office Restroom Ceiling Plaster White No Access N/A				U j							
1 2 210A Staff Lounge adjacent to Nurse's Office Restroom Floor Ceramic Unpainted N/A				ů ,							Negative
12210AStaff Lounge adjacent to Nurse's Office RestroomFloorCeramicUnpaintedN/AN/AN/AN/A12210AStaff Lounge adjacent to Nurse's Office RestroomRadiatorMetalGrayFlaking1011.1Positiv12210AStaff Lounge adjacent to Nurse's Office RestroomGrateMetalBlackNone00Negativ12210AStaff Lounge adjacent to Nurse's Office RestroomDoorWoodVarnishNone00Negativ12210BStaff Lounge adjacent to Nurse's Office ClosetDoorWoodVarnishNone00Negativ12210BStaff Lounge adjacent to Nurse's Office ClosetDoorWoodVarnishNone00Negativ12210BStaff Lounge adjacent to Nurse's Office ClosetDoor FrameWoodVarnishNone00Negativ12210BStaff Lounge adjacent to Nurse's Office ClosetDor FrameWoodVarnishNone00Negativ12210BStaff Lounge adjacent to Nurse's Office ClosetW2PlasterWhiteNone04.6Positiv12210BStaff Lounge adjacent to Nurse's Office ClosetW4PlasterWhiteNo AccessNo AccessNo AccessNo AccessNo AccessNo AccessNo AccessNo AccessNo AccessNo Access <td></td> <td>_</td> <td></td> <td>ŭ ,</td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td>		_		ŭ ,							
1 2 210A Staff Lounge adjacent to Nurse's Office Restroom Grate Metal Black None 0 0 0 Negativ 1 2 210A Staff Lounge adjacent to Nurse's Office Restroom Door Wood Varnish None 0 0 0 Negativ 1 2 210B Staff Lounge adjacent to Nurse's Office Restroom Door Frame Wood Varnish None 0 0 0 Negativ 1 2 210B Staff Lounge adjacent to Nurse's Office Closet Door Frame Wood Varnish None 0 0 Negativ 1 2 210B Staff Lounge adjacent to Nurse's Office Closet Door Frame Wood Varnish None 0 0 Negativ 1 2 210B Staff Lounge adjacent to Nurse's Office Closet Door Frame Wood Varnish None 0 0 Negativ 1 2 210B Staff Lounge adjacent to Nurse's Office Closet W1 Plaster White None 0 0 0 Negativ 1 2 210B Staff Lounge adjacent to Nurse's Office Closet W2 Plaster White Flaking 2 5.8 Positiv 1 2 210B Staff Lounge adjacent to Nurse's Office Closet W3 Plaster White Flaking 3 4.4 Positiv 1 2 210B Staff Lounge adjacent to Nurse's Office Closet W4 Plaster White None 0 0 Negativ 1 2 210B Staff Lounge adjacent to Nurse's Office Closet W4 Plaster White Flaking 3 4.4 Positiv 1 2 210B Staff Lounge adjacent to Nurse's Office Closet W4 Plaster White No Access No A			-	U J							
1 2 210A Staff Lounge adjacent to Nurse's Office Restroom 1 2 210A Staff Lounge adjacent to Nurse's Office Restroom 1 2 210A Staff Lounge adjacent to Nurse's Office Restroom 1 2 210A Staff Lounge adjacent to Nurse's Office Restroom 1 2 210B Staff Lounge adjacent to Nurse's Office Restroom 1 2 210B Staff Lounge adjacent to Nurse's Office Closet 1 2 210B Staff Loung				ŭ ,			•				
1 2 210A Staff Lounge adjacent to Nurse's Office Restroom Door Wood Varnish None 0 0 0 Negative 1 2 210B Staff Lounge adjacent to Nurse's Office Closet Door Wood Varnish None 0 0 0 Negative 1 2 210B Staff Lounge adjacent to Nurse's Office Closet Door Wood Varnish None 0 0 0 Negative 1 2 210B Staff Lounge adjacent to Nurse's Office Closet Door Frame Wood Varnish None 0 0 0 Negative 1 2 210B Staff Lounge adjacent to Nurse's Office Closet W1 Plaster White None 0 0 4.6 Positive 1 2 210B Staff Lounge adjacent to Nurse's Office Closet W2 Plaster White None 0 4.6 Positive 1 2 210B Staff Lounge adjacent to Nurse's Office Closet W3 Plaster White Flaking 2 5.8 Positive 1 2 210B Staff Lounge adjacent to Nurse's Office Closet W3 Plaster White Flaking 3 4.4 Positive 1 2 210B Staff Lounge adjacent to Nurse's Office Closet W4 Plaster White No Access			-	y j			,				
1 2 210A Staff Lounge adjacent to Nurse's Office Restroom 1 2 210B Staff Lounge adjacent to Nurse's Office Closet 1 2 210B Staff Lounge adjacent to Nurse's Office 1 2 210B Staff Lounge adjacent to Nurse's Office 1 2 210B Staff Lounge adjacent to Nurse's Office 1 2 210B Staff Lounge adjacent to Nurse's Office 1 2 210B Staff Lounge adjacent to Nurse's Office 1 2 210B Staff Lounge adjacent to Nurse's Office 1 2 210B Staff Lounge adjacent to Nurse's Office 1 2 210B Staff Lounge adjacent to Nurse's Office 1 2 210B Staff Lounge adjacent to Nurse's Office 1 2 210B Staff Lounge adjacent to Nurse's Office 1 2 210B Staff Lounge adjacent to Nurse's Office 1 2 211B Girl's Restroom near Nurse's Office 1 2 211 Girl's Restroom											
1 2 210B Staff Lounge adjacent to Nurse's Office Closet Door Wood Varnish None 0 0 Negative 1 2 210B Staff Lounge adjacent to Nurse's Office Closet W1 Plaster White None 0 4.6 Positive 1 2 210B Staff Lounge adjacent to Nurse's Office Closet W2 Plaster White Flaking 2 5.8 Positive 1 2 210B Staff Lounge adjacent to Nurse's Office Closet W3 Plaster White Flaking 3 4.4 Positive 1 2 210B Staff Lounge adjacent to Nurse's Office Closet W4 Plaster White No Access No Acc											
1 2 210B Staff Lounge adjacent to Nurse's Office Closet W1 Plaster White None 0 4.6 Positive None 1 2 210B Staff Lounge adjacent to Nurse's Office Closet W2 Plaster White Flaking 2 5.8 Positive None 1 2 210B Staff Lounge adjacent to Nurse's Office Closet W3 Plaster White Flaking 3 4.4 Positive None 1 2 210B Staff Lounge adjacent to Nurse's Office Closet W3 Plaster White Flaking 3 4.4 Positive None 1 2 210B Staff Lounge adjacent to Nurse's Office Closet W4 Plaster White None 0 0 Naccess No Access No Ac				ŭ ,						_	
1 2 210B Staff Lounge adjacent to Nurse's Office Closet W1 Plaster White None 0 4.6 Positive Flaking 2 5.8 Positive Flaking 1 2 210B Staff Lounge adjacent to Nurse's Office Closet W3 Plaster White Flaking 3 4.4 Positive Flaking 3 4.4 Positive Flaking 1 2 210B Staff Lounge adjacent to Nurse's Office Closet W4 Plaster White No Access No				ŭ ,						-	
1 2 210B Staff Lounge adjacent to Nurse's Office Closet W3 Plaster White Flaking 3 4.4 Positive Flaking 1 2 210B Staff Lounge adjacent to Nurse's Office Closet W3 Plaster White Flaking 3 4.4 Positive Flaking 3 4.4 Positive Flaking 3 4.4 Positive Flaking 4 2 210B Staff Lounge adjacent to Nurse's Office Closet W4 Plaster White No Access				, ,							
1 2 210B Staff Lounge adjacent to Nurse's Office Closet W3 Plaster White Flaking 3 4.4 Positive No. Access No. Acces No. Access No. Acces No. Access No. Acces No.	1			ů ,				I			
1 2 210B Staff Lounge adjacent to Nurse's Office Closet W4 Plaster White No Access No	1		-	y j							
1 2 210B Staff Lounge adjacent to Nurse's Office Closet Baseboard Wood White None 0 0 Negative None 1 2 210B Staff Lounge adjacent to Nurse's Office Closet Ceiling Plaster White No Access N/A	1			ŭ ,							
1 2 210B Staff Lounge adjacent to Nurse's Office Closet Ceiling Plaster White No Access N/A	1		-								
1 2 210B Staff Lounge adjacent to Nurse's Office Closet Floor Wood Unpainted N/A	1			ŭ ,							
1 2 211 Girl's Restroom near Nurse's Office W1 Plaster White None 0 12.7 Positive 1 2 211 Girl's Restroom near Nurse's Office W2 Plaster White None 0 10.1 Positive 1 2 211 Girl's Restroom near Nurse's Office W3 Plaster White None 0 13.3 Positive 1 2 211 Girl's Restroom near Nurse's Office W3 Plaster White None 0 13.3 Positive				<u> </u>							
12211Girl's Restroom near Nurse's OfficeW2PlasterWhiteNone010.1Positive12211Girl's Restroom near Nurse's OfficeW3PlasterWhiteNone013.3Positive											
1 2 211 Girl's Restroom near Nurse's Office W3 Plaster White None 0 13.3 Positive	-										Positive
	1										Positive
1 2 211 Girl's Restroom near Nurse's Office W4 Plaster White Flaking 10 15.9 Positive	1			!	_				-		Positive

			Dates: 3/13/2023 to 7/21/2023	Lead-Safe Certification Assessment Report						
			Inspector Name and PA License Number:						-	
			Lawrence Jackson 003683		Pai	rkway Ce	nter City Mic	idie Colle	ge	
			Inspection Company: USA Environmental		= 40 N				10100	
			Management Inc		540 Nor	th 13th S	treet, Philad	elphia, P <i>i</i>	1 19123	
E I e	F									
m e n	0	0#	One its Decom Name	2	Out at the Material	Baint Calan	Description of	Damage	XRF Reading	XRF (positive/
1	2	Space # 211	Onsite Room Name Girl's Restroom near Nurse's Office	Component Ceiling	Substrate Material Concrete	Paint Color White	Damage Flaking	Quantity (sf)	(mg/cm2) 18.8	negative) Positive
1	2	211	Girl's Restroom near Nurse's Office	Floor	Concrete	Gray	None	0	0.3	Negative
1	2	211	Girl's Restroom near Nurse's Office	Door	Wood	Varnish	None	0	0.5	Negative
1	2	211	Girl's Restroom near Nurse's Office	Door Frame	Wood	Brown	None	0	0.2	Negative
1	2	211	Girl's Restroom near Nurse's Office	Window Casing	Wood	Brown	None	0	0.2	Positive
1	2	211	Girl's Restroom near Nurse's Office	Radiator	Metal	Gray	Flaking	5	0.5	Negative
1	2	211B	Pipe Chase in Girl's Restroom near Nurse's Office	Door	Wood	Brown	None	0	0.1	Negative
1	2	211B	Pipe Chase in Girl's Restroom near Nurse's Office	Door Frame	Wood	Brown	None	0	0.1	Negative
1	2	211B	Pipe Chase in Girl's Restroom near Nurse's Office	W1	No Access	No Access	No Access	N/A	N/A	N/A
1	2	211B	Pipe Chase in Girl's Restroom near Nurse's Office	W2	No Access	No Access	No Access	N/A	N/A	N/A
1	2	211B	Pipe Chase in Girl's Restroom near Nurse's Office	W3	No Access	No Access	No Access	N/A	N/A	N/A
1	2	211B	Pipe Chase in Girl's Restroom near Nurse's Office	W4	No Access	No Access	No Access	N/A	N/A	N/A
1	2	211A	Custodial Closet Next to Second Floor Girl's Restroom	W1	Plaster	Tan	Cracking	8	2.9	Positive
1	2	211A	Custodial Closet Next to Second Floor Girl's Restroom	W2	Plaster	White	Cracking	20	2.1	Positive
1	2	211A	Custodial Closet Next to Second Floor Girl's Restroom	W3	Plaster	White	Cracking	60	0	Negative
1	2	211A	Custodial Closet Next to Second Floor Girl's Restroom	W4	Plaster	White	Cracking	20	2	Positive
1	2	211A	Custodial Closet Next to Second Floor Girl's Restroom	Floor	Concrete	Unpainted	N/A	N/A	N/A	N/A
1	2	211A	Custodial Closet Next to Second Floor Girl's Restroom	Ceiling	Plaster	White	Cracking	20	No Access	Assumed
1	2	211A	Custodial Closet Next to Second Floor Girl's Restroom	Drain Pipe	Metal	White	Flaking	12	0.6	Negative
1	2	211A	Custodial Closet Next to Second Floor Girl's Restroom	Door	Wood	Varnish	None	0	0	Negative
1	2	211A	Custodial Closet Next to Second Floor Girl's Restroom	Door Frame	Wood	Varnish	None	0	0	Negative
1	2	H2	Hallway outside Second Floor Girl's Restroom	W1	Plaster	Gray	None	0	24	Positive
1	2	H2	Hallway outside Second Floor Girl's Restroom	W2	Plaster	Gray	None	0	21.6	Positive
1	2	H2	Hallway outside Second Floor Girl's Restroom	W3	Plaster	Gray	None	0	24.7	Positive
1	2	H2	Hallway outside Second Floor Girl's Restroom	W4	Plaster	Gray	None	0	22.1	Positive
1	2	H2	Hallway outside Second Floor Girl's Restroom	Floor	Concrete	Gray	None	0	2	Positive
1	2	H2	Hallway outside Second Floor Girl's Restroom	Ceiling	Plaster	Tan	None	0	20.6	Positive
1	2	H2C	Hallway from IMC 205 to Nurse's Office	W1	Plaster	Gray	None	0	22.6	Positive
1	2	H2C	Hallway from IMC 205 to Nurse's Office	W2	Plaster	Gray	None	0	19.5	Positive
1	2	H2C	Hallway from IMC 205 to Nurse's Office	W3	Plaster	Gray	None	0	22.8	Positive
1	2	H2C	Hallway from IMC 205 to Nurse's Office	W4	Plaster	Gray	None	100	18.9	Positive
1	2	H2C	Hallway from IMC 205 to Nurse's Office	Ceiling Floor	Plaster Concrete	Tan Grav	Cracking None	100	26.6 2.8	Positive Positive
1	2	H2C H2C	Hallway from IMC 205 to Nurse's Office Hallway from IMC 205 to Nurse's Office	Radiator	Metal	Gray	None	0	0.7	Positive
1	2	H2C	· · · · · · · · · · · · · · · · · · ·	Radiator	Metal	Gray	None	0	0.7	Negative
1	2	H2C	Hallway from IMC 205 to Nurse's Office Hallway from IMC 205 to Nurse's Office	Radiator	Metal	Gray	None	0	0.2	Negative
1	2	H2C	Hallway from IMC 205 to Nurse's Office Hallway from IMC 205 to Nurse's Office	Lockers	Metal	Red	None	0	0	Negative
1	2	H2CPCS	Pipe/Cable Shaft in Hallway next to Classroom 206	Door	Wood	Varnish	None	0	0	Negative
		HZUPUS	ripercable Sharrin Hallway flext to Classicoth 206	וטטט	vvoou	varriisti	INUITE		U	iveyalive

			Dates: 3/13/2023 to 7/21/2023	Lead-Safe Certification Assessment Report						
			Inspector Name and PA License Number:		D	.1	4 O'4 M'-	1.11. 0.11.		
			Lawrence Jackson 003683		Pai	rkway Ce	nter City Mid	iale Colle	ge	
			Inspection Company: USA Environmental		E40 Nor	4h 124h C	troot Dhilad	alabia D	10422	
		•	Management Inc		540 NO r	tn 13tn 5	treet, Philad	eipnia, P	19123	
E I e m e	FIO						Description of	Domore	XRF Reading	XRF (positive/
n t	o r	Space #	Onsite Room Name	Component	Substrate Material	Paint Color	Description of Damage	Damage Quantity (sf)	(mg/cm2)	negative)
1	2	H2CPCS	Pipe/Cable Shaft in Hallway next to Classroom 206	Door Frame	Wood	Varnish	None	0	0	Negative
1	2	H2CPCS	Pipe/Cable Shaft in Hallway next to Classroom 206	W1	Concrete	Unpainted	N/A	N/A	N/A	N/A
1	2	H2CPCS	Pipe/Cable Shaft in Hallway next to Classroom 206	W2	Terracotta	Unpainted	N/A	N/A	N/A	N/A
1	2	H2CPCS	Pipe/Cable Shaft in Hallway next to Classroom 206	W3	Terracotta	Unpainted	N/A	N/A	N/A	N/A
1	2	H2CPCS	Pipe/Cable Shaft in Hallway next to Classroom 206	W4	Terracotta	Unpainted	N/A	N/A	N/A	N/A
1	2	H2B	Hallway outside Auditorium Balcony	W1	Plaster	White	None	0	20.3	Positive
1	2	H2B	Hallway outside Auditorium Balcony	W2	Plaster	White	None	0	19.4	Positive
1	2	H2B	Hallway outside Auditorium Balcony	W3	Plaster	White	None	0	23.5	Positive
1	2	H2B	Hallway outside Auditorium Balcony	W4	Plaster	White	None	0	27	Positive
1	2	H2B	Hallway outside Auditorium Balcony	Floor	Concrete	Unpainted	N/A	N/A	N/A	N/A
1	2	H2B	Hallway outside Auditorium Balcony	Ceiling	Plaster	White	None	0	15.7	Positive
1	2	H2B	Hallway outside Auditorium Balcony	Door	Wood	Varnish	None	0	0	Negative
1	2	H2B	Hallway outside Auditorium Balcony	Door Frame	Wood	Varnish	None	0	0.1	Negative
1	2	H2B	Hallway outside Auditorium Balcony	Spindle	Metal	Blue	None	0	13.7	Positive
1	2	H2B	Hallway outside Auditorium Balcony	Post	Metal	Blue	None	0	11.1	Positive
1	2	H2BPCS1	Pipe/Cable Shaft in Hallway next to Stairwell by Main Office	Door	Wood	Varnish	None	0	0.1	Negative
1	2	H2BPCS1	Pipe/Cable Shaft in Hallway next to Stairwell by Main Office	Door Frame	Wood	Varnish	None	0	0.1	Negative
1	2	H2BPCS1	Pipe/Cable Shaft in Hallway next to Stairwell by Main Office	W1	Terracotta	Unpainted	N/A	N/A	N/A	N/A
1	2	H2BPCS1	Pipe/Cable Shaft in Hallway next to Stairwell by Main Office	W2	Terracotta	Unpainted	N/A	N/A	N/A	N/A
1	2	H2BPCS1	Pipe/Cable Shaft in Hallway next to Stairwell by Main Office	W3	Concrete	Unpainted	N/A	N/A	N/A	N/A
1	2	H2BPCS1	Pipe/Cable Shaft in Hallway next to Stairwell by Main Office	W4	Terracotta	Unpainted	N/A	N/A	N/A	N/A
1	2	H2BPCS2	Pipe/Cable Shaft in Hallway above Hydration Station near Main Office	Door	Wood	Varnish	None	0	0.1	Negative
1	2	H2BPCS2	Pipe/Cable Shaft in Hallway above Hydration Station near Main Office	Door Frame	Wood	Varnish	None	0	0.1	Negative
1	2	H2BPCS2	Pipe/Cable Shaft in Hallway above Hydration Station near Main Office	W1	Terracotta	Unpainted	N/A	N/A	N/A	N/A
1	2	H2BPCS2	Pipe/Cable Shaft in Hallway above Hydration Station near Main Office	W2	Terracotta	Unpainted	N/A	N/A	N/A	N/A
1	2	H2BPCS2	Pipe/Cable Shaft in Hallway above Hydration Station near Main Office	W3	Terracotta	Unpainted	N/A	N/A	N/A	N/A
1	2	H2BPCS2	Pipe/Cable Shaft in Hallway above Hydration Station near Main Office	W4	Terracotta	Unpainted	N/A	N/A	N/A	N/A
1	2	H2BPCS3	Pipe/Cable Shaft in Hallway next to Stairwell by IMC	Door	Wood	Varnish	None	0	0	Negative

			Dates: 3/13/2023 to 7/21/2023	Lead-Safe Certification Assessment Report						
			Inspector Name and PA License Number:		_				•	
			Lawrence Jackson 003683		Pai	'kway Ce	nter City Mic	idle Colle	ge	
			Inspection Company: USA Environmental							
			Management Inc		540 Nor	th 13th S	treet, Philad	elphia, P <i>l</i>	A 19123	
E			3				,			
e	F									
m	1									
е	0						-	_		XRF
n	o r	Space #	Onsite Room Name	Component	Substrate Material	Paint Color	Description of Damage	Damage Quantity (sf)	XRF Reading (mg/cm2)	(positive/ negative)
1	2	H2BPCS3	Pipe/Cable Shaft in Hallway next to Stairwell by IMC	Door Frame	Wood	Varnish	None	Qualitity (SI)	0.2	Negative
1	2	H2BPCS3	Pipe/Cable Shaft in Hallway next to Stairwell by IMC	W1	Concrete	Unpainted	N/A	N/A	N/A	N/A
1	2	H2BPCS3	Pipe/Cable Shaft in Hallway next to Stairwell by IMC	W1 W2	Terracotta	Unpainted	N/A	N/A	N/A	N/A
1	2	H2BPCS3	Pipe/Cable Shaft in Hallway next to Stairwell by IMC	W3	Terracotta	Unpainted	N/A	N/A	N/A	N/A
1	2	H2BPCS3	Pipe/Cable Shaft in Hallway next to Stairwell by IMC	W4	Terracotta	Unpainted	N/A	N/A	N/A	N/A
1	2	S22	Main Entrance Stairwell	W1	Plaster	White	None	0	24.4	Positive
1	2	S22	Main Entrance Stairwell	W2	Plaster	White	None	0	20.1	Positive
1	2	S22	Main Entrance Stairwell	W3	Plaster	White	None	0	21.5	Positive
1	2	S22	Main Entrance Stairwell	Window Casing	Concrete	Black	None	0	0.1	Negative
1	2	S22	Main Entrance Stairwell	Newel Post	Metal	Blue	None	0	12.8	Positive
1	2	S22	Main Entrance Stairwell	Spindle	Metal	Blue	None	0	18.8	Positive
1	2	H2A	Hallway from Office Suite 201 to Main Office	W1	Plaster	Gray	None	0	24.5	Positive
1	2	H2A	Hallway from Office Suite 201 to Main Office	W2	Plaster	Gray	None	0	0.2	Negative
1	2	H2A	Hallway from Office Suite 201 to Main Office	W3	Plaster	Gray	None	0	16.5	Positive
1	2	H2A	Hallway from Office Suite 201 to Main Office	W4	Plaster	Gray	None	0	18.8	Positive
1	2	H2A	Hallway from Office Suite 201 to Main Office	Ceiling	Plaster	Tan	None	0	18.3	Positive
1	2	H2A	Hallway from Office Suite 201 to Main Office	Floor	Concrete	Gray	Cracking	10	1.6	Positive
1	2	H2A	Hallway from Office Suite 201 to Main Office	Radiator	Metal	Gray	Flaking	3	0.3	Negative
1	2	H2A	Hallway from Office Suite 201 to Main Office	Radiator	Metal	Gray	Flaking	2	0.3	Negative
1	2	H2A	Hallway from Office Suite 201 to Main Office	Radiator	Metal	Gray	Flaking	2	0.3	Negative
1	2	H2A	Hallway from Office Suite 201 to Main Office	Lockers	Metal	Red	None	0	0.1	Negative
1	2	H2A	Hallway from Office Suite 201 to Main Office	Electrical Panel	Metal	Brown	None	0	0.1	Negative
1	2	H2APCS	Pipe/Cable Shaft in Hallway next to Classroom 202	Door	Wood	Varnish	None	0	0.1	Negative
1	2	H2APCS	Pipe/Cable Shaft in Hallway next to Classroom 202	Door Frame	Wood	Varnish	None	0	0	Negative
1	2	H2APCS	Pipe/Cable Shaft in Hallway next to Classroom 202	W1	Concrete	Unpainted	N/A	N/A	N/A	N/A
1	2	H2APCS	Pipe/Cable Shaft in Hallway next to Classroom 202	W2	Terracotta	Unpainted	N/A	N/A	N/A	N/A
1	2	H2APCS	Pipe/Cable Shaft in Hallway next to Classroom 202	W3	Concrete	Unpainted	N/A	N/A	N/A	N/A
1	2	H2APCS	Pipe/Cable Shaft in Hallway next to Classroom 202	W4	Terracotta	Unpainted	N/A	N/A	N/A	N/A
1	2	H2D	Hallway outside Second Floor Boy's Restroom	W1	Plaster	Gray	None	0	0.2	Negative
1	2	H2D	Hallway outside Second Floor Boy's Restroom	W2	Plaster	Gray	None	0	15.4	Positive
1	2	H2D	Hallway outside Second Floor Boy's Restroom	W3	Plaster	Gray	None	0	20.3	Positive
1	2	H2D	Hallway outside Second Floor Boy's Restroom	W4	Plaster	Gray	None	0	20.5	Positive
1	2	H2D	Hallway outside Second Floor Boy's Restroom	Floor	Concrete	Gray	None	0	0.1	Negative
1	2	H2D	Hallway outside Second Floor Boy's Restroom	Ceiling	Plaster	Tan	Cracking	80	18.8	Positive
1	1	108	Auditorium Control Room adjacent to Stage	W1	Plaster	White	Cracking	20	6.8	Positive
1	1	108	Auditorium Control Room adjacent to Stage	W2	Plaster	White	Cracking	40	0.5	Negative
1	1	108	Auditorium Control Room adjacent to Stage	W3	Plaster	White	Cracking	40	0.3	Negative
1	1	108	Auditorium Control Room adjacent to Stage	W4	Plaster	White	Cracking	20	7	Positive

			Dates: 3/13/2023 to 7/21/2023	Lead-Safe Certification Assessment Report						
			Inspector Name and PA License Number:		Des	dansan Ca	ndon City Mi			
			Lawrence Jackson 003683		Par	rkway Ce	nter City Mic	adie Colle	ege	
			Inspection Company: USA Environmental Management Inc		540 Nor	th 13th S	treet, Philad	elphia, P	A 19123	
E I e	F									
m e n t	0 0 r	Space #	Onsite Room Name	Component	Substrate Material	Paint Color	Description of Damage	Damage Quantity (sf)	XRF Reading (mg/cm2)	XRF (positive/ negative)
1	1	108	Auditorium Control Room adjacent to Stage	Ceiling	Plaster	White	Cracking	12	6.4	Positive
1	1	108	Auditorium Control Room adjacent to Stage	Floor	Wood	Unpainted	N/A	N/A	N/A	N/A
1	1	109	Men's Restroom near Building Engineer's Office	W1	Plaster	White	Flaking	120	6.3	Positive
1	1	109	Men's Restroom near Building Engineer's Office	W2	Plaster	White	Flaking	50	8.3	Positive
1	1	109	Men's Restroom near Building Engineer's Office	W3	Plaster	White	Flaking	80	6.5	Positive
1	1	109	Men's Restroom near Building Engineer's Office	W4	Plaster	White	Flaking	100	0.2	Negative
1	1	109	Men's Restroom near Building Engineer's Office	Ceiling	Plaster	White	Flaking	30	6.5	Positive
1	1	109	Men's Restroom near Building Engineer's Office	Floor	Concrete	Gray	None	0	0.1	Negative
1	1	109	Men's Restroom near Building Engineer's Office	Radiator	Metal	Gray	Flaking	2	0	Negative
1	1	109A	Pipe Shaft near First Floor Men's Restroom	Door	Wood	Varnish	None	0	0	Negative
1	1	109A	Pipe Shaft near First Floor Men's Restroom	Door Frame	Wood	Varnish	None	0	0	Negative
1	1	109A	Pipe Shaft near First Floor Men's Restroom	W1	No Access	No Access	No Access	N/A	N/A	N/A
1	1	109A	Pipe Shaft near First Floor Men's Restroom	W2	No Access	No Access	No Access	N/A	N/A	N/A
1	1	109A	Pipe Shaft near First Floor Men's Restroom	W3	No Access	No Access	No Access	N/A	N/A	N/A
1	1	109A	Pipe Shaft near First Floor Men's Restroom	W4	No Access	No Access	No Access	N/A	N/A	N/A
1	1	100	Building Engineer's Office	W1	Plaster	White	Cracking	10	8	Positive
1	1	100	Building Engineer's Office	W2	Plaster	White	None	0	10.5	Positive
1	1	100	Building Engineer's Office	W3	Plaster	White	Cracking	40	8.4	Positive
1	1	100	Building Engineer's Office	W4	Plaster	White	Cracking	20	8.8	Positive
1	1	100	Building Engineer's Office	Ceiling	Plaster	White	Alligatoring	70	11.1	Positive
1	1	100	Building Engineer's Office	Floor	Wood	Unpainted	N/A	N/A	N/A	N/A
1	1	100	Building Engineer's Office	Radiator	Metal	Gray	Flaking	10	0.4	Negative
1	1	100	Building Engineer's Office	Radiator	Metal	Gray	Flaking	10	0.7	Positive
1	1	100A	Pipe Chase outside Building Engineer's Office	Door	Wood	Varnish	None	0	0.1	Negative
1	1	100A	Pipe Chase outside Building Engineer's Office	Door Frame	Wood	Varnish	None	0	0.2	Negative
1	1	100A	Pipe Chase outside Building Engineer's Office	W1	No Access	No Access	No Access	N/A	N/A	N/A
1	1	100A	Pipe Chase outside Building Engineer's Office	W2	No Access	No Access	No Access	N/A	N/A	N/A
1	1	100A	Pipe Chase outside Building Engineer's Office	W3	No Access	No Access	No Access	N/A	N/A	N/A
1	1	100A	Pipe Chase outside Building Engineer's Office	W4	No Access	No Access	No Access	N/A	N/A	N/A
1	1	H11C	Hallway to Best Door	W1	Plaster	Gray	None	0	17.3	Positive
1	1	H11C	Hallway to Best Door	W2	Plaster	Gray	None	0	17.8	Positive
1	1	H11C	Hallway to Best Door	W3	Plaster	Gray	None	0	19.5	Positive
1	1	H11C	Hallway to Best Door	Ceiling	Plaster	Gray	None	0	15.3	Positive
1	1	H11C	Hallway to Best Door	Door	Metal	Brown	None	0	0.1	Negative
1	1	H11C	Hallway to Best Door	Door Frame	Metal	Brown	None	0	0.1	Negative
1	1	H11C	Hallway to Best Door	Floor	Concrete	Gray	None	0	1.1	Positive
1	1	H11C	Hallway to Best Door	Drain Pipe	Metal	White	None	0	0.1	Negative
1	1	H11D	Best Door Vestibule	W1	Brick	White	None	0	5.1	Positive

			Dates: 3/13/2023 to 7/21/2023	Lead-Safe Certification Assessment Report						
			Inspector Name and PA License Number:		Do	dansı Ca	ntor City Mic			
			Lawrence Jackson 003683		Pai	rkway Ce	nter City Mic	iale Colle	ge	
			Inspection Company: USA Environmental Management Inc		540 Nor	th 13th S	treet, Philad	elphia, PA	\ 19123	
E I e m e	F I o									XRF
n	o r	Space #	Onsite Room Name	Component	Substrate Material	Paint Color	Description of Damage	Damage Quantity (sf)	XRF Reading (mg/cm2)	(positive/ negative)
1	1	H11D	Best Door Vestibule	W2	Brick	White	None	Qualitity (SI)	3.9	Positive
1	1	H11D	Best Door Vestibule Best Door Vestibule	W3	Brick	White	None	0	6.1	Positive
1	1	H11D	Best Door Vestibule Best Door Vestibule	W4	Brick	White	Cracking	5	5.1	Positive
1	1	H11D	Best Door Vestibule	Floor	Concrete	Gray	None	0	0	Negative
1	1	H11D	Best Door Vestibule	Ceiling	Concrete	White	Cracking	8	0	Negative
1	1	H11D	Best Door Vestibule Best Door Vestibule	Door	Metal	Brown	None	0	0	Negative
1	1	H11D	Best Door Vestibule	Door Frame	Metal	Brown	None	0	0	Negative
1	1	101	Office 101	W1	Sheetrock	Unpainted	N/A	N/A	N/A	N/A
1	1	101	Office 101	W2	Plaster	White	Flaking	5	0	Negative
1	1	101	Office 101	W3	Plaster	White	None	0	0.1	Negative
1	1	101	Office 101	W4	Plaster	White	None	0	6.8	Positive
1	1	101	Office 101	Ceiling	Plaster	White	Flaking	70	9.2	Positive
1	1	101	Office 101	Radiator	Metal	Gray	None	0	1	Positive
1	1	101	Office 101	Door	Wood	Brown	None	0	0	Negative
1	1	101	Office 101	Door Frame	Wood	Brown	None	0	0.1	Negative
1	1	101	Office 101	Baseboard	Wood	Brown	None	0	0.1	Negative
1	1	101	Office 101	Window Casing	Wood	Brown	None	0	0.1	Negative
1	1	101	Office 101	Window Sill	Wood	Brown	None	0	0.1	Negative
1	1	101	Office 101	Window Apron	Wood	Brown	None	0	0	Negative
1	1	102	Office Suite 102 Common Area	Door	Wood	Varnish	None	0	0	Negative
1	1	102	Office Suite 102 Common Area	Door Frame	Wood	Varnish	None	0	0.1	Negative
1	1	102	Office Suite 102 Common Area	W1	Plaster	White	None	0	16.7	Positive
1	1	102	Office Suite 102 Common Area	W2	Plaster	White	None	0	0.2	Negative
1	1	102	Office Suite 102 Common Area	W3	Fabric	Unpainted	N/A	N/A	N/A	N/A
1	1	102	Office Suite 102 Common Area	W4	Plaster	White	None	0	17.4	Positive
1	1	102	Office Suite 102 Common Area	Baseboard	Wood	Brown	None	0	0.3	Negative
1	1	102	Office Suite 102 Common Area	Floor	12 x 12 Floor Tile	Unpainted	N/A	N/A	N/A	N/A
1	1	102	Office Suite 102 Common Area	Ceiling	Plaster	Tan	None	0	15.8	Positive
1	1	102H	Office Suite 102 Common Area Closet	No Access	No Access	No Access	No Access	No Access	No Access	No Access
1	1	102H	Office Suite 102 Common Area Closet	No Access	No Access	No Access	No Access	No Access	No Access	No Access
1	1	102H	Office Suite 102 Common Area Closet	No Access	No Access	No Access	No Access	No Access	No Access	No Access
1	1	102H	Office Suite 102 Common Area Closet	No Access	No Access	No Access	No Access	No Access	No Access	No Access
1	1	102H	Office Suite 102 Common Area Closet	No Access	No Access	No Access	No Access	No Access	No Access	No Access
1	1	102H	Office Suite 102 Common Area Closet	No Access	No Access	No Access	No Access	No Access	No Access	No Access
1	1	102G	Office 102B (Left Office)	Ceiling	Plaster	Tan	None	0	15.1	Positive
1	1	102G	Office 102B (Left Office)	Floor	Carpet	Unpainted	N/A	N/A	N/A	N/A
1	1	102G	Office 102B (Left Office)	W1	Plaster	White	None	0	16.2	Positive
1	1	102G	Office 102B (Left Office)	W2	Plaster	White	None	0	0	Negative

			Dates: 3/13/2023 to 7/21/2023	Lead-Safe Certification Assessment Report						
			Inspector Name and PA License Number:		Por	dayay Ca	ntor City Mic	Idla Calla		
			Lawrence Jackson 003683		Pai	kway ce	nter City Mic	idle Colle	ge	
			Inspection Company: USA Environmental Management Inc		540 Nor	th 13th S	treet, Philad	elphia, PA	19123	
E I e m e n t	F I o o r	Space #	Onsite Room Name	Component	Substrate Material	Paint Color	Description of Damage	Damage Quantity (sf)	XRF Reading (mg/cm2)	XRF (positive/ negative)
1	1	102G	Office 102B (Left Office)	W3	Plaster	White	None	0	17.3	Positive
1	1	102G	Office 102B (Left Office)	W4	Plaster	White	None	0	0	Negative
1	1	102G	Office 102B (Left Office)	Window Casing	Wood	Brown	None	0	0.5	Negative
1	1	102G	Office 102B (Left Office)	Window Sill	Wood	Brown	None	0	0.1	Negative
1	1	102G	Office 102B (Left Office)	Window Apron	Wood	Brown	None	0	0.2	Negative
1	1	102G	Office 102B (Left Office)	Radiator	Metal	Gray	None	0	2.8	Positive
1	1	102G	Office 102B (Left Office)	Baseboard	Wood	Brown	None	0	0.3	Negative
1	1	102G	Office 102B (Left Office)	Door	Wood	Varnish	None	0	0.1	Negative
1	1	102G	Office 102B (Left Office)	Door Frame	Metal	Brown	None	0	0.1	Negative
1	1	102F	Office 102C (Center Office)	Ceiling	Plaster	Tan	Flaking	4	11.7	Positive
1	1	102F	Office 102C (Center Office)	Floor	Carpet	Unpainted	N/A	N/A	N/A	N/A
1	1	102F	Office 102C (Center Office)	W1	Plaster	White	None	0	17.1	Positive
1	1	102F	Office 102C (Center Office)	W2	Plaster	Gray	None	0	13.2	Positive
1	1	102F	Office 102C (Center Office)	W3	Fabric	Unpainted	N/A	N/A	N/A	N/A
1	1	102F	Office 102C (Center Office)	W4	Fabric	Unpainted	N/A	N/A	N/A	N/A
1	1	102F	Office 102C (Center Office)	Door	Wood	Varnish	None	0	0	Negative
1	1	102F	Office 102C (Center Office)	Door Frame	Metal	Brown	None	0	0.1	Negative
1	1	102F	Office 102C (Center Office)	Window Casing	Wood	Brown	None	0	0.4	Negative
1	1	102F	Office 102C (Center Office)	Window Sill	Wood	Brown	None	0	0.2	Negative
1	1	102F	Office 102C (Center Office)	Window Apron	Wood	Brown	None	0	0.2	Negative
1	1	102F	Office 102C (Center Office)	Radiator	Metal	Gray	None	0	0.4	Negative
1	1	102E	Office 102D (adjacent to Computer Classroom)	Ceiling	Plaster	Tan	None	0	13.7	Positive
1	1	102E	Office 102D (adjacent to Computer Classroom)	Floor	Carpet	Unpainted	N/A	N/A	N/A	N/A
1	1	102E	Office 102D (adjacent to Computer Classroom)	W1	Plaster	Gray	None	0	17.7	Positive
1	1	102E	Office 102D (adjacent to Computer Classroom)	W2	Plaster	Gray	None	0	14.5	Positive
1	1	102E	Office 102D (adjacent to Computer Classroom)	W3	Fabric	Unpainted	N/A	N/A	N/A	N/A
1	1	102E	Office 102D (adjacent to Computer Classroom)	W4 Door	Fabric	Unpainted	N/A N/A	N/A	N/A N/A	N/A N/A
1	1	102E	Office 102D (adjacent to Computer Classroom)	Door Door Door Frame	Wood Metal	Unpainted		N/A 0	N/A 0	
1	1	102E	Office 102D (adjacent to Computer Classroom)	Radiator	Metal	Brown	None	5		Negative Positive
	1	102E	Office 102D (adjacent to Computer Classroom)		Wood	Gray Varnish	Flaking None	0	1.9 0.2	
1	1	102E 102E	Office 102D (adjacent to Computer Classroom)	Window Casing Window Sill	Wood	Varnish Varnish	None	0	0.2	Negative
1	1	-	Office 102D (adjacent to Computer Classroom)		Wood	Varnish Varnish	None	0	0.2	Negative
1	1	102E 101A	Office 102D (adjacent to Computer Classroom)	Window Apron W1	Plaster	White	Flaking	40	15.2	Negative Positive
1	1	101A 101A	Office Suite 102 Computer Room	W2	Fabric	Unpainted	N/A	N/A	N/A	N/A
1	1		Office Suite 102 Computer Room	W3	Plaster	White	N/A None	0 N/A	22.1	Positive
1	1	101A 101A	Office Suite 102 Computer Room	W4	Sheetrock	White	None	0	0.1	
1	1		Office Suite 102 Computer Room	Ceiling	Plaster	Tan	Flaking	20	19.8	Negative Positive
11	1 1	101A	Office Suite 102 Computer Room	Ceiling	riastei	ıdlı	riaking		19.0	rosilive

			Dates: 3/13/2023 to 7/21/2023		Lead-S	afe Certi	fication Asse	essment l	Report	
			Inspector Name and PA License Number:		Pai	rkway Ca	nter City Mic	Idla Calla		
			Lawrence Jackson 003683		rai	kway Ce	inter City wiit	idle Colle	ye	
			Inspection Company: USA Environmental Management Inc		540 Nor	th 13th S	treet, Philad	elphia, P	A 19123	
E	_									
e m e n	F 0 0						Description of	Damage	XRF Reading	XRF (positive/
t	r	Space #	Onsite Room Name	Component	Substrate Material	Paint Color	Damage	Quantity (sf)	(mg/cm2)	negative)
1	1	101A	Office Suite 102 Computer Room	Floor	12 x 12 Floor Tile	Unpainted	N/A	N/A	N/A	N/A
1	1	101A	Office Suite 102 Computer Room	Door	Wood	Varnish	None	0	0	Negative
1	1	101A	Office Suite 102 Computer Room	Door Frame	Metal	Brown	None	0	0	Negative
1	1	101A	Office Suite 102 Computer Room	Baseboard	Wood	Brown	None	0	0.1	Negative
1	1	101A	Office Suite 102 Computer Room	Window Casing	Wood	Brown	None	0	0.3	Negative
1	1	101A	Office Suite 102 Computer Room	Window Sill	Wood	Brown	None	0	0.3	Negative
1	1	101A	Office Suite 102 Computer Room	Window Apron	Wood	Brown	None	0	0.2	Negative
1	1	101A	Office Suite 102 Computer Room	Radiator	Metal	Gray	Flaking	10	1.5	Positive
1	1	101A	Office Suite 102 Computer Room	Radiator	Metal	Gray	Flaking	10	0.5	Negative
1	1	102D	Office Suite 102 Computer Room Restroom	W1	Sheetrock	White	None	0	0	Negative
1	1	102D	Office Suite 102 Computer Room Restroom	W2	Plaster	White	None	0	0	Negative
1	1	102D	Office Suite 102 Computer Room Restroom	W3	Sheetrock	White	None	0	0.1	Negative
1	1	102D	Office Suite 102 Computer Room Restroom	W4	Sheetrock	White	None	0	0.1	Negative
1	1	102D	Office Suite 102 Computer Room Restroom	Baseboard	Wood	Brown	None	0	0.1	Negative
1	1	102D	Office Suite 102 Computer Room Restroom	Door	Wood	Varnish	None	0	0	Negative
1	1	102D	Office Suite 102 Computer Room Restroom	Door Frame	Metal	Brown	None		0	Negative
1	1	102D	Office Suite 102 Computer Room Restroom	Ceiling	No Access	No Access	No Access	No Access	No Access	No Access
1	1	101B	Office Suite 102 Computer Room Closet with Stove	W1	Sheetrock	Tan	None	0	0	Negative
1	1	101B	Office Suite 102 Computer Room Closet with Stove	W2	Plaster	Tan	None	0	18.9	Positive
1	1	101B	Office Suite 102 Computer Room Closet with Stove	W3	Sheetrock	Tan	None	0	0	Negative
1	1	101B	Office Suite 102 Computer Room Closet with Stove	W4	Sheetrock	Tan	None	0	0	Negative
1	1	101B	Office Suite 102 Computer Room Closet with Stove	Ceiling	No Access Textured	No Access	No Access	No Access	No Access	No Access
1	1	101C	Office Suite 102 Computer Room Kitchen	W1	Wallpapered Sheetrock	Unpainted	N/A	N/A	N/A	N/A
1	1	101C	Office Suite 102 Computer Room Kitchen	W2	Plaster	Tan	None	0	0.1	Negative
1	1	101C	Office Suite 102 Computer Room Kitchen	W3	Textured Wallpapered Sheetrock	Unpainted	N/A	N/A	N/A	N/A
1	1	101C	Office Suite 102 Computer Room Kitchen	W4	Textured Wallpapered Sheetrock	Unpainted	N/A	N/A	N/A	N/A
1	1	101C	Office Suite 102 Computer Room Kitchen	Ceiling	No Access	No Access	No Access	No Access	No Access	No Access
1	1	101C	Office Suite 102 Computer Room Kitchen	Floor	12 x 12 Floor Tile	Unpainted	N/A	N/A	N/A	N/A
1	1	S14	Stairwell adjacent to "SYOP" Classroom	W1	Plaster	Gray	None	0	9.4	Positive
1	1	S14	Stairwell adjacent to "SYOP" Classroom	W2	Plaster	Gray	None	0	0	Negative
1	1	S14	Stairwell adjacent to "SYOP" Classroom	W3	Plaster	Gray	None	0	8.5	Positive
1	1	S14	Stairwell adjacent to "SYOP" Classroom	W4	Plaster	Gray	None	0	10.4	Positive
1	1	S14	Stairwell adjacent to "SYOP" Classroom	Ceiling	Plaster	Gray	None	0	7.3	Positive

			Dates: 3/13/2023 to 7/21/2023		Lead-S	afe Certi	fication Asse	essment l	Report		
			Inspector Name and PA License Number:	Parkway Center City Middle College							
			Lawrence Jackson 003683 Inspection Company: USA Environmental		rai	Kway Ce	inter Only wife	idle Colle	ge		
			Management Inc		540 Nor	th 13th S	treet, Philad	elphia, P	A 19123		
E I e m e n	F I o						Description of	Damage	XRF Reading	XRF (positive/	
t	r	Space #	Onsite Room Name	Component	Substrate Material	Paint Color	Damage .	Quantity (sf)	(mg/cm2)	negative)	
1	1	S14	Stairwell adjacent to "SYOP" Classroom	Floor	Concrete	Gray	None	0	1.3	Positive	
1	1	S14	Stairwell adjacent to "SYOP" Classroom	Door	Metal	Brown	None	0	0	Negative	
1	1	S14	Stairwell adjacent to "SYOP" Classroom	Door Frame	Metal	Brown	None	0	2.2	Positive	
1	1	S14	Stairwell adjacent to "SYOP" Classroom	Entry Door	Metal	Brown	None	0	0	Negative	
1	1	S14	Stairwell adjacent to "SYOP" Classroom	Entry Door Frame	Metal	Brown	None	0	0	Negative	
1	1	S14	Stairwell adjacent to "SYOP" Classroom	Stair Tread	Concrete	Gray	Chipping	4	0.3	Negative	
1	1	S14	Stairwell adjacent to "SYOP" Classroom	Stair Riser	Concrete	Gray	Chipping	4	0.6	Negative	
1	1	S14	Stairwell adjacent to "SYOP" Classroom	Stair Stringer	Metal	Gray	Chipping	4	1.1	Positive	
1	1	S14	Stairwell adjacent to "SYOP" Classroom	Stair Spindle	Metal	Gray	Chipping	4	7.2	Positive	
1	1	S14	Stairwell adjacent to "SYOP" Classroom	Radiator	Metal	Gray	None	0	0	Negative	
1	1	S14A	Stairwell adjacent to "SYOP" Classroom Closet	Door	Metal	Brown	None	0	0	Negative	
1	1	S14A	Stairwell adjacent to "SYOP" Classroom Closet	Door Frame	Wood	Varnish	None	0	0.1	Negative	
1	1	S14A	Stairwell adjacent to "SYOP" Classroom Closet	W1	No Access	No Access	No Access	No Access	No Access	No Access	
1	1	S14A	Stairwell adjacent to "SYOP" Classroom Closet	W2	No Access	No Access	No Access	No Access	No Access	No Access	
1	1	S14A	Stairwell adjacent to "SYOP" Classroom Closet	W3	No Access	No Access	No Access	No Access	No Access	No Access	
1	1	S14A	Stairwell adjacent to "SYOP" Classroom Closet	W4	No Access	No Access	No Access	No Access	No Access	No Access	
1	1	102A	SYOP Classroom	W1	CMU	Gray	None	0	0.1	Negative	
1	1	102A	SYOP Classroom	W2	Plaster	Gray	None	0	0.1	Negative	
1	1	102A	SYOP Classroom	W3	Plaster	Gray	Efflorescence	10	0.1	Negative	
1	1	102A	SYOP Classroom	W4	Plaster	Gray	None	0	3.5	Positive	
1	1	102A	SYOP Classroom	Ceiling	Plaster	White	Flaking	40	10.7	Positive	
1	1	102A	SYOP Classroom	Floor	Wood	Unpainted	N/A	N/A	N/A	N/A	
1	1	102A	SYOP Classroom	Radiator	Metal	Gray	Chipping	2	3.1	Positive	
1	1	102A	SYOP Classroom	Radiator	Metal	Gray	Chipping	2	3.9	Positive	
1	1	102A	SYOP Classroom	Baseboard	Wood	Brown	None	0	0.1	Negative	
1	1	102A	SYOP Classroom	Window Casing	Wood	Brown	None	0	0.1	Negative	
1	1	102A	SYOP Classroom	Window Sill	Wood	Brown	None	0	0.1	Negative	
1	1	102A	SYOP Classroom	Window Apron	Wood	Brown	None	0	0.1	Negative	
1	1	1021	SYOP Classroom Pipe Shaft	Door	Wood	Varnish	None	0	0.2	Negative	
1	1	1021	SYOP Classroom Pipe Shaft	Door Frame	Wood	Varnish	None	0	0.1	Negative	
1	1	1021	SYOP Classroom Pipe Shaft	No Access	No Access	No Access	No Access	No Access	No Access	No Access	
1	1	1021	SYOP Classroom Pipe Shaft	No Access	No Access	No Access	No Access	No Access	No Access	No Access	
1	1	1021	SYOP Classroom Pipe Shaft	No Access	No Access	No Access	No Access	No Access	No Access	No Access	
1	1	1021	SYOP Classroom Pipe Shaft	No Access	No Access	No Access	No Access	No Access	No Access	No Access	
1	1	H11A	Hallway outside First Floor Men's Restroom	W1	Plaster	Gray	None	0	19.4	Positive	
1	1	H11A	Hallway outside First Floor Men's Restroom	W2	Plaster	Gray	None	0	21.8	Positive	
1	1	H11A	Hallway outside First Floor Men's Restroom	W3	Plaster	Gray	None	0	20.1	Positive	

			Dates: 3/13/2023 to 7/21/2023							
			Inspector Name and PA License Number:							
			Lawrence Jackson 003683		Pai	'kway Ce	nter City Mid	idie Colle	ge	
			Inspection Company: USA Environmental		5 40 N				10400	
			Management Inc		540 Nor	th 13th S	treet, Philade	elphia, P <i>i</i>	A 19123	
E										
	F									
e m	[
e	0									XRF
n	0						Description of	Damage	XRF Reading	(positive/
t	r	Space #	Onsite Room Name	Component	Substrate Material	Paint Color	Damage	Quantity (sf)	(mg/cm2)	negative)
1	1	H11A	Hallway outside First Floor Men's Restroom	W4	Plaster	Gray	None	60	21.8	Positive
1	1	H11A	Hallway outside First Floor Men's Restroom	Ceiling Floor	Plaster Concrete	Tan Grav	Moisture Damage None	0	5.5 1.6	Positive Positive
- '	- '	H11A	Hallway outside First Floor Men's Restroom Hallway from Building Engineer's Office to "SYOP"			,				
1	1	H11	Classroom	W1	Plaster	Gray	Cracking	10	18.7	Positive
1	1	H11	Hallway from Building Engineer's Office to "SYOP" Classroom	W2	Plaster	Gray	Cracking	10	27.5	Positive
1	1	H11	Hallway from Building Engineer's Office to "SYOP" Classroom	W3	Plaster	Gray	Cracking	10	19.9	Positive
1	1	H11	Hallway from Building Engineer's Office to "SYOP" Classroom	W4	Plaster	Gray	Cracking	5	21.2	Positive
1	1	H11	Hallway from Building Engineer's Office to "SYOP" Classroom	Ceiling	Plaster	Tan	Cracking	60	20.3	Positive
1	1	H11	Hallway from Building Engineer's Office to "SYOP" Classroom	Floor	Concrete	Gray	None	0	2.4	Positive
1	1	H11	Hallway from Building Engineer's Office to "SYOP" Classroom	Locker	Metal	Tan	None	0	0	Negative
1	1	H11	Hallway from Building Engineer's Office to "SYOP" Classroom	Electrical Panel	Metal	Brown	None	0	0.1	Negative
1	1	H11	Hallway from Building Engineer's Office to "SYOP" Classroom	Radiator	Metal	Gray	Cracking	5	0.7	Positive
1	1	H11	Hallway from Building Engineer's Office to "SYOP" Classroom	Radiator	Metal	Gray	Cracking	5	0.1	Negative
1	1	H11	Hallway from Building Engineer's Office to "SYOP" Classroom	Radiator	Metal	Gray	Cracking	5	0.3	Negative
1	1	H11PCS	Pipe/Cable Shaft in Hallway next to Classroom 101	Door	Wood	Varnish	None	0	0	Negative
1	1	H11PCS	Pipe/Cable Shaft in Hallway next to Classroom 101	Door Frame	Wood	Varnish	None	0	0.2	Negative
1	1	H11PCS	Pipe/Cable Shaft in Hallway next to Classroom 101	W1	No Access	No Access	No Access	No Access	No Access	No Access
1	1	H11PCS	Pipe/Cable Shaft in Hallway next to Classroom 101	W2	No Access	No Access	No Access	No Access	No Access	No Access
1	1	H11PCS	Pipe/Cable Shaft in Hallway next to Classroom 101	W3	No Access	No Access	No Access	No Access	No Access	No Access
1	1	H11PCS	Pipe/Cable Shaft in Hallway next to Classroom 101	W4 W1	No Access	No Access	No Access	No Access	No Access	No Access
1	1	H11B H11B	Stairs to Auditorium Left Side Stairs to Auditorium Left Side	W2	Plaster Tile	Gray Unpainted	None N/A	0 N/A	20.8 N/A	Positive N/A
1	1	H11B	Stairs to Auditorium Left Side Stairs to Auditorium Left Side	W3	Plaster	Gray	None None	0	13.9	Positive
1	1	H11B	Stairs to Additionant Left Side Stairs to Auditorium Left Side	W4	Plaster	Gray	None	0	0	Negative
1	1	H11B	Stairs to Auditorium Left Side	Ceiling	Plaster	Tan	None	0	13	Positive
1	1	H11B	Stairs to Auditorium Left Side	Floor	Concrete	Gray	None	0	1.6	Positive
1	1	H11B	Stairs to Auditorium Left Side	Stair Tread	Concrete	Gray	None	0	0.2	Negative
1	1	H11B	Stairs to Auditorium Left Side	Stair Riser	Concrete	Gray	None	0	1.4	Positive
1	1	H11B	Stairs to Auditorium Left Side	Stair Stringer	Concrete	Gray	None	0	1.5	Positive

			Dates: 3/13/2023 to 7/21/2023		Lead-S	afe Certi	fication Asse	essment l	Report	
			Inspector Name and PA License Number: Lawrence Jackson 003683		Par	kwav Ce	nter City Mid	Idle Colle	ae	
			Inspection Company: USA Environmental				treet, Philad			
E	_	1	Management Inc		340 1101	11 13111 3	treet, i illiad	ipilia, i <i>r</i>	13123	
1 5										
е	F									
m	1									
e	0						Description of	Damage	XRF Reading	XRF (positive/
n t	r	Space #	Onsite Room Name	Component	Substrate Material	Paint Color	Description of Damage	Quantity (sf)	(mg/cm2)	negative)
1	1	H11B	Stairs to Auditorium Left Side	Window Casing	Wood	Varnish	None	0	0.3	Negative
1	1	H13	Hallway outside Rear Auditorium Entrance	W1	cmu	White	None	0	22.1	Positive
1	1	H13	Hallway outside Rear Auditorium Entrance	W2	CMU	White	None	0	24.1	Positive
1	1	H13	Hallway outside Rear Auditorium Entrance	W3	CMU	White	None	0	22.3	Positive
1	1	H13	Hallway outside Rear Auditorium Entrance	W4	CMU	White	None	0	21.1	Positive
1	1	H13	Hallway outside Rear Auditorium Entrance	Floor	Concrete	Unpainted	N/A	N/A	N/A	N/A
1	1	H13	Hallway outside Rear Auditorium Entrance	Ceiling	Plaster	White	None	0	18.9	Positive
1	1	H13PCS1	Pipe/Cable Shaft in Hallway next to Stairwell by Classroom 102A	Door	Wood	Varnish	None	0	0.1	Negative
1	1	H13PCS1	Pipe/Cable Shaft in Hallway next to Stairwell by Classroom 102A	Door Frame	Wood	Varnish	None	0	0.2	Negative
1	1	H13PCS1	Pipe/Cable Shaft in Hallway next to Stairwell by Classroom 102A	W1	No Access	No Access	No Access	No Access	No Access	No Access
1	1	H13PCS1	Pipe/Cable Shaft in Hallway next to Stairwell by Classroom 102A	W2	No Access	No Access	No Access	No Access	No Access	No Access
1	1	H13PCS1	Pipe/Cable Shaft in Hallway next to Stairwell by Classroom 102A	W3	No Access	No Access	No Access	No Access	No Access	No Access
1	1	H13PCS1	Pipe/Cable Shaft in Hallway next to Stairwell by Classroom 102A	W4	No Access	No Access	No Access	No Access	No Access	No Access
1	1	H13PCS2	Pipe/Cable Shaft in Hallway above Hydration Station near Classroom 102B	Door	Wood	Varnish	None	0	0	Negative
1	1	H13PCS2	Pipe/Cable Shaft in Hallway above Hydration Station near Classroom 102B	Door Frame	Wood	Varnish	None	0	0.3	Negative
1	1	H13PCS2	Pipe/Cable Shaft in Hallway above Hydration Station near Classroom 102B	W1	No Access	No Access	No Access	No Access	No Access	No Access
1	1	H13PCS2	Pipe/Cable Shaft in Hallway above Hydration Station near Classroom 102B	W2	No Access	No Access	No Access	No Access	No Access	No Access
1	1	H13PCS2	Pipe/Cable Shaft in Hallway above Hydration Station near Classroom 102B	W3	No Access	No Access	No Access	No Access	No Access	No Access
1	1	H13PCS2	Pipe/Cable Shaft in Hallway above Hydration Station near Classroom 102B	W4	No Access	No Access	No Access	No Access	No Access	No Access
1	1	H13PCS3	Pipe/Cable Shaft in Hallway next to Stairwell by Room 103	W1	Brick	Unpainted	N/A	N/A	N/A	N/A
1	1	H13PCS3	Pipe/Cable Shaft in Hallway next to Stairwell by Room 103	W2	Brick	Unpainted	N/A	N/A	N/A	N/A
1	1	H13PCS3	Pipe/Cable Shaft in Hallway next to Stairwell by Room 103	W3	Brick	Unpainted	N/A	N/A	N/A	N/A
1	1	H13PCS3	Pipe/Cable Shaft in Hallway next to Stairwell by Room 103	Door	Wood	Varnish	None	0	0	Negative
1	1	H13PCS3	Pipe/Cable Shaft in Hallway next to Stairwell by Room 103	Door Frame	Wood	Varnish	None	0	0.2	Negative

			Dates: 3/13/2023 to 7/21/2023		Lead-S	afe Certi	fication Asse	essment l	Report	
			Inspector Name and PA License Number:		Pai	rkway Co	nter City Mid	Idla Calla	uuo	
			Lawrence Jackson 003683 Inspection Company: USA Environmental		ı aı	Kway Oc	inter Only Wild	idie Oolie	ge	
			Management Inc		540 Nor	th 13th S	treet, Philade	elphia, PA	A 19123	
E			<u> </u>				·	<u> </u>		
I	_									
e m	F									
e	6									XRF
n	0						Description of	Damage	XRF Reading	(positive/
t	r	Space #	Onsite Room Name	Component	Substrate Material	Paint Color	Damage	Quantity (sf)	(mg/cm2)	negative)
1	1	107	Auditorium	W1	Plaster	White	Flaking	40	20.2	Positive
1	1	107	Auditorium	W1	Wood	White	None	0	13.2	Positive
1	1	107	Auditorium	W2	Plaster	White	Efflorescence	200	25.3	Positive
1	1	107	Auditorium	W2	Wood	White	None	0	13.6	Positive
1	1	107	Auditorium	W3	Plaster	White	Efflorescence	100	22.7	Positive
1	1	107	Auditorium	W3 W4	Wood	White	None	20	12.6 24	Positive Positive
1	1	107	Auditorium	W4	Plaster Wood	White White	Cracking None	0	12.7	Positive
1	1	107 107	Auditorium Auditorium	Door	Wood	White	None	0	14.9	Positive
1	1	107	Auditorium	Door Casing	Wood	White	None	0	16.5	Positive
1	1	107	Auditorium	Window Casing	Wood	White	None	0	16.5	Positive
1	1	107	Auditorium	Radiator Cover	Metal	White	None	0	4.9	Positive
1	1	107	Auditorium	Floor	Wood	Unpainted	N/A	N/A	N/A	N/A
1	1	107	Auditorium	Baseboard	Wood	Brown	None	0	22.4	Positive
1	1	107	Auditorium	Ceiling	Plaster	White	Flaking	300	11.9	Positive
1	1		Auditorium Stage	W1	Plaster	Black	Flaking	120	4.3	Positive
1	1		Auditorium Stage	W2	Plaster	White	Flaking	300	0	Negative
1	1		Auditorium Stage	W3	Plaster	White	Flaking	100	5.7	Positive
1	1		Auditorium Stage	W4	Plaster	White	Flaking	220	0	Negative
1	1		Auditorium Stage	Ceiling	Plaster	White	Flaking	60	No Access	Assumed
1	1		Auditorium Stage	Floor	Wood	Unpainted	N/A	N/A	N/A	N/A
1	1		Auditorium Stage	Radiator	Metal	Gray	Flaking	5	0.1	Negative
1	1	H13A	Main Lobby	W1	Plaster	White	None	0	8.2	Positive
1	1	H13A	Main Lobby	W2	Plaster	White	Cracking	10	10	Positive
1	1	H13A	Main Lobby	W3	Plaster	White	None	0	8.3	Positive
1	1	H13A	Main Lobby	W4	Plaster	White	Cracking	5	9.3	Positive
1	1	H13A	Main Lobby	Floor	Ceramic	Unpainted	N/A	N/A	N/A	N/A
1	1	H13A	Main Lobby	Ceiling	Plaster	White	None	0	9.6	Positive
1	1	H13B	Main Entrance Vestibule	W1	Ceramic Tile	Unpainted	N/A	N/A	N/A	N/A
1	1	H13B	Main Entrance Vestibule	W2	Ceramic Tile	Unpainted	N/A	N/A	N/A	N/A
1	1	H13B	Main Entrance Vestibule	W3	Ceramic Tile	Unpainted	N/A	N/A	N/A	N/A
1	1	H13B	Main Entrance Vestibule	W4	Ceramic Tile	Unpainted	N/A	N/A	N/A	N/A
1	1	H13B	Main Entrance Vestibule	Floor	Ceramic	Unpainted	N/A	N/A	N/A	N/A
1	1	H13B	Main Entrance Vestibule	Ceiling	Plaster	White	Flaking	5	6.5	Positive
1	1	H13B	Main Entrance Vestibule	Door	Metal	Brown	None	0	0	Negative

			Dates: 3/13/2023 to 7/21/2023		Lead-S	afe Certi	fication Asso	essment l	Report	
			Inspector Name and PA License Number:		D	.1	4 O'4 NI'-	1-11- 0-11-		
			Lawrence Jackson 003683		Pai	rkway Ce	nter City Mic	adie Colle	ege	
			Inspection Company: USA Environmental		F40 No.	41- 4041- 0	4ma a4 Dla!la d	alalaia Di	10400	
			Management Inc		540 NOr	tn 13tn 5	treet, Philad	eipnia, P	4 19123	
E										
l e	F									
m	Ι'n									
е	o									XRF
n	0			_			Description of	Damage	XRF Reading	(positive/
t	r	Space #	Onsite Room Name	Component	Substrate Material	Paint Color	Damage	Quantity (sf)	(mg/cm2)	negative)
1	1	H13B	Main Entrance Vestibule	Door Frame	Metal	Brown	None	0	0	Negative
1	1	102B	Classroom to Left of Main Entrance Vestibule	W1 W2	Plaster CMU	White White	Efflorescence None	60	5.1 0.2	Positive
1	1	102B 102B	Classroom to Left of Main Entrance Vestibule Classroom to Left of Main Entrance Vestibule	W3	Plaster	White		3	3.3	Negative Positive
1	1	102B	Classroom to Left of Main Entrance Vestibule Classroom to Left of Main Entrance Vestibule	W4	Plaster	White	Chipping None	0	0.3	Negative
1	1	102B	Classroom to Left of Main Entrance Vestibule Classroom to Left of Main Entrance Vestibule	Ceiling	Plaster	White	None	0	9.8	Positive
1	1	102B	Classroom to Left of Main Entrance Vestibule Classroom to Left of Main Entrance Vestibule	Floor	Wood	Unpainted	N/A	N/A	N/A	N/A
1	1	102B	Classroom to Left of Main Entrance Vestibule	Door	Wood	Brown	None	0	0	Negative
1	1	102B	Classroom to Left of Main Entrance Vestibule	Door Frame	Wood	Brown	None	0	0.1	Negative
1	1	102B	Classroom to Left of Main Entrance Vestibule	Baseboard	Wood	Brown	None	0	0.1	Negative
1	1	102B	Classroom to Left of Main Entrance Vestibule	Radiator	Metal	Brown	None	0	3.1	Positive
1	1	102B	Classroom to Left of Main Entrance Vestibule	Window Casing	Wood	Brown	None	0	0.2	Negative
1	1	102B	Classroom to Left of Main Entrance Vestibule	Window Sill	Wood	Brown	None	0	0	Negative
1	1	102B	Classroom to Left of Main Entrance Vestibule	Window Apron	Wood	Brown	None	0	0.1	Negative
1	В	S06	Main Entrance Vestibule Stairs to Men's Restroom	W1	Plaster	White	Flaking	60	16.1	Positive
1	В	S06	Main Entrance Vestibule Stairs to Men's Restroom	W2	Plaster	White	Flaking	20	19.6	Positive
1	В	S06	Main Entrance Vestibule Stairs to Men's Restroom	W3	Plaster	White	Flaking	80	0	Negative
1	В	S06	Main Entrance Vestibule Stairs to Men's Restroom	W4	Plaster	White	Flaking	10	16.4	Positive
1	В	S06	Main Entrance Vestibule Stairs to Men's Restroom	Ceiling	Plaster	White	Flaking	5	16.2	Positive
1	В	S06	Main Entrance Vestibule Stairs to Men's Restroom	Door	Wood	Varnish	None	0	0.1	Negative
1	В	S06	Main Entrance Vestibule Stairs to Men's Restroom	Door Casing	Wood	Varnish	None	0	0.2	Negative
1	В	S06	Main Entrance Vestibule Stairs to Men's Restroom	Radiator Panel	Wood	Varnish	None	0	0	Negative
1	В	S06	Main Entrance Vestibule Stairs to Men's Restroom	Stair Tread	Marble	Unpainted	N/A N/A	N/A N/A	N/A N/A	N/A N/A
1	В	S06	Main Entrance Vestibule Stairs to Men's Restroom	Stair Riser	Marble	Unpainted	N/A N/A		N/A N/A	N/A N/A
1	B	S06 9	Main Entrance Vestibule Stairs to Men's Restroom Men's Restroom below Main Entrance Vestibule	Stair Stringer W1	Marble Plaster	Unpainted White	Flaking	N/A 40	18.8	N/A Positive
1	В	9	Men's Restroom below Main Entrance Vestibule	W2	Plaster	White	Flaking	80	17.3	Positive
1	В	9	Men's Restroom below Main Entrance Vestibule	W3	Plaster	White	Flaking	20	0	Negative
1	В	9	Men's Restroom below Main Entrance Vestibule	W4	Plaster	White	Flaking	100	2	Positive
1	В	9	Men's Restroom below Main Entrance Vestibule	Ceiling	Plaster	White	Flaking	50	19.1	Positive
1	В	9	Men's Restroom below Main Entrance Vestibule	Floor	Concrete	Gray	Flaking	40	0.2	Negative
1	В	9	Men's Restroom below Main Entrance Vestibule	Window Casing	Wood	Varnish	None	0	0.5	Negative
1	В	9	Men's Restroom below Main Entrance Vestibule	Drain Pipe	Metal	White	Chipping	4	24.3	Positive
1	В	9	Men's Restroom below Main Entrance Vestibule	Radiator	Metal	White	Chipping	3	No Access	Assumed
1	В	9	Men's Restroom below Main Entrance Vestibule	Partition Wall	Marble	White	Flaking	5	0.2	Negative
1	В	9	Men's Restroom below Main Entrance Vestibule	Partition Door	Wood	White	None	0	0.2	Negative
1	В	9	Men's Restroom below Main Entrance Vestibule	Partition Wall	Wood	White	None	0	0.2	Negative
1	В	9	Men's Restroom below Main Entrance Vestibule	Partition Door	Wood	White	Flaking	5	0	Negative

			Dates: 3/13/2023 to 7/21/2023		Lead-S	afe Certi	fication Asse	essment l	Report	
			Inspector Name and PA License Number:		_				•	
			Lawrence Jackson 003683		Pai	rkway Ce	nter City Mid	ldle Colle	ge	
			Inspection Company: USA Environmental							
			Management Inc		540 Nor	th 13th S	treet, Philade	elphia, P <i>i</i>	A 19123	
E										
ı	_									
e	F									
m e										XRF
n	0						Description of	Damage	XRF Reading	(positive/
t	r	Space #	Onsite Room Name	Component	Substrate Material	Paint Color	Damage	Quantity (sf)	(mg/cm2)	negative)
1	В	S05	Main Entrance Vestibule Stairs to Women's Restroom	W1	Plaster	White	Cracking	40	17.5	Positive
1	В	S05	Main Entrance Vestibule Stairs to Women's Restroom	W2	Plaster	White	Flaking	15	19.1	Positive
1	В	S05	Main Entrance Vestibule Stairs to Women's Restroom	W3	Plaster	White	Flaking	10	19.2	Positive
1	В	S05	Main Entrance Vestibule Stairs to Women's Restroom	Ceiling	Plaster	White	Alligatoring	10	21.8	Positive
1	В	S05	Main Entrance Vestibule Stairs to Women's Restroom	Door	Wood	Varnish	None	0	0	Negative
1	В	S05	Main Entrance Vestibule Stairs to Women's Restroom	Door Casing	Wood	Varnish	None	0	0.1	Negative
1	В	S05	Main Entrance Vestibule Stairs to Women's Restroom	Radiator Panel Stair Tread	Wood Marble	Varnish Unpainted	None N/A	N/A	0.2 N/A	Negative N/A
1	B	S05 S05	Main Entrance Vestibule Stairs to Women's Restroom Main Entrance Vestibule Stairs to Women's Restroom	Stair Riser	Marble	Unpainted	N/A N/A	N/A N/A	N/A N/A	N/A N/A
1	В	S05	Main Entrance Vestibule Stairs to Women's Restroom	Stair Stringer	Marble	Unpainted	N/A N/A	N/A N/A	N/A N/A	N/A N/A
1	В	S05	Main Entrance Vestibule Stairs to Women's Restroom	Drain Pipe	Metal	White	Flaking	3	0.1	Negative
1	В	8-1	Women's Restroom below Main Entrance Vestibule	W1	Plaster	White	Flaking	100	20.4	Positive
1	В	8-1	Women's Restroom below Main Entrance Vestibule	W2	Plaster	White	Cracking	200	20.4	Positive
1	В	45139	Women's Restroom below Main Entrance Vestibule	W3	Plaster	White	Cracking	100	0	Negative
1	В	45139	Women's Restroom below Main Entrance Vestibule	W4	Plaster	White	Cracking	200	3.8	Positive
1	В	45139	Women's Restroom below Main Entrance Vestibule	Ceiling	Plaster	White	Flaking	200	0.1	Negative
1	В	45139	Women's Restroom below Main Entrance Vestibule	Floor	Concrete	Unpainted	N/A	N/A	N/A	N/A
1	В	45139	Women's Restroom below Main Entrance Vestibule	Window Casing	Wood	Varnish	None	0	0.5	Negative
1	В	8-1	Women's Restroom below Main Entrance Vestibule	Drain Pipe	Metal	White	Flaking	12	25.3	Positive
1	В	8-1	Women's Restroom below Main Entrance Vestibule	Radiator	Metal	White	Cracking	10	No Access	Assumed
1	1	103A	Women's Restroom Next to Main Lobby	W1	Plaster	White	Flaking	20	21	Positive
1	1	103A	Women's Restroom Next to Main Lobby	W2	Plaster	White	Flaking	10	15.6	Positive
1	1	103A	Women's Restroom Next to Main Lobby	W3	Plaster	White	Flaking	10	1.2	Positive
1	1	103A	Women's Restroom Next to Main Lobby	W4	Plaster	White	None	0	1.6	Positive
1	1	103A	Women's Restroom Next to Main Lobby	Ceiling	Plaster	Tan	Chipping	30	18.3	Positive
1	1	103A	Women's Restroom Next to Main Lobby	Floor	Concrete	Gray	None	0	0	Negative
1	1	103A	Women's Restroom Next to Main Lobby	Floor	Wood	Brown	None	0	0.3	Negative
1	1	103A	Women's Restroom Next to Main Lobby	Door	Wood	Varnish	None	0	0.1	Negative
1	1	103A	Women's Restroom Next to Main Lobby	Door Frame	Wood	Brown	None	0	0.1	Negative
1	1	103A	Women's Restroom Next to Main Lobby	Baseboard	Wood	Brown	None	0	0.2	Negative
1	1	103A	Women's Restroom Next to Main Lobby	Window Casing	Wood	Brown	None	0	0.4	Negative
1	1	103A	Women's Restroom Next to Main Lobby	Window Sill	Wood	Brown	None	0	0.1	Negative
1	1	103A	Women's Restroom Next to Main Lobby	Window Apron	Wood	Brown	None	0	0.3	Negative
1	1	103A	Women's Restroom Next to Main Lobby	Radiator	Metal	Gray	None	0	6.2	Positive
1	1	103E	Women's Restroom Next to Main Lobby Closet 1	Door	Wood	Varnish	None	0	0.1	Negative

			Dates: 3/13/2023 to 7/21/2023	Lead-Safe Certification Assessment Report Parkway Center City Middle College							
			Inspector Name and PA License Number:		Pai	kway Co	nter City Mic	Idla Calla	ane.		
			Lawrence Jackson 003683 Inspection Company: USA Environmental		ı aı	Kway Oc	inter Only wife	idie Oolie	ge		
			Management Inc		540 Nor	th 13th S	treet, Philad	elphia, P	A 19123		
E											
e	F										
m	l i l										
е	o									XRF	
n	0						Description of	Damage	XRF Reading	(positive/	
t	r	Space #	Onsite Room Name	Component	Substrate Material	Paint Color	Damage	Quantity (sf)	(mg/cm2)	negative)	
1	1	103E	Women's Restroom Next to Main Lobby Closet 1	Door Frame	Wood	Varnish	None	0	0.1	Negative	
1	1	103E	Women's Restroom Next to Main Lobby Closet 1	W1	Plaster	Tan	None	0	1.7	Positive	
1	1	103E	Women's Restroom Next to Main Lobby Closet 1	W2 W3	Plaster	Tan	None	0	1.5 1.5	Positive	
1	1	103E	Women's Restroom Next to Main Lobby Closet 1	W4	Plaster Plaster	Tan Tan	None None	0	1.6	Positive Positive	
1	1	103E 103E	Women's Restroom Next to Main Lobby Closet 1	Shelf	Wood	Tan	None	0	0.1	Negative	
1	1	103E	Women's Restroom Next to Main Lobby Closet 1 Women's Restroom Next to Main Lobby Closet 1	Ceiling	Plaster	Tan	None	0	2	Positive	
1	1	103E	Women's Restroom Next to Main Lobby Closet 1	Door	Wood	Varnish	None	0	0.2	Negative	
1	1	103F	Women's Restroom Next to Main Lobby Closet 2	Door Frame	Wood	Varnish	None	0	0.1	Negative	
1	1	103F	Women's Restroom Next to Main Lobby Closet 2	W1	Plaster	Tan	None	0	1.8	Positive	
1	1	103F	Women's Restroom Next to Main Lobby Closet 2	W2	Plaster	Tan	None	0	2	Positive	
1	1	103F	Women's Restroom Next to Main Lobby Closet 2	W3	Plaster	Tan	None	0	2.2	Positive	
1	1	103F	Women's Restroom Next to Main Lobby Closet 2	W4	Plaster	Tan	None	0	2.4	Positive	
1	1	103F	Women's Restroom Next to Main Lobby Closet 2	Ceiling	Plaster	Tan	None	0	2.1	Positive	
1	1	103F	Women's Restroom Next to Main Lobby Closet 2	Shelf	Wood	Tan	None	0	0.1	Negative	
1	1	103	Office Suite 103 Reception Area	W1	Fabric	Unpainted	N/A	N/A	N/A	N/A	
1	1	103	Office Suite 103 Reception Area	W2	Plaster	White	None	0	20.7	Positive	
1	1	103	Office Suite 103 Reception Area	W3	Fabric	Unpainted	N/A	N/A	N/A	N/A	
1	1	103	Office Suite 103 Reception Area	W4	Plaster	White	None	0	16.6	Positive	
1	1	103	Office Suite 103 Reception Area	Floor	12 x 12 Floor Tile	Unpainted	N/A	N/A	N/A	N/A	
1	1	103	Office Suite 103 Reception Area	Door	Wood	Varnish	None	0	0	Negative	
1	1	103	Office Suite 103 Reception Area	Door Frame	Wood	Varnish	None	0	0.2	Negative	
1	1	103	Office Suite 103 Reception Area	Ceiling	Plaster	Tan	Cracking	60	25	Positive	
1	1	103	Office Suite 103 Reception Area	Radiator	Metal	Gray	None	0	0.2	Negative	
1	1	103	Office Suite 103 Reception Area	Window Casing	Wood	Varnish	None	0	0.3	Negative	
1	1	103	Office Suite 103 Reception Area	Window Sill	Wood	Varnish	None	0	0.4	Negative	
1	1	103	Office Suite 103 Reception Area	Floor Trench Cover	Metal	Black	None	0	0.4	Negative	
1	1	103B	Office Suite 103 Office adjacent to Kitchen	W1	Plaster	Tan	None	0	0.3	Negative	
1	1	103B	Office Suite 103 Office adjacent to Kitchen	W2	Plaster	Tan	None	0	9.8	Positive	
1	1	103B	Office Suite 103 Office adjacent to Kitchen	W3	Fabric	Unpainted	N/A	N/A	N/A	N/A	
1	1	103B	Office Suite 103 Office adjacent to Kitchen	W4	Fabric	Unpainted	N/A	N/A	N/A	N/A	
1	1	103B	Office Suite 103 Office adjacent to Kitchen	Floor	12 x 12 Floor Tile	Unpainted	N/A	N/A	N/A	N/A	
1	1	103B	Office Suite 103 Office adjacent to Kitchen	Ceiling	Plaster	Tan	Efflorescence	25	25.1	Positive	
1	1	103B	Office Suite 103 Office adjacent to Kitchen	Door	Wood	Varnish	None	0	0	Negative	
1	1	103B	Office Suite 103 Office adjacent to Kitchen	Door Frame	Metal	Brown	None	0	0	Negative	
1	1	103B	Office Suite 103 Office adjacent to Kitchen	Window Casing	Wood	Varnish	None	0	0.5	Negative	
1	1	103B	Office Suite 103 Office adjacent to Kitchen	Window Casing	Wood	Varnish	None	0	0.5	Negative	

			Dates: 3/13/2023 to 7/21/2023		Lead-S	afe Certif	fication Asse	essment l	Report		
			Inspector Name and PA License Number:	Parkway Center City Middle College							
			Lawrence Jackson 003683 Inspection Company: USA Environmental		ı aı	Kway Oc	inter Only Wife		gc		
			Management Inc		540 Nor	th 13th S	treet, Philad	elphia, PA	19123		
E I e m e n t	F I O O r	Space #	Onsite Room Name	Component	Substrate Material	Paint Color	Description of Damage	Damage Quantity (sf)	XRF Reading (mg/cm2)	XRF (positive/ negative)	
1	1	103B	Office Suite 103 Office adjacent to Kitchen	Window Sill	Wood	Varnish	None	0	0.3	Negative	
1	1	103B	Office Suite 103 Office adjacent to Kitchen	Radiator	Wood	Varnish	None	0	0.4	Negative	
1	1	103C	Office Suite 103 Kitchen	W1	Fabric	Unpainted	N/A	N/A	N/A	N/A	
1	1	103C	Office Suite 103 Kitchen	W2	Plaster	White	Flaking	10	23	Positive	
1	1	103C	Office Suite 103 Kitchen	W3	Plaster	White	Flaking	50	20.5	Positive	
1	1	103C	Office Suite 103 Kitchen	W4	Fabric	Unpainted	N/A	N/A	N/A	N/A	
1	1	103C	Office Suite 103 Kitchen	Ceiling	Plaster	Tan	Flaking	40	27.1	Positive	
1	1	103C	Office Suite 103 Kitchen	Floor	12 x 12 Floor Tile	Unpainted	N/A	N/A	N/A	N/A	
1	1	103C	Office Suite 103 Kitchen	Door	Wood	Varnish	None	0	0	Negative	
1	1	103C	Office Suite 103 Kitchen	Door Frame	Metal	Brown	None	0	0	Negative	
1	1	103G	Office Suite 103 Office adjacent to Restroom	Ceiling	Plaster	Tan	Cracking	5	24.3	Positive	
1	1	103G	Office Suite 103 Office adjacent to Restroom	W1	Plaster	White	None	0	20.4	Positive	
1	1	103G	Office Suite 103 Office adjacent to Restroom	W2	Plaster	White	None	0	28	Positive	
1	1	103G	Office Suite 103 Office adjacent to Restroom	W3	Plaster	White	None	0	27.2	Positive	
1	1	103G	Office Suite 103 Office adjacent to Restroom	W4	Fabric	Unpainted	N/A	N/A	N/A	N/A	
1	1	103G	Office Suite 103 Office adjacent to Restroom	Door Frame	Metal	Brown	None	0	0	Negative	
1	1	103G	Office Suite 103 Office adjacent to Restroom	Door	Wood	Varnish	None	0	0	Negative	
1	1	103G	Office Suite 103 Office adjacent to Restroom	Window Casing	Wood	Varnish	None	0	0.4	Negative	
1	1	103G	Office Suite 103 Office adjacent to Restroom	Window Sill	Wood	Varnish	None	0	0.3	Negative	
1	1	103G	Office Suite 103 Office adjacent to Restroom	Radiator	Metal	Gray	None	0	0.3	Negative	
1	1	103D	Office Suite 103 Restroom	W1	Plaster	White	None	0	14	Positive	
1	1	103D	Office Suite 103 Restroom	W2	Plaster	White	None	0	11.2	Positive	
1	1	103D	Office Suite 103 Restroom	W3	Plaster	White	None	0	9.7	Positive	
1	1	103D	Office Suite 103 Restroom	W4	Plaster	White	None	0	13.8	Positive	
1	1	103D	Office Suite 103 Restroom	Ceiling	Plaster	Tan	No Access	N/A	No Access	Negative	
1	1	103D	Office Suite 103 Restroom	Floor	12 x 12 Floor Tile	Unpainted	N/A	N/A	N/A	N/A	
1	1	103D	Office Suite 103 Restroom	Door	Wood	Varnish	None	0	0	Negative	
1	1	103D	Office Suite 103 Restroom	Door Frame	Wood	Varnish	None	0	0	Negative	
1	1	S13	Stairwell adjacent to Office Suite 103	W1	Plaster	Gray	Cracking	20	0.3	Negative	
1	1	S13	Stairwell adjacent to Office Suite 103	W2	Plaster	Gray	Cracking	5	0.1	Negative	
1	1	S13	Stairwell adjacent to Office Suite 103	W3	Plaster	Gray	Cracking	40	3.8	Positive	
1	1	S13	Stairwell adjacent to Office Suite 103	W4	Plaster	Gray	Cracking	8	6.8	Positive	
1	1	S13	Stairwell adjacent to Office Suite 103	Ceiling	Plaster	Gray	None	0	7.6	Positive	
1	1	S13	Stairwell adjacent to Office Suite 103	Floor	Concrete	Gray	None	0	1.7	Positive	
1	1	S13	Stairwell adjacent to Office Suite 103	Radiator	Metal	Gray	Chipping	5	0.3	Negative	
1	1	S13	Stairwell adjacent to Office Suite 103	Stair Tread	Concrete	Gray	Chipping	4	0	Negative	
1	1	S13	Stairwell adjacent to Office Suite 103	Stair Riser	Concrete	Gray	Chipping	2	1.2	Positive	
1	1	S13	Stairwell adjacent to Office Suite 103	Stair Stringer	Metal	Gray	Chipping	4	1.7	Positive	

			Dates: 3/13/2023 to 7/21/2023		Lead-S	afe Certi	fication Asse	essment l	Report	
			Inspector Name and PA License Number:		Par	kway Co	nter City Mic	Idla Calla	uuo	
			Lawrence Jackson 003683		ı aı	Kway Oc	inter Only wife	idie Oolie	ge	
			Inspection Company: USA Environmental Management Inc		540 Nor	th 13th S	treet, Philad	elphia, PA	A 19123	
Е							,	•		
ı	l _									
e m	F									
e										XRF
n	0						Description of	Damage	XRF Reading	(positive/
t	r	Space #	Onsite Room Name	Component	Substrate Material	Paint Color	Damage	Quantity (sf)	(mg/cm2)	negative)
1	1	S13A	Closet in Stairwell adjacent to Office Suite 103	No Access	No Access	No Access	No Access	No Access	No Access	No Access
1	1	S13A	Closet in Stairwell adjacent to Office Suite 103	No Access	No Access	No Access	No Access	No Access	No Access	No Access
1	1	S13A	Closet in Stairwell adjacent to Office Suite 103	No Access	No Access	No Access	No Access	No Access	No Access	No Access
1	1	S13A	Closet in Stairwell adjacent to Office Suite 103	No Access	No Access	No Access	No Access	No Access	No Access	No Access
1	1	S13A	Closet in Stairwell adjacent to Office Suite 103	No Access	No Access	No Access	No Access	No Access	No Access	No Access
1	1	S13A	Closet in Stairwell adjacent to Office Suite 103	No Access	No Access	No Access	No Access	No Access	No Access	No Access
1	1	104	Office Suite 104 Hallway and Common Area	W1	Sheetrock	White	None	0	0.1	Negative
1	1	104	Office Suite 104 Hallway and Common Area	W2	Sheetrock	White	None	0	0.1	Negative
1	1	104	Office Suite 104 Hallway and Common Area	W3	Sheetrock	White	None	0	5.5	Positive
1	1	104	Office Suite 104 Hallway and Common Area	W4	Sheetrock	White	None	0	23.3	Positive
1	1	104	Office Suite 104 Hallway and Common Area	Door	Wood	White	None	0	0	Negative
1	1	104	Office Suite 104 Hallway and Common Area	Floor	12 x 12 Floor Tile	White	None	0	0	Negative
1	1	104	Office Suite 104 Hallway and Common Area	Door Frame	Wood	Brown	None	0	0.1	Negative
1	1	104A	Office Suite 104 Southwest Office	W1	Sheetrock	White	None	0	0	Negative
1	1	104A	Office Suite 104 Southwest Office	W2	Tile	White	None	0	24.8	Positive
1	1	104A	Office Suite 104 Southwest Office	W3 W4	Plaster	White	None	0	0.7	Positive
1	1	104A	Office Suite 104 Southwest Office		Sheetrock	White	None	0	0.1	Negative
1	1	104A	Office Suite 104 Southwest Office	Door Floor	Wood 12 x 12 Floor Tile	White White	None None	0	0	Negative Negative
1	1	104A	Office Suite 104 Southwest Office	Door Frame	Metal	Brown	None	0	0.1	Negative
1	1	104A	Office Suite 104 Southwest Office Office Suite 104 Southwest Area Facilities		ivietai	DIOWII	None	-		ivegative
1	1	104B	Management Office	W1	Sheetrock	White	None	0	0	Negative
1	1	104B	Office Suite 104 Southwest Area Facilities Management Office	W2	Plaster	White	None	0	19.1	Positive
1	1	104B	Office Suite 104 Southwest Area Facilities Management Office	W3	Sheetrock	White	None	0	0.1	Negative
1	1	104B	Office Suite 104 Southwest Area Facilities Management Office	W4	Sheetrock	White	None	0	0.1	Negative
1	1	104B	Office Suite 104 Southwest Area Facilities Management Office	Door	Wood	Varnish	None	0	0	Negative
-	+-'-	1040	Office Suite 104 Southwest Area Facilities					_		
1	1	104B	Management Office	Door Frame	Metal	Brown	None	0	0	Negative
1	1	104B	Office Suite 104 Southwest Area Facilities Management Office	Floor	12 x 12 Floor Tile	Unpainted	N/A	N/A	N/A	N/A
1	1	104C	Office Suite 104 Camera Room	W1	Tile	Tan	None	0	36	Positive
1	1	104C	Office Suite 104 Camera Room	W1	Plaster	Tan	None	0	27.3	Positive
1	1	104C	Office Suite 104 Camera Room	W2	Tile	Tan	None	0	34	Positive
1	1	104C	Office Suite 104 Camera Room	W2	Plaster	Tan	None	0	21.4	Positive
1	1	104C	Office Suite 104 Camera Room	W3	Sheetrock	Tan	None	0	0.1	Negative

			Dates: 3/13/2023 to 7/21/2023		Lead-S	afe Certi	fication Asse	essment F	Report	
			Inspector Name and PA License Number:		D	-l O -	4 O:4 NA:-I			
			Lawrence Jackson 003683		Pai	rkway Ce	nter City Mid	iale Colle	ge	
			Inspection Company: USA Environmental		540 Nor	th 12th S	treet, Philad	olobia D/	10122	
	1	1	Management Inc		340 1101	นา เจนา จ	treet, Filliau	eipilia, P	19123	
E I e m e	F I o									XRF
n t	o r	Space #	Onsite Room Name	Component	Substrate Material	Paint Color	Description of Damage	Damage Quantity (sf)	XRF Reading (mg/cm2)	(positive/ negative)
1	1	104C	Office Suite 104 Camera Room	W3	Plaster	Tan	None	0	17.2	Positive
1	1	104C	Office Suite 104 Camera Room	W3	Tile	Tan	None	0	36	Positive
1	1	104C	Office Suite 104 Camera Room	W4	Sheetrock	Tan	None	0	0.1	Negative
1	1	104C	Office Suite 104 Camera Room	Door	Wood	Varnish	None	0	0	Negative
1	1	104C	Office Suite 104 Camera Room	Door Frame	Metal	Brown	None	0	0	Negative
1	1	104C	Office Suite 104 Camera Room	Window Casing	Wood	Varnish	None	0	0	Negative
1	1	105A	Office Suite 104 Camera Room Closet	Door	Wood	Varnish	None	0	0	Negative
1	1	105A	Office Suite 104 Camera Room Closet	Door Frame	Wood	Brown	None	0	0.1	Negative
1	1	105A	Office Suite 104 Camera Room Closet	W1	Plaster	White	None	0	3.4	Positive
1	1	105A	Office Suite 104 Camera Room Closet	W2	Plaster	White	None	0	3.3	Positive
1	1	105A	Office Suite 104 Camera Room Closet	W3	Plaster	White	Efflorescence	40	2.3	Positive
1	1	105A	Office Suite 104 Camera Room Closet	W4	Plaster	White	Efflorescence	10	4.1	Positive
1	1	105A	Office Suite 104 Camera Room Closet	Window Casing	Wood	Varnish	None	0	0.3	Negative
1	1	105A	Office Suite 104 Camera Room Closet	Window Sill	Wood	Varnish	None	0	0.2	Negative
1	1	105A	Office Suite 104 Camera Room Closet	Window Apron	Wood	Varnish	None	0	0.1	Negative
1	1	104D	Office Suite 104 Office at end of Hallway	W1	Plaster	White	None	0	15.3	Positive
1	1	104D	Office Suite 104 Office at end of Hallway	W2	Plaster	White	None	0	21.7	Positive
1	1	104D	Office Suite 104 Office at end of Hallway	W3	Sheetrock	White	None	0	0	Negative
1	1	104D	Office Suite 104 Office at end of Hallway	W4	Sheetrock	White	None	0	0.1	Negative
1	1	104D	Office Suite 104 Office at end of Hallway	Door	Wood	Varnish	None	0	0	Negative
1	1	104D	Office Suite 104 Office at end of Hallway	Door Frame	Metal	Brown	None	0	0.1	Negative
1	1	104D	Office Suite 104 Office at end of Hallway	Floor	12 x 12 Floor Tile	Unpainted	N/A	N/A	N/A	N/A
1	1	104E	Office Suite 104 Northeast Area Services Office in Center	W1	Sheetrock	White	None	0	0.1	Negative
1	1	104E	Office Suite 104 Northeast Area Services Office in Center	W2	Plaster	White	None	0	11.4	Positive
1	1	104E	Office Suite 104 Northeast Area Services Office in Center	W3	Sheetrock	White	None	0	0.1	Negative
1	1	104E	Office Suite 104 Northeast Area Services Office in Center	W4	Sheetrock	White	None	0	0.1	Negative
1	1	104E	Office Suite 104 Northeast Area Services Office in Center	Door	Wood	Varnish	None	0	0	Negative
1	1	104E	Office Suite 104 Northeast Area Services Office in Center	Door Frame	Metal	Brown	None	0	0	Negative
1	1	104E	Office Suite 104 Northeast Area Services Office in Center	Floor	12 x 12 Floor Tile	Unpainted	N/A	N/A	N/A	N/A
1	1	104F	Office Suite 104 Northwest Area Services Office on End	W1	Sheetrock	White	None	0	0	Negative

			Dates: 3/13/2023 to 7/21/2023		Lead-S	afe Certi	fication Asse	essment l	Report	
			Inspector Name and PA License Number:		D	d	4 a O!4 NA! a	Idla Oalla		
			Lawrence Jackson 003683		Pai	rkway Ce	nter City Mid	iale Colle	ge	
			Inspection Company: USA Environmental		E 40 No.	4h 404h 0	tuant Dhilad	alabia Di	10400	
			Management Inc		540 NOr	tn 13tn 5	treet, Philad	eipnia, P	19123	
E										
e	F									
m	i									
е	0									XRF
n	0	0	Ouelte De eur Neue	0	Outstant Material	Daint Calan	Description of	Damage	XRF Reading	(positive/
t	r	Space #	Onsite Room Name Office Suite 104 Northwest Area Services Office on	Component	Substrate Material	Paint Color	Damage	Quantity (sf)	(mg/cm2)	negative)
1	1	104F	End	W2	Plaster	White	None	0	26	Positive
			Office Suite 104 Northwest Area Services Office on	W3	Sheetrock	White	None	0	0.2	Negative
1	1	104F	End Office Suite 104 Northwest Area Services Office on		0.1001.001.				0.2	
1	1	104F	End	W4	Sheetrock	White	None	0	0.1	Negative
<u> </u>	<u> </u>	.511	Office Suite 104 Northwest Area Services Office on	Door	Wood	Varnish	None	0	0	Negative
1	1	104F	End	1000	vvoou	vaiiliSii	NULLE	U	U	iveyative
1	1	104F	Office Suite 104 Northwest Area Services Office on End	Door Frame	Metal	Brown	None	0	0	Negative
<u> </u>	<u>'</u>	1041	Office Suite 104 Northwest Area Services Office on		10 10 51 71		A1/A			N./A
1	1	104F	End	Floor	12 x 12 Floor Tile	Unpainted	N/A	N/A	N/A	N/A
1	1	105	Classroom 105	W1	Plaster	White	None	0	0	Negative
1	1	105	Classroom 105	W2	Plaster	White	None	0	8.2	Positive
1	1	105	Classroom 105	W3	Plaster	White	None	0	8	Positive
1	1	105	Classroom 105	W4	Plaster	White	None	0	8.9	Positive
1	1	105	Classroom 105	W1	Sheetrock	White	None	0	0	Negative
1	1	105	Classroom 105	W2	Sheetrock	White	None	0	0	Negative
1	1	105	Classroom 105	Ceiling	Plaster	White	Cracking	10	10.5	Positive
1	1	105	Classroom 105	Radiator	Metal	Gray	None	0	0	Negative
1	1	105B	Classroom 105 Cleaning Supply Usage Restroom	W1	Plaster	White	Cracking	30	7.8	Positive
1	1	105B	Classroom 105 Cleaning Supply Usage Restroom	W2	Plaster	White	None	0	9.9	Positive
1	1	105B	Classroom 105 Cleaning Supply Usage Restroom	W3 W4	Sheetrock	White	None	0	0	Negative
1	1 1	105B	Classroom 105 Cleaning Supply Usage Restroom	Ceiling	Sheetrock Plaster	White White	None	15	10.2	Negative Positive
1	1	105B 105B	Classroom 105 Cleaning Supply Usage Restroom	Floor	Wood	Unpainted	Chipping N/A	N/A	N/A	N/A
1	1	H12C	Classroom 105 Cleaning Supply Usage Restroom Hallway adjacent to Classroom 105	W1	Plaster	Gray	None	0	17.7	Positive
1	1	H12C	Hallway adjacent to Classroom 105	W2	Plaster	Gray	None	0	17.5	Positive
1	1	H12C	Hallway adjacent to Classroom 105	W3	Plaster	Gray	None	0	16.3	Positive
1	1	H12C	Hallway adjacent to Classroom 105	W4	Plaster	Gray	None	0	0.1	Negative
1	1	H12C	Hallway adjacent to Classroom 105	Floor	Concrete	Gray	None	0	1.6	Positive
1	1	H12C	Hallway adjacent to Classroom 105	Radiator	Metal	Gray	None	0	0	Negative
1	1	H12C	Hallway adjacent to Classroom 105	Radiator	Metal	Gray	None	0	0	Negative
1	1	H12C	Hallway adjacent to Classroom 105	Radiator	Metal	Gray	None	0	0.3	Negative
1	1	H12C	Hallway adjacent to Classroom 105	Locker	Metal	Tan	None	0	0	Negative
1	1	H12C	Hallway adjacent to Classroom 106	Electrical Panel	Metal	Brown	None	0	5.7	Positive
1	1	H12D	Vestibule adjacent to Classroom 105	W1	Plaster	Gray	None	0	20.5	Positive
1	1	H12D	Vestibule adjacent to Classroom 105	W2	Plaster	Gray	None	0	19	Positive
1	1	H12D	Vestibule adjacent to Classroom 105	W3	Plaster	Gray	None	0	20.6	Positive

			Dates: 3/13/2023 to 7/21/2023	Lead-Safe Certification Assessment Report							
			Inspector Name and PA License Number:		D	d 0 -	4 a O!4 M! a	Idla Calla			
			Lawrence Jackson 003683		Pai	rkway Ce	nter City Mic	iale Colle	ge		
			Inspection Company: USA Environmental Management Inc		540 Nor	th 13th S	treet, Philad	elphia, PA	A 19123		
E I e m	F						·				
e n t	0 0 r	Space #	Onsite Room Name	Component	Substrate Material	Paint Color	Description of Damage	Damage Quantity (sf)	XRF Reading (mg/cm2)	XRF (positive/ negative)	
1	1	H12D	Vestibule adjacent to Classroom 105	Ceiling	Plaster	Gray	None	0	15.5	Positive	
1	1	H12D	Vestibule adjacent to Classroom 105	Floor	Concrete	Gray	None	0	1.1	Positive	
1	1	H12D	Vestibule adjacent to Classroom 105	Handrail	Metal	Gray	Chipping	6	1.5	Positive	
1	1	H12D	Vestibule adjacent to Classroom 105	Stair Tread	Concrete	Gray	None	0	1.8	Positive	
1	1	H12D	Vestibule adjacent to Classroom 105	Stair Riser	Concrete	Gray	None	0	1.6	Positive	
1	1	H12D	Vestibule adjacent to Classroom 105	Stair Stringer	Concrete	Gray	None	0	1.7	Positive	
1	1	H12D	Vestibule adjacent to Classroom 105	Door	Metal	Brown	None	0	0	Negative	
1	1	H12D	Vestibule adjacent to Classroom 105	Door Frame	Metal	Brown	None	0	0.1	Negative	
1	1	S16	Fire Tower adjacent to Building Engineer's Office	W1	Brick	White	None	0	8.4	Positive	
1	1	S16	Fire Tower adjacent to Building Engineer's Office	W2	Brick	White	Flaking	10	8.3	Positive	
1	1	S16	Fire Tower adjacent to Building Engineer's Office	W3	Brick	White	None	0	6	Positive	
1	1	S16	Fire Tower adjacent to Building Engineer's Office	Floor	Concrete	Gray	None	0	1	Positive	
1	1	S16	Fire Tower adjacent to Building Engineer's Office	Handrail	Metal	Gray	Chipping	10	1.7	Positive	
1	1	S16	Fire Tower adjacent to Building Engineer's Office	Stair Tread	Concrete	Gray	None	0	0.7	Positive	
1	1	S16	Fire Tower adjacent to Building Engineer's Office	Stair Riser	Concrete	Gray	None	0	1.5	Positive	
1	1	S15	Fire Tower adjacent to Classroom 105	W1	Brick	White	None	0	15.9	Positive	
1	1	S15	Fire Tower adjacent to Classroom 105	W2	Brick	White	None	0	17.2	Positive	
1	1	S15	Fire Tower adjacent to Classroom 105	W3	Brick	White	None	0	16.2	Positive	
1	1	S15	Fire Tower adjacent to Classroom 105	W4	Brick	White	None	0	15	Positive	
1	1	S15	Fire Tower adjacent to Classroom 105	Ceiling	Concrete	White	Flaking	30	13.7	Positive	
1	1	S15	Fire Tower adjacent to Classroom 105	Door	Concrete	Brown	None	0	0.1	Negative	
1	1	S15	Fire Tower adjacent to Classroom 105	Door Frame	Concrete	Brown	None	0	0.1	Negative	
1	1	S15	Fire Tower adjacent to Classroom 105	Stair Tread	Concrete	Gray	None	0	0.5	Negative	
1	1	S15	Fire Tower adjacent to Classroom 105	Stair Riser	Concrete	Gray	None	0	1.8	Positive	
1	1	S15	Fire Tower adjacent to Classroom 105	Stair Stringer	Concrete	Gray	None	0	1.7	Positive	
1	1	S15	Fire Tower adjacent to Classroom 105	Handrail	Metal	Gray	Flaking	14	6.6	Positive	
1	1	S15	Fire Tower adjacent to Classroom 105	Floor	Concrete	Gray	None	0	0.1	Negative	
1	1	S15	Fire Tower adjacent to Classroom 105	Drain pipe	Metal	White	Flaking	12	13.9	Positive	
1	1	S15	Fire Tower adjacent to Classroom 105	Drain pipe	Metal	Brown	Flaking	12	5.5	Positive	
1	1	106	Facilities Training Center Room 106	W1	Plaster	White	Flaking	10	0	Negative	
1	1	106	Facilities Training Center Room 106	W2	Plaster	White	Flaking	40	0.1	Negative	
1	1	106	Facilities Training Center Room 106	W3	Plaster	White	Flaking	20	0	Negative	
1	1	106	Facilities Training Center Room 106	W4	Plaster	White	Flaking	30	0.1	Negative	
1	1	106	Facilities Training Center Room 106	Ceiling	Plaster	White	Efflorescence	70	0	Negative	
1	1	106	Facilities Training Center Room 106	Floor	Wood	Unpainted	N/A	N/A	N/A	N/A	
1	1	106B	Staff Restroom next to Office 106	W1	Plaster	Tan	None	0	10.1	Positive	
1	1	106B	Staff Restroom next to Office 106	W2	Plaster	Tan	Efflorescence	15	12.4	Positive	
1	1	106B	Staff Restroom next to Office 106	W3	Plaster	Tan	Efflorescence	40	8.7	Positive	

			Dates: 3/13/2023 to 7/21/2023		Lead-S	afe Certi	fication Asse	essment l	Report	
			Inspector Name and PA License Number:		_					
			Lawrence Jackson 003683		Pai	rkway Ce	nter City Mic	ldle Colle	ge	
			Inspection Company: USA Environmental			_				
			Management Inc		540 Nor	th 13th S	treet, Philad	elphia, P <i>l</i>	A 19123	
E							•			
1										
е	F									
m										XRF
e n	0						Description of	Damage	XRF Reading	(positive/
l "t	r	Space #	Onsite Room Name	Component	Substrate Material	Paint Color	Damage	Quantity (sf)	(mg/cm2)	negative)
1	1	106B	Staff Restroom next to Office 106	W4	Plaster	Tan	Cracking	8	13	Positive
1	1	106B	Staff Restroom next to Office 106	Ceiling	Plaster	Tan	No Access	80	No Access	Assumed
1	1	106B	Staff Restroom next to Office 106	Floor	12 x 12 Floor Tile	Unpainted	N/A	N/A	N/A	N/A
1	1	106B	Staff Restroom next to Office 106	Door	Wood	Varnish	None	0	0.1	Negative
1	1	106B	Staff Restroom next to Office 106	Door Frame	Wood	Varnish	None	0	0.2	Negative
1	1	106B	Staff Restroom next to Office 106	Window Casing	Wood	Varnish	None	0	0.3	Negative
1	1	106B	Staff Restroom next to Office 106	Window Sill	Wood	Varnish	None	0	0.1	Negative
1	1	106B	Staff Restroom next to Office 106	Window Apron	Wood	Varnish	None	0	0.3	Negative
1	1	106B	Staff Restroom next to Office 106	Radiator	Metal	Gray	Flaking	5	2.4	Positive
1	1	106A	Custodial Closet 106A Next to Restroom	W1	Plaster	Blue	Efflorescence	100	0.1	Negative
1	1	106A	Custodial Closet 106A Next to Restroom	W2	Plaster	Blue	Efflorescence	100	0	Negative
1	1	106A	Custodial Closet 106A Next to Restroom	W3	Plaster	Blue	Efflorescence	100	14.4	Positive
1	1	106A	Custodial Closet 106A Next to Restroom	W4	Plaster	Blue	Efflorescence	100	3.5	Positive
1	1	106A	Custodial Closet 106A Next to Restroom	Column	Plaster	Blue	Flaking	30	11.3	Positive
1	1	106A	Custodial Closet 106A Next to Restroom	Drain Pipe	Metal	Blue	Flaking	10	0.7	Positive
1	1	106A	Custodial Closet 106A Next to Restroom	Door	Wood	Varnish	None	0	0	Negative
1	1	106A	Custodial Closet 106A Next to Restroom	Door Frame	Wood	Varnish	None	0	0.2	Negative
1	1	106A	Custodial Closet 106A Next to Restroom	Ceiling	Concrete	White	Flaking	20	Limited Access	Assumed
1	1	106A	Custodial Closet 106A Next to Restroom	Radiator	Metal	Gray	Cracking	5	0.3	Negative
1	1	106A	Custodial Closet 106A Next to Restroom	Floor	Wood	Gray	Moisture Damage	50	0.1	Negative
1	1	H12	Hallway from Office Suite 103 to Classroom 105	W1	Plaster	Gray	None	0	15.1	Positive
1	1	H12	Hallway from Office Suite 103 to Classroom 105	W2	Plaster	Gray	None	0	15.7	Positive
1	1	H12	Hallway from Office Suite 103 to Classroom 105	W3	Plaster	Gray	None	0	24	Positive
1	1	H12	Hallway from Office Suite 103 to Classroom 105	W4	Plaster	Gray	None	0	16.4	Positive
1	1	H12	Hallway from Office Suite 103 to Classroom 105	Floor	Concrete	Gray	None	0	1.8	Positive
1	1	H12	Hallway from Office Suite 103 to Classroom 105	Ceiling	Plaster	Tan	Efflorescence	100	21.3	Positive
1	1	H12	Hallway from Office Suite 103 to Classroom 105	Radiator	Metal	Gray	Flaking	4	0.1	Negative
1	1	H12	Hallway from Office Suite 103 to Classroom 105	Radiator	Metal	Gray	Flaking	4	0	Negative
1	1	H12	Hallway from Office Suite 103 to Classroom 105	Radiator	Metal	Gray	Flaking	2	0.2	Negative
1	1	H12	Hallway from Office Suite 103 to Classroom 105	Window Casing	Wood	Varnish	None None	0	0.3 0.2	Negative
1	1	H12	Hallway from Office Suite 103 to Classroom 105	Locker Door	Metal Wood	Tan	None	0	0.2	Negative
1	1	H12PCS	Pipe/Cable Shaft in Hallway next to Office Suite 104	Door Door Frame	Wood	Varnish Varnish	None	0	0.1	Negative
1	1	H12PCS	Pipe/Cable Shaft in Hallway next to Office Suite 104	W1			None N/A	N/A	0.2 N/A	Negative
1	1	H12PCS H12PCS	Pipe/Cable Shaft in Hallway next to Office Suite 104	W2	Terracotta Terracotta	Unpainted Unpainted	N/A N/A	N/A N/A	N/A N/A	N/A N/A
1	1		Pipe/Cable Shaft in Hallway next to Office Suite 104	W3	Terracotta	Unpainted	N/A	N/A N/A	N/A N/A	N/A N/A
1	1	H12PCS H12PCS	Pipe/Cable Shaft in Hallway next to Office Suite 104 Pipe/Cable Shaft in Hallway next to Office Suite 104	W4	Terracotta	Unpainted	N/A N/A	N/A N/A	N/A N/A	N/A N/A
1	1	H12PCS	Stairs to Auditorium Right Side	W1	Plaster	Gray	None	0	0.5	Negative
		ПІZА	Stall's to Additionalli Right Side	V V I	1 103151	Glay	INOLIC		0.5	inegative

			Dates: 3/13/2023 to 7/21/2023								
			Inspector Name and PA License Number:		_				•		
			Lawrence Jackson 003683		Pai	rkway Ce	nter City Mic	idie Colle	ge		
			Inspection Company: USA Environmental								
			Management Inc		540 Nor	th 13th S	treet, Philad	elphia, P <i>l</i>	A 19123		
Е							·				
1											
е	F										
m e	 0									XRF	
n	0						Description of	Damage	XRF Reading	(positive/	
l ii	r	Space #	Onsite Room Name	Component	Substrate Material	Paint Color	Damage	Quantity (sf)	(mg/cm2)	negative)	
1	1	H12A	Stairs to Auditorium Right Side	W2	Tile	Unpainted	N/A	N/A	N/A	N/A	
1	1	H12A	Stairs to Auditorium Right Side	W3	Plaster	Gray	None	0	22.5	Positive	
1	1	H12A	Stairs to Auditorium Right Side	W4	Tile	Unpainted	N/A	N/A	N/A	N/A	
1	1	H12A	Stairs to Auditorium Right Side	Ceiling	Plaster	Gray	None	0	21.1	Positive	
1	1	H12A	Stairs to Auditorium Right Side	Floor	Concrete	Gray	None	0	2.7	Positive	
1	1	H12A	Stairs to Auditorium Right Side	Stair Tread	Concrete	Gray	None	0	0.3	Negative	
1	1	H12A	Stairs to Auditorium Right Side	Stair Riser	Concrete	Gray	None	0	2.1	Positive	
1	1	H12A	Stairs to Auditorium Right Side	Stair Stringer	Concrete	Gray	None	0	2.1	Positive	
1	1	H12A	Stairs to Auditorium Right Side	Window Casing	Wood	Varnish	None	0	0.3	Negative	
1	1	E1	Passenger Elevator	W1	Metal	Unpainted	N/A	N/A	N/A	N/A	
1	1	E1	Passenger Elevator	W2	Metal	Unpainted	N/A	N/A	N/A	N/A	
1	1	E1	Passenger Elevator	W3	Metal	Unpainted	N/A	N/A	N/A	N/A	
1	1	E1	Passenger Elevator	W4	Metal	Unpainted	N/A	N/A	N/A	N/A	
1	1	E1	Passenger Elevator	Door	Metal	Tan	None	0	0	Negative	
1	1	E1	Passenger Elevator	Ceiling	Metal	Unpainted	N/A	N/A	N/A	N/A	
1	В	4	Older Lower Boiler Room	W1	Concrete	White	Flaking	200	0	Negative	
1	В	4	Older Lower Boiler Room	W1	Concrete	Gray	Flaking	200	0.4	Negative	
1	В	4	Older Lower Boiler Room	W2	Brick	White	Flaking	200	0.1	Negative	
1	В	4	Older Lower Boiler Room	W2	Brick	Gray	Flaking	200	22.3	Positive	
1	В	4	Older Lower Boiler Room	W3	Concrete	White	Flaking	200	0.1	Negative	
1	В	4	Older Lower Boiler Room	W3 W4	Concrete	Gray	Flaking	200	0.1	Negative	
1	В	4	Older Lower Boiler Room		Concrete	White	Flaking	200	0.2	Negative	
1	В	4	Older Lower Boiler Room	W4 Ceiling	Concrete Concrete	Gray Gray	Flaking	200	0.2	Negative Assumed	
1	B B	4	Older Lower Boiler Room Older Lower Boiler Room	Floor	No Access	No Access	No Access No Access	No Access	No Access No Access	No Access	
1	В	4	Older Lower Boiler Room Older Lower Boiler Room	Column	Concrete	White	Flaking	200	0.2	Negative	
1	В	4	Older Lower Boiler Room Older Lower Boiler Room	Column	Concrete	Gray	Flaking	200	0.2	Negative	
1	В	4	Older Lower Boiler Room Older Lower Boiler Room	Drain Pipe	Metal	White	Flaking	200	23.3	Positive	
1	В	4	Older Lower Boiler Room Older Lower Boiler Room	Drain Pipe	Metal	Gray	Flaking	200	15.7	Positive	
1	В	004B	Small Sump Pump Room in Old Boiler Room Area	W1	Concrete	White	Flaking	40	0.1	Negative	
1	В	004B	Small Sump Pump Room in Old Boiler Room Area	W1	Concrete	Gray	Flaking	40	0.3	Negative	
1	В	004B	Small Sump Pump Room in Old Boiler Room Area	W2	Concrete	White	Flaking	40	0.2	Negative	
1	В	004B	Small Sump Pump Room in Old Boiler Room Area	W2	Concrete	Gray	Flaking	40	0.4	Negative	
1	В	004B	Small Sump Pump Room in Old Boiler Room Area	W3	Brick	White	Flaking	40	No Access	Assumed	
1	В	004B	Small Sump Pump Room in Old Boiler Room Area	W3	Brick	Gray	Flaking	40	No Access	Assumed	
1	В	004B	Small Sump Pump Room in Old Boiler Room Area	W4	Brick	White	Flaking	40	0.7	Positive	
1	В	004B	Small Sump Pump Room in Old Boiler Room Area	W4	Brick	Gray	Flaking	40	0.2	Negative	
1	В	004B	Small Sump Pump Room in Old Boiler Room Area	Ceiling	Concrete	Unpainted	N/A	N/A	N/A	N/A	

			Dates: 3/13/2023 to 7/21/2023		Lead-S	afe Certi	fication Asse	essment l	Report	
			Inspector Name and PA License Number:		Dav	d O -		Idla Calla		
			Lawrence Jackson 003683		Pai	rkway Ce	nter City Mic	iale Colle	ge	
			Inspection Company: USA Environmental		E40 Non	46 4346 C	treat Dhilad	alabia Di	10400	
			Management Inc		540 NOr	tn 13tn 5	treet, Philad	eipnia, P	19123	
E										
e	F									
m	1									
е	0						-	_		XRF
n	o r	Space #	Onsite Room Name	Component	Substrate Material	Paint Color	Description of Damage	Damage Quantity (sf)	XRF Reading (mg/cm2)	(positive/ negative)
1	В	004B	Small Sump Pump Room in Old Boiler Room Area	Floor	Concrete	Unpainted	N/A	N/A	N/A	N/A
	۲	0048	Large Storage Room in Old Boiler Room (Old Coal							
1	В	2	Room)	W1	Concrete	Unpainted	N/A	N/A	N/A	N/A
1	В	2	Large Storage Room in Old Boiler Room (Old Coal Room)	W2	Concrete	Unpainted	N/A	N/A	N/A	N/A
1	В	2	Large Storage Room in Old Boiler Room (Old Coal Room)	W3	Concrete	Unpainted	N/A	N/A	N/A	N/A
1	В	2	Large Storage Room in Old Boiler Room (Old Coal Room)	W4	Concrete	Unpainted	N/A	N/A	N/A	N/A
1	В	2	Large Storage Room in Old Boiler Room (Old Coal Room)	Ceiling	Concrete	Unpainted	N/A	N/A	N/A	N/A
1	В	2	Large Storage Room in Old Boiler Room (Old Coal Room)	Floor	Concrete	Unpainted	N/A	N/A	N/A	N/A
1	В	3	Small Storage Room next to Old Boiler Room (Old Ash Room)	W1	No Access	No Access	No Access	No Access	No Access	No Access
1	В	3	Small Storage Room next to Old Boiler Room (Old Ash Room)	W2	No Access	No Access	No Access	No Access	No Access	No Access
1	В	3	Small Storage Room next to Old Boiler Room (Old Ash Room)	W3	No Access	No Access	No Access	No Access	No Access	No Access
1	В	3	Small Storage Room next to Old Boiler Room (Old Ash Room)	W4	No Access	No Access	No Access	No Access	No Access	No Access
1	В	3	Small Storage Room next to Old Boiler Room (Old Ash Room)	Ceiling	No Access	No Access	No Access	No Access	No Access	No Access
1	В	3	Small Storage Room next to Old Boiler Room (Old Ash Room)	Floor	No Access	No Access	No Access	No Access	No Access	No Access
1	В	6	New Boiler Room	W1	Brick	Gray	Flaking	60	12.7	Positive
1	В	6	New Boiler Room	W2	Concrete	Gray	Flaking	40	2.1	Positive
1	В	6	New Boiler Room	W3	Concrete	Gray	Flaking	100	0.4	Negative
1	В	6	New Boiler Room	W4	Brick	Gray	Flaking	200	8.9 0.2	Positive
1	B	6	New Boiler Room	Ceiling Floor	Concrete Concrete	Gray Gray	Flaking None	0	0.2	Negative Negative
1	В	6	New Boiler Room New Boiler Room	Floor	Concrete	Black	None	0	0.1	Negative
1	В	6	New Boiler Room	Column	Concrete	Gray	Flaking	60	9.4	Positive
1	В	6	New Boiler Room	Window Casing	Wood	Gray	None	0	9.7	Positive
1	В	7	Electrical Gated Area	W1	Metal	Unpainted	N/A	N/A	N/A	N/A
1	В	7	Electrical Gated Area	W2	Concrete	Gray	Flaking	60	3.7	Positive
1	В	7	Electrical Gated Area	W3	Concrete	Gray	Flaking	40	0.2	Negative
1	В	7	Electrical Gated Area	W4	Metal	Unpainted	N/A	N/A	N/A	N/A
1	В	7	Electrical Gated Area	Ceiling	Concrete	Gray	Flaking	10	No Access	Assumed
1	В	7	Electrical Gated Area	Floor	No Access	No Access	No Access	No Access	No Access	No Access

			Dates: 3/13/2023 to 7/21/2023		Lead-Safe Certification Assessment Report									
			Inspector Name and PA License Number: Lawrence Jackson 003683		Parkway Center City Middle College									
			Inspection Company: USA Environmental											
			Management Inc		540 Nor	tn 13tn S	treet, Philad	eipnia, P	A 19123					
E I e m e	F I o									XRF				
n	0 r	Space #	Onsite Room Name	Component	Substrate Material	Paint Color	Description of Damage	Damage Quantity (sf)	XRF Reading (mg/cm2)	(positive/ negative)				
1	В	8-2	Fan Room along 13th Street (adjacent to the New Boiler Room's Electrical Gated Area)	W1	Brick	White	Flaking	100	0.6	Negative				
1	В	8-2	Fan Room along 13th Street (adjacent to the New Boiler Room's Electrical Gated Area)	W1	Brick	Gray	Flaking	100	0.1	Negative				
1	В	8-2	Fan Room along 13th Street (adjacent to the New Boiler Room's Electrical Gated Area)	W2	Brick	White	Flaking	100	0.1	Negative				
1	В	45140	Fan Room along 13th Street (adjacent to the New Boiler Room's Electrical Gated Area)	W2	Brick	Gray	Flaking	100	0	Negative				
1	В	8-2	Fan Room along 13th Street (adjacent to the New Boiler Room's Electrical Gated Area)	W3	Concrete	White	Flaking	100	1.9	Positive				
1	В	8-2	Fan Room along 13th Street (adjacent to the New Boiler Room's Electrical Gated Area)	W3	Concrete	Gray	Flaking	100	2	Positive				
1	В	8-2	Fan Room along 13th Street (adjacent to the New Boiler Room's Electrical Gated Area)	W4	Brick	White	Flaking	100	0.1	Negative				
1	В	8-2	Fan Room along 13th Street (adjacent to the New Boiler Room's Electrical Gated Area)	W4	Brick	Gray	Flaking	100	0.1	Negative				
1	В	8-2	Fan Room along 13th Street (adjacent to the New Boiler Room's Electrical Gated Area)	Ceiling	Concrete	No Access	Flaking	200	No Access	Assumed				
1	В	45140	Fan Room along 13th Street (adjacent to the New Boiler Room's Electrical Gated Area)	Floor	Concrete	Gray	None	0	0.3	Negative				
1	В	8-2	Fan Room along 13th Street (adjacent to the New Boiler Room's Electrical Gated Area)	Column	Concrete	White	Flaking	16	0.2	Negative				
1	В	8-2	Fan Room along 13th Street (adjacent to the New Boiler Room's Electrical Gated Area)	Column	Concrete	Gray	Flaking	16	0.3	Negative				
1	В	45140	Fan Room along 13th Street (adjacent to the New Boiler Room's Electrical Gated Area)	Window Casing	Wood	Gray	None	0	12.3	Positive				
1	В	45140	Fan Room along 13th Street (adjacent to the New Boiler Room's Electrical Gated Area)	Door	Wood	Gray	None	0	23.8	Positive				
1	В	45140	Fan Room along 13th Street (adjacent to the New Boiler Room's Electrical Gated Area)	Door Casing	Wood	Gray	None	0	23.6	Positive				
1	В	8-2	Fan Room along 13th Street (adjacent to the New Boiler Room's Electrical Gated Area)	Stair Tread	Concrete	Gray	Flaking	20	0.5	Negative				
1	В	8-2	Fan Room along 13th Street (adjacent to the New Boiler Room's Electrical Gated Area)	Stair Riser	Concrete	Gray	Flaking	5	2.3	Positive				
1	В	8-2	Fan Room along 13th Street (adjacent to the New Boiler Room's Electrical Gated Area)	Fan Unit	Metal	Gray	Flaking	100	0	Negative				
1	В	8-2	Fan Room along 13th Street (adjacent to the New Boiler Room's Electrical Gated Area)	Duct Work	Concrete	Gray	Flaking	100	0.1	Negative				
1	В	5	Fan Room No. 1 (next to Basement Stairs to New Boiler Room - Under BE Office)	W1	Concrete	Gray	Flaking	300	0.4	Negative				
1	В	5	Fan Room No. 1 (next to Basement Stairs to New Boiler Room - Under BE Office)	W2	Concrete	Gray	Flaking	500	0.4	Negative				

			Dates: 3/13/2023 to 7/21/2023	Lead-Safe Certification Assessment Report									
			Inspector Name and PA License Number:				4 014 141		•				
			Lawrence Jackson 003683		Pai	rkway Ce	nter City Mic	idie Colle	ge				
			Inspection Company: USA Environmental										
			Management Inc		540 Nor	th 13th S	treet, Philad	elphia, P <i>l</i>	A 19123				
Е													
I	_												
e m	F												
e	0									XRF			
n	o						Description of	Damage	XRF Reading	(positive/			
t	r	Space #	Onsite Room Name	Component	Substrate Material	Paint Color	Damage	Quantity (sf)	(mg/cm2)	negative)			
1	В	5	Fan Room No. 1 (next to Basement Stairs to New Boiler Room - Under BE Office)	W3	Concrete	Gray	Flaking	300	25.2	Positive			
1	В	5	Fan Room No. 1 (next to Basement Stairs to New Boiler Room - Under BE Office)	W4	Brick	Gray	Flaking	500	16.7	Positive			
1	В	5	Fan Room No. 1 (next to Basement Stairs to New Boiler Room - Under BE Office)	Fan Unit	Metal	Gray	Flaking	200	0.1	Negative			
1	В	5	Fan Room No. 1 (next to Basement Stairs to New Boiler Room - Under BE Office)	Floor	Concrete	White	Chipping	2000	No Access	Assumed			
1	В	5	Fan Room No. 1 (next to Basement Stairs to New Boiler Room - Under BE Office)	Ceiling	Concrete	Unpainted	N/A	N/A	N/A	N/A			
1	В	1	Fan Room No. 2 next to Rear stair to Old Boiler Room	W1	Concrete	White	Flaking	200	0.3	Negative			
1	В	1	Fan Room No. 2 next to Rear stair to Old Boiler Room	W1	Concrete	Gray	Flaking	200	26.7	Positive			
1	В	1	Fan Room No. 2 next to Rear stair to Old Boiler Room	W2	Concrete	White	Flaking	200	0.2	Negative			
1	В	1	Fan Room No. 2 next to Rear stair to Old Boiler Room	W2	Concrete	Gray	Flaking	200	0.3	Negative			
1	В	1	Fan Room No. 2 next to Rear stair to Old Boiler Room	W3	Brick	White	Flaking	200	0.3	Negative			
1	В	1	Fan Room No. 2 next to Rear stair to Old Boiler Room	W3	Brick	Gray	Flaking	200	0.3	Negative			
1	В	1	Fan Room No. 2 next to Rear stair to Old Boiler Room	W4	Brick	White	Flaking	200	0.6	Negative			
1	В	1	Fan Room No. 2 next to Rear stair to Old Boiler Room	W4	Brick	Gray	Flaking	200	0.9	Positive			
1	В	1	Fan Room No. 2 next to Rear stair to Old Boiler Room	Ceiling	Concrete	White	Flaking	1000	No Access	Assumed			
1	В	1	Fan Room No. 2 next to Rear stair to Old Boiler Room	Floor	Concrete Wood	Unpainted	N/A	N/A	N/A	N/A			
1	В	1	Fan Room No. 2 next to Rear stair to Old Boiler Room	Door		Gray	Flaking	28 10	24.2 25.7	Positive			
1	В	1	Fan Room No. 2 next to Rear stair to Old Boiler Room Former Shower Room next to Fan Room #2 near rear	Door Casing	Wood	Gray	Flaking	10	25.7	Positive			
1	В	001A	stair to Old Boiler Room	No Access	No Access	No Access	No Access	No Access	No Access	No Access			
1	В	001A	Former Shower Room next to Fan Room #2 near rear stair to Old Boiler Room	No Access	No Access	No Access	No Access	No Access	No Access	No Access			
1	В	001A	Former Shower Room next to Fan Room #2 near rear stair to Old Boiler Room	No Access	No Access	No Access	No Access	No Access	No Access	No Access			
1	В	001A	Former Shower Room next to Fan Room #2 near rear stair to Old Boiler Room	No Access	No Access	No Access	No Access	No Access	No Access	No Access			
1	В	001A	Former Shower Room next to Fan Room #2 near rear stair to Old Boiler Room	No Access	No Access	No Access	No Access	No Access	No Access	No Access			
1	В	001A	Former Shower Room next to Fan Room #2 near rear stair to Old Boiler Room	No Access	No Access	No Access	No Access	No Access	No Access	No Access			
1	В	S001	Rear Stair to Old Boiler Room near Room 106	W1	Brick	Gray	Flaking	100	7.1	Positive			
1	В	S001	Rear Stair to Old Boiler Room near Room 106	W1	Brick	White	Flaking	100	7.3	Positive			
1	В	S001	Rear Stair to Old Boiler Room near Room 106	W2	Concrete	Gray	Flaking	100	0.3	Negative			
1	В	S001	Rear Stair to Old Boiler Room near Room 106	W2	Concrete	White	Flaking	100	0.2	Negative			
1	В	S001	Rear Stair to Old Boiler Room near Room 106	W3	Brick	Gray	Flaking	100	5.3	Positive			
1	В	S001	Rear Stair to Old Boiler Room near Room 106	W3	Brick	White	Flaking	100	6.1	Positive			

			Dates: 3/13/2023 to 7/21/2023	Lead-Safe Certification Assessment Report							
			Inspector Name and PA License Number:		_		4 614 551		•		
			Lawrence Jackson 003683		Pai	rkway Ce	nter City Mic	idie Colle	ge		
			Inspection Company: USA Environmental								
			Management Inc		540 Nor	th 13th S	treet, Philad	elphia, P <i>l</i>	A 19123		
Е											
ı											
e	F										
m e	0									XRF	
n	0						Description of	Damage	XRF Reading	(positive/	
t	r	Space #	Onsite Room Name	Component	Substrate Material	Paint Color	Damage	Quantity (sf)	(mg/cm2)	negative)	
1	В	S001	Rear Stair to Old Boiler Room near Room 106	W4	Brick	Gray	Flaking	12	5.1	Positive	
1	В	S001	Rear Stair to Old Boiler Room near Room 106	W4	Brick	White	Flaking	12	6.3	Positive	
1	В	S001	Rear Stair to Old Boiler Room near Room 106	Ceiling	Concrete	White	Flaking	80	3.6	Positive	
1	В	S001	Rear Stair to Old Boiler Room near Room 106	Door	Metal	Tan	None	0	0.1	Negative	
1	В	S001	Rear Stair to Old Boiler Room near Room 106	Door Casing	Metal	Tan	None	0	0.4	Negative	
1	В	S001	Rear Stair to Old Boiler Room near Room 106	Handrail	Metal	Gray	Chipping	20	18.3	Positive	
1	В	S001	Rear Stair to Old Boiler Room near Room 106	Stair Tread	Concrete	Gray	Flaking	100	15.3	Positive	
1	В	S001	Rear Stair to Old Boiler Room near Room 106	Stair Riser	Concrete	Gray	Flaking	100	11.3	Positive	
1	В	SB1	Stairs to Fan Room No. 1 and New Boiler Room	W1	Brick	Tan	None	0	0.6	Negative	
1	В	SB1	Stairs to Fan Room No. 1 and New Boiler Room	W1	Brick	White	None	0	0.5	Negative	
1	В	SB1	Stairs to Fan Room No. 1 and New Boiler Room	W2	Concrete	Tan	None	0	0	Negative	
1	В	SB1	Stairs to Fan Room No. 1 and New Boiler Room	W2	Concrete	White	None	0	0.2	Negative	
1	В	SB1	Stairs to Fan Room No. 1 and New Boiler Room	W3	Brick	Tan	None	0	2.2	Positive	
1	В	SB1	Stairs to Fan Room No. 1 and New Boiler Room	W3	Brick	White	None	0	0.7	Positive	
1	В	SB1	Stairs to Fan Room No. 1 and New Boiler Room	Door	Metal	Gray	None	0	0.1	Negative	
1	В	SB1	Stairs to Fan Room No. 1 and New Boiler Room	Door Casing	Metal	Gray	None	0	0.3	Negative	
1	В	SB1	Stairs to Fan Room No. 1 and New Boiler Room	Stair Tread	Concrete	Gray	Cracking	80	0.4	Negative	
1	В	SB1	Stairs to Fan Room No. 1 and New Boiler Room	Stair Riser Handrail	Concrete Metal	Gray Gray	Cracking None	50 0	0	Negative	
1	В	SB1	Stairs to Fan Room No. 1 and New Boiler Room	Ceiling	Concrete	White	None	0	0.3	Negative Negative	
1	В	SB1 Main AT	Stairs to Fan Room No. 1 and New Boiler Room Main Attic	No Access	No Access	No Access	No Access	No Access	No Access	No Access	
1	A		Main Attic	No Access	No Access	No Access	No Access	No Access	No Access	No Access	
1	A	Main AT Main AT	Main Attic	No Access	No Access	No Access	No Access	No Access	No Access	No Access	
1	A	Main AT	Main Attic	No Access	No Access	No Access	No Access	No Access	No Access	No Access	
1	A	Main AT	Main Attic	No Access	No Access	No Access	No Access	No Access	No Access	No Access	
1	A	Main AT	Main Attic	No Access	No Access	No Access	No Access	No Access	No Access	No Access	
1	3	Aud AT	Auditorium Attic	No Access	No Access	No Access	No Access	No Access	No Access	No Access	
1	3	Aud AT	Auditorium Attic	No Access	No Access	No Access	No Access	No Access	No Access	No Access	
1	3	Aud AT	Auditorium Attic	No Access	No Access	No Access	No Access	No Access	No Access	No Access	
1	3	Aud AT	Auditorium Attic	No Access	No Access	No Access	No Access	No Access	No Access	No Access	
1	3	Aud AT	Auditorium Attic	No Access	No Access	No Access	No Access	No Access	No Access	No Access	
1	3	Aud AT	Auditorium Attic	No Access	No Access	No Access	No Access	No Access	No Access	No Access	
1	C	CS	Crawl Space	No Access	No Access	No Access	No Access	No Access	No Access	No Access	
1	C	CS	Crawl Space	No Access	No Access	No Access	No Access	No Access	No Access	No Access	
1	С	CS	Crawl Space	No Access	No Access	No Access	No Access	No Access	No Access	No Access	
1	С	CS	Crawl Space	No Access	No Access	No Access	No Access	No Access	No Access	No Access	
1	С	CS	Crawl Space	No Access	No Access	No Access	No Access	No Access	No Access	No Access	
1	С	CS	Crawl Space	No Access	No Access	No Access	No Access	No Access	No Access	No Access	

			Dates: 3/13/2023 to 7/21/2023		Lead-Safe Certification Assessment Report								
			Inspector Name and PA License Number:				4 0:4 14:		-				
			Lawrence Jackson 003683		Parkway Center City Middle College								
			Inspection Company: USA Environmental		540 North 13th Street, Philadelphia, PA 19123								
E	1		Management Inc		0 +0 1101		tioot, i iiiaa		10120				
l e	F												
m e										XRF			
n	0						Description of	Damage	XRF Reading	(positive/			
t	r	Space #	Onsite Room Name	Component	Substrate Material	Paint Color	Damage	Quantity (sf)	(mg/cm2)	negative)			
1	1	S13	Stairwell adjacent to Office Suite 103	Entry Door	Metal	Brown	None	0	0	Negative			
1	1	S13	Stairwell adjacent to Office Suite 103	Entry Door Frame	Metal	Brown	None	0	0	Negative			
1	1	S13	Stairwell adjacent to Office Suite 103	Door	Metal	Brown	None	0	0	Negative			
1	1	S13	Stairwell adjacent to Office Suite 103	Door Frame	Metal	Brown	None	0	0.8	Positive			
1	4	413	Boy's Restroom adjacent to Classroom 401	Drain Pipe	Metal	Brown	Flaking	6	2	Positive			
1	4	413	Boy's Restroom adjacent to Classroom 401	Window Casing	Wood	Brown	None	0	0.2	Negative			
1	4	413	Boy's Restroom adjacent to Classroom 401	Door Casing	Wood	Brown	None	0	0.2	Negative			
1	4	401	Classroom 401	Radiator	Metal	Gray	Flaking	4	3.5	Positive			
1	4	401	Classroom 401	Radiator	Metal	Gray	Flaking	5	0 0.1	Negative			
1	4	401	Classroom 401 Classroom 401	Radiator Drain Pipe	Metal Metal	Gray Gray	Flaking	1	0.1	Negative			
<u> </u>		401					Chipping	+	3.7	Negative			
1	4	401	Classroom 401	Drain Pipe	Metal	White	Chipping	1		Positive			
1	4	401	Classroom 401	Door	Wood Wood	Varnish	None	0	0.1	Negative			
1	4	401 401	Classroom 401 Classroom 401	Door Casing Window Casing	Wood	Varnish Varnish	None None	0	0.2	Negative Negative			
1	4	401	Classroom 401	Window Casing Window Sill	Wood	Varnish	None	0	0.2	Negative			
1	4	401	Classroom 401	Window Apron	Wood	Varnish	None	0	0.2	Negative			
1	4	H41A	Hallway outside 4th Floor Boy's Restroom	Stair Riser	Concrete	Gray	None	0	4.8	Positive			
1	4	H41A	Hallway outside 4th Floor Boy's Restroom	Stair Stringer	Concrete	Gray	None	0	5.9	Positive			
1	4	S46	Fire Tower adjacent to Classroom 402	Door	Metal	Brown	None	0	0	Negative			
1	4	S46	Fire Tower adjacent to Classroom 402	Door Casing	Metal	Brown	None	0	0	Negative			
1	4	S46	Fire Tower adjacent to Classroom 402	Door	Metal	Brown	None	0	0.1	Negative			
1	4	S46	Fire Tower adjacent to Classroom 402	Door Casing	Metal	Brown	None	0	0	Negative			
1	4	S46	Fire Tower adjacent to Classroom 402	Drain Pipe	Metal	Brown	None	0	0	Negative			
1	4	S46	Fire Tower adjacent to Classroom 402	Drain Pipe	Metal	White	None	0	0	Negative			
1	4	S46	Fire Tower adjacent to Classroom 402	Drain Pipe	Metal	Brown	Flaking	12	11.4	Positive			
1	4	S46	Fire Tower adjacent to Classroom 402	Security Gate	Metal	Brown	Flaking	100	9.8	Positive			
1	4	S46	Fire Tower adjacent to Classroom 402	Door	Metal	Brown	None	0	0	Negative			
1	4	S46	Fire Tower adjacent to Classroom 402	Door Casing	Metal	Brown	Flaking	5	0.1	Negative			
1	4	S46	Fire Tower adjacent to Classroom 402	Ceiling	Concrete	White	Flaking	100	0	Negative			
1	4	S46	Fire Tower adjacent to Classroom 402	Handrail	Metal	Brown	Chipping	10	0.8	Positive			
1	4	S46	Fire Tower adjacent to Classroom 402	Stair Riser	Concrete	Grey	None	0	1.9	Positive			
1	4	S46	Fire Tower adjacent to Classroom 402	Stair Tread	Concrete	Grey	None	0	1.5	Positive			
1	4	S46	Fire Tower adjacent to Classroom 402	Stair Stringer	Concrete	Grey	None	0	2.3	Positive			
1	4	S44	Stairwell adjacent to Classroom 405	Floor	Concrete	Gray	None	0	1.5	Positive			
1	4	S44	Stairwell adjacent to Classroom 405	Newel Post	Metal	Brown	None	0	5.8	Positive			
1	4	S44	Stairwell adjacent to Classroom 405	Door	Metal	Brown	None	0	0	Negative			

			Dates: 3/13/2023 to 7/21/2023		Lead-S	afe Certi	fication Asse	essment F	Report	
			Inspector Name and PA License Number: Lawrence Jackson 003683		Par	kway Ce	nter City Mic	ldle Colle	ge	
			Inspection Company: USA Environmental Management Inc		540 Nor	th 13th S	treet, Philad	elphia, PA	A 19123	
E I e m e n t	F I o o r	Space #	Onsite Room Name	Component	Substrate Material	Paint Color	Description of Damage	Damage Quantity (sf)	XRF Reading (mg/cm2)	XRF (positive/ negative)
1	4	S44	Stairwell adjacent to Classroom 405	Door Casing	Metal	Brown	None	0	2.4	Positive
1	4	S44	Stairwell adjacent to Classroom 405	Ceiling	Plaster	White	None	0	10.8	Positive
1	4	S44	Stairwell adjacent to Classroom 405	Radiator	Metal	Gray	None	0	1.5	Positive
1	4	H41	Hallway outside Classrooms 401 to 404	Radiator	Metal	Gray	None	0	0	Negative
1	4	H41	Hallway outside Classrooms 401 to 404	Radiator	Metal	Gray	Chipping	5	0	Negative
1	4	H41	Hallway outside Classrooms 401 to 404	Radiator	Metal	Gray	Chipping	5	0	Negative
1	4	H41	Hallway outside Classrooms 401 to 404	Lockers	Metal	Blue	None	0	0.1	Negative
1	4	H41	Hallway outside Classrooms 401 to 404	Door Electrical Panel	Metal	Blue	None	0	3.5	Positive
1	4	405A	Classroom 405 Copy Room	Door Casing	Metal	Brown	None	0	0	Negative
1	4	405A	Classroom 405 Copy Room	Baseboard	Wood	Brown	None	0	0	Negative
1	4	405A	Classroom 405 Copy Room	Window Casing	Wood	Brown	None	0	0.5	Negative
1	4	H43	Hallway outside Classrooms 405 to 408	Lockers	Metal	Blue	None	0	0.2	Negative
1	4	H43	Hallway outside Classrooms 405 to 408	Lockers	Metal	Orange	None	0	0.4	Negative